

Local Government Engineering Department

Subproject List of All SSWRD Project

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Barguna (Total SPs : 36 Nos.)				
Amtali				
SSWRDSP-1				
SP15333, Khatachora DR Subproject, DR, Union : Pancha Koralia, HO Date: 17/09/2002				
	Khatachora Khal Re-excavation	4.95	1,414,143	Main
SSWRDSP-2				
SP25318, Mirar Khal-Magan Khar Khal Subproject, DR&IRR, Union : Haldia, HO Date:				
	O&M Shed	Size: 9mX5m 0.00	603,474	Main
	Re-excavation of Mirar Khal-1	4.05	1,149,732	Main
	Re-excavation of Mirar Khal-2	3.05	688,870	Main
	Re-excavation of Mirar Khal-3	2.70	969,104	Main
	Re-excavation of Magan Khar Khal	6.95	2,439,617	Main
	Part-A: Re-excavation of Mirar khal-Magan Khal Branch-1	1.00	618,090	PSSWRSP
	Part-B: Re-excavation of Mirar khal-Magan Khal Branch-2	2.20	1,399,175	PSSWRSP
	Part-C: Re-excavation of Mirar khal-Magan Khal Branch-3	0.50	91,777	PSSWRSP
	Sardarer khal re-excavation(ch.00-4250m)	4.25	4,042,116	SSSWRD
	Boshirgudi khal re-excavation(ch.00-2280m)	2.28	4,092,767	SSSWRD
	Madborer khal re-excavation(ch.00-1370m)	1.37	1,420,182	SSSWRD
	Mouje Ali khal re-excavation(ch.00-1070m)	1.07	1,196,103	SSSWRD
	Referenced line seciton(9nos)	0.00	135,000	SSSWRD
PSSWRSP				
SP43040, Singkhali Khal Subproject, DR, Union : Amtali, HO Date: 28/11/2013				
	Part-A: Re-excavation of Singkhali Khal	3.40	4,930,506	Main
	Part-F: Re-excavation of Sardar Khal	0.90	500,476	Main
	Part-H: Re-excavation of Khaser Khal	0.70	306,840	Main
	Part-C: Re-excavation of Shialia Khal	1.00	781,761	Main
	Part-G: Re-excavation of Karsher Khal	0.70	208,731	Main
	Part-D: Re-excavation of Matbaria khal	1.00	819,852	Main
	Part-B: Re-excavation of Manikjuri Khal	1.50	1,082,563	Main
	Part-I: Construction of Reference Lined section	0.00	238,329	Main
	Part-A: Construction of WMCA office & others	12mx6m 0.00	301,000	Main
	Part-E: Re-excavation of Matbaria Branch khal	2.00	1,049,049	Main
	Morichbunia khal(ch.00-5700m)	5.70	6,288,008	SSSWRD
	Morichbunia Branch khal(ch.00-1900m)	1.90	2,027,284	SSSWRD
	Referenced line section(7nos)	0.00	218,125	SSSWRD
	Bamboo bridge(7 nos)	0.00	433,174	SSSWRD
SP43044, Garabunia Subproject, DR, Union : Atharogasia., HO Date: 04/06/2014				
	Part-A: Re-excavation of Garabunia khal	4.25	2,445,294	Main
	Part-D: Re-excavation of Chalitabunia khal	1.66	1,146,470	Main
	Part-F: Re-excavation of Algir khal	0.93	196,085	Main
	Part-B: Re-excavation of Garabunia Branch khal-1	1.05	477,819	Main
	Part-C: Re-excavation of Garabunia Branch khal-2	0.35	163,312	Main
	Part-E: Re-excavation of Chalitabunia Branch khal	0.26	55,456	Main
	Part-G: Reference lined section	0.00	213,312	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,390,035	Main
SP44103, Gotkhali-Chalitabunia Khal Subproject, DR, Union : Chawra, HO Date:				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,569,000	Main
	Part-A: Re-excavation of Ghotkhali Khal	6.90	4,562,033	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Re-excavation of Betmur Khal	2.00	1,706,610	Main
	Part-C: Re-excavation of Chalitabunia Khal	2.58	1,653,763	Main
	Part-D: Re-excavation of Uzir/Zugir Khal	3.30	2,371,832	Main
	Part-E: Construction of reference Lined Section	0.00	361,460	Main
	Ghotkhali khal(ch.00-1000m)	1.00	1,459,866	SSSWRDP
	Reference Line (8nos)	0.00	225,238	SSSWRDP
	Bamboo Bridge(4nos)	0.48	183,992	SSSWRDP
	Patakata Khal(ch.00-7100m)	7.10	8,005,412	SSSWRDP
SP44120, Jabbar Ali - Sharif Shimon Subproject, DR, Union : Haldia, HO Date: 06/09/2017				
	Part-A: WMCA Office & others	12mX6m 0.00	1,432,972	Main
	Part-A: Re-excavation of Aura Sharif Guinggakhalir Khal	1.50	1,488,331	Main
	Part-B: Re-excavation of Badsha Vita Khal	0.20	118,522	Main
	Part-C: Re-excavation of Balaibunia Khal	3.15	1,847,060	Main
	Part-D: Re-excavation of Harar Khal	1.01	709,962	Main
	Part-E: Re-excavation of Mthurar-Amandir Khal	1.00	897,978	Main
	Part-F: Re-excavation of Swrsaty-Jabar ali Khal	2.00	1,663,128	Main
	Part-G: Construction of Reference Lined Section	0.00	208,658	Main
SP46252, Kukua- Nimter Khal Subproject, DR, Union : Kukua, HO Date: 06/09/2017				
	Part-A: Construction of WMCA office and others	12mX6m 0.00	1,181,659	Main
	Part-A: Re-excavation of Nimtar Khal	1.32	1,132,880	Main
	Part-B: Re-excavation of Nimta-1 Khal	0.80	366,957	Main
	Part-C: Re-excavation of Nimta-2 Khal	0.70	860,954	Main
	Part-D: Re-excavation of Nimta-3 Khal	2.50	3,310,783	Main
	Part-E: Re-excavation of Moynar Khal	1.95	709,846	Main
	Part-F: Re-excavation of Nichkata Khal	1.60	848,882	Main
	Part-G: Re-excavation of Israr Khal	1.45	165,493	Main
	Part-H: Construction of reference lined section	0.00	25,445	Main
SP46253, Arua-Kamini Khal Subproject, DR&WC, Union : Athargachia, HO Date:				
	Part-A: Construcion of WMCA Office and others	12mX6m 0.00	1,182,905	Main
	Part-I: Construction of Reference Lined Section	0.00	178,135	Main
	Part-A: Re-excavation of Kamini Khal	0.30	243,712	Main
	Part-B: Re-excavation of Kumaria Khal	0.87	517,130	Main
	Part-C: Re-excavation of Dauwa Khal	0.60	365,821	Main
	Part-D: Re-excavation of Arua Khal	0.20	108,012	Main
	Part-E: Re-excavation of Kalia-arua Khal	0.70	186,793	Main
	Part-F: Re-excavation of Tarabunia Khal	0.37	169,428	Main
	Part-G: Re-excavation of Kalia Khal	1.09	602,669	Main
	Part-H: Re-excavation of Daria Khal	0.97	458,794	Main
SP46276, Purba Chila Khal Subproject, DR, Union : Haldia, HO Date: 06/09/2017				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,431,087	Main
	Part-A:Re-excavation of Kalir khal	1.62	1,541,621	Main
	Part-B:Re-excavation of Ashikkar khal	1.68	1,092,686	Main
	Part-C:Re-excavation of Dumuria khal	1.53	1,430,875	Main
	Part-D:Re-excavation of Boro khani khal	1.37	1,133,905	Main
	Part-E:Re-excavation of Munasharif khal	0.80	550,580	Main
	Part-F:Re-excavation of Thakurer Barir,Bhagulir, Sajjal kha	1.40	311,876	Main
	Part-G: Re-excavation of Talgasial khal	0.60	447,959	Main
	Part-H: Construction of Reference Lined Section	0.00	267,433	Main

Bamna
SSWRDSP-1

SP13049, Dawatala DR Subproject, DR, Union : Dawatala, HO Date: 12/01/2002

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
PSSWRSP SP46240, Amtoli Ruhita Potkakhali, DR, Union : Ramna, HO Date: 20/06/2017	Vijora Khal Re-excavation	4.65	212,436	Main
	Part-A: WMCA office & others	12mX6m 0.00	1,235,533	Main
	Part-A: Re-excavation of Rohita Garader Khal	3.30	2,703,299	Main
	Part-B: Re-excavation of Kutir Khal	2.69	3,045,305	Main
	Part-C: Re-excavation of Tutaramer Khal	2.98	2,733,826	Main
	Part-D: Re-excavation of Swanirver Khal	3.10	3,286,374	Main
	Part-E: Re-excavation of Khazura Khal	3.45	2,196,636	Main
SP46246, Ramna Subproject, DR, Union : Ramna, HO Date: 20/06/2017	Part-F: Construction of Reference Lined section	0.00	336,300	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	1,413,018	Main
	Part-A: Re-excavation of Golaghata-Moulvir Khal	1.67	571,333	Main
	Part-B: Re-excavation of Uttar Ramna Khal	1.71	289,305	Main
	Part-C: Re-excavation of Dakshin Golaghata Karaitala Khal	5.02	2,084,917	Main
	Part-D: Re-excavation of Ramna Khal	4.74	3,016,687	Main
	Part-E: Re-excavation of Rohita Garader Khal	3.94	716,178	Main
Betagi SSWRDSP-1 SP14182, Kawnia-Mirjaganj FCD Subproject, FCD, Union : Bura Majumder, HO Date:	Part-F: Re-excavation of Uttar Ramna Golahata Khal	1.00	619,933	Main
	Part-G: Construction of Reference Lined Section	0.00	311,998	Main
	Embankment Re-sectioning	1.73	808,011	Main
	Monarkhali Khal Regulator at Ch.0+740m	2-V(1.5mX1.5m)	2,890,299	Main
	Chachaimaji Khal Regulator at Ch.1+141m	1-V(1.5mX1.5m)	1,675,925	Main
	Mirjaganj-Border Khal Pipe Sluice at Ch.1+600m	1-V(1.2m dia)	1,104,000	Main
SSWRDSP-2 SP25308, Chhoto Mokamia-Bara Mokamia Subproject, DR&IRR, Union : Mokamia, HO	O&M Sheed	Size: 9mX5m 0.00	603,474	Main
	Re-excavation of Kazir Khal	2.40	709,706	Main
	Re-excavation of Banier Khal	5.58	2,044,536	Main
	Re-excavation of Kathalia Khal	4.27	2,185,828	Main
	Re-excavation of Akaner Khal	1.54	399,199	Main
	Re-excavation of Uttar Chhoto Mokamia Khal	2.75	406,596	Main
	Re-excavation of Katalkhali Branch Khal	3.60	1,951,157	PSSWRSP
	Re-excavation of Banier Khal	6.94	852,687	PSSWRSP
	Houder khal re-excavation(ch.00-3200m)	3.20	4,392,234	SSSWRDP
	Houder branch khal-1re-excavation(ch.00-600m)	0.60	572,157	SSSWRDP
	Houder branch khal-2 re-excavation(ch.00-1300m)	1.30	1,472,821	SSSWRDP
	Houder branch khal-3 re-excavation(ch.00-1200m)	1.20	1,228,958	SSSWRDP
	Sarder jugir khal re-excavation(ch.00-1500m)	1.50	1,757,168	SSSWRDP
	Chorkhali khal re-excavation(ch.00-1525m)	1.53	1,413,595	SSSWRDP
	Kurular khal re-excavation(ch.00-600m)	0.60	541,731	SSSWRDP
	Referenced line section(12nos)	0.00	180,000	SSSWRDP
PSSWRSP SP42016, Gabua Fultala Subproject, DR&WC, Union : Bibichini, HO Date: 09/07/2014	Part-F: Const. of reference lined section (10nos.)	0.00	332,022	Main
	Part-A: WMCA office & others	Size: 12mX6m 0.00	1,399,000	Main
	Part-A: Reexcavation of Baroir Khal	3.40	5,065,889	Main
	Part-B: Reexcavation of Fultala Khal	3.35	3,788,451	Main
	Part-C: Reexcavation of Gabua Khal	2.08	2,889,344	Main
	Part-D: Reexcavation of East Kata Khal	2.55	2,891,568	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP43048, Deshantarkathi-Gouribunia Subproject, DR, Union : Bibichini, HO Date:	Part-E: Rexcavation of Sener Khal	1.45	1,762,936	Main
	Part-A: Re-excavation of Desher khal	4.20	3,555,208	Main
	Part-E: Re-excavation of Pollimongol branch khal	0.60	112,624	Main
	Part-F: Re-excavation of Bhamoner khal	3.10	2,021,714	Main
	Part-C: Re-excavation of Parer khal	1.71	3,345,291	Main
	Part-D: Re-excavation of Pollimongol khal	1.59	700,087	Main
	Part-G: Re-excavation of Sirajuddin khal	0.80	129,348	Main
	Part-H: Re-excavation of Gainer khal	1.50	295,353	Main
	Part-I: Construction of Lined Ref. section	0.00	236,720	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,340,048	Main
SP46238, Lakshmipur-Ranipur-Khantakata SP, DR, Union : Bibichini, HO Date: 22/05/2017	Part-B: Re-excavation of Desher Branch khal-3	0.50	285,212	Main
	Part-A: WMCA office & others	12mX6m 0.00	1,483,510	Main
	Part-J: Construction of Reference Lined Section	0.50	227,640	Main
	Part-I: Re-excavation of Jagaikhal-Khondokarbari Link kh	0.00	351,187	Main
	Part-A: Re-excavation of Ranipur Jogaikhal khal	2.50	1,819,390	Main
	Part-B: Re-excavation of Ranipur Jogaikhal Branch khal	0.43	268,534	Main
	Part-C: Re-excavation of khandakerbari khal	2.90	2,044,242	Main
	Part-D: Re-excavation of Laxmipur khal	1.05	661,309	Main
	Part-E: Re-excavation of Laxmipur Branch-1 khal	0.96	348,847	Main
	Part-F: Re-excavation of Laxmipur Branch-2 khal	0.61	498,709	Main
SP46245, Koruna Khal Subproject, DR, Union : Mokamia/ Hosnabad, HO Date: 22/05/2017	Part-G: Re-excavation of Morkhali khal	2.40	1,536,449	Main
	Part-H: Re-excavation of Morkhali -Khondokarbari Link kha	0.68	168,146	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	1,523,430	Main
	Part-A: Re-excavation of Kalighata Khal	2.50	1,814,086	Main
	Part-B: Re-excavation of Koruna Khal	9.30	8,364,921	Main
	Part-C: Re-excavation of Liner Khal	2.00	752,758	Main
	Part-D: Re-excavation of Jore Koruna Khal	1.95	1,466,895	Main
	Part-E: Re-excavation of Chalitabunia Khal	1.78	924,953	Main
	Part-F: Re-excavation of Dhooper Khal	1.00	811,597	Main
	Part-G: Construction of Reference Lined Section	0.00	378,100	Main
Patharghata SSWRDSP-1				
SP13071, Koralia-Hazir Khal DR Subproject, DR, Union : Patharghata, HO Date:				
	Part-A: Re-excavation of Koralia Khal	2.63	1,571,885	PSSWRSP
	Part-B: Re-excavation of Ruhita Baltalata Khal	0.91	553,812	PSSWRSP
	Part-C: Re-excavation of Ruhita lata khal	0.90	554,384	PSSWRSP
	Part-D: Re-excavation of Ruhita Baltala khal	0.30	387,211	PSSWRSP
	Padda Sluicgate-Karomjatola khal re-excavation(ch.00-31	3.10	5,532,296	SSSWRDP
	Gohorpur moddhokola-purbo Mirabari khal re-excavation(cl	2.00	2,275,908	SSSWRDP
	Ruhita -majher khal re-excavation(ch.00-1820)	1.82	2,084,008	SSSWRDP
	Koralia-Hazir khal re-excavation(ch.00-1400m)	1.40	2,022,162	SSSWRDP
	Khal Re-excavation	3.40	88,869	Main
	Koralia Khal(A) Re-excavation	4.90	1,109,523	Main
	Koralia Br. Khal(B) Re-excavation	1.40	218,423	Main
	Koralia Br. Khal(C) Re-excavation	1.20	195,296	Main
SP15268, Kakchira DR Subproject, DR, Union : Kakchira, HO Date: 14/11/2002				
	Part-A: Construction of WMCA office and others	12mX6m 0.00	1,426,148	PSSWRSP
	Part-A: Re-excavation of Kakchira Puran Barani Khal & 4 N	3.80	2,034,680	PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Golbunia khal re-excavation(ch.00-3000m)	3.00	3,719,164	SSSWRDP
	Katakhali-Fakirhat khal re-excavation(ch.00-5270m)	5.27	8,261,767	SSSWRDP
	Referenced line section(8nos)	0.00	120,000	SSSWRDP
	Hoglapati Khal Re-excavation	0.30	30,830	Main
	Kakchira Bharani Khal Re-excavation	2.45	446,448	Main
	Kakchira Br. Khal Re-excavation	1.00	104,044	Main
	Lakurtala Khal Re-excavation	2.55	560,482	Main
	Amtala Khal Re-excavation	1.80	342,511	Main
SP15279, Nachnapara Khal DR Subproject, DR, Union : Nanchnapara, HO Date:				
	part-A: Construction of WMCA Office and others	12mX6m 0.00	1,426,148	PSSWRSP
	part-A: Re-excavation of Aplier Khal & 3 Nos. reference line	1.90	1,237,010	PSSWRSP
	part-B: Re-excavation of Nachanpara Branch Khal-1 & 1 N	0.71	219,210	PSSWRSP
	part-C: Re-excavation of Nachanpara Branch Khal-2 & 1 N	0.50	160,175	PSSWRSP
	Natchnapara Khal Re-excavation	3.00	245,160	Main
	Natchnapara Br. Khal Re-excavation	0.87	72,554	Main
SSWRDSP-2				
SP25315, Kalmegha-Ghutabachha Subproject, DR&IRR, Union : Kalmegha, HO Date:				
	O&M Shed	Size: 9mX5m 0.00	603,474	Main
	Re-excavation of Napit Khal	1.37	276,553	Main
	Re-excavation of Bhaibra Khal	2.74	917,554	Main
	Re-excavation of Chhoto Pathorghata Khal	5.60	1,046,964	Main
	Re-excavation of Kalmegha Khal	2.00	2,332,607	Main
	Choto Pathorghata khal re-excavation(ch.00-7100m)	7.10	11,005,817	SSSWRDP
	Choto Pathorghata branch khal re-excavation(ch.00-840m)	0.84	1,166,517	SSSWRDP
	Referenced line section	0.00	120,000	SSSWRDP
Sadar				
SSWRDSP-1				
SP15290, Maitha Khal DR Subproject, DR, Union : Burir Char, HO Date: 22/06/2002				
	Part-A: WMCA Office & others	12mX6m 0.00	1,332,150	PSSWRSP
	Part-A: Re-excavation of Amrajuri Branch khal	0.30	92,026	PSSWRSP
	Part-B: Re-excavation of Dasher khal	0.75	27,612	PSSWRSP
	Part-C: Re-excavation of Dakatia khal	1.61	700,855	PSSWRSP
	Part-D: Re-excavation of Motheratala khal	0.50	116,069	PSSWRSP
	Amrajuri Khal re-excavation(ch.00-3500m)	3.50	3,142,258	SSSWRDP
	Khakbunia Khal re-excavation(ch.00-1485m)	1.49	1,807,171	SSSWRDP
	Koraitola Khal re-excavation(ch.00-1860m)	1.86	1,471,034	SSSWRDP
	Khejurtola Khal re-excavation(ch.00-1460m)	1.46	1,278,911	SSSWRDP
	Ehurchan Khal re-excavation(ch.00-1000m)	1.00	780,339	SSSWRDP
	Referenced Line section(11nos)	0.00	233,781	SSSWRDP
	Bamboo bridge(11nos)	0.00	459,979	SSSWRDP
	Maitha Khal Re-excavation	3.35	250,394	Main
	Branch Khal Re-excavation	1.17	131,224	Main
SP15332, Baliatali DR Subproject, DR, Union : Baliatali, HO Date: 15/07/2002				
	Part-A: Re-excavation of Baro Baliatali khal	3.31	1,378,175	PSSWRSP
	Part-B: Re-excavation of Baro Baliatali Branch khal	1.00	400,864	PSSWRSP
	Baliatali Khal Re-excavation	3.45	1,069,453	Main
	Agapara-Kumirmara Khal Re-excavation	2.25	775,631	Main
	Baliatali Branch Khal Re-excavation	0.55	165,031	Main
SSWRDSP-2				
SP25324, Parir Khal Subproject, FMD&WC, Union : M.Balaitali, HO Date: 03/04/2011				
	Re-excavation of Parir Khal	2.00	506,749	Main
	Re-excavation of Monasatali Branch Khal-2	0.70	189,109	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Latakata Khal	1.32	374,868	Main
	Re-excavation of Banai Khal	2.60	1,177,725	Main
	Re-excavation of Baishamerto Khal	0.60	144,519	Main
	O&M Shed	Size: 12mX6m 0.00	602,379	Main
	Re-excavation of Monasatali Khal	1.03	682,262	Main
	Re-excavation of Monasatali Branch Khal-1	1.47	272,235	Main
	Re-excavation of Parir khal	4.00	3,340,232	PSSWRSP
	Amlokitola khal re-excavation(ch.00-6100m)	6.10	7,386,641	SSSWRDP
	Bain Samerto khal re-excavation(ch.00-2000m)	2.00	2,677,052	SSSWRDP
	Referenced line section(8nos)	0.00	147,505	SSSWRDP
PSSWRSP				
SP42024, Nishanbari-Gazi Mahmud Subproject, DR, Union : Naltona, HO Date:				
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,400,000	Main
	Part-E: Construction of Reference Line Section	0.00	402,000	Main
	Part-A: Re-excavation of Nishanbari Khal	4.80	6,580,570	Main
	Part-B: Re-excavation of Bakshir Khal	0.51	332,909	Main
	Part-C: Re-excavation of Garjanbunia Khal	3.20	1,807,961	Main
	Part-D: Re-excavation of Dakatia Khal	3.20	1,973,343	Main
SP43029, Nur Ali-Burirchar Charakgachia, DR&WC, Union : Burir Char, HO Date:				
	Part-G: Re-excavation of Katakali Main khal	0.74	267,467	Main
	Part-H: Re-excavation of Katakali Branch-2 khal	1.20	295,372	Main
	Part-I: Construction of Reference Lined Section	0.00	289,983	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,385,000	Main
	Part-A: Re-excavation of Rabiul Mian khal	3.00	3,125,245	Main
	Part-B: Re-excavation of Rabiul Branch-1 khal	0.51	418,006	Main
	Part-C: Re-excavation of Rabiul Branch-2 khal	0.45	266,116	Main
	Part-D: Re-excavation of Rabiul Branch-3 khal	0.27	172,064	Main
	Part-E: Re-excavation of Rabiul khal West End	1.60	844,596	Main
	Part-F: Re-excavation of Bharini khal	0.78	650,137	Main
	Nolitolar khal re-excavation(ch.00-4500m)	4.50	3,975,345	SSSWRDP
	Charakgachia khal re-excavation(ch.00-3800m)	3.80	4,379,957	SSSWRDP
	Referenced line section(8nos)	0.00	195,356	SSSWRDP
	Bamboo bridge(6nos)	0.00	356,484	SSSWRDP
SP43030, Aylapatakata Sub-project, DR, Union : Aylapatakata, HO Date: 10/04/2014				
	Part-E: Construction of reference lined section	0.00	305,169	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,396,000	Main
	Part-A: Re-excavation of Khajuria sluice khal	4.20	3,650,255	Main
	Part-B: Re-excavation of Karamchatala khal	1.35	780,987	Main
	Part-C: Re-excav. of Lemua Daktarer sluice khal	2.40	1,963,978	Main
	Part-D: Re-excav. of Char Nalia khal	1.23	1,085,127	Main
SP43034, Potka Khali Subproject, DR, Union : Dhalua, HO Date: 02/02/2014				
	Part-G: Re-excavation of Golbonia khal	0.12	82,495	Main
	Part-H: Re-excavation of Baraitala khal	0.78	621,188	Main
	Part-I: Construction of reference lined section	0.00	471,378	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,387,000	Main
	Part-A: Re-excavation of Potkakhali Sluice khal	1.20	521,848	Main
	Part-B: Re-excavation of Potkakhali Branch khal	0.42	332,084	Main
	Part-C: Re-excavation of Lemua Khajura khal	2.60	2,290,884	Main
	Part-D: Re-excavation of Lemua Khajura Branch khal	0.70	394,398	Main
	Part-E: Re-excavation of Lemua Khajura sluice khal	1.40	809,178	Main
	Part-F: Re-excavation of Latbaria khal	0.65	490,764	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Noli Bharani khal re-excavation(ch.2600-5950m)	3.35	4,046,887	SSSWRDP
	Noli Bharani Branch khal re-excavation(ch.00-2600m)	2.60	1,703,124	SSSWRDP
	Uttar Dhalvanga khal re-excavation(ch.00-1260m)	1.26	646,833	SSSWRDP
	Golbunia khal re-excavation(ch.00-985m)	0.99	857,671	SSSWRDP
	Tunibaria khal re-excavation(ch.00-700m)	0.70	295,690	SSSWRDP
	Referenced line section(11nos)	0.00	232,773	SSSWRDP
	Bamboo bridge(11nos)	0.09	344,984	SSSWRDP
SP43041, Sonbunia Subproject, DR, Union : Baliatali, HO Date: 03/12/2013				
	Part-A : Embankment & Excavation of Drain on the East N	2.44	4,241,402	Main
	Part-B : WMCA office & others	12mx6m 0.00	1,396,854	Main
	Part-A: Regulator on Nalidon khal	1V-1.2mx1.5m 0.00	7,230,005	Main
	Aga Poddha khal re-excavation(ch.00-4700m)	4.70	6,235,789	SSSWRDP
	Ungaria khal re-excavation(ch.00-540m)	0.54	611,592	SSSWRDP
	Nolirdon khal re-excavation(ch.00-335m)	0.34	378,081	SSSWRDP
	Referenced line section(7nos)	0.00	205,521	SSSWRDP
	Bamboo bridge4nos)	0.05	183,992	SSSWRDP
SP45195, Jailkhana Khal Subproject, DR, Union : Baliatali, HO Date: 06/09/2017				
	Part-A:Construction of Box Culvert	(2v-3.0mX3.5m) 0.00	2,133,182	Main
	Part-B:Construction of Box Culvert	(1v-1.5mX1.5m) 0.00	471,106	Main
	Part-C:Construction of WMCA Office & Others	12mX6m 0.00	1,093,476	Main
	Part-A:Re-excavation of Jailkhana Khal	4.20	5,047,149	Main
	Part-B:Re-excavation of Daskin Jailkhana Khal	2.40	2,626,090	Main
	Part-C: Re-excavation of Paglar Khal	1.50	2,875,195	Main
	Part-D: Construction of Reference Lined Section	0.00	257,257	Main
SP45204, Monshatola Khal Subproject, DR&WC, Union : Baliatoli, HO Date: 06/09/2017				
	Part-A: Construction of Box Culvert (1v-3.0mX3.5m)	(1v-3.0mX3.5m) 0.00	0	Main
	Part-B: Construction of WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Monosatali khal	2.20	1,023,525	Main
	Part-B: Re-excavation of Urmitala khal	0.70	329,970	Main
	Part-C: Re-excavation of Lakurtala khal	2.40	1,850,403	Main
	Part-D: Re-excavation of Lakurtala Branch khal	0.70	263,037	Main
	Part-E: Re-excavation of Gilatala khal	1.10	1,271,684	Main
	Part-F: Construction of Reference Lined Section	0.00	193,764	Main
SP45205, Napitkhali-Burirchar Subproject, DR&WC, Union : Burirchar, HO Date:				
	Part-A: Construction of Box Culvert (2vX2.5mX3.0m)	(2vX2.5mX3.0m) 0.00	0	Main
	Part-G: Re-excavation of Madartala khal	1.70	1,086,820	Main
	Part-H: Re-excavation of Madartala Branchkhal	0.50	272,358	Main
	Part-I: Construction of reference Lined section	0.00	245,040	Main
	Part-B: Construction of Box Culvert (1vX3.0mX3.0m)	1vX3.0mX3.0m) 0.00	0	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Napitkhali Khal	1.90	1,542,241	Main
	Part-B: Re-excavation of Hazarbigha khal	1.80	2,001,777	Main
	Part-C: Re-excavation of Mozar khal	0.70	319,357	Main
	Part-D: Re-excavation of Chalitatali khal	1.00	419,358	Main
	Part-E: Re-excavation of Chalitatali Branch khal	0.50	170,838	Main
	Part-F: Re-excavation of Boroitala khal	2.10	995,919	Main
SP46216, Bayestabak Sub-project, DR, Union : Gauichanna, HO Date: 06/09/2017				
	Part-A: WMCA Office & others	12mX6m 0.00	1,483,434	Main
	Part-A: Re-excavation of Lakurtala khal,	2.70	662,528	Main
	Part-B: Re-excavation of Uttar Lakurtala khal,	3.60	1,916,101	Main
	Part-C: Re-excavation of Roadpara khal,	3.00	1,015,208	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-D: Re-excavation of Baistabok khal,	1.20	436,474	Main
	Part-E: Re-excavation of Dopur khal,	1.00	642,835	Main
	Part-F: Re-excavation of Hotar khal,	1.20	701,104	Main
	Part-G: Construcion of Reference Lined section	0.00	260,776	Main
SP46268, Nali Maitha Subproject, DR, Union : Baliatoli, HO Date: 06/09/2017				
	Part-A: Construction of WMCA Office and Others	12mX6m 0.00	1,454,274	Main
	Part-A: Re-excavation of Nalimaitha Khal	3.33	4,755,599	Main
	Part-B: Re-excavation of Harmamun Khal	1.03	437,824	Main
	Part-C: Re-excavation of Diba Maitha Khal	2.50	2,264,392	Main
	Part-D: Re-excavation of Kewatala Khal	1.13	559,285	Main
	Part-E: Re-excavation of Amtala Khal	2.05	920,545	Main
	Part-F: Re-excavation of Agnarpora Khal	1.50	576,188	Main
	Part-G: Re-excavation of Mother Tali Khal	1.40	502,376	Main
	Part-H: Construction of reference lined section	0.00	265,325	Main
Taltoli PSSWRSP				
SP46254, Karaibaria Khal, DR&WC, Union : Karaibaria, HO Date: 06/09/2017				
	Part-A: Construction of WMCA office and others	12mX6m 0.00	1,523,431	Main
	Part-A: Re-excavation of Nakchira Khal	1.00	798,101	Main
	Part-B: Re-excavation of Karaibaria Khal	5.60	2,670,581	Main
	Part-C: Re-excavation of Dobandhar Khal	0.72	107,951	Main
	Part-D: Re-excavation of Sarkar Barir Khal	0.40	84,029	Main
	Part-E: Construction of Reference lined section	0.00	97,823	Main
Barisal (Total SPs : 47 Nos.)				
Babuganj SSWRDSP-1				
SP14200, Chandrapara FCD Subproject, FCD, Union : Chandrapara, HO Date: 30/06/2003				
	Embankment Re-sectioning	6.25	2,485,100	Main
	Chandrapara khal re-excavation(ch.00-3340m)	3.34	4,275,224	SSSWRDP
	Baka khal re-excavation(ch.00-1020m)	1.02	1,475,167	SSSWRDP
	Mushuria branch khal re-excavation(ch.00-990m)	0.99	1,457,638	SSSWRDP
	Referenced line section(5nos)	0.00	115,935	SSSWRDP
	Chandrapara Embankment re-sectioning(ch.1300-2914m)	1.61	1,477,522	SSSWRDP
	Chandrapara Regulator at Ch.6+050m	1-V(1.5mX1.5m)	2,484,303	Main
	Musuria Regulator at Ch.3+115m	1-V(1.5mX1.5m)	2,335,878	Main
	Pipe Sluice at Ch.5+170m	1-V(900mm Dia.)	867,478	Main
SSWRDSP-2				
SP25314, Madhabpasa Subproject, DR&WC, Union : Madhabpasa, HO Date: 30/06/2003				
	Re-excavation of Khosaghata Khal	1.50	668,843	Main
	Re-excavation of Fultala Khal	1.56	867,734	Main
	Re-excavation of Lafadia Br. Khal	1.17	349,729	Main
	Re-excavation of Kalikhola Khal	1.50	759,424	Main
	Re-excavation of Lafadia Khal	2.50	902,298	Main
	Re-excavation of Dulaghata Khal	2.50	1,081,902	Main
	Re-excavation of Jatraghata Khal	1.00	414,637	Main
	Re-excavation of Darogabari Khal	2.50	1,025,897	Main
	Re-excavation of Badamtali-Rajner Khal	2.30	914,425	Main
	O&M Shed	Size-9mX5m 0.00	603,474	Main
	Re-excavation of Shibbari Khal	2.81	1,510,310	Main
	Part-A: Re-excavation of Durgakhali Khal	2.34	1,424,919	PSSWRSP
	Part-B: Re-excavation of Lafadi Branch Khal	1.24	643,667	PSSWRSP
	Part-C: Re-excavation of Dukur Khal	1.80	776,446	PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Uttar Lafadi khal re-excavation(ch.00-3500m)	3.50	5,003,755	SSSWRDP
	Birpasha khal re-excavation(ch.00-950m)	0.95	2,098,826	SSSWRDP
	Sultan master barir khal re-excavation(ch.00-2200m)	2.20	4,407,276	SSSWRDP
	Referenced line section(9nos)	0.00	213,663	SSSWRDP
	Bamboo bridge(11nos)	0.00	372,527	SSSWRDP
PSSWRSP				
SP43043, Dehergati Subproject, DR, Union : Dehergati, HO Date: 12/06/2016				
	Part-A: Re-excavation of Bhuter Khal	3.60	3,787,237	Main
	Part-C: Re-excavation of Darogabarir Khal	1.50	1,268,582	Main
	Part-B: Re-excavation of Chairmanbarir Khal	2.53	2,386,149	Main
	Part-E: Re-excavation of Nomorejore Khal	1.78	1,846,206	Main
	Part-D: Re-excavation of Kalibari Khal	2.15	1,661,509	Main
	Part-F: Re-excavation of Chairmanbarir branch Khal	1.04	441,575	Main
	Part-G: Construction of Reference Lined section	0.00	558,709	Main
	Part-A: Construction of WMCA Office & others	12mx6m 0.00	1,399,056	Main
SP44081, Thakur Mollik Subproject, WC,DR&IRR, Union : Jahangir nagar(Agorpur), HO				
	Part-B: Re-excavation of Thakurmallik Meherhowla khal	2.73	2,579,980	Main
	Part-A: Constructon of WMCA Office	0.00	3,409,500	Main
	Part-C: Re-excavation of Beparibarir khal	0.49	224,409	Main
	Part-D: Re-excavation of Daiibarir khal	4.37	3,849,194	Main
	Part-E: Re-excavation of Char Mahisha khal	0.77	395,211	Main
	Part-F: Re-excavation of Hakim Moulavir khal	2.24	1,877,547	Main
	Part-A: Re-excavation of Char Mahisha Thakurbarir khal	3.64	3,306,513	Main
	Part-G: Constructon of Reference Lined Section	0.00	542,027	Main
SP45150, Chandpasha Subproject, DR&WC, Union : Chandpasha, HO Date: 06/09/2017				
	Part-A: WMCA Office & others	12mX6m 0.00	1,059,094	Main
	Part-I: Re-excavation of Sonabhanir Khal	0.95	701,996	Main
	Part-J: Re-excavation of Sonai Mollah Varani Khal	1.00	701,510	Main
	Part-K: Construction of Reference Lined Section	0.00	344,997	Main
	Part-A: Re-excavation of Chandipur Khal	2.70	1,832,737	Main
	Part-B: Re-excavation of Varanir Khal	1.50	1,358,755	Main
	Part-C: Re-excavation of Chandipur Branch Khal	1.29	1,521,448	Main
	Part-D: Re-excavation of Chandipur Sub Branch Khal	0.45	531,497	Main
	Part-E: Re-excavation of Adurhota Khal	0.32	210,045	Main
	Part-F: Re-excavation of Rari Barir Khal	0.90	822,084	Main
	Part-G: Re-excavation of Sadai Barir Khal	0.90	533,064	Main
	Part-H: Re-excavation of Gain Barir Khal	0.95	795,194	Main
SP45171, Mohongonj Subproject, DR&WC, Union : Madhabpasha, HO Date: 07/05/2018				
	Part-A: Construction of Pucca Drain-1 (L=.200km)	(L=.200km) 0.00	934,323	Main
	Part-C: Re-excavation of Mohongonj Br. Khal	0.50	421,458	Main
	Part-D: Re-excavation of Hijla Khal	4.00	2,982,227	Main
	Part-E: Re-excavation of Goalbathan Khal	1.59	515,208	Main
	Part-F: Re-excavation of Gajalia Khal	1.70	1,256,089	Main
	Part-G: Construction of Reference Lined Section	0.00	387,974	Main
	Part-B: Construction of Pucca Drain-2 (L=.200km)	(L=.200km) 0.00	934,323	Main
	Part-D: Construction of Pucca Drain-4 (L=.200km)	(L=.200km) 0.00	934,323	Main
	Part-E: Box Culvert-1 (1v-4.00mX4.00m)	(1v-4.00mX4.00m) 0.00	1,630,628	Main
	Part-F: Box Culvert-2 (1v-3.50mX3.50m)	(1v-3.50mX3.50m) 0.00	1,393,144	Main
	Part-C: Construction of Pucca Drain-3 (L=.200km)	(L=.200km) 0.00	934,323	Main
	Part-G: WMCA Office & Others	12mX6m 0.00	1,112,732	Main
	Part-A: Re-excavation of Mohonganj Khal	2.05	1,795,606	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP46273, Niamotullah-Daskin Bhulordia Subproject, DR, Union : Jahangir nagar(Agorpur),	Part-B: Re-excavation of Satia khal	1.44	789,694	Main
	Part-A: Construction of WMCA office and others	12m X 6m 0.00	1,438,746	Main
	Part-A: Re-excavation of Niamotullah Khal	4.73	1,924,086	Main
	Part-B: Re-excavation of Khonker Khal	2.08	1,751,747	Main
	Part-C: Re-excavation of Mallik Barir Khal	0.90	858,910	Main
	Part-D: Re-excavation of Beeler Khal	3.20	1,475,707	Main
	Part-E: Re-excavation of Chaltir Khal	1.18	1,052,550	Main
	Part-F: Re-excavation of Chaltir Branch Khal	0.80	642,598	Main
SP46274, Rabipur Subproject, FMD&WC, Union : Jahangir nagar(Agorpur), HO Date:	Part-G: Construction of Reference Lined Section	0.00	0	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	1,480,875	Main
	Part-A: Re-excavation of Embankment (south)	1.19	2,721,794	Main
	Part-B: Re-excavation of Khalishakhali-Bharanir khal	0.60	422,762	Main
	Part-C: Re-excavation of Khalishakhali khal	1.80	869,101	Main
	Part-D: Re-excavation of Sharif Barir khal	0.61	279,212	Main
	Part-E: Re-excavation of Meur khal	1.73	2,277,224	Main
	Part-F: Construction of Referenece Lined Section	0.00	154,890	Main
Bakerganj SSWRDSP-1				
SP13102, Faridpur FCD Subproject, FCD, Union : Faridpur, HO Date: 18/12/2003				
	Embankment Re-sectioning	6.68	2,440,521	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	1,496,477	PSSWRSP
	Part-A: Re-excavation of Faridpur khal	2.30	1,671,270	PSSWRSP
	Part-B: Re-excavation of Mangali khal	1.70	1,063,644	PSSWRSP
	Part-C: Re-excavation of Mangali Mora khal	0.70	405,053	PSSWRSP
	Mallikbari Khal Re-excavation	1.50	48,399	Main
	Faridpur Regulator	1-V(1.5mX1.8m)	2,126,771	Main
SP14122, Raghunathdi FCD Subproject, FCD, Union : Faridpur, HO Date: 12/10/2005	Embankment Re-sectioning	14.88	3,782,891	Main
	Bhatsala Khal Re-excavation	1.05	124,327	Main
	Raghunathdi Khal Regulator at Ch. 3+680m	2-V(1.2mX1.5m)	3,347,892	Main
	Mollar Khal Regulator at Ch. 5+430m	2-V(1.2mX1.5m)	1,959,911	Main
	Pipe Sluice at Ch. 9+330m	1-V(1.2m dia)	1,142,175	Main
	Bhatsala Khal Regulator at Ch. 11+280m	1-V(2.0mX2.4m)	1,989,487	Main
SP14123, Niamati FCD Subproject, FCD, Union : Niamati, HO Date: 06/12/2006	Embankment Re-sectioning	10.06	2,815,027	Main
	Samaddar Khal Re-excavation	1.50	162,668	Main
	Niamati-Varani Khal Regulator at Ch. 0+310m	3-V(1.2mX1.2m)	2,278,309	Main
	Mandalbari Khal Regulator at Ch. 3+280m	1-V(1.5mX1.5m)	1,314,123	Main
	Samaddar Khal Regulator at Ch. 3+660m	1-V(1.5mX1.5m)	1,567,007	Main
	Matiadubir Khal Regulator at Ch. 5+800m	2-V(1.5mX1.5m)	2,620,530	Main
	Tengrakhal Khal Regulator at Ch. 6+300m	2-V(1.2mX1.2m)	2,454,521	Main
	Barardhan Br. Khal Regulator at Ch. 7+600m	2-V(1.2mX1.2m)	2,683,021	Main
SP14181, Kazlakathi FCD Subproject, FCD, Union : Darial, HO Date: 10/05/2003				
	Embankment Re-sectioning	15.90	4,920,284	Main
	Andahrmanik Khal Regulator at Ch.6+950m	1-V(1.5mX1.5m)	1,645,600	Main
	Matibhanga Khal Regulator at Ch.7+750m	1-V(1.5mX1.5m)	1,708,000	Main
	Khutnar Khal Regulator at Ch.9+120m	1-V(1.5mX1.5m)	2,768,177	Main
	Nimair Khal Regulator at Ch.12+130m	1-V(1.5mX1.5m)	1,613,927	Main
SP15270, Bharpasa FCD Subproject, FCD, Union : Bharpasa, HO Date: 20/05/2010				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Embankment Re-sectioning	14.55	6,397,355	Main
	Gazalia Regulator at Ch.9+780m	2-V(1.5mX1.8m)	2,968,991	Main
	Purashula Regulator at Ch.8+730m	2-V(1.5mX1.8m)	4,055,111	Main
	Kamarkhali Regulator at Ch.5+850m	2-V(1.5mX1.8m)	3,023,773	Main
SP15294, Kabai FCD Subproject, FCD, Union : Kabai, HO Date: 10/05/2010				
	Embankment Re-sectioning	17.13	6,310,672	Main
	Part-A: WMCA & others	(12mX6m) 0.00	1,506,808	PSSWRSP
	Part-A: Re-excavation fo Datta Bari khal	3.08	191,490	PSSWRSP
	Part-B: Re-excavation fo Datta Bari Branch khal	1.35	512,731	PSSWRSP
	Chunakhali Regulator at Ch.0+000m	1-V(1.5mX1.8m)	2,730,264	Main
	Sundarkathi Regulator at Ch.1+470m	1-V(1.5mX1.8m)	1,724,450	Main
	Dattabari Regulator at Ch.2+630m	1-V(1.5mX1.8m)	2,500,774	Main
	Kristoganj Regulator at Ch.8+800m	2-V(1.5mX1.5m)	3,917,308	Main
	Bholania Regulator at Ch.15+585m	1-V(1.5mX1.8m)	4,077,526	Main
SP15319, Baloikathi FCD Subproject, FCD, Union : Charadi, HO Date: 22/07/2003				
	Embankment Re-sectioning	16.65	8,374,047	Main
	Nomor Regulator at Ch.8+585m	2-V(1.5mX1.8m)	2,859,820	Main
	Gopalpur Regulator at Ch.5+110m	2-V(1.5mX1.8m)	4,001,000	Main
	Mokimabad Pipe Sluice	1-V(900mm Dia)	813,750	Main
	Dupabaria Pipe Sluice	1-V(900mm Dia)	815,289	Main
SSWRDSP-2				
SP24133, Padrishibpur Subproject, DR&WC, Union : Padrishibpur, HO Date: 03/11/2008				
	Re-excavation of Kolar Khal	0.60	55,808	Main
	Re-excavation of Asir Khal	0.37	41,333	Main
	Re-excavation of Noakata Khal	2.50	281,719	Main
	Re-excavation of Andhar Manik Khal	1.13	126,918	Main
	Re-excavation of Andhar Manik Branch Khal	0.69	60,455	Main
	Re-excavation of Masuakhali Khal	1.60	185,853	Main
	Re-excavation of Girjar Khal	2.40	325,060	Main
	Re-excavation of Molla Danga Khal	2.04	279,700	Main
	Re-excavation of Kata Khali Khal	1.67	455,208	Main
	Re-excavation of Mollar Jor Khal	2.04	636,228	Main
	Re-excavation of Balahi Khal	1.40	221,250	Main
	Re-excavation of Joint Khal	1.80	383,796	Main
	Re-excavation of Sundarkhali Khal	1.70	142,930	Main
	Re-excavation of Kazir Danga Khal	0.57	106,529	Main
PSSWRSP				
SP43049, Kafila-Krishnanagar Subproject, DR, Union : Niamati, HO Date: 05/06/2016				
	Part-E: Re-excavation of Krishnanagar Khal	1.75	1,486,664	Main
	Part-F: Re-excavation of Sikdarbari Branch Khal	2.35	3,650,409	Main
	Part-A: Re-excavation of Boulakir Khal	2.68	2,082,894	Main
	Part-B: Re-excavation of Choukidarbarir Khal	1.50	1,758,727	Main
	Part-D: Re-excavation of Karkarbarir Khal	1.47	1,226,435	Main
	Part-C: Re-excavation of Gazibarir Khal	2.20	2,876,385	Main
	Part-G: Construction of Ref. Lined Section of khal	0.00	513,636	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,374,243	Main
SP44075, Losnabad Phalaghar Subproject, DR, Union : Rangusree, HO Date: 06/06/2016				
	Part-A: Re-excavation of Manik khali Branch Khal	2.62	484,518	Main
	Part-B: Re-excavation of Kaliabari khal	2.25	1,229,474	Main
	Part-C: Re-excavation of Mothura khal	2.13	1,399,549	Main
	Part-D: Re-excavation of Manik Khali khal	1.08	629,135	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-E: Re-excavation of Manik Khali khal (Branch)	1.75	484,518	Main
	Part-F: Re-excavation of Kamarbari khal	2.61	2,547,700	Main
	Part-G: Re-excavation of Kumarbari khal	2.25	1,915,624	Main
	Part-H: Construction of Reference Lined Section	0.00	541,430	Main
	Part-A: WMCA Office & Others	12mx6m 0.00	1,509,447	Main
SP44097, Dudhal Subproject, FMD, Union : Dudhol, HO Date: 14/06/2018				
	Part-A: Construction of Begbari khal Regulator	(2-V 1.2mx1.5m) 0.00	0	Main
	Part-B: Construction of Molikjhir khal pipe Sluice	(1-v 900mm dia) 0.00	0	Main
	Part-C: Construction of Howladar Barir khal pipe Sluice	(1-v 900mm dia) 0.00	0	Main
	Part-D: Construction of WMCA Office & others	12mx6m 0.00	0	Main
	Part-A: Re-excavation of Begbari Khal	1.70	901,524	Main
	Part-B: Re-excavation of Molikjhir Khal	0.87	560,925	Main
	Part-C: Re-excavation of Howladar bari Khal	0.52	417,071	Main
	Part-D: Re-excavation of Belebarir Khal	1.00	687,949	Main
	Part-E: Re-Sectioning of Embankment	6.33	2,157,269	Main
SP45155, Baro Raghunathpur Subproject, DR, Union : Fadrishibpur, HO Date: 06/09/2017				
	Part-A: WMCA Office & others	12mX6m 0.00	1,381,100	Main
	Part-A: Re-excavation of Tulatoli khal	2.10	1,236,517	Main
	Part-B: Re-excavation of Katakali khal	1.63	2,023,388	Main
	Part-C: Re-excavation of Motherbania khal	2.20	1,199,735	Main
	Part-D: Re-excavation of Patacharia khal	0.64	338,554	Main
	Part-E: Re-excavation of Nazurhota khal	1.10	1,169,660	Main
	Part-F: Construction of Reference Lined Section	0.00	222,780	Main
SP45165, Darial Subproject, DR&WC, Union : Darial, HO Date: 27/06/2018				
	Part-A: Construction of Pucca Drain-1, Length.300 km	0.00	1,385,152	Main
	Part-F: Construction of Reference Lined Section	0.00	494,581	Main
	Part-B: Construction of Pucca Drain-2, Length .300 km	0.00	1,339,822	Main
	Part-C: Construction of Box Culvert (1v-2.50mX2.50m)	0.00	1,050,559	Main
	Part-D: Construction of WMCA Office & Others	12mX6m 0.00	1,070,689	Main
	Part-A: Re-excavation of Barujipara khal	1.15	699,852	Main
	Part-B: Re-excavation of Arial Khan khal	2.98	816,378	Main
	Part-C: Re-excavation of Nawaberhat khal	0.63	443,231	Main
	Part-D: Re-excavation of Kamarkali khal	4.78	2,944,204	Main
	Part-E: Re-excavation of Kumarbarirkhal	4.44	1,799,483	Main
SP45173, Charadi Subproject, DR&WC, Union : Charadi, HO Date: 06/09/2017				
	Part-A: Construction of Pucca Drain -1 (L=0.100km)	(L=0.100km) 0.00	497,682	Main
	Part-D: Re-excavation of Suterbarir Khal	0.70	386,707	Main
	Part-E: Re-excavation of Malek Khondokarbarir Khal	1.00	509,774	Main
	Part-F: Re-excavation of Debidaser Khal	0.70	404,257	Main
	Part-G: Re-excavation of Rohajer Khal	1.12	948,781	Main
	Part-H: Re-Sectioning of Charadi Embankment	5.30	6,144,958	Main
	Part-I: Construction of Reference Lined section	0.00	288,101	Main
	Part-B: Construction of Pucca Drain -2 (L=0.100km)	(L=0.100km) 0.00	509,684	Main
	Part-C: Construction of Pucca Drain -3 (L=0.100km)	(L=0.100km) 0.00	507,098	Main
	Part-D: Box Culvert-1 (1v-2.50mX3.50m)	(1v-2.50mX3.50m) 0.00	1,136,083	Main
	Part-E: Box Culvert-2 (1v-3.50mX3.50m)	(1v-3.50mX3.50m) 0.00	1,777,599	Main
	Part-F: WMCA Office & Others	12mX6m 0.00	1,035,207	Main
	Part-A: Re-excavation of Kazem Sikderbarir Khal	1.90	1,337,423	Main
	Part-B: Re-excavation of Baniar Khal	0.65	331,202	Main
	Part-C: Re-excavation of Madrar Khal	1.00	474,768	Main
SP45211, Uttampur Drainage Subproject, DR, Union : Uttampur, HO Date: 14/05/2018				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: WMCA Office & others	12mX6m 0.00	1,372,902	Main
	Part-A: Re-excavation of Baorer khal	2.50	1,974,562	Main
	Part-B: Re-excavation of Dhali Barir khal	2.40	1,185,926	Main
	Part-C: Re-excavation of Dhali Barir Branch khal	0.70	643,851	Main
	Part-D: Re-excavation of Jalia Barir khal	1.40	1,271,193	Main
	Part-E: Re-excavation of Modhu kati khal	2.60	1,189,107	Main
	Part-F: Re-excavation of Modhu kati Branch khal	1.00	714,311	Main
	Part-G: Construction of Reference Lined Section	0.00	207,184	Main
Banaripara SSWRDSP-2 SP22020, Kachua Subproject, DR, Union : Baisari, HO Date: 06/12/2006				
	Molla Bari,Haider & Balipara Khal Re-excavation	1.57	203,798	Main
	Sekender & Kasem Bepari Khal Re-excavation	1.30	230,311	Main
	Lalu Farazi Bari Khal Re-excavation	0.80	154,490	Main
	Natuapara Khal Re-excavation	1.05	182,813	Main
	Sialkathi Khal Re-excavation	1.20	341,189	Main
	Panchayet Bari Khal Re-excavation	0.82	91,325	Main
	Dandat Khal Re-excavation	2.95	786,354	Main
	Basur Hat Khal Re-excavation	2.70	441,172	Main
	Datt Bari Khal Re-excavation	1.50	173,664	Main
	Andha Huzur Khal Re-excavation	0.63	120,820	Main
	Swanirbhar Khal-2 Re-excavation	1.35	253,840	Main
	Barammagati Masjid Khal Re-excavation	1.02	170,745	Main
	Muslimpara Khal Re-excavation	0.70	123,713	Main
	Dandat Br. Khal Re-excavation	1.50	167,734	Main
	Kachua Br. & Jalal Khal Re-excavation	1.90	293,345	Main
	Balipara Khal Re-excavation	1.78	325,902	Main
	Sabuj Biplob Khal Re-excavation	1.05	120,879	Main
	Swanirbhar Khal-1 Re-excavation	1.56	264,827	Main
SP22041, Jambudwip Subproject, DR, Union : Banaripara, HO Date: 06/12/2006				
	Machrang Khal Re-excavation	2.27	281,349	Main
	Rajakpur-Ghoperpal Khal Re-excavation	2.05	631,248	Main
	Satten Master Bari Khal Re-excavation	1.38	318,537	Main
	Sadhak Bari Khal Re-excavation	0.97	157,023	Main
	Chowkider Bari & Kalikhola Khal Re-excavation	0.80	142,173	Main
	Alta Rajakpur Khal Re-excavation	1.65	515,093	Main
	Talibari Dighirpar Khal Re-excavation	0.70	113,044	Main
	Napitbari Khal Re-excavation	1.33	196,655	Main
	Howlader,Mridah & Dewri Bari Khal Re-excavation	1.00	125,602	Main
	Suratia Khal Re-excavation	0.95	221,881	Main
	Khan Bari Khal Re-excavation	1.47	267,018	Main
	Uttara Gabha Khal Re-excavation	1.00	223,933	Main
	Gabha School Khal Re-excavation	1.85	477,395	Main
	Kazi Bari Khal Re-excavation	1.34	260,499	Main
	Shyem Bari Khal Re-excavation	1.22	275,071	Main
	Ali Hossain Bari Khal Re-excavation	0.52	71,001	Main
PSSWRSP SP44125, Chakhar Subproject, DR, Union : Chakhar, HO Date: 05/09/2017				
	Part-A: Construction of WMCA Office & others	12mX6m 0.00	1,493,370	Main
	Part-A: Re-excavation of Chakhar Khal	6.80	4,121,320	Main
	Part-B: Re-excavation of Ashurail Khal	4.98	3,227,903	Main
	Part-C: Re-excavation of Kholishakota Khal	2.75	2,908,976	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-G: Construction of Reference Lined Section	0.00	408,288	Main
	Part-D: Re-excavation of Asurail Khal	1.83	1,738,793	Main
	Part-E: Re-excavation of Pachim Chakar Khal	0.80	694,928	Main
	Part-F: Re-excavation of Shakharia Khal	0.93	1,138,704	Main
SP46275, Saidkati Subproject, DR, Union : Chakhar, HO Date: 13/09/2017				
	Part-G: Re-excavation of Mokbul Howlader Barir Khal	0.83	206,012	Main
	Part-H: Construction of reference Lined Section	0.00	303,158	Main
	Part-A: WMCA office & Others	12mX6m 0.00	1,440,376	Main
	Part-A: Re-excavation of Saidkati khal	3.92	3,496,770	Main
	Part-B: Re-excavation of Inder Howla khal	4.12	2,747,496	Main
	Part-C: Re-excavation of Hakim Akand Khal	1.70	785,340	Main
	Part-D: Re-excavation of Ali Hossen Khal	1.48	836,746	Main
	Part-E: Re-excavation of Mokbul Howlader Barir Br. Khal	1.43	252,534	Main
	Part-F: Re-excavation of Jirakati Khal	1.25	1,002,373	Main
Gournadi SSWRDSP-1				
SP15306, Mahilara FCD Subproject, FCD, Union : Mahilara, HO Date: 03/12/2003				
	Embankment Re-sectioning	16.85	7,045,310	Main
	Re-excavation of Madha Bejagar Khal	1.43	1,210,223	PSSWRSP
	Re-excavation of Uttar Bejagar Khal	1.14	1,217,360	PSSWRSP
	Re-excavation of Kashembad Khal	0.65	1,736,126	PSSWRSP
	Lebutoli khal re-excavation(ch.00-3500m)	3.50	4,249,966	SSSWRDP
	Mahilara embankment re-sectioning(ch.6600-10900m)	4.30	7,049,986	SSSWRDP
	Referenced line section(4nos)	0.00	109,287	SSSWRDP
	Bamboo Bridge(3nos)	0.00	147,605	SSSWRDP
	Labutali Regulator at Ch.6+605m	1-V(1.5mX1.8m)	3,352,917	Main
	Sarifabad Regulator at Ch.14+805m	1-V(1.5mX1.8m)	3,352,967	Main
	Char Diasur Khal Pipe Sluice at Ch.4+850m	1-V(900mm Dia)	1,555,488	Main
	Char Ramjanpur Khal Pipe Sluice at Ch.3+810m	1-V(900mm Dia)	1,555,487	Main
	Haolader Bari Khal Pipe Sluice at Ch.8+410m	1-V(900mm Dia)	1,555,487	Main
SP15307, Sarikal FCD Subproject, FCD, Union : Sarikal, HO Date: 21/08/2004				
	Embankment Re-sectioning	11.85	3,579,426	Main
	Part-A: Re-excavation of Hsnabad khal	3.30	2,093,787	PSSWRSP
	Part-B: Re-excavation of Saricol khal	2.00	1,307,900	PSSWRSP
	Part-C: Construction of Reference Lined Section	0.00	101,569	PSSWRSP
	Char sarikal khal re-excavation(ch.00-1600m)	1.60	1,982,674	SSSWRDP
	Maddha Hasnabad khal re-excavation(ch.00-1400m)	1.40	2,046,991	SSSWRDP
	Patur khal re-excavation(ch.00-1600m)	1.60	2,021,414	SSSWRDP
	Referenced line section(5nos)	0.00	106,890	SSSWRDP
	Bamboo bridge(3 nos)	0.00	158,148	SSSWRDP
	Embankment re-sectioning(ch.00-1200m)	1.20	1,787,667	SSSWRDP
	Hasnabad Regulator at Ch.7+770m	1-V(1.5mX1.8m)	3,352,967	Main
	Sarikol Regulator at Ch.7+920m	1-V(1.5mX1.8m)	3,352,967	Main
	Hasnabad Khal Pipe Sluice at Ch.1+170m	1-V(900mm Dia)	1,555,487	Main
	Purba Hasnabad Khal Pipe Sluice at Ch.4+485m	1-V(900mm Dia)	1,555,487	Main
	Maddham Hasnabad Khal Pipe Sluice at Ch.5+460m	1-V(900mm Dia)	1,555,487	Main
SP15308, Nalchira FCD Subproject, FCD, Union : Nalchira, HO Date: 07/12/2003				
	Embankment Re-sectioning	10.80	4,255,245	Main
	Part-A: Re-excavation of South Pingiakathi Khal	2.70	1,800,870	PSSWRSP
	Part-B: Re-excavation of West Hazipara Khal	1.60	1,575,389	PSSWRSP
	Gorangal khal re-excavation(ch.00-6200m)	6.20	0	SSSWRDP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Referenced line section(6nos)	0.00	169,047	SSSWRDP
	Bamboo bridge (6nos)	0.00	316,297	SSSWRDP
	WMCA Office	12mX6m 0.00	2,079,594	SSSWRDP
	Pingati-Nalchira Bazar Khal Re-excavation	3.96	1,078,437	Main
	Paschim Pingamkathi Regulator at Ch.2+065m	1-V(1.5mX1.8m)	3,352,967	Main
	Garangal Regulator at Ch.17+885m	1-V(1.5mX1.8m)	3,352,967	Main
	Pingalkathi Regulator at Ch.19+360m	1-V(1.5mX1.8m)	3,352,967	Main
	Ambari Pipe Sluice at Ch.6+600m	1-V(900mm Dia)	1,555,888	Main
	Kalibari Pipe Sluice at Ch.1+328m	1-V(900mm Dia)	1,555,487	Main
	Nalchira Pipe Sluice at Ch.10+500m	1-V(900mm Dia)	1,555,487	Main
	Kutubpur Pipe Sluice at Ch.15+175m	1-V(900mm Dia)	1,555,487	Main

Mehendiganj
SSWRDSP-1

SP13040, Chilmar FCD Subproject, FCD, Union : Biddyanandapur, HO Date: 16/08/2010

Embankment Re-sectioning	8.69	3,716,038	Main
Approach Embankment of Regulator	0.06	18,873	Main
Naktir Khal Re-excavation (Ch: 0 - 1700 m)	1.70	1,548,233	SSSWRDP
Beparir Khal Re-excavation (Ch: 0 - 1800 m)	1.80	1,389,974	SSSWRDP
Khal Bunia Khal Re-excavation (Ch: 0 - 1300 m)	1.30	1,069,020	SSSWRDP
Chilmar Embankment Re-sectioning(1500m)	1.50	5,229,983	SSSWRDP
Referenced line section (6nos)	0.00	132,691	SSSWRDP
Byder & Nayer Khal Re-excavation	0.52	16,981	Main
Pipe Sluice at Ch.2+508m	1-V(600mm Dia)	402,017	Main
Pipe Sluice at Ch.4+458m	1-V(600mm Dia)	404,635	Main
Pipe Sluice at Ch.4+858m	1-V(600mm Dia)	398,871	Main
Pipe Sluice at Ch.6+410m	1-V(600mm Dia)	407,995	Main
Regulator at Ch.8+483m	1-V(1.5mx1.8m)	524,522	Main
Regulator at Ch.4+858m	1-V(1.5mx1.5m)	2,454,271	Main

SP14170, Bhasanchar FCD Subproject, FCD, Union : Bhasanchar, HO Date: 16/08/2010

Embankment Re-sectioning	14.25	4,067,158	Main
Majgram Khal Re-excavation	1.50	94,156	Main
Bhasanchar Regulator at Ch.0+000	1-V(1.2mX1.5m)	2,477,877	Main

SP14171, Khajuria FCD Subproject, FCD, Union : Biddyanandapur, HO Date: 16/08/2010

Embankment Re-sectioning	16.10	6,971,311	Main
Part-A: Re-excavation east Ratanpur Khal	3.50	1,630,059	PSSWRSP
Char khajuria khal re-excavation(ch.00-2600m)	2.60	3,513,427	SSSWRDP
Tulatoli khal re-excavation(ch.00-2300m)	2.30	2,435,042	SSSWRDP
Majer khal re-excavation(ch.00-1700m)	1.70	1,741,569	SSSWRDP
Referenced line section(6nos)	0.00	136,287	SSSWRDP
Bamboo bridge(1nos)	0.10	337,383	SSSWRDP
Embankment re-sectioning(ch.00-3200m)	3.20	4,060,519	SSSWRDP
WMCA Office	12mX6m 0.00	0	SSSWRDP
Ratanpur Khal Re-excavation	1.20	82,617	Main
Char Santoshpur Regulator at Ch.7+450m	1-V(1.2mX1.2m)	1,663,275	Main
Tulatuliir Khal Regulator at Ch.8+840m	1-V(1.2mX1.2m)	1,660,051	Main
Ratanpur Khal Regulator at Ch.10+950m	1-V(1.2mX1.2m)	1,683,378	Main

PSSWRSP

SP44136, Paschim Cheyam Takta, DR, Union : Bshanchar, HO Date: 07/09/2017

Part-A: WMCA office & others	12mX6m 0.00	1,452,940	Main
Part-A: Re-excavation fo Chilman khal	2.20	3,709,097	Main
Part-B: Re-excavation fo Paschim Chayan Taktkf Khal	2.10	1,176,739	Main
Part-C: Re-excavation fo Kazikanda Khal	1.27	1,150,180	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-E: Re-excavation fo Chaimanbarir Khal	1.00	429,973	Main
	Part-D: Re-excavation fo Tumchar Khal	0.40	386,252	Main
	Part-F: Construction of Reference lined Section	0.00	521,924	Main
SP45152, Biddyanandapur Subproject, DR, Union : Bidyanandapur, HO Date: 12/11/2016				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,452,940	Main
	Part-A: Re-excavation of Mia Khar Varanir Khal	3.50	2,913,839	Main
	Part-B: Re-excavation of Mollar Khal	1.90	1,828,141	Main
	Part-C: Re-excavation of Chaukiderbarir Khal	0.20	115,403	Main
	Part-D: Re-excavation of Hossain Chaukiderbarir Khal	0.50	258,862	Main
	Part-E: Re-excavation of Babul Chaukiderbarir Khal	1.80	610,918	Main
	Part-F: Re-excavation of Burir Shikarir Khal	1.00	368,057	Main
	Part-G: Construction of Reference Lined Section	0.00	218,181	Main
Muladi SSWRDSP-1				
SP13073, Kazir Char DR Subproject, DR, Union : Kazir Char, HO Date: 07/12/2003				
	Part-A: Re-excavation of Koyler Branch Khal	1.90	2,148,970	PSSWRSP
	Part-B: Re-excavation of Howlader Branch Khal	1.10	559,990	PSSWRSP
	Part-C: Re-excavation of Madrashar Khal	0.60	730,775	PSSWRSP
	Bariar Khal Re-excavation	3.23	464,000	Main
	Ragua Khal Re-excavation	2.98	466,000	Main
	Bangabandhu Khal Re-excavation	1.55	53,353	Main
SP14196, Toyka FCD Subproject, FCD, Union : Batamara, HO Date: 20/10/2003				
	Embankment Re-sectioning	12.30	6,757,945	Main
	Part-A: Re-excavation of khoner Dange Khal	0.48	295,683	PSSWRSP
	Part-B: Re-excavation of Bepari barir khal	1.60	832,551	PSSWRSP
	Part-C: Re-excavation of Shajir khal	0.50	164,092	PSSWRSP
	Part-D: Re-excavation of Char Algi Shajir khal	1.45	493,810	PSSWRSP
	Part-E: Re-excavation of Rishi Barir khal	1.30	776,460	PSSWRSP
	Part-F: Re-excavation of Char Algi Shajir Branch khal	0.50	391,139	PSSWRSP
	Beparir Khal Re-excavation	2.30	163,160	Main
	Beparir Khal Regulator	1-V(1.5mX1.8m)	1,737,326	Main
	Pipe Sluice at Ch.1+328m	1-V(900mm Dia)	939,730	Main
	Pipe Sluice at Ch.2+595m	1-V(900mm Dia)	939,680	Main
	Pipe Sluice at Ch.8+280m	1-V(900mm Dia)	939,680	Main
SP15274, Sreemoti FCD Subproject, FCD, Union : Gachua, HO Date: 05/02/2006				
	Embankment Re-sectioning	10.95	6,767,061	Main
	Re-excavation of Modha-Gachua Khal	2.10	2,652,052	PSSWRSP
	Re-excavation of Hosnabad Khal	5.03	632,897	PSSWRSP
	Domoritata Khal Re-excavation	2.10	664,054	Main
	Nomorhat Pakhya Khal Re-excavation	2.60	984,350	Main
	Domoritata Regulator at Ch.1+815m	2-V(1.5mX1.8m)	3,137,000	Main
	Nomorhat Regulator at Ch.7+685m	2-V(1.5mX1.8m)	3,103,176	Main
	Galaibhanga Pipe Sluice at Ch.10+025m	1-V(900mm Dia)	618,244	Main
	O&M Shed		0	Main
SSWRDSP-2				
SP25313, Char Batamara & Shafipur Subproject, IRR, Union : Batamara, HO Date:				
	Re-excavation of Char Batamara Shofipu-Boalia Khal	6.40	5,065,659	Main
	O&M shed	Size: 9mX5m 0.00	603,474	Main
PSSWRSP				
SP46217, Tum Char -Charshahebrampur Subproject, DR, Union : Batamara, HO Date:				
	Part-B: Re-excavation of Thumchar khal	2.55	1,968,365	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: Re-excavation of Chitirchar-Chaklabazar khal	2.50	1,647,653	Main
	Part-C: Re-excavation of Thumchar Branch khal	1.10	1,418,042	Main
	Part-D: Re-excavation of Madrasa Bazar khal	1.50	358,921	Main
	Part-E: Re-excavation of Madrasa Bazar Branch khal	0.25	176,196	Main
	Part-F: Construction of Reference Lined Section	0.00	166,028	Main
	Part-A: WMCA office & others	12mX6m 0.00	1,479,084	Main
SP46219, Muladi Drainge Subproject, DR, Union : Muladi,Kazir Char, HO Date:				
	Part A: Construction of WMCA Office & Others	12m X 6m 0.00	1,376,249	Main
	Part A: Re-excavation of Baider Khal	1.20	1,903,033	Main
	Part B: Re-excavation of Boyatibarir Khal	2.40	1,552,518	Main
	Part C: Re-excavation of Dhumer Khal	2.20	1,832,427	Main
	Part D: Re-excavation of Dhumer Branch Khal	0.50	758,299	Main
	Part E: Re-excavation of Jailer Khal	1.30	1,891,255	Main
	Part F: Re-excavation of Jamtolar Khal	2.40	354,565	Main
	Part G: Re-excavation of Rayer Khal	2.10	457,328	Main
	Part H: Construction of Reference Link Section	0.00	351,696	Main
Sadar				
SSWRDSP-1				
SP13105, Charmonai FCD Subproject, FCD, Union : Charmonai, HO Date: 10/04/2002				
	Embankment Re-sectioning	19.93	7,785,296	Main
	Embankment Rehab.(Ch. 5+080m - 5+109m)	0.03	11,382	Main
	Embankment Rehab.(Ch. 2+790m - 2+908m)	0.12	26,964	Main
	Embankment Rehab.(Ch. 0+805m - 0+965m)	0.16	41,364	Main
	Pasurikathi Khal Re-excavation	1.91	117,790	Main
	Ichaguri & Biswa Khal Re-excavation	0.90	115,451	Main
	Pasurikathi Regulator	1-V(1.5mX1.8m)	1,621,971	Main
	Char Hogla Regulator	1-V(1.5mX1.5m)	1,680,047	Main
	Ichagura Regulator	1-V(1.5mX1.8m)	1,740,102	Main
	Embankment Protection Works		241,400	Main
SP14213, Saluka FCD Subproject, FCD, Union : Sayestabad, HO Date: 11/04/2002				
	Embankment Re-sectioning	11.70	5,383,299	Main
	Saluka Khal Re-excavation	0.60	68,468	Main
	Keutia Khal Re-excavation	1.05	50,893	Main
	Regulator at Ch.4+381m	1-V(1.2mX1.2m)	1,149,414	Main
	Pipe Sluice at Ch.0+154m	1-V(900mm Dia.)	788,328	Main
PSSWRSP				
SP44111, Kasipur Subproject, DR, Union : Kasipur, HO Date: 21/09/2017				
	Part-A: Construction of WMCA Office & Others	12mX6m 0.00	1,516,742	Main
	Part-A: Re-excavation of Rayer khal	4.38	5,832,465	Main
	Part-B: Re-excavation of Billabarir khal	1.16	1,385,349	Main
	Part-C: Re-excavation of Bhangarpool khal	2.85	4,211,302	Main
	Part-D: Re-excavation of Cementer khal	2.85	4,166,396	Main
	Part-E: Construction of Reference Lined Section	0.00	277,134	Main
SP46272, Karapur Subproject, DR, Union : Kasipur, HO Date: 30/04/2018				
	Part-A: Construction of WMCA and others	12m X 6m 0.00	1,440,181	Main
	Part-I: Re-excavation of Dhoper khal	0.50	270,389	Main
	Part-J: Construction of Reference Lined Section	0.00	334,045	Main
	Part-A: Re-excavation of Paipasa khal	4.02	4,050,045	Main
	Part-B: Re-excavation of Doanir khal	1.58	2,155,723	Main
	Part-C: Re-excavation of Khabir Bari khal	1.33	710,185	Main
	Part-D: Re-excavation of Popular khal	1.70	1,564,888	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Uzirpur PSSWRSP SP46221, Uzirpur Subproject, DR, Union : Skirpur, Wazirpur, HO Date: 24/06/2018	Part-E: Re-excavation of Miaker khal	1.05	458,748	Main
	Part-F: Re-excavation of Mirer khal	1.75	1,498,666	Main
	Part-G: Re-excavation of Chowkider khal	1.03	933,999	Main
	Part-H: Re-excavation of Majir khal	0.45	275,295	Main
SP46243, Sholok-Jugihati Subproject, DR, Union : Sholok, HO Date: 10/05/2018	Part-A:WMCA office & others	12mX6m 0.00	1,376,057	Main
	Part-A:Re-excavation of Gupter khal	2.40	2,218,440	Main
	Part-B: Re-excavation of Gupter Br. khal	1.60	1,793,455	Main
	Part-C: Re-excavation of Karer khal	2.90	1,337,245	Main
	Part-D: Re-excavation of Thander bibi khal	2.70	1,221,167	Main
	Part-E: Re-excavation of Horen Daktar bari khal	2.60	2,389,942	Main
	Part-F: Re-excavation of Horen Daktar bari Br. khal	0.70	244,032	Main
	Part-G: Construction of Reference Lined Section	0.00	303,482	Main
Bhola (Total SPs : 16 Nos.)	Part-A: Construction of Pucca Irrigation Drain 1 & 2	0.00	0	Main
	Part-H: Construction of Reference Lined Section	0.00	548,354	Main
	Part-B: Construction of WMCA office & others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Daksin Sholok khal	1.10	991,255	Main
	Part-B: Re-excavation of Jugihati khal	3.76	3,119,061	Main
	Part-C: Re-excavation of Mirar khal	3.12	2,349,630	Main
	Part-D: Re-excavation of Paschim Sholok khal	1.50	758,769	Main
	Part-E: Re-excavation of Sener khal	1.80	2,735,803	Main
	Part-F: Re-excavation of Sholok Batajore khal	2.60	438,522	Main
	Part-G: Re-excavation of Uttar Sholok khal	2.50	1,966,386	Main
Borhanuddin SSWRDSP-2 SP23076, Batamara Subproject, DR&IRR, Union : Pakkhia, HO Date: 16/05/2007	Kachia Khal Re-excavation	0.50	46,278	Main
	Nawab Mir Khal Re-excavation	7.18	1,440,395	Main
	Kata Khal Re-excavation	2.78	1,330,260	Main
	Sharif Babur Khal Re-excavation	1.78	602,219	Main
	Darogar Khal-1 Re-excavation	1.07	609,907	Main
	Darogar Khal-2 Re-excavation	1.07	598,630	Main
	Muhurir Khal Re-excavation	0.97	447,384	Main
	Shabuz Re-excavation	1.19	159,523	Main
SP23084, Tobgi Subproject, DR&IRR, Union : Tobgi, HO Date: 30/05/2007	Muchir Khal Re-excavation	7.68	2,896,155	Main
	Moniram Khal Re-excavation	4.81	1,512,952	Main
	Buri Khal Re-excavation	2.58	588,480	Main
	Chawdhury Khal Re-excavation	2.36	395,568	Main
	Moniram Khal Br-1 Re-excavation	1.00	490,326	Main
	Moniram Khal Br-2 Re-excavation	1.13	336,130	Main
	Sabuz Khal Re-excavation	0.80	202,218	Main
	Dochila Khal Re-excavation	0.94	133,483	Main
SP23106, Pakshia Subproject, IRR, Union : Pakkhia, HO Date: 16/05/2007	Modhumita Khal Re-excavation	3.10	455,201	Main
	Modhumita Br. Khal Re-excavation	0.65	135,789	Main
	Kata Khal Re-excavation	1.36	338,186	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Kata Khal Br.-1 Re-excavation	0.75	230,932	Main
	Kata Khal Br.-2 Re-excavation	1.90	470,742	Main
	Ranigonj Khal Re-excavation	2.42	135,355	Main
	Muchir Khal Re-excavation	3.59	909,655	Main
Charfassion SSWRDSP-1 SP15264, Aminabad DR Subproject, DR, Union : Aminabad, HO Date: 09/12/2001				
	Manik khali khal re-excavation(ch.00-2800m)	2.80	6,257,797	SSSWRDP
	Gohin khali khal re-excavation(ch.00-2300m)	2.30	4,116,871	SSSWRDP
	Referenced line section(6nos)	0.00	167,962	SSSWRDP
	Bamboo bridge(4nos)	0.05	168,692	SSSWRDP
	Manikkhali Khal Re-excavation	2.35	239,266	Main
	Kachukhali Khal Re-excavation	5.55	823,005	Main
	Shiba-Chatlakhali Khal Re-excavation	3.35	455,402	Main
	O&M Shed		0	Main
SP15282, Sarujkhali Khal DR Subproject, DR, Union : Osmanganj, HO Date: 09/12/2001				
	Surujkhali Khal Re-excavation	2.60	508,651	Main
SP15283, South Char Aicha DR & IRR Subproject, DR&IRR, Union : Char Manika, HO				
	Dokkhin char aicha khal re-excavation(ch.00-3510m)	3.51	4,577,987	SSSWRDP
	Referenced line section(4nos)	0.00	141,002	SSSWRDP
	Bamboo bridge(3 nos)	0.00	161,663	SSSWRDP
	Khal Re-excavation	3.90	531,881	Main
SP15317, Nilkamal DR & IRR Subproject, DR&IRR, Union : Nilkamal, HO Date: 10/06/2002				
	Morangani Khal Re-excavation	5.52	1,612,356	Main
	Talukder Khal Re-excavation	2.40	223,097	Main
	Nilkamal Khal Re-excavation	4.20	689,356	Main
	Gungakhali Khal Re-excavation	3.00	176,165	Main
PSSWRSP SP43067, Purba Char Madras Subproject, DR, Union : Char Madraz, HO Date: 17/04/2017				
	Part-A: Re-excavation of Hazir khal	5.50	3,541,302	Main
	Part-F: Reference lined sections (13 nos.)	0.00	418,885	Main
	Part-A: WMCA office & Others	12mX6m 0.00	1,374,429	Main
	Part-B: Re-excavation of Goalkhalir khal	5.50	3,694,648	Main
	Part-C: Re-excavation of Mollabari khal	1.70	1,368,384	Main
	Part-D: Re-excavation of Taktir khal	1.60	1,483,822	Main
	Part-E: Re-excavation of Hafizuddinir khal	2.20	3,284,511	Main
SP43068, Paschim Char Madras Subproject, DR, Union : Char Madraz, HO Date:				
	Part-A: Re-excavation of Taktakhalir khal	6.50	5,118,826	Main
	Part-F:Reference lined sections (16 nos.)	0.00	474,183	Main
	Part-A: WMCA office & Others	12mX6m 0.00	1,374,252	Main
	Part-B: Re-excavation of Naya khal	2.20	1,593,694	Main
	Part-C: Re-excavation of Karier khal	5.80	3,518,628	Main
	Part-D: Re-excavation of Noalia khal	3.80	3,494,463	Main
	Part-E: Re-excavation of Mohallar khal	3.70	4,194,843	Main
Lalmohon SSWRDSP-2 SP22014, Farazganj Subproject, FMD, Union : Farazganj, HO Date: 08/09/2009				
	Lata Khal Re-excavation	0.50	108,634	Main
	Re-excavation of Khal D/S of Sluice at Ch.0+045 km	0.21	102,088	Main
	Katakhali Khal Regulator at Ch.2+400 km	4-V(1.5mX1.8m) 0.00	7,482,196	Main
	Pipe Sluice at Ch.0+450 km	1-V(900mm Dia) 0.00	748,500	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Lata Khal Pipe Sluice at Ch.1+700 km	1-V(900mm Dia) 0.00	824,661	Main
	Pipe Sluice at Ch.3+600 km	1-V(900mm Dia) 0.00	1,141,055	Main
	O&M Shed	12.00mX6.00m 0.00	407,824	Main
	Satani Khal Re-excavation	1.83	553,990	Main
	Katakhali Khal Re-excavation	1.59	392,340	Main
SP22030, Char Sakhina Subproject, FMD, Union : Kalma, HO Date: 21/01/2019				
	Embankment Re-sectioning	1.20	867,925	Main
	Construction of Closer	0.04	649,191	Main
	Re-sectioning of 3 vent Nazirpur Regulator Approac	0.04	95,349	Main
	Re-excavation of Diversion Khal NazirpurRegulator	0.12	344,657	Main
	Nazirpur Regulator at Ch.1+200 km	3-V(1.50mX1.80m) 0.00	5,592,333	Main
	Char Sakhina Regulator at Ch.0+060 km	2-V(1.50mX1.80m) 0.00	4,824,667	Main
	Char Sakhina Khal Re-excavation	4.19	318,338	Main
	Kachhapia Khal Re-excavation	2.25	111,588	Main
	Rairabad Khal Re-excavation	2.35	339,887	Main
	Gudir Khal Re-excavation	1.07	168,540	Main
	O&M Shed	12.00mX6.00m 0.00	308,170	Main
SP22035, Lengutia Subproject, FMD, Union : Charbhuta, HO Date: 13/06/2007				
	Embankment Re-sectioning	5.75	3,454,855	Main
	O&M Shed	12.00mX6.00m 0.00	308,169	Main
	Lengutia Khal Regulator at Ch.0+582 km	2-V(1.50mX1.50m) 0.00	3,458,177	Main
	Katakhali Khal Regulator at Ch.3+222 km	2-V(1.50mX1.50m) 0.00	3,458,504	Main
	Muguria Khal Regulator at Ch.4+588 km	2-V(1.50mX1.50m) 0.00	3,452,819	Main
	Katakhali Khal Re-excavation	3.45	244,776	Main
	Muguria Khal Re-excavation	4.55	969,847	Main
	Lengatia Khal Re-excavation	2.73	415,869	Main
	Purbo Char Regulator at Ch.2+130 km	1-V(1.50mX1.50m) 0.00	2,595,803	Main
Sadar SSWRDSP-1				
SP13088, South Charpata Khal DR Subproject, DR&WC, Union : Ilisha, HO Date:				
	Kumari khal re-excavation(ch.00-4200m)	4.20	4,838,528	SSSWRDP
	Junglia khal re-excavation(ch.00-4200m)	4.20	4,592,295	SSSWRDP
	Referenced line section(9nos)	0.00	212,689	SSSWRDP
	Bamboo bridge(5nos)	0.05	175,721	SSSWRDP
	Charpata Khal Re-excavation	2.84	939,375	Main
SP15324, Rajapur-Bangerchar FCD Subproject, FCD, Union : Rajapur, HO Date:				
	Embankment Re-sectioning	14.81	5,840,025	Main
	Closure on Majidpur Khal	0.03	63,665	Main
	Closure on Sitampur Khal	0.15	2,405,989	Main
	Majidpur Khal Regulator at Ch.0+570m	1-V(1.5mx1.5m)	1,846,274	Main
	Sitaramer Khal Regulator at Ch.4+070m	2-V(1.5mx1.5m)	2,448,630	Main
	Katakhali Khal Regulator at Ch.9+220m	1-V(1.5mx1.5m)	1,989,333	Main
	Pipe Sluice at Ch.14+120m	1-V(900mm Dia)	677,621	Main
	Pipe Sluice at Ch.6+260m	1-V(900mm Dia)	605,717	Main
	Pipe Sluice at Ch.12+667m	1-V(900mm Dia)	635,527	Main
	Pipe Sluice at Ch.9+702m & O&M Shed	1-V(900mm Dia)	933,817	Main
PSSWRSP				
SP43066, Bhelumia Subproject, DR, Union : Velumia, HO Date: 17/11/2016				
	Part-G: Re-excavation of Sharif Khal bazarer khal	0.70	387,588	Main
	Part-H: Reference lined sections (19 nos.)	0.00	618,108	Main
	Part-A: Re-excavation of Abdullar khal	4.10	2,559,360	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Re-excavation of Baranir khal	1.20	790,824	Main
	Part-C: Re-excavation of Doger khal	1.90	2,998,970	Main
	Part-D: Re-excavation of Haloter khal	2.00	3,121,047	Main
	Part-E: Re-excavation of Koler khal	4.90	1,925,335	Main
	Part-F: Re-excavation of Mollar khal	2.10	578,848	Main
SP43069, Char Samaia Subproject, DR, Union : Char Samaia, HO Date: 07/09/2017				
	Part-D: Reference lined sections	0.00	314,010	Main
	Part-A: Re-excavation of Sher-e-bangla Khal	1.90	2,375,827	Main
	Part-B: Re-excavation of Ponditer khal	3.10	1,005,144	Main
	Part-C: Re-excavation of Ujier khal	2.80	2,985,256	Main
Jhalokathi (Total SPs : 34 Nos.)				
Kathalia				
PSSWRSP				
SP44083, Amua Patikhalghata Subproject, DR, Union : Amua, HO Date: 14/09/2017				
	Part-A: Re-excavation of Mollakhali khal	4.30	3,158,719	Main
	Part-I: Re-excavation of Talukdar Khal	1.24	709,933	Main
	Part-J: Re-excavation of Bairagir Khal	0.95	601,160	Main
	Part-K: Construction of Rreference Lined section (18 nos.)	0.00	622,689	Main
	Part-A: WMCA Office	12mX6m 0.00	1,374,427	Main
	Part-B: Re-excavation of Branch khal-1	1.25	930,584	Main
	Part-C: Re-excavation of Branch khal-2	0.70	475,927	Main
	Part-D: Re-excavation of Napiter Jore Khal	2.10	2,055,486	Main
	Part-E: Re-excavation of Masterbari Khal	1.00	831,276	Main
	Part-F: Re-excavation of Amtola Khal	1.78	851,859	Main
	Part-G: Re-excavation of Ghatir Khal	1.70	957,208	Main
	Part-H: Re-excavation of Chairmanbari Khal	0.90	233,590	Main
SP44085, Aorabunia Subproject, DR, Union : Aorabunia, HO Date: 22/04/2018				
	Part-A: Re-excavation of Borobarir Khal	2.05	1,738,167	Main
	Part-A: WMCA Office & Others	12mx6m 0.00	1,374,243	Main
	Part-H: Re-excavation of Koiborter Khal	1.00	879,582	Main
	Part-I: Re-excavation of Boshir Khal	2.38	1,724,820	Main
	Part-B: Re-excavation of Bamoner Khal	1.50	1,372,870	Main
	Part-C: Re-excavation of Doctor Khal	1.05	940,883	Main
	Part-D: Re-excavation of Khacharbari Khal	1.80	1,481,296	Main
	Part-E: Re-excavation of Kazir Khal	0.90	840,684	Main
	Part-F: Re-excavation of Choddo Boalier Khal	1.70	1,157,842	Main
	Part-J: Re-excavation of Boshir Khal (Branch)	1.18	855,856	Main
	Part-G: Re-excavation of Joruar Khal	1.20	1,134,703	Main
	Part-K: Construction of Reference Lined section (15 nos.)	0.00	608,019	Main
Nalchiti				
SSWRDSP-1				
SP14174, Bhairabpasa FCD Subproject, FCD, Union : Magor, HO Date: 19/06/2002				
	Embankment Re-sectioning	12.37	2,720,436	Main
	Somadder Bari Khal Re-excavation	3.72	1,064,382	Main
	Bhairabpasha Khal Re-excavation	3.75	1,108,049	Main
	Ghatakhali Khal Re-excavation	2.85	784,059	Main
	Nalir Khal Re-excavation	3.30	568,208	Main
	Somadder Bari Regulator	2-V(1.2mX1.5m)	2,660,613	Main
	Bhairabpasha Regulator	2-V(1.5mX1.5m)	2,917,175	Main
	Nalir Khal Regulator	2-V(1.2mX1.2m)	3,006,331	Main
	Ghatakhali Khal Regulator	2-V(1.2mX1.5m)	2,091,399	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP14214, Magor FCD Subproject, FCD, Union : Magar, HO Date: 15/05/2002				
	Embankment Re-sectioning	15.53	4,886,357	Main
	North Magor Khal Re-excavation	1.19	178,957	Main
	South Magor Khal Re-excavation	2.70	617,075	Main
	Lakmipur Khal Re-excavation	2.30	526,945	Main
	South Magor Khal Regulator at Ch.0+095m	2-V(1.5mX1.5m)	1,433,176	Main
	North Magor Khal Regulator at Ch.0+290m	1-V(1.5mX1.5m)	1,491,526	Main
	Lakmipur Khal Regulator at Ch.0+040m	2-V(1.5mX1.5m)	2,461,675	Main
	Pipe Sluice at Ch.17+330m	1-V(900mm Dia.)	671,823	Main
	Pipe Sluice at Ch.18+530m	1-V(900mm Dia.)	654,540	Main
SP15218, Dapdapia FCD Subproject, FCD, Union : Dapdapia, HO Date: 25/06/2002				
	Embankment Re-sectioning	5.04	1,825,317	Main
	Part-A: Re-excavation of Borohota Branch khal	1.10	982,240	PSSWRSP
	Part-B: Re-excavation of Borohota khal	0.82	260,781	PSSWRSP
	Part-D: Re-excavation of Kobiraj bari khal	0.75	410,082	PSSWRSP
	Part-C: Re-excavation of Bhaharar khal	1.30	1,336,798	PSSWRSP
	Gohalkathi-Kajem Ali khan barir khal re-excavation(ch.00-4	4.00	3,966,938	SSSWRDP
	Nager barir khal re-excavation(ch.00-1500m)	1.50	1,142,243	SSSWRDP
	Talukder barir khal re-excavation(ch.00-1500m)	1.50	850,505	SSSWRDP
	Biswas barir khal re-excavation(ch.00-1000m)	1.00	978,280	SSSWRDP
	Referenced line section (9nos)	0.00	206,536	SSSWRDP
	Bamboo bridge (9nos)	0.00	221,408	SSSWRDP
	Embankment re-sectioning(ch.00-1385m)	1.39	1,867,751	SSSWRDP
	Bager Ponchayet Khal-1 Re-excavation	1.84	271,294	Main
	Bager Ponchayet Khal-2 Re-excavation	2.12	397,806	Main
	Jolakhali Khal Re-excavation	1.80	417,542	Main
	Wills King Son Ponchayet Khal Re-excavation	4.95	1,055,632	Main
	Uttar Jurkathi Br. Khal Re-excavation	0.65	38,826	Main
	Khondoker Bari Khal Re-excavation	0.90	84,850	Main
	Uttar Jurkathi Khal Re-excavation	2.17	144,931	Main
	Majhi Bari Br. Khal Re-excavation	0.60	40,387	Main
	Borrow Khal Regulator at Ch.3+928m	1-V(1.2mX1.2m)	2,038,486	Main
	Tarar Khal Regulator at Ch.2+583m	1-V(1.2mX1.2m)	1,194,062	Main
SSWRDSP-2				
SP25310, Subidpur-Nalbunia Subprject, DR&IRR, Union : Shubidpur, HO Date: 29/04/2010				
	Rehabilitation of BWDB's Regulator	0.00	130,516	Main
	O&M Shed	Szie: 9mX5m 0.00	314,646	Main
	Re-excavation of Nalbunia Khal	2.26	406,092	Main
	Re-excavation of Matura Khal	1.39	703,577	Main
	Re-excavation of Khanbari Khal	2.02	363,128	Main
	Re-excavation of Sikder Bari Khal	0.80	178,909	Main
	Re-excavation of Hizal Talir Khal	0.57	186,388	Main
	Re-excavation of Biswas Barir Khal	2.03	528,898	Main
	Re-sectioning of Regulator Approach	0.03	61,669	Main
	Part-A: Re-excavation of Mollakhali Khal	2.18	1,321,268	PSSWRSP
	Part-B: Re-excavation of Uzir Barir Khal	1.40	830,353	PSSWRSP
SP25319, Kusangal-Manapasa Subproject, DR&IRR, Union : Kushangle, HO Date:				
	Re-excavation of Manpasa-Bhattacharjee Khal	1.95	535,240	Main
	Re-excavation of Manpasa Khal	2.55	274,677	Main
	Re-excavation of Kusangal Khal	1.35	288,504	Main
	Re-excavation of Seota Khal	1.20	286,179	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP25320, Rajabaria Subproject, DR&IRR, Union : Mollarhat, HO Date: 25/11/2009	Re-excavation of Chharar Khal	0.50	152,474	Main
	Re-excavation of Poara Khal	1.65	934,463	Main
	Re-excavation of Lahortala Khal	2.43	1,127,044	Main
	Re-excavation of Dhopabari Khal	1.50	251,868	Main
	Re-excavation of Gainner Khal	1.80	719,181	PSSWRSP
	Re-excavation of Zaider katakhali Khal	1.53	754,603	PSSWRSP
	Re-excavation of Jhorjoriatola Khal	1.53	508,657	PSSWRSP
	Re-excavation of Jhorjoriatola Branch-01 Khal	0.45	63,219	PSSWRSP
	Re-excavation of Jhorjoriatola Branch-02Khal	0.60	116,367	PSSWRSP
	Re-excavation of Sadogar Barir Khal	1.10	389,418	PSSWRSP
	Katakhali khal re-excavation(ch.00-4500m)	4.50	5,659,254	SSSWRDP
	Referenced Line section(5 nos)	0.00	138,710	SSSWRDP
	Bamboo bridge(3 nos)	0.00	147,605	SSSWRDP
SP25331, Kathipara-Tetulbari Subproject, DR, Union : Ranapasha, HO Date: 05/07/2010	Re-excavation of Kathipara Khal	6.76	1,935,612	Main
	Re-excavation of Chhaliabunia Khal	2.87	1,462,209	Main
	Re-excavation of Dakshin Kathipara Khal	1.07	410,171	Main
	Re-excavation of Kathipara Branch-1 Khal	0.20	117,079	Main
	Re-excavation of Kathipara Branch-2 Khal	0.40	212,294	Main
	Part-A: Construction of WMCA Office	12mX6m 0.00	875,274	PSSWRSP
	Re-excavation of Harigada Khal	0.54	87,565	PSSWRSP
	Re-excavation of Mazibarir Branch Khal	0.67	88,963	PSSWRSP
	Part-B: Rain Water Harvesting of WMCA Office	12mx6m 0.00	46,930	PSSWRSP
	Part-C: Electrification work of WMCA Office	12mX6m 0.00	70,892	PSSWRSP
	Part-D: Supplying of furniture of WMCA Office	12mX6m 0.00	50,500	PSSWRSP
	Part-E: Tender preparation & published	12mx6m 0.00	25,000	PSSWRSP
	Re-excavation of Uttar Katipara Khal	1.50	314,015	PSSWRSP
	Re-excavation of Mazibarir Khal	1.10	389,603	PSSWRSP
	Re-excavation of Fokir Khalir Khal	1.62	515,599	PSSWRSP
	Re-excavation of Jola Khalir Khal	1.10	268,773	PSSWRSP
	AkonBarir khal re-excavation(ch.00-2000m)	2.00	1,909,604	SSSWRDP
	Gazi Barir khal re-excavation(ch.00-1100m)	1.10	1,142,744	SSSWRDP
	Molla Barir khal re-excavation(ch.00-1230m)	1.23	1,533,056	SSSWRDP
	Ukil Barir khal re-excavation(ch.00-1100m)	1.10	1,042,562	SSSWRDP
	Referenced line section(9nos)	0.00	195,671	SSSWRDP
	Bamboo Bridge(9nos)	0.09	298,725	SSSWRDP
PSSWRSP				
SP43070, Panchagram Subproject, DR, Union : Kulkathi, HO Date: 14/09/2017	Part-A: Re-excavation of Paota-Bigpasha khal	3.45	4,285,900	Main
	Part-D: Re-excavation of Bilasher khal	1.81	1,512,290	Main
	Part-C: Re-excavation of Kabirbarir khal	1.71	1,977,862	Main
	Part-B: Re-excavation of Rajabarir khal	2.61	2,119,041	Main
	Part-E: Re-excavation of Noborayer khal	1.61	1,572,286	Main
	Part-F: Re-excavation of Kafurkathi khal	2.15	1,877,528	Main
	Part-G: Lined reference sections (10 nos.)	0.00	370,736	Main
	Part-A: WMCA office & others	12mX6m 0.00	1,374,196	Main
SP44076, Paschim Gopalpur Subproject, DR, Union : Shubidpur, HO Date: 14/09/2017	Part-D: Re-excavation of Akonbarir Khal	0.70	562,184	Main
	Part-J Reference Section	0.00	524,119	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	1,317,789	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Re-excavation of Choukiderbari Khal	0.60	444,172	Main
	Part- I: Re-excavation of Ichhapasa Khal	2.80	2,185,646	Main
	Part-F:- Re-excavation of Mallikbari Khal	1.30	963,826	Main
	Part-H:- Re-excavation of Munshibarir Khal	1.35	1,325,608	Main
	Part-C: Re-excavation of Panchana Khal	1.72	978,848	Main
	Part-A:- Re-excavation of Salimerbarir Khal	1.62	963,190	Main
	Part-G:- Re-excavation of Uzirbarir Khal	0.55	484,078	Main
	Part-E:-Re-excavation of Sarkarbarir Branch Khal	3.76	2,801,114	Main
SP45148, Bot-tola Subproject, DR&WC, Union : Ranapasha, HO Date: 04/10/2017				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,229,376	Main
	Part-I: Construction of Reference Lined Section	0.00	328,402	Main
	Part-A: Re-excavation of Bottola Khal	1.50	1,606,374	Main
	Part-B: Re-excavation of Katakhal Khal	2.25	1,402,730	Main
	Part-C: Re-excavation of Member Barir Khal	0.25	293,049	Main
	Part-D: Re-excavation of Amittir Khal	0.95	1,013,279	Main
	Part-E: Re-excavation of Jamaddar Barir Khal	1.45	1,251,828	Main
	Part-F: Re-excavation of Nomo Barir Khal	1.10	1,485,893	Main
	Part-G: Re-excavation of Tema Khali Khal	0.80	821,401	Main
	Part-H: Re-excavation of Haolader Barir Khal	3.67	3,891,850	Main
Rajapur SSWRDSP-1				
SP15217, Satura DR Subproject, DR, Union : Satura, HO Date: 04/04/2002				
	Gainbari Khal Re-excavation	0.60	95,305	Main
	Kacharibari Khal Re-excavation	2.27	484,800	Main
	Bager Khal Re-excavation	3.00	415,832	Main
	Bairagir Khal Re-excavation	1.65	342,769	Main
	Kadamtala Khal Re-excavation	2.42	342,671	Main
	Kadamtala Br. Khal Re-excavation	1.20	136,097	Main
	Khandaker Bari Khal Re-excavation	3.15	632,500	Main
	Taltala Khal Re-excavation	0.90	151,788	Main
SP15288, Rajapur DR Subproject, DR, Union : Rajapur,Satura, HO Date: 20/06/2002				
	Kaibarta Khal Re-excavation	5.70	2,640,985	Main
	Gazir Khal Re-excavation	1.78	320,618	Main
	Adam Ali Khal Re-excavation	0.85	135,040	Main
	Bazlu Memberbari Khal Re-excavation	2.30	515,823	Main
	Phulhar Ghoshbari Khal Re-excavation	5.05	1,991,555	Main
	Mallikbari Khal Re-excavation	2.25	320,861	Main
SSWRDSP-2				
SP22025, Galua Subproject, DR, Union : Galua, HO Date: 29/06/2006				
	Khalifabari Khal Re-excavation	2.47	404,713	Main
	Chauhandi,Chakarbari & Munshibari Khal Re-ex.	2.50	292,373	Main
	Huzurbari Khal Re-excavation	1.02	246,585	Main
	Danga Khal Re-excavation	0.62	58,710	Main
	Galua Khal Re-excavation	1.03	58,710	Main
	Sateroghar and Basabari Khal Re-excavation	2.10	235,181	Main
	Borojor and Chotojor Khal Re-excavation	1.80	226,859	Main
	Katakhal Khal Re-excavation	1.33	278,527	Main
	Tita Molla Khal Re-excavation	1.71	342,355	Main
	Kumarbari Khal Re-excavation	1.63	114,557	Main
	Nagarbari Khal Re-excavation	1.46	293,419	Main
	Jalabari and Banerwar Khal Re-excavation	3.30	295,508	Main
	Beparibari and Jor Khal Re-excavation	2.44	197,969	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: Re-excavation of Faraji Bari Khal	0.81	368,278	PSSWRSP
	Part-B: Re-excavation of Sheikh Jahangir Khal	0.90	445,279	PSSWRSP
	Part-C: Re-excavation of jhor Khal	0.51	18,815,331	PSSWRSP
	Part-D: Re-excavation of Burir Khal	1.21	892,023	PSSWRSP
	Part-E: Re-excavation of Taluckder Khal Reference lined S	0.81	328,087	PSSWRSP
PSSWRSP				
SP44080, Chollish Kawnia Subproject, DR, Union : Baruia, HO Date: 30/04/2016				
	Part-F: Re-excavation of Dharer khal	1.05	623,362	Main
	Part-J: Construction of Reference Section	0.00	374,857	Main
	Part-A: WMCA Office & others	12mX6m 0.00	1,317,573	Main
	Part-C: Re-excavation of Datter Khal	1.30	848,071	Main
	Part-D: Re-excavation of Char Uttampur Khal	1.00	938,107	Main
	Part-G: Re-excavation of Dopakhali khal	0.70	812,510	Main
	Part-H: Re-excavation of kapurtala khal	0.40	459,088	Main
	Part-A: Re-excavation of Katakali khal	1.98	1,758,801	Main
	Part-I: Re-excavation of Malirkhali khal	1.83	1,973,490	Main
	Part-B: Re-excavation of Morichbunia khal	1.41	1,155,050	Main
	Part-E: Re-excavation of Napitkhali khal	1.95	1,664,090	Main
SP46281, Kodomtola Subproject, DR, Union : Satoria, HO Date: 30/05/2018				
	Part-A: WMCA office & others	12mX6m 0.00	1,486,824	Main
	Part-A: Re-excavation of Amtola Khal	1.90	975,316	Main
	Part-B: Re-excavation of Chanderbari Khal	1.90	1,007,770	Main
	Part-C: Re-excavation of Charambari Khal	1.64	2,150,300	Main
	Part-D: Re-excavation of Memberbari Khal	1.60	1,129,315	Main
	Part-E: Construction of reference Lined Section	0.00	224,700	Main
Sadar				
SSWRDSP-1				
SP11009, Kafurkathi Khal DR Subproject, DR, Union : Nabogram, HO Date: 18/06/2002				
	Re-excavation of Dogal Chira Khal	2.11	1,176,101	PSSWRSP
	Re-excavation of Shimule Shwar Khal	2.20	749,462	PSSWRSP
	Re-excavation of Shimulia Khal	1.29	1,457,171	PSSWRSP
	Re-excavation of Hawlar Khal	1.38	307,329	PSSWRSP
	Poschim Kafurkathi rambala barir khal re-excavation(ch.00-	1.78	3,818,679	SSSWDRDP
	Kafurkathi Sunil beparir khal re-excavation(ch.00-1650m)	1.65	2,976,604	SSSWDRDP
	Sotodaskathi Sorojit Howladar barir khal re-excavation(ch.0	1.52	2,409,980	SSSWDRDP
	Poschim Kafurkathi majhi barir khal re-excavation(ch.00-35	0.35	367,122	SSSWDRDP
	Referenced line section(7nos)	0.00	168,413	SSSWDRDP
	Bamboo bridge(7nos)	0.00	274,124	SSSWDRDP
	Kafurkathi Khal Re-excavation	2.47	132,475	Main
	Main Khal Re-excavation	2.07	372,124	Main
	Branch Khal Re-excavation	1.80	222,273	Main
SP13059, Binoykathi DR Subproject, DR, Union : Binoykathi, HO Date: 29/03/2002				
	Re-excavation of Sikder Barir Khal and Branch Khal	3.83	1,781,135	PSSWRSP
	Re-excavation of Manphasa kader Member babir Khal	1.05	1,238,495	PSSWRSP
	Re-excavation of Sharif Barir Khal	1.23	641,789	PSSWRSP
	Khagutia khal re-excavation(ch.00-2460m)	2.46	1,810,466	SSSWDRDP
	Dokkhin Manpasa khondoker barir khal re-excavation(ch.00-	1.85	2,088,114	SSSWDRDP
	Khagutia Majhibarir khal re-excavation(ch.00-650m)	0.65	878,598	SSSWDRDP
	Bishnudia Hawladar barir khal re-excavation(ch.00-1000m)	1.00	759,310	SSSWDRDP
	Referenced line section(8nos)	0.00	222,234	SSSWDRDP
	Bamboo bridge(7nos)	0.00	295,210	SSSWDRDP
	Re-excavation of Khal-1	4.32	786,191	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Khal-2 & Br. Khal	4.85	429,276	Main
	Thailkhola-Ganginer Khal Re-excavation	2.69	475,142	Main
	Garanga-Ganginer Khal Re-excavation	2.12	327,685	Main
	Lalu-Misturi Khal Re-excavation	0.72	97,758	Main
	Murashata Khal Re-excavation	1.52	335,627	Main
	Gafur Khan Khal Re-excavation	0.90	266,064	Main
	Tarashighat Khal Re-excavation	0.70	170,857	Main
	Diarjor Khal Re-excavation	1.42	312,140	Main
	Fakirbari Khal Re-excavation	0.98	202,882	Main
	Baharampur Khal Re-excavation	1.50	279,160	Main
SP14206, Basanda DR Subproject, DR, Union : Basanda, HO Date: 29/03/2002				
	Re-excavation of Goal Bari khal	1.35	604,062	PSSWRSP
	Re-excavation of Taltalka khal	1.35	476,925	PSSWRSP
	Re-excavation of Sambol khal	2.55	1,452,469	PSSWRSP
	Re-excavation of Verne khal	0.63	301,973	PSSWRSP
	Talukderbari Khal Re-excavation	1.14	197,208	Main
	Bagmari Khal Re-excavation	1.36	331,901	Main
	Rajamia Bari Khal Re-excavation	2.56	298,351	Main
	Dhoper Khal Re-excavation	1.40	287,521	Main
	Satraj Khal-1 Re-excavation	1.07	129,292	Main
	Satraj Khal-2 Re-excavation	1.01	155,576	Main
	Noamia Khal Re-excavation	1.14	144,696	Main
	Sundar Khal Re-excavation	3.41	376,095	Main
	Nor Bari Khal Re-excavation	1.65	194,067	Main
	Boksher Khal Re-excavation	1.35	103,301	Main
	Darki Bobardanga Khal Re-excavation	1.20	87,212	Main
	Dumjuri Khal Re-excavation	1.20	129,193	Main
	Omus Khalifa Bari Khal Re-excavation	0.37	99,967	Main
	Kalikhola Khal Re-excavation	0.95	104,123	Main
	Agolpasha Khal Re-excavation	1.72	154,119	Main
	Agorbari Khal Re-excavation	1.65	227,089	Main
SP15233, Ponabalia DR Subproject, DR, Union : Ponabalia, HO Date: 29/03/2002				
	Part-A: Re-excavation of Bharani khal	1.20	686,613	PSSWRSP
	Part-B: Re-excavation of Bhaolitar khal	1.41	651,293	PSSWRSP
	Part-C: Re-excavation of Bashabari khal	1.56	878,019	PSSWRSP
	Part-D: Re-excavation of Hatkhalar khal	0.57	336,749	PSSWRSP
	Part-E: Re-excavation of Jaggswarer khal	0.94	445,658	PSSWRSP
	Part-F: Re-excavation of Deury khal	1.35	345,752	PSSWRSP
	Chilarist Khal Re-excavation	1.01	209,705	Main
	Hakimuddin Khal Re-excavation	0.75	195,364	Main
	Dakterbari Khal Re-excavation	1.35	192,036	Main
	Darogabari Khal Re-excavation	0.60	158,889	Main
	Nayabari Khal Re-excavation	0.90	287,381	Main
	Kulaitalar Khal Re-excavation	1.65	224,052	Main
	Khalifa Barir Khal Re-excavation	1.15	110,281	Main
	Bolmari Khal Re-excavation	0.60	106,765	Main
	Molla Bari Khal Re-excavation	0.50	115,687	Main
	Lachur Bari Khal Re-excavation	1.55	366,088	Main
	Dalu Fakir Bari Khal Re-excavation	1.51	330,655	Main
	Chilarist Sardere Bari Khal Re-excavation	0.45	89,760	Main
SP15236, Natullabad DR Subproject, DR, Union : Natullabad, HO Date: 15/06/2002				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Shah Bangol khal Re-excavation(ch.00-1500m)	1.50	1,051,271	SSSWRDP
	Latimsar khal Re-excavation(ch.00-1350m)	1.35	1,387,780	SSSWRDP
	Hazi Barir khal Re-excavation(ch.00-1800m)	1.80	833,182	SSSWRDP
	Khalifa Barir khal Re-excavation(ch.00-650m)	0.65	566,108	SSSWRDP
	Sikder Barir khal Re-excavation(ch.00-425m)	0.43	426,180	SSSWRDP
	Referenced line section(9nos)	0.00	213,782	SSSWRDP
	Bamboo bridge(9nos)	0.00	288,182	SSSWRDP
	Khal-1 Re-excavation	2.17	481,615	Main
	Branch of Khal-1 Re-excavation	0.79	86,211	Main
	Khal-2 Re-excavation	1.67	271,497	Main
	Khal-3 Re-excavation	1.91	274,752	Main
SP15258, Gava-Ramchandrapurur DR Subproject, DR, Union : Gabha-Ramchandrapurur,				
	Part-A: Re-excavation of Bermahal Khal	1.20	1,251,819	PSSWRSP
	Part-B: Re-excavation of Bermahal Sharoali Khal	1.66	967,530	PSSWRSP
	Part-C: Re-excavation of Omar Ali Balir Khal	1.73	456,773	PSSWRSP
	Part-D: Re-excavation of Hosenpur Khal	1.42	353,753	PSSWRSP
	Guhader Khal Re-excavation	2.97	732,485	Main
	Panchakaran Khal Re-excavation	2.37	845,029	Main
	Guha Chitra Khal Re-excavation	2.38	661,660	Main
	Bermahal Khal Re-excavation	1.58	377,224	Main
SSWRDSP-2				
SP22002, Nabogram Subproject, DR, Union : Basanda, HO Date: 29/06/2006				
	Jim Gachia Khal-2 Re-excavation	1.35	446,868	Main
	Ghosal Bari Khal Re-excavation	0.63	66,765	Main
	Gola Bari Khal Re-excavation	2.70	402,184	Main
	Napit Bari Khal Re-excavation	2.25	481,111	Main
	Sholakhera Khal-1 Re-excavation	1.40	245,797	Main
	Sholakhera Khal-2 Re-excavation	1.00	280,598	Main
	Salpushena Khal Re-excavation	1.10	222,998	Main
	Shimuleshwar Pal Bari Khal Re-excavation	1.00	276,879	Main
	Nabagram Purveyar Khal Re-excavation	1.90	537,332	Main
	Telikhali Khal Re-excavation	2.35	699,165	Main
	Jim Gachia Khal-1 Re-excavation	1.05	176,989	Main
	Re-excavation of Parmahal Khalifa Bari Khal	5.03	1,601,132	PSSWRSP
	Re-excavation of BawkatiThal Phori Bari Khal	2.00	603,585	PSSWRSP
	Betora khal re-excavation(ch.00-1500m)	1.50	1,500,457	SSSWRDP
	Rampura khal re-excavation(ch.00-3000m)	3.00	1,916,700	SSSWRDP
	Napitkhali khal re-excavation(ch.00-2300m)	2.30	2,341,493	SSSWRDP
	Gudighata khal re-excavation(ch.00-600m)	0.60	464,196	SSSWRDP
	Referenced line section(9nos)	0.00	233,776	SSSWRDP
	Bamboo bridge(9nos)	0.00	439,301	SSSWRDP
PSSWRSP				
SP44077, Saorakathi Subproject, DR, Union : Gabha-Ramchandrapurur, HO Date:				
	Part-A:Re-excavation of Kanchabalia Khal	4.60	4,444,902	Main
	Part-D: Re-excavation of Shirajbarir Khal	1.71	1,095,429	Main
	Part-F: Re-excavation of Madhay Saorakathi Khal	0.60	5,789,693	Main
	Part-E: Re-excavation of Dakshin Saorakathi Khal	0.70	604,337	Main
	Part-B: Re-excavation of Dhopabarir Khal	2.35	2,508,232	Main
	Part-C: Re-excavation of Hamandakati Khal	1.21	1,141,577	Main
	Part-G: Construction of reference Lined sections	0.00	370,407	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	1,375,000	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP44104, Sarengal Subproject, DR, Union : Kewda, HO Date: 29/12/2015				
	Part-A: construction of WMCA office & others	12mX6m 0.00	1,373,372	Main
	Part-I: Re-excavation of Serengal Brance khal-2	0.30	118,525	Main
	Part-J: Re-excavation of Serengal-Pakmahor khal	0.43	281,438	Main
	Part-K: Re-excavation of Pakmahor Branch khal	0.20	183,186	Main
	Part-L: Construction of Reference Lined Section	0.00	226,770	Main
	Part-A: Re-excavation of Salamuddiner Barir Khal	0.75	762,696	Main
	Part-B: Re-excavation of Naohata Khal	10.00	913,975	Main
	Part-C: Re-excavation of Pakmahor Varani khal	1.60	1,453,042	Main
	Part-D: Re-excavation of Kachoria khal	1.70	2,091,408	Main
	Part-E: Re-excavation of Sarengal-Varani khal	1.50	1,847,514	Main
	Part-F: Re-excavation of Khan Saifur Rhaman khal	0.60	565,925	Main
	Part-G: Re-excavation of Talukder Barir khal	0.80	753,803	Main
	Part-H: Re-excavation of Serengal Brance khal-1	0.40	445,386	Main
SP44106, Sachilapur Subproject, DR, Union : Gabkhan danshiri, HO Date: 30/04/2016				
	Part-A: Construction of WMCA Office & othres	12mX6m 0.00	1,373,552	Main
	Part-I: Re-excavation of Majhibarir Khal-2	0.21	161,872	Main
	Part-J: Re-excavation of Varani Khal	1.23	1,234,330	Main
	Part-K: Re-excavation of Varani Branch Khal	0.50	411,277	Main
	Part-L: Construction of Reference Lined Section	0.00	0	Main
	Part-A: Re-excavation of Mollabarir Khal-1	0.85	463,336	Main
	Part-B: Re-excavation of Mollabarir Khal-2	0.90	724,160	Main
	Part-C: Re-excavation of Boaler khal	1.80	1,790,660	Main
	Part-D: Re-excavation of Boaler Branch khal-1	0.30	211,886	Main
	Part-E: Re-excavation of Shariar khal	1.73	2,032,314	Main
	Part-F: Re-excavation of Shariar Branch khal-1	0.39	304,331	Main
	Part-G: Re-excavation of Shariar Branch khal-2	0.30	269,664	Main
	Part-H: Re-excavation of Majhibarir Khal-1	1.00	519,606	Main
SP44117, Deulkathi-Binnapara Subproject, DR, Union : Gabkhan danshiri, HO Date:				
	Part-A: Construction of WMCA Office & others	12mX6m 0.00	1,373,298	Main
	Part-A: Re-excavation of Kitish Bari Khal	4.50	3,083,435	Main
	Part-B: Re-excavation of Daker Bari Khal	1.85	1,453,834	Main
	Part-C: Re-excavation of Berpass Khal	1.25	1,113,930	Main
	Part-D: Re-excavation of Dayal Bari Khal	0.95	621,700	Main
	Part-E: Re-excavation of Fakir Bari Khal	1.10	809,376	Main
	Part-F: Re-excavation of Sikder Bari Branch Khal	0.98	921,054	Main
	Part-G: Re-excavation of Sikder Bari Khal	2.60	2,700,200	Main
	Part-H: Construction of Reference lined section	0.00	298,565	Main
SP44127, Haripasha Pironda Subproject, DR, Union : Natullabad, HO Date: 30/04/2016				
	Part-A: Construction WMCA Office & others	12mX6m 0.00	1,373,977	Main
	Part-A: Re-excavation of Pironda-Talukderbari khal	1.85	1,997,491	Main
	Part-B: Re-excavation of Naiari -Rayergorer Khal	1.25	1,768,124	Main
	Part-C: Re-excavation of Naiari -Charabair Khal	1.43	1,828,556	Main
	Part-D: Re-excavation of Sikderbari Khal	1.04	1,180,363	Main
	Part-E: Re-excavation of Dibakorkhati-Ghosher Khal	1.85	2,098,492	Main
	Part-F: Re-excavation of Dibakorkhati-Arujuddiner Khal	1.43	875,573	Main
	Part-G: Re-excavation of Naiari Sugandhia-kalijira Khal	3.21	2,492,250	Main
	Part-H: Construction of Reference Lined Section	0.00	299,538	Main
SP44138, Ramanathpur Subproject, DR, Union : Kirtipasa, HO Date: 18/09/2017				
	Part-A: WMCA Office @ Others	12mXcm 0.00	0	Main
	Part-I: Re-excavation of Khorda Barahar Khal	0.65	530,538	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-J: Re-excavation of Ramanathpur Khal	0.99	855,184	Main
	Part-K: Construction of Reference Lined Section	0.00	250,873	Main
	Part-A: Re-excavation of Gobindadhabal Khal	1.06	925,177	Main
	Part-B: Re-excavation of Gobindadhabal Branch Khal	1.75	1,528,949	Main
	Part-C: Re-excavation of Gobindadhabal Khal-2	0.65	528,806	Main
	Part-D: Re-excavation of Garkhai Khal	1.51	1,083,660	Main
	Part-E: Re-excavation of Mirakathi-Panjiputpara Khal	2.32	1,172,383	Main
	Part-F: Re-excavation of Matbari Khal-1	1.59	1,131,902	Main
	Part-G: Re-excavation of Matbari Khal-2	1.62	1,593,841	Main
	Part-H: Re-excavation of Mirakhati Khal	1.51	1,001,365	Main
SP46235, Ashiar DR Subproject, DR, Union : Binoykathi, HO Date: 06/12/2017				
	Part-I: Re-excavation of Baharampur khal	0.85	365,767	Main
	Part-J: Construction of Reference Lined Section	0.00	406,237	Main
	Part-A: Re-excavation of Goidal khal	1.31	1,375,634	Main
	Part-B: Re-excavation of Diarjori khal	2.45	2,995,839	Main
	Part-C: Re-excavation of Diarjori Br. khal	0.95	812,683	Main
	Part-D: Re-excavation of Ashiar Basabari khal	2.70	2,875,518	Main
	Part-E: Re-excavation of Murasata khal	1.60	816,380	Main
	Part-F: Re-excavation of Murasata Br-1 khal	1.60	1,314,693	Main
	Part-G: Re-excavation of Murasata Br-2 khal	1.00	886,013	Main
	Part-H: Re-excavation of Murasata Br-3 khal	0.46	376,217	Main
SP46239, Kirtipasha Subproject, DR, Union : Kirtipasha, HO Date: 22/03/2018				
	Part-I: Re-excavation of Sankar Dhabal Hawlader Bari Kha	0.60	0	Main
	Part-J: Re-excavation of Beshain Khal	1.16	0	Main
	Part-K: Re-excavation of Khajura Khal	1.29	0	Main
	Part-L: Re-excavation of Khajura Br.-1 Khal	0.40	0	Main
	Part-M: Re-excavation of Khajura Br.-2 Khal	0.50	0	Main
	Part-N: Re-excavation of Than Sinhapur Khal	0.59	0	Main
	Part-O: Re-excavation of Dumuria bairampur Khal	1.80	0	Main
	Part-P: Construction of Reference Lined Section	0.00	0	Main
	Part-A: Re-excavation of Beukhir Khal	1.00	0	Main
	Part-B: Re-excavation of Beukhir Br.-1 Khal	0.43	0	Main
	Part-C: Re-excavation of Beukhir Br.-2 Khal	0.23	0	Main
	Part-D: Re-excavation of Alamgir Barir Khal	0.60	0	Main
	Part-E: Re-excavation of Sankar Dhabal Khal	1.70	0	Main
	Part-F: Re-excavation of Sankar Dhabal Br.-1 Khal	0.20	0	Main
	Part-G: Re-excavation of Sankar Dhabal Br.-2 Khal	0.85	0	Main
	Part-H: Re-excavation of Sankar Dhabal Br.-3 Khal	0.30	0	Main
SP46280, Daikul Subproject, DR, Union : Ponabalia, HO Date: 30/04/2017				
	Part-A: Re-excavation of Rajapur Khal	2.22	1,783,729	Main
	Part-B: Re-excavation of Nakechira Khal	2.23	1,374,973	Main
	Part-C: Re-excavation of Ghater Khal	2.13	1,735,219	Main
	Part-D: Re-excavation of Mirzapur Khal	1.68	1,070,745	Main
	Part-E: Re-excavation of Kistakhati Khal	2.10	1,456,119	Main
	Part-F: Re-excavation of Azghar Khal	0.70	438,795	Main
	Part-H: Construction of Reference Lined Section	0.00	0	Main
JICA-LGED TA Project				
SP51002, Chamta Drainage Subproject, DR&IRR, Union : Basanda, HO Date: 31/01/2018				
	Re-excavation of Kalabunia Khal	0.80	605,391	Main
	Re-excavation of Dangachira Khal	0.60	555,315	Main
	Re-excavation of Sundartala Khal	1.20	226,154	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Joysi Khal	0.91	398,922	Main
	Re-excavation of Lesprotap Khal	1.22	873,366	Main
	Re-excavation of Khalifa Bari Khal	0.70	415,493	Main
	Construction Reference Lined Section (13 Nos.)	0.00	599,236	Main
	Construction of 18m long RCC Girder Bridge on Darkhi Bha	Span = 18 m 0.00	10,521,871	Main
	Construction of Lined Canal on Beltoch Khal & Kalabunia K	I = 300 m 0.00	9,881,929	Main
	Construction of two storied WMCA Office building	0.00	2,217,607	Main
	Re-excavation of Darkhi Bharani Khal	2.80	1,514,995	Main
	Re-excavation of Sikdar Barir Khal	0.40	356,336	Main
	Re-excavation of Beltoch Khal	1.70	976,176	Main
	Re-excavation of Dhara Khan Khal	2.00	1,034,315	Main

Patuakhali (Total SPs : 23 Nos.)

Bauphal

SSWRDSP-1

SP14192, Char Roy Shaheb FCD Subproject, FCD, Union : Nazirpur, HO Date: 18/06/2002

Embankment Re-sectioning(Sec. A)	11.77	6,756,360	Main
Embankment Re-sectioning(Sec. B)	0.31	227,760	Main
Regulator at Ch.0+640m	1-V(1.5mX1.8m)	1,732,043	Main
Regulator at Ch.2+850m	2-V(1.5mX1.8m)	2,815,767	Main
Regulator at Ch.10+800m	2-V(1.5mX1.8m)	2,841,736	Main
Pipe Sluice at Ch.7+650m	1-V(900mm Dia)	885,338	Main

SP14194, Anarashia FCD Subproject, FCD, Union : Kachipara, HO Date: 02/10/2003

Embankment Re-sectioning	3.43	1,358,422	Main
Betaler Khal-1 Re-excavation	2.70	484,318	Main
Betaler Khal-2 Re-excavation	1.80	176,456	Main
Meser Khan Khal Re-excavation	0.70	44,255	Main
Bauser Suta Khal Re-excavation	0.52	37,449	Main
Anarashia-Gopalia Khal Re-excavation	3.00	210,339	Main
Betaler Khal-1 Regulator at Ch.0+200m	2-V(1.5mX1.5m)	2,638,688	Main
Betaler Khal-2 Pipe Sluice at Ch.3+235m	1-V(900mm Dia)	546,417	Main
Meser Khan Khal Pipe Sluice at Ch.4+125m	1-V(900mm Dia)	508,749	Main
Box Sluice at Ch.5+680m	1-V(1.5mX1.5m)	1,077,000	Main
Box Sluice at Ch.6+530m	1-V(1.5mX1.5m)	859,237	Main
Pipe Sluice at Ch.4+125m	1-V(900mm Dia)	778,500	Main
O&M Shed		270,987	Main

SP15345, Rajapur Patilapara FCD Subproject, FCD, Union : Kalisuri, HO Date: 04/10/2003

Embankment Re-sectioning	7.56	2,696,423	Main
Arainaw-Kamal Howlader Khal Re-excavation	3.80	75,284	Main
Burir Khal Re-excavation	2.60	138,063	Main
Patilapara Khal Re-excavation	1.35	93,113	Main
Rajapur Khal Re-excavation	1.05	92,271	Main
Arainaw-Kamal Howlader Khal-2 Re-excavation	2.05	183,128	Main
Mohisbari Khal Re-excavation	3.75	552,923	Main
Rajapur Br. Khal Re-excavation	0.45	31,769	Main
Burir Khal Regulator	1-V(1.5mX1.8m)	2,290,630	Main
Patilapara Khal Regulator	1-V(1.5mX1.8m)	1,694,266	Main
Kalibari Regulator	1-V(1.5mX1.8m)	1,678,849	Main
Kamal Howlader Khal Pipe Sluice at Ch. 5+006m	1-V(900mm Dia)	696,799	Main
Rajapur Khal Pipe Sluice at Ch.1+010m	2-V(900mm Dia)	524,052	Main
O&M Shed		270,987	Main

SSWRDSP-2

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP22027, Dhulia Subproject, FMD, Union : Dhulia, HO Date: 28/04/2009				
	Embankment Re-sectioning	13.77	2,360,438	Main
	O&M Shed	12.00mX6.00m 0.00	278,083	Main
	Embankment Re-sectioning	0.66	145,582	Main
	Mondol Bari Khal Regulator at Ch.12+809 km	1-V(1.5mX1.5m) 0.00	1,921,956	Main
	Patuakhali Regulator at Ch.19+204 km	1-V(1.5mX1.5m) 0.00	1,974,661	Main
	Dhulia Bazar Pipe Sluice at Ch.8+093 km	1-V(900mm Dia) 0.00	931,051	Main
	Anser Bari Pipe Sluice at Ch.11+450 km	1-V(900mm Dia) 0.00	930,976	Main
	Rabaiyer Khal Re-excavation	2.45	371,175	Main
	Patukhali Khal Re-excavation	1.95	225,082	Main
	Dhulia Bazar Khal Re-excavation	0.35	24,685	Main
	Rabaiyer Bazar Regulator at Ch.2+850 km	2-V(1.5mX1.5m) 0.00	2,804,183	Main
PSSWRSP				
SP41005, Kanakdia FMD Subproject, FMD, Union : Konkadia, HO Date: 04/03/2018				
	Part A: Re-sectioning of Embankment	8.14	7,006,075	Main
	Part D: Kumbakhali Khal Regulator	1V-1.5mX1.8m 0.00	3,699,289	Main
	Part G: WMCA Office & Related works	12.0mX6.0m 0.00	1,410,639	Main
	Part C: Re-excavation of Hogla Khal	2.45	1,405,603	Main
	Part D: Re-excavation of Kalta Khal	3.45	1,236,538	Main
	Part B: Re-excavation of Narayanpasha Khal	3.15	720,869	Main
	Part E: Re-excavation of Kalta Branch Khal	0.85	285,340	Main
	Part A: Narayanpasha Khal Regulator	1V-1.5mX1.8m 0.00	5,248,090	Main
	Part C: Hogla Khal Regulator	2V-1.5mX1.8m 0.00	7,372,205	Main
	Part B: Kalta Khal Regulator	2V-1.5mX1.8m 0.00	7,433,815	Main
	Part F: Purba Narayanpasha Khal Pipe Sluice	1V-900 mm dia 0.00	2,186,244	Main
	Part E: Amirabad Bautali Khal Pipe Sluice	1V-900 mm dia 0.00	2,186,244	Main
SP43050, Moddah-Purba Rajapur Subproject, DR, Union : Kalisuri, HO Date: 28/09/2017				
	Part-G: Lined Reference section	0.00	248,969	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,469,637	Main
	Part-A: Re-excavaion of Kumarkhali khal	1.70	3,323,867	Main
	Part-B: Re-excavaion of Shikalgara khal	2.50	3,936,915	Main
	Part-C: Re-excavaion of Hizbullah khal	1.10	1,248,614	Main
	Part-D: Re-excavaion of Shauder khal	0.50	377,958	Main
	Part-E: Re-excavaion of Thakurbari khal	0.30	210,172	Main
	Part-F: Re-excavaion of Dighir khal	0.40	285,308	Main
SP43057, Adabaria Subproject, FMD&IRR, Union : Adabaria, HO Date: 15/11/2016				
	Part-B: Embankment (Lximapasa Vill. to Closure of Paksira	1.80	271,649	Main
	Part-C: Embankment (Closure of Paksira to Balia Bazar)	0.95	491,983	Main
	Part-D: Embankment (Hazirhat-Baga road to the outfall to F	1.20	593,476	Main
	Part-E: Reference Lined Section	0.00	98,151	Main
	Part-A: Re-excavation of Paksiraj khal	2.30	2,495,126	Main
	Part-D: WMCA office &related work	12mx6m 0.00	1,693,360	Main
	Part-C: Outlet Structure-2 (Pipe regulator)	1V-0.9m 0.00	1,140,893	Main
	Part-B: Outlet Structure-1 (Pipe regulator)	1V-0.9m 0.00	1,273,454	Main
	Part-A: Paksiraj Khal Regulator	1V-1.5mx1.8m 0.00	6,624,764	Main
SP43058, Shabupura Khal Subproject, DR, Union : Boga, HO Date: 06/09/2015				
	Part-E: Re-excavation of Daser Howla Khal	1.00	419,339	Main
	Part-F: Lined Reference section	0.00	278,585	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,604,043	Main
	Part-A: Re-excavation of Hastaram Link khal & Uttar Rajna	1.65	2,116,297	Main
	Part-B: Re-excavation of Fultala khal-2	1.80	1,839,529	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP43060, Ponahura Subproject, FMD&WC, Union : Kalushuri, HO Date: 16/11/2015	Part-C: Re-excavation of Fultala khal-1	0.40	240,116	Main
	Part-D: Re-excavation of Gazirhota Part 1 & 2 Khal	1.70	1,566,741	Main
	Part-E: Inlet Structure-4	1V-0.9m dia 0.00	2,018,989	Main
	Part-D: Outlet Structure-3	1V-0.9m dia 0.00	1,610,202	Main
	Part-C: Outlet Structure-2	1V-0.9m dia 0.00	1,319,917	Main
	Part-F: FC Structure-5	1V-0.9m dia 0.00	466,962	Main
	Part-B: Outlet Structure-1	1V-0.6m dia 0.00	1,136,346	Main
	Part-A: Re-excavation of Farid khar-Jimtla khal & filling with	2.60	4,214,933	Main
	Part-B: Re-sectioning of Embankment (Dhulia don part)	2.40	1,642,721	Main
	Part-C: Re-sectioning of Embankment (Dhlapara part)	1.60	1,029,008	Main
	Part-D: Re-sectioning of Embankment (Panuhara part)	0.64	366,030	Main
	Part-E: Reference lined section	0.00	85,497	Main
	Part-G: WMCA office & others	12mx6m 0.00	1,656,166	Main
	Part-A: Farid khar khal Regulator	2V-1.2mx1.5m 0.00	10,525,595	Main
Dumki PSSWRSP				
SP46249, Noldoari Subproject, DR, Union : Sreerumpur, HO Date: 28/05/2018				
	Part-A: construction of WMCA office and others	12mX6m 0.00	1,228,941	Main
	Part-A: Re-excavation of Noldoani khal	2.60	3,134,863	Main
	Part-B: Re-excavation of Pichakhali Khal	2.90	2,026,149	Main
	Part-C: Re-excavation of Pichakhali Branch Khal	0.47	456,993	Main
	Part-D: Re-excavation of Gabtoli Khal	0.50	432,961	Main
	Part-E: Re-excavation of Noldoani Branch Khal	1.50	989,811	Main
	Part-F: Construction of Referenced Lined Section	0.00	262,332	Main
Galachipa SSWRDSP-1				
SP11011, Chalitabunia FCD Subproject, FCD, Union : Chalitabunia, HO Date: 30/06/1999				
	Embankment Re-sectioning (Sec. 1)	7.60	4,445,471	Main
	Embankment Re-sectioning(Sec.2)	7.13	3,485,591	Main
	Gurubhanga Regulator	2-V(1.5mX1.8m)	3,667,530	Main
	Bibirhaola Regulator	1-V(1.5mX1.8m)	2,518,387	Main
PSSWRSP				
SP45187, Majumdar Khal-Daser Khal Subprojec, DR, Union : Dakua, HO Date: 25/07/2017				
	Part-A: Construction of Box Culvert (1v-3.5mX3.0m)on Bai	(1v-3.5mX3.0m) 0.00	0	Main
	Part-G: Re-excavation of thakurer Khal	1.05	577,209	Main
	Part-H: Construction of Reference Lined Section	0.00	222,144	Main
	Part-B: Construction of Box Culvert (2v-2.5mX2.7m) on Ba	(2v-2.5mX2.7m) 0.00	0	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Majumder Khal	3.00	1,280,799	Main
	Part-B: Re-excavation of Daser Khal	1.73	1,088,958	Main
	Part-C: Re-excavation of Gaijuddinhota Khal	0.90	539,595	Main
	Part-D: Re-excavation of Laragachhi Khal	1.76	810,650	Main
	Part-E: Re-excavation of Bansbaria Khal	0.80	573,330	Main
	Part-F: Re-excavation of Raybari Khal	0.50	374,424	Main
Kalapara SSWRDSP-1				
SP15337, Nilganj DR Subproject, DR, Union : Nilganj, HO Date: 23/05/2002				
	Kumirmara Khal Re-excavation	1.40	492,798	Main
	Mustafapur Khal Re-excavation	2.37	1,086,987	Main
	Pakhimara Khal Re-excavation	1.95	181,026	Main
	Box Culvert at Ch. 0+160m	2-V(2.0mX2.5m)	860,615	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
PSSWRSP SP45170, Lalua-Golbunia Subproject, DR, Union : Tiakhali, HO Date: 20/09/2017	Box Culvert at Ch. 0+190m	2-V(2.0mX2.5m)	860,763	Main
	Part-A: Box Culvert-1(1v-3.0mX3.0m)	(1v-3.0mX3.0m) 0.00	1,334,802	Main
	Part-B: Box Culvert-2 (2v-2.50mX2.50m)	(2v-2.50mX2.50m) 0.00	1,446,588	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	1,077,995	Main
	Part-A: Re-excavation of Swanirvar Khal	3.15	1,076,467	Main
	Part-B: Re-excavation of Chingura Khal	1.72	552,411	Main
	Part-C: Re-excavation of Dashkani Khal	1.62	1,023,489	Main
	Part-D: Re-excavation of Mollapara Khal	1.91	366,606	Main
Mirzaganj SSWRDSP-2 SP25210, Deuli-Subidkhali Subproject, DR&WC, Union : Dewli Subidkhali, HO Date:	Part-E: Construction of Reference Lined Section	0.00	221,129	Main
	Re-excavation of Goalkhali Khal	6.38	1,031,068	Main
	Deuli Subidkhali Regulator at Ch.6+350Km	2 Vent-1.5mx1.5m 0.00	4,584,293	Main
	O&M Shed	Size: 9mX5m 0.00	365,179	Main
PSSWRSP SP45160, Chaitya-Bajita Subproject, DR&WC, Union : Madhabkhali, HO Date: 13/09/2017	Part-A: Construction of regulator (1V-1.5mX1.5m) on Napit	(1v-1.5mX1.5m) 0.00	0	Main
	Part-D: Re-excavation of Ghurniarjhor Khal	1.15	814,116	Main
	Part-H: Re-excavation of Puran Khal	0.57	291,729	Main
	Part-E: Re-excavation of Napitkhali khal	2.07	1,189,204	Main
	Part-F: Re-excavation of Nayakatakhali khal	3.10	1,354,845	Main
	Part-G: Re-excavation of Parakhali khal	1.52	679,592	Main
	Part-I: Re-excavation of Sihkderbarir khal	1.82	1,203,751	Main
	Part-J: Re-excavation of Mojumderbarir khal	2.64	1,568,746	Main
	Part-K: Construction of Reference Lined Section	0.00	322,599	Main
	Part-B: Construction of regulator (1V-1.5mX1.5m) on Ghur	(1v-1.5mX1.5m) 0.00	0	Main
	Part-C: Construction of Box Culvert (1V-3.5mX3.5m) on Cl	(1v-3.5mX3.5m) 0.00	0	Main
	Part-D: Construction of Box Culvert (1V-3.0mX2.7m) on M	(1v-3.0mX2.7m) 0.00	0	Main
	Part-E: Construction of Box Culvert (1V-3.0mX2.0m) near	(1v-3.0 mX2.0m) 0.00	0	Main
	Part-F: Construction of WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Betbunia Khal	2.90	912,271	Main
	Part-B: Re-excavation of Chakar Khal	2.15	718,173	Main
	Part-C: Re-excavation of Chakar Br.Khal	0.73	322,180	Main
Sadar SSWRDSP-1 SP13103, Hetalia-Madarbunia FCD Subproject, FCD, Union : Madarbunia, HO Date:	Embankment Re-sectioning	9.54	4,524,246	Main
	Re-excavation of Maderbunia Khal	3.00	849,156	PSSWRSP
	Re-excavation of Kalir Khal	2.20	1,475,605	PSSWRSP
	Patabunia khal re-excavation(ch.00-2200m)	2.20	4,006,748	SSSWRDP
	Meser Mollar khal re-excavation(ch.00-1000m)	1.00	1,611,862	SSSWRDP
	Hetalia embankment re-sectioning(ch.1000-4000m)	3.00	4,563,975	SSSWRDP
	Referenced line section(4nos)	0.00	113,925	SSSWRDP
	Bamboo bridge(2nos)	0.03	103,495	SSSWRDP
	Regulator at Ch.1+980m	1-V(1.5mX1.8m)	2,333,616	Main
	Regulator at Ch.3+840m	2-V(1.5mX1.8m)	4,061,674	Main
	Regulator at Ch.6+574m	2-V(1.5mX1.8m)	4,061,729	Main
	Pipe Sluice at Ch.0+425m	1-V(900mm Dia)	432,227	Main
	Pipe Sluice at Ch.4+320m	1-V(900mm Dia)	445,919	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP13104, Barobigha Mollabari FCD Subproject, FC, Union : Barobigha, HO Date:	Regulator at Ch.3+240m	1-V(1.5mX1.5m)	444,597	Main
	Embankment Resectioning	5.47	2,180,137	Main
	Saheber Khal Regulator	1-V(1.2mX1.2m)	2,136,967	Main
SP15265, Pairakunja FCD Subproject, FCD, Union : Itabaria, HO Date: 20/06/2002				
	Embankment-1 Re-sectioning	11.85	3,961,105	Main
	Kurir Khal Regulator at Ch.1+080m	2-V(1.5mX1.8m)	2,234,321	Main
	Galachip Khal Regulator at Ch.3+382m	3-V(1.5mX1.8m)	4,710,395	Main
	Durgapur Khal Regulator at Ch.10+940m	2-V(1.5mX1.8m)	2,231,447	Main
	Gilabunia Khal Pipe Sluice	1-V(900mm Dia)	995,172	Main
	Hala-Bash Khal Pipe Sluice	2-V(900mm Dia)	992,290	Main
SP15266, Barabighai DR Subproject, DR, Union : Barabighai, HO Date: 19/06/2002				
	Katakhali Khal Re-excavation	2.50	358,590	Main
	Chakrobari Khal Re-excavation	4.00	350,857	Main
	Main Khal Re-excavation	2.70	376,783	Main
SP15316, Bhagirabad-Jainkathi FCD Subproject, FCD, Union : Jainkathi, HO Date:				
	Embankment Re-sectioning	1.85	1,372,677	Main
	Kalibari khal re-excavation(ch.00-800m)	0.80	1,529,938	SSSWRDP
	Referenced line section((2nos)	0.00	45,693	SSSWRDP
	Bamboo bridge((1nos)	0.00	38,332	SSSWRDP
	Embankment re-sectioning(ch.00-1800m)	1.80	3,571,142	SSSWRDP
	Kalibari Khal Re-excavation	1.20	31,391	Main
	Kalibari Khal Pipe Sluice at Ch.0+490m	2-V(900mm Dia)	848,671	Main
	Taluderbari Khal Pipe Sluice at Ch.1+650m	1-V(900mm Dia)	866,995	Main
PSSWRSP				
SP44143, Hetalia-Ballabhpur Khal Subproject, DR, Union : Ballavpur, HO Date: 24/01/2017				
	Part-A: Construction of Box Culvert (1v-3.0mX3.50) on Bal	1v-3.0mX3.50m 0.00	0	Main
	Part-G: Re-excavation of Dibupur khal	1.10	1,872,283	Main
	Part-H: Construction of Reference lined Section	0.00	316,324	Main
	Part-B: Construction of Box Culvert (1v-2.50mX2.50m)on l	1V-2.50mX2.50m 0.00	0	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Hetalia khal	1.50	399,169	Main
	Part-B: Re-excavation of Khalek Fakirer khal	2.00	1,697,811	Main
	Part-C: Re-excavation of Ballabpur khal	3.58	4,773,901	Main
	Part-D: Re-excavation of Bisshas Bari khal	1.10	1,265,349	Main
	Part-E: Re-excavation of Battaler khal	1.49	974,768	Main
	Part-F: Re-excavation of Khalek Fakirer (2) khal	0.46	789,564	Main
SP46258, Itbaria Subproject, DR, Union : Itabaria, HO Date: 12/10/2017				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,184,840	Main
	Part-A: Re-excavation of Atar-Jamadar Barir Khal	3.40	2,345,041	Main
	Part-B: Re-excavation of Gopalkhali-Haoladerbarir Khal	1.80	2,583,751	Main
	Part-C: Re-excavation of Gopalkhali-Madrassa Khal	4.00	5,469,798	Main
	Part-D: Re-excavation of Kchichhira-bishwaas Khal	1.50	2,433,923	Main
	Part-E: Re-excavation of kismat-pukurjana branch Khal	0.50	170,953	Main
	Part-F: Re-excavation of kismat-pukurjana Khal	0.90	628,404	Main
	Part-G: Construction of Reference Lined Section	0.00	309,776	Main

Pirojpur (Total SPs : 27 Nos.)

Bhandaria

SSWRDSP-1

SP15271, Matibhanga DR Subproject, DR, Union : Gauripur, HO Date: 21/06/2002

Re-excavation of Uttar Paikkhali Fayzoddin khal.	1.90	1,378,592	PSSWRSP
--	------	-----------	---------

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Uttar Paikkhali Etbaria khal.	1.30	1,685,396	PSSWRSP
	Re-excavation of Maliarhat Jalils khal.	1.40	376,124	PSSWRSP
	Re-excavation of Maliarhat Jabbars khal.	0.80	711,146	PSSWRSP
	Main Khal Re-excavation	4.95	1,596,227	Main
	Main Khal-2 Re-excavation	0.86	204,274	Main
	Thakurbari Khal Re-excavation	1.80	324,535	Main
	Pareyer Khal Re-excavation	1.65	464,548	Main
	Utkura Khal Re-excavation	2.38	600,570	Main
	Gazishiparkandi Khal Re-excavation	2.40	781,542	Main
	Charail Madrasha Khal Re-excavation	1.45	201,719	Main
	Amiruddin Khal Re-excavation	0.55	65,148	Main
	Afiluddin Khal Re-excavation	0.45	120,561	Main
	Baroy Bahir Khal Re-excavation	0.30	24,161	Main
	Hogal Gasir Khal Re-excavation	0.30	28,923	Main
	Napit Barir Khal Re-excavation	0.33	19,065	Main
	Tohoshilder Khal Re-excavation	0.30	63,167	Main
SP15322, Harinpala FCD Subproject, FCD, Union : Telikhali, HO Date: 15/08/2003				
	Embankment Re-sectioning	7.62	5,156,090	Main
	Re-excavation of Padma Khal-1	1.50	603,826	PSSWRSP
	Re-excavation of Padma Khal-2	1.50	782,926	PSSWRSP
	Re-excavation of Master Khal	1.50	579,353	PSSWRSP
	Re-excavation of Ruhita Khal	1.50	1,221,403	PSSWRSP
	Paddha branch khal -1(ch.00-900m)	0.90	1,941,763	SSSWRDP
	Embankment re-sectioning(ch.700-2250m)	1.55	1,684,523	SSSWRDP
	Referenced line section(2 nos)	0.00	48,204	SSSWRDP
	Bamboo bridge(1nos)	0.00	42,173	SSSWRDP
	Padma Khal-1 Re-excavation	2.70	309,115	Main
	Padma Khal-2 Khal Re-excavation	2.70	137,904	Main
	Padma Khal-3 Khal Re-excavation	0.90	117,821	Main
	Rohita Khal Re-excavation	1.53	205,154	Main
	Master Khal Re-excavation	1.50	87,089	Main
	Regulator at Ch.1+636m	2-V(1.5mX1.5m)	1,319,391	Main
	Regulator at Ch.3+769m	2-V(1.5mX1.5m)	1,319,391	Main
	Regulator at Ch.7+350m	1-V(1.2mX1.5m)	1,319,391	Main
	Pipe Sluice at Ch.5+950m	2-V(900mm Dia)	721,231	Main
	O&M Shed		263,084	Main
	Box Culvert over Padma Khal-2 at Ch.2+020m	1-V(2.5mX2.75m)	287,515	Main
PSSWRSP				
SP43062, Gouripur Subproject, DR, Union : Gauripur, HO Date: 17/09/2017				
	Part-A: Re-excavation of Talukdarbari-Mollabari khal	4.85	2,211,480	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,314,220	Main
	Part-B: Re-excavation of Maliarhat-Charail Madrasha khal	2.00	868,584	Main
	Part-C: Re-excavation of Gosher khal	3.52	2,173,512	Main
	Part-D: Re-excavation of Shaheber khal	3.10	2,095,311	Main
	Part-E: Re-excavation of Panchayeter khal	0.70	409,513	Main
	Part-F: Re-excavation of Afzalkhar khal	0.71	419,595	Main
	Part-G: Re-excavation of Bhasabarir khal	0.55	248,996	Main
	Part-H: Re-excavation of Palwanbarir khal	0.60	285,836	Main
	Part-I: Ref. Lined Section of Khal	0.00	862,080	Main

Kowkhali
SSWRDSP-1

SP12019, Nilty-Chirapara FCD Subproject, FCD, Union : Chirapara, HO Date: 15/05/2001

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Embankment Re-sectioning	8.57	2,318,400	Main
	Damaged Embankment Re-sectioning	1.64	448,971	Main
	Embankment Palasiding Works	0.00	235,853	Main
	Part-A: Re-sectioning of Embankment from Nilty-Chirapara	1.44	1,384,119	PSSWRSP
	Part-B: Re-excavation of Nilty-GPS khal	1.52	1,184,679	PSSWRSP
	Part-C: Re-excavation of Kesarta khal	1.80	700,675	PSSWRSP
	Part-D: Re-excavation of Kesarta Branch khal	0.70	454,484	PSSWRSP
	Kachari Barir Khal re-excavation(ch00-2950m)	2.95	5,303,049	SSSWRDP
	Kumar Barir Khal re-excavation(ch00-1650m)	1.65	1,916,684	SSSWRDP
	Kesta Khal re-excavation(ch00-630m)	0.63	699,017	SSSWRDP
	Referenced line section(6nos)	0.00	158,690	SSSWRDP
	Bamboo Bridge(6nos)	0.08	263,581	SSSWRDP
	Badamtala Khal Re-excavation	0.60	48,374	Main
	Kacharibari Khal Re-excavation	0.71	49,997	Main
	Kumerbari Khal Re-excavation	1.14	154,228	Main
	Nilty Khal Re-excavation	1.01	51,104	Main
	Nilty-Fakirbari Khal Re-excavation	1.06	32,262	Main
	Kesarta Regulator	2-V(1.2mx1.5m)	2,086,353	Main
	Kacharibari Box Sluice	1-V(1.2mx1.2m)	904,684	Main
	Nilty Box Sluice	1-V(1.2mX1.2m)	900,018	Main
	Badamtala Box Sluice	1-V(1.2mX1.2m)	900,045	Main
	Kumerbari Box Sluice	1-V(1.2mX1.2m)	901,984	Main
	Nilty-Fakirbari Box Sluice	1-V(1.2mX1.2m)	985,542	Main
	O&M Shed		0	Main
SP13052, Nilty Khal FCD Subproject, FCD, Union : Chirapara, HO Date: 02/10/2003				
	Embankment Re-sectioning	2.05	525,983	Main
	Part-A: Re-excavation of Nilti Khal	1.00	1,348,780	PSSWRSP
	Part-B: Re-excavation of Nilti Branch Khal	0.90	735,678	PSSWRSP
	Part-C: Re-excavation of Saturia Khal	0.90	840,372	PSSWRSP
	Nilty Khal Regulator	1-V(1.2mX1.5m)	1,027,111	Main
	Pipe Sluice	1-V(900mm Dia)	421,985	Main
PSSWRSP				
SP46236, Dumjuri Khal Subproject, DR, Union : Kalakhali, HO Date: 03/11/2017				
	Part-A: WMCA office & others	12mX6m 0.00	1,407,251	Main
	Part-I: Re-excavation of Chirapara Juri khal	1.00	899,270	Main
	Part-J: Construction of Reference Lined Section	0.00	360,946	Main
	Part-A: Re-excavation of Mittabazar khal	0.90	469,402	Main
	Part-B: Re-excavation of Dumjori khal	1.00	535,104	Main
	Part-C: Re-excavation of Madartola khal	1.10	565,743	Main
	Part-D: Re-excavation of Majibari khal	0.50	360,521	Main
	Part-E: Re-excavation of Atomollabari khal	0.30	289,589	Main
	Part-F: Re-excavation of Mollakhalii khal	1.20	566,747	Main
	Part-G: Re-excavation of Basabari khal	0.90	243,181	Main
	Part-H: Re-excavation of Chirapara khal	0.90	405,946	Main
Mothbaria				
SSWRDSP-1				
SP13090, Singrabunia FCD Subproject, FCD, Union : Amragachia, HO Date: 04/10/2012				
	Embankment Re-sectioning	6.72	1,793,847	Main
	Part-A: Re-excavation of Rammalar Khal	2.05	2,123,832	PSSWRSP
	Part-B: Re-excavation of Bisshaser Khal	1.10	988,446	PSSWRSP
	Part-D: Re-excavation of Darbeshar Khal	1.10	1,642,342	PSSWRSP
	Regulator at Ch.1+400m	1-V(1.2mX1.5m)	1,711,513	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Regulator at Ch.2+050m	1-V(1.2mX1.5m)	1,803,320	Main
	Regulator at Ch.5+350m	1-V(1.2mX1.5m)	1,643,514	Main
	Regulator at Ch.6+510m	1-V(1.2mX1.5m)	3,039,100	Main
SP14134, Tushkhali FCD Subproject, FCD, Union : Dhanishapa, HO Date: 20/06/2002				
	Embankment Re-sectioning	9.54	3,071,930	Main
	Re-excavation of Masser Khal	1.28	365,830	PSSWRSP
	Re-excavation of Masser Branch Khal	0.62	286,919	PSSWRSP
	Re-excavation of Kata Khali Khal	1.00	452,096	PSSWRSP
	Re-excavation of Kata Khali Branch Khal	0.78	100,509	PSSWRSP
	Re-excavation of Bishaser Khal	1.40	278,738	PSSWRSP
	Macher Khal Regulator at Ch.0+646m	2-V(1.2mX1.5m)	3,349,729	Main
	Katakhali Khal Regulator at Ch.6+100m	2-V(1.2mX1.5m)	1,945,235	Main
	Pipe Sluice at Ch.2+515m	2-V(900mm Dia)	957,097	Main
	Pipe Sluice at Ch.5+365m	2-V(900mm Dia)	1,066,076	Main
	O&M Shed		0	Main
SP14205, Rajarhat-Mirukhali FCD Subproject, FCD, Union : Mirukhali, HO Date:				
	Embankment Re-sectioning	2.92	242,007	Main
	Part-A: Re-excavation of Bashabarir khal.	1.02	1,380,194	PSSWRSP
	Part-A: WMCA Office & others	12mx6m 0.00	2,428,630	PSSWRSP
	Part-B: Re-excavation of Gotichara khal.	1.12	1,048,436	PSSWRSP
	Basabari Regulator at Ch.1+254m	2-V(1.5mX1.5m)	3,199,278	Main
	Chanmiar Khal Regulator at Ch.2+400m	2-V(1.5mX1.5m)	3,200,442	Main
	Rayer Khal Pipe Sluice	1-V(900mm Dia)	727,733	Main
PSSWRSP				
SP42022, Sapleza Subproject, DR, Union : Sapleza, HO Date: 09/06/2015				
	Part-A: WMCA office & others	12mx6m 0.00	1,398,697	Main
	Part-I: Re-excavation of Dakhin Charakgacha Khal	3.05	637,324	Main
	Part-J: Re-excavation of Tafalbaria Khal	1.30	335,639	Main
	Part-K: Re-excavation of Khandakarer Khal	1.75	768,989	Main
	Part-L: Reference Lined Section	0.00	628,490	Main
	Part-A: Re-excavation of Gornali Bharani Khal	5.95	4,452,330	Main
	Part-B: Re-excavation of Bhajjora Khal	3.54	1,421,917	Main
	Part-C: Re-excavation of Bhajjora Branch Khal	1.16	420,482	Main
	Part-D: Re-excavation of Hashem Khar Khal	0.50	160,173	Main
	Part-E: Re-excavation of Hormobunia Khal	1.26	98,525	Main
	Part-F: Re-excavation of Chaltabunia Khal	1.60	475,918	Main
	Part-G: Re-excavation of Malbaria Khal	0.55	414,511	Main
	Part-H: Re-excavation of Hajigonj Khal	1.65	466,190	Main
SP45168, Chalitabunia Ghatichara Subproject, DR&WC, Union : Daudkhali, HO Date:				
	Part-A: Pucca Drain-1	0.00	0	Main
	Part-E: Re-excavation of Olchira khal	0.83	542,842	Main
	Part-F: Re-excavation of Kakrabunia khal	3.85	2,051,340	Main
	Part-G: Re-excavation of Biswasbarir khal	0.70	573,652	Main
	Part-H: Construction of Reference Lined Section	0.00	425,975	Main
	Part-B: Pucca Drain-2	0.00	0	Main
	Part-C: Box Culvert-1 (1v-3.00m X 2.75m)	(1v-3.00m X 2.75m) 0.00	0	Main
	Part-D: Box Culvert-2 (1v-3.00m X 3.00m)	(1v-3.00m X 3.00m) 0.00	0	Main
	Part-E: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A:Re-excavation of Haq Masters	0.95	571,798	Main
	Part-B: Re-excavation ofChalitabunia Beparir khal	3.40	1,466,388	Main
	Part-C: Re-excavation of Azitulla Daktarbarir khal	2.43	1,912,685	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP45169, Betmor-Rajpara Subproject, DR&WC, Union : Betmor Rajpara, HO Date:	Part-D: Re-excavation of Gilabader khal	2.88	2,430,766	Main
	Part-A: Pucca Drain-1	0.00	0	Main
	Part-E: Re-excavation of Beparibarir Khal	3.15	2,664,943	Main
	Part-F: Re-excavation of Muchibarir Khal	2.05	1,909,182	Main
	Part-G: Re-excavation of Nagorer Khal	1.10	697,316	Main
	Part-H: Construction of Reference Lined Section	0.00	637,319	Main
	Part-B: Pucca Drain-2	0.00	1,599,826	Main
	Part-C: Box Culvert-1 (2v-3.00mX3.00m)	(2v-3.00mX3.00m) 0.00	0	Main
	Part-D: Box Culvert-2 (2v-4.00mX4.00m)	(2v-4.00mX4.00m) 0.00	0	Main
	Part-E: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Sangrail Khal	9.55	4,740,058	Main
	Part-B: Re-excavation of Kulurhater Khal	0.65	33,552	Main
	Part-C: Re-excavation of Jankhali Khal	1.05	695,099	Main
	Part-D: Re-excavation of Betmore Khal	2.00	1,643,931	Main
SP45189, Nali-Badurtali Subproject, DR&IRR, Union : Sapleza, HO Date: 18/09/2017				
	Part-A: Inlet (1v-0.60m dia)	(1v-0.60m dia) 0.00	890,915	Main
	Part-C: Re-excavation of Gulbunia khal	4.20	3,468,630	Main
	Part-D: Re-excavation of Gopher khal	1.40	1,103,826	Main
	Part-E: Re-excavation of Nali khal	4.92	4,948,285	Main
	Part-F: Re-excavation of Nali Branch khal	2.30	1,619,574	Main
	Part-G: Re-excavation of Gomastabari khal	1.21	1,047,490	Main
	Part-H: Re-excavation of Chandokhali khal	2.40	1,895,047	Main
	Part-I: Construction of Reference Lined Section	0.00	557,481	Main
	Part-B: Box Culvert-1 (1v-3.50mX3.50m)	(1v-3.50mX3.50m) 0.00	1,901,401	Main
	Part-C: Box Culvert-2 (1v-3.00mX3.00m)	1v-3.00mX3.00m) 0.00	1,521,654	Main
	Part-D: Canal-1 L=.25 km	L=.25 km 0.00	1,443,979	Main
	Part-E: Canal-2 L=.250 km	L=.250 km 0.00	1,465,332	Main
	Part-F: Canal-3 L=.250 km	L=.250 km 0.00	1,444,313	Main
	Part-G: WMCA Office & Others	12mX6m 0.00	1,307,561	Main
	Part-A: Re-excavation of Surojmoni khal	0.80	571,548	Main
	Part-B: Re-excavation of Gazir khal	1.05	1,099,911	Main
SP45206, Mithakhali Subproject, DR&IRR, Union : Betmor Rajpara, HO Date: 19/09/2017				
	Part-A: Irrigation water supply brick canal-1	0.00	0	Main
	Part-E: Re-excavation of Yeasin khar khal	2.24	1,598,180	Main
	Part-F: Re-excavation of Yeasin khar Br. khal	1.70	165,413	Main
	Part-G: Construction of reference lined section	0.00	437,819	Main
	Part-B: Irrigation water supply brick canal-2	0.00	0	Main
	Part-C: Regulator (2v-1.50mX1.80m)	(2v-1.50mX1.80m) 0.00	0	Main
	Part-D: Box Culvert (1v-2.50mX2.50m)	(1v-2.50mX2.50m) 0.00	0	Main
	Part-E: WMCA office & others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Sakharikathi Dhondoa khal	5.33	5,067,614	Main
	Part-B: Re-excavation of Jomaddarbarir khal	0.50	316,677	Main
	Part-C: Re-excavation of kazir khal	2.56	1,690,648	Main
	Part-D: Re-excavation of kazir Br. khal	0.70	339,925	Main
Nazirpur SSWRDSP-1 SP14133, Mitharkul Sachia FCD Subproject, FCD, Union : Malikhali, HO Date: 29/07/2002				
	Embankment Re-sectioning	8.54	1,213,861	Main
	Malikhali Khal Re-excavation	1.92	462,693	Main
	Chapakhali Khal Re-excavation	1.98	433,825	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Kenuabhanga Khal Re-excavation	0.90	182,655	Main
	Malikhali Regulator at Ch.1+985m	1-V(1.5mX1.8m)	2,291,147	Main
	Chapakhali Regulator at Ch.2+700m	1-V(1.5mX1.8m)	2,274,103	Main
	Kenuabhanga Pipe Sluice at Ch.3+100m	2-V(900mm Dia)	1,806,163	Main
SSWRDSP-2				
SP22034, Sreeramkathi Subproject, FMD, Union : Nazirpur, HO Date: 11/09/2007				
	Chowthimahal-Varani Khal Re-excavation	1.22	505,204	Main
	Kumar Khal Re-excavation	1.32	162,069	Main
	Charkhola Khal Re-excavation	1.45	393,633	Main
	Fakirbari Khal Re-excavation	0.65	104,182	Main
	Dariabad Khal Re-excavation	0.98	142,042	Main
	Baro Hazar Br. Khal Re-excavation	0.73	92,111	Main
	Ghoskathi Khal Re-excavation	1.11	191,269	Main
	O&M Shed	12.00mX6.00m 0.00	258,440	Main
	Suta Khal Re-excavation	0.57	78,941	Main
	Hasan Seikh Khal Re-excavation	0.70	55,364	Main
	Chowgacha Khal Regulator at Ch.0+050 km	2-V(1.50mX1.80m) 0.00	3,250,492	Main
	Nailtala-Khajurtala Khal Re-excavation	2.62	1,738,813	Main
	Chougacha Khal Re-excavation	2.97	1,711,376	Main
	Chowtimahal Khal Re-excavation	3.84	1,609,546	Main
	Part-A: Re-excavation of Madha aypur Varanir khal	1.60	1,312,792	PSSWRSP
	Part-B: Re-excavation of Goshkati khal	0.90	187,146	PSSWRSP
	Part-C: Re-excavation of Charkhala khal	0.75	423,080	PSSWRSP
	Part-D: Re-excavation of Moktar Mazir khal	0.40	486,698	PSSWRSP
	Part-E: Re-excavation of Shetanath Mistirir khal	0.50	455,501	PSSWRSP
	Part-F: Re-excavation of Admar khal	0.30	156,622	PSSWRSP
PSSWRSP				
SP46224, Kalardonida Sub-Project, DR, Union : Nazirpur, HO Date: 08/11/2017				
	Part-A: WMCA office & others	12mX6m 0.00	1,402,778	Main
	Part-I: Re-excavation of Dakuabari khal	3.00	1,313,305	Main
	Part-J: Re-excavation of Dakuabari Branch-1 khal	1.00	944,190	Main
	Part-K: Re-excavation of Dakuabari Branch-1 khal	0.00	425,595	Main
	Part-A: Re-excavation of Doctor Bariri khal	1.20	819,766	Main
	Part-B: Re-excavation of Kuloitola khal	1.20	483,990	Main
	Part-C: Re-excavation of Kuloitola Branch-1 khal	0.60	221,762	Main
	Part-D: Re-excavation of Vorani khal	0.75	790,478	Main
	Part-E: Re-excavation of Heshakhali Branch-1 khal	1.30	533,226	Main
	Part-F: Re-excavation of Patakhali khal	1.40	626,472	Main
	Part-G: Re-excavation of Patakhali branch-1 khal	0.90	631,546	Main
	Part-H: Re-excavation of Kata khal	1.90	919,867	Main
Nesarabad (swaru PSSWRSP)				
SP42023, Jalabaria Subproject, DR, Union : Jalabari., HO Date: 06/06/2015				
	Part-A: Re-excavation Bashabari Khal	1.36	1,231,950	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,398,701	Main
	Part-B: Re-excavation Durgamandir Khal	1.65	730,922	Main
	Part-C: Re-excavation Bashirpur Khal	1.65	1,421,308	Main
	Part-D: Re-excavation Boundari Khal	2.05	1,435,980	Main
	Part-E: Re-excavation Panthasala Biddhya Bari Khal	2.35	1,104,001	Main
	Part-F: Re-excavation Prakash Baral Bari Khal	1.25	1,444,603	Main
	Part-G: Re-excavation Rajani Biddyer Bari Khal	1.50	562,902	Main
	Part-H: Re-excavation Maddhya Jalabari Khal	2.22	2,159,454	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP44131, Guarekha Subproject, DR, Union : Guarekha, HO Date: 09/11/2017	Part-I: Construction of Reference Lined Section	0.00	406,954	Main
	Part-A: Construction of WMCA Office & others	12mX6m 0.00	0	Main
	Part-I: Construction Of Reference Lined section	0.00	400,366	Main
	Part-A: Re-excavation of Fultola Khal	1.72	1,356,091	Main
	Part-B: Re-excavation of Bashkhali-chandkati Khal	1.40	985,149	Main
	Part-C: Re-excavation of Rangakhati-Bishal Khal	2.90	2,648,820	Main
	Part-D: Re-excavation of Debidashkati-Chandkhati Khal	0.40	78,509	Main
	Part-E: Re-excavation of Batnata-Gazia Khal	1.20	713,961	Main
	Part-F: Re-excavation of Guarekha (Uttar) Khal	1.25	746,325	Main
	Part-G: Re-excavation of Guarekha (Dakhin) Khal	1.11	1,388,701	Main
	Part-H: Re-excavation of Ambari-Barani Khal	1.40	948,661	Main
SP45181, Sharsina Alonkerkati Subproject, DR, Union : Swarupkhati, HO Date: 21/09/2017	Part-A: Box Culvert (1v-3.5m X3.3m) at Ch. 0+775 km (pa	0.00	0	Main
	Part-E: Re-excavation of Paschim Hauria khal	1.21	1,062,705	Main
	Part-F: Re-excavation of Basurvita khal	1.43	693,426	Main
	Part-G: Re-excavation of Talukder Barir khal	1.25	860,777	Main
	Part-H: Construction of Reference Lined Section	0.00	345,194	Main
	Part-B: Box Culvert (1v-3.5m X3.3m) at Ch. 1+243 km (Tali	0.00	0	Main
	Part-C: Box Culvert (1v-3.5m X3.0m) at Ch. 1+243 km (Kur	0.00	0	Main
	Part-D: Box Culvert (1v-2.0m X2.0m) at Ch. 0+007 km (Dor	0.00	0	Main
	Part-E: WMCA Office & Others	0.00	0	Main
	Part-A: Re-excavation of Alonkarkathi khal	2.60	1,068,567	Main
	Part-B: Re-excavation of Uttar Sarsina khal	1.95	159,908	Main
	Part-C: Re-excavation of Rahutkathi khal	3.18	2,297,082	Main
	Part-D: Re-excavation of Kuniari Sultanpur khal	1.15	780,773	Main
SP45185, Aramkathi-Kumarkathi Subproject, DR, Union : Jalabari., HO Date: 21/09/2017	Part-A: Box Culvert (2v-3.0mX3.0m) on Kamarkathi	(2v-3.0mX3.0m) 0.00	0	Main
	Part-E: Re-excavation of Mollbari Khal	1.35	585,961	Main
	Part-F: Re-excavation of Rahman Master Bari Khal	1.37	352,930	Main
	Part-G: Re-excavation of Rahman Idilkathi Khal	2.15	237,092	Main
	Part-H: Construction of Reference Lined Section	0.00	295,732	Main
	Part-B: Box Culvert (2v-3.0mX3.0m) on Uttar Aramkathi Kh	(2v-3.0mX3.0m) 0.00	0	Main
	Part-C: Box Culvert (2v-2.5mX3.0m) on Kamatkathi Branch	(2v-2.5mX3.0m) 0.00	0	Main
	Part-D: Box Culvert (2v-3.0mX3.0m) on Idilkathi Branch Kl	(2v-3.0mX3.0m) 0.00	0	Main
	Part-E: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Kamarkathi Khal	3.11	918,400	Main
	Part-B: Re-excavation of Uttar Kamarkathi Khal	2.60	1,116,531	Main
	Part-C: Re-excavation of Kamarkathi Branch Khal	2.91	1,019,983	Main
	Part-D: Re-excavation of Idilkathi Branch Khal	1.00	709,179	Main
Sadar SSWRDSP-1 SP14132, Sarikatala-Dumurtala FCD Subproject, FCD, Union : Sarikatala, HO Date:	Embankment Re-sectioning	9.57	4,510,363	Main
	Embankment Extention Re-sectioning	0.70	226,368	Main
	Approach Embankment of Kesorta Regulator	0.40	134,729	Main
	Approach Embankment of Nalbunia Regulator	1.89	433,488	Main
	Goborkhana branch khal re-excavation(ch.00-2600m)	2.60	5,523,028	SSSWRDP
	Monpasha khal re-excavation(ch.00-2430m)	2.43	2,582,869	SSSWRDP
	Nager khal re-excavation(ch.00-1940m)	1.94	2,189,874	SSSWRDP
	Referenced line section(9nos)	0.00	210,198	SSSWRDP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Bamboo bridge(6nos)	0.00	233,708	SSSWRDP
	WMCA Office	12mX6m 0.00	2,020,913	SSSWRDP
	Jugir Khal Regulator at Ch.4+715m	2-V(1.5mX1.5m)	2,064,987	Main
	Kesorta Khal Regulator at Ch.5+695	2-V(1.5mX1.5m)	3,603,931	Main
	Nalbunia Regulator at Ch.2+680m	2-V(1.5mX1.5m)	2,961,900	Main
	Kumir Khal Pipe Sluice at Ch.0+954m	2-V(900mm Dia)	820,706	Main
PSSWRSP				
SP46248, Sikdermaollik-Hizlabari Subproject, DR, Union : Sikder Mollik, HO Date:				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,409,173	Main
	Part-A: Re-excavation of Juskhola-Kumarchira Khal	4.31	4,420,125	Main
	Part-B: Re-excavation of Juskhola-Raibari Khal	1.45	1,339,913	Main
	Part-C: Re-excavation of Mirua-Sikdermollik Khal	4.38	4,527,888	Main
	Part-D: Re-excavation of Panchpara Dakshin Gabtoli Khal	1.31	1,327,490	Main
	Part-E: Re-excavation of Baniari-Kuniari Khal	1.00	710,025	Main
	Part-F: Re-excavation of Hizalbari Khal	1.65	1,543,152	Main
	Part-G: Re-excavation of Juskhola-Nilkhola Khal	0.88	1,223,317	Main
	Part-H: Construction of Reference Lined Section	0.00	374,333	Main
Zia Nagar				
SSWRDSP-1				
SP13069, Saidkhali FCD Subproject, FCD, Union : Balipara, HO Date: 30/06/2002				
	Embankment Re-sectioning	18.20	5,274,269	Main
	Regulator at Ch.4+035m	1-V(1.2mx1.8m)	1,755,956	Main
	Regulator at Ch.0+809m	1-V(1.8mX2.4m)	2,794,783	Main
	Regulator at Ch.1+590m	1-V(1.2mX1.8m)	1,639,699	Main
	Pipe Sluice at Ch.11+180m	1-V(900mm Dia)	448,846	Main
	Fish Screen		46,071	Main
SP13075, Balipara FCD Subproject, FC, Union : Balipara, HO Date: 30/06/2002				
	Embankment Re-sectioning	9.00	4,014,869	Main
	Part-A: Re-excavation of Shorer Khal	4.50	3,802,240	PSSWRSP
	Part-B: Re-excavation of Darghabai Khal	1.10	737,107	PSSWRSP
	Regulator at Ch.0+860m	1-V(1.5mX1.8m)	2,911,176	Main
	Regulator at Ch.9+103m	1-V(1.5mX1.8m)	3,078,021	Main
SP13107, Kalaron FCD Subproject, FC, Union : Balipara, HO Date: 05/01/2004				
	Embankment Re-sectioning(Part-A)	8.93	3,696,086	Main
	Approach Embankment	2.70	395,970	Main
	Re-excavation of Madrasha Khal	0.90	429,986	PSSWRSP
	Re-excavation of Osimuddin Khal	1.11	201,524	PSSWRSP
	Re-excavation of Zomadder Khal	2.25	1,433,937	PSSWRSP
	Re-excavation of Horar Khal	1.62	1,205,748	PSSWRSP
	Re-excavation of Satghar Khal	0.54	240,352	PSSWRSP
	Re-sectioning of Kalaron Embankment	9.45	1,238,744	PSSWRSP
	Regulator at Ch.1+346m	1V(1.5mX1.8m)	3,077,924	Main
	Regulator at Ch.2+263m	1V(1.5mX1.8m)	3,076,764	Main
	Regulator at Ch.9+490m	1-V(1.5mX1.8m)	3,076,999	Main
	Regulator at Ch.2+830m	1-V(1.2mX1.2m)	1,368,930	Main
	Regulator at Ch.6+650m	1-V(1.5mX1.8m)	2,922,411	Main
	Pipe Sluice at Ch.0+230m	1-V(600mm Dia)	449,930	Main
	Pipe Sluice at Ch.0+685m	1-V(900mm Dia)	570,389	Main
	Pipe Sluice at Ch.1+045m	1-V(600mm Dia)	511,385	Main
PSSWRSP				
SP46237, Parerhat Subproject, DR, Union : Parerhat, HO Date: 05/11/2017				
	Part-A: WMCA office & others	12mX6m 0.00	1,405,505	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-I: Re-excavation of Lahuri khal	1.70	1,247,411	Main
	Part-J: Construction of Reference Lined Section	0.00	535,021	Main
	Part-A: Re-excavation of Darichar-Gazipur khal	1.70	142,302	Main
	Part-B: Re-excavation of Darichar-Gazipur Branch-1 khal	0.60	770,686	Main
	Part-C: Re-excavation of Darichar-Lahauri khal	1.20	1,236,360	Main
	Part-D: Re-excavation of Nalbunia-Baraikhali khal	2.90	1,703,708	Main
	Part-E: Re-excavation of Baraikhali-Ikrabunia khal	0.80	764,319	Main
	Part-F: Re-excavation of Baraikhali khal	2.00	1,015,004	Main
	Part-G: Re-excavation of Shorer Branch-1 khal	0.70	376,999	Main
	Part-H: Re-excavation of Shorer khal	3.30	2,217,510	Main

Bandarban (Total SPs : 1 Nos.)

Sadar
Rubber Dam
SP99005, Rajvilla Shilok Khal Rubber Dam Project, WC, Union : , HO Date:

Rajvilla Shilok Khal Rubber Dam	Size: 28mX3.5m 0.00	70,912,000	Main
U-Drain	0.00	1,592,000	Main
Protective Works & Pump Safty Room	0.00	385,000	Main

Brahmanbaria (Total SPs : 7 Nos.)

Kashba
PSSWRSP
SP46234, Sambari-Kalihari Khal Subproject, DR, Union : Mulgram, HO Date: 25/04/2018

Part-A: WMCA office & others	12mX6m 0.00	1,381,812	Main
Part-A: Re-excavation of Hatina Beel	4.23	2,532,568	Main
Part-B: Re-excavation of Dholai khal	1.65	716,242	Main
Part-C: Re-excavation of Kalihari khal	1.52	478,803	Main
Part-D: Re-excavation of Noa khal	2.63	3,905,127	Main
Part-E: Construction of reference lined section	0.00	366,919	Main

Nabinagar
PSSWRSP
SP45144, Parimial khal- Baroaulia Beel, DR, Union : Uttar kaitala., HO Date: 07/09/2017

Part-A: WMCA Office & others	12mX6m 0.00	1,169,633	Main
Part-A: Re-excavation of Perimal khal	4.40	2,655,109	Main
Part-B: Re-excavation of Kapuria khal	1.00	296,804	Main
Part-C: Construction of Reference Lined Section	0.00	80,049	Main

SP45166, Burinadi - Jogidhara Khal Subproject, DR, Union : Ibrahimpur., HO Date:

Part-A: WMCA Office & Others	12mX6m 0.00	1,308,359	Main
Part-A: Re-excavation of Jugidhara khal	4.43	5,314,584	Main
Part-B: Construction of Reference Lined Section	0.00	118,868	Main

SP45172, Birgaon - Tilokia khal Subproject, DR&WC, Union : Birgaon., HO Date:

Part-A: Construction of Regulator (1v-1.5mX1.5m)	(1v-1.5mX1.5m) 0.00	1,974,676	Main
Part-B: Construction of Regulator (1v-1.2mX1.2m)	(1v-1.2mX1.2m) 0.00	1,769,321	Main
Part-C: WMCA Office & Others	12mX6m 0.00	1,231,497	Main
Part-A: Re-excavation of Bilkader Khal	3.50	5,895,543	Main
Part-B: Re-Sectioning of Embankment	2.70	3,249,499	Main
Part-C: Construction of Reference Lined Section	0.00	122,535	Main

Nasirnagar
SSWRDSP-2
SP23051, Singra Khal Subproject, DR&IRR, Union : Gokorna, HO Date: 31/05/2007

Singra Khal Re-excavation	7.40	5,667,531	Main
Boalia Khal Re-excavation	2.23	636,854	Main
Bhadur Khal Re-excavation	2.50	1,243,417	Main

Sadar

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SSWRDSP-2				
SP23083, Birampur Subproject, FMD&WC, Union : Sadekpur, HO Date: 03/05/2006				
	Afili Pipe Sluice at Ch.0+030Km (Khal)	1 Vent-0.90m Dia 0.00	928,667	Main
	Katakhali Pipe Sluice at Ch.0+020Km (Khal)	1 Vent-0.90m Dia 0.00	929,375	Main
PSSWRSP				
SP43038, Shilaur-Dogangy Khal Subproject, DR, Union : Sultanpur, HO Date: 25/05/2014				
	Part-A: WMCA office & others	12mx6m 0.00	1,398,475	Main
	Part-A: Re-excavation of Silaur-Dogangy khal	2.90	4,021,484	Main
	Part-B: Re-excava. of Silaur-Dogangy Branch khal	0.30	273,831	Main
	Part-C: Re-excavation of Nayahati khal	1.30	1,655,607	Main
Chandpur (Total SPs : 13 Nos.)				
Faridganj				
SSWRDSP-2				
SP25294, Aicher Bager Khal Subproject, CAD&IRR, Union : Subidpur East, Subidpur West,				
	Re-excavation of Aicher Bager Khal	2.47	785,964	Main
	WRS	3 Vent-1.5mX1.5m 0.00	2,273,461	Main
	Brick Lined Canal	Length: 3150m 0.00	4,898,839	Main
	Re-excavation of Telishair Khal	0.55	279,111	Main
	Re-excavation of Lakshipur khal	0.75	744,625	PSSWRSP
	Re-excavation of Embankment	3.10	2,989,298	PSSWRSP
SP25295, Chowdhuri Miji Khal Subproject, CAD&IRR, Union : Subidpur East, HO Date:				
	Chawdhury Miji WRS at Ch.0+100Km(Khal)	3 Vent-1.5mX1.5m 0.00	2,490,414	Main
	Re-excavation of Chowdhury Miji Khal	2.58	852,008	Main
	Re-excavation of Soban-Karati Khal Khal	1.76	188,502	Main
	Chawdhury Miji Check Structure at Ch.2+500Km(Khal)	2 vent-1.5mX1.5m 0.00	1,332,334	Main
	Sump (8ns) & Lined Canal	Length: 4000m 0.00	6,154,006	Main
	Part-A: Re-section of Dighar Corner Embankment	1.20	1,807,076	PSSWRSP
	Part-B: Re-section of Dighar Embankment	0.90	909,351	PSSWRSP
	Part-C: Re-excavation of Dighar Hajiganj Khal	0.90	670,597	PSSWRSP
SP25296, Sreekhalia Khal Subproject, CAD&IRR, Union : Gupti East, HO Date: 11/03/2012				
	Re-excavation of Sreekhalia Khal	2.17	1,058,546	Main
	Sreekhalia Khal WRS at Ch. 0+100Km (Khal)	3 Vent-1.5mX1.5m 0.00	2,359,101	Main
	Sump (6 nos.) & Lined Canal	Length: 2950m 0.00	4,805,748	Main
	Part-A: re-sectioning of hajiganj Embankment	1.99	1,894,379	PSSWRSP
	Part-B: Re-sectioning of hajiganj Khal & reference lined Se	1.50	1,379,880	PSSWRSP
PSSWRSP				
SP45188, Subidpur Khal Subproject, CAD, Union : Subidpur East,, HO Date: 26/04/2018				
	Part-A: Construction of of Brick Lined Canal	0.00	0	Main
	Part-B: WMCA Office 7 Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Subidpur Khal and Construction o	2.20	1,093,156	Main
	Part-B: Re-excavation of Bagpur Khal and Construction of I	1.00	706,411	Main
SP46242, Montola saliapara Subproject, DR&WC, Union : Subidpur East,, HO Date:				
	Part-A: Box Culvert	(1v-3.50mX3.50m) 0.00	1,861,188	Main
	Part-J: Irrigation Water supply Brick Canal-09	0.00	1,132,191	Main
	Part-k: WMCA Office & Others	12mX6m 0.00	1,402,633	Main
	Part-A: Re-excavation of Montala Khal	2.90	2,617,593	Main
	Part-B: Re-excavation of Montala Br. Khal	0.20	146,147	Main
	Part-C: Re-excavation of Chaliapara Khal	2.42	2,212,166	Main
	Part-D: Construction of Reference Lined Section	0.00	206,722	Main
	Part-B: Irrigation Water supply Brick Canal-01	0.00	880,716	Main
	Part-C: Irrigation Water supply Brick Canal-02	0.00	1,153,855	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Haziganj PSSWRSP SP46225, Sendra Belchow Subproject, CAD, Union : Barkol East,, HO Date: 25/04/2018	Part-D: Irrigation Water supply Brick Canal-03	0.00	873,638	Main
	Part-E: Irrigation Water supply Brick Canal-04	0.00	874,543	Main
	Part-F: Irrigation Water supply Brick Canal-05	0.00	877,952	Main
	Part-G: Irrigation Water supply Brick Canal-06	0.00	,142,699,375	Main
	Part-H: Irrigation Water supply Brick Canal-07	0.00	1,146,737	Main
	Part-I: Irrigation Water supply Brick Canal-08	0.00	1,153,896	Main
	Part-A: Construction of RCC Irrigation Channel-1	0.00	0	Main
	Part-J: Construction of RCC Irrigation Channel-10 & 10A	0.00	0	Main
	Part-K: WMCA office & others	12mX6m 0.00	0	Main
SP46229, Patanish Noapara Subproject, DR&WC, Union : hatila, HO Date: 22/04/2018	Part-A: Re-excavation of Kendra khal	1.54	864,321	Main
	Part-B: Re-excavation of Sonaimuri khal	1.20	731,579	Main
	Part-C: Re-excavation of Kazirkhil-Mollar Dahar khal	2.83	1,059,762	Main
	Part-D: Re-excavation of Sendra khal	0.60	258,763	Main
	Part-E: Construction of Reference Lined Section	0.00	154,989	Main
	Part-B: Construction of RCC Irrigation Channel-2	0.00	0	Main
	Part-C: Construction of RCC Irrigation Channel-3	0.00	0	Main
	Part-D: Construction of RCC Irrigation Channel-4	0.00	0	Main
	Part-E: Construction of RCC Irrigation Channel-5	0.00	0	Main
	Part-F: Construction of RCC Irrigation Channel-6	0.00	0	Main
	Part-G: Construction of RCC Irrigation Channel-7	0.00	0	Main
	Part-H: Construction of RCC Irrigation Channel-8 & 8A	0.00	0	Main
	Part-I: Construction of RCC Irrigation Channel-9A	0.00	0	Main
	Part-A: Construction of RCC Irrigation Canal-1	0.00	1,778,071	Main
	Part-B: Construction of RCC Irrigation Canal-2	0.00	1,211,758	Main
SP46247, Firoj khal Subproject, DR&IRR, Union : Kaloch (North), HO Date: 23/04/2018	Part-C: Construction of RCC Irrigation Canal-3	0.00	2,931,702	Main
	Part-D: Construction of RCC Irrigation Canal-4	0.00	4,303,403	Main
	Part-E: Construction of RCC Irrigation Canal-5	0.00	3,976,875	Main
	Part-F: WMCA Office & others	12mX6m 0.00	1,434,296	Main
	Part-A: Re-excavation of Baghira khal	2.13	1,286,128	Main
	Part-B: Re-excavation of Noapara khal	0.00	123,824	Main
	Part-C: Construction of reference lined section	0.00	123,824	Main
	Part-A: Construction of RCC Irrigation Canal-1	0.00	3,629,091	Main
	Part-D: Construction of Reference Linde section	0.00	227,126	Main
	Part-B: Construction of RCC Irrigation Canal-2	0.00	1,137,477	Main
Kachua PSSWRSP SP42013, South Gohat Subproject, CAD, Union : South gohat, HO Date: 11/09/2017	Part-C: Construction of RCC Irrigation Canal-3	0.00	720,654	Main
	Part-D: Construction of RCC Irrigation Canal-4	0.00	2,328,808	Main
	Part-E: Construction of RCC Irrigation Canal-5	0.00	662,148	Main
	Part-F: Construction of WMCA Office & Others	0.00	603,715	Main
	Part-A: Re-excavation of Firoj khal	4.90	4,316,150	Main
	Part-B: Re-excavation of Abarai khal	0.40	413,375	Main
	Part-C: Re-excavation of Jugir khal	3.40	3,120,848	Main
	Part-C: Re-excavation of Rahimnagar-Kalthuri khal	2.80	912,490	Main
	Part-A: Field Irrigation channel	3.00 Km 0.00	7,611,868	Main
	Part-B: Construction of WMCA office & Others	12mx6.0m 0.00	1,784,470	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP42014, Udura Khal Subproject, CAD, Union : Kadla, HO Date: 12/09/2017	Part-D: Construction of reference lined section	0.00	369,672	Main
	Part-A: Re-excavation of Muragaon-Amujan khal	3.60	1,941,106	Main
	Part-B: Re-excavation of Muragaon-Kalthuri khal	3.20	2,800,917	Main
	Part A: Ferro Cement Channel	3.65km 0.00	9,080,050	Main
	Part C: Construction of Reference Lined Section	0.00	329,701	Main
	Part B: Existing Link Road Improvement	0.46km 0.00	2,621,270	Main
	Part C: Box Culvert in link road improvement	1V-1.0mx1.0m 0.00	625,454	Main
SP42015, Sunduri Khal Subproject, WC&IRR, Union : Shahadebpur., HO Date: 25/09/2017	Part D: WMCA Office & others	12mx6m 0.00	1,420,870	Main
	Part A: Re-excavation of Udhara Khal	6.00	4,196,274	Main
	Part B: Re-excavation of Chand-Gazi Khal	3.50	2,513,497	Main
	Part B: WMCA Office & Related Works	12mx6m 0.00	0	Main
	Part A: Re-excavation of Sunduri khal	7.00	8,630,073	Main
	Part A: Ferro Cement Line Channel	3.50 km 0.00	0	Main
	Part B: Reference Lined Section	0.00	198,746	Main
Sadar				
SSWRDSP-2				
SP25299, Bishaw Khal Subproject, WC, Union : Shah Mohammadpur, Ashikati, HO Date:				
	Bishaw Khal WRS at Ch. 0+300Km (Khal)	4 Vent-1.5mX2.5m 0.00	6,449,047	Main
	Brick Lined Canal	Length: 500m 0.00	866,044	Main
	Re-sectioning of Embankment	3.10	1,834,960	Main
PSSWRSP				
SP46267, Kamranga-Monihar Subproject, CAD, Union : Rampur, HO Date: 15/04/2018				
	Part-A: Construction of RCC Irrigation Canal-1	0.00	3,393,798	Main
	Part-A: Re-excavation of Kamranga Khal	1.10	648,476	Main
	Part-B: Construction of reference lined section	0.00	16,738	Main
Chittagong (Total SPs : 24 Nos.)				
Banshkhali				
PSSWRSP				
SP45153, Bamer Chara Subproject, DR&WC, Union : Puichari, HO Date: 09/08/2018				
	Part-A:Con. of Earthen Dam L=30m, Outlet Struc.1-vent, N	L=30m, 0.00	28,883,675	Main
	Part-B:Con. of WRS 5-vent (1.5mX1.8m)	(1.5mX1.8m) 0.00	4,285,395	Main
	Part-C:Shilkup Ch. Near Miar Goda 3- vent (3.2mX2.0m) V	(3.2mX2.0m) 0.00	2,296,081	Main
	Part-D: Protective Work of 8- vent WRS (1.5mX1.8m)	WRS (1.5mX1.8m) 0.00	883,809	Main
	Part-E: Construction of Irrigation Canal, L=500m	L=500m 0.00	2,296,081	Main
	Part-F: Construction of WMCA Office & Others	12mX6m 0.00	1,312,310	Main
Chandanais				
SSWRDSP-2				
SP25204, Guilla Chhara Subproject, WC, Union : Kanchanabad, HO Date: 30/07/2009				
	Guilla Chhara WRS at Ch. 4+000Km (Khal)	5 Vent-1.5mX2m 0.00	5,844,325	Main
	Guilla Chhara Check Structure at Ch.2+320Km (Khal)	5 Vent-1.5mx1.5m 0.00	1,973,222	Main
	Re-excavation of Guilla Chhara Khal	4.08	733,340	Main
	O&M Shed	Size: 9mX5m 0.00	395,491	Main
Fatikchari				
SSWRDSP-2				
SP24157, Lelung-Kutubchhari-Kalapania Khal Subproject, WC, Union : Lelung, HO Date:				
	WRS-1 at Ch. 0+500Km (Khal)	7 Vent-1.5mX2.5m 0.00	7,358,379	Main
	WRS-2 at Ch. 3+060Km (Khal)	5 vent-1.5mX2.5m 0.00	5,230,816	Main
	Re-excavation of Kalapani Branch Khal	0.78	295,786	Main
	Re-excavation of Kalapani Khal	2.52	919,522	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	443,132	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP24159, Dolu-Mohorkhil Khal Subproject, WC, Union : Paidong, HO Date: 26/07/2009				
	Dolu Khal WRS at Ch.0+545Km	4 Vent-1.5mX2.0m 0.00	5,469,953	Main
	Re-excavation of Dolu Khal	1.80	487,363	Main
	Re-excavation of Dolu-Patial Link Khal	1.30	325,058	Main
	Patial Khal WRS at Ch. 0+450Km (Khal)	2 Vent-1.5mX2.0m 0.00	3,874,012	Main
SP25258, Narayan Hat Gazaria Khal Subproject, WC, Union : Narayanhat, HO Date:				
	Gazaria Khal WRS at Ch. 1+050 Km (main Khal)	5 Vent-1.5mX2.5m+2	11,518,601	Main
	Sreemanta Khal WRS at Ch. 0+100 Km (Branch Khal)	1 Vent-1.5mX1.8m 0.00	2,619,617	Main
SP25293, Rakthachari Subproject, WC, Union : Kanchannagar, HO Date: 27/07/2010				
	Rakthachari WRS at Ch 1+250 Km (Chara)	7 Vent-1.5mx2.5m 0.00	14,235,307	Main
PSSWRSP				
SP41007, Harwalchari Subproject, WC, Union : Harwalchari, HO Date: 10/12/2014				
	A: Rubber Dam, con.bridge, pump house & WMCA off.	30.0mX4.5m 0.00	74,319,552	Main
SP44095, Kalapania Khal Subproject, DR&WC, Union : Kanchannagar, HO Date:				
	Part-A:- Construction of Kalapania WRS	8-1.50mX2.0m 0.00	23,762,649	Main
	Part-B:- Construction of WMCA Office & others	12mX6m 0.00	1,347,316	Main
	Part-A:- Re-excavation of Kalapania Khal	4.60	1,502,905	Main
	Part-B:- Construction of Reference Lined Section	0.00	50,695	Main
Rubber Dam				
SP99001, Halda River Rubber Dam Project, WC, Union : , HO Date:				
	Halda River Rubber Dam	Size: 55mX4.5m 0.00	112,531,000	Main
	Koyachara Regulator	Size: 2 Vent-1.5mX1.8m 0.00	5,820,000	Main
	Horina Khal Regulator	Size: 1.5mX1.8m 0.00	5,796,000	Main
Lohagara				
PSSWRSP				
SP45178, KulPagli chara Subproject, DR&WC, Union : Adunagar, HO Date:				
	Part-A: Construction of of WRS (4v-1.5mX1.5m) on kulpagl	(4v-1.5mX1.5m) 0.00	11,837,027	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Kulpagli Chara Khal	3.10	2,393,418	Main
	Part-B: Construction of Reference Lined Section	0.00	72,258	Main
SP45179, Karam Ali Chara Subproject, DR&WC, Union : Kalauzan, HO Date: 05/09/2018				
	Part-A: Construction of Karam Ali Khal WRS (3v-1.5mX3.5m)	(3v-1.5mX3.5m) 0.00	0	Main
	Part-B: Construction of Irrigation Brick Canal (Length-2295m)	(Length-2295m) 0.00	0	Main
	Part-C: Construction of WMCA Office 7 Others	12mX6m 0.00	36,816	Main
	Part-A: Re-Sectioning of Embankment	0.00	36,816	Main
SP46214, Hungor Khal Subproject, WC, Union : Padua, HO Date: 10/05/2018				
	Part-A: Hangor khal Rubber Dam	0.00	54,496,506	Main
	Part-B: Hangor khal Pump House and Guard Shed	0.00	1,472,333	Main
	Part-C: Outlet Structure (3 Nos. of 2V-900MM Dia) and 50r	12mX6m 0.00	2,689,037	Main
	Part-D: WMCA Office & others	12mX6m 0.00	1,724,279	Main
	Part-A: Construction of canal dyke at Ch.1+200 km to 2+50	1.30	1,227,866	Main
SP46222, Chambhi Khal Subproject, WC, Union : Chunati, HO Date: 20/05/2018				
	Part-A: Chambhi Khal Rubber Dam	0.00	47,874,337	Main
	Part-B: Chambhi Khal Rubber Dam Pump House and Guard	0.00	1,442,711	Main
	Part-C: WMCA Office & Others	0.00	1,724,279	Main
Rubber Dam				
SP98003, Tankabati River Rubber Dam Project, WC, Union : Kalauzan, HO Date:				
	Tankaboti Rubber Dam	Size: 50mX3.5 0.00	29,481,000	Main
Mirsharai				
SSWRDSP-2				
SP25247, Bawa Chhara Subproject, WC, Union : Wahedpur, HO Date: 13/06/2010				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Bawa Chhara Spillway at Ch. 4+400Km	3 Vent-3mX2m 0.00	3,565,852	Main
	Bawa Chhara Reservoir Outlet	Size: 0.9mX0.9m 0.00	5,374,768	Main
	Bawa Chhara Earthen Dam at Ch.4+400Km (Chhara)	0.094Km 0.00	4,784,166	Main
	Bawa Chhara Check Structure-1 at Ch.3+450Km (Khal)	3 Vent-1.5mX1.2m 0.00	1,766,306	Main
	Bawa Chhara Check Structure-3 at Ch.0+600Km (Khal)	5 Vent-1.5mX1.2m 0.00	3,661,640	Main
	Re-excavation of Bawa Chhara Khal	0.95	508,313	Main
	Bawa Chhara Syphon at 4+400Km (Khal)	0.9mX0.9m 0.00	399,438	Main
	Part-A: Construction of Uuder ground Irrigation pipe line,dr	0.00	6,179,221	PSSWRSP
PSSWRSP				
SP44093, Paschim Joar Subproject, CAD, Union : Koror Hat, HO Date: 10/05/2018				
	Part-C: Construction of Box culvert over lined canal	0.00	411,130	Main
	Part-A: Construction of pump Sump with RCC Foundation	0.00	149,294	Main
	Part-B: Construction of Irrigation lined cannal	0.00	17,445,036	Main
	Part-D: WMCA Office & Others	12mX6m 0.00	1,660,394	Main
SP45203, Sonai Chhara Subproject, DR&WC, Union : Khaiyachhara, HO Date:				
	Part-A: Re-excavation of Sonaichhara Main Khal	2.10	485,274	Main
	Part-F: Construction of Sonaichara Check Structure-3	0.00	2,969,093	Main
	Part-I: WMCA office & others	12mX6m 0.00	1,351,686	Main
	Part-D: Re-excavation of of Sonaichara Branch khal-3	0.43	316,862	Main
	Part-E: Re-excavation of of Sonaichara Branch khal-4	0.40	108,704	Main
	Part-F: Construction of Reference Lined Section	0.00	87,296	Main
	Part-G: Construction of Sonaichara Check Structure-4	0.00	1,924,215	Main
	Part-H: Construction of Sonaichara Check Structure-5	0.00	5,430,302	Main
	Part-C: Re-excavation of of Sonaichara Branch khal-2	0.70	320,524	Main
	Part-B: Re-excavation of of Sonaichara Branch khal-1	0.50	320,524	Main
	Part-B: Construction of Sonaichara spillway (3v-3.0mX2.0m	(3v-3.0mX2.0m) 0.00	10,198,525	Main
	Part-C: Construction of Sonaichara Reservoir Outlet (1v-1.	(1v-1.5mX1.5m) 0.00	11,660,668	Main
	Part-A: Construction of Earthen Dam (L=85m)	(L=85m) 0.00	5,163,047	Main
	Part-D: Construction of Sonaichara Check Structure-1	0.00	1,118,206	Main
	Part-E: Construction of Sonaichara Check Structure-2	0.00	1,121,968	Main
Rangunia				
SSWRDSP-2				
SP24125, Silok Khal Mormor Mukh Subproject, WC, Union : Shilok, HO Date: 22/03/2009				
	Silok Khal Rubber Dam at Ch.0+150Km	Size: 50mX3m 0.00	37,129,871	Main
	O&M Shed	Size: 12mX6m 0.00	365,812	Main
	Procurement of Rubber Bag	0.00	5,805,000	Main
SP25251, Chiringa Khal Subproject, WC, Union : Sarapbhata, HO Date: 19/04/2010				
	Chiringa Khal WRS at Ch.0+300Km (Khal)	6 Vent-1.5mX3.0m 0.00	10,520,491	Main
	O&M Shed	Size: 9mX5m 0.00	366,904	Main
SP25255, Rui Khal Subproject, WC, Union : Pomra, HO Date: 24/03/2010				
	Rui Khal Earthen Dam	180m Length 0.00	840,150	Main
	Rui Khal WRS-3 at Ch. 0+175km (Dam)	1 Vent-0.9mX0.9m 0.00	1,056,404	Main
	Rui Khal Spillway at Ch. 0+455Km (Khal)	5 Vent-3.5mX1.5m 0.00	5,104,910	Main
	Rui Khal WRS-1 at Ch. 0+455km (Khal)	1 Vent-0.9mX0.9m 0.00	2,339,805	Main
	Rui Khal WRS-2 at Ch. 0+020km (Dam)	1 Vent-0.9mX0.9m 0.00	998,218	Main
Rauzan				
SSWRDSP-2				
SP25263, Dabua Khal Subproject, WC, Union : Dabua, HO Date: 18/10/2012				
	Part-B: WMCA Office & Others	12mX6m 0.00	7,230,173	Main
	Part-A: Re-excavation of Dabua Khal (Downstream WRS)	0.60	317,237	Main
	Part-A: Enhancement of the water Retention Structure of D	Size: 9mX5m 0.00	5,209,350	Main
	Part-A: Enhancement of the retention Structure Of Dadua k	0.00	5,209,350	PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: WMCA Office & Others	12mX6m 0.00	7,230,173	PSSWRSP
	Part-A: Re-excavation of Dabua Khal	0.60	318,137	PSSWRSP
Satkania SSWRDSP-2 SP25256, Sonaichhari (Satkania) Subproject, WC, Union : Sonakania, HO Date:				
	Sonaichhari Earthen Dam	150m Length 0.00	786,464	Main
	Sonaichhari Khal WRS	1 Vent-0.9mX0.9m 0.00	3,095,916	Main
	Sonaichhari Khal Spillway Spillway	5 Vent-2.0mX1.5m 0.00	3,752,824	Main
	O&M Shed	Size: 9mX5m 0.00	468,801	Main
	Sonaichhari Khal Irrigation Inlet	1 Vent-0.9mX0.9m 0.00	2,057,550	Main
Sitakunda SSWRDSP-2 SP21006, Chotokumira Subproject, WC, Union : Saidpur, HO Date: 19/07/2006				
	Choto Kumira WRS at Ch.2+700km	3-V(1.50mX2.00m) 0.00	3,999,279	Main
	Rehab. of BWDB's Reg. & Pipe Sluice	3-V & 6-V 0.00	1,019,695	Main
	Re-excavation of Choto Kumira Main Khal	4.35	1,801,069	Main
	Re-excavation of Choto Kumira Br. Khal-1	1.20	153,696	Main
	Re-excavation of Choto Kumira Br. Khal-2	2.15	226,863	Main
SP24171, Sahasradhara Subproject, WC, Union : Baraiyadala, HO Date: 21/04/2013				
	Sahasradhara Dam	55m 0.00	2,184,716	Main
	Re-excavation of Sahasradhara Chhara	5.60	790,337	Main
	Sahasradhara WRS at Ch. 13+4000Km	1 Vent-0.9mX0.9m 0.00	4,432,915	Main
	Sahasradhara Spillway at Ch. 13+4000Km (Sahasradha	3 Vent-3.4mX2.0m 0.00	5,775,619	Main
	Sahasradhara Check Structure-1 at Ch. 6+440Km	3 Vent-1.5mX1.5m 0.00	578,423	Main
	Sahasradhara Check Structure-2 at Ch. 9+300Km	3 Vent-1.5mX1.5m 0.00	582,101	Main
	Sahasradhara Check Structure-3 at Ch. 11+370Km	3 Vent-1.5mX1.5m 0.00	583,189	Main
	O&M Shed	Size: 12mX6m 0.00	346,295	Main
Comilla (Total SPs : 11 Nos.)				
Burichang SSWRDSP-2 SP23091, Kusumpur-Verella-Fultali Subproject, DR, Union : Varellah, HO Date: 11/02/2008				
	Kusumpur-Fultali Main Khal Re-excavation	5.20	1,665,899	Main
	Rampur-Verella Khal Re-excavation	1.85	538,866	Main
Chandina PSSWRSP SP43056, Latifpur- Etbarpur Khal Subproject, DR, Union : Borkoit, Khosbash, Etbarpur, HO				
	Part-A: Re-excavation of Latifpur-Etbarpur Khal	5.30	7,174,432	Main
	Part-A: Construction of Box Culvert	1V-3.0mx3.0m 0.00	4,968,320	Main
	Part-B: Construction of Ref. Lined Section of Khal	0.00	287,872	Main
	Part-B: WMCA office & others	12mx6m 0.00	1,502,651	Main
SP43059, Kedarpur-Gobindapur Subproject, DR&WC, Union : Borkoit, HO Date:				
	Part-A: Re-excavation of Kedarpur-Gobindapur Khal (D/S)	5.80	7,165,528	Main
	Part-D: Construction of Ref. lined section of khal	0.00	324,487	Main
	Part-B: WMCA office & related work	12mx6m 0.00	1,549,915	Main
	Part-A:Kedarpur-Gobindapur Khal WRS	(2v-1.5mX1.8m) 0.00	5,784,644	Main
	Part-B: Re-excavation of Kedarpur-Gobindapur Khal (Main	1.50	1,795,223	Main
	Part-C: Re-excavation of Kedarpur-Gobindapur Khal (U/S)	0.70	923,194	Main
SP45147, Barkarai-Derpar Kaduti Subproject, DR&WC, Union : Barkarai, HO Date:				
	Part-A: Kala khal WRS (4v-1.5mX2.0m) at Ch. 0+250 km	(4v-1.5mX2.0m) 0.00	10,787,453	Main
	Part-H: Re-excavation of Bamonda Bhuari Khal	1.70	371,807	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	1,369,771	Main
	Part-A: Re-excavation of Kala Khal	5.40	4,477,894	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Re-excavation of Noabpur Kala Khal Linked Chane	0.90	433,063	Main
	Part-C: Re-excavation of Bangshidari Gazaria Bamonda Kh	5.30	1,564,988	Main
	Part-D: Re-excavation of Habibuallah Chairman Bari to Nar	1.60	402,110	Main
	Part-E: Re-excavation of Chandshar Tehura Khal	1.82	322,315	Main
	Part-F: Re-excavation of Chandshar Tehura Branch Khal	0.21	60,363	Main
	Part-G: Re-excavation of Fatepur Khal	1.55	479,284	Main
SP45154, Harina Changagachia Sub-Project, DR, Union : Mahichail, HO Date: 24/04/2018				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,371,559	Main
	Part-A: Re-excavation of Keshera Khal	2.67	2,187,956	Main
	Part-B: Re-excavation of Keshera Branch Khal	1.50	251,864	Main
	Part-C: Re-excavation of Gatigara Khal	3.65	2,297,063	Main
	Part-D: Re-excavation of Bamutia Khal	4.00	1,925,509	Main
	Part-E: Re-excavation of Bamutia Brunch Khal	0.64	151,652	Main
	Part-F: Re-excavation of Chengagashia khal	1.91	156,319	Main
	Part-G: Re-excavation of Harina khal	2.07	1,936,989	Main
SP45156, Orain Golicho Noagaon Subproject, DR&WC, Union : 13 No. Joag, HO Date:				
	Part-A: Orain kailine Khal regulator (3v-1.5mX1.8m) at ch.0	(3v-1.5mX1.8m) 0.00	11,621,784	Main
	Part-B: Fakira Khal regulator (1v-1.5mX1.5m) at ch.1+936	(1v-1.5mX1.5m) 0.00	4,610,130	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	1,368,707	Main
	Part-A: Re-excavation of Orain Kailine Khal	5.94	2,430,046	Main
	Part-B: Re-excavation of Gulicho Naogaon Khal	2.45	2,720,258	Main
	Part-C: Re-excavation of Jatassher Deakamta Khal	5.88	2,880,250	Main
SP45190, Nababpur- Kaliarchar Subproject, DR&WC, Union : Dollai Nawabpur, HO Date:				
	Part-A: Nababpur Kaliarchar Khal WRS (3vX1.5mX2.50m)	(3vX1.5mX2.50m) 0.00	10,153,073	Main
	Part-B: WMCA Office & others	12mX6m 0.00	1,470,277	Main
	Part-A: Re-excavation of Nababpur Kaliarchar Khal & Cons	2.56	1,720,097	Main
	Part-B: Re-excavation of Basantapur Kaliarchar Khal & Cor	0.70	678,625	Main
	Part-C: Re-excavation of Surikhola Nababpur Khal & Cons.	1.72	1,318,928	Main
Muradnagar PSSWRSP				
SP45176, Deowra CAD Subproject, CAD, Union : Andikot, HO Date: 18/04/2018				
	Part-A: Construction of Brick Lined Canal no. 01(L=0.70 km	0.00	3,846,250	Main
	Part-B: Construction of Brick Lined Canal no. 02(L=0.70 km	(L=0.70 km) 0.00	3,946,745	Main
	Part-C: Construction of Brick Lined Canal no. 03(L=0.90 km	(L=0.90 km) 0.00	5,387,123	Main
	Part-D: Construction of Box Culvert (1v-2.0mX2.0m) on nol	(1v-2.0mX2.0m) 0.00	921,125	Main
	Part-E: Construction of WMCA Office & Others	12mX6m 0.00	1,367,122	Main
	Part-A: Re-excavation of Nolir Khal	1.13	691,314	Main
	Part-B: Construction of Reference Lined Section	0.00	21,333	Main
SP45177, Dhakshin Trish CAD Subproject, CAD, Union : Nobipur west, HO Date:				
	Part-A: Construction of Irrigation Canal	0.00	3,373,140	Main
	Part-B: Construction of Proposed Check Structure Canal	0.00	430,096	Main
	Part-C: Construction of WMCA Office & others	12mX6m 0.00	1,368,204	Main
	Part-A: Re-excavation to Deir Khal and Construction of Ref	0.00	0	Main
Nangolkot SSWRDSP-2				
SP23062, Kulakani Subproject, FM, Union : Raykot, HO Date: 21/04/2009				
	Kulakhani Regulator at Ch.0+257Km(Emb)	2 Vent-1.50mX1.80m 0.00	4,719,090	Main
	O&M Shed	9.00mX5.00m 0.00	290,336	Main
	Embankment Re-sectioning (Kharghar-Sharifpur)	1.55	682,164	Main
	Embankment Re-sectioning (Kharghar-West Kharghar)	1.50	257,151	Main
SP23065, Chukuri-Mokimpur Subproject, FMD, Union : Dhalua, HO Date: 16/03/2009				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Embankment Re-sectioning	1.13	1,600,270	Main
	Chukuri-Mokimpur Khal Regulator at Ch.0+405 km	2 Vent-1.50mX1.80m 0.00	3,540,528	Main
	O&M Shed	9.00mX5.00m 0.00	263,900	Main
	Chukuri-Mukimpur Khal Re-excavation	0.94	181,603	Main
	Mukimpur Br. Khal Re-excavation	1.89	229,632	Main
	Mukimpur Sub Br. Khal Re-excavation	0.49	35,166	Main
	Kinara Sub Br. Khal Re-excavation	0.35	21,209	Main
Coxs Bazar (Total SPs : 23 Nos.)				
Chakoria				
SSWRDSP-2				
SP23097, Khutakhali Chhara Subproject, WC, Union : Khutakhali, HO Date: 10/12/2007				
	Procurement of Rubber Bag	0.00	4,054,000	Main
	Resectioning of Approach	0.08	314,138	Main
	Khutakhali Chhara Rubber Dam	25.00mX3.00m 0.00	23,080,746	Main
	O&M Shed	9.00mX5.00m 0.00	300,000	Main
	Part-A: Construction of Lined Canal with sump & platfrom L	L=240m 0.00	597,305	PSSWRSP
	Part-B: Construction of Lined Canal with sump & platfrom L	L=450m 0.00	1,108,855	PSSWRSP
	Part-C: Construction of Lined Canal with sump & platfrom L	L=404m 0.00	995,186	PSSWRSP
	Part-D: Construction of Lined Canal with sump & platfrom L	L=400m 0.00	968,644	PSSWRSP
	Part-E: Construction of Lined Canal with sump & platfrom L	L=200m 0.00	483,909	PSSWRSP
PSSWRSP				
SP42021, Fasiakhali Irrigation Subproject, CAD, Union : Fasiakhali, HO Date: 29/06/2016				
	Part-D: WMCA office & others	12mx6m 0.00	2,027,940	Main
	Part-A: Ferro Cement Canal & Pumping Platform	2.9km 0.00	8,255,695	Main
	Part-B: Aquiduct	Length: 6.6m 0.00	76,722	Main
	Part-C: Pipe Culvert	Length: 5m 0.00	139,693	Main
	Part-E: Box Culvert	2 Nos. 0.00	782,527	Main
SP44124, Sonaichari Subproject, DR&WC, Union : Boroitali, HO Date: 03/12/2018				
	Part-A: Construction of Sonaichari Khal WRS-1	(5v-1.50mX1.80m) 0.00	0	Main
	Part-B: Construction of Sonaichari Khal WRS-2	(5v-1.50mX1.80m) 0.00	0	Main
	Part-C: Construction of WMCA Office & others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Sonaichri khal	12.80	2,786,434	Main
	Part-B: Construction of Reference Lined Section	0.00	75,674	Main
SP46262, Boalia Chhara Subproject, WC, Union : Sujapur Manikpur, HO Date:				
	Part-A: Construction of Rubber Dam With Bridge Deck (20)	0.00	41,837,719	Main
	Part-B: Construction of Pump House & Guard shed	0.00	1,409,576	Main
	Part-C: Irrigation Lined Canal l=1200m	0.00	7,512,943	Main
	Part-D: WMCA Office & others	0.00	1,414,437	Main
Moheshkhali				
SSWRDSP-2				
SP23059, Barunaghat Khal Subproject, DR&WC, Union : Gorakghata, Chhoto Moheshkhali,				
	Barunaghat Khal Re-excavation	3.42	839,106	Main
	Barunaghat Khal Regulator at Ch.0+000Km (Khal)	3 Vent-1.50mX1.80m 0.00	5,029,325	Main
	Re-sectioning of Barunaghat Regulator Approach	0.49	259,809	Main
Pekua				
SSWRDSP-2				
SP23098, Tetang-Sonaichari Khal Subproject, WC, Union : Tetong, HO Date: 24/01/2010				
	Tetang Sonaichari Khal Rubber Dam	28.00mX4.00m 0.00	32,266,794	Main
	Procurement of Rubber Bag	0.00	5,471,000	Main
	Part-A: Construction of irrigation Drain	1050 m 0.00	2,956,979	PSSWRSP
	Part-B: Development of road by HBB	60m 0.00	671,149	PSSWRSP

Ramu

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SSWRDSP-2				
SP22040, Sonaichhari (Ramua) Subproject, WC, Union : Joarinala, HO Date: 02/09/2007				
	Rubber Dam at Illisipara	1-V(30.00mX3.00m) 0.00	15,879,691	Main
	O&M Shed	12.00mX6.00m 0.00	357,538	Main
	Rubber Bag Procurement	0.00	3,422,449	Main
	Part-A: Construction of U-Drain	700 m 0.00	2,269,489	PSSWRSP
	Part-B: Construction of Approach road	75m 0.00	338,738	PSSWRSP
SP23096, Borojung Chhari Subproject, WC, Union : Kachhapia, HO Date: 26/11/2008				
	Baro Jungchari Rubber Dam	28mX4.0m 0.00	23,784,221	Main
	Procurement of Rubber Bag	0.00	5,399,600	Main
	Part-A: Constructon of U-Drain	l=733m 0.00	2,379,663	PSSWRSP
	Part-B: Constructon of Approach road	0.00	402,574	PSSWRSP
	Part-C: WMCA Office & Others	12mx6m 0.00	1,366,093	PSSWRSP
	Part-D: Earth work of Left and Right	0.00	390,956	PSSWRSP
SP25244, Choto Jungchhari Subproject, WC, Union : Kachhapia, HO Date: 30/06/2009				
	Chhoto Jungchari WRS at Ch.4+80Km	8 Vent-1.5mX2.1m 0.00	11,954,080	Main
	O&M Shed	Size: 9mX5m 0.00	400,000	Main
	Resectioning of Right Bank Dyke	1.00	350,769	Main
	Resectioning of Left Bank Dyke	1.00	293,912	Main
	Resectioning of WRS Approach	0.06	296,319	Main
SP25253, Kaimmergona-Katakhal Subproject, WC, Union : Dakkhin Mithachar, HO Date:				
	Paglir Chhara WRS at Ch. 0+300Km	5 Vent-1.5mX2.0m 0.00	7,424,159	Main
	Chaidar Chhara WRS at Ch. 0+000Km	5 Vent-1.5mX2.0m 0.00	6,717,422	Main
	Resectioning of Left Embankment	0.17	272,310	Main
SP25265, Bara Garjai Khal Subproject, WC, Union : 2 no. Garzania, HO Date: 31/08/2009				
	O&M Shed	Size:9mX5m 0.00	338,021	Main
	Pipe Sluice at Ch. 1+300Km	1 Vent-0.9m Dia 0.00	688,900	Main
	Bara Garjai Khal Weir at Ch. 0+300Km (Khal)	9 Vent-3mx1.5m+1	15,920,799	Main
	Re-sectioning of Bara Garjai Khal Dyke	1.05	682,559	Main
	Re-excavation of Irrigation Sub Branch Khal	0.50	107,305	Main
	Resectioning of WRS Approach	0.07	179,278	Main
PSSWRSP				
SP43051, Monirjheel-Sonaichari Khal Subproject, WC, Union : Kaoerkhop, HO Date:				
	Part-A: Monirjhil Rubber Dam with connecting Bridge, pumj	20mX3.5m 0.00	51,682,281	Main
	Part-B: WMCA office & others	12mx6m 0.00	1,949,746	Main
SP45159, Paner chhara Purbakul Khal Subproject, WC, Union : Dakshin Mitachhari, HO				
	Part-A: Construction of Paner Chhara WRS	(4V-1.5mX2.0m) 0.00	12,536,462	Main
	Part-B: Construction of WMCA Office & Others	12mX6m 0.00	507,582	Main
	Part-A: Construction of dykes on both banks of paner Char:	2.30	210,588	Main
Rubber Dam				
SP97002, Idgaon River Rubber Dam Project, WC, Union : Idgaon, HO Date:				
	Idgaon Rubber Dam	Size: 52mX3m 0.00	18,000,000	Main
Sadar				
SSWRDSP-2				
SP21007, Bakkhali Subproject, WC, Union : Jhilwanja,PM Khali, HO Date: 12/12/2007				
	Rehabilitation of WRS(Rubber Dam)	1-V(87.0mX3.5m) 0.00	22,994,139	Main
	U/S & D/S Cross-Dam and Bank Protection Works	0.00	3,383,537	Main
SP23085, Sonkhola Subproject, FMD, Union : P.M.Khali, HO Date: 14/09/2008				
	Embankment Re-sectioning	0.59	181,472	Main
	Sonkhola Khal Regulator at Ch.0+460Km(Khal)	2 Vent-1.50mX1.80m 0.00	3,810,672	Main
	O&M Shed	9.00mX5.00m 0.00	294,061	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Para Khal Re-excavation	2.99	257,928	Main
	Daser Khal Re-excavation	1.35	137,305	Main
	Embankment Re-sectioning (Part-2)	1.42	0	Main
	Re-sectioning of Embankment	2.08	1,466,000	PSSWRSP
SP25245, Chaufaldandi Subproject, WC, Union : Chaufal Dandi, HO Date: 24/03/2011				
	Re-excavation of Bargoda Khal	2.00	221,965	Main
	Zia Khal Regulator at Ch.2+405Km (Zia Khal)	2 Vent-1.5mX1.8m 0.00	4,723,392	Main
	Re-excavation of Zia Khal-2	2.00	268,329	Main
	Re-excavation of Chikon Khal	1.20	94,794	Main
	Part-A: Construction of Pipe Sluice	(1v-900 mm dia) 0.00	2,074,339	PSSWRSP
	Part-A: Re-excavation of Valuaguri Khal	0.06	93,712	PSSWRSP
	Part-B: Re-section of Embankment	0.20	433,542	PSSWRSP
PSSWRSP				
SP43045, Pokkhali-Naikhongdia Subproject, WC, Union : Pokkhali, HO Date: 25/06/2018				
	Part-A: Pokkhali Rubber Dam connecting Bridge, pump ho	40mx4m 0.00	86,209,964	Main
	Part-B: WMCA office & others	12mx6m 0.00	1,631,910	Main
Teknaf				
PSSWRSP				
SP45158, Raikhong Khal Subproject, DR&WC, Union : Howaikang, HO Date: 26/06/2018				
	Part-A: Raikhong Khal WRS (4V-1.5mX2.0m)	(4V-1.5mX2.0m) 0.00	12,307,041	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	762,434	Main
Ukhia				
SSWRDSP-2				
SP25252, Paglir Beel-Sikderpara subproject, WC, Union : Halodia Palong, HO Date:				
	Rubber Dam over Rezu Khal at 135m U/S from confl.	Size:30mX3m 0.00	24,410,919	Main
	O & M Shed	Size: 9mX5m 0.00	414,712	Main
	Procurement of Rubber Bag	0.00	5,000,000	Main
	Part-A: Construction of Drain Culvert	0.00	108,026	PSSWRSP
	Part-B: Construction of Lined Canal wit sump & platform.30	at Ch. 0+000 km to 0+300 k	766,008	PSSWRSP
	Part-C: Construction of Lined Canal wit sump & platform.40	0+000 km to 0+400 km 0.00	1,017,473	PSSWRSP
	Part-D: Construction of Ruber dam Road .695 km	at Ch.0+000 km to 0+695 km	2,330,340	PSSWRSP
PSSWRSP				
SP43046, Thim Chari-Purbakul Subproject, WC, Union : Ratna Palong, HO Date:				
	Part-A: Rubber Dam 20m	20mX3.5m 0.00	35,250,511	Main
	Part-D: WMCA office & others	12mx6m 0.00	1,183,305	Main
	Part-B: Pump house and Guar shed	0.00	1,608,772	Main
	Part-C: Foot Bridge 21m	21m 0.00	1,132,683	Main
SP43047, Paschim Digulia Subproject, WC, Union : Raja Palong, Ratna Palong, HO Date:				
	Part-A: Paschim Digulia Rubber Dam with Rubber bag	30.00mx3.50m 0.00	50,097,138	Main
	Part-C: WMCA office & others	12mx6m 0.00	1,622,662	Main
	Part-B: Pump house & Guard shed	0.00	1,681,637	Main
SP45151, Harinmara-Dhusri Khal Subproject, WC, Union : Raja Palong, HO Date:				
	Part-A:- Construction of Harinmara Dusrikhal Rubber Dam	25.0mX3.0m 0.00	42,989,751	Main
	Part-B:- Construction of Pump House	0.00	534,586	Main
	Part-C:- Construction of Rubber Dam connecting foot Bridg	0.00	2,206,402	Main
	Part-D:- Construction of WMCA Office & Others	12mX6m 0.00	1,116,893	Main
Feni (Total SPs : 3 Nos.)				
Dagonbhuyan				
PSSWRSP				
SP44089, Shindurpur Sekanderpur Subproject, DR&WC, Union : Shindurpur, HO Date:				
	Part-C: Re-sectioning of Embankment	2.51	2,587,622	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: Re-excavation of Jailla Khal	0.51	170,802	Main
	Part-B: Re-excavation of Kuchimura Khal	1.35	199,936	Main
	Part-A: Construction of Jailla Khal Regulator	at Ch. 0+098 km 0.00	7,195,315	Main
	Part-B: Construction of Kuchimura Khal Regulator	at Ch. 0+935 km 0.00	6,658,738	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	1,876,584	Main
	Part-D: Construction of Reference Lined Section	0.00	29,724	Main

Sadar
PSSWRSP
SP46228, Abupur Subproject, DR&WC, Union : Sarshadi, HO Date: 17/09/2017

Part-A: WRS (4v-1.5mX1.8m)	(4v-1.5mX1.8m) 0.00	0	Main
Part-B: Box Culvert (2v-4.0mX4.5m)	(2v-4.0mX4.5m) 0.00	0	Main
Part-C: WMCA Office & Others	12mX6m 0.00	0	Main
Part-A: Re-excavation of Boro Chora khal	3.00	2,712,969	Main
Part-B: Re-excavation of South Abupur khal	1.75	2,185,874	Main
Part-C: Re-excavation of Hotu chara khal	0.70	458,802	Main
Part-D: Construction of Embankment	1.38	2,410,359	Main
Part-E: Construction of Reference lined Section	0.00	129,709	Main

Sonagazi
PSSWRSP
SP46260, Badarmokan Khal, DR&WC, Union : Motigonj, HO Date: 21/05/2018

Part-A: Construction of WRS	4v-1.50mX1.80m 0.00	13,771,748	Main
Part-G: Construcion of Reference Lined Section	0.00	208,717	Main
Part-B: Construction of Checked structure	0.00	2,805,529	Main
Part-C: Construction of WMCA Office and Others	12mX6m 0.00	1,453,423	Main
Part-A: Re-excavation of Badar Mokam Khal	9.00	10,450,470	Main
Part-B: Re-excavation of Badar Mokam Branch-1 Khal	1.00	914,748	Main
Part-C: Re-excavation of Badar Mokam Branch-2 Khal	1.50	472,502	Main
Part-D: Re-excavation of Badar Mokam Branch-3 Khal	4.20	5,349,446	Main
Part-E: Re-excavation of Kacchaibba Khal	1.30	1,675,980	Main
Part-F: Re-excavation of Tirikkha Pathar Khal	0.75	197,500	Main

Khagrachari (Total SPs : 1 Nos.)

Panchari
Rubber Dam
SP99007, Chengi River Rubber Dam Project, WC, Union : , HO Date:

Chengi River Rubber Dam	Size: 80mX4m 0.00	123,622,000	Main
-------------------------	-------------------	-------------	------

Laxmipur (Total SPs : 17 Nos.)

Raipur
PSSWRSP
SP44132, Dakkhin Char Ababil Subproject, DR&WC, Union : South Char Ababil, HO Date:

Part-A: Irrigation Water Supply Brick Canal	0.00	0	Main
Part-D: Re-excavation of E2A khal (Kamarbarir Khal)	2.80	1,648,556	Main
Part-E:Construction of Reference Lined Section	0.00	333,281	Main
Part-B: Box Culvert-1 (1V-3.00mX3.00m)	(1v-3.00mX3.00m) 0.00	0	Main
Part-C: Box Culvert-2 (1V-3.00mX3.5m)	(1v-3.00mX3.5m) 0.00	0	Main
Part-D: Box Culvert-3 (2V-3.00mX3.00m)	2v-3.00mX3.00m) 0.00	0	Main
Part-E: Box Culvert-4 (1V-2.50mX3.50m)	(1v-2.50mX3.50m) 0.00	0	Main
Part-F: WMCA Office & Others	12mX6m 0.00	0	Main
Part-A: Re-excavation of D2B khal	1.90	1,398,052	Main
Part-B: Re-excavation of D1 khal(Dewanbarir khal)	4.75	3,108,701	Main
Part-C: Re-excavation of E2 khal (Chowdhuribarir Khal)	3.00	2,697,177	Main

Ramganj
SSWRDSP-2

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP23103, Katakhal Khal Subproject, DR&WC, Union : Kanchanpur, HO Date: 23/07/2009				
	Katakhal Khal WRS at Ch.0+000	Katakhal Khal WRS at	4,440,183	Main
	Katakhal-Naogaon Khal Re-excavation	2.98	958,031	Main
	Katakhal-Joypura Khal Re-excavation	4.18	531,090	Main
Sadar SSWRDSP-2				
SP22016, Purba Syedpur Subproject, WC, Union : Char Shahi, HO Date: 07/07/2009				
	WRS at Ch.0+075 km	5-V(1.5mX3.0m) 0.00	7,275,120	Main
	Closure	0.02	16,183	Main
	Kachua Khal (U/S Part) Re-excavation	3.07	2,429,216	Main
	Kachua Khal (D/S Part) Re-excavation	1.35	2,236,186	Main
	Kazir Zorah Khal Re-excavation	1.80	844,591	Main
	Tie Embankment Re-sectioning	0.04	42,443	Main
SP23090, Bhuluar Khal Subproject, WC, Union : Bhabanigonj, HO Date: 26/07/2009				
	Bhulur Khal WRS at Ch.1+450 Km (Khal)	5 Vent-1.50mX1.80m 0.00	6,921,988	Main
	O&M Shed	9.00mX5.00m 0.00	375,082	Main
	Bhulur Khal Re-excavation	0.92	471,046	Main
	Horakhali Khal Re-excavation	3.50	1,075,335	Main
	Musar Khal Re-excavation	3.90	2,161,001	Main
	Zillur Rahim Khal Re-excavation	4.00	2,231,995	Main
	Re-sectioning of Approach Embankment	0.09	256,783	Main
SP24141, Goaliar Dogi Subproject, CAD, Union : Dighli, HO Date: 30/06/2009				
	Header Tank	Size: 6.1mX2.6m 0.00	193,614	Main
	Burried Pipe Networks System	Length: 6.45Km 0.00	10,349,749	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	330,635	Main
	Construction of 910 RCC Buried pipes	910,15,7 nos, 150m 0.00	4,992,354	PSSWRSP
SP25216, Mandari-Gondharbapur Subproject, WC, Union : Mandari, HO Date: 14/10/2009				
	Manik Poddar Khal WRS at Ch.0+050 km	1 Vent-1.5mX2m 0.00	4,067,077	Main
	Mandari-Gondobbyapurb Khal WRS at Ch.0+075 km	2 Vent-1.5mx2m 0.00	4,046,690	Main
	Re-excavation of Mandari-Gondharbapur Khal	3.64	1,102,619	Main
	Re-excavation of Manik Poddar Khal	2.70	943,466	Main
SP25233, Agrani-Dighali-Gandharbapur Subproject, CAD, Union : Mandari, HO Date:				
	Header Tank	Size: 6.1mX2.6m 0.00	299,133	Main
	Buried Pipe Network System	6950m 0.00	12,053,559	Main
	O&M Shed	Size: 9mX5m 0.00	341,114	Main
	Construction of 1277 nos RCC Buried Pipe Joints	0.00	8,357,645	PSSWRSP
SP25300, Ramkrishnapur-Dewpara Subproject, CAD, Union : Chandraganj, HO Date:				
	Header Tank	Size: 6.1mX3.0m 0.00	574,317	Main
	Burried Pipe Irrigation Networks System	0.00	6,218,028	Main
SP25301, Latifpur-Panchpara Subproject, CAD, Union : Chandraganj, HO Date:				
	Header Tank	Size: 6.1mX3.0m 0.00	626,809	Main
	Burried Pipe Irrigation System	6294 m Length 0.00	12,595,880	Main
SP25304, Ganipur-Rajapur Subproject, CAD, Union : Chandraganj, HO Date: 11/03/2013				
	Header Tank	Size: 6.1mX3.0m 0.00	659,242	Main
	Burried Pipe Irrigation Networks	4370 m Length 0.00	7,162,163	Main
PSSWRSP				
SP43065, Bhanga kha-Niyamatpur Subproject, WC,DR&IRR, Union : Bhanga kha, HO				
	Part-A: Re-excavation of Bhangakhan Khal-1	2.23	795,225	Main
	Part-A: Construction of (Hatibandha (HK) Lined Canals-1,2	0.00	8,018,556	Main
	Part-B: Gate of Cheak Gates, Turn outs and precast RCC r	0.00	243,480	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-C: Construction of 12m Foot Bridge-1 Bhangakhan kh	0.00	893,402	Main
	Part-D: Construction of 10m Foot Bridge-2 Bhangakhan kh	0.00	864,421	Main
	Part-E: Construction of 10m Foot Bridge-3 Mohespur khal-	0.00	900,877	Main
	Part-F: WMCA Office & Others	12mX6m 0.00	1,387,431	Main
	Part-B: Re-excavation of Bhangakhan Khal-2	2.10	3,886,334	Main
	Part-C: Re-excavation of Mohespur Khal	1.50	208,414	Main
	Part-D: Re-excavation of Chagolehra Khal	2.50	985,196	Main
	Part-E: Reference sections & BM post (8 nos.)	0.00	272,202	Main
SP43073, Tumchar-Kalirchar Subproject, WC,DR&IRR, Union : Shakchar, HO Date:				
	Part-A: Re-excavation of Tumchar-Kalichar khal	1.80	1,994,061	Main
	Part-B: Construction of Ferro Cement pucca field channel	0.00	5,013,179	Main
	Part-A: Construction of Tumchar khal WRS	2V-1.2mx1.5m 0.00	7,419,144	Main
	Part-C: WMCA office & others	12mx6m 0.00	1,363,226	Main
	Part-B: Construction of Reference Lined Section	0.00	115,378	Main
SP44100, Dighuli kathali Subproject, WC, Union : Dighli, HO Date: 15/05/2018				
	Part-A: Construction of Gokuler khal Regulator	3V-15mX1.8m 0.00	10,233,399	Main
	Part-B: WMCA Office & others	12mx6m 0.00	1,453,551	Main
	Part-A: Re-excavation of Gokuler Khal	6.20	9,535,486	Main
	Part-B: Re-excavation of Purba Dighuli Khal	1.78	1,127,258	Main
	Part-C: Re-excavation of Pachim Dighuli Khal	0.81	536,499	Main
	Part-D: Re-excavation of Uttar Kathali Khal	0.68	326,105	Main
SP44128, Gorur Khal Subproject, CAD, Union : Char Ramani Mohon, HO Date: 19/09/2018				
	Part-A: Irrigation Water supply Brick Canal	0.00	7,388,997	Main
	Part-B:Garur Khal WRS	2v-1.50mX1.80m 0.00	7,696,698	Main
	Part-C: WMCA Office & others	12mX6m 0.00	1,676,273	Main
	Part-A: Re-excavation of Garur Khal	3.85	5,762,313	Main
	Part-B: Construction of Reference Lined Section	0.00	111,970	Main
SP45162, Pukurdia-Naldugi Subproject, DR&IRR, Union : Kushakhali, HO Date:				
	Part-A: porakhali Khal Regulator at Ch. 6+870km (2v-1.50n	(2v-1.50mX1.80m) 0.00	0	Main
	Part-B: Detail Estimate Brick Irrigation Canal	0.00	0	Main
	Part-C: WMCA Office & Others	0.00	0	Main
	Part-A: Re-excavation of Porakhali khal	6.83	5,446,849	Main
	Part-B: Construction of Reference Lined Section	0.00	294,337	Main
SP45202, Ramanadi-Kutubpur Subproject, CAD, Union : Laharkandi, HO Date: 11/04/2018				
	Part-A: Errigation Line Canal-1, Length-.450 km	Length-.450 km 0.00	1,578,270	Main
	Part-J: Road Crossing (MC-5)	0.00	98,798	Main
	Part-K: WMCA Office & Others	12mX6m 0.00	1,368,754	Main
	Part-B: Errigation Line Canal-2, Length-.600 km	Length-.600 km 0.00	2,231,083	Main
	Part-C: Errigation Line Canal-3, Length-.650 km	Length-.650 km 0.00	2,229,277	Main
	Part-D: Errigation Line Canal-4, Length-.750 km	Length-.750 km 0.00	2,698,885	Main
	Part-E: Errigation Line Canal-5, Length-.800 km	Length-.800 km 0.00	2,966,198	Main
	Part-F: Road Crossing (MC-1)	0.00	53,966	Main
	Part-G: Road Crossing (MC-2)	0.00	53,912	Main
	Part-H: Road Crossing (MC-3)	0.00	2,032,005	Main
	Part-I: Road Crossing (MC-4)	0.00	63,619	Main
SP46264, Char Bhuta Hatem Ali Subproject, CAD, Union : Bhobanigonj, HO Date:				
	Part-A:Construction of RCC Irrigation Canal-ZKL1	0.00	823,861	Main
	Part-J:Construction of RCC Irrigation Canal-ZKL11	0.00	0	Main
	Part-K:Construction of WMCA office and others	12mX6m 0.00	1,450,852	Main
	Part-A:Re-excavation of Zia Khal and Reference Lined Sec	5.11	8,492,319	Main
	Part-B:Re-excavation of Mora Musa Khal and Reference Li	4.00	4,277,659	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B:Construction of RCC Irrigation Canal-ZKL2	0.00	826,677	Main
	Part-C:Construction of RCC Irrigation Canal-ZKL3	0.00	1,021,000	Main
	Part-D:Construction of RCC Irrigation Canal-ZKL5	0.00	628,319	Main
	Part-E:Construction of RCC Irrigation Canal-ZKL6	0.00	824,168	Main
	Part-F:Construction of RCC Irrigation Canal-ZKL7	0.00	1,016,616	Main
	Part-G:Construction of RCC Irrigation Canal-ZKL8	0.00	823,475	Main
	Part-H:Construction of RCC Irrigation Canal-ZKL9	0.00	825,522	Main
	Part-I:Construction of RCC Irrigation Canal-ZKL10	0.00	633,402	Main

Noakhali (Total SPs : 11 Nos.)

Begumganj
PSSWRSP

SP44119, Banglabazar-Gopalpur Subproject, WC, Union : Gopalpur, HO Date: 17/08/2016

Part-A: Construction of Regulator	(4v-1.5mX1.8m) 0.00	13,634,020	Main
Part-B: Construction of pump Platform	Ch.0+015 km khal 0.00	56,981	Main
Part-C: Construction of WMCA Office & Others	12mX6m 0.00	1,644,997	Main
Part-A: Re-excavation of Goplapur -Shahadapur Khal	4.59	3,964,082	Main
Part-B: Re-excavation of Bashantobag-Chand Kashimpur k	1.10	318,316	Main
Part-C: Re-excavation of Atiyakandi-Ramnathpur Khal	0.74	72,686	Main
Part-D: Re-excavation of Kalikapur-Titahajira-Sonarapur Kh	1.00	416,351	Main
Part-E: Construction of Reference Lined Section	0.00	241,491	Main

SP45213, Fanaghata Rajullhpur khal, DR&WC, Union : Jirtaly, HO Date: 10/06/2018

Part-A: WRS (2v-1.2mX1.8m)	(2v-1.2mX1.8m) 0.00	7,604,411	Main
Part-B: WRS (2v-1.5mX2.0m)	(2v-1.5mX2.0m) 0.00	8,677,208	Main
Part-C: WRS (2v-1.2mX1.8m)	(2v-1.2mX1.8m) 0.00	6,339,148	Main
Part-D: WMCA Office & others	12mX6m 0.00	1,598,500	Main
Part-A: Re-excavation of Fenaghata-Rajullahpur	10.45	8,103,106	Main
Part-B: Re-excavation of Naimuddin Branch-1 khal	1.20	873,516	Main
Part-C: Re-excavation of Naimuddin Branch-2 khal	2.50	2,905,792	Main
Part-D:Constrauction of Reference Lined section	0.00	358,541	Main

Companiganj
PSSWRSP

SP45210, Char Parbati Subproject, DR&WC, Union : Charparboti, HO Date: 22/04/2018

Part-A: Construction of WRS-01 (3v-1.5mX1.8m)	(3v-1.5mX1.8m) 0.00	10,896,736	Main
Part-F: Re-excavation of Dhora Branch khal	0.50	459,821	Main
Part-G: Constrction of Reference Lined Section	0.00	329,153	Main
Part-B: Construction of WRS-02 (1v-1.5mX1.8m)	(1v-1.5mX1.8m) 0.00	5,369,744	Main
Part-C: Construction of Box Culvert	0.00	1,592,490	Main
Part-D: Construction of WMCA office & others	12mX6m 0.00	1,332,461	Main
Part-A: Re-excavation of Sattariar khal	0.87	1,191,519	Main
Part-B: Re-excavation of Dadnar khal	3.60	2,397,000	Main
Part-C: Re-excavation of Berir khal	2.68	1,852,501	Main
Part-D: Re-excavation of Dhora khal	3.11	1,527,444	Main
Part-E: Re-excavation of Bata khal	1.64	982,450	Main

SP46215, Char kakra Subproject, DR&WC, Union : Charkakra, HO Date: 12/06/2018

Part-A: WRS (3v-1.5mX1.8)	(3v-1.5mX1.8) 0.00	8,581,134	Main
Part-B: Construction of link road from UP Building to WMC/	0.00	7,242,717	Main
Part-C: Construction of cross drainage structure on link roa	0.00	223,065	Main
Part-D: WMCA office & others	12mX6m 0.00	2,413,619	Main
Part-A: Re-excavation of Chaprashir khal	1.25	1,547,703	Main
Part-B: Re-excavation of Chaprashir (Upper eastern) khal	7.50	1,258,258	Main
Part-C: Re-excavation of purba char kakra Main (3.27 km)	5.20	311,322	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP46218, Char Fakira Sub-project, DR&WC, Union : Char Fakira, HO Date: 12/06/2018	Part-D: Construction of Reference Lined Section	0.00	200,983	Main
	Part A: Chaprashshi Khal Regulator (5v - 1.5m X 1.8m)	(5v - 1.5m X 1.8m) 0.00	15,328,929	Main
	Part B: Jalia Khal Regulator (3v - 1.5m X 1.5m)	(3v - 1.5m X 1.5m) 0.00	8,723,004	Main
	Part C: Construction of WMCA office & Others	12m X 6m 0.00	1,408,654	Main
	Part A: Re-excavation of Chaprashshi Khal	9.90	10,766,611	Main
	Part B: Re-excavation of Jalia Khal	5.00	3,859,892	Main
	Part C: Re-excavation of DB Khal	1.10	1,504,208	Main
	Part D: Re-excavation of Logi Banga Khal	2.06	1,383,403	Main
SP46223, Musapur Sub-project, DR&WC, Union : Musapur, HO Date: 27/06/2018	Part E: Construction of Reference Link Section	0.00	473,566	Main
	Part A: Gusto Khal WRS (2v-1.50m X 1.80m)	(2v-1.50m X 1.80m) 0.00	6,521,064	Main
	Part E: Re-excavation of Nagordona Khal	0.85	1,239,700	Main
	Part F: Re-excavation of Rongmala Khal	2.10	3,509,103	Main
	Part G: Re-excavation of Bhuiyar Khal	2.63	2,642,689	Main
	Part H: Re-excavation of Bhuiyar Link Khal	0.67	933,163	Main
	Part I: Construction of Reference Linked Section	0.00	347,014	Main
	Part B: Bangla Bazar Khal WRS (2v-1.50m X 1.80m)	(2v-1.50m X 1.80m) 0.00	10,970,787	Main
	Part C: Bhuiyan Khal WRS (2v-1.50m X 1.80m)	(2v-1.50m X 1.80m) 0.00	5,051,600	Main
	Part D: Pamping Platform & Sump.	0.00	66,041	Main
	Part E: Construction of WMCA office & Others	12m X 6m 0.00	1,408,654	Main
	Part A: Re-excavation of Bangla Bazar Khal	4.37	1,267,814	Main
	Part B: Re-excavation of Gusto Khal	3.70	2,531,486	Main
	Part C: Re-excavation of Gusto Link Khal	0.89	1,041,852	Main
	Part D: Re-excavation of Gusto Branch Khal	0.20	169,933	Main
SP46233, Char Hazari Sub-project, DR&WC, Union : Char Hazari, HO Date: 27/06/2018	Part-A: WRS (4v-1.5mX1.8m)	(4v-1.5mX1.8m) 0.00	15,121,765	Main
	Part-E: Re-excavation of Madhu Branch-2 Khal	1.00	1,236,621	Main
	Part-F: Re-excavation of Madhu Branch-3 Khal	0.50	411,553	Main
	Part-G: Re-excavation of Masterbari Khal	1.13	1,410,321	Main
	Part-H: Re-excavation of chaprashshi Khal	1.67	1,258,628	Main
	Part-I: Construction of Reference Lined Section	0.00	425,217	Main
	Part-B: WRS (1v-1.5mX1.8m)	(1v-1.5mX1.8m) 0.00	7,306,387	Main
	Part-C: WRS Modification (1v-1.5mX1.8m)	(1v-1.5mX1.8m) 0.00	718,500	Main
	Part-D: Pumping platform & sump	0.00	101,765	Main
	Part-E: WMCA Office & others	12mX6m 0.00	1,516,537	Main
	Part-A: Re-excavation of Sattaria Khal	1.84	2,446,816	Main
	Part-B: Re-excavation of Machuadona Khal	7.90	12,424,052	Main
	Part-C: Re-excavation of Madhu main Khal	2.36	2,550,200	Main
	Part-D: Re-excavation of Madhu Branch-1 Khal	0.80	666,225	Main
SP46269, Rampur Subproject, DR&WC, Union : Rampur, HO Date: 12/06/2018	Part-A: Construction of Regulator	4v - 1.5mX1.5m 0.00	14,451,235	Main
	Part-D: Re-excavation of Joinal Khal	2.21	180,093	Main
	Part-E: Construction of Reference Lined Section	0.00	290,815	Main
	Part-B: Construction of Regulator	1v - 1.2mX1.5m 0.00	3,887,290	Main
	Part-C: Construction of Culvert	2v - 4.5mX5.0m 0.00	4,425,652	Main
	Part-D: Construction of Culvert	2v - 4.5mX4.5m 0.00	3,753,056	Main
	Part-E: Construction of Culvert	2v - 4.5mX4.5m 0.00	4,593,211	Main
	Part-F: Construction of WMCA Office and others	12m X 6m 0.00	1,594,245	Main
	Part-A: Re-excavation of Sara Khal	8.40	4,967,741	Main
	Part-B: Re-excavation of Bancharam Khal	5.38	1,192,918	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Sadar SSWRDSP-2 SP46270, Sirajpur Subproject, DR&WC, Union : Sirajpur, HO Date: 24/04/2018	Part-C: Re-excavation of Rampur Khal	3.80	1,398,345	Main
	Part-A: Construction of Gabadia basurhat khal WRS (2v-1.1	(2v-1.5mX1.8m) 0.00	8,136,213	Main
	Part-A: Construction of WMCA Office & Others	0.00	1,380,208	Main
	Part-A: Re-excavation Gahadia Basurhat khal	3.83	2,939,588	Main
	Part-B: Re-excavation of Snakar Bangshi Khal	3.50	1,345,341	Main
	Part-C: Re-excavation of Pudrba Chaprashir khal	2.20	2,574,266	Main
	Part-D:Construction of Reference Lined Section	0.00	196,949	Main
Sonaimuri PSSWRSP SP25317, Gobadia-Buraburi Khal Subproject, WC, Union : Newajpur, HO Date: 21/03/2011	Re-excavation of Jadumoni Khal	3.15	965,542	Main
	Re-excavation of Shantar Khal	6.00	2,804,143	Main
	Jadumoni Khal WRS	10 Vent-1.5mX2.3m 0.00	7,529,022	Main
	Shantar Khal WRS	4 Vent-1.5mX2.00m 0.00	3,380,806	Main
	O&M Shed	Size: 9mX5m 0.00	570,536	Main
	Part-A: Construction of Shantar WRS	4v-1.5mX2.0m 0.00	1,335,749	PSSWRSP
	Part-B: Construction of Jadurmonir khal WRS	10v-1.5mX2.3m 0.00	1,361,503	PSSWRSP
	Part-A: Re-excavation of Buaburi Khal	0.40	638,008	PSSWRSP
	Part-B: Re-excavation of Shantar Khal	1.00	879,607	PSSWRSP
Sonaimuri PSSWRSP SP45200, Kamaldeni- Amishapara Subproject, FC, Union : Sonaimui, HO Date: 27/02/2017	Part-A: WMCA Office & Others	12mX6m 0.00	1,312,615	Main
	Part-A: Re-excavation of Amisha para khal	5.10	3,582,074	Main
	Part-B: Construction of Reference Lined Section	0.00	138,277	Main
Dhaka (Total SPs : 12 Nos.)				
Dhamrai SSWRDSP-2 SP23045, Manukhali Subproject, DR&WC, Union : Balia, HO Date: 12/09/2007	Re-excavation of Manukhali Khal	0.85	364,419	Main
	Manukhali Khal Regulator at Ch.0+040 (Khal)	2 Vent-1.50mX1.80m 0.00	4,296,716	Main
	O&M Shed	9.00mX5.00m 0.00	268,279	Main
	Improvement of road from Tatailed jame mosque to manu k	450m 0.00	2,047,742	PSSWRSP
	Re-excavation of Manukhali khal	1.35	151,381	PSSWRSP
	Re-sectioning of Embankment	0.57	549,798	PSSWRSP
	Re-sectioning of Embankment	0.88	560,861	PSSWRSP
	Part-A: Re-excavation of Manukhali Branch khal	1.40	0	SSWRDP-JICA-2
	Part-B: Construction of Reference Lined section	0.00	0	SSWRDP-JICA-2
	SP23060, Alam Khali Subproject, DR&WC, Union : Balia, HO Date: 30/06/2008			
	Alamkhali Khal Re-excavation	4.80	1,832,463	Main
	Link Khal Re-excavation	0.18	32,820	Main
	Indora Branch Khal Re-excavation	0.85	318,547	Main
	Regulator at Ch.0+145m on Alamkhali Khal	1 Vent-1.50mX1.80m 0.00	3,659,418	Main
	Pipe Sluice at Ch.0+000 km on Link Khal	1 Vent-0.60m Dia 0.00	859,455	Main
	O&M Shed	9.00mX5.00m 0.00	276,534	Main
	Maderpur Br. Khal Re-excavation	0.80	120,165	Main
	Borrowpit Khal Re-excavation	2.07	470,730	Main
	Jangalia Khal Re-excavation	0.50	115,030	Main
	Part-A: Re-sectioning of Embankment Dakatmara to Millgai	(3 Vent 900mm dia)at	1,918,959	PSSWRSP
	Part-A: Construction of Borrowpit khal Pipe Sluice (3 Vent 9	(3 Vent 900mm dia)at	2,989,016	PSSWRSP
	Part-B: Construction of Borrowpit khal Pipe Sluice (2 Vent 9	(2 Vent 900mm dia) 0.00	2,029,382	PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-C: Construction of Indra khal Pipe Sluice (2 Vent 900n	(2 Vent 900mm dia) 0.00	2,343,379	PSSWRSP
	Part-D: Alamkhali khal Regulator Downstream protection	0.00	1,054,305	PSSWRSP
	Part-B: Re-sectioning of Embankment Basta Bazar To Slui	0.22	71,472	PSSWRSP
	Part-C: Re-excavation of Borrowpit Khal	2.00	639,680	PSSWRSP
	Part-D: Re-excavation of Nayachar khal	0.30	83,875	PSSWRSP
	Part-E: Re-excavation of West Sutrapur khal	0.50	80,862	PSSWRSP
SP24113, Deldha-Anandanagar Subproject, FMD&WC, Union : Suapur, HO Date:				
	Re-section of Barta Beel Embankment	1.24	1,730,986	Main
	Anandanagar Khal Regulator at 0+040Km	3 Vent-1.5mX1.8m 0.00	6,017,760	Main
	Re-excavation of Anandanagar Khal	1.40	536,471	Main
	Re-excavation of Deldha Khal	1.80	556,572	Main
SP24137, Pachal Ragunathpur Subproject, FMD&WC, Union : Nannar, HO Date:				
	Rehabilitation 5 nos. Pipe culvert with Flap Gates	0.00	307,647	Main
	Pachal Regulator at Ch.0+070Km	3 Vent-1.5mX1.8m 0.00	5,114,485	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	311,157	Main
	Resectioning of Pachal-Ragunathpur Embankment(West	3.79	1,973,691	Main
	Resectioning of Pachal-Ragunathpur Embankment(East	6.03	1,196,314	Main
	Re-excavation of Pachal-Ragunathpur Khal	1.55	659,860	Main
	Mitigation Measures of Pachal Khal Regulator	3 nos. .6m & 2nos. .9m Dia	1,929,566	Main
PSSWRSP				
SP41010, Sawrnakhali Khal Subproject, FMD, Union : Kushura, Balia, HO Date:				
	Part A: Swarna Khali Khal Regulator at ch. 0+088km	2V-1.5mX1.8m 0.00	8,406,153	Main
	Part B: Fish Check Structure	1V-0.60m dia 0.00	701,243	Main
	Part C: WMCA office & related works	12mX6m 0.00	1,335,376	Main
	Part A: Re-excavation of Swarna khali Khal	1.25	497,138	Main
	Part B: Re-sectioning Approach Road	1.80	1,192,620	Main
SP45163, Chayani Khal Subproject, DR, Union : Chowhatta, HO Date: 08/08/2018				
	Part-A: Re-excavation of Chayani Khal	1.40	1,862,946	Main
Dohar				
SSWRDSP-2				
SP23047, Karunamayee Beel Subproject, FMD, Union : Sutarpara, HO Date: 11/12/2012				
	Re-excavation of Diarkum Branch Khal	0.37	39,246	Main
	Embankment Re-sectioning	2.69	1,246,806	Main
	Diarkum Br. Khal Regulator	1 Vent-1.50mX1.80m 0.00	2,124,971	Main
	Karunamayee Br. Khal Pipe Suice at Ch. 0+115 Km (E	1 Vent-0.90m 0.00	974,226	Main
	Diarkumar Br. Khal-1 Pipe Suice at Ch. 1+600 Km (E	1 Vent-0.90m 0.00	976,539	Main
SP23086, Kotabari Beel Subproject, DR&WC, Union : Kusumhati, HO Date: 28/07/2008				
	Re-excavation of Nayanagar Khal	3.90	1,824,323	Main
	Nayanagar Khal WRS-1 at Ch 0+980Km	4 Vent-1.50mX2.00m 0.00	5,078,409	Main
	Nayanagar Khal WRS-2 at Ch 3+800km	3 Vent-1.50mX2.00m 0.00	3,398,169	Main
	O&M Shed	9.00mX5.00m 0.00	298,846	Main
	Re-excavation of Suti Khal	0.92	341,257	Main
	Re-excavation of Porulia Khal	1.33	330,443	Main
	Re-excavation of Jomirmolla Khal	1.15	341,226	Main
Keraniganj				
SSWRDSP-2				
SP23102, Sirajnagar-Dewli Subproject, FMD&WC, Union : Taranagar, HO Date:				
	Embankment Re-sectioning	5.10	892,108	Main
	Approach Filling of Nimtali Regulator	1.20	414,159	Main
	Remaining works of 3 nos hydraulic Structures	0.00	2,134,147	Main
	Bewta Khal Re-excavation	2.50	731,433	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Bhawal Regulator at 50m North of Existing Bridge	1 Vent-1.50mX1.80m 0.00	3,949,699	Main
	Neemtali Regulator at 70m D/S of Existing Bridge	3 Vent-1.50mX1.80m 0.00	6,363,046	Main
	Nazirpur Regulator at Ch. 4+953Km (Embkt.)	1 Vent-1.50mX1.80m 0.00	3,898,817	Main
	Neemtali Khal Re-excavation	1.55	410,615	Main
	Approach Filling of Nazirpur Regulator	0.07	459,103	Main
	Approach Filling of Bhawal Regulator	1.22	1,052,957	Main
SP24170, Nishanbari-Belna Subproject, FMD, Union : Kalatiya, HO Date: 11/03/2009				
	Re-excavation of Zia Khal	2.60	336,299	Main
	Re-excavation of Mithapur Khal	0.39	34,291	Main
	Re-sectioning of Eastern Embankment	2.21	1,410,729	Main
	Re-sectioning of Southern Embankment	0.80	307,509	Main
	Mithapur Pipe Sluice at Ch 0+218Km (Khal)	1 Vent-0.90m dia 0.00	1,544,979	Main
	Belna Regulator at Ch. 1+480Km (Khal)	1 Vent-1.5mX1.8m 0.00	2,461,764	Main
	Re-sectioning of Embankment	0.21	254,285	Main
	Re-sectioning of Embankment (Near Belna Regulator)	0.21	275,749	Main
Nawabganj SSWRDSP-2				
SP24119, Kahalia Khal Subproject, DR&WC, Union : Agla, HO Date: 15/01/2009				
	Re-excavation of Kahalia Khal	6.60	1,953,925	Main
	Re-excavation of Shinghar Khal	1.10	90,350	Main
	Re-excavation of Kawakuli Khal	1.88	284,320	Main
	Re-excavation of Nawabari Khal	1.50	276,094	Main
	Re-excavation of Jura Khal	1.10	121,235	Main
SP24150, Kholshi Beel Subproject, DR&WC, Union : Jantrail, HO Date: 10/02/2010				
	Harishkhali Khal WRS at Ch. 0+600Km (Khal)	2 Vent-1.5mX2m & 1 Vent	5,835,165	Main
	Maraganga Khal WRS at Ch. 1+300Km (Khal)	1 Vent-1.5mX2.0m 0.00	2,549,227	Main
	Shovoria Khal WRS at Ch. 0+300Km (Khal)	1 Vent 1.5mX2m & 1 Vent	4,507,666	Main
	Re-excavation of Shovoria-Shollanagar Khal	8.20	3,864,905	Main
	Re-excavation of Harishkul Khal	3.20	251,956	Main
	Re-excavation of Maraganga Khal	2.60	783,229	Main
Faridpur (Total SPs : 29 Nos.)				
Alfadanga SSWRDP-JICA				
SP33044, Bajra Panail Subproject, CAD&DR, Union : Gopalpur, Tagarbanda, HO Date:				
	Re-excavation of Chapulia Khal	2.10	310,975	Main
	Part-E: Pump House	0.00	277,902	Main
	Deposite Money for Electric Connection to Pump House	0.00	0	Main
	Discharge Box for Hose Pipe (12 nos)	0.00	281,976	Main
	Part-C: Rehabilitation of Chapulia Regulator at Ch	1 Vent-1.2mX1.5m 0.00	1,205,743	Main
	Part-B: Buried Pipe Network System	Length=4450m 0.00	20,834,723	Main
	Part-A: Header Tank	Size: 6.1mX3.0m 0.00	2,093,811	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	0	Main
	Part-F: Accessories of Pump	0.00	1,663,623	Main
Bhanga SSWRDSP-1				
SP11008, Bogail Chowkighata DR Subproject, DR, Union : Tujarpur, HO Date: 17/10/2000				
	Bogail-Chowkighata Khal Re-excavation	5.30	968,592	Main
Boalmari SSWRDSP-1				
SP15331, Asharia Beel DR Subproject, DR, Union : Moina, HO Date: 10/11/2002				
	Embankment Re-sectioning	2.60	605,394	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	0	PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Improveent of HBB WMCA Connecting Road 00m-	0.00	0	PSSWRSP
	Part-A: Re-excavation of Asharia Khal	0.54	422,356	PSSWRSP
	Part-B: Re-Sectioning of Asharia Khal	2.64	2,501,159	PSSWRSP
	Moder Khal Re-excavation	2.44	460,294	Main
	Pipe Sluice at Ch.0+000m	1-V(1.0m dia)	690,214	Main
SSWRDSP-2				
SP25191, Foliar Beel Subproject, FMD, Union : Boalmari, HO Date: 30/12/2009				
	Ramnagar Khal Regulator at Ch. 0+420Km	5 Vent-1.5mX1.8m 0.00	6,167,884	Main
	O&M Shed	Size: 9mX5m 0.00	551,274	Main
SP25326, Atghoria Beel Subproject, FMD, Union : Goshpur, HO Date: 22/10/2010				
	Re-excavation of Atghoria Khal	0.65	218,550	Main
	Re-excavation of Sadaria Khal	0.85	246,569	Main
	Re-sectioning of Atghoria Embankmet	5.48	2,617,489	Main
	Rehabilitation of Atghoria Khal Regulator	1 Vent-1.5mx1.8m 0.00	608,573	Main
	Rehabilitation of Sadaria Khal Pipe Sluice	1 Vent-0.9m Dia 0.00	0	Main
	Part-A: Construction of RCC Lined Canal (L=800m)	(L=800m) 0.00	0	PSSWRSP
	Part-B: WMCA Office & Others	12mX6m 0.00	0	PSSWRSP
	Part-C: Improvement Of HBB WMCA Connecting Road (L=	(L=55m) 0.00	0	PSSWRSP
SSWRDP-JICA				
SP33046, Rupadia-Majurdia Khal Subproject, DR, Union : Satoir, HO Date: 14/01/2015				
	WMCA Office with Alied Item	Size: 12mX6m 0.00	2,278,141	Main
	Re-excavation of Rupdia-Majurdia Khal	5.30	7,582,943	Main
SP34129, Bhoraduba Beel Subproject, FMD, Union : Moina, HO Date: 10/12/2014				
	Reference Lined Sections (3 nos.)	0.00	97,734	Main
	Part-A: Rehabilitation of Thakurpur Khal Regulator	2 Vent-1.5mX1.8m 0.00	2,753,530	Main
	Part-B: Rehabilitation of Babur Khal Pipe Sluice	1 Vent-0.90m 0.00	167,148	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,754,322	Main
	Reexcavation of Thakurpur Khal	1.03	655,036	Main
	Reexcavation of Babur Khal	0.80	511,076	Main
Charbhadrasan				
SSWRDSP-1				
SP14162, Gazirtek Beel DR Subproject, DR, Union : Gazirtek, HO Date: 01/10/2000				
	Gazirtek Khal Re-excavation	3.60	946,065	Main
Madhukhali				
SSWRDSP-1				
SP13056, Sonatala FCD Subproject, FCD&WC, Union : Dumain, HO Date: 07/06/2000				
	Embankment Re-sectioning	3.97	3,438,338	Main
	Approach of Patapuar Regulator	0.10	38,358	Main
	Approach of Khedakular Regulator	0.10	48,444	Main
	Approach of Dhuliar Regulator	0.20	132,544	Main
	Approach of Bardual Regulator	0.10	30,231	Main
	Part-A : Pipe Sluice	1V - 900mm dia 0.00	1,502,546	PSSWRSP
	Part-B: Replacement of vertical lift gate & flapgate	1V-1.2mx1.5m 0.00	12,395	PSSWRSP
	Part-C: Provision of Fall Board for existing Sildhiajuri Pipe	1V -900mm dia 0.00	111,026	PSSWRSP
	Part-D: Impr. of road by HBB pavem on Dumaim Mosque to	ch. 0+0km to ch. 4+085 km	9,057,926	PSSWRSP
	Part-E: Construction of Masonry Pillars (6 Nos.) to monitor	6 Nos. 0.00	13,072	PSSWRSP
	Part-A: Re-excavation of Potanga Khal	1.70	1,631,798	PSSWRSP
	Part-B: Re-excavation of Khadakhola Khal	0.50	410,667	PSSWRSP
	Khal Re-excavation-4 nos.	1.60	108,672	Main
	Khedakular Khal Re-excavation	0.90	92,782	Main
	Bardual Khal Re-excavation	0.70	80,032	Main
	Dhuliar Khal Re-excavation	0.40	30,750	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Patapuar Khal Re-excavation	0.30	17,544	Main
	Patenga Khal Re-excavation	1.78	303,385	Main
	Bardual Regulator	1-V(1.2mX1.5m)	1,020,362	Main
	Patapuar Regulator	1-V(1.2mX1.5m)	1,024,659	Main
	Dhuliar Regulator	1-V(1.2mX1.5m)	1,595,027	Main
	Khedakular Regulator	1-V(1.5mX1.5m)	1,794,131	Main
	Sidhlajuri Pipe Sluice at Ch.3+820m	1-V(900mm Dia)	924,029	Main
	Flap Gate Repair-4 Nos.		20,000	Main
SP13057, Fuleswari FCD Subproject, FCD&WC, Union : Meghchami, HO Date: 07/05/2002				
	Embankment Re-sectioning	6.52	4,602,997	Main
	Embankment Rehabilitation	5.85	1,253,928	Main
	Ghorachula & Gojarer Khal Re-excavation	3.00	78,285	Main
	Gojarer Khal Re-excavation	1.55	142,513	Main
	Shambabu Khal Re-excavation	1.10	127,828	Main
	Dhopadanga Khal Re-excavation	0.50	90,731	Main
	Ghorachula Khal Re-excavation	0.90	118,477	Main
	Kalagachi Khal Re-excavation	0.75	69,739	Main
	Gojarer Regulator	1-V(1.5mX1.5m)	1,668,540	Main
	Ghorachula Regulator	1-V(1.2mX1.5m)	1,405,964	Main
	Shambabu Regulator	1-V(1.2mX1.5m)	1,399,806	Main
	Kalagachi Regulator	1-V(1.8mX2.4m)	1,360,606	Main
	Dhopadanga Pipe Sluice	1-V(900mm Dia)	525,953	Main
	Chakuliar Pipe Sluice	1-V(900mm Dia)	532,965	Main
	Utariar Beel Pipe Sluice	1-V(900mm Dia)	529,558	Main
SP14173, Harinkhola Beel FCD Subproject, FCD, Union : Dumain, HO Date: 13/03/2003				
	Embankment Re-sectioning	1.65	373,844	Main
	Re-sectioning of Compartmental Dyke	0.90	86,295	Main
	Nawdara Khal Re-excavation	0.35	71,962	Main
	Dengrakhal Khal Re-excavation	1.32	80,464	Main
	Katakhal Khal Regulator at Ch.2+120	1-V(1.2mX1.5m)	1,249,083	Main
SP14193, Komorpur-Gopalbila FCD Subproject, FCD, Union : Kamarkhali, HO Date:				
	Embankment Re-sectioning(Sec. A)	5.20	1,984,243	Main
	Embankment Re-sectioning(Sec. B)	1.50	755,327	Main
	Part-A: Construction of WMCA office and others	12mX6m 0.00	1,420,718	PSSWRSP
	Part-B: Improvement of HBB WMCA Connecting Road	Length=19.00 km 0.00	58,932	PSSWRSP
	Salamatpur & Joarer Khal Re-excavation	1.55	31,626	Main
	Komorpur Khal Re-excavation	1.08	8,624	Main
	Regulator at Ch. 1+950m	1-V(1.5mX1.5m)	1,707,364	Main
	O&M Shed		0	Main
SP14197, Mitain-Naldanga FCD Subproject, FCD, Union : Bagat, HO Date: 07/05/2002				
	Embankment Re-sectioning(Sec. A)	3.80	1,076,068	Main
	Embankment Re-sectioning(Sec. B)	0.48	206,265	Main
	Improvement of HBB road/embankment on Mitain-Naldang	1.22	3,975,174	PSSWRSP
	Gomara Khal Re-excavation	2.70	218,776	Main
	Naldanga Khal Re-excavation	1.98	317,485	Main
	Mitain Khal Re-excavation	1.12	184,411	Main
	O&M Shed		0	Main
SP15256, Arkandi FCD Subproject, FCD, Union : Nowapara, HO Date: 13/03/2003				
	Embankment Re-sectioning	4.95	461,472	Main
	Pipe Sluice at Ch.0+718m	1-V(900mm Dia)	414,424	Main
	Pipe Sluice at Ch.1+893m	1-V(900mm Dia)	420,311	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Pipe Sluice at Ch.3+070m	1-V(900mm Dia)	417,718	Main
	Pipe Sluice at Ch.4+906m	1-V(900mm Dia)	476,863	Main
SSWRDSP-2				
SP22026, Sriramkandi Subproject, FMD, Union : Noapara, HO Date: 11/12/2008				
	Embankment Re-sectioning	7.44	2,006,934	Main
	Dharmahati Regulator at Ch.5+331 km	1-V(1.5mX1.8m) 0.00	3,241,887	Main
	Pichulia Pipe Sluice at Ch. 0+735	1-V(900mm Dia) 0.00	987,333	Main
	Khoitala Pipe Sluice at Ch. 2+720 km	1-V(900mm Dia) 0.00	1,107,292	Main
	O&M Shed	12.00mX6.00m 0.00	301,279	Main
	Kumardah Pipe Culvert at Ch.3+298 km	1-V(900mm Dia) 0.00	80,743	Main
	Re-sectioning of Embankment	2.32	1,378,495	Main
	Part-A: Drainage outlet Structure (1V-900mm) dia at Ch.2+	(1V-900mm) dia at Ch.2+200	1,787,695	PSSWRSP
	Part-B: Drainage outlet Structure (1V-900mm) dia at Ch.7+	(1V-900mm) dia at	1,567,576	PSSWRSP
SP24181, Meghchami Subproject, DR&WC, Union : Meghchami, HO Date: 14/02/2008				
	Megchami WRS at Ch. 4+750 Km	2 Vent-1.5mX1.8m 0.00	2,498,682	Main
	Remodelling of Intake Structure at Ch.0+030Km (Kha	2 Vent-0.9m Dia 0.00	551,351	Main
	Re-excavation of Megchami Khal	5.22	1,153,467	Main
	O&M Shed	Size: 12mX6m 0.00	305,474	Main
	Approach Filling of Norkona WRS	0.21	130,352	Main
	Part-A: Improv. of HBB road H/O Azad Sk.-Magchami H. S	Ch.125.0m to 425.0m 0.00	858,642	PSSWRSP
	Part-A: Re-excavation of Magchami Manabeel Khal	0.60	279,503	PSSWRSP
	Part-B: Re-Sectioning of Magchami Meghami Norokona f	0.30	860,026	PSSWRSP
SSWRDP-JICA				
SP32009, Satgavia Beel Subproject, DR&WC, Union : Raypur, HO Date: 17/09/2013				
	Re-excavation of WAPDA Khal with Fish Shelter	7.50	4,148,789	Main
	Part-C: Thanarjol Khal WRS- at Ch.0+600 Km (Khal)	1 Vent-1.2mX1.5m 0.00	2,066,012	Main
	Reference Lined Section (8 nos.)	0.00	271,062	Main
	Re-excavation of Thaner Jola Khal with FishShelter	1.30	372,295	Main
	Re-excavation of Fish Sanctuary on Ichamoti Beel	0.00	240,597	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	770,594	Main
	Part-A: WAPDA Khal WRS-1 at Ch.0+203 Km (Khal)	3 Vent-1.5mX1.8m 0.00	5,496,115	Main
	Part-B: WAPDA Khal WRS-2 at Ch.4+200 Km (Khal)	2 Vent-1.2mX1.5m 0.00	2,749,705	Main
Nagarkanda				
SSWRDSP-1				
SP14163, Kaichal Beel FCD Subproject, FCD, Union : Ijuni,Nagarkanda, HO Date:				
	Embankment Re-sectioning	5.12	3,108,019	Main
	Kaichal Khal Re-excavation	6.14	1,043,313	Main
	Kaichal Regulator	4-V(1.5mX1.8m)	5,210,001	Main
SSWRDP-JICA				
SP31003, Beel Gobindapur Subproject, FMD&WC, Union : Dangi, HO Date: 20/04/2015				
	Part-K: WMCA Office and Related Items	Size: 12mX6m 0.00	994,698	Main
	Part-A: Masuajan Khal Regulator at Ch. 0+010Km (Kh	1 Vent-1.5mX1.8m 0.00	2,834,607	Main
	Part-B: Krishnan Khal Regulator at Ch. 0+560Km (Kh	2 Vent-1.5mX1.8m 0.00	3,906,283	Main
	Part-C: Kaloir Beel Khal Regulator at Ch.0+710Km	1 Vent-1.5mX1.5m 0.00	2,065,968	Main
	Part-D: Zikatola Khal Regulator at Ch.1+305Km	1 Vent-1.5mX1.5m 0.00	1,790,251	Main
	Part-E: Asharia Beel Khal Regulator at Ch.1+633Km	1 Vent-1.5mX1.8m 0.00	2,017,220	Main
	Part-F: Harihar Beel Khal Regulator at Ch.2+400Km	1 Vent-1.5mX1.2m 0.00	1,318,664	Main
	Part-G: Chander Beel Khal Regulator at Ch.2+485Km	1 Vent-1.5mX1.8m 0.00	2,120,610	Main
	Part-H: Shohrab Membe Khal Regulator at Ch.3+260Km	1 Vent-1.5mX1.5m 0.00	2,094,788	Main
	Part-I: Mannan Member Khal Regulator at Ch.3+260Km	1 Vent-1.5mX1.5m 0.00	1,839,855	Main
	Part-J: Maser Khal Regulator at Ch.4+050Km	1 Vent-1.5mX1.8m 0.00	2,512,346	Main
SP33059, Baneswardi Subproject, CAD&DR, Union : Char Josordi, HO Date: 13/11/2014				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Reexcavation of Burimari Khal	0.52	170,291	Main
	Reexcavation of Kata Khal	0.50	157,079	Main
	Reexcavation of Moher Khal	0.46	242,393	Main
	Part-A: Header Tank	Size: 6.1mX4.2m 0.00	3,700,716	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,502,985	Main
	Part-B: Buried Pipe Irrigation Network System	Length= 7.495Km 0.00	24,994,921	Main
	Part-D: Pump House	0.00	591,812	Main
	Part-E: Supply of 4 nos. 4 Cuses Pumps (2 for Bajra Panail	0.00	1,009,000	Main
SP34130, Phulsuti Subproject, DR&IRR, Union : Fulsuti, HO Date: 11/12/2014				
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,682,076	Main
	Re-excavation of Rampasa Khal	1.25	1,370,212	Main
	Re-excavation of Harinkhali Khal	0.77	1,981,408	Main
	Re-excavation of Bautipara Khal	0.55	662,211	Main
SP34131, Gopinathpur Khal Subproject, DR&WC, Union : Ramnagar, HO Date:				
	Re-excavation of Gopinathpur Khal	4.40	1,465,373	Main
	Reference Lined Sections	0.00	31,221	Main
	Part-A: Gopinathpur Khal WRS at Ch.0+770Km	1 Vent-1.5mX2.0m 0.00	2,747,865	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	2,042,908	Main
	Part-B: Gopinathpur Flushing Sluice at Ch.4+378Km	1 Vent-1.5mX1.5m 0.00	2,789,215	Main
	Pard-H: 900mmX900mm, 7.60m Long U type Drain Culvert	2 nos. 0.00	368,444	Main
	Pard-I: 900mmX900mm, 9.00m Long U type Drain Culvert	1 no. 0.00	207,945	Main
Sadar SSWRDSP-1				
SP14164, Chilakandi-Madhabpur DR Subproject, DR, Union : Krishna Nagar, HO Date:				
	Madhabpur Khal Re-excavation	3.90	542,009	Main
	Kotajola Khal Re-excavation	0.90	60,849	Main
	Nakortala Khal Re-excavation	1.20	17,553	Main
SP14165, Hawaikhali Beel-Sukunia DR Subproject, DR, Union : Kaijuni, HO Date:				
	Hawaikhali Khal Re-excavation	5.60	1,078,543	Main
	Vanger Khal Re-excavation	1.80	328,102	Main
SP14166, Pandanga-Kendor Beel DR Subproject, DR, Union : Kaijuri, HO Date:				
	Part-A: Construction of WMCA office and others	12mX6m 0.00	2,909,965	PSSWRSP
	Ghorada Khal Re-excavation	0.45	76,457	Main
	Bangdoba Khal Re-excavation	1.70	194,183	Main
SSWRDP-JICA				
SP34144, Chotrar Calk-Gonoshayampur Khal Subproject, DR&WC, Union : Machchar, HO				
	Re-excavation of Chatrar Chalk-Ghanashyampur Khal	2.40	2,259,881	Main
	Re-excavation of Ziar Khal	1.65	426,109	Main
	Reference Lined Sections (3 nos)	0.00	106,334	Main
	Part-A: Chatrar Chalk Khal WRS at Ch.0+060Km	3 Vent-1.5mX2.2m 0.00	11,842,703	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,888,816	Main
Sadarpur SSWRDP-JICA				
SP32035, Akoterchar-Nolertek-Chaiterkole Khal Subproject, DR, Union : Akterchar, HO				
	Re-excavation of Akoter Char Khal	5.00	3,305,702	Main
	Re-excavation of Lohartek Khal	1.40	233,086	Main
	Re-excavation of Nalertek Khal	0.50	468,869	Main
	Re-excavation of Hizoltala Khal	1.00	128,490	Main
	Re-excavation of Jamir Mridha's Khal	0.60	150,706	Main
	Referenece Lined Section	0.00	198,703	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,392,798	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP35173, Char Ramnagar Subproject, DR, Union : Akoterchar, HO Date: 23/04/2015	Part-A: Nolertek Regulator At Ch. 0+025 Km	1 Vent-1.5mX1.5m 0.00	3,809,640	Main
	Re-excavation of Char Ramnagar Khal	4.10	6,463,400	Main
	Re-excavation of Choudhury Barir Khal	1.50	609,677	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,707,544	Main
Saltha				
SSWRDP-JICA				
SP34141, Atghar-Durgapur Khal Subproject, DR, Union : Atghar, HO Date: 22/12/2014				
	Re-excavation of Atghar-Durgapur Khal	3.30	2,689,468	Main
	Re-excavation of Kushtia Khal	0.30	239,913	Main
	Re-excavation of Sulapur Khal	0.50	182,567	Main
	Re-excavation of Telangar Khal	0.60	210,873	Main
	Reference Lined Sections (3 nos.)	0.00	97,929	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,617,335	Main
	Re-excavation of Atghar-Durgapur Khal (adll)	3.60	4,253,758	Main
Gazipur (Total SPs : 6 Nos.)				
Kaliganj				
SSWRDSP-2				
SP23069, Nalijuri Khal Subproject, DR&WC, Union : Bahadurshadi, HO Date: 10/06/2009				
	Nalijuri Khal Re-excavation	13.00	4,817,069	Main
	Nalijuri Khal WRS at Ch.9+000Km(Khal)	6 Vent-1.50mX2.00m 0.00	8,132,754	Main
SP23099, Noli Khal Subproject, WC, Union : Bakterpur, HO Date: 10/11/2009				
	Re-excavation of Shubudia Khal	1.20	310,675	Main
	Noli WRS at Ch. 3+6300Km (Khal)	1 Vent-1.50mX1.80m 0.00	3,888,275	Main
	Re-excavation of Noli Khal	5.30	1,415,400	Main
	Re-excavation of Putimara Br. Khal	0.41	36,917	Main
	Re-excavation of Queener Khal	0.55	133,712	Main
	Re-excavation of Khoikhara Khal	0.50	107,986	Main
	Re-excavation of Berua Khal	1.80	60,103	Main
	Re-excavation of Putimara Khal	2.30	207,219	Main
Kapasia				
SSWRDSP-2				
SP23053, Banarkandi-Barishaba Subproject, FMD, Union : Barishabo, HO Date:				
	Re-excavation of Ahar khal & Chati Khal	0.45	119,300	Main
	Re-sectioning of West Embankment	2.89	1,418,533	Main
	Chati Khal Regulator at Ch.0+030km (Khal)	1 Vent-1.50mX1.80m 0.00	2,720,718	Main
	Ahar Khal Regulator at Ch.0+030km (Khal)	1 Vent-1.50mX1.80m 0.00	2,844,242	Main
	Pipe Sluice at Ch. 3+230 Km	1 Vent-0.90m Dia 0.00	792,368	Main
	Re-sectioning of East Embankment	0.65	147,984	Main
SP23055, Sutarkandi Subproject, FMD&WC, Union : Ghagatia, HO Date: 02/06/2009				
	Embankment Re-sectioning	0.30	211,860	Main
	Suterkandi Khal Re-excavation	1.60	266,493	Main
	Suterkandi Khal Regulator at Ch. 0+050 Km	1 Vent-1.50mX1.80m 0.00	3,093,785	Main
Sreepur				
PSSWRSP				
SP41008, Gosinga-Sitalakha Subproject, CAD, Union : Gosinga, HO Date: 16/05/2018				
	Part A: Header Tank	6.1mx3.0m 0.00	1,361,233	Main
	Part B: Burried Pipe Network System	0.00	64,778,802	Main
	Part-C: Flow Control Measurement Structure	7 Nos. 0.00	3,389,769	Main
	Part-D: WMCA office & others	12mx6m 0.00	1,585,994	Main
Rubber Dam				
SP98002, Kaoraid River Rubber Dam Project, WC, Union : Kaoraid, Rajoi, HO Date:				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Kawraith-Suti Nodi Rubber Dam	Size: 30mX3.0m 0.00	21,682,000	Main
	Matikata Khal (Golaghat) Rubber Dam	Size: 20mX2.5m 0.00	15,222,000	Main
Gopalganj (Total SPs : 25 Nos.)				
Kasiani				
SSWRDSP-2				
SP25290, Khodar Khal Subproject, IRR, Union : Nizamkandi, HO Date: 22/04/2010				
	Re-excavation of Khodar Khal	3.20	1,618,265	Main
SSWRDP-JICA				
SP32016, Mamudpur-Jikarbari Subproject, DR&IRR, Union : Mahmudpur, HO Date:				
	Re-excavation of Laxmipur-Jikarbari Khal	4.20	1,767,310	Main
SP34118, Aruakandi-Arkandi Khal Subproject, DR&IRR, Union : Orakandi, HO Date:				
	Part-A: WMCA Office and Related Item	Size: 12mnX6m 0.00	1,128,776	Main
	Re-excavation of Aruakandi Khal	4.40	3,359,584	Main
	Re-excavation of Pati Bhanga Khal	1.05	1,166,140	Main
	Re-excavation of Pati Bhanga Branch Khal	0.50	286,750	Main
Kotalipara				
SSWRDSP-1				
SP12022, Tarashee-Teehati FCD Subproject, FCD, Union : Khusla, HO Date: 29/04/2002				
	Embankment Re-sectioning	9.67	4,077,287	Main
	Jhatia Regulator	1-V(1.8mX2.4m)	807,950	Main
	Pabnarpur Regulator	1-V(1.8mX2.4m)	846,346	Main
	Kushla Regulator	1-V(1.8mX2.4m)	851,925	Main
	Tarashee Regulator	1-V(1.8mX2.4m)	845,272	Main
	Bhankura Regulator	1-V(1.8mX2.4m)	845,892	Main
	Pipe Sluice at Ch.4+480m	1-V(900mm dia)	453,675	Main
SSWRDSP-2				
SP24151, Kunjaban-Pittalpara Subproject, FMD, Union : Radhaganj, HO Date: 30/06/2008				
	Ambari Khal Regulator at Ch. 0+020Km	1 Vent-2.5mX2.0m 0.00	2,443,532	Main
SSWRDP-JICA				
SP31007, Barua-Kumaria Subproject, FMD&IRR, Union : Kalabari, HO Date: 25/11/2015				
	Re-excavation of Bacher Bhanga Khal	0.67	543,746	Main
	Reference Lined Section	0.00	161,966	Main
	Part-A: Barua-Kumaria Khal Regulator at Ch 0+030Km	2 V-1.5mX2m & 1	7,169,599	Main
	Part-B: Bacher-Bhanga Khal Regulator at Ch 0+030Km	1 Vent-1.5mX1.8m 0.00	2,612,145	Main
	Part-C: Nalua Br. Khal Regulator at Ch 0+385Km	1 Vent-2mX1.8m 0.00	2,361,368	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	1,187,173	Main
	Re-excavation of Barua Kumaria Khal	4.60	3,852,019	Main
	Re-excavation of Barua Br. Khal	1.50	414,588	Main
	Re-excavation of Nalua Br. Khal	1.00	184,023	Main
SP33069, Suagram Subproject, DR&IRR, Union : Suagram, HO Date: 09/12/2015				
	Reference Lined Section (16 nos.)	0.00	334,086	Main
	Part-A: WMCA Office with related items	Size: 12mX6m 0.00	1,134,551	Main
	Reexcavation of Suagram Boro Khal	5.61	3,299,195	Main
	Reexcavation of SuagramPurbo Para Khal	3.30	854,841	Main
	Reexcavation of Suagram Narayan Khana Branch Khal	1.50	603,935	Main
	Reexcavation of Dakshinpar Saturia Khal	0.70	205,973	Main
SP34132, Bandhabari Beel Subproject, FMD&IRR, Union : Bandhabari, HO Date:				
	Re-excavation of Guldarbari Khal	0.54	412,299	Main
	Part-B: Gulderbari Khal Regulator at Ch.0+020Km	1 Vent-1.5mX2.3m 0.00	4,197,351	Main
	Part-C: Hardor Khal Regulator at Ch.0+230Km	1 Vent-1.5mX2.0m 0.00	3,655,722	Main
	Reference Lined Sections	0.00	121,595	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,603,080	Main
	Part-A: Arua Khal Regulator at Ch.0+004Km	1 Vent-1.5mX2.3m 0.00	3,237,797	Main
	Re-excavation of Bandhabari Khal	2.90	2,098,667	Main
	Re-excavation of Arua Khal	0.39	198,259	Main
SP34137, Malirkhola-Khochkola Subproject, DR&IRR, Union : Bandhabari, HO Date:				
	Re-excavation of Garumara Khal	2.12	1,455,699	Main
	Reference Lined Sections	0.00	183,748	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,413,205	Main
	Part-A: Baherer Bhanga Pipe Sluice at Ch.2+430Km	1 Vent-0.90m Dia 0.00	868,193	Main
	Part-B: Arifer Bhanga Pipe Sluice at Ch.2+850Km	1 Vent-0.90m Dia 0.00	848,582	Main
	Re-excavation of Bandhabari Kaborbari Khal	3.43	1,085,757	Main
Moksudpur SSWRDSP-1 SP15330, Ramkrishnapur DR Subproject, DR, Union : Moharajpur,Dignagar & Mochna, HO				
	Khal Re-excavation	8.05	2,072,486	Main
SSWRDSP-2 SP22012, Kaliadaha Subproject, FMD, Union : Nanikhir, HO Date: 27/04/2010				
	Approach filling of Regulator at Ch.1+300Km	0.03	262,398	Main
	Approach filling of Pipe Sluice at Ch.2+525Km	0.17	217,227	Main
	Approach filling of Regulator at Ch.4+920Km	0.18	302,365	Main
	Approach filling of Inlet Structure at Ch.0+500Km	0.25	183,921	Main
	Earthwork for Block Setting for 3 nos. Structures	0.00	172,657	Main
	Block setting of 3 nos. Structures	0.00	249,880	Main
	Embankment Re-sectioning	4.92	2,262,683	Main
	Regulator at Ch.1+300 km	1-V(1.50mX1.80m) 0.00	1,795,455	Main
	Mohistoli-Nonikhir Khal Re-excavation	0.41	61,891	Main
	Kalidah Khal Re-excavation	0.60	173,118	Main
	Pipe Sluice at Ch.2+525 km	1-V(900mm Dia.) 0.00	979,450	Main
	Inlet Structure at Ch.0+500 km	1-V(900mm Dia.) 0.00	992,032	Main
	Outlet Structure at Ch.4+060 km	1-V(900mm Dia.) 0.00	979,450	Main
	Regulator at Ch.4+920 km	2-V(1.50mX1.80m) 0.00	2,719,053	Main
SSWRDP-JICA SP33040, Ghechua-Simulsur-Kalinagar Subproject, DR&IRR, Union : Bashbaria, HO Date:				
	Re-excavation of Dhigharia Link Khal	1.30	568,944	Main
	Reference Lined Section (3 nos.)	0.00	37,047	Main
	WMCA Office and Related Item	Size: 12mX6m 0.00	1,822,610	Main
	Re-excavation of Bongram-Ujani Khal	3.90	2,847,977	Main
	Re-excavation of Manik- Mollar Beel Link Khal	0.70	174,299	Main
	Re-excavation of Ghechua- Chhoto Beel Link Khal	0.30	123,464	Main
	Re-excavation of Dhalibari Beel Link Khal	0.30	139,117	Main
	Re-excavation of Shimulshur-Jhitigram Br. Khal	0.47	37,362	Main
	Re-excavation of Patil Bhanga Beel Link Khal	0.30	23,536	Main
SP35216, Krishnadia-Kaoaldia Subproject, DR&IRR, Union : Poshargatiu, HO Date:				
	WMCA Office and Related Item	Size: 12mX6m 0.00	1,106,481	Main
	Re-excavation of Napitbari Khal	4.10	5,082,374	Main
	Re-excavation of Beparibari Khal	0.80	687,265	Main
	Re-excavation of Katakhal Khal	3.01	2,356,479	Main
	RCC Box Culvert at Ch. 2+490Km	1 Vent-5.0mX5.0m 0.00	2,282,118	Main
Sadar SSWRDSP-1 SP13043, Gobra FCD Subproject, FCD, Union : Gobra, HO Date: 08/10/2001				
	Embankment Re-sectioning	0.92	322,072	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Closure	0.08	65,492	Main
	Gobra Khal Re-excavation	2.30	386,453	Main
	Gobra Regulator	1-V(2.0mx2.4m)	2,128,045	Main
	Pipe Sluice	2-V(900mm Dia)	509,557	Main
SP14167, Charboira-Chargobra-Bhatia Khal DR Subproject, DR, Union : Gobra, HO Date:				
	Part-A: Construction of WMCA Office amd others	12mX6m 0.00	1,100,438	PSSWRSP
	Khal Re-excavation	3.60	1,255,319	Main
SP14168, Kuthibari Khal DR & WCS Subproject, DR&WC, Union : Suktail, HO Date:				
	Kuthibari Khal Re-excavation	1.56	217,859	Main
	Kuthibari WRS at Ch.0+450m	4-V	2,181,785	Main
SSWRDP-JICA				
SP32019, Katarbari-Karagati Subproject, DR&IRR, Union : Durgapur, HO Date: 11/09/2013				
	Re-excavation of Katar Bari Khal	2.50	2,336,652	Main
	Re-excavation of Gopalgonj-Kotalipara Khal	5.40	3,184,050	Main
	Re-excavation of Karagati Khal	1.70	311,685	Main
SP33061, Urafi-Jangal Danga Subproject, DR&IRR, Union : Urfi, HO Date: 20/08/2013				
	Re-excavation of Urfi Boro Khal	2.55	1,119,672	Main
	Re-excavation of Jangal Danga Khal	3.70	732,750	Main
	Re-excavation of Urfi Nichupara-1 Khal	0.50	392,644	Main
	Re-excavation of Urfi Nichupara-2 Khal	0.40	334,213	Main
Tungipara				
SSWRDSP-1				
SP13042, Kaikubunia-Chinguri FCD Subproject, FCD, Union : Patgati, HO Date:				
	Embankment Re-sectioning	2.00	1,026,706	Main
	Part-A: Construction of 3 nos RCC pond and 741.0 m RCC	741.0 m 0.00	2,990,183	PSSWRSP
	Nabukhali & Kaikubunia Khal Re-excavation	0.70	53,958	Main
	Bhushali Regulator	1-V(2.0mX2.4m)	1,804,727	Main
	Nabukhali Regulator	1-V(1.2mX1.5m)	1,268,398	Main
	Kaikubunia Khal Regulator	1-V(1.5mX1.8m)	1,350,878	Main
	Pipe Inlet-8Nos.	1-V(300mm dia)	240,180	Main
SP14169, Kushli Khal WCS Subproject, WC, Union : Kushli, HO Date: 25/06/2002				
	Kushli Main Khal Re-excavation	1.60	166,812	Main
	Kushli-Boyra Khal Re-excavation	1.05	177,053	Main
	Kushli Khal WRS at Ch.1+600m	1-V(1.5mX1.8m)	1,148,918	Main
SP14203, Mondalbari DR Subproject, DR, Union : Patgati, HO Date: 01/09/2000				
	Mondalbari Khal Re-excavation	1.14	282,604	Main
	Mondalbari Br. Khal Re-excavation	0.30	59,522	Main
SSWRDSP-2				
SP24131, Balajtala-Kalmadanga Subproject, FMD&WC, Union : Borni, HO Date:				
	Re-excavation of Swanirvar Branch Khal-1	1.20	128,118	Main
	Re-excavation of Swanirvar Branch Khal-2	1.00	127,229	Main
	Resectioning of Approach of 2 structures	0.15	328,355	Main
	Fish Net, Approach Filling, Head Wall etc.	0.00	732,930	Main
	Re-excavation of Swanirvar Khal	0.96	541,837	Main
	Re-Sectioning of Embankment	2.34	923,410	Main
	Remodelling of Hazir Culvert as WRS at Ch. 0+415Km	1 Vent-2.2mX1.8m 0.00	1,972,447	Main
	Bolajtala Khal Pipe Sluice at Ch0+020 Km (Khal)	Size: 1 Vent-1.2m Dia 0.00	1,144,068	Main
	Swanirvar Khal Regulator at Ch. 1+500Km (Embkt)	2 Vent-1.5mX1.8m 0.00	2,900,502	Main
	Re-excavation of Balajtala Khal	0.11	15,185	Main
	Re-excavation of Hazir Khal	1.60	526,360	Main
	Part-A: Re-Sectioning of Embakment Munsir char Remodel	1.05	1,970,057	PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SSWRDP-JICA SP33060, Lebutala-Bashbaria Subproject, FMD&WC, Union : Domuria, HO Date:	Part-B: Re-excavation of sener char khal & referense lined	1.25	944,177	PSSWRSP
	Re-excavation of Tarikullah Khal	0.60	192,396	Main
	Re-excavation of Chhoto-Pukurtia Khal	0.45	217,896	Main
	Re-excavation of Tarikullah Link Khal	0.80	350,575	Main
	Re-excavation of Boiragir Khal	0.80	556,682	Main
	Resectioning of Embankment (Extension)	0.69	1,091,407	Main
	Re-construction of Labutala Bashbaria Embankment	6.00	15,726,408	Main
	Referenece Lined Section (3 nos.)	0.00	77,625	Main
	Resectioning of Embankment	3.80	3,781,311	Main
	Part-A: Gangnir Khal Regulator at Ch.0+050Km	Size: 1 vent-1.5mX1.8m 0.00	4,657,003	Main
	Part-B: Rajendra Khal Regulator at Ch.2+385Km	Size: 1 Vent-1.5mX1.8m 0.00	4,716,824	Main
	Part-C: Chhoto Pukuria Khal Regulator at Ch.0+050	Size: 1 Vent-1.5mX1.8m 0.00	4,716,824	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	1,592,761	Main
	Re-excavation of Rajendra-Gangnir Khal	2.42	971,856	Main
	SP35160, Sriramkandi-Ghoperdanga Khal Subproject, DR&IRR, Union : Phatgati, HO			
	Rexcavation of Sriramkandi-Ghoperdanga Khal	7.30	5,325,074	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,572,339	Main
	Earth Filling & Site Development of WMCA Office	0.00	0	Main
	SP35188, Boro Dumuria Subproject, FMD, Union : Dumuria, HO Date: 19/08/2015			
	Re-excavation of Kata Khal	2.30	554,540	Main
	Re-excavation of Jhonjhonia Khal	1.71	936,900	Main
	Re-excavation of Par Jhonjhonia Khal	2.10	1,300,578	Main
	Re-excavation of Munshibarir Khal	2.50	857,600	Main
	Resectioning of Boro Dumuria Embankment	5.33	7,210,483	Main
	Part-A: Supplying of Gates for Existing Pipe Sluice	Size: 0.55mX0.60m 0.00	0	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,258,965	Main
Kishoregonj (Total SPs : 28 Nos.)				
Austogram				
SSWRDP-JICA				
SP35184, Patirdia Beel Subproject, FMD&WC, Union : Kolma, HO Date: 30/11/2015	Part-A: Patirdia Khal Regulator at Ch.0+520Km (Khal)	1 Vent-1.5mX1.8m 0.00	5,129,851	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,729,988	Main
	Reexcavation of Patirdia Beel Khal	2.78	3,716,482	Main
SP35185, Ekurdia-Boro Khal Subproject, FMD, Union : Purba Austagram, HO Date:	Part-A: Boro Khal Regulator	3 Vent-1.5m1.8m 0.00	7,954,106	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6.0m 0.00	1,902,396	Main
	Re-excavation of Boro Khal	3.75	5,714,250	Main
	Re-excavation of Branch Khal	0.10	72,707	Main
SP35193, Baithakhali Khal Subproject, FMD&WC, Union : Adampur, HO Date: 01/12/2015	Part-A: Ruer Khal Regulator at Ch.0+275Km	2 Vent-1.5mX1.8m 0.00	9,981,977	Main
	Fish Scentuary	0.00	1,243,656	Main
	Part-B: Elevated WMCA Office and Related Item	Size: 12mX6m 0.00	2,008,939	Main
	Reexcavation of Baithakhali Khal	2.60	4,059,420	Main
	Reexcavation of Ruer Khal	1.70	1,265,723	Main
	Reexcavation of Adampur Bazar Khal	0.48	519,366	Main
SP35194, Tofa-Jaldubi Beel Subproject, FMD&WC, Union : Kolma, HO Date: 30/11/2015	Re-excavation of Tofa-Jaldubi Beel Khal	2.30	1,461,456	Main
	Resectioning of Embankment	0.90	1,359,141	Main
	Part-C: Elevated WMCA Office and Related Item	Size: 12mX6m 0.00	1,596,508	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP35196, Beel Bolli Haor Subproject, FMD&WC, Union : Berahaor, HO Date: 29/11/2015	Part-A: Tofa Beel Khal Regulator at Ch. 0+175 Km (Khal)	1 Vent-1.5mX1.8m 0.00	6,484,704	Main
	Part-B: Jaldubi Beel Khal Regulator at Ch. 0+175 Km (Khal)	1 Vent-1.5mX1.8m 0.00	6,502,332	Main
	Re-excavation of Beel Bolli Khal	7.30	7,789,728	Main
	Part-A: Beel Bolli Khal Regulator at Ch.0+050Km (Khal)	3 Vent-1.5mX1.8m 0.00	9,965,017	Main
	Part-B: Elevated WMCA Office Stair and Related Item	Size: 12mX6m 0.00	1,707,061	Main
Bajitpur SSWRDSP-2 SP25250, Baliardi Subproject, CAD, Union : Baliardi, HO Date: 29/08/2011				
	Header Tank	Size: 6.5mX3.5m 0.00	361,943	Main
	Buried Pipe Network System	5470m 0.00	11,006,514	Main
	Part-A: Electrical estimate of Baliardi CAD Subproject	0.00	2,332,125	PSSWRSP
	Part-A: Construction of Pumping Platform of Biliardi CAD S	0.00	1,748,122	PSSWRSP
Hossainpur SSWRDSP-2 SP25209, Hazipur-Porabari Subproject, FMD&WC, Union : Jinari, HO Date: 01/06/2009				
	Porabari Regulator at Ch. 6+828Km (Khal)	1 Vent-1.5mX1.8m 0.00	3,798,406	Main
	Katihari Regulator at Ch. 0+135Km(Khal)	1 Vent-1.5mX1.8m 0.00	3,130,060	Main
	Re-sectionig of Embankment	5.37	1,653,292	Main
	Re-excavation of Katihari khal	2.16	142,511	Main
SSWRDP-JICA SP35187, Rupsha Beel Sonadal Subproject, DR&WC, Union : Pumdi, HO Date:				
	Re-excavation of Gajaria Khal	3.12	2,612,735	Main
	Re-excavation of Sonadal Khal	1.10	994,592	Main
	Re-excavation of Sahedal Khal	1.65	633,857	Main
	Part-A: Gajaria Khal WRS-1 at Ch.0+100Km (Khal)	2 Vent-1.5mX1.8m 0.00	5,621,126	Main
	Part-B: Gajaria Khal WRS-2 at Ch.2+400Km (Khal)	2 Vent-1.5mX1.8m 0.00	2,959,182	Main
	PArt-C: Sonadal Khal WRS at Ch.0+050Km (Khal)	1 Vent-1.5mX1.8m 0.00	4,597,028	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	2,023,607	Main
SP35223, Char Jamail-Narsundha Khal Subproject, FMD&WC, Union : Araibaria, HO Date:				
	Part-A: Narsundha Khal Regulator at Off-take of Narsundha	3 Vent-1.5mX1.8m 0.00	10,970,096	Main
	Part-B: Kaona Khal Regulator at place of existng culvert	1 Vent-1.5mX1.8m 0.00	4,528,943	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	906,593	Main
	Re-excavation of Narsundha Khal	0.73	2,026,684	Main
Itna SSWRDP-JICA SP33084, Chandrapur Subproject, FMD, Union : Chowganga, HO Date: 26/04/2015				
	Re-sectioning of Embankment	5.40	2,919,027	Main
	Part-A: Chandrapur Regulator at Ch. 0+250Km (Khal)	2 Vent-1.2mX1.2m 0.00	7,925,231	Main
	Part-B: Badati Regulator at Ch. 4+350Km (Embkt)	2 Vent-1.2mX1.2m 0.00	3,971,464	Main
	Part-C:Mathikater Bundth Regulator at Ch.7+600Km(E	1 Vent-1.2mX1.2m 0.00	2,734,566	Main
	Re-excavation of Chandrapur Khal	1.80	1,567,460	Main
	Reference Lined Sections	0.00	81,237	Main
	Part-D: WMCA Office and Related Item	0.00	1,418,557	Main
	Re-sectioning of Embankment (Addll.)	5.40	1,226,736	Main
SP35175, Badla N. Sahila Subproject, FMD, Union : Baribari, Badla, HO Date: 15/03/2016				
	Part-A: Simer Khal Regulator at Ch.0+105Km (Embkt)	1 Vent-1.5mX1.8m 0.00	4,816,040	Main
	Part-B: Protective Works of Embankment on Both Sides of	L=120m Length 0.00	2,119,337	Main
	Part-D: Protective Works of Embankment on Both Sides of	L=180m Length 0.00	2,844,081	Main
	Reexcavation of Simer Khal, Link Khal & Kunia Khal	0.90	476,114	Main
	Part-C: Varer Khal Regulator at Ch.2+132Km (Embkt)	1 Vent-1.5mX1.8m 0.00	4,394,219	Main
	Part-E: Kunia Khal Regulator at Ch.0+810Km	1 Vent-1.5mX1.8m 0.00	4,784,924	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-F: WMCA Office and Related Item	Size: 12mX6m 0.00	1,224,554	Main
	Resectioning of Simer Khak to Verar Embankment	2.07	1,043,564	Main
	Resectioning of Baribari Village-Kunia Embankment	1.00	440,769	Main
SP35176, Simulbag-Tiyarkona Subproject, FM, Union : Boribari, HO Date: 01/07/2015				
	Part-A: Kuttamara Bundh Regulator at Ch.1+078Km	2 Vent-1.5mX1.8m 0.00	6,531,457	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,230,700	Main
	Part-B: Protective Works of Emankment on Both Sides of K	L=110m Long 0.00	2,395,470	Main
	Resectioning of Simulbag-Agalpa Beel Embankment	1.52	634,982	Main
	Resectioning of Tiyarkona-Udlir Dhair Embankment	1.20	700,570	Main
	Uglir Dhair Clouser	0.00	525,455	Main
SP35203, Dhara Subproject, FM, Union : Raituti, HO Date: 26/07/2015				
	Re-excavation of Ghukri Khal	3.20	1,752,074	Main
	Re-sectioning of Dhara Embankment	4.20	3,273,511	Main
	Part-A: Ghukri Khal Regulator	2 Vent-1.5mX1.8m 0.00	8,764,375	Main
	Part-B: WMCA office with related facilities	Size: 12mX6m 0.00	2,025,148	Main
SP35207, Elongjuri Khorer Khal Subproject, FMD, Union : Elonjuri, HO Date: 13/03/2016				
	Part-A: Deorkila Regulator at Ch.0+065Km	1 Vent-1.5mX1.8m 0.00	5,782,486	Main
	Part-B: Kara Khal Regulator at Ch.0+070Km	1 Vent-1.5mX1.8m 0.00	7,049,851	Main
	Re-excavation of Deorkila Khal	0.90	819,034	Main
	Re-excavation of Kara Khal	0.35	591,791	Main
	Bank Closure of Kalaitashia river	0.25	398,327	Main
	Part-C: WMCA Office with Related Item	Size: 12mX6m 0.00	1,581,425	Main
SP35213, Dhanpur Subproject, FMD, Union : Dhanpur, HO Date: 02/12/2015				
	Part-A: Dukra Regulator at Ch.0+034 Km (Khal)	1 vent-1.5mX1.8m 0.00	4,180,826	Main
	Part-F: Drainage Sluice-5 at Ch. 8+410 Km (Embkt.)	1 Vent-0.9mX1.2m 0.00	2,345,695	Main
	Part-G: WMCA Office with Related Items	Size: 12mX6m 0.00	1,338,626	Main
	Re-excavation of Dukra Khal	0.12	37,383	Main
	Re-sectioning of submersible Embankment	11.06	7,827,845	Main
	Part-B: Drainage Sluice-1 at Ch. 1+447Km (Embkt.)	1 Vent-0.9mX1.2m 0.00	1,995,856	Main
	Part-C: Drainage Sluice-2 at Ch. 5+321 Km (Embkt.)	1 Vent-0.9mX1.2m 0.00	2,165,613	Main
	Part-D: Drainage Sluice-3 at Ch. 5+516 Km (Embkt.)	1 Vent-0.9mX1.2m 0.00	2,261,259	Main
	Part-E: Drainage Sluice-4 at Ch. 7+245 Km (Embkt.)	1 Vent-0.9mX1.2m 0.00	2,380,111	Main
Karimganj SSWRDP-JICA				
SP33057, Saguli-Prayag Beel Subproject, FMD, Union : Sutarpara, HO Date: 03/11/2015				
	Part-A: Repair of Exisiting Prayag Beel Regulator	2 Vent-2.0mX2.0m 0.00	897,179	Main
	Part-B:Protective Works in Embkt. from Ch. 1+550k	Length= 260m 0.00	1,160,000	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,870,450	Main
	Re-sectioning of Embankment	1.70	1,929,559	Main
	Protective works by bamboo palisading and filled gunny ba	0.00	431,740	Main
SP33102, Chang Noagaon-Rangamati Khal Subproject, FMD, Union : Sutarpara, HO				
	Reexcavation of Rangamati Khal	2.00	1,080,367	Main
	Reexcavation of Pangair Dhair Khal	1.40	1,124,420	Main
	Resectioning of Rangamati Embankment	1.90	1,995,665	Main
	Resectioning of Ujanhati Embankment	0.90	395,767	Main
	Part-A: Rangamati Khal Regulator at Ch.0+050Km	1 Vent-1.5mX1.8m 0.00	6,011,404	Main
	Part-B: Pangair Dhair Khal Regulator at Ch.0+064Km	1 Vent-1.2mX1.5m 0.00	5,124,688	Main
	Refernece Lined Section (4 nos.)	0.00	144,503	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,772,700	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP24115, Bara Bundh-Natun Khal Subproject, FMD&WC, Union : Singpur, HO Date:				
	Re-sectioning of Embankment	3.60	526,516	Main
	Natun Khal WRS at Ch.0+040km	2 Vent-1.5mX2.0m & 1	4,050,016	Main
	Slope Protection Works	at Ch. 2+000 km to 2+060	124,725	PSSWRSP
	Re-sectioning of Embankment	3.20	3,039,819	PSSWRSP
SSWRDP-JICA				
SP33052, Dubir Boro Dhair Subproject, FM, Union : Singpur, HO Date: 27/04/2015				
	Part-A: Dubi Regulator at Ch. 0+793Km	4 Vent-1.5mX1.8m 0.00	7,086,782	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,531,132	Main
	Re-sectioning of Embankment (Regular)	1.06	710,730	Main
	Resectioning of Embankment (Emergency)	0.09	139,948	Main
	Part-B: Protection Work of Embankment near Dubi Reg	0.15	2,118,721	Main
SP33083, Roda Nodir Khal (Pudda Beel) Subproject, DR&IRR, Union : Nikli, HO Date:				
	Reexcavation of Roda Pudda Khal	2.40	3,841,930	Main
Pakundia				
SSWRDSP-2				
SP23087, Sukhia Padmakuri Beel Subproject, DR&WC, Union : Sukhia, HO Date:				
	Sukhia Padmakuri Khal Re-excavation	5.78	800,287	Main
	WRS on Sukhia Padmakuri Khal at Ch. 0+070Km	3 Vent-1.50mX1.80m 0.00	3,381,852	Main
	O&M Shed	9.00mX5.00m 0.00	310,560	Main
	Part-A: Re-excavation of Sukhia Paddakuri Khal	5.50	2,218,527	PSSWRSP
	Part-B: Re-excavation of Sukhia Paddakuri Branch Khal	1.04	882,812	PSSWRSP
SSWRDP-JICA				
SP34149, Annesha Dighi Subproject, FMD, Union : Barudia, HO Date: 25/11/2015				
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,111,453	Main
	Resectioning of Embankment	2.10	1,660,146	Main
	Reexcavation of Bejurnala Khal	0.50	227,172	Main
	Part-A: Bejurnala Khal Regulator	2 Vent-1.5mX1.8m 0.00	6,653,558	Main
Sadar				
SSWRDSP-2				
SP23081, Korsha Kariail Subproject, FMD&WC, Union : Korsa Karail, HO Date: 29/07/2009				
	Nagdora Khal Re-excavation	4.52	988,267	Main
	Nagdora Regulator at Ch. 0+040 Km (Khal)	3 Vent-1.50mX1.80m 0.00	6,603,415	Main
SP25323, Majikhpapan Subproject, DR&WC, Union : Majikhal, HO Date: 19/12/2011				
	Kaliakuri Khal Regulator at Ch. 0+030 km	4 Vent-1.5mX1.8m 0.00	9,043,680	Main
	Re-excavation of Kalia kuri Khal	4.17	2,364,847	PSSWRSP
SSWRDP-JICA				
SP33103, Shaylon Beel Subproject, FMD&WC, Union : Danapathuli, HO Date: 01/06/2014				
	Reexcavation of Kaibudia Khal	3.05	2,901,471	Main
	Resectioning of Embankment	1.00	484,215	Main
	Referenece Lined Sections (3 nos.)	0.00	131,234	Main
	Part-A: Kaibudia Khal Regulator at Ch.0+050Km	2 Vent-1.2mX1.5m 0.00	4,637,800	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,572,816	Main
SP35177, Langer Khal Subproject, DR&WC, Union : Josodal, HO Date: 24/04/2016				
	Part-A: Langer Khal WRS at Ch. 1+200Km	2 Vent-1.5mX1.8m 0.00	6,281,649	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,216,103	Main
	Re-excavation of Langer Khal i/c Dykes on Both Banks	5.40	9,406,679	Main
	Re-excavation of Gabon Khal	0.90	606,891	Main
	Re-excavation of Bhamka Khal	0.75	334,717	Main
Tarail				
SSWRDSP-2				
SP23048, Kajla Subproject, FMD, Union : Dhamiha, HO Date: 24/07/2008				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Embankment Re-sectioning	1.53	142,536	Main
	Kestopur Regulator at Ch.3+457 with Slope Protecti	1 Vent-1.50mX1.80m 0.00	2,097,864	Main
	Sesukandi Regulator at Ch.1+525km	1 Vent-1.50mX1.80m 0.00	2,108,251	Main
	Sajnar Khal Pipe Sluice at Ch.0+715km	1 Vent-0.90m Dia 0.00	1,554,761	Main
	O&M Shed	9.00mX5.00m 0.00	272,712	Main
	Re-excavation of Sajnar Khal	0.89	223,693	Main
	Re-excavation of Sesukandi Kata Khal	0.68	51,801	Main
	Approach Road of Kestupur Regulator	0.05	133,111	Main
	Part-A: Re-excavation of Sechuakandi khal	2.40	709,396	PSSWRSP
	Part-B: Re-excavation of Kestupur khal	0.68	346,534	PSSWRSP

SSWRDP-JICA

SP32030, Phuleswari-Sonai Beel Subproject, FMD, Union : Dhala, HO Date: 26/01/2015

Part-A: Kumarkanda Regulator at Ch.2+952Km (Emkt)	2 Vent-1.5mX1.8m 0.00	5,607,808	Main
Part-B: Ghuliakuri Regulator at Ch. 4+325Km (Embt)	1 Vent-1.2mX1.5m 0.00	3,172,337	Main
Part-C: WMCA Office and Related Item	Size:12mX6m 0.00	1,050,219	Main
Resectioning of Embankment	4.65	2,619,597	Main

Madaripur (Total SPs : 33 Nos.)

Kalkini

SSWRDSP-2

SP25187, Madhukhali Subproject, DR&IRR, Union : Kazibakai, HO Date: 10/11/2008

Re-excavation of Madhukhali Khal	5.20	2,475,174	Main
O&M Shed	Size: 9mX5m 0.00	474,460	Main
Site Development for O&M Shed	0.00	200,716	Main

SSWRDP-JICA

SP32020, Bangsari Subproject, DR&IRR, Union : Banshgari, HO Date: 22/08/2013

Part-A: WMCA Office and Related Items	Size: 12mX6m 0.00	894,760	Main
Re-excavation of Baraitala Khal	3.30	2,504,588	Main
Re-excavation of Bhaduria Khal	3.20	2,342,478	Main
Re-excavation of Nayakandi Khal	1.50	1,023,748	Main
Re-excavation of Nayakandi Link Khal	0.60	498,217	Main
Reference Lined Section	0.00	243,692	Main

SP34112, Alipur-Enayetnagar Subproject, DR&IRR, Union : Enayetnagar, HO Date:

Re-excavation of Alipur Baor Khal	1.66	3,310,969	Main
Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,268,821	Main
Reference Lined Sections (7 nos.)	0.00	34,796	Main
Re-excavation of Alipur-Enayetnagar Khal	3.90	5,498,697	Main
Re-excavation of Maharaddir Khal	2.30	1,129,810	Main
Re-excavation of Alipur Khal	2.20	3,613,797	Main
Re-excavation of Kacharikandi Khal	1.21	1,513,318	Main
Re-excavation of Maharaddir Char Khal	1.29	2,037,009	Main

SP34113, Urarchar-Snanghata-Akalbaris Khal Subproject, DR&IRR, Union : Banshgari, HO

Re-excavation of Snanghata Boro Khal	2.90	2,345,210	Main
Re-excavation of Sonir Khal	0.92	1,259,077	Main
Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,276,929	Main
Re-excavation of Urar Char-Snanghata Khal	1.70	1,730,289	Main
Re-excavation of Bjabani Sankar Khal	2.10	2,698,568	Main
Re-excavation of Urarchar-Mujibar Rarer Khal	0.91	481,423	Main
Re-excavation of Snanghata Branch Khal-1	0.18	133,705	Main
Re-excavation of Snanghata Branch Khal-2	0.30	78,900	Main
Re-excavation of Snanghata Branch Khal-3	0.66	422,130	Main

SP34114, Char Lakshimpur Khal Subproject, DR&IRR, Union : Alinagar, HO Date:

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,196,195	Main
	Re-excavation of Char Laxmipur Khal	9.70	16,916,863	Main
	Re-excavation of Gabtali Khal	0.65	1,392,531	Main
	Re-excavation of Kolchari Swasthal Khal	1.03	2,357,794	Main
	Re-excavation of Sardar Bari Khal	1.08	1,135,801	Main
	Re-excavation of Ray Sardar Bari Khal	2.02	5,486,451	Main
	Part-A: Re-excavation of Khan Bari Khal	1.10	0	SSWRDP-JICA-2
	Part-B: Re-excavation of Hindu Para Khal	1.50	0	SSWRDP-JICA-2
	Part-C: Re-excavation of Ray Sardar Bari khal	1.10	0	SSWRDP-JICA-2
	Part-D: Construction of Reference Bed Block	0.00	0	SSWRDP-JICA-2
SP34136, Alimabad Khal Subproject, DR&IRR, Union : Kayaria, HO Date: 06/01/2015				
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,297,477	Main
	Re-excavation of Dakshin Char Alimabad Khal	1.25	1,420,288	Main
	Re-excavation of Rainandapur Khal	0.85	1,279,669	Main
	Re-excavation of Purba Char Alimabad Khal	4.05	5,979,612	Main
SP34145, Asramer Khal Subproject, DR&IRR, Union : Dasar, HO Date: 07/01/2015				
	Reference Lined Section (1 no.)	0.00	28,500	Main
	Part-A: WMCA Office and Related Items	Size: 12mX6m 0.00	1,208,296	Main
	Re-excavation of Asramer Khal	4.70	10,562,404	Main
	Re-excavation of Basa Bari Khal	2.12	2,167,216	Main
	Re-excavation of Mohori Bari Khal	1.50	1,656,933	Main
	Re-excavation of Purbo Kamlapur Khal	1.62	3,841,356	Main
SP35234, Char Palordi-Jojira Subproject, DR&IRR, Union : Ramjanpur, HO Date:				
	Re-excavation of Char Palordi Khal	5.36	6,493,918	Main
	Re-excavation of Ramerhat Khal	2.80	2,431,998	Main
	WMCA Office and Related Item	Size: 12mX6m 0.00	1,219,300	Main
	Site Development of WMCA Office	0.00	98,375	Main
	Installation of Deep Set Tubewell for WMCA Office	0.00	76,673	Main
SP35238, Auliar Char Subproject, DR&IRR, Union : Banshgari, HO Date: 13/09/2015				
	Site Development of WMCA Office	0.00	92,216	Main
	Installation of Tube Well for WMCA Office.	0.00	0	Main
	Re-excavation of Gajaria Khal (Extension)	1.50	1,260,651	Main
	Re-excavation of Boro Kachna Khal	4.03	3,425,396	Main
	Re-excavation of Choto Kachna Khal	1.52	2,133,406	Main
	Re-excavation of Dhakir Hat Khal (Extension)	2.25	1,354,924	Main
	WMCA Office and Related Item	Size: 12mX6m 0.00	1,448,395	Main
	Re-excavation of Auliar Char Khal	2.76	2,442,889	Main
	Re-excavation of Nayakandi Khal	0.73	197,386	Main
	Re-excavation of Auliar Char Branch Khal	0.30	314,345	Main
	Re-excavation of Kalinagar Khal	1.72	1,477,984	Main
	Re-excavation of Dhakairhati Khal	1.00	170,266	Main
	Re-excavation of Auliar Char Sahurhati Khal	0.94	368,841	Main
	Re-excavation of Gajaria Khal	3.14	3,074,332	Main
SP35239, Bhanga Bridge- Moddya Dhulgram Khal Subproject, DR&IRR, Union : Baligram,				
	Re-excavation of Maddhya Dhulgram Khal	10.01	7,838,734	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,460,500	Main
	Re-excavation of Bothla Khal	1.50	1,785,210	Main
	Re-excavation of Gungoria Khal	2.30	3,234,531	Main
	Site Development of WMCA Office	0.00	106,000	Main
SP35240, Palordi-Alinagar Subproject., DR&IRR, Union : Alinagar, HO Date: 17/09/2015				
	Re-excavation of Uttar Kanaipur-Jorerpar Khal	3.90	4,872,808	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Mirakhandi Khal	2.35	1,956,650	Main
	Re-excavation of Link Khal	0.43	330,432	Main
	Re-excavation of Kalinagar-Masjikhola Khal	0.00	2,088,376	Main
	Re-excavation of Dakshin Kanaipur Khal	2.30	2,080,175	Main
	WMCA and Related Item	Size: 12mX6m 0.00	884,592	Main
	Site Development of WMCA Office	0.00	67,443	Main
	Part-A: Re-excavation of Jhorerpar khal	4.50	3,883,061	SSWRDP-JICA-2
	Part-B: Re-excavation of Kasimpur khal	0.70	722,038	SSWRDP-JICA-2
	Part-C: Re-excavation of Lamchori khal	0.63	1,420,389	SSWRDP-JICA-2
	Part-D: Re-excavation of Minajdi khal	1.80	1,558,084	SSWRDP-JICA-2
	Part-E: Re-excavation of Pachim Minajdi khal	2.10	1,284,109	SSWRDP-JICA-2
	Part-F: Re-excavation of Ramnagar khal	2.59	2,727,075	SSWRDP-JICA-2
	Part-G: Re-excavation of Sadipur khal	2.65	1,783,534	SSWRDP-JICA-2
	Part-H: Construction of Reference Lined Section	0.00	253,315	SSWRDP-JICA-2
SP35250, Anderchar Subproject, DR&IRR, Union : Sahebrampur, HO Date: 15/09/2015				
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,530,944	Main
	Re-excavation of Anderchar Khal including Reference Bed	2.48	1,434,722	Main
	Re-excavation of Anderchar Branch Khal	0.71	1,063,154	Main
	Re-excavation of Maddhya Anderchar Khal including Refer	1.60	1,469,413	Main
	Re-excavation of Maddhya Anderchar Branch Khal	0.31	308,096	Main
	Re-excavation of Natun Anderchar Khal including Fish She	1.05	237,844	Main
	Installation of Deep Tubewell of Ander Char Subproject	0.00	80,660	Main
SP35252, Uttarkandi-Mathabhanga Subproject, DR&IRR, Union : C.D.Khan, HO Date:				
	WMCA Office and Related Item	Size: 12mX6m 0.00	1,552,253	Main
	Re-excavation of Dhakikandi Khal	2.90	1,874,779	Main
	Re-excavation of Noakandi Khal including Construction Re	3.90	1,994,468	Main
	Re-excavation of Uttarkandi Khal including Construction Re	4.20	2,472,477	Main
	Re-excavation of Dhakikandi Branch Khal	0.60	359,845	Main
	Re-excavation of Monur Khal	0.66	379,152	Main
	Site Development of WMCA Office	0.00	68,820	Main
Rajoir SSWRDSP-1				
SP14202, Baikkar Beel DR Subproject, DR, Union : Amgram, HO Date: 22/01/2003				
	Baikker Khal Re-excavation	6.19	554,545	Main
SP14207, Sutarkandi FCD Subproject, FCD, Union : Bajitpur, HO Date: 18/08/2002				
	Embankment Re-sectioning	10.69	3,311,843	Main
	Kotalia Khal Re-excavation	2.82	519,764	Main
	Box Sluice at Ch.5+740	2-V(1.2mX1.2m)	1,554,001	Main
	Box Sluice at Ch.7+362	1-V(1.2mX1.2m)	1,296,575	Main
	Pipe Sluice at Ch.2+025m	1-V(900mm Dia.)	1,168,265	Main
SSWRDSP-2				
SP25325, Kadambari Subproject, FMD, Union : Kadambari, HO Date: 24/10/2013				
	Re-excavation of Kadambari Beel Khal	3.30	1,412,504	Main
	Re-excavation of Laxmipur-Puradia Khal	2.10	171,938	Main
	Re-excavation of Babur Khal	1.90	595,299	Main
	Re-excavation of Babur Khal Goplagonj Point	4.90	1,735,176	Main
	Re-excavation of Babu Khal (Gopalgonj Part)	4.89	2,487,732	PSSWRSP
	Re-excavation of Babu Khal (Madaripur part)	1.87	889,348	PSSWRSP
	Re-excavation of Laxmari-Puradia Khal	2.10	2,219,878	PSSWRSP
SSWRDP-JICA				
SP32032, Kamarer Khal Subproject, DR&IRR, Union : Bajitpur, HO Date: 22/08/2013				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	WMCA Office and Related Items	Size: 12mX6m 0.00	893,267	Main
	Re-excavation of Kamarer Khal	8.32	3,941,324	Main
	Re-excavation of Bulkir Beel Link Khal	2.10	209,130	Main
	Re-excavation of Kamlapur Khal	1.50	310,707	Main
	Reference Lined Section	0.00	345,391	Main
SP33078, Amgram Subproject, DR&IRR, Union : Amgram, HO Date: 10/04/2016				
	Reexcavation of Amgram-Chitkibari-Bilpabania Khal	6.60	1,206,709	Main
	Reexcavation of Amgram-Khagradia-Lakhanda Khal	6.60	1,948,340	Main
	Reexcavation of Vennabari Khal	1.60	1,783,880	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,222,562	Main
SP35241, Chhoto Kumar Nadi-Amgram Subproject, DR&IRR, Union : Amgram, HO Date:				
	Re-excavation of Hogla-Amgram Khal including Refferance	5.75	4,562,564	Main
	WMCA Office and Related Item	Size: 12mX6m 0.00	928,844	Main
SP35242, Kalibari Khal Subproject, DR&IRR, Union : Kabirajpur, HO Date: 10/04/2016				
	Re-excavation of Kalibari Khal	6.80	5,149,875	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,303,680	Main
SP35257, Baliar Beel Boro Khal Subproject, DR&IRR, Union : Isubpur, HO Date:				
	Re-excavation of Boro Khal i/c Reference Bed Blocks	3.75	1,903,864	Main
	Re-excavation of Serestantala Khal i/c Reference Bed Bloc	4.00	2,865,600	Main
	WMCA Office and Related Items	Size: 12mX6m 0.00	1,273,184	Main
Sadar				
SSWRDSP-1				
SP12017, Housdi-Patiladi FCD Subproject, FCD, Union : Dudkhali, HO Date: 12/04/2002				
	Embankment Re-sectioning	6.31	1,833,204	Main
	Anchra Khal Re-excavation	0.30	7,980	Main
	Fakirbari Khal Re-excavation	0.51	37,475	Main
	Fakirbari Regulator	1-V(1.2mx1.5m)	1,591,161	Main
	Housdi Regulator	1-V(1.2mx1.2m)	1,647,315	Main
	Durgabari Regulator	1-V(1.0mx1.0m)	2,156,608	Main
	Balsabari Box Sluice	1-V(1.0mx1.0m)	740,073	Main
	Anchra Box Sluice	1-V(1.0mx1.0m)	906,416	Main
	Embankment Protection Works Ch.0+000m-0+425m		453,017	Main
	Namobari Pipe Sluice	1-V(900mm Dia)	734,483	Main
SP14208, Kumrakhali DR & WCS Subproject, DR&WC, Union : Pearpur, HO Date:				
	Kumarkhali Khal Re-excavation	4.43	1,040,248	Main
	Mongola-Bhangola Khal Re-excavation	1.32	29,648	Main
	Anchar Kata Khal Re-excavation	1.54	106,520	Main
	Kumarkhali WRS at Ch.0+150m	2-V(1.5mX1.8m)	2,389,268	Main
	Pearpur WRS at Ch.4+300m	1-V(1.2mX1.5m)	2,377,918	Main
SP14209, Balsa Chandibardi FCD Subproject, FCD, Union : Dudkhali, HO Date:				
	Embankment Re-sectioning	5.82	4,653,609	Main
	Boalia-Chandibordi Khal Re-excavation	2.55	562,175	Main
	Pipe Sluice at Ch.3+310m	1-V(900mm Dia.)	1,630,405	Main
	Pipe Sluice at Ch.4+180m	1-V(900mm Dia.)	1,604,031	Main
	Regulator at Ch.5+820m	1-V(1.2mX1.2m)	1,601,615	Main
	Box Sluice at Ch.7+480m		1,954,054	Main
	Regulator at Ch.8+100m	2-V(1.2mX1.2m)	1,959,102	Main
SP15357, Natun Rajarhat-Char Nashna FC Subproject, FC, Union : Bahadurpur, HO Date:				
	Embankment Re-sectioning	4.96	2,557,733	Main
	Closure	0.02	34,047	Main
SSWRDSP-2				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP24174, Mostafapur Subproject, DR&WC, Union : Mostafapur, HO Date: 11/02/2009				
	Mostafapur DC Khal Regulator at Ch. 0+030Km	1 Vent-1.5mX1.8m 0.00	3,896,486	Main
	Mostafapur DC Khal WRS at Ch. 8+160Km	3 Vent-1.5mX1.8m 0.00	5,791,962	Main
	Re-excavation of DC Khal	7.75	4,277,010	Main
	O&M Shed	Size: 12mX6m 0.00	284,810	Main
	Part-A: Construction of RCC Lined Canal	at ch. 0+000 km to 0+750 km	2,475,114	PSSWRSP
SSWRDP-JICA				
SP32028, Lauer Beel Subproject, DR&IRR, Union : Kendua, HO Date: 22/08/2013				
	Re-excavation of Bahadurpur-Chauhuddi Khal	7.70	3,214,729	Main
	Part-A: WMCA Office and Related Items	Size: 12mX6m 0.00	871,245	Main
	Reference Lined Section	0.00	45,213	Main
SP32038, Laxmiganj-Rupriya Khal Subproject, DR&IRR, Union : Rasti, HO Date:				
	Re-excavation of Kaligonga Khal	0.50	315,689	Main
	Part-A: Box Culvert at 1+205Km	2V x 4.0 m x 4.2m RCC Box	1,849,121	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,283,000	Main
	Reference Lined Section (6 nos.)	0.00	125,353	Main
	Re-excavation of Laxmigonj-Rupriya Khal	3.55	4,936,222	Main
	Re-excavation of Char Muguria Khal	0.95	516,609	Main
	Re-excavation of Kaligonga Link Khal	0.30	295,304	Main
	Re-excavation of Putia Khal	2.00	1,776,153	Main
SP34139, Shirkhara Subproject, DR&WC, Union : Sirkhara, HO Date: 26/10/2015				
	Reexcavation of Morolpara Khal	1.10	1,023,100	Main
	Reexcavation of Gonchi-Kuciamora Khal	8.15	11,577,532	Main
SP35251, Baherchar Subproject, DR&IRR, Union : Panchkhola, HO Date: 25/10/2015				
	Re-excavation of Baherchar Khal including Reference Bed	4.10	5,202,105	Main
	Re-excavation of Jafarabad Branch Khal-2 including Refera	0.70	819,982	Main
	Re-excavation of Jafarabad Masher Khal including Referan	2.40	2,775,764	Main
	Re-excavation of Jafarabad Branch Khal-1	1.76	1,549,471	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,065,300	Main
SP35255, Gaidi Khal Subproject, DR, Union : Ghatmajhi, HO Date: 25/10/2015				
	Re-excavation of Gaidi Branch Khal	4.00	2,213,246	Main
	Re-excavation of Kordi Khal	4.10	2,470,524	Main
	Re-excavation of Kordi Branch Khal	0.50	391,589	Main
	WMCA Office and Related Item	Size: 12mX6m 0.00	1,008,688	Main
SP35262, Char Bajitpur Subproject, DR&IRR, Union : Dhurail, HO Date: 26/10/2015				
	WMCA Office and Related Item	Size: 12mX6m 0.00	1,022,460	Main
	Re-excavation of Mollakandi Khal i/c reference Bed Block	1.12	1,099,754	Main
	Re-excavation of Chawkidarbari Khal i/c reference Bed Blo	0.60	662,867	Main
	Re-excavation of Sardarkandi Khal i/c reference Bed Block	1.50	1,972,115	Main
	Re-excavation of Mirdhakandi Khal i/c reference Bed Block	0.74	1,305,680	Main
	Re-excavation of Joariar Baorer Khal i/c reference Bed Blo	2.40	790,190	Main
Shibchar				
SSWRDSP-2				
SP25194, Char Bachamara Subproject, FMD, Union : Dattapara, HO Date: 25/04/2010				
	Re-sectioning of Embankment	7.30	5,451,872	Main
	Re-excavation of Ana Molla Khal	0.50	89,397	Main
	Re-excavation of Panja Khal	1.40	235,798	Main
	Ana Molla Khal Regulator at Ch. 0+074Km(Khal)	1 Vent-1.5mX1.8m 0.00	3,512,245	Main
	Panja Sikder Khal Regulator at Ch. 0+287 Km (Khal)	1 Vent-1.5mX1.8m 0.00	2,674,874	Main
	O&M Shed	Size: 9mX5m 0.00	401,544	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Manikgonj (Total SPs : 11 Nos.)				
Daulatpur SSWRDSP-2 SP25264, Rauha-Naihati Subproject, FMD, Union : Khalshi, HO Date: 30/06/2009				
	Satani Khal Regulator at Ch.0+025Km	1 Vent-1.5mX1.8m 0.00	2,831,798	Main
	Pipe Sluice at Ch.3+740m (Embk)	1 Vent-0.9m Dia 0.00	936,019	Main
PSSWRSP SP44088, Roha Kumargara Beel Subproject, FMD, Union : Khalshi, HO Date: 15/02/2018				
	Part-B: Re-sectioning of an Embankment	4.07	5,387,329	Main
	Part-A: Raninagar Khal Regulator	at Ch. 0+496 0.00	0	Main
	Part-A: Re-excavation of Raninagar Khal	0.70	761,730	Main
	Part-B: WMCA Office & others	12mX6m 0.00	0	Main
Ghior SSWRDSP-2 SP25206, BKS Subproject, FMD&WC, Union : Balia Khora, HO Date: 25/04/2010				
	Re-excavation of Binora-Angarpara Khal	1.90	785,385	Main
	Re-excavation of Kusunda-Bamna Khal	1.10	312,842	Main
	Binora Khal Regulator at Ch. 0+050Km (khal)	2 Vent-1.5mx1.8m 0.00	4,371,478	Main
	Kusunda Khal Regulator at Ch. 0+145Km (khal)	2 Vent-1.5mx1.8m 0.00	3,842,851	Main
	O&M Shed	Size: 9mX5m 0.00	499,509	Main
PSSWRSP SP41009, Kusta-Thakurkandi Subproject, FMD&WC, Union : Gheor, HO Date: 05/09/2017				
	Part A: Thakurkandi Khal Regulator	1V-1.5mX1.8m 0.00	5,117,312	Main
	Part B: WMCA office & related works	12mX6m 0.00	1,147,774	Main
	Part A: Re-excavation of Thakurkandia Khal	0.61	272,593	Main
	Part B: Re-excavation of Kusta Approach Khal	0.28	675,564	Main
	Part C: Re-sectioning of Ichamoti Approach Road	0.83	1,173,710	Main
	Part D: Re-sectioning of Narchi Approach Road	0.50	429,403	Main
	Part E: Reference Lined section	0.00	15,704	Main
Harirampur SSWRDSP-2 SP23079, Jatrapur-Ichamati Subproject, FMD&WC, Union : Boira, HO Date: 14/01/2009				
	Ichhamoti Regulator at Ch.0+050km	2 Vent-1.50mX1.80m 0.00	5,315,519	Main
	O&M Shed	9.00mX5.00m 0.00	280,344	Main
	Jatrapur-Ichamati Khal Re-excavation	3.80	1,558,876	Main
PSSWRSP SP41003, Baika-Bara Hapania-Jhikutia Subproject, FMD, Union : Balla, HO Date:				
	Part-A: Re-excavation of Brahmondi Khal	0.88	895,697	Main
	Part-A: Lohachara Regulator	1 Vent 1.5mX1.8m 0.00	5,745,742	Main
	Part-B: Brahmondi khal Pipe Sluice	1 Vent 900 mm dia 0.00	2,373,209	Main
	Part-C: Dakshin Gorail khal Pipe Sluice	1 Vent 900 mm dia 0.00	2,171,300	Main
	Part-D: WMCA office & others	12mX6m 0.00	937,184	Main
SP45209, Gopinathpur Beel Subproject, DR&WC, Union : Gopinathpur, HO Date:				
	Part-A: Bahadurpur khal Regulator	2v-1.50mX1.80m 0.00	11,940,664	Main
	Part-B: WMCA Office & others	12mX6m 0.00	1,559,332	Main
	Part-A: Re-excavation of Bahadurpur khal	2.20	3,930,190	Main
	Part-B: Re-Sectioning of Gopinathpur Embankment	3.00	6,171,072	Main
	Part-C: Construction of Reference Lined Section	0.00	100,370	Main
Saturia SSWRDSP-2 SP23056, Khalilabad Subproject, DR&WC, Union : Baliati, HO Date: 09/09/2007				
	Chandrakhal Khal Re-excavation	3.30	726,634	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Shibalay SSWRDSP-2 SP23108, Kasadah CAD Subproject, CAD, Union : Shibalay, HO Date: 29/10/2008	Khalilabad Khal Re-excavation	0.25	72,015	Main
	Khalilabad Pipe Sluice at Ch.0+030km (Khal)	1 Vent-0.90m dia 0.00	1,630,691	Main
	Embankment Re-sectioning	1.30	220,139	Main
Singair SSWRDSP-2 SP23066, Atrail Beel Subproject, DR&WC, Union : Balldhara, HO Date: 12/08/2009	Kasadah Irrigation System	3.81 Km 0.00	13,389,054	Main
	Kasadah Khal WRS at Ch. 1+900Km	1 Vent-1.50mX1.80m 0.00	2,146,626	Main
	O&M Shed	9.00mX5.00m 0.00	278,628	Main
	Kasadah Khal Check Structure at Ch. 0+865Km	1 Vent-1.50mX1.80m 0.00	1,036,539	Main
	Kasadah Khal Dyke	1.90	560,883	Main
	Part-A: Construction of 5 Nos Lined Canal	0.00	5,135,417	PSSWRSP
PSSWRSP SP44082, Volda Beel Subproject, DR&WC, Union : Charigram, Jamsha, HO Date:	Atrail Khal Re-excavation	1.80	927,897	Main
	Regulator at Ch.0+030 Km on Atrail Khal	2 Vent-1.50mX1.80m 0.00	4,797,214	Main
	O&M Shed	9.00mX5.00m 0.00	316,972	Main
	Re-sectioning of Atrail Beel Embankment	2.00	1,287,705	Main
Munshigonj (Total SPs : 4 Nos.)	Part-A: Re-excavation of Volda khal	1.90	2,420,305	Main
	Part-E: Bank Protection Work	0.00	2,411,087	Main
	Part-B: Re-Sectioning of Embankment	4.40	6,611,765	Main
	Part-A: Volda khal Regulator	(2v-1.2mx1.5m) 0.00	7,829,896	Main
	Lined reference section at 500m interval (4 nos.)	0.00	0	Main
	Part-C: Pipe Sluice at Ch.3+670 km	(1v-900mm dia) 0.00	2,501,981	Main
	Part-B: Pipe Sluice at Ch.1+240 km	(1v-900mm dia) 0.00	2,294,142	Main
	Part-D: Rehabilitation of existing culvert at ch.	at Ch. 0+350 km 0.00	1,627,934	Main
	Part-F: WMCA Office & Others	12mx6m 0.00	1,449,917	Main
	Part-C: Reference Lined Section	0.00	117,763	Main
Gazaria SSWRDSP-2 SP23089, Laxmipur Hoglakandi Subproject, DR&WC, Union : Imampur & Bausia, HO Date:	Pangasia Khal Re-excavation	4.62	1,735,830	Main
	Branch Khal-1 Re-excavation	3.10	785,699	Main
	Branch Khal-2 Re-excavation	4.10	1,633,941	Main
	Hoglakandi WRS at Ch. 0+090Km on Branch Khal-2	2 Vent-1.50mX1.80m 0.00	3,746,318	Main
	O&M Shed	12mX6m 0.00	302,860	Main
Sirajdikhan SSWRDSP-2 SP24121, Dosarpara-Kairakhola Subproject, DR&IRR, Union : Latabdi, HO Date:	Re-excavation of Khal Ichamoti Branch Khal	4.70	3,206,302	Main
Sreenagar SSWRDSP-2 SP24112, Alampur-Madankhali Subproject, DR&IRR, Union : Baraikhali, HO Date:	Re-excavation of Alampur-Madankhali Khal	6.94	2,444,566	Main
	Re-excavation of Sreedharpur Khal	1.23	402,635	Main
	Re-excavation of Baraikhali Khal	2.60	1,047,725	Main
	Re-excavation of Patalia Khal	0.33	77,143	Main
	Re-excavation of Madankhali Khal	2.44	409,076	Main
Tangibari				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
PSSWRSP				
SP45186, Chasri beel subproject, DR&WC, Union : Autshahi, HO Date: 20/08/2017				
	Part-A: Silimpur Chasri Regulator (2v-1.5mX1.8m) at Ch. 0	(2v-1.5mX1.8m) 0.00	7,147,995	Main
	Part-B: Silimpur Chasri khal Box culvert (1v-4.0mX4.5m) at	(1v-4.0mX4.5m) 0.00	3,356,709	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	1,323,326	Main
	Part-A: Re-excavation of Silimpur Chasri Khal & Construct	0.90	512,529	Main
Narayanganj (Total SPs : 3 Nos.)				
Araihazar				
SSWRDSP-2				
SP23061, Daibari-Barokhal Subproject, FMD&WC, Union : Brahmandi, HO Date:				
	Re-excavation of Katali Khal	0.37	52,459	Main
	Re-excavation of Daibari Khal	3.63	1,640,524	Main
	Baghmara WRS at Ch.0+400 Km (Daibari Khal)	1 Vent-1.50mX1.80m 0.00	2,799,210	Main
	Farida Bazar WRS at Ch. 0+000 Km (Khal)	1 Vent-1.20mX1.50m 0.00	3,312,801	Main
	Re-excavation of Baghmara Khal	0.90	475,406	Main
	Pipe Sluice at Ch. 3+600Km (Khal)	1 Vent-0.9m Dia 0.00	1,073,449	Main
	Pipe Sluice at Ch. 0+430Km on Baliagara Road.	1 Vent-0.9m Dia 0.00	715,632	Main
Bandar				
SSWRDSP-2				
SP24180, Kuripara-Langalbandh Subproject, FMD&WC, Union : Dhamgar, HO Date:				
	Kuripara Khal Regulator at Ch.4+800Km (Khal)	3 Vent-1.5mX1.8m 0.00	4,355,289	Main
	Laxmankhola Pipe Sluice at Ch.0+020Km (Khal)	1 Vent-0.9mm Dia 0.00	1,370,102	Main
	Brick Lined Canal	3050m 0.00	3,922,154	Main
Sonargaon				
Rubber Dam				
SP98009, Brahmaputra River Rubber Dam Project, WC, Union : Sanmondi, HO Date:				
	Brahamahputra Nodi Rubber Dam	Size: 54mX3.5m 0.00	52,947,000	Main
Narsingdi (Total SPs : 5 Nos.)				
Monohardi				
SSWRDSP-2				
SP23067, Arjunchar-Asadnagar Subproject, DR, Union : Chandanbari, HO Date:				
	Arjunchar Khal Re-excavation	1.87	231,987	Main
	Asadnagar Khal Re-excavation	1.03	97,018	Main
	Regulator at Ch. 0+200Km on Arjunchar Khal	1 Vent-1.50mX1.80m 0.00	1,803,094	Main
	Gujigarer Khal Re-excavation	0.28	48,345	Main
Raipura				
SSWRDSP-2				
SP23095, Barachar Subproject, FMD, Union : Uttar Bakharnagar, HO Date: 09/01/2008				
	Chandoler Khal Re-excavation	0.40	15,576	Main
	Chandoler Khal Regulator at Ch 0+030Km(Khal)	1 Vent-1.50mX1.80m 0.00	3,076,680	Main
	Barachar Uttarpara Embankment Resectioning	2.00	201,316	Main
SP24124, Adiabab PB Nagar Subproject, FMD, Union : Dowkarcahr, HO Date: 20/05/2009				
	PB Nagar Pipe Sluice at Ch.0+250Km	1 Vent-1.2m Dia 0.00	1,637,988	Main
PSSWRSP				
SP44105, Kumira Beel (Uttar Duba Khal), FMD, Union : Amirganj, HO Date: 09/07/2018				
	Part-A: Construction of Kumira Beel WRS	(2V1.50mX1.50m) 0.00	7,108,573	Main
	Part-B: Construction of Drainage Outlet	0.00	296,904	Main
	Part-C: Construction of Protection work	0.00	643,972	Main
	Part-D: Construction of WMCA Office & Others	12mX6m 0.00	1,557,382	Main
	Part-A: Re-excavation of kumira Beel	3.20	1,769,280	Main
	Part-B: Re-sectioning of Kakon river Emb.	1.43	736,744	Main
	Part-C: Onstruction of reference Lined Section	0.00	49,495	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Shibpur				
SSWRDSP-2				
SP24182, Bhurburia Khal Subproject, FMD&WC, Union : Ayubpur, HO Date: 18/06/2009				
	Bansirdia Pipe Sluice	1 Vent-0.9m Dia 0.00	309,250	Main
	Renovation of 4 nos. Pipe Culvert	0.00	830,873	Main
	Bhurburia Regulator at Ch.0+315Km (Khal)	1 Vent-1.5mX1.8m 0.00	2,486,389	Main
	O&M Shed	Size:12mX6m 0.00	333,452	Main
	Re-excavation of Bhurburia Khal	1.80	392,965	Main
Rajbari (Total SPs : 31 Nos.)				
Baliakandi				
SSWRDSP-1				
SP12020, Irsalbari-Madardoel FCD Subproject, FCD, Union : Baliakandi, HO Date:				
	Embankment Re-sectioning	4.07	1,175,796	Main
	Madhya Khal Box Sluice	1-V(0.9mX0.9m)	799,973	Main
	Baburnali Box Sluice	1-V(0.9mX0.9m)	799,970	Main
SP14114, Beel Salua DR & WCS Subproject, WC, Union : Baharpur, HO Date: 30/03/2004				
	Beel Salua Khal Re-excavation	1.90	153,112	Main
	WRS	2-V(1.5mX1.5m)	1,196,500	Main
SSWRDSP-2				
SP21009, Sadhukhali Subproject, FMD, Union : Jangal, HO Date: 26/06/2006				
	Aksukna Regulator at Ch.1+355 km	2-V(1.50mX1.80m) 0.00	2,641,490	Main
	Bashukhali Regulator at Ch.5+830 km	1-V(1.50mX1.80m) 0.00	1,804,635	Main
	Bonogram Regulator at Ch.8+400 km	1-V(1.50mX1.80m) 0.00	1,804,635	Main
	Embankment Re-sectioning	8.16	5,927,311	Main
	Paiteer Nali Pipe Sluice at Ch.7+590 km	1-V(900mm Dia) 0.00	1,046,213	Main
	Rehab. of Titu Kata Regulator at Ch.4+885 km	1-V(1.06mX1.40m) 0.00	442,240	Main
SSWRDP-JICA				
SP32014, Talbaria Beel Subproject, FMD&WC, Union : Islampur, HO Date: 21/07/2013				
	Re-excavation of Talbaria Khal	0.90	303,330	Main
	Part-A: Talbaria Khal Regulator at Ch.0+040 Km (Kh	2 vent-1.5mX1.8m 0.00	5,529,384	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,100,050	Main
	Part-B: Dhubaria WRS (Culvert Modification)	2 vent-1.5mX1.8m 0.00	589,340	Main
	Reference Lined Section	0.00	52,087	Main
	Earth Filling of Talbaria WMCA Office	0.00	189,116	Main
SP33094, Chaltakhali Khal Subproject, DR&WC, Union : Jamalpur, HO Date: 01/10/2014				
	Reexcavation of Chalitakhali Khal including Reference Pilla	5.00	4,210,963	Main
	Part-A: Chalitakhali Khal WRS at Ch. 0+100Km	3 Vent-1.5mX1.8m 0.00	8,367,612	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,543,371	Main
SP33095, Dakshinbari Khal Subproject, DR&WC, Union : Nababpur, HO Date: 20/08/2013				
	Reexcavation of Paban Miar Khal	2.00	1,397,150	Main
	Reexcavation of Kuthir Khal	1.20	1,245,919	Main
	Part-B:Paban Miar Khal WRS by Modif of Box Culvert	2 Vent-1.5mX1.8m 0.00	2,694,238	Main
	Part-A: Kuthir Khal WRS at Point of Existin Pipe C	1 Vent-1.5mX2.0m 0.00	4,246,436	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,596,071	Main
SP34111, Saldar Beel Subproject, DR&WC, Union : Nawabpur, HO Date: 06/11/2014				
	Re-excavation of Pakuria Khal	1.00	221,767	Main
	Re-excavation of Jhaodangi Khal	0.60	141,079	Main
	Reference Lined Sections (4 nos.)	0.00	61,170	Main
	Part-A: Bhatir Khal WRS at Ch. 0+615Km	2 Vent-1.5mX2.2m 0.00	7,256,530	Main
	Part-B: WMCA Office and Related Item	ize: 12mX6m 0.00	1,512,530	Main
	Re-excavation of Kana Khal	0.30	167,818	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP35201, Bangdubi Beel Subproject, WC, Union : Nawabpur, HO Date: 12/11/2015				
	Part-A: Bangdubi Khal WRS at Ch. 0+035Km	2 Vent-1.5mX2.0m 0.00	8,364,242	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,575,166	Main
	Re-excavation of Bangdubi Khal	2.83	3,622,310	Main
SP35210, Ghoshkhali Subproject, DR&WC, Union : Narua, HO Date: 14/11/2015				
	Re-excavation of Ghoshkhali Khal	3.30	937,762	Main
	Re-excavation of Ghoshkhali Khal Branch-1	0.26	30,044	Main
	Re-excavation of Ghoshkhali Khal Branch-2	0.53	194,105	Main
	Re-excavation of Ghoshkhali Khal Branch-3	0.40	290,293	Main
	Re-excavation of Bhati Khal	0.39	61,142	Main
	Part-A: Ghoshkhali Khal WRS at Ch.0+400Km	2 Vent-1.5mX2.0m 0.00	2,884,604	Main
	Part-B: Ghoshkhali Khal Regulator at Ch.3+097Km	1 Vent-1.5mX1.8m 0.00	5,427,840	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,586,597	Main
SP35212, Thakur Naopara Subproject, DR&WC, Union : Islampur, HO Date: 12/11/2015				
	Re-excavation of Thakur Naopara Khal	1.86	946,726	Main
	Re-excavation of Bairagir Khal	3.75	1,262,360	Main
	Re-excavation of Branch Khal	0.29	44,152	Main
	Part-A: Noapara Khal WRS at Ch. 0+640Km	1 Vent-1.5mX1.8m 0.00	2,574,350	Main
	Part-B: Bairagir Khal WRS at Ch. 0+240Km	2 Vent-1.5mX1.8m 0.00	3,344,628	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,602,305	Main
SP35224, Rotandia-Balughat Subproject, DR&WC, Union : Jamalpur, HO Date: 24/11/2015				
	Re-excavation of Horai Khal	7.20	12,843,271	Main
	Part-A: Horai Khal WRS at Ch.3+958	5 Vent-1.5mX2.0m 0.00	15,780,668	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,561,485	Main
Kalukhali SSWRDSP-1				
SP13068, Brajamul-Bhitikhal FCD Subproject, FCD&WC, Union : Saorail, HO Date:				
	Part-A: Check Structure-1	1V(1.5mX1.8m) 0.00	1,612,947	PSSWRSP
	Part-B: Check Structure-2	1V(1.5mX1.8m) 0.00	1,311,104	PSSWRSP
	Part-C: Construction of Box Culvert	1V(4.0mX4.0m) 0.00	1,167,443	PSSWRSP
	Part-D: Construction of Box Culvert	1V(1.5mX3.0m) 0.00	645,935	PSSWRSP
	Bhiti Khal Re-excavation	1.22	42,002	Main
	Brajamul Khal Re-excavation	2.78	66,712	Main
	Paturia Khal Re-excavation	1.83	187,573	Main
	Bhiti Khal Regulator	1-V(1.5mX1.5m)	1,103,155	Main
	Brajamul Regulator	1-V(1.5mX1.5m)	1,311,989	Main
	Paturia Regulator	1-V(1.5mX1.5m)	1,185,259	Main
	O&M Shed		0	Main
SSWRDP-JICA				
SP33063, Betbaria Khal Subproject, DR&WC, Union : Majbari, HO Date: 08/05/2013				
	Reexcavation of Betbaria Khal	3.80	5,299,570	Main
	Reexcavation of Monai Khal	1.00	467,421	Main
	Reexcavation of Kana Beel Khal	0.25	223,180	Main
	Reexcavation of Betbaria Branch Khal	0.20	145,724	Main
	Reference Lined Section (6 nos)	0.00	147,182	Main
	Part-A: Betbaria WRS-1 at Ch.0+035Km	2 Vent-1.5mX2.0m 0.00	5,790,462	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,626,626	Main
SP35202, Satota Shibbari Khal Subproject, FMD&WC, Union : Kalikapur, HO Date:				
	Re-excavation of Satota Shibbari Khal	2.25	5,051,563	Main
	Part-A: Satota Shibbari Regulator at Ch. 2 Vent-1.5mX1.8n	2 Vent-1.5mX1.8m 0.00	8,646,049	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,534,164	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP35225, Kumri Rani Khal Subproject, FMD&WC, Union : Saorail, HO Date: 25/08/2015				
	Kumri Rani Khal with Fish Sanctuary	3.23	4,140,821	Main
	Part-A: Kurmi Rani Khal Regulator at Ch.0+032Km	2 Vent-1.5mX1.8m 0.00	9,949,680	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,551,161	Main
SP35227, Kalkalia-Boroichora Khal Subproject, FMD&WC, Union : Mrigi, HO Date:				
	Re-excavation of Boro Kalkalia Khal with Fish Shelter	1.90	2,893,170	Main
	Re-excavation of Sayestapur Khal with Fish Shelter	1.75	783,139	Main
	Re-excavation of Puran Sikjan Khal with Fish Shelter	1.20	1,095,313	Main
	Part-A: Boro Kalkalia Khal Regulator at Ch.0+400Km	2 Vent-1.5mX1.8m 0.00	10,988,125	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,561,219	Main
Pangsha SSWRDSP-1				
SP12032, Sirajpur Haor WCS Subproject, WC, Union : Kalimohor,Sarisa,Patta & Saorail,				
	Sirajpur Haor Re-excavation	14.80	12,287,219	Main
	Regulator	9-V(1.5mX1.8m)	7,716,409	Main
	Fish Screen at Sirajpur Regulator		80,613	Main
SP14115, Sarisa-Pitapara WCS Subproject, WC, Union : Sarisha, HO Date: 27/04/2003				
	Sharisha Khal Re-excavation	0.90	188,750	Main
	Pitapara Khal Re-excavation	1.80	108,049	Main
	Sharisha WRS at Ch.0+000m	1-V(1.5mX1.5m)	1,240,736	Main
	Pitapara WRS-2 at Ch.0+150m	2-V(1.2mX1.5m)	1,300,001	Main
SP14116, Piralipara-Bagher Char WCS Subproject, WC, Union : Sarisha, HO Date:				
	Piralipara Khal Re-excavation	2.10	164,845	Main
	Piralipara WRS	2-V(1.2mX1.8m)	1,517,782	Main
SP14117, Bishukhali Khal WCS Subproject, WC, Union : Sarisha, HO Date: 27/04/2003				
	Re-excavation of Bishukhali khal	3.20	848,999	PSSWRSP
	Re-excavation of Kadari khal	2.80	866,849	PSSWRSP
	Re-excavation of Doal khal	0.30	148,419	PSSWRSP
	Khal Re-excavation	1.10	142,084	Main
	WRS at Ch.0+100m	2-V(1.2mX1.5m)	1,040,909	Main
SSWRDSP-2				
SP22019, Mashalia-Pranpur Subproject, WC, Union : Kalimohar, HO Date: 14/03/2007				
	Mashalia-Pranpur Khal Re-excavation	1.77	240,761	Main
	Pranpur WRS at Ch.0+000 km	3-V(1.50mX2.00m) 0.00	3,509,712	Main
	Nacha Muradpur WRS at Ch.0+000 km	1-V(900mm Dia) 0.00	891,272	Main
	Tortipur WRS at Ch.0+000 km	1-V(900mm Dia) 0.00	891,272	Main
	O&M Shed	12.00mX6.00m 0.00	339,483	Main
	Re-excavation Muradpur Khal	1.27	394,221	Main
	Re-excavation Torti Khal	0.35	106,727	Main
	Part-B: Re-excavation of Mashalia Khal	1.64	870,328	PSSWRSP
	Part-C: Re-excavation of Muradpur Khal	1.28	280,696	PSSWRSP
	Part-A: Re-excavation of Tattipur Khal	0.30	204,205	PSSWRSP
SP24142, Muchidaha Khal Subproject, DR&WC, Union : Pata, HO Date: 14/07/2009				
	Re-excavation of Muchidah Khal	1.85	834,815	Main
	Muchidah Khal Regulator at Ch. 0+180Km(Khal)	3 Vent-1.5mX1.8m 0.00	4,999,376	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	330,767	Main
SP24148, Dhenkipara Khal Subproject, DR&WC, Union : Jasai, HO Date: 24/12/2008				
	Re-excavation of Dhenkipara Khal	7.33	915,072	Main
	Dhenkipara Regulator at Ch. 0+030Km (Khal)	3 Vent-1.5mX1.8m 0.00	5,385,580	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	342,162	Main
	Part-A: Extension of one vent Regulator (1v-1.5mX1.80m)	(1v-1.5mX1.80m) 0.00	5,273,020	PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP25223, Laxmipur Khal Subproject, FMD, Union : Ratandia, HO Date: 25/03/2010				
	Re-excavation of Laxmipur Khal	1.10	369,057	Main
	Laxmipur Khal Regulator at Ch.0+080Km	2 Vent-1.5mX1.5m 0.00	2,534,941	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	4,173,165	PSSWRSP
SP25225, Puijor Patta Subproject, FMD, Union : Moural, Patta, HO Date: 25/03/2010				
	O&M Shed	Size: 9mX5m 0.00	467,066	Main
	Puijor Khal Regulator at Ch.0+060Km (Khal)	1 Vent-1.2m Dia 0.00	4,654,634	Main
	Block Casting of Regulator	0.00	393,543	Main
SSWRDP-JICA				
SP33064, Machpara-Lakshmandia Khal Subproject, DR&WC, Union : Majpara, HO Date:				
	Reexcavation of Laxmandia Khal	4.10	3,842,074	Main
	Reexcavation of Noapara Khal	2.76	757,734	Main
	Reexcavation of Kalukhali Khal	2.90	1,436,543	Main
	Reference Lined Section (7 nos)	0.00	244,648	Main
	Part-A: Lakshmandia Khal WRS	3 Vent-1.5mX2.5m 0.00	7,326,902	Main
	Reexcavation of Laxmandia Khal (Extension)	2.30	3,427,274	Main
SP35226, Durgapur Khal Subproject, FMD&WC, Union : Babupara, HO Date: 24/08/2015				
	Re-excavation of Durgapur Khal	3.10	1,862,757	Main
	Re-excavation of Chaitagram Beel Khal	0.35	124,701	Main
	Part-A: Durgapur Khal Regulator at Ch.0+400Km	2 Vent-1.5mX1.8m 0.00	8,460,983	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,560,967	Main
	Re-excavation of Bali para Khal	0.50	91,271	Main
	Re-excavation of Malu Bhaggyaban Khal	0.30	67,330	Main
Sadar				
SSWRDSP-1				
SP13066, Bara Nurpur WCS Subproject, DR&WC, Union : Shahid wahabpur, HO Date:				
	Khal Re-excavation	1.23	47,885	Main
	Bara Nurpur WRS	2-V(1.5mX1.5m)	1,252,322	Main
SP14121, Ershalmari Khal WCS Subproject, WC, Union : Mulghar, HO Date: 20/03/2003				
	Re-sectioning of Embankment	1.80	1,767,894	PSSWRSP
	Re-excavation of Irshalmari Khal	2.43	1,785,402	PSSWRSP
	Ershalmari Khal Re-excavation	2.79	395,433	Main
	Widening Ershalmari Khal	0.80	73,159	Main
	WRS at Ch.0+150m	2-V(1.5mX1.8m)	1,479,009	Main
SSWRDSP-2				
SP24167, Koidanga-Bethulia Subproject, DR&WC, Union : Ramkantapur, HO Date:				
	Re-excavation of Koidanga Khal	2.53	1,151,437	Main
	Koidanga Regulator at Ch 0+158 Km (Khal)	3 Vent-1.5mX1.8m 0.00	4,961,434	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	306,599	Main
	Part-A: Construction of 2 vent Box Culvert (4.0 mX4.0 m)	(4.0 mX4.0 m) 0.00	2,991,978	PSSWRSP
SSWRDP-JICA				
SP32015, Nimtala Beel Subproject, DR&WC, Union : Shahidohabpur, HO Date: 08/05/2013				
	Re-excavation of Chandra Khal	2.20	390,028	Main
	Part-A: Nimtala WRS at Ch. 2+950Km (Khal)	2 Vent-1.5mX1.5m 0.00	3,175,818	Main
	Reference Lined Section	0.00	119,571	Main
	Part-B: Box Culvert at Ch. 2+710Km (Khal)	2 Vent-2mX2m 0.00	1,002,578	Main
	Part-C: Box Culvert at Ch. 3+130Km (Khal)	2 Vent-2mX2m 0.00	1,002,578	Main
	Part-D: Box Culvert at Ch. 3+615Km (Khal)	2 Vent-2mX2m 0.00	994,917	Main
	Part-E: Box Culvert at Ch. 3+808Km (Khal)	2 Vent-2mX2m 0.00	986,064	Main

Shariatpur (Total SPs : 22 Nos.)

Bhedarganj

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SSWRDSP-1				
SP15309, Shakhipur-Arshinagar FCD Subproject, FCD, Union : Shakhipur, HO Date:				
	Embankment Re-sectioning	4.44	3,533,258	Main
	Hazikandi Khal Re-excavation	3.15	829,888	Main
	Rashid Bepari Khal Re-excavation	1.55	511,733	Main
	Mohizzer Char Khal Re-excavation	2.40	484,065	Main
	Sakhipur Regulator at Ch.0+000m	1-V(1.5mX1.8m)	1,449,045	Main
	Hazikandi Regulator	1-V(1.5mX1.8m)	1,427,045	Main
	D&M Khali Regulator	2-V(1.5mX1.8m)	2,374,330	Main
	Shakhipur Pipe Sluice	1-V(900mm Dia)	726,715	Main
	Rashid Bepari Pipe Sluice	1-V(900mm Dia)	722,112	Main
SSWRDP-JICA				
SP33091, Chukdar Kandi Khal Subproject, DR&IRR, Union : Chorsensus, HO Date:				
	Re-excavation of Chukder Kandi Khal	3.20	5,119,059	Main
	Part-A: Chulder Kandi Khal Check Structure	2 Vent-1.5mX1.5m 0.00	4,012,146	Main
	Reference Lined Sections (4 nos) & Posts (96 nos.	0.00	108,045	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,658,898	Main
SP35235, Char Chanda-Kumuria Khal Subproject, DR&IRR, Union : D.M Khali, HO Date:				
	WMCA Office and Related Item	Size: 12mX6m 0.00	894,382	Main
	Re-excavation of Char Chanda Char Kumuria Khal	7.50	5,550,637	Main
	Re-excavation of Char Paiatali Khal	1.00	1,053,724	Main
Damuddya				
SSWRDSP-1				
SP14118, Altakuri-Huyorgaria DR Subproject, DR, Union : Kaneswar, HO Date: 15/01/2002				
	Closure	0.01	2,213	Main
	Altakuri Khal Re-excavation	1.92	290,361	Main
SP14119, Charpatalia-Saghata WCS Subproject, WC, Union : Dhankathi, HO Date:				
	Closure	0.02	4,548	Main
	Charpatalia-Saghata Khal Re-excavation	6.30	1,163,578	Main
	WRS at Ch.0+000m	2-V(2.0mX1.8m)	2,299,314	Main
SSWRDP-JICA				
SP32011, Char Narayanpur-Naogaon Khal Subproject, DR&IRR, Union : Purbo Damuddya,				
	Part-A: WMCA Office and Related Items	Size: 12mX6m 0.00	879,384	Main
	Re-excavation of Char Narayanpur-Naogaon Khal	4.20	2,701,111	Main
	Re-excavation of Guakhola Khal	1.50	283,256	Main
	Reference Lined Section	ch 00+000 to 1+500 km 0.00	155,000	Main
SP35236, Nandra Khal Subproject, DR&IRR, Union : Darul Aman, HO Date: 31/08/2015				
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	849,577	Main
	Reexcavation of Nandra Khal i/c Reference Bed Block.	4.00	4,248,700	Main
	Reexcavation of Nandra Branch Khal i/c Reference Bed Blk	1.09	917,086	Main
	Reexcavation of Kalatala Khal i/c Reference Bed Block.	1.54	1,413,143	Main
	Reexcavation of Sar Khal i/c Reference Bed Block.	0.91	967,024	Main
Gosairhat				
SSWRDP-JICA				
SP35237, Kuchaipatti Subproject, DR&IRR, Union : Kuchai Patti, HO Date: 21/12/2015				
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	845,378	Main
	Reexcavation of Sakhya Char Majari Khal	5.49	4,158,771	Main
	Reexcavation of Narkeli Khal	1.58	865,821	Main
	Reexcavation of Nalmuri Boikhola Khal	2.11	1,652,927	Main
	Reexcavation of Masurgaon Khal	2.62	2,676,556	Main
Naria				
SSWRDSP-1				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
---	-----------	------------------------	------------------------------	-----------------------

SP12021, Muktarer Char FCD Subproject, FCD, Union : Muktarer Char, HO Date:

Embankment Re-sectioning	8.15	1,697,313	Main
Embankment Rehabilitation	0.58	358,324	Main
Mulpara Khal Re-excavation	1.80	120,808	Main
Mulpara Regulator	2-V(1.2mx1.8m)	1,632,557	Main
Bilaspur Regulator	1-V(1.5mx1.8m)	1,301,665	Main
Kunder Khal Box Sluice	1-V(1.1mx1.1m)	551,021	Main
Pipe Sluice at Ch.0+500m	1-V(900mm Dia)	398,580	Main
Pipe Sluice at Ch.2+310m	1-V(900mm Dia)	396,580	Main
Pipe Sluice at Ch.2+810m	1-V(900mm Dia)	396,080	Main
Pipe Sluice at Ch.8+072m	1-V(900mm Dia)	462,893	Main

SP13082, Maizpara-Muktarer Char FCD Subproject, FCD, Union : Muktarer Char, HO

Embankment Re-sectioning	10.87	5,631,133	Main
Regulator at Ch.4+613m	2-V(1.5mX1.8m)	2,661,695	Main
Regulator at Ch.6+903m	2-V(1.5mX1.8m)	2,614,194	Main
Regulator at Ch.8+508m	1-V(1.5mX1.8m)	2,581,559	Main
Regulator at Ch. 9+875m	1-V(1.5mX1.8m)	2,523,734	Main

SSWRDSP-2

SP25281, Gagrizora Beel Subproject, DR&IRR, Union : Nasasani, HO Date: 24/05/2009

Re-excavation of Gagrizora Khal	4.85	1,969,808	Main
Re-excavation of Nasasan Khal	2.83	805,028	Main
Re-excavation of Akonkandi Khal	0.85	162,891	Main
Re-excavation of Nalikandi	0.50	33,136	Main

Sadar

SSWRDSP-1

SP13081, Bhanga Beel FCD Subproject, FCD&WC, Union : Domsher, HO Date:

Embankment Re-sectioning	3.75	823,430	Main
Bhanga Beel Khal Re-excavation	2.09	369,936	Main
Kuarpur Khal Re-excavation	3.15	414,914	Main
Kuarpur Regulator	1-V(1.5mX1.8m)	1,469,850	Main
Domsher Regulator	1-V(1.5mX1.8m)	2,069,978	Main

SP14215, Paschimpara FCD Subproject, FCD, Union : Chitalia, HO Date: 20/10/2004

Embankment Re-sectioning	6.40	2,304,110	Main
Paschimpara Khal Re-excavation	0.78	237,762	Main
Kata Khal Re-excavation	0.65	164,248	Main
Regulator at Ch.1+335m	1-V(1.5mX1.8m)	1,908,825	Main
Pipe Sluice at Ch.4+610m	1-V(900mm Dia)	658,775	Main
Regulator at Ch.0+000m	1-V(1.5mX1.8m)	2,161,562	Main

SP15227, Sonamukhi FCD Subproject, FCD, Union : Rudrakar, HO Date: 30/08/2004

Embankment Re-sectioning	8.35	4,209,854	Main
Gazikandi Khal Re-excavation	1.80	137,636	Main
Basalia Khal Re-excavation	0.75	261,703	Main
Char Lakminarayan Khal Re-excavation	0.90	107,503	Main
Sonamukhi Khal Re-excavation	0.75	118,472	Main
Gani Bepari Khal Re-excavation	0.75	115,446	Main
Maddhya Sonamukhi Khal Re-excavation	0.56	142,060	Main
Sonamukhi Regulator at Ch.3+400m	1-V(1.5mX1.8m)	1,574,326	Main
Balasia Regulator at Ch.4+290m	1-V(1.5mX1.8m)	1,830,030	Main

SSWRDSP-2

SP23054, Char Rosundi Subproject, FMD, Union : Rudrakar, HO Date: 28/06/2009

Re-excavation of Rahman Choukiderbari Khal	0.70	250,977	Main
--	------	---------	------

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Talukdar-Hawladarbari Khal	0.50	100,316	Main
	Re-excavation of Samudraibari Khal	0.38	95,404	Main
	Re-excavation of Bishay Hawladarbari Khal	0.85	164,065	Main
	Embankment Re-sectioning	8.56	4,594,881	Main
	Molla bari Khal Pipe Sluice at Ch.1+770km	1 Vent-0.90m Dia 0.00	1,103,620	Main
	Samudra Bari Khal Pipe Sluice at Ch.3+900km	1 Vent-0.90m Dia 0.00	1,098,542	Main
	Bishai Hawlader BariKhal Pipe Sluice at Ch.4+625km	1 Vent-0.90m Dia 0.00	1,098,240	Main
	Kalai Talukder Khal Pipe Sluice at Ch.7+870km	1 Vent-0.90m Dia 0.00	1,112,039	Main
	O&M Shed	9.00mX5.00m 0.00	318,002	Main
	Re-excavation of Mollabari Khal	1.50	498,291	Main
	Re-excavation of Kalai Talukderbari Khal	1.00	240,574	Main
SP25271, Shawnirbhar Khal Subproject, DR&IRR, Union : Binodpur, HO Date: 07/03/2009				
	Re-excavation of Shawnirbhar Khal	4.66	649,195	Main
	Re-excavation of Kachari-Kandi Khal	1.35	374,272	Main
SP25272, Tulatala-Katakhali Subproject, DR&IRR, Union : Angoria, HO Date: 30/06/2010				
	Re-excavation of Tulakata Khal	4.45	1,055,638	Main
	Re-excavation of Katakhali Khal	3.70	937,885	Main
	Re-excavation of Hazir Khal	2.15	1,893,788	Main
SP25275, Shimanar Khal Subproject, DR&IRR, Union : Chikandi, HO Date: 08/03/2009				
	Re-excavation of Shimanar Khal	1.63	919,664	Main
	Re-excavation of Binodpur Khal	0.73	250,652	Main
SSWRDP-JICA				
SP33066, Chitalia Khal Subproject, DR&IRR, Union : Chatalia, HO Date: 23/12/2013				
	Reference Lined Section (8 nos.)	0.00	169,688	Main
	Part-A: WMCA Office and Related Item	Szie: 12mX6m 0.00	1,917,585	Main
	Re-excavation of Chitalia Khal	3.90	2,657,507	Main
	Re-excavation of Chitalia Branch Khal	2.66	2,070,386	Main
	Re-excavation of Tung Char Khal	1.60	1,945,635	Main
SP33076, Chandrapur Khal Subproject, DR&IRR, Union : Chandrapur, HO Date:				
	Re-excavation of Chandrapur Khal	2.70	1,434,850	Main
	Re-excavation of Chandrapur Khal Branch-1	0.50	978,857	Main
	Re-excavation of Chandrapur Khal Branch-2	0.28	765,816	Main
	Re-excavation of Chandrapur Khal Branch-3	1.45	1,199,637	Main
	Re-excavation of Bahir Chandrapur Khal	0.15	362,264	Main
	PArt-A: WMCA Office Related Item	Size: 12mX6m 0.00	1,099,012	Main
	Reference Lined Section (7 nos.)	0.00	385,291	Main
SP35183, Mahmudpur Beel Subproject, DR&IRR, Union : Mahamudpur, HO Date:				
	Re-excavation of Dhamra Khal	2.05	4,136,644	Main
	Re-excavation of Dhamra Branch Khal	0.60	1,767,948	Main
	Re-excavation of Joenuddin Hazibari Khal	1.45	1,188,581	Main
	Re-excavation of Joenuddin Hazibari Branch Khal	0.40	799,166	Main
	Re-excavation of paschim Mahmudpur Khal	1.35	1,990,953	Main
Zanjira				
SSWRDSP-1				
SP15251, Ramkrisnapur FCD Subproject, FCD, Union : Senerchar,Dhuparia, HO Date:				
	Embankment Re-sectioning	12.43	8,268,277	Main
	Khal-2 Re-excavation	0.98	205,097	Main
	Khal-3 Re-excavation	2.70	277,494	Main
	Regulator at Ch.3+200m	1-V(1.5mX1.5m)	1,327,226	Main
	Regulator at Ch.7+660m	2-V(1.2mX1.5m)	1,767,909	Main
	Regulator at Ch.8+720m	1-V(1.5mX1.5m)	1,326,748	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Tangail (Total SPs : 21 Nos.)				
Delduar				
SSWRDP-JICA				
SP35230, Aglasin-Abatpur Beel Subproject, FMD, Union : Elasin, HO Date: 20/04/2016				
	Re-excavation of Aglasin-Abatpur Khal	2.25	1,182,229	Main
	Part-A: Aglasin-Abatpur Khal Regulator at Ch.0+320Km	2 Vent-1.5mX1.8m 0.00	8,192,382	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,254,888	Main
SP35231, Maistha Beel Subproject, FMD, Union : Dubail, HO Date: 11/01/2016				
	Re-excavation of Maistha Khal	0.70	622,931	Main
	Re-sectioning of Embankment	0.03	222,114	Main
	Part-A: Maistha Khal Regulator at Ch.0+050Km	1 Vent-1.5mX1.8m 0.00	5,432,370	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,279,272	Main
SP35259, Boror Beel Subproject, FMD, Union : Dewli, HO Date: 14/06/2016				
	Part-A: Sthal Barsha Teuria Khal Regulator	2 Vent-1.5mX1.8m 0.00	8,679,150	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,026,818	Main
	Re-excavation of Sthal Barsha Teuria Khal	0.50	566,822	Main
	Re-excavation of Boror Beel Khal i/c Reference Bed Block	0.73	257,714	Main
SP35260, Charparal-Barphakia Khal Subproject, DR, Union : Delduar, HO Date:				
	Part-B: Kurir Beel Khal Box Culvert at Ch. 0+002Km	1 Vent-2.5mX3m 0.00	1,479,622	Main
	Re-excavation of Gangarbada Khal i/c Reference Bed Bloc	0.35	128,436	Main
	Re-excavation of Kurir Beel Khal i/c Reference Bed Blocks	0.20	97,225	Main
	Part-A: Charpara Beel Baraphakia Khal Box Culvert at Ch.	1 Vent-5.0mX4.5m 0.00	2,663,169	Main
	Part-C: Charpara Beel Barapakhia Khal Foot Bridge at Ch.	1 Span 10mX3m 0.00	3,043,610	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	2,897,473	Main
	Re-excavation of Charpara Beel Barapakhia Khal i/c Refer:	4.20	2,598,862	Main
Dhanbari				
SSWRDSP-2				
SP24173, Koshaibari Khal Subproject, FMD, Union : Musuddi, HO Date: 26/01/2011				
	Re-sectioning of Embankment/Dyke	1.79	634,281	Main
	Kasaibari Khal Regulator at Ch 0+045Km	1 Vent-1.2mX1.2m 0.00	2,102,754	Main
	Noya Khal Regulator at Ch 0+125Km	2 Vent-1.2mX1.2m 0.00	2,613,538	Main
	O&M Shed	Size:12.mX6m 0.00	262,524	Main
	Re-excavation of Koshaibari Khal	0.40	211,315	Main
	Re-excavation of Noya Khal	1.60	706,732	Main
SSWRDP-JICA				
SP33041, Goalia (Dhanbari) Beel Subproject, FMD, Union : Birtara, HO Date: 10/03/2013				
	Part-A: Shapkhali Khal Regulator at Ch.0+250Km(Kha	1 Vent-1.5mX1.5m 0.00	2,552,432	Main
	Re-excavation of Shapkhali Khal	0.50	223,579	Main
SP33042, Goilla Beel Subproject, FMD, Union : Dhopakhali, HO Date: 26/08/2013				
	Part-B: Pipe Sluice Ch. 0+010	3 Vent-0.90m Dia 0.00	3,628,452	Main
	Part-A:Modification of Existing Culvert at Ch5+575	2 Vent-1.7mX1.5m 0.00	979,245	Main
	Part-C: Pipe Sluice at Ch. 1+225	3 Vent-0.90m Dia 0.00	3,661,999	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,495,330	Main
	Re-excavation of Goilla Beel Khal	0.40	102,150	Main
	Re-sectioning of Embankment	1.28	1,418,400	Main
Ghatail				
SSWRDSP-2				
SP23068, Shanki Bhanga Khal Subproject, DR&WC, Union : Dewpara, HO Date:				
	Shankibhanga Khal Re-excavation	4.50	3,830,374	Main
	Regulator at Ch.0+030km	5 Vent-1.50mX1.80m 0.00	8,034,099	Main
	O&M Shed	9.00mX5.00m 0.00	310,666	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: Re-excavation of Shanki Bhanga khal	7.00	3,563,470	PSSWRSP
	Part-B: Construction of reference Linned section	0.00	73,801	PSSWRSP
SSWRDP-JICA				
SP34146, Kulia Garodoba-Dublakuri Khal Subproject, FMD&WC, Union : Ghatail, HO Date:				
	Reexcavation of Kulia Garodoba Dublakuri Khal	1.90	938,258	Main
	Resectioning of Kulia Garodoba Embankment	1.30	2,453,674	Main
	Reference Line Sections (2 nos.)	0.00	53,901	Main
	Part-A: Kulia Garodoba Regulator	1 Vent-1.5mX1.8m 0.00	5,231,993	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	2,334,228	Main
Gopalpur				
SSWRDSP-2				
SP25190, Doga Beel Subproject, FMD, Union : Nagda Shimla, HO Date: 11/01/2011				
	Re-sectioning of Embankment	4.29	571,641	Main
	Doga Beel Regulator	3 Vent-1.5mX1.8m 0.00	6,056,036	Main
	Part-A: WMCA Office & Others	12mX6m 0.00	1,436,733	PSSWRSP
SSWRDP-JICA				
SP32025, Barasila Beel Subproject, DR&WC, Union : Mirzapur, HO Date: 21/08/2013				
	Part-A: Barshila Khal Regulator at Ch.0+050Km	1 Vent-1.5mX1.5m 0.00	5,713,662	Main
	Re-excavation of Barsila Beel Khal	1.70	970,165	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,104,245	Main
	Referenece Line Section	0.00	60,867	Main
	Fish Sanctuary	0.00	824,210	Main
SP32036, Basan Beel Subproject, FMD, Union : Dhopakandi, HO Date: 21/08/2013				
	Re-excavation of Basan Khal	2.00	1,493,786	Main
	Re-excavation of Chofer Khal	0.70	204,982	Main
	Re-excavation of Sarkarbari Khal	1.10	395,356	Main
	Re-excavation of Link Khal (Kuillar and Basan Beel	0.50	161,144	Main
	Part-A: Basan Khal Regulator at Ch. 0+750Km (Khal)	2 Vent-1.5mX1.8m 0.00	7,951,948	Main
	Part-B: WMCA Office and Related Item	Szie:12mX6m 0.00	1,276,168	Main
	Referenece Lined Section	0.00	94,045	Main
	Approach Filling and Protection Works	0.00	230,000	Main
SP35199, Benai Beel Subproject, DR&WC, Union : Dhopakandi, HO Date: 26/08/2015				
	Part-A: Benai Beel Khal WRS at Ch.0+000Km to Ch.1+500	2 Vent-1.5mX1.8m 0.00	6,285,699	Main
	Re-excavation Benai Khal	1.55	739,145	Main
	Re-excavation Fish Sanctuary	0.00	506,283	Main
	Part-B: Palisading Works on Both Banks of Benai Beel Kha	Length =217 m 0.00	3,093,906	Main
	Part-C: WMCA Office & Related Item	Size: 12mX6m 0.00	1,496,706	Main
Kalihati				
SSWRDSP-2				
SP23107, Ratanganj-Gandhina Subproject, FM, Union : Nagbari, HO Date: 25/04/2011				
	Re-sectioning of East Embankment	7.25	4,570,747	Main
	Gandhina Regulator adjacent to 12m bridge	2 Vent-1.50mX1.50m 0.00	2,998,181	Main
	Domagar Pipe Sluice at Ch.6+750Km (East Embkt.)	1 Vent-0.90m dia 0.00	988,903	Main
	Dorbeshi K Pipe Sluice at Ch.2+425Km (East Embkt.)	1 Vent-0.90m dia 0.00	1,152,728	Main
	Jorbari Regulator at Ch 0+635 Km (Eat embkt.)	1 Vent-1.50mX1.80m 0.00	2,980,304	Main
	Resectioning of West Embankment	2.30	1,050,907	Main
SSWRDP-JICA				
SP35182, Panch Joair Singna Subproject, FMD, Union : Birbasunda, HO Date: 12/04/2016				
	Resectioning of Embankment (Ch.1+600Km to Ch.8+100K)	6.50	8,215,465	Main
	Resectioning of Embankment i/c Reexcavation of Fatikjani	5.00	5,208,640	Main
	Reexcavation of Fatikjani River	0.90	699,506	Main
	Reexcavation of Singna Beel Khal i/c Resectioning of Emb	2.10	2,399,040	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Mirzapur SSWRDSP-2 SP24138, Umed Ali Khal Subproject, FMD&WC, Union : Azgana, HO Date: 18/05/2011	Reexcavation of Singna Beel Fish Sanctuary	0.00	376,215	Main
	Part-A: Panch Joair Regulator	3 Vent-1.5mX1.8m 0.00	10,795,686	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,490,544	Main
SP25277, Bankurtala-Kalimajani Subproject, FMD, Union : Gorai, HO Date: 14/12/2009	Rexcavation Umed Ali Khal	2.60	927,067	Main
	Rexcavation Ukunmari Khal	0.55	318,189	Main
	Umed Ali Khal Regulator at Ch. 0+070Km(Khal)	2 Vent-1.5mX1.8m 0.00	4,464,020	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	262,234	Main
	Re-sectioning of Approach of Regulator	0.12	194,071	Main
Shakhipur SSWRDSP-2 SP25215, Bajail Goalia Khal Subproject, DR&WC, Union : Hatibandha, HO Date:	Re-excavation of Zia Khal	0.50	178,234	Main
	Re-sectioning of Embankment	5.25	4,551,624	Main
	Zia Khal Regulator at Ch.0+232Km(Khal)	2 Vent-1.5mX1.8m 0.00	4,817,182	Main
SP25229, Shail Sindur Khal Subproject, DR&WC, Union : Kakrajan, HO Date: 01/08/2009	Re-excavation of Bajail Goalia Khal	6.20	1,075,003	Main
	Bajail-Goalia Khal Regulator at Ch.0+569Km	4 Vent-1.5mX1.8m 0.00	8,626,369	Main
	Re-excavation of Shail Shindur Khal	3.50	1,953,753	Main
SSWRDP-JICA SP35254, Tengra-Madla Khal Subproject, WC, Union : Kakrajan, HO Date: 25/05/2016	Shail Shindur Khal WRS at Ch.0+691Km	4 Vent-1.5mX1.8m 0.00	5,673,315	Main
	Part-B: Tengra Khal WRS at Ch. 0+325Km (Khal)	2 Vent-1.5mX2.8m 0.00	7,365,714	Main
	Part-A; Madhla Khal WRS at Ch. 0+100Km (Khal)	3 Vent-1.5mX2.8m 0.00	10,048,961	Main
JICA-LGED TA Project SP51003, Bajail Borochala Subproject, DR&WC, Union : Hatibandha, HO Date:	Part-C: Tengra Khal Box Culvert at Ch. 1+825Km (Khal)	2 Vent-3.0mX3.0m 0.00	1,745,261	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,410,038	Main
	Re-excavation of Fish Shelter in Tengra Khal	0.15	193,672	Main
	Re-excavation of Fish Shelter in Madhla Khal	0.30	475,982	Main
	Part-A: Construction of WRS-1 at Ch 0+240Km	3 Vent-1.5mX2.0m 0.00	9,143,189	Main
SP51003, Bajail Borochala Subproject, DR&WC, Union : Hatibandha, HO Date:	Re-excavation of Bajail Borochala Khal	8.30	4,848,810	Main
	Construction of Reference Lined Sections	0.00	154,574	Main
	Part-D: Construction of WEIR-1 at Ch.6+515Km	L=6.0m 0.00	4,475,781	Main
	Part-F: Construction of Outlet Pipe (22 nos.)	10 nos 0.00	1,750,328	Main
	Carpeting Road (5.0 km)	4.517 km 0.00	29,633,446	Main
	Development of Rural Market Bajail Bazar (MMC Office No	Size: 5.5mX7.0m 0.00	1,234,493	Main
	Part-B: Construction of WRS-2 at Ch.1+735Km	3 Vent-1.5mX2.0m 0.00	8,595,970	Main
	Development of Rural Market Bajail Bazar (Meat Shed No.	Size: 8.0mX6.0m 0.00	426,898	Main
	Development of Rural Market Bajail Bazar (Fish Shed No. (Size: 8.0mX6.0m 0.00	426,644	Main
	Development of Rural Market Bajail Bazar (Multipurpose Sl	Size: 8.0mX4.0m 0.00	671,585	Main
	Development of Rural Market Bajail Bazar (Women Vendor	Size: 4.8mX6.0m 0.00	1,214,117	Main
	Development of Rural Market Bajail Bazar (Male Toilet No.	Size: 3.4mX3.4m 0.00	855,810	Main
	Development of Rural Market Bajail Bazar (Female Toilet N	Size: 3.5mX2.425m 0.00	595,755	Main
	Development of Rural Market Bajail Bazar (CC Road: 140n	CC Road: 140mX1.85m 0.00	329,560	Main
	Development of Rural Market Bajail Bazar (Drain: 150m)	Drain: 150m 0.00	216,354	Main
	Development of Rural Market Bajail Bazar (RCC Cross Dra	RCC Cross Drain: 09m 0.00	239,376	Main
	Development of Rural Market Bajail Bazar (Tube Wells Nos	2 nos. Tubewell 30m depth	62,940	Main
	Part-C: Construction of WRS-3 at Ch.4+240Km	2 Vent-1.5mX2.0m 0.00	6,516,405	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Development of Rural Market Bajail Bazar (Garbage Pit No	Size: 1.25mX1.25m 0.00	22,419	Main
	Development of Rural Market Rajabari Bazar (MMC Office	Size: 5.5mX7.0m 0.00	1,097,149	Main
	Development of Rural Market Rajabari Bazar (Meat Shed N	Size: 8.0mX6.0m 0.00	419,917	Main
	Development of Rural Market Rajabari Bazar (Fish Shed N	Size: 8.0mX6.0m 0.00	419,906	Main
	Development of Rural Market Rajabari Bazar (Multipurpose	Size: 8.0mX4.0m 0.00	653,426	Main
	Development of Rural Market Rajabari Bazar (Women Ven	Size: 4.8mX6.0m 0.00	1,154,799	Main
	Development of Rural Market Rajabari Bazar (Male Toilet N	Size: 3.4mX3.4m 0.00	790,033	Main
	Development of Rural Market Rajabari Bazar (Female Toile	Size: 3.25mX2.425m 0.00	547,596	Main
	Development of Rural Market Rajabari Bazar (CC Road 90	CC Road 90mX1.85m 0.00	211,860	Main
	Development of Rural Market Rajabari Bazar (Drain 100m)	Drain 100m 0.00	145,470	Main
	Development of Rural Market Rajabari Bazar (RCC Cross I	RCC Cross Drain 09m 0.00	239,416	Main
	Development of Rural Market Rajabari Bazar (Tube Well N	Tube Well Nos 2 30m each	72,931	Main
	Development of Rural Market Rajabari Bazar (Garbage Pit	Size:1.25mX1.25m 0.00	21,419	Main
	Protection of Bridge Approach	0.00	468,318	Main
	WMCA Office & others	12m X 6m 0.00	3,005,298	Main

Bagerhat (Total SPs : 11 Nos.)

Chitalmari

SSWRDSP-1

SP12028, Melarkul Khal FCD Subproject, FCD&WC, Union : Kalatala, HO Date:

Melarkul khal re-excavation(ch.1960-7100m)	5.14	13,278,684	SSSWRDP
Referenced line section(6nos)	0.00	191,287	SSSWRDP
Bamboo bridge(6nos)	0.00	384,480	SSSWRDP
Melarkul Khal Re-excavation	6.45	1,182,851	Main
Melarkul Regulator	1-V(1.8mX2.4m)	2,769,752	Main

SP13108, Kachubunia-Saratkhali FCD Subproject, FCD, Union : Char Baniari,Santoshpur,

Kachubunia Khal Re-excavation	5.36	379,300	Main
Regulator at Ch.0+000m	2-V(1.5mX1.8m)	3,241,687	Main
Regulator at Ch.5+360m	1-V(1.5mX1.8m)	2,308,202	Main
Larar Khal Regulator	1-V(1.8mX2.4m)	1,809,727	Main

Fakirhat

SSWRDSP-1

SP11010, Maskata Khal FCD Subproject, FCD, Union : Betaga,Lakpur, HO Date:

Embankment Re-sectioning	2.36	978,031	Main
Earthen Cross Dam	0.12	116,945	Main
Guide bundh,Cross Dam and Diversion Fill	0.10	35,224	Main
Pasur River Re-excavation	10.00	12,947,580	Main
Doania Khal Re-excavation	1.05	619,028	Main
Kultia Khal Re-excavation	1.40	172,915	Main
Sayamganj Bara Khal Re-excavation	0.75	212,412	Main
Arar Khal Re-excavation	0.75	116,813	Main
Amirpur Bara Jola Khal Re-excavation	0.45	133,821	Main
Amirpur Gora Khal Re-excavation	0.25	67,004	Main
Sayamganj Joarer Khal Re-excavation	1.65	454,370	Main
Hadirabad Didarer Khal Re-excavation	1.32	259,037	Main
Minadia Khal Re-excavation	2.80	175,185	Main
Pasur Regulator	6-V(1.5mX1.8m)	5,593,000	Main
Fish Screen at Pasur Regulator		79,042	Main

Kachua

PSSWRSP

SP45180, Tengrakhali-Char Tengrakhali Subproject, DR&WC, Union : Kachua, HO Date:

Part-A: Box Culvert-1 (1v-3.5m X2.5m) at Ch. 2+870 km or	(1v-3.5m X2.5m) 0.00	1,155,516	Main
Part-B: Box Culvert-2 (1v-3.5m X2.5m) at Ch. 3+558 km or	(1v-3.5m X2.5m) 0.00	1,201,687	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Morelganj SSWRDSP-2 SP24184, Tafalbari Khal Subproject, DR&WC, Union : Baroikhali, HO Date: 04/11/2010	Part-C: WMCA Office & Others	12mX6m 0.00	1,579,223	Main
	Part-A: Re-excavation of Arar khal	6.27	5,012,072	Main
	Part-B: Re-excavation of Tengrakhali khal	3.03	2,260,200	Main
	Part-C:Construction of Reference Lined Section	0.00	204,089	Main
PSSWRSP SP43072, Pathuria-Kalibari Subproject, FMD, Union : Jewdhara, HO Date: 21/09/2016	Re-excavation of Tafalbari Khal	2.00	522,509	Main
	Tafalbari Khal Regulator at Ch.0+000Km(Khal)	2 Vent-1.5mX1.8m 0.00	2,849,385	Main
	Pipe Sluice-1 at Ch.0+800Km(Embkt)	1 Vent-0.9m Dia Pipe 0.00	1,027,936	Main
	Pipe Sluice-2 at Ch.5+915Km(Embkt)	1 Vent-0.9m Dia Pipe 0.00	1,028,181	Main
	Resectioning of Embankment	7.20	4,632,607	Main
Sadar SSWRDSP-1 SP14112, Harikhali-Doborkhali FCD Subproject, FCD, Union : Karapara, HO Date:	Part-C: Re-sectioning of Embankment	7.50	10,567,642	Main
	Part-A: Re-excavation of Kalibari khal	2.20	1,606,071	Main
	Part-B: Re-excavation of Pathuria khal	1.70	1,745,265	Main
	Part-A: Kalibari Khal Regulator	at Ch. 0+030 km 0.00	7,615,945	Main
	Part-B: Pathuria khal Regulator	at Ch. 0+000 km 0.00	5,593,601	Main
	Part-D: Construction of Reference lined section	at Ch. 0+000 km to 1+700	79,694	Main
	Part-C: WMCA office & others	12mx6m 0.00	1,496,386	Main
SP14113, Nilur Khal FCD Subproject, FCD, Union : Jatrapur, HO Date: 23/05/2004	Embankment Re-sectioning	4.31	1,094,397	Main
	Harikhali khal re-excavation(ch.00-2100m)	2.10	3,775,583	SSSWRDP
	Embankment re-sectioning(ch.370-2285m)	1.92	2,385,975	SSSWRDP
	Referenced line section(3 nos)	0.00	105,487	SSSWRDP
	WMCA office and 3 other structures	12mX6m 0.00	3,764,013	SSSWRDP
	Dobor Khal Re-excavation	0.90	254,305	Main
	Arar Khal Re-excavation	0.45	120,901	Main
	Dakkhin Dobor Khal Re-excavation	0.55	188,790	Main
	Choro Khal Re-excavation	0.90	196,673	Main
	Chitli Khal Re-excavation	1.14	142,526	Main
	Harikhali Regulator at Ch.0+000m	3-V(1.5mX1.8m)	2,441,378	Main
	Doborkhali Regulator at Ch.1+365m	2-V(1.5mX1.8m)	2,847,397	Main
	Choro Khal Pipe Sluice at Ch.2+066m	1-V(900mm Dia)	583,217	Main
	River Protection Works	0.11 km	0	Main
SSWRDSP-2 SP25198, Laupala-Surjabedi Subproject, FM, Union : Baroipara, HO Date: 04/10/2010	Nilur khal re-excavation(ch.00-1275m)	1.28	2,135,139	SSSWRDP
	Referenced line section(2nos)	0.00	57,309	SSSWRDP
	Bamboo bridge(3nos)	0.00	135,699	SSSWRDP
	Structure maintenance	0.00	1,195,573	SSSWRDP
	Nilur Khal Re-excavation	1.27	156,400	Main
	Regulator at Ch.0+160m	2-V(1.2mX1.5m)	2,389,324	Main
	Re-sectioning of Embankment	3.10	2,147,966	Main
	Laupala Khal Regulator	2 Vent-1.5mx1.8m 0.00	4,990,470	Main
	Surjabedi Khal Regulator	1 Vent-1.5mX1.8m 0.00	3,356,737	Main
	Panchur Khal Pipe Sluice	1 Vent-0.9m 0.00	1,575,881	Main
	Approach Road	0.14	86,620	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Surjabedi khal re-excavation(ch.00-2700m)	2.70	7,586,140	SSSWRDP
	Pachur khal re-excavation(ch.00-600m)	0.60	1,131,413	SSSWRDP
	Referenced line section(4nos)	0.00	108,840	SSSWRDP
	Bamboo bridge(4 nos)	0.00	188,471	SSSWRDP
SP25284, Goshala Subproject, FMD, Union : Jatrapur, HO Date: 20/03/2011				
	Goshala Khal Regulator	4 Vent-1.5mX1.8m 0.00	9,301,650	Main
	Masidpur Khal Regulator	1 Vent-1.5mX1.8m 0.00	4,056,026	Main
	Rehabilitation of Existing Culvert to Gated Struct	2 Vent-1.0mX1.5m 0.00	509,014	Main
	Re-excavation Of Gosala Khal	2.90	1,080,624	Main
	Re-excavation Of Masidpur Khal	0.88	443,717	Main
	Part-C: WMCA Office & others	12mx6m 0.00	1,367,384	PSSWRSP
	Part-A: Construction of O&M Sheed HBB Connecting road	12mx6m 0.00	1,689,498	PSSWRSP
	Part-B: Construction of 1no U-Drain	600mmx625mm 0.00	91,571	PSSWRSP
PSSWRSP				
SP43064, Dier Khal Subproject, FMD, Union : Baroipara, HO Date: 24/09/2017				
	Part-A: Re-excavation of Dier khal	1.85	1,846,577	Main
	Part-B: WMCA office & others	0.00	1,598,022	Main
	Part-H: Construction of Embankment	1.75	1,092,909	Main
	Part-B: Re-excavation of Kata khal	2.00	1,201,276	Main
	Part-C: Re-excavation of Takimara khal	2.10	440,646	Main
	Part-D: Re-excavation of Naluar khal	1.40	103,523	Main
	Part-E: Re-excavation of Doulosise khal	1.05	108,420	Main
	Part-F: Re-excavation of Doasise khal	0.73	116,027	Main
	Part-G: Re-excavation of Anajer khal	0.45	103,768	Main
	Part-I: Reference lined section	0.00	174,179	Main
	Part-A: Construction of Box Culvert on Dier khal	0.00	3,494,064	Main
Chuadanga (Total SPs : 15 Nos.)				
Alamdanga				
SSWRDSP-2				
SP24163, Bhangabari-Amanjhola Beel Subproject, FMD, Union : Bhangabari, HO Date:				
	Re-excavation of Amanjhola Khal	1.80	558,773	Main
	Re-excavation of Dulagarir Khal	0.30	38,702	Main
	Re-excavation of Nalbata Khal	0.40	39,920	Main
	Amanjhola Khal Regulator at Ch. 0+050Km (Khal)	2 Vent-1.5mX1.8m 0.00	4,379,882	Main
	Dulagarir Pipe Sluice at Ch. 0+040Km (Khal)	1 Vent-0.90m Dia 0.00	1,165,445	Main
	Amanjhola Box Culvert at Ch. 1+118Km	1 Vent-3.5mX3.0m 0.00	559,435	Main
	Amanjhola Box Culvert at Ch. 1+633Km	1 Vent-3.5mX3.0m 0.00	588,111	Main
	Nalbata Box Culvert at Ch. 0+075Km	1 Vent-3.0mX3.0m 0.00	532,410	Main
PSSWRSP				
SP45212, Nauda Durgapur - Maddamath Subproject, DR&WC, Union : Kumari., HO Date:				
	Part-A: Construction of Mohirbagan khal Regulator (1v-1.5	(1v-1.50mX1.8m) 0.00	0	Main
	Part-A: Re-excavation of Mohirbagan Khal	0.60	305,890	Main
	Part-B: Construction of WMCA Office & others	12mX6m 0.00	0	Main
	Part-B: Construction of Reference Lined section	0.00	18,825	Main
Dhamurhuda				
SSWRDSP-1				
SP12018, Razukhali Khal FCD Subproject, FCD, Union : Damurhuda, HO Date:				
	Embankment Re-sectioning	0.84	298,869	Main
	Rajukhali khal re-excavation(ch.00-2750m)	2.75	3,437,248	SSSWRDP
	Referenced line section(3nos)	0.00	84,034	SSSWRDP
	Bamboo bridge(3nos)	0.00	143,112	SSSWRDP
	Razukhali Regulator	2-V(1.2mx1.8m)	2,261,744	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Koilakhali Regulator	2-V(1.2mx1.8m)	2,505,356	Main
	Fish Screen at Koilakhali Regulator		46,171	Main
	Fish Screen at Razukhali Regulator		49,057	Main
SP14136, Gopalkhali FCD Subproject, FCD, Union : Howli, HO Date: 23/04/2002				
	Gopalkhali khal re-excavation(ch.00-1000m)	1.00	2,079,133	SSSWRDP
	Referenced line section(2nos)	0.00	68,750	SSSWRDP
	Bamboo bridge(1nos)	0.00	52,725	SSSWRDP
	Gopalkhali Khal Re-excavation	2.29	354,610	Main
	Gopalkhali Khal Regulator at Ch.0+080m	2-V(1.5mX1.5m)	2,962,318	Main
	Bridge over Gopalkhali Khal at Ch.1+100m	9.8m span	842,669	Main
SP14137, Trimohini FCD Subproject, FCD, Union : Howli, HO Date: 24/04/2002				
	Embankment Re-sectioning	0.60	252,614	Main
	Trimohini Khal Re-excavation	1.26	306,163	Main
	Trimohini Regulator at Ch.0+680m	2-V(1.2mX1.5m)	3,602,642	Main
SP14172, Barade-Kamarpara FCD Subproject, FCD, Union : Darshana,Kurolgachi, HO				
	Baradi Khal Re-excavation	0.94	374,420	Main
	Baradi Khal Regulator at Ch. 0+310m	2-V(1.5mX1.5m)	4,297,868	Main
	O&M Shed		227,610	Main
SSWRDSP-2				
SP24126, Kathal Khali-Patachora-Uttar Chandpur Subproject, FMD, Union : Damurhuda,				
	Uttar Chandpur Pipe Sluice at Ch.0+050Km	2 Vent-0.90m Dia 0.00	1,859,457	Main
	Chulkhani Regulator at Ch. 0+121 Km	2 vent-1.5mX1.8m 0.00	4,593,842	Main
	Kata Khal Pipe Sluice at Ch. 0+050Km	2 Vent-0.9m Dia 0.00	624,567	Main
	O&M Shed	Size: 12mX6m 0.00	386,449	Main
	Kathal Khali Regulator at 0+114Km (Khal)	1 Vent-1.5mX1.8m 0.00	3,630,215	Main
	Re-excavation of Chukani Khal	0.85	187,199	Main
SP25322, Kanaidanga Khal Subproject, FMD, Union : Kanaidanga, HO Date: 03/07/2011				
	Re-excavation of Kanaidanga Khal	0.39	221,363	Main
	Kanaidanga Khal Regulator	Size: 2 Vent-1.5mX1.8m 0.00	6,037,553	Main
	O&M Shed	Size: 9mX5m 0.00	482,318	Main
	Part-A: Improvement of Road From Kanaidanga FRB Bridg	atCh.0 +480 km&at	2,192,872	PSSWRSP
	Part-B: Improvement of HBB Road From Kanaidanga FRB	at Ch 0+000km to 0+1000km	159,909	PSSWRSP
	Part-C: Re-excavation of Kanaidanga khal	2.60	241,194	PSSWRSP
PSSWRSP				
SP45201, Fakirkhali khal Subproject, DR&WC, Union : Karpushdanga, HO Date:				
	Part-A: Modification of Box Culvert in to gated Structure (2\	(2v-1.50mX1.80m) 0.00	0	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Fakirkhali Khal	0.75	136,474	Main
	Part-B: Construction of Reference Lined Section	0.00	18,176	Main
Jiban Nagar				
SSWRDSP-1				
SP15230, Shankheri & Ruer Beel FCD Subproject, FCD, Union : Jiban Nagar, HO Date:				
	Sakharia Ruier khal re-excavation(ch.00-1000m)	1.00	1,348,292	SSSWRDP
	Referenced line section	0.00	45,000	SSSWRDP
	Shankaria Beel Khal Re-excavation	5.95	1,580,434	Main
	Shankaria Beel Br. Khal Re-excavation	1.03	197,340	Main
	Shankaria Regulator at Ch.0+300m	2-V(1.5mX1.5m)	2,365,984	Main
	Re-construction of Bridge at Ch.5+394m	8.6m Spam	865,382	Main
SP15231, Digir Beel DR Subproject, DR, Union : Uthali, HO Date: 28/04/2002				
	Kazla Khal Re-excavation	1.35	100,770	Main
	Chikon Khal Re-excavation	1.08	119,078	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP15232, Raufkhali FCD Subproject, FCD, Union : Banka & Andulbaria, HO Date:	Box Culvert at Ch.2+860m	1-V(2.5mX2.5m)	330,000	Main
	Embankment Re-sectioning	3.00	1,001,526	Main
	Khal Re-excavation	0.90	81,130	Main
	Regulator at Ch.0+325m	1-V(1.2mX1.2m)	932,905	Main
	Regulator at Ch.2+250m	1-V(1.2mX1.2m)	968,745	Main
SP15286, Aruar Khal DR & WCS Subproject, DR&WC, Union : Banka, HO Date:	Aruar Khal Re-excavation	3.01	215,850	Main
	WRS at Ch.0+390m	2-V(1.5mX1.8m)	1,751,097	Main
	Box Culvert at Ch.2+860m	1-V(2.5mX2.5m)	330,181	Main
Sadar				
SSWRDSP-1				
SP13044, Nabo Ganga Khal FCD Subproject, FCD&WC, Union : Chuadanga, HO Date:				
	Part-A: Construction of 2 vent(2.0mX2.0m). BoX Culvert K	2 vent(2.0mX2.0m) at	1,103,502	PSSWRSP
	Part-B: Construction of 1 vent(1.3mX1.3m) BoX Culvert K	1 vent(1.3mX1.3m) at	465,411	PSSWRSP
	Nabo Ganga Khal Re-excavation	3.46	1,441,015	Main
	Regulator	3V(1.5mX1.8m)	3,587,600	Main
	Pipe Sluice at Ch.0+945m	1-V(900mm Dia)	181,459	Main
	Pipe Sluice at Ch.0+975m(Left)	1-V(900mm Dia)	192,269	Main
	Pipe Sluice at Ch.0+975m(Right)	1-V(900mm Dia)	148,997	Main
	Pipe Sluice at Ch.1+580m	1-V(900mm Dia)	264,697	Main
SP14138, Kamri-Paksia Beel FCD Subproject, FCD, Union : Titudaha, HO Date:				
	Kamria Paksia khal re-excavation(ch.1000-3040m)	2.04	6,516,611	SSSWRDP
	Referenced line section	0.00	60,000	SSSWRDP
	Kamria Khal Re-excavation	3.20	812,011	Main
	Paksia Khal Re-excavation	1.05	70,645	Main
	Kamria Khal Regulator at Ch.0+170m	2-V(1.5mX1.5m)	2,303,818	Main
Jessore (Total SPs : 9 Nos.)				
Bagharpara				
PSSWRSP				
SP43063, Kuthurakandi Khal Subproject, DR&WC, Union : Bandabila, HO Date:				
	Part-A: Re-excavation of Katuarkandi Khal	0.85	246,596	Main
	Part-A: Katurakandi khal Regulator	2V-1.5mx1.8m 0.00	9,099,212	Main
	Part-B: WMCA office & others	12mx6m 0.00	1,555,489	Main
Chowgacha				
PSSWRSP				
SP44074, Swarupdaha Dhunar Khal Subproject, DR&WC, Union : Swarupdaha, HO Date:				
	Part-A: Construction of Dhunar khal Regulator by modificat	1V-10mx4.5m 0.00	10,825,649	Main
	Part-B: Construction of Sukra khal Regulator by modificatio	1V-5.2mx4.30m 0.00	6,286,211	Main
	Part-C: WMCA Office & Others	12mx6m 0.00	1,898,538	Main
	Part-A: Re-excavation Dhunar Khal	0.96	663,910	Main
	Part-B: Re-excavation Sukra Khal	0.24	236,151	Main
Jhikargacha				
SSWRDSP-1				
SP15281, Padma Beel FCD Subproject, FCD, Union : Shankarpur, HO Date: 20/01/2004				
	Embankment Re-sectioning	0.80	159,227	Main
	WMCA Office & Others	12mx6m 0.00	4,647,774	PSSWRSP
	Construction of 02 Nos U-Type Drain Culvert	7.0 Long 375mmx450mm	151,895	PSSWRSP
	Construction of 01 Nos U-Type Drain Culvert	7.0m long 625mmx600mm	101,782	PSSWRSP
	Khal Re-excavation	0.60	61,891	Main
	Regulator	1-V(1.5mX1.8m)	1,442,290	Main
	Box Culvert	1-V(2.5mX2.5m)	479,220	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Kesabpur SSWRDSP-1 SP12030, Baga Beel FCD Subproject, FCD, Union : Biddyanandakathi, HO Date:	O&M Shed & Fish Screen		227,801	Main
	Embankment Re-sectioning	0.45	78,074	Main
	Baga Khal Re-excavation	1.45	344,301	Main
	Branch Khal Re-excavation	1.83	151,910	Main
	Rehabilitation Baga Khal	2.83	739,658	Main
	Box Culvert	1-V(3.6mX3.6m)	358,608	Main
	Baga Beel Regulator	2-V(1.2mX1.8m)	3,419,881	Main
Monirampur SSWRDSP-2 SP24147, Gazsree-katakhali Subproject, FMD&WC, Union : Shyamkur, HO Date:	Re-excavation of Katakhali Khal	0.60	133,273	Main
	Re-sectioning of Embankment	3.65	1,361,641	Main
	Katakhali Regulator at Ch. 0+035 Km (Khal)	1 Vent-1.5mX1.8m 0.00	2,367,102	Main
	Drainage Outlet at Ch. 0+320Km (Embkt)	1 Vent-0.6mX0.9m 0.00	71,472	Main
	Drainage Outlet at Ch. 0+770Km (Embkt)	1 Vent-0.6mX0.9m 0.00	77,987	Main
	Drainage Outlet at Ch. 2+620Km (Embkt)	1 Vent-0.6mX0.9m 0.00	100,955	Main
	Drainage Outlet at Ch. 2+780Km (Embkt)	1 Vent-0.6mX0.9m 0.00	90,676	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	296,819	Main
Sadar SSWRDSP-1 SP13079, Ichali WCS Subproject, WC, Union : Ichali, HO Date: 15/05/2002	Part-A: Construction of 5 Nos 625mmx600mm U-drain	625mmx600mm & length5.0	3,649,170	PSSWRSP
	Part-B: Construction O &M sheed connction HBB Road	12mx6m 0.00	178,073	PSSWRSP
	Nanga Khal Re-excavation	4.77	682,476	Main
	Nanga Khal Rehabilitation	4.48	631,755	Main
	Ichali WRS	3-V(1.5mX2.0m)	4,276,754	Main
	Pipe Sluice-1	1-V(600mm Dia)	59,231	Main
	Pipe Sluice-2	1-V(600mm Dia)	64,714	Main
	Fish Landing		262,631	Main
	Fish Screen		53,341	Main
SSWRDSP-2 SP24144, Dolpur-Mukteshwary Khal Subproject, DR&WC, Union : Diara, HO Date:	Re-excavation of Dolpur Khal	1.08	388,891	Main
	Re-excavation of Mukteshwary Khal	2.80	1,583,904	Main
	Dolpur Khal WRS at Ch. 0+050Km(Khal)	2 Vent-1.5mX1.5m 0.00	3,369,649	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	291,849	Main
PSSWRSP SP46265, Khal Ghat Basundia Subproject, DR&WC, Union : Diara, HO Date: 30/05/2018	Part-A: Constuction of Regulator	1v - 1.2m X 1.5m 0.00	0	Main
	Part-B: Constuction of WMCA office and others	12m X 6m 0.00	0	Main
Sharsha SSWRDSP-2 SP24156, Gobra Beel - Batoker Beel Subproject, FMD, Union : Nizampur, HO Date:	Re-excavation of Shumurer Khal	1.00	182,604	Main
	Re-sectioning of Embankment	4.60	841,062	Main
	Gobra Beel Drainage Structure at CH. 0+500Km(Khal)	1 Vent-0.90m Dia 0.00	113,091	Main
	Gobra Beel Box Sluice at Ch. 0+100 Km (Khal)	1 Vent-0.9mX0.9m 0.00	1,116,050	Main
	O&M Shed	Size: 12mX6m 0.00	317,542	Main

Jhenaidah (Total SPs : 7 Nos.)

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Harinakunda PSSWRSP SP44084, Shitly Khal Subproject, DR, Union : Kapashatia, HO Date: 23/06/2016				
	Part-A: Re-excavation of Sitly Khal	4.30	2,418,498	Main
	Part-B: Re-excavation of Sitly Branch Khal	2.20	1,609,045	Main
	Part-C: Re-excavation of Badonert Khal	0.90	307,680	Main
	Part-D: Lined reference sections (7 nos.)	0.00	39,900	Main
	Part-A: WMCA Office & Others	12mx6m 0.00	1,492,908	Main
Kaliganj SSWRDSP-1 SP13048, Shirish Kath Khal FCD Subproject, FCD, Union : Niamatpur,Kola, HO Date:				
	Trimohoni -Doulatpur khal re-excavation(ch.00-1000m)	1.00	1,596,632	SSSWRDP
	Referenced line section (1nos)	0.00	23,164	SSSWRDP
	Structure	0.00	1,934,362	SSSWRDP
	Shirish Kath Khal Re-excavation	5.65	622,577	Main
	Balarampur Regulator	2-V(1.5mX1.8m)	2,326,466	Main
	O&M Shed		0	Main
	Pipe Culvert adjacent to Balarampur Regulator	2-V(900 mm dia)	0	Main
SP14198, Natopara Beel DR Subproject, DR, Union : Jamal, HO Date: 28/05/2001				
	Natopara Khal Re-excavation	1.30	222,074	Main
SSWRDSP-2 SP24179, Tetul Beel - Uri Beela Subproject, DR&WC, Union : Sundarpur Durgapur, HO				
	Re-excavation of Tetul Beel Khal	3.10	579,894	Main
	Tetul Beel WRS at Ch. 0+270 Km (Khal)	3 Vent-1.5mX2.0m 0.00	4,291,984	Main
	Tetul Beel Drainage Structure at Ch.2+330 Km(Khal)	1 Vent-2.5mX2.2m 0.00	674,001	Main
	Tetul Beel Drainage Structure at Ch.2+700Km(Khal)	1 Vent-2.5mX2.2m 0.00	674,001	Main
	O&M Shed	Size: 12mX6m 0.00	380,296	Main
Moheshpur SSWRDSP-1 SP12024, Goalhuda Khal FCD Subproject, FCD&WC, Union : Fatehpur, HO Date:				
	Embankment Re-sectioning	3.62	432,164	Main
	Rakhalbhoga Approach Embankment Re-sectioning	0.20	108,576	Main
	Goalhuda Khal Re-excavation	1.50	240,050	Main
	Rakhalbhoga Khal Re-excavation	1.36	130,143	Main
	Goalhuda Regulator	1-V(1.2mX1.2m)	1,176,999	Main
	Rakhalbhoga Regulator	1-V(1.5mX1.8m)	985,376	Main
Sadar SSWRDSP-1 SP12023, Baroikhali Khal FCD Subproject, FCD, Union : Porahati, HO Date: 14/06/2000				
	Baroikhali Khal Re-excavation	1.33	132,915	Main
	Baroikhali Regulator	1-V(1.5mX1.8m)	806,931	Main
SP14204, Gorer Beel DR Subproject, DR, Union : Naldanga, HO Date: 24/06/2001				
	Khal-1 Re-excavation	1.33	127,725	Main
	Khal-2 Re-excavation	0.75	159,686	Main
	Khal-3 Re-excavation	0.97	250,696	Main
Khulna (Total SPs : 9 Nos.)				
Batiaghata SSWRDSP-1 SP12026, Narayankhali FCD Subproject, FCD, Union : Amirpur, HO Date: 08/08/2001				
	Embankment Re-sectioning	7.78	1,473,157	Main
	Doania khal re-excavation(ch.80-1760m)	1.68	3,142,471	SSSWRDP
	Koria Vita khal re-excavation(ch.00-890m)	0.89	1,421,567	SSSWRDP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Kapur Pura khal re-excavation(ch.00-266m)	0.27	418,496	SSSWRDP
	Embankment re-sectioning(ch.900-1390m,3700-4075,3700)	1.66	5,109,113	SSSWRDP
	Bamboo Bridge(4nos)	0.05	192,240	SSSWRDP
	Salabunia Khal Re-excavation	2.11	279,959	Main
	Jabbarkhali Khal Re-excavation	1.14	72,086	Main
	Nangladah Khal Re-excavation	1.14	268,028	Main
	Nangladah Regulator	1-V(1.2mX1.5m)	2,356,786	Main
	Salabunia Box Sluice	1-V(0.9mx0.9m)	843,596	Main
	Jabbarkhali Box Sluice	1-V(0.9mX0.9m)	778,952	Main
	Doanar Regulator	1-V(1.2mX1.5m)	2,356,786	Main

PSSWRSP

SP45183, Bhandercot-Laksmikhola Subproject, DR, Union : Bhandercot, HO Date:

Part-A: Box Culvert-1 (2v-2.50m X3.50m)	(2v-2.50m X3.50m) 0.00	0	Main
Part-A: Re-excavation of Kalitola khal	1.90	1,769,196	Main
Part-E: Re-excavation of Bora Hazirabad khal	1.30	51,494	Main
Part-F: Re-excavation of Kolatola khal-2	0.70	760,508	Main
Part-G: Construction of Reference Lined Section	0.00	226,010	Main
Part-B: Box Culvert-2 (2v-2.50m X3.50m)	(2v-2.50m X3.50m) 0.00	0	Main
Part-C: Box Culvert-3 (1v-2.50m X3.50m)	(1v-2.50m X3.50m) 0.00	0	Main
Part-D: Box Culvert-4 (1v-2.50m X3.50m)	(1v-2.50m X3.50m) 0.00	0	Main
Part-E: WMCA Office & Others	12mX6m 0.00	0	Main
Part-B:Re-excavation of Katakhal khal	3.39	2,929,200	Main
Part-C: Re-excavation of Kolatola khal	1.30	1,143,754	Main
Part-D: Re-excavation of Ghater & Keshokhali khal	0.40	533,743	Main

Dakope

PSSWRSP

SP45161, Kalatala Kailashgonj Subproject, DR, Union : Kailashgonj, HO Date: 21/09/2017

Part-A: Re-excavation of Dhanapoti Khal	3.70	1,966,032	Main
Part-B: Re-excavation of Baro Khalir Khal	1.60	130,906	Main
Part-C: Re-excavation of Goalchira Khal	1.10	143,923	Main
Part-D: Re-excavation of Gholar Khal	0.80	53,705	Main
Part-E: Re-excavation of Kolatola Khal	1.00	96,944	Main
Part-F: Construction of Reference Lined Section	0.00	0	Main

SP45197, Harintala Goler Khal Subproject, DR, Union : Kailashgonj, HO Date: 21/09/2017

Part-A: WMCA office & Others	12mX6m 0.00	1,300,053	Main
Part-A: Re-excavation of Charar Khal	9.55	7,884,872	Main
Part-B: Re-excavation of Taktamari Khal	2.55	2,588,785	Main
Part-C: Re-excavation of Hetalbania Khal	1.10	342,787	Main
Part-D: Construction of Reference Lined Section	0.00	375,653	Main

Dumuria

SSWRDSP-1

SP13099, Latabunia FCD Subproject, FC, Union : Sahas, HO Date: 10/02/2002

Embankment Re-sectioning	5.75	2,660,170	Main
Latabunia Regulator	1-V(1.5mX1.5m)	2,232,672	Main

SP13106, Bagchar-Badurgacha FCD Subproject, FC, Union : Shobhana,Atalia, HO Date:

Embankment Re-sectioning(Sec. A)	9.83	4,375,840	Main
Embankment Re-sectioning(Sec. B)	4.98	774,997	Main
Re-sectioning of embankment	4.60	3,774,971	PSSWRSP
Simanar Khal Re-excavation	1.00	75,335	Main
Reshiker Khal Re-excavation	1.97	332,049	Main
Naptir Khal Re-excavation	1.50	254,971	Main
Simanar Regulator at Ch.1+850m	1-V(1.5mX1.5m)	2,175,810	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Rupsha SSWRDSP-1 SP12027, Jabusa Beel FCD Subproject, FCD, Union : Naihati, HO Date: 31/10/2000	Bakotmari Regulator at Ch.8+670m	1-V(1.5mX1.5m)	2,101,869	Main
	O&M Shed		264,419	Main
SSWRDSP-2 SP21011, Padma Beel Subproject, FMD, Union : Naihati, HO Date: 30/01/2008	Embankment Re-sectioning	5.66	1,313,955	Main
	Embankment Rehabilitation	2.76	542,800	Main
	Gupia khal re-excavation(ch.00-1075m)	1.08	2,347,247	SSSWRDP
	Gupia khal re-excavation(ch.3000-3840m)	0.84	1,749,236	SSSWRDP
	Saijar khal re-excavation(ch.00-560m)	0.56	1,122,268	SSSWRDP
	Fedur khal re-excavation(ch.00-430m)	0.43	658,990	SSSWRDP
	Embankment re-sectioning(ch.00-2808m)	2.81	4,690,098	SSSWRDP
	Bamboo bridge(4nos)	0.08	188,471	SSSWRDP
	Referenced line section(6nos)	0.00	179,876	SSSWRDP
	Gupier Khal Re-excavation	1.05	385,591	Main
	Sukurmari Khal Re-excavation	3.26	409,889	Main
	Haraniar Khal Re-excavation	0.90	55,818	Main
	Sukurmari Khal Rehabilitation	2.37	119,135	Main
	Noashiyar Khal Re-excavation	1.25	338,777	Main
	Haraniar Khal Rehabilitation	1.50	183,583	Main
	Haraniar Khal(Br.) Rehabilitation	0.64	145,542	Main
	Gupier Khal Rehabilitation	1.00	197,114	Main
	Harigosh Khal Re-excavation	1.78	526,241	Main
	Gupier Regulator	2-V(1.5mX1.8m)	3,575,159	Main
	Haraniar Regulator	1-V(1.2mX1.5m)	1,684,156	Main
	Sukurmari Regulator	2-V(1.5mX1.8m)	2,019,472	Main
	Harigosh Box Sluice	1-V(1.2mX1.2m)	1,093,420	Main
	Noashiyar Khal Pipe Sluice at Ch.2+675m	1-V(900mm Dia)	658,479	Main
	Fish Screen at Sukumari Regulator		51,227	Main
	Fish Screen at Gupier Regulator		51,227	Main
SP25228, Sreerampur Subproject, FMD&WC, Union : Naihati, HO Date: 05/12/2012	Padma Beel Regulator	4-V(1.50mX1.80m) 0.00	5,548,643	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	242,880	Main
Kushtia (Total SPs : 7 Nos.) Bheramara SSWRDSP-1 SP13111, Bahirchar FCD Subproject, FC, Union : Bahirchar, HO Date: 21/04/2002	Re-sectioning of Embankment	2.80	1,154,091	Main
	Sreerampur Khal Regulator at Ch. 0+200Km (Khal)	1 Vent-1.5mX1.8m 0.00	5,734,898	Main
	Re-excavation of Sreerampur Khal	1.25	416,188	Main
	Re-excavation of Branch Khal	0.60	107,012	Main
	Re-sectioning of Sreerampur embankment	0.75	758,957	PSSWRSP
	Embankment Re-sectioning	6.72	2,330,752	Main
	Podda Nodir Embankment re-sectioning(ch.4260-6550m)	2.29	4,529,752	SSSWRDP
	Podda Nodir Embankment's regulator repair	0.00	458,930	SSSWRDP
	Regulator at Ch.6+685m	1-V(1.5mX1.8m)	2,305,179	Main
	Box Sluice at Ch. 4+216m	1-V(1.2mX1.2m)	551,381	Main
	Pipe Sluice at Ch. 5+500m	1-V(1.05m Dia)	551,382	Main
	Pipe Sluice at Ch. 0+774m	1-V(900mm Dia)	685,525	Main
	Pipe Sluice at Ch. 3+315m	1-V(900mm Dia)	585,292	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP15261, Satbaria-Dharampur DR & WCS Subproject, DR&WC, Union : Dharampur, HO				
	Khal Re-excavation	2.32	197,059	Main
	WRS	4-V(1.5mX1.8m)	3,055,523	Main
	Satbaria Flushing Sluice at Ch. 2+370m	2-V(1.5mX1.8m)	3,099,918	Main
	Satbaria Flood Bypass on Hisna River	3-V(2.5mX1.75m)	1,612,073	Main
Daulatpur SSWRDSP-1				
SP12031, Khired Shah FCD Subproject, FCD&WC, Union : Pragpur, HO Date: 22/01/2001				
	Embankment Re-sectioning	0.38	236,470	Main
	Moirampur Khal Re-excavation	0.78	108,815	Main
	Kashir Dara Khal Re-excavation	1.00	118,392	Main
	Moirampur Regulator	1-V(1.5mX1.8m)	1,482,179	Main
	Kashir Dara Regulator	1-V(1.2mX1.2m)	1,151,022	Main
Khoksa SSWRDSP-1				
SP12029, Sirajpur Haor FCD Subproject, WC, Union : Khoksa,Janipur, HO Date:				
	Earthen Cross Dam	0.06	272,459	Main
	Sirajpur Haor Re-excavation	6.21	7,450,117	Main
	Flushing Sluice	2-V(1.5mX1.8m)	2,717,798	Main
	Fish Screen		0	Main
PSSWRSP				
SP46230, Uthuli-Jayantihazra Mashilia Khal, DR&WC, Union : Joyontihazra, HO Date:				
	Part-A: WRS (1v-1.5mX2.0m)	(1v-1.5mX2.0m) 0.00	0	Main
	Part-E: Re-excavation of Bhaduri Chalk khal	0.72	75,492	Main
	Part-F: Construction of Reference Lined Section	0.00	166,028	Main
	Part-B: WRS (2v-1.5mX1.8m)	(2v-1.5mX1.8m) 0.00	0	Main
	Part-C: Box Culvert (1v-4.0mX3.7m)	(1v-4.0mX3.7m) 0.00	0	Main
	Part-D: Box Culvert (1v-3.0mX3.0m)	(1v-3.0mX3.0m) 0.00	0	Main
	Part-E: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Jayantihazra-Radhanagar-Mamur	2.20	1,166,022	Main
	Part-B: Re-excavation of Uthuli -masisbathan khal	3.17	1,629,154	Main
	Part-C: Re-excavation of Mashila khal	1.10	288,201	Main
	Part-D: Re-excavation of Uttar shampur khal	0.40	87,229	Main
SP46279, Komorbogh-Raipur Ajail Subproject, DR, Union : Osmanpu, HO Date:				
	Part-G: Construction of Reference Lined Section	0.00	214,696	Main
	Part-A: Re-exavation of Hijlabot khal	2.80	1,101,151	Main
	Part-B: Re-exavation of Ajail khal	2.76	919,965	Main
	Part-C: Re-exavation of Ajail Branch khal	0.90	174,627	Main
	Part-D: Re-exavation of Raipur khal	2.29	52,486	Main
	Part-E: Re-exavation of Raipur Branch khal	0.85	476,417	Main
	Part-F: Re-exavation of komorbhogh khal	1.10	217,941	Main
Kumarkhali PSSWRSP				
SP45164, Nandigram-Muragasha Khal Subproject, DR, Union : Sadki, HO Date:				
	Part-A: Construction of 2v-(3.5mX4.0m) Box culvert on Mur	2v-(3.5mX4.0m) 0.00	0	Main
	Part-F: Re-excavation of kana Beel Khal	0.65	426,769	Main
	Part-G: Re-excavation of Mohishakhola Khal	0.70	291,889	Main
	Part-H: Construction of Reference Lined Section	0.00	331,372	Main
	Part-B: Construction of 1v-(2.0mX2.0m) Box culvert on Mat	1v-(2.0mX2.0m) 0.00	0	Main
	Part-C: Construction of 1v-(3.0mX3.0m) Box culvert on Mai	1v-(3.0mX3.0m) 0.00	0	Main
	Part-D: Construction of WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of muragacha Khal	2.99	1,467,326	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Re-excavation of Karatkandi Khal	1.10	273,805	Main
	Part-C: Re-excavation of Maliat-Sultanpur Khal	1.00	468,401	Main
	Part-D: Re-excavation of Mat Maliat Khal	1.94	267,730	Main
	Part-E: Re-excavation of Nalbatora Khal	0.60	398,551	Main
Magura (Total SPs : 6 Nos.)				
Sadar				
SSWRDSP-1				
SP11007, Kapashati FCD Subproject, FCD, Union : Maghi, HO Date: 20/11/2001				
	Kapashati Khal Re-excavation	1.45	160,259	Main
	Digha Beel Khal Re-excavation	0.80	57,660	Main
	Kapashati Regulator	2-V(1.5mX1.8m)	2,219,072	Main
SP14139, Chaprar Khal FCD Subproject, FCD, Union : Kuchiamora, HO Date: 26/05/2004				
	Embankment Re-sectioning	0.30	69,082	Main
	Chaprar khal re-excavation(ch.00-850m)	0.85	1,335,720	SSSWRDP
	Referenced line section(1nos)	0.00	24,451	SSSWRDP
	Bamboo Bridge(1nos)	0.02	56,637	SSSWRDP
	Chapra Khal Re-excavation	0.94	121,411	Main
	Pipe Sluice at Ch.0+050m	2-V(900mm Dia)	1,211,961	Main
SSWRDSP-2				
SP24118, Lakshmipur Khal Subproject, FMD, Union : Jagdal, HO Date: 05/05/2009				
	Re-excavation of Laxmipur Khal	3.20	427,120	Main
	Re-section of Dyke	0.40	290,467	Main
	O & M Shed	Size: 9.0mX5.0m 0.00	319,947	Main
	Laxmipur Khal Regulator at Ch. 1+355Km(Khal)	3 Vent-1.5mX1.8m 0.00	4,639,883	Main
	Part-A: Imp. of Jagla Bazar-Laxmipur sluice Gate Road	0.00	2,973,778	PSSWRSP
	Part-A: Re-excavation of Laxmipur-Charpara khal	1.65	3,005,986	PSSWRSP
	Part-B: Re-sectioning of Laxmipur-Charpara khal	0.37	342,679	PSSWRSP
PSSWRSP				
SP45199, Beel Aksi Subproject, FMD, Union : Jogodal, HO Date: 21/09/2017				
	Part-A: Construction of Pipe Sluice	(1v-0.9m dia) 0.00	0	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-sectioning of Beel Aksi Embankment	0.80	434,720	Main
	Part-B: Re-excavation of Iro Khal	0.40	264,647	Main
	Part-C: Construction of Reference lined section	0.00	26,007	Main
Shalikha				
SSWRDSP-1				
SP13058, Kathalbaria Khal FCD Subproject, FCD&WC, Union : Salikha,Bunagati, HO				
	Embankment Re-sectioning	1.18	84,554	Main
	Kathalbaria Khal Re-excavation	2.75	160,279	Main
	Kathalbaria Regulator	2-V(1.5mX1.8m)	1,805,441	Main
	Sorsuna WRS	1-V(1.5mX1.8m)	1,710,714	Main
Sreepur				
SSWRDSP-1				
SP14140, Sonatundi WCS Subproject, WC, Union : Sabdalpur, HO Date: 17/11/2001				
	Sonatundi Khal Re-excavation	1.22	246,886	Main
	WRS at Ch.0+200m	1-V(1.5mX1.5m)	1,774,428	Main
Meherpur (Total SPs : 20 Nos.)				
Gangni				
SSWRDSP-1				
SP14175, Pirtola FCD Subproject, FCD, Union : Kazipur, HO Date: 15/05/2002				
	Pirtola Khal Re-excavation	1.35	212,970	Main
	Regulator	2-V(1.2mX1.5m)	2,223,288	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	O&M Shed		0	Main
SSWRDSP-2				
SP22028, Damush-Mathabhanga Subproject, FMD, Union : Kazipur, HO Date: 26/12/2006				
	Shahebnagar Khal Re-excavation	1.25	235,183	Main
	Shahebnagar Khal Regulator at Ch.0+070 km	2-V(1.50mX1.80m) 0.00	4,239,852	Main
	O&M Shed	12.00mX6.00m 0.00	360,148	Main
SP24116, Chechania Khal Subproject, FMD, Union : Mothmura, HO Date: 05/11/2008				
	Re-excavation of Chechania Khal	1.60	1,095,199	Main
	Chechania Khal Regulator at Ch 0+125 Km	5 Vent-1.5mX1.8m 0.00	8,114,075	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	307,309	Main
SP25268, Nagder Khal Subproject, FMD&WC, Union : Raipur, HO Date: 07/04/2014				
	Kaikuri Khal Regulator at Ch. 0+247Km(Khal)	2 Vent-1.5mX1.8m 0.00	3,877,124	Main
	Nagder Khal Regulator at Ch. 0+020Km(Khal)	3 Vent-1.5mX1.8m 0.00	4,812,814	Main
	Re-excavation fo Markerhat Khal	4.20	1,271,280	Main
	Re-excavation fo Kaikuri Khal	2.00	607,397	Main
	Re-excavation fo Nagder Khal	0.30	60,583	Main
	O&M Shed	Size: 9mX5m 0.00	441,981	Main
	Part-A: Improvement of HBB road Shimultola to Hariadah n	at ch.0+000 to 1+300 km	3,659,000	PSSWRSP
PSSWRSP				
SP42017, Nabinpur Dholar Beel Subproject, FMD, Union : Kathuli, HO Date: 05/09/2017				
	Part-A: Re-excavation of Nabinpur Khal & Resectioning of i	3.30	3,685,261	Main
	Part-C: Construction of reference lined section (Nabinpur kl	0.00	219,094	Main
	Part-B: Re-excavation of Petkata Khal	0.70	432,912	Main
	Part-A: Nabinpur Khal Regulator	3V-1.5mx1.8m 0.00	9,309,602	Main
	Part-D: Construction of pipe culvert	At Ch.0+500km to	1,409,645	Main
	Part-C: WMCA office and others	12.0mx6.0m 0.00	1,211,309	Main
	Part-B: Nabinpur foot Bridge	At Ch.1+170km to	1,313,048	Main
SP45193, Madiar Beel Subproject, DR&WC, Union : Dhankhola, HO Date: 05/09/2017				
	Part-A: Construction of Box Culvert (1v-4.50mX5.50m) at K	(1v-4.50mX5.50m) 0.00	0	Main
	Part-C: Re-excavation of Boalia Khal and Construction of F	0.90	843,993	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-B: Re-excavation of Madiar Khal and Construction of F	0.80	788,698	Main
	Part-A: Re-excavation of Jhumra Ghat Khal and Constructi	2.00	4,803,975	Main
	Part-D: Earth Filling of Nityanandapur Madianama Road (0	0.65	2,847,975	Main
SP46251, Mundail Khal Subproject, DR&WC, Union : Sholotaka, HO Date:				
	Part-A: Construction of Mundail Khal WRS	(3v-1.50mX2.00m) 0.00	8,430,909	Main
	Part-B: Construction of Box Culvert	(1v-4.00mX3.25m) 0.00	2,119,944	Main
	Part-C: Construction of WMCA Office and Others	12mX6m 0.00	1,361,550	Main
	Part-A: Re-excavation of Mundail Khal and Construction of	3.85	3,073,014	Main
	Part-B: Re-excavation of Mundail Branch Khal and Constr	0.65	182,209	Main
	Part-C: Re-excavation of Morka Khal and Construction of F	1.10	1,055,734	Main
Mujibnagar				
PSSWRSP				
SP42018, Kata Khal Subproject, FMD, Union : Mohajanpur, HO Date: 05/09/2017				
	Part-A: Re-excavation of kata khal	0.70	491,000	Main
	Part-A: Kata Khal Regulator	1V-1.5mx1.8m 0.00	4,621,279	Main
	Part-C: WMCA office and others	12mx6m 0.00	1,037,797	Main
	Part-B: Kata Khal Foot Bridge at Ch. 0+500km	at Ch. 0+500km 0.00	566,754	Main
Sadar				
SSWRDSP-1				
SP11006, Garir Khal FCD Subproject, Fisheries & WC, Union : Amdaha, Monakhali, HO				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Approach Embankment	0.78	257,593	Main
	Garir Khal Re-excavation	1.75	350,134	Main
	Garir Khal Regulator	2-V(1.2mX1.5m)	2,300,060	Main
	Culvert		565,618	Main
	Culvert at Ch.0+335m		18,238	Main
	Culvert at Ch.0+380m		18,238	Main
	Culvert at Ch.0+086m		18,238	Main
SP13050, Toplah Khal FCD Subproject, FCD, Union : Baguan, HO Date: 16/08/2001				
	Embankment Re-sectioning	1.80	635,476	Main
	Toplah Khal Re-excavation	0.70	298,402	Main
	Toplah Regulator	1-V(1.5mX1.5m)	1,876,411	Main
SP13051, Asrafpur FC Subproject, FC, Union : Amdaha, HO Date: 13/08/2001				
	Asrafpur Regulator	1-V(1.5mX1.5m)	1,914,997	Main
	RCC Palasiding Work		0	Main
	O&M Shed		0	Main
SP14135, Saraswati Khal FCD Subproject, FCD, Union : Pirojpur, HO Date: 14/11/2012				
	Saraswati Khal Re-excavation	0.30	122,000	Main
	Saraswati Khal Regulator at Ch.0+100m	3-V(1.5mX1.5m)	2,974,603	Main
SP14176, Nowadapara FCD Subproject, FCD, Union : Monakhali, HO Date: 04/06/2002				
	Nawdapara Khal Re-excavation	0.27	52,115	Main
	Regulator at Ch.0+113m	1-V(1.2mX1.2m)	1,422,557	Main
SP15237, Kakrajal FCD Subproject, FCD, Union : Kutubpur, HO Date: 25/05/2002				
	Rehabilitation of Kakrazol Regulator	2-V(1.5mX1.8m)	675,140	Main
SP15259, Kutubpur Beel FCD Subproject, FCD, Union : Kutubpur, HO Date: 28/05/2002				
	Embankment Re-sectioning	3.20	228,477	Main
	Hitimpur Khal Re-excavation	0.75	77,730	Main
	Hitimpur Regulator at Ch.0+220m	1-V(1.2mX1.5m)	1,168,696	Main
SSWRDSP-2				
SP21008, Katakhal Subproject, FMD, Union : Buripota, HO Date: 27/12/2006				
	Katakhal Khal Re-excavation	0.49	22,513	Main
	Katakhal Regulator at Ch.0+050km	2-V(1.50mX1.80m) 0.00	1,978,764	Main
	Part-A: Fatapur-Tatultala khal	0.90	4,449,843	PSSWRSP
SP24135, Gomara Beel Subproject, FMD, Union : Perojpur, HO Date: 07/01/2010				
	Gomara Khal Regulator at Ch. 0+315Km(Khal)	Size: 2 Vent-1.5mX1.8m 0.00	3,921,306	Main
	Re-sectioning Embankment	2.92	697,499	Main
	Re-excavation Gomara Khal	0.84	229,835	Main
	O&M Shed	Size: 12.0mmX6.0m 0.00	319,502	Main
	Improvement of Baliarpur-Ragunathpur Road	at Ch. 1514km to 2314 km	4,007,230	PSSWRSP
SP25316, Nol Beel Subproject, FMD, Union : Buripota, HO Date: 13/11/2012				
	Nol Beel Khal Regulator at Ch.0+042Km (Khal)	2 Vent-1.5mX1.8m 0.00	5,330,864	Main
	O&M Shed	Size: 9mX5m 0.00	438,913	Main
PSSWRSP				
SP44101, Bonduk Khali Khal Subproject, FMD, Union : Buripota, HO Date: 14/09/2016				
	Part-A: Modification of Existing Regulator	1 No. 0.00	0	Main
	Part-B: Construction of Box Culvert	1No. 0.00	0	Main
	Part-C: Construction of HBB Road	.5 km 0.00	0	Main
	Part-D: Construction of WMCA Office & Others	12mx6m 0.00	0	Main
	Part-A: Re-excavation of Bonduk Khal	1.03	720,951	Main
SP44112, Harirampur Beel Subproject, FMD, Union : Buripota, HO Date: 14/09/2016				
	Part-A: Modification of existing Culvert-1 in to Gated Struct	0.00	0	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Modification of existing Culvert-1 in to Gated Struct	0.00	0	Main
	Part-C: Improvement Of HBB Road	0.00	0	Main
	Part-D:WMCA office & others	0.00	0	Main
	Part-A: Re-Sectioning Of Embankment	2.40	2,819,648	Main
Narail (Total SPs : 22 Nos.)				
Kalia				
SSWRDSP-1				
SP15325, Mulasree-Pakhimara FCD Subproject, FCD, Union : Pahardanga, HO Date:				
	Embankment Re-sectioning	4.23	1,058,732	Main
	Mulasree Khal Re-excavation	0.75	103,590	Main
	Pakhimara Khal Re-excavation	2.00	179,634	Main
	Mulasree Regulator	2-V(1.5mx1.8m)	1,978,228	Main
	Pakhimara Regulator	2-V(1.2mx1.5m)	2,332,838	Main
SP15326, Gachbaria Khal DR Subproject, DR, Union : Joynagar, HO Date: 25/05/2002				
	Gachbaria Khal Re-excavation	4.00	1,281,259	Main
	Gachbaria Br. Khal Re-excavation	0.50	51,297	Main
	Gachbaria Br. Khal-1 Re-excavation	0.48	95,103	Main
SSWRDSP-2				
SP22013, Jogania Beel Subproject, FMD, Union : Bauisona, HO Date: 17/07/2007				
	Dudkura Khal Regulator at Ch.0+050 km	2-V(1.50mX1.80m) 0.00	3,173,506	Main
	Sitkitala Khal Re-excavation	4.35	492,778	Main
	Dudkura Khal Re-excavation	2.20	416,072	Main
	Sitkitala Khal Regulator at Ch.0+050 km	2-V(1.50mX1.80m) 0.00	3,112,055	Main
	O&M Shed	12.00mX6.00m 0.00	293,746	Main
PSSWRSP				
SP44135, Debdun Baisena Khal Subproject, DR&WC, Union : Bayosona/ Joynagar, HO				
	Part-A: Box Culvert (1V-5mX2.5m)	(1V-5mX2.5m) 0.00	1,526,122	Main
	Part-B: Construction of WMCA Office & others	12mX6m 0.00	1,430,100	Main
	Part-A: Re-excavation fo Debdan Khal	1.70	1,200,969	Main
	Part-B: Re-excavation fo Ranmanagar Khal	0.55	677,340	Main
	Part-C: Re-excavation fo Bunar Khal	0.30	256,728	Main
	Part-D:Consturction Of Reference Lined Section	0.00	63,961	Main
Lohagara				
SSWRDSP-1				
SP13076, Maigram FCD Subproject, FCD, Union : Kotakul, HO Date: 26/10/2000				
	Embankment Re-sectioning	4.05	970,806	Main
	Khal Re-excavation	1.31	677,054	Main
	Maigram Regulator	2-V(1.2mX1.8m)	2,302,741	Main
SP14177, Hazrakhali WCS Subproject, WC, Union : Lakmipasa, HO Date: 31/12/2003				
	Hazrakhali Khal Re-excavation	4.25	1,001,288	Main
	WRS at Ch.1+630m	2-V(1.5mX1.5m)	2,163,637	Main
SP15339, Beel Jatkia DR & WCS Subproject, DR&WC, Union : Noagram, HO Date:				
	Approach Dyke Re-sectioning	1.85	471,237	Main
	Dodaria Khal Re-excavation	4.50	832,757	Main
	Manikganj-Sultia Khal Re-excavation	4.50	1,657,811	Main
	WRS	4-V(1.5mX1.8m)	4,646,318	Main
SSWRDSP-2				
SP25217, Sarulia Subproject, FMD, Union : Kotakul, Auria, HO Date: 11/04/2011				
	Arenda Khal Regulator at Ch. 0+080Km(Khal)	1 Vent-1.5mX1.5m 0.00	2,908,174	Main
	Sarulia Khal Regulator at Ch. 0+075Km(Khal)	2 Vent-1.5mX1.8m 0.00	3,964,290	Main
	O&M Shed	Size: 9mX5m 0.00	317,456	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Arenda Khal	1.00	404,906	Main
	Re-excavation of Sarulia Khal	2.00	184,408	Main
PSSWRSP				
SP46288, Gondab Dhopadah Khal Subproject, DR, Union : kashipur, HO Date:				
	Part-A: Re-excavation of Gondab Dhopadaha Tushkhali kh	3.70	3,712,578	Main
	Part-B: Construction of Reference Lined Section	0.00	0	Main
Sadar				
SSWRDSP-1				
SP12038, Chanduliar Char FCD Subproject, FCD&WC, Union : Maizpara, HO Date:				
	Embankment Re-sectioning	1.00	305,273	Main
	Chanduliar Khal Re-excavation	0.50	12,689	Main
	Chanduliar Khal Regulator	1-V(1.5mx1.8m)	1,164,373	Main
SP13067, Rehabilitation of Khatnur Beel WCS Subproject, FCD&WC, Union :				
	Embankment Re-sectioning	1.05	270,466	Main
	Khatnur Beel WRS	2-V(1.05m Dia)	788,512	Main
SP13077, Siapagla FCD Subproject, FCD&WC, Union : Tularampur, HO Date: 25/10/2000				
	Barmara Regulator	1-V(1.5mX1.8m)	932,648	Main
	Siapagla Regulator	2-V(1.5mX1.8m)	1,521,588	Main
SP14190, Panu Khal DR & WCS Subproject, DR&WC, Union : Maizpara, HO Date:				
	Panu Khal Re-excavation	0.78	258,255	Main
	WRS at Ch.0+150m	1-V(1.2mX1.8m)	891,055	Main
SSWRDSP-2				
SP22018, Dumkuria-Datbanga Beel Subproject, DR, Union : Bichhali, HO Date: 18/12/2007				
	Khal Re-excavation	2.76	1,003,538	Main
SP25202, Bahirgram Subproject, FMD, Union : Kalora, HO Date: 12/10/2010				
	Bahirgram Khal Regulator at Ch. 0+260Km(Khal)	3 Vent-1.5mX1.8m 0.00	5,458,518	Main
	Re-sectioning of Bahirgram & Bahirgram-RamnagaEmkt	0.35	325,480	Main
	Haribhanga Khal Regulator at Ch.0+120Km (Khal)	3 Vent-1.5mX1.8m 0.00	5,815,250	Main
	Re-excavation of Musuri Khal	1.57	241,010	Main
	O&M Shed	Size: 9mX5m 0.00	351,935	Main
	Re-sectioning of Bahirgram Embankment Reach-1	0.30	181,392	Main
	Re-sectioning of Bahirgram Embankment Reach-2	1.50	625,737	Main
	Re-sectioning of Bahirgram Embankment Reach-3	0.58	311,780	Main
SP25219, Debbhog-Sheikhpara Subproject, FMD, Union : Shekhhati, HO Date: 17/05/2010				
	Re-excavation of Sheikhpara Khal	1.40	584,583	Main
	Re-excavation of Shemulia Khal	2.00	281,728	Main
	Re-sectioning of Devbhog-Shekhpara Embankment	7.50	6,185,730	Main
	Debbhog Khal Regulator at Ch. 0+102Km (Khal)	3 Vent-1.5mX1.8m 0.00	9,277,560	Main
	Sheikhpara Regulator	2 Vent-1.5mX1.8m 0.00	7,108,569	Main
	O&M Shed	Size: 9mX5m 0.00	448,467	Main
	Re-excavation of Devbhog Khal	3.48	1,616,645	Main
	Re-excavation of Devbhog Branch Khal	1.40	389,164	Main
	Re-excavation of Paschimpara Khal	2.30	318,385	Main
	Part-A: Construction of Devbog Branch Khal Pipe sluice Ga	(3v-900m) 0.00	3,244,539	PSSWRSP
	Part-B: Re-excavation of Devbog Branch Khal .	1.20	247,948	PSSWRSP
	Devboge khal re-excavation(ch.00-3600m)	3.60	5,548,296	SSSWRDP
	Sekhpara khal re-excavation(ch.00-1850m)	1.85	2,864,356	SSSWRDP
	Referenced line section (5 nos)	0.00	172,179	SSSWRDP
	Bamboo bridge(2 nos)	0.00	151,031	SSSWRDP
SP25242, Hawai Khali Subproject, DR&WC, Union : Auria, Chandipur, HO Date:				
	Hawai Khali WRS at Ch. 1+815Km	4 Vent-1.5mx1.8m 0.00	5,507,122	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	O&M Shed	Size: 9mX5m 0.00	553,176	Main
	Re-excavation of Hawai Khali Khal	4.00	1,086,405	Main
	Re-excavation of Koi Beel Khal	0.40	24,790	Main
SP25243, Charabari Subproject, FMD&WC, Union : Auria, HO Date: 13/04/2010				
	Re-excavation of Charabari Khal	0.36	62,474	Main
	Charabari Khal Regulator at Ch. 0+340 Km	1 Vent-1.5mX1.8m 0.00	1,828,597	Main
	O&M Shed	Size: 9mX5m 0.00	347,881	Main
SP25249, Madhurgarea Subproject, FMD&WC, Union : Tularampur, HO Date: 21/04/2010				
	Re-excavation of Madhurgarea Khal	2.40	303,396	Main
	Madhurgarea Regulator at Ch. 0+050Km (Khal)	2 Vent-1.5mX1.8m 0.00	4,573,302	Main
	Malidanga WRS at Ch. 2+150Km (Khal)	1 Vent-1.2mX1.2m 0.00	297,090	Main
	Re-sectioning of Madhurgarea Embankment	2.80	1,336,973	Main
	O&M Shed	Size: 9mX5m 0.00	293,170	Main
SP25279, Bhomordia Subproject, FMD, Union : Chandibarpur, HO Date: 03/08/2010				
	Bhomordia Khal Regulator at Ch.0+080Km	1 Vent-1.5mx1.8m 0.00	4,331,244	Main
	Re-excavation of Bhomordia Khal	1.50	594,429	Main
	O&M Shed	Size: 9mx5m 0.00	476,713	Main
SP25283, Shaikati Subproject, FMD, Union : Shaikhati, HO Date: 19/04/2011				
	Tapanbag Khat Regulator at Ch. 0+530Km	3 Vent-1.5mX1.8m 0.00	6,563,608	Main
	O&M Shed	Size: 9mX5m 0.00	0	Main
	Re-excavation of Tapanbag Main & Br. Khal	1.90	1,359,919	Main
	Seikhhati khal re-excavation(ch.00-1470m)	1.47	1,789,917	SSSWRDP
	Referenced line section(2nos)	0.00	59,375	SSSWRDP
	Bamboo bridge(1nos)	0.01	45,309	SSSWRDP
SP25292, Hezia Subproject, CAD, Union : Bhadrabila, HO Date: 10/04/2011				
	RCC Irrigation Canal System	2435 m Length 0.00	10,500,686	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	0	Main
	Re-excavation of Hezia Khal	2.75	538,355	Main
Satkhira (Total SPs : 10 Nos.)				
Kalaroa				
SSWRDSP-1				
SP12015, Vorvoria Beel FCD Subproject, FCD&WC, Union : Kushadanga,Keralkata, HO				
	Embankment Re-sectioning	4.84	618,359	Main
	Part-A: Re-sectioning of chittla Battala Road by 25 mm	0.37	4,593,537	PSSWRSP
	WMCA Office building and others	WMCA(12mX6m) 0.00	1,715,351	SSSWRDP
	Chetla Beel Khal Re-excavation	0.37	9,628	Main
	Padma Beel Khal Re-excavation	0.30	1,723	Main
	Vorvoria Beel Khal Re-excavation	0.16	7,844	Main
	Nata Beel Khal Re-excavation	0.73	20,605	Main
	Vorvoria Pipe Culvet	2-V(1000mm Dia)	80,510	Main
	Nata Beel Box Culvert	1-V(3.6mx3.6m)	512,042	Main
	Chetla Box Sluice	1-V(.9mx.9m)	540,937	Main
SP13054, Khorda Baor FCD Subproject, FCD, Union : Diara, HO Date: 20/03/2002				
	Khorda Baor Khal Re-excavation	0.30	60,613	Main
	Bridge cum Regulator	3-V(1.5mx1.8m)	4,563,412	Main
SP13092, Sonai Khal FCD Subproject, FCD, Union : Sonabaria, HO Date: 30/06/2002				
	Sonai Khal Regulator	3-V(1.5mX1.8m)	4,859,025	Main
SP15301, Sibananda Khal DR Subproject, DR, Union : Kushodanga, HO Date: 16/10/2002				
	Shabananda Khal Re-excavation	0.57	33,146	Main
	Shabananda Khal Regulator	2-V(1.5mX1.5m)	1,677,909	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
---	-----------	------------------------	------------------------------	-----------------------

SP15302, Panikaoria FCD Subproject, FCD, Union : Kushodanga, HO Date: 16/10/2002

Part-A: WMCA Office & Others	12mX6m 0.00	1,722,897	PSSWRSP
Atalia Bandal Khal Re-excavation	0.36	24,218	Main
Regulator	1-V(1.5mX1.5m)	1,701,661	Main

SP15303, Daipara Khal DR Subproject, DR, Union : Jugikhali,Diara, HO Date: 14/10/2002

Khal Re-excavation	0.44	17,959	Main
Culvert at Ch.0+440m	1v(2.5mX2.5m)	252,143	Main

PSSWRSP

SP46263, Khetrapara Subproject, FMD, Union : Joynagar, HO Date:

Part-A: Construction of WRS	2v-1.5mX1.8m 0.00	7,264,820	Main
Part-B: Construction of Box-Culvert	2v-4.5mX4.0m 0.00	3,733,446	Main
Part-C: Construction of WMCA office and others	12mX6m 0.00	1,276,816	Main
Part-A: Re-excavation of Thakurpara Embankment	2.50	4,244,710	Main
Part-B: Re-excavation of Khetrapara-Joynogor Khal	1.30	1,684,594	Main
Part-C: Construction of reference lined section	0.00	63,302	Main

Sadar

PSSWRSP

SP46257, Hazipur Subproject, DR&WC, Union : Jaudanga, HO Date:

Part-A: Regulator	(2v-1.5mX1.8m) 0.00	7,073,740	Main
Part-B: Construction of WMCA Office and others	12mX6m 0.00	1,143,484	Main
Part-A: Re-excavation of Hajipur khal	1.00	1,331,658	Main
Part-B: Construction of Reference Lined Section	0.00	51,576	Main

Tala

SSWRDSP-1

SP15335, Jetua-Kanaidha FCD Subproject, FCD, Union : Jalalpur, HO Date: 24/02/2003

Embankment Re-sectioning	14.13	7,343,023	Main
Jetua Khal Re-excavation	0.77	323,897	Main
Jetua Gher Khal Re-excavation	1.38	135,871	Main
Dudher Khal Re-excavation	0.74	59,683	Main
Jetua Regulator at Ch.1+750m	2-V(1.5mX1.8m)	3,089,203	Main
Kalaparia Regulator at Ch.8+225m	2-V(1.5mX1.8m)	3,123,288	Main
Jetua Gher Regulator at Ch.2+100m	2-V(1.5mX1.8m)	3,127,981	Main
Dudher Khal Regulator	1-V(1.5mX1.8m)	1,659,118	Main

SSSWRDP

SP61001, Balia Bhangunkul Subproject, FMD&WC, Union : Khesra, HO Date:

Re-sectioning of Embankment	11.98	10,786,951	Main
Re-excavation of Jona Khal	0.74	796,728	Main
Re-excavation of Dumuria Khesra Khal	2.63	4,919,915	Main
Re-excavation of Madiar Khal	1.79	3,178,871	Main
Re-excavation of Amtala Khal	1.10	1,640,884	Main
Re-excavation of Shahzadpur-Purbachar Khal	0.65	989,816	Main
Re-excavation of Hazratata Khal	0.40	579,253	Main
Const. of Reference Lined Section	0.00	1,404,953	Main

Jamalpur (Total SPs : 15 Nos.)

Dewanganj

SSWRDP-JICA

SP32022, Khorma-Tilokpur Subproject, FMD, Union : Dewanganj, HO Date: 25/03/2014

Part-A: Tilokpur Khal Regulator at Ch. 0+200Km (Kh	1 Vent-1.2mX1.5m 0.00	2,665,690	Main
Part-B: Khorma Pipe Sluice at Ch. 0+630Km (Emkt)	1 Vent-0.9m Dia 0.00	2,384,247	Main
Part-C: Drainage Outlet with 200m Link Canal	1 Vent-3.0mX5.5m 0.00	1,682,237	Main
Resectioning of Road-Cum-Embankment	4.75	3,554,257	Main
Part-E: WMCA Office and Related Items	Size: 12mX6m 0.00	1,190,677	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Islampur SSWRDSP-2 SP23052, Digir Char Subproject, DR, Union : Char Putimari & Char Goalini, HO Date:				
	Regulator with Drainage Canal	1 Vent-1.50mX1.80m 0.00	2,980,765	Main
	O&M Shed	9.00mX5.00m 0.00	257,185	Main
	Re-excavation of Digir Char Khal	0.29	169,609	Main
	Box Culvert	Size: 2mX2m 0.00	634,778	Main
SSWRDP-JICA SP32018, Batikamari Beel Subproject, FMD, Union : Polbandha, HO Date: 19/05/2014				
	Part-A: Batikamari Regulator at Ch.2+500Km (Khal)	6 Vent-1.5mX1.8m 0.00	9,327,618	Main
	Part-B: Modification of Existing Box Culvert into	4 Vent-1.2mX1.5m 0.00	922,721	Main
	Resectioning of Embankment	1.60	1,838,054	Main
	Reexcavation of Balikamari Branch Khal	1.40	445,430	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,117,433	Main
Madarganj SSWRDP-JICA SP34117, Char Madargopal-Rayer Chara Subproject, FMD, Union : Sidhli, HO Date:				
	Re-excavation of Baria Khal	1.20	211,787	Main
	Resectioning of Embankment	0.85	509,262	Main
	Part-B: Char Madargopal WRS at Ch. 0+000Km (Khal)	2 Vent-1.5mX1.8m 0.00	5,121,334	Main
	Part-A: Baria Khal WRS at Ch. 0+025Km (Khal)	1 Vent-1.2mX1.5m 0.00	1,895,897	Main
	Part-D: WMCA Office and Related Item	0.00	1,234,968	Main
SP35195, Dudiagachha-Jorkhali Ghat Subproject, FMD, Union : Adharbhita, Jorkhali, HO				
	Part-A: Dudiagachha Regulator at Ch.0+265Km (Khal)	3 Vent-1.5mX1.8m 0.00	12,844,110	Main
	Part-B: Modification of Box Culvert to Regulator at Ch.0+85	2 Vent-1.5mX1.8m 0.00	1,758,330	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,451,481	Main
	Re-excavation of Dudiagachha-Jorkhali Khal	5.80	3,307,997	Main
	Resectioning of Embankment	5.63	4,197,543	Main
	Flood Damaged Rehabilitation of Dudiagacha-Jorkhali Gha	1.27	2,878,393	Main
Melandah SSWRDP-JICA SP34121, Daghi-Gangpara Subproject, FMD, Union : Nayanagar, HO Date: 26/04/2016				
	Part-B: Daghi Khal Regulator at Ch. 0+013Km	2 Vent-1.5mX1.5m 0.00	4,530,557	Main
	Part-A: Gangpara Khal Regulator at Ch. 0+080Km	2 Vent-1.5mX1.8m 0.00	4,429,144	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,083,808	Main
	Re-excavation of Dhagi Khal including Reference Bed Bloc	0.63	428,273	Main
	Re-excavation of Gangpara Khal including Reference Bed I	0.14	49,371	Main
SP35170, Gujabaida Khal Subproject, FMD, Union : Fulkocha, HO Date: 26/04/2016				
	Part-A: Guja Baida Khal Regulator at Ch.0+150Km (Embkt)	1 Vent-1.5mX1.8m 0.00	5,467,971	Main
	Part-B: Pipe Sluice at Ch.1+980Km (Embkt)	1 Vent-0.90m Dia 0.00	2,363,266	Main
	Resectioning of Embankment	4.46	6,307,097	Main
	Reexcavation of Gujabaidya Khal	1.00	445,586	Main
	Resectioning of North Embankment	1.70	2,959,724	Main
	Part-C: Pipe Sluice at Ch.0+450Km (N.Embkt)	1 Vent-0.90m Dia 0.00	2,431,798	Main
	Part-D: Box Sluice at Ch.2+280Km (Embkt)	1 Vent-0.90mX0.90m 0.00	2,181,316	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	2,166,956	Main
SP35218, Baira Khali Khal Subproject, FMD, Union : Kulia, HO Date: 05/01/2016				
	Part-A: Kalabari Khal Regulator at Ch. 5+025Km (Embkt)	1 Vent-1.5mX1.8m 0.00	4,643,257	Main
	Closer of Culvert Opening	0.00	899,471	Main
	Fish Sanchuary in Stanir Beel	0.00	403,889	Main
	Re-excavation of Bairakhali Khal including including Bed BI	1.93	526,772	Main
	Re-excavation of Kalabari Khal	0.70	879,082	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Sadar SSWRDSP-2 SP24114, Tetulia-Sadarbari Subproject, FMD, Union : Kendua, HO Date: 28/12/2010	Part-B: Regulator-1 by Modification of 1 Vent-Culvert at Ch	1 Vent-1.5mX1.5m 0.00	3,151,528	Main
	Part-C: Regulator-2 by Modification of 3 Vent-Culvert at Ch	6 Vent-1.5mX1.8m 0.00	8,498,813	Main
	Part-D: Regulator-3 by Modification of 2 Vent-Culvert at Ch	2 Vent-1.5mX1.5m 0.00	4,593,234	Main
	Part-E: Regulator-4 by Modification of 1 Vent-Culvert at Ch	1 Vent-1.5mX1.5m 0.00	3,452,494	Main
	Part-F: WMCA Office and Related Item	Size: 12mX6m 0.00	1,840,235	Main
	Re-sectioning of Embankment	3.02	4,505,232	Main
SSWRDP-JICA SP33093, Nachna Salika Khal Subproject, FMD&WC, Union : Sreepur, HO Date:	Re-excavation of Gobra Khal	3.62	3,574,615	Main
	Re-excavation of Sadarbari Khal	0.70	144,871	Main
	Re-Sectioning of Embankment	4.95	3,119,252	Main
	Gobra Khal Regulator at Ch 0+050Km (Khal)	4 Vent-1.5mX1.8m 0.00	9,029,577	Main
	Sadarbari Khal Pipe Sluice at Ch 0+465Km (Khal)	1 Vent-0.90m Dia 0.00	1,498,550	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	549,100	Main
Sharishabari SSWRDP-JICA SP32017, Rothkhola-Kamarbari Subproject, FMD, Union : Doail, HO Date: 03/09/2013	Re-excavation of Nachna Khal	8.20	9,417,489	Main
	Re-excavation of Salikha Khal	2.00	695,322	Main
	Re-sectioning of Approach road of WRS-1	0.60	991,410	Main
	Reference Lined Section (8 nos.)	0.00	300,054	Main
	Part-A: Nachna Khal WRS-1 at Ch.1+350Km	4 Vent-1.5mX2.0m 0.00	8,257,003	Main
	Part-B: Nachna Khal WRS-2 at Ch.6+550Km	3 Vent-1.5mX1.8m 0.00	6,276,851	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,749,335	Main
	Improvement Work of Earth Cutting of Shoshakhali link Kh	1.93	2,700,407	Main
	Improvement Work of Earth Cutting of Shalika Khal	2.55	3,979,702	Main
SP33071, Borobarua-Suakair Subproject, FMD, Union : Kamrabad, HO Date: 10/12/2015	Re-excavation of Khal	0.60	139,355	Main
	Re-Sectioning of Embankment	0.70	450,625	Main
	Part-A: Rothkhola Regulator at Ch. 0+278 (Khal)	2 Vent-1.5mX1.5m 0.00	2,245,538	Main
	Part-B: WMCA Office and Related Items	Size: 12mX6m 0.00	1,322,065	Main
	Part-A: Construction of Houshi Khal	2 Vent (1.5mX1.5m) 0.00	0	SSWRDP-JICA-2
	Part-A: Re-excavation of Houshi Khal	3.60	4,450,314	SSWRDP-JICA-2
	Part-B: Construction of Reference Bed Blocks	0.00	60,104	SSWRDP-JICA-2
	Part-A: Re-sectioning of Rothkhola-Kamarbari Embankmer	0.90	3,089,927	SSWRDP-JICA-2
SP35222, Takuria-Malipara Subproject, FMD, Union : Pogladhigahi, HO Date: 26/04/2016	Part-C: Suakair Inward Drainage Sluice at Ch.2+500	1 Vent-1.0mX1.0m 0.00	2,512,788	Main
	Reference Lined Section (3 nos)	0.00	300,054	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	2,231,987	Main
	Resectioning of Embankment	5.96	11,386,007	Main
	Resectioning of Embankment (East)	1.33	2,415,072	Main
	Embankment Protective Works	0.11	1,875,543	Main
	Rehabilitation of East Embankment	0.03	1,488,765	Main
	Reexcavation of Borobarua Khal	2.40	972,502	Main
	Reexcavation of Suakair Khal	0.80	141,988	Main
	Part-A: Borobarua Khal Regulator at Ch. 0+070Km	3 Vent-1.5mX1.8m 0.00	10,079,573	Main
	Part-B: Suakair Khal Regulator at Ch.2+210Km	2 Vent-1.5mX1.8m 0.00	6,483,436	Main
	Part-D: Hatbari Inward Drainage Sluice at Ch.5+725	1 Vent-1.0mX1.0m 0.00	2,201,985	Main
	Part-A: Takuria Khal Regulator at Ch.10+560 Km (Embkt)	3 Vent-1.5mX1.8m 0.00	8,879,553	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Regulator-1 at Ch.1+170 Km (Embkt)	1 Vent-1.2mX1.2m 0.00	2,304,293	Main
	Part-C: Regulator-2 at Ch.2+500 Km (Embkt)	1 Vent-1.2mX1.2m 0.00	2,712,063	Main
	Part-D: Inward Drainage Regulator-3 at Ch.6+750 Km (Eml)	1 Vent-1.2mX1.2m 0.00	2,036,032	Main
	Part-E: Inward Drainage Regulator-4 at Ch.7+340 Km (Eml)	1 Vent-1.5mX1.8m 0.00	3,165,212	Main
	Part-F: WMCA Office and Related Item	Size: 12mX6m 0.00	1,212,152	Main
	Resectioning of Embankment	3.60	6,070,621	Main
	Re-excavation of Takuria Khal	2.10	2,157,671	Main
	Re-excavation of Malipara Khal	0.75	380,302	Main
SP35232, Pakhadubi Subproject, FMD, Union : Bhatara, HO Date: 06/01/2016				
	Re-sectioning of Pakhadubi Embankment	2.60	3,710,477	Main
	Re-sectioning of Embankment (Extension)	0.65	1,719,327	Main
	Part-C: Remodeling of Existing Culvert at Ch. 1+984Km (Ei)	2 Vent-1.5mX1.8m 0.00	2,425,066	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,160,747	Main
	Part-A: Pipe Sluice at Ch. 0+350Km (Embkt)	1 Vent-0.90m Dia 0.00	895,020	Main
	Part-B: Pipe Sluice at Ch. 0+800Km (Embkt)	1 Vent-0.90m Dia 0.00	875,392	Main
SP35243, Kawakhali Beel Subproject, FMD, Union : Bhatara, HO Date: 06/01/2015				
	Part-A: Kawakhali Khal Regulator at Ch.0+550Km (Khal)	2 Vent-1.5mX1.8m 0.00	7,586,548	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,238,098	Main
	Resectioning of Embankment	2.00	3,354,288	Main
	Reexcavation of Kawakhali Khal including Reference Bed E	0.60	253,077	Main
Mymensingh (Total SPs : 40 Nos.)				
Dhobaura				
SSWRDP-JICA				
SP33055, Tarai Nadi Subproject, DR&WC, Union : Bagber, HO Date: 23/03/2014				
	Re-excavation of Tarai Nadi (Main)	4.00	3,298,651	Main
	Re-excavation of Tarai Nadi Branch	2.90	1,046,069	Main
	Part-A: Tarai Nadi WRS-1 at Ch.0+090Km	4 Vent-1.5mX2.0m 0.00	10,350,914	Main
	Part-B: Tarai Nadi WRS-2 at Ch.4+965Km	4 Vent-1.5mX2.0m 0.00	10,256,496	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,514,200	Main
	Reference Lined Section	0.00	228,364	Main
SP33056, Pachai Khal Subproject, WC, Union : Ghoshgaon, HO Date: 23/03/2014				
	Re-excavation of Pachai Khal	4.30	1,009,844	Main
	Part-B: Tengramari WRS at Ch. 3+100Km (Khal)	3 Vent-1.5mX2.0m 0.00	3,055,225	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,556,276	Main
	Part-C1: Header Tank & Service Connection of BPDB	Size: 6.1mX3.1m 0.00	2,008,330	Main
	Part-C2: Buried Pipe Network System	Length= 2115m 0.00	8,421,600	Main
	Maintenance Works of Buried Pipe Network System	0.00	555,414	Main
	Re-excavation of Pachai Khal	3.10	843,258	Main
	Referenece Lined Section (5 nos.)	0.00	115,952	Main
	Part-A: Bamanbadua WRS at Ch. 0+000Km (Khal)	4 Vent-1.5mX2.0m 0.00	3,613,067	Main
SP35190, Satarkhali Khal Subproject, DR&WC, Union : Dhobaura, HO Date: 18/11/2015				
	Re-excavation of Satar Khali Khal	7.60	2,336,835	Main
	Re-excavation of Ulukhali Khal	2.55	1,127,185	Main
	Re-excavation of Sathiar Khal	1.40	430,561	Main
	Part-A: Star Khali Khal WRS at Ch.0+000Km (Khal)	4 Vent-1.5mX1.8m 0.00	10,388,710	Main
	Part-B : WMCA Office and Related Item	Size:12mX6m 0.00	1,701,219	Main
SP35247, Ghagotia Par Nodi Subproject, WC, Union : Goatala, HO Date: 27/06/2016				
	Re-excavation of Tarai Nodi	2.40	4,081,738	Main
	Part-A: Ghagotia WRS at Ch.0+075Km	6 Vent-1.5mX2.5m 0.00	19,475,491	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,078,728	Main

Rubber Dam

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP98006, Netai River Rubber Dam Project, WC, Union : Gamaritala, HO Date:				
Fulbaria	Netai Nodi Rubber Dam	Size: 60mX3.5m 0.00	51,946,000	Main
SSWRDSP-2				
SP23093, Barail Beel Subproject, FMD, Union : Kaladash, HO Date: 01/01/2008				
	Baril Beel Khal Re-excavation	1.50	339,955	Main
	Baril Beel Regulator at Ch.0+200km	1 Vent-1.50mX1.80m 0.00	3,045,059	Main
	Kata Khali Pipe Sluice at Ch. 0+030 Km (Khal)	1 Vent-0.90m Dia 0.00	967,655	Main
	O&M Shed	9.00mX5.00m 0.00	381,194	Main
SSWRDP-JICA				
SP33080, Gujakuri Khal Subproject, FMD&WC, Union : Kaladaha, HO Date: 22/01/2014				
	Reexcavation of Gujakuri Khal	3.30	33,300	Main
	Resectioning of Biddaynanda Bazar-Ramnagar Embankment	2.80	3,055,931	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,566,107	Main
	Re-construction of Guzakuri Khal (Biddaynanda Kasem Ho	1.50	855,200	Main
	Reference Lined Section (5 nos.)	0.00	8,400	Main
	Part-A: Gujakuri Khal Regulator at Ch. 0+100Km	2 Vent-1.5mX1.8m 0.00	9,510,133	Main
SP33081, Salnar Khal Subproject, FM&WC, Union : Bakta, HO Date: 22/09/2013				
	Re-excavation of Salnar Khal	3.30	1,281,918	Main
	Re-excavation of Pagaria Khal	1.77	869,063	Main
	Reference Lined Sections (5 nos.)	0.00	198,379	Main
	Part-A: Pagaria Khal Regulator	4 Vent-1.5mX1.8m 0.00	6,550,409	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,566,107	Main
	Re-Construction of Salnar Khal Embankment (Koyer Chala	1.20	848,300	Main
SP33082, Kalmina Khal Subproject, FMD&WC, Union : Balian, HO Date: 25/11/2014				
	Reexcavation of Kalmina Khal	2.46	215,044	Main
	Part-C: Mahara Khal Regulator at Ch.0+900Km (Khal)	1 Vent-1.5mX1.8m 0.00	3,253,609	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,566,107	Main
	Part-C1: RCC Box Culvert on Khamerer More to Baddobari	Size: 4mX4m 0.00	3,601,563	Main
	Re-construction of Kalmina Khal Embankment (Boiddabari	1.40	880,750	Main
	Reexcavation of Ahazani Khal	1.70	378,212	Main
	Reexcavation of Ulgi Khal	0.89	65,622	Main
	Part-A: Kalmina Khal Regulator at 0+100Km (Khal)	2 Vent-1.5mX2.0m 0.00	7,288,020	Main
	Part-B: Ahazani Khal Regulator at 0+050Km (Khal)	2 Vent-1.5mX2.0m 0.00	7,140,638	Main
SP33088, Foliar Khal Subproject, FMD&WC, Union : Naogaon, HO Date: 26/09/2013				
	Reexcavation of Foliar Khal	3.78	2,585,786	Main
	Reference Lined Section (4 nos.)	0.00	117,243	Main
	Resectioning of Embankment	0.25	240,728	Main
	Part-A: Foliar Khal Regulator	3 Vent-1.5mX1.8m 0.00	10,774,604	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,361,325	Main
	Part-B: Foliar Khal Check Structure	2 Vent-1.2mX1.5m 0.00	1,538,048	Main
	Re-construction of Foliar Khal (Kashorgonj Trimohoni to Ab	1.60	857,610	Main
	Part-A: Foliar Khal WRS (Ch. 1+335km)	Ch. 1+335km 0.00	0	SSWRDP-JICA-2
	Part-A: Re-excavation of Foliar Khal	4.10	0	SSWRDP-JICA-2
	Part-A: Re-sectioning of Embankment	0.83	0	SSWRDP-JICA-2
Fulpur				
SSWRDP-JICA				
SP32027, Kharia Nadi Subproject, DR&WC, Union : Rambhadrapur, HO Date: 30/03/2014				
	Re-excavation of Kharia Nadi	12.94	3,504,918	Main
	Part-C: Check Structure WRS-1 at Ch. 11+177Km	6 Vent-1.2mX1.2m 0.00	2,555,521	Main
	Reference Lined Section	0.00	359,767	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Repairing works of Embankment of Kharia Nodi Subproject	0.00	923,126	Main
	Re-excavation of Kharia Nadi (Adll.)	6.13	1,664,555	Main
	Re-excavation of Suti Khal	1.10	34,944	Main
	Re-excavation of Charaldanga Khal	0.80	102,913	Main
	Re-Sectioning of Embankment	3.10	1,757,599	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	931,211	Main
	Part-A: Kharia Nodi Regulator-1 at Ch. 0+045Km (Kh	3 Vent-1.5mX1.8m 0.00	9,904,235	Main
SP35163, Dholai Khal Subproject, DR, Union : Balia, HO Date: 01/06/2015				
	Reexcavation of Dholai Khal	10.00	9,691,766	Main
	WMCA Office and Related Item	Size: 12mX6m 0.00	1,130,992	Main
SP35164, Nakananda-Batikura Subproject, FMD&WC, Union : Fulpur, Singerswar, HO				
	Part-A: Batikura Regulator at Ch.0+685Km	Size: 4 Vent-1.5mX1.8m 0.00	14,518,379	Main
	Reexcavtion of Nakananda-Batikura Khal	7.40	4,125,526	Main
	Reexcavtion of Boulir Khal	2.10	408,997	Main
	Part-C: Bongaon Gated Regulator at Ch.2+100Km	Size: 2 Vent-1.5mX1.8m 0.00	3,223,648	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,272,988	Main
Gafargaon SSWRDSP-2				
SP23109, Charipara Subproject, CAD, Union : Barbaria, HO Date: 01/04/2008				
	RCC Buried Pipe System	7.50 Km 0.00	11,106,939	Main
	O&M Shed	9.00mX5.00m 0.00	284,920	Main
	Header Tank	5.50mX2.00m 0.00	262,625	Main
	Extention of uPVC Pipe, Ms pipe and RCC Pipes	upvc=945,RCC=72.00m	5,953,766	PSSWRSP
SP25212, Kura Beel Subproject, FMD, Union : Jassora, HO Date: 12/11/2009				
	Re-excavation of Kura Beel Khal	2.01	322,399	Main
	Re-excavation of Kirtania Beel Khal	0.80	68,539	Main
	Kura Beel Khal Regulator	2 Vent-1.5mx1.8m 0.00	5,285,352	Main
	O&M Shed	Size: 9mX5m 0.00	340,088	Main
	Re-excavation of Bara Beel Khal	1.45	144,948	Main
SP25240, Unmesh CAD Subproject, CAD, Union : Datter Bazar, HO Date: 01/01/2013				
	Buried Pipe Irrigation Network	8303m Length 0.00	12,668,648	Main
	Header Tank	Size: 6.5mX3m 0.00	355,973	Main
	O&M Shed	Size: 9mX5m 0.00	324,617	Main
SSWRDP-JICA				
SP31001, Rouha CAD Subproject, CAD, Union : Shaltia, HO Date: 30/01/2014				
	Part-A: Header Tank	Size: 6.1mX3.0m 0.00	1,516,988	Main
	Part-B: Buried Pipe Network System	Length: 9880m 0.00	26,790,908	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,302,612	Main
	Part-A1: Construction of Pump House	0.00	336,355	Main
	Part-A2: Supply of Electric Pump and Motor With Power Cc	0.00	1,663,644	Main
	Part-A3: Supply of Accessories for Pump	0.00	1,063,112	Main
SP33079, Chait Beel Subproject, FMD, Union : Rasulpur, HO Date: 21/01/2014				
	Rexcavation of Chait Khal	1.55	400,479	Main
	Rexcavation of Fetrakuli Khal	0.71	125,000	Main
	Rexcavation of Boniar Khal	0.85	167,868	Main
	Part-A: Chait Beel Regulator at Ch. 0+125Km	2 Vent-1.5mX1.8m 0.00	7,462,616	Main
	Reference Lined Section (6nos.)	0.00	100,000	Main
SP35245, Goraber Subproject, CAD, Union : Gaffergaon, HO Date: 28/06/2016				
	Part-A: Header Tank	Size: 6.10mX4m 0.00	3,493,133	Main
	Part-B: Burried Pipe Networks System	Length = 9.430 Km 0.00	27,124,832	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,388,453	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	part-C1: Construction of Pump House	0.00	328,256	Main
	part-C2: Supply of Electric Pump and Motor with Power Cc	0.00	1,125,072	Main
	part-C3: Supply of Accessories for Pump	0.00	344,676	Main
SP35249, Dogachhia Subproject, CAD, Union : Gaffergaon, HO Date: 28/06/2016				
	Part-A: Header Tank	Size: 6.10mX3.75m 0.00	2,033,026	Main
	Part-B3: Supply of Accessories for Pump	0.00	6,529	Main
	Part-B: Supply of Accessories for Pump and Service Conne	0.00	1,025,126	Main
	Part-D: Burried Pipe Network System	Length= 8.310 Km 0.00	23,819,812	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	1,365,031	Main
	Part-B1: Construction of Pump House	0.00	227,619	Main
	Part-B2: Supply of Electric Pump with Motor with Power Cc	0.00	1,175,072	Main
Gauripur SSWRDSP-2				
SP24130, Chatal-Agrail Beel Subproject, DR&WC, Union : Mailakanda, Achintapur, HO				
	Re-excavation of Akbaria Khal	5.20	948,631	Main
	Agrail Beel WRS at Ch 050Km (Khal)	3 Vent-1.5mX1.8m 0.00	2,856,652	Main
	Chatal Beel WRS at Ch. 3+184 Km (Khal)	2 Vent-1.5mX1.8m 0.00	2,390,687	Main
	O & M Shed	Size: 12.0mX6.0m 0.00	397,988	Main
SSWRDP-JICA				
SP35219, Beel Kaila-Balua Khal Subproject, DR, Union : Ramgopal, HO Date: 09/12/2015				
	Re-excavation of Beel Kaila-Chowka Khal	14.00	4,489,351	Main
	Re-excavation of Rowa Khal	1.50	615,764	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,309,021	Main
	Part-A: Rehabilitation of Rowa Khal Pipe Culvert at Ch.1+00	1 Vent-0.90m Dia 0.00	135,746	Main
	Re-excavation of Maizga Branch Khal	2.50	1,722,582	Main
	Re-excavation of Kaytapuri Branch Khal	1.30	467,390	Main
Haluaghat SSWRDSP-2				
SP24177, Buraghat Subproject, WC, Union : Gazirvita, HO Date: 20/03/2008				
	O&M Shed	Size: 12mX6m 0.00	295,143	Main
	Buraghat Rubber Dam at Ch. 1+280Km	30mX3.5m 0.00	22,422,737	Main
	Procurement of Rubber Bag	0.00	4,645,000	Main
	Re-sectioning of Earthen Dyke (West Bank)	2.51	713,742	Main
	Re-sectioning of Earthen Dyke (East Bank)	2.51	898,074	Main
	Re-excavation of Approach Khal	0.10	114,966	Main
	Andakhali Khal Inlet Structure	4 Vent-1.5mX1.8m 0.00	4,171,843	Main
	Construction of 02 Nos IRR Drain of Bouraghat Rubber Dai	0.00	3,895,698	PSSWRSP
SP25213, Tukiar Khal Subproject, WC, Union : Jugli, HO Date: 20/04/2009				
	Re-excavation of Tukiar Khal	1.30	804,727	Main
	Tukiar Khal WRS-1 at Ch.0+450Km	3 Vent-1.5mX2m 0.00	5,248,127	Main
	Tukiar Khal WRS-2 at Ch.5+530Km	2 Vent-1.5mX2m 0.00	3,670,508	Main
	Tukiar Khal WRS-3 at Ch.8+635Km	2 Vent-1.5mX2m 0.00	3,757,966	Main
	O&M Shed	Size: 9mx5m 0.00	391,275	Main
SP25262, Gumuria Subproject, WC, Union : Gazirvita, HO Date: 13/07/2009				
	Gumuria WRS at Ch.2+240Km	8 Vent-1.5mX2.2m 0.00	12,682,758	Main
	O&M Shed	Size: 9mX5m 0.00	423,111	Main
	Re-sectioning of Gumuria Khal Left Dyke	0.80	382,810	Main
	Re-sectioning of Gumuria Khal Right Dyke	0.40	141,545	Main
	Part-A: Extension of Gumuri River WRS	(4v-1.5mX2.2m) 0.00	8,216,134	PSSWRSP
	Part-B: Construction of Lined Cannel	0.00	513,615	PSSWRSP
	Part-A: Re-excavation of Char Cutting Khal	1.07	139,032	PSSWRSP
	Part-B: Re-sectoning of Embankment	1.18	1,274,612	PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-C: Re-sectioning of Embankment	0.62	236,050	PSSWRSP
SSWRDP-JICA				
SP34155, Saul Nadi Bishnajuri Khal Subproject, WC, Union : Bhubankura, HO Date:				
	Re-excavation of Saul Nadi	1.20	2,680,692	Main
	Part-A: Saul Nadi WRS at Ch.0+660 Km	6 Vent-1.5mX2.5m 0.00	17,461,734	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,273,851	Main
Iswarganj				
SSWRDSP-2				
SP23058, Govia Beel Subproject, FMD, Union : Iswarganj, HO Date: 01/07/2008				
	Govia Regulator at Ch. 0+375 Km (Khal)	2 Vent-1.50mX1.80m 0.00	3,240,888	Main
	O&M Shed	9.00mX5.00m 0.00	298,485	Main
	Govia Beel Khal Re-excavation	1.90	443,395	Main
	Govia Beel Br. Khal Re-excavation	1.00	33,706	Main
	Govia-Shinni Beel Khal Re-excavation	1.50	459,082	Main
Muktagacha				
SSWRDP-JICA				
SP31002, Tekhala-Naodhara-Katajora Khal Subproject, DR&WC, Union : Baragram, HO				
	Part-A: Bahenga WRS at Ch. 0+103Km (Khal)	5 Vent-1.5mX2.0m 0.00	13,875,015	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,761,477	Main
	Re-excavation of Tekhal-Naodhara-Katajora Khal	6.60	5,686,572	Main
	Part-B: Tekhala WRS at Ch. 5+220Km (Khal)	4 Vent-1.5mX1.8m 0.00	3,449,754	Main
Nandail				
SSWRDP-JICA				
SP33048, Bapail Beel Subproject, DR&WC, Union : Moazzempur, HO Date: 03/11/2013				
	Reexcavation of Chengua Khal	2.51	1,080,558	Main
	Reexcavation of Kath Mogha Khal	1.82	927,166	Main
	Reexcavation of Mogha Nadi	4.59	3,142,595	Main
	Reference Lined Section	0.00	328,738	Main
	Part-A: Bahadurpur WRS	4 Vent-1.5mX2.0m 0.00	10,319,158	Main
	Part-B: WMCA Office and Related Items	Size: 12mX6m 0.00	1,935,971	Main
SP33049, Bawlar Beel Subproject, FMD, Union : Sherpur, HO Date: 03/11/2013				
	Re-excavation of Garail Khal	3.20	794,360	Main
	Re-excavation of Garail Branch Khal	1.55	431,158	Main
	Re-excavation of Bamankhali-Sharmara Nadi	3.26	3,412,295	Main
	Reference Lined Section (10 nos)	0.00	353,336	Main
	Part-A: Barilla Regulator at Ch.0+050Km (Khal)	3 Vent-1.5mX1.8m 0.00	7,246,638	Main
	Part-B: WMCA Office and Related Items	Size: 12mX6m 0.00	2,012,357	Main
	Re-excavation of Garail Khal (adll)	3.15	1,278,406	Main
	Re-excavation of Garail Branch Khal (Adll)	1.50	767,900	Main
SP33050, Narsunda-Tongi Khal Subproject, DR, Union : Achargaon, HO Date: 08/06/2015				
	Re-excavation of Narasunda Khal	6.04	7,361,932	Main
	Re-excavation of Tongi Khal	3.40	1,281,305	Main
	Re-excavation of Gaiar Khal	1.40	622,100	Main
	Reference Lined Section	0.00	476,009	Main
	Part-C: WMCA Office and Related Item	Size:12mX6m 0.00	2,013,646	Main
	Re-excavation of Dhulia Beel Khal	2.95	149,178	Main
	Part-A: Box Culvert at Ch. 0+822Km	1 Vent-3.5mX3.0m 0.00	970,382	Main
	Part-B: Box Culvert at Ch. 2+859Km	1 Vent-3.0mX3.0m 0.00	870,455	Main
SP35228, Udlar Khal Subproject, FMD&WC, Union : Achargaon, HO Date: 07/01/2016				
	Part-A: Dhamai Khal Regulator at Ch.0+300 Km	2 Vent-1.5mX1.8m 0.00	5,226,490	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,265,055	Main
	Re-excavation of Dhamai Khal	2.10	891,670	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP35248, Boular Khal Subproject, DR&WC, Union : Nandail, HO Date: 09/12/2015	Re-excavation of Udlar Khal	1.13	258,210	Main
	Re-excavation of Boular Khal i/c Bed Blocks	5.40	5,508,158	Main
	Re-excavation of Gazaria Khal i/c Bed Blocks	2.40	913,380	Main
	Part-A: Boular Khal WRS at Ch.1+300Km (Boular Khal)	2 Vent-1.5mX2.0m 0.00	4,705,401	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,203,365	Main
Sadar				
SSWRDSP-2				
SP24158, Beki Beel Subproject, DR&WC, Union : Ghagra, HO Date: 08/05/2009	Re-excavation of Beki Khal	5.80	3,184,318	Main
	Beki Beel Khal WRS	3 Vent-1.5mX1.8m 0.00	4,248,813	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	307,025	Main
Trishal				
SSWRDSP-2				
SP24123, Chiratal Beel Subproject, FMD&WC, Union : Rampur, HO Date: 04/12/2011	Re-excavation of Chiratal Khal	5.70	2,689,116	Main
	Chiratal Beel Khal Regulator	2 Vent-1.5mX1.8m 0.00	5,066,095	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	320,723	Main
SP25203, Ichamoti Subproject, CAD, Union : Kalipara, HO Date: 06/06/2009	Header Tank	Size: 6.1mX2.6m 0.00	282,061	Main
	Burried Pipe Networks System	5970m 0.00	9,433,950	Main
	O&M Shed	Size: 9mX5m 0.00	313,008	Main
SP25218, Dauhail-Kechuri Subproject, FMD, Union : Mathbari, HO Date: 23/07/2009	Re-sectioning of Embankment	3.20	1,514,373	Main
	Re-excavation of Dauhail Khal	0.72	166,553	Main
	Re-excavation of Kechuri Khal	0.40	51,209	Main
	Dauhail Khal Regulator	1 Vent-1.5mX1.8m 0.00	3,438,010	Main
	Kechuri Khal Regulator	1 Vent-1.5mX1.8m 0.00	3,157,537	Main
	Gerakuri Pipe Culvert with Flap Gate (R/S)	1 Vent-0.9m Dia 0.00	449,501	Main
	O&M Shed	Size: 9mX5m 0.00	719,952	Main
	Part-A: Improvement of Mothbari UP road via Roymoni nud	at 130m-1520 m 0.00	4,176,685	PSSWRSP
SP25259, Baroigaon Jhilki Subproject, CAD, Union : Kanihari, HO Date: 17/06/2010	O&M Shed	Size: 9mX5m 0.00	455,920	Main
	Burried Pipe Pipe Irrigation System	5550 m Length 0.00	8,514,260	Main
	Header Tank	Size: 6.5mX3m 0.00	324,909	Main
SSWRDP-JICA				
SP34108, Mora Khal (Meduary River) Subproject, WC, Union : Mokokpur, HO Date:				
	Part-A: Mora Khal WRS (2 Stage Gate) at Ch.0+000Km	4 Vent-1.5mX3.0m (2	13,672,788	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,205,735	Main
	Reexcavation of Khal	5.10	5,080,286	Main
SP35162, Nageswari Nadi Subproject, DR&WC, Union : Dhanikhola, HO Date: 02/02/2015	Part-A: Nageswari Nadi WRS at Ch.1+800Km	4 Vent-1.5mX2.50m 0.00	11,671,538	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,511,800	Main
	Re-excavation of Nageswari Nadi	8.30	5,268,882	Main
	Re-excavation of Latia Khal	1.75	1,346,922	Main
Netrokona (Total SPs : 27 Nos.)				
Atpara				
SSWRDP-JICA				
SP32010, Langulia Khal Subproject, FM&WC, Union : Sonai, HO Date: 10/11/2014				
	Part-C:Langulia Khal Flushing Regulator at Ch.4+76	1 Vent-1.5mX1.8m 0.00	6,949,227	Main
	Emergency protective works of embankment and approach	0.06	306,852	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A:Khalia Khali Regulator at 19m U/S of Br	3 Vent-1.5mX1.8m 0.00	9,735,474	Main
	Part-B:Langulia Khali Regulator at 36m U/S of Br	2 Vent-1.5mX1.8m 0.00	9,619,011	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	1,454,862	Main
SP33045, Pudda Khali Khali Subproject, FMD, Union : Sonai, HO Date: 09/10/2013				
	Part-A: Pudda Khali Khali Regulator at Ch.0+055Km	2 Vent-1.5mX1.8m 0.00	8,387,223	Main
	Part-B: WMCA Office and Related Items	Size: 12mX6m 0.00	1,061,392	Main
	Re-excavation of Pudda Khali Khali	0.50	298,815	Main
	Re-sectioning of Embankment	4.82	4,422,821	Main
SP35174, Nasir Khali Khali Subproject, FMD&WC, Union : Duaz, HO Date: 05/11/2015				
	Re-excavation of Nasir Khali Khali	2.70	3,462,347	Main
	Part-A: Nasir Khali Khali Regulator at Ch.0+075Km	4 Vent-1.5mX1.8m 0.00	14,425,862	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,826,537	Main
SP35186, Narayanpur Khali Subproject, FMD, Union : Loneswar, HO Date: 04/11/2015				
	Re-sectioning of Embankment	3.18	2,838,266	Main
	Re-excavation of Narayanpur Khali	0.40	234,414	Main
	Re-excavation of Fish Sanctuary in Petna Beel	0.00	376,211	Main
	Part-A: Narayanpur Khali Regulator at Ch.1+330Km	2 Vent-1.5mX1.8m 0.00	8,872,554	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	2,186,433	Main
Durgapur SSWRDSP-2				
SP22039, Bipington Subproject, WC, Union : Kullagora, HO Date: 05/02/2008				
	Ghoramara Khali Re-excavation	4.20	1,993,576	Main
	Bagaura Branch Khali Re-excavation	0.70	101,503	Main
	Ghoramara WRS at Ch. 0+200 km	3-V(1.50mX2.00m) 0.00	3,301,139	Main
	Bagaura WRS at Ch. 3+675 km	2-V(1.50mX1.50m) 0.00	2,044,467	Main
	O&M Shed	12.00mX6.00m 0.00	317,581	Main
	Bagaura Khali Re-excavation	1.50	237,664	Main
	Part-A: Re-excavation of Dhanipara-China kuri khali at Ch. :	2.20	2,445,169	PSSWRSP
	Part-B: Re-excavation of Bagaura khali at Ch.4+230 km to	1.00	927,986	PSSWRSP
	Part-C:Construction of nos Lined Section	0.00	89,490	PSSWRSP
SP24132, Mekurjani Khali Subproject, DR&WC, Union : Bucklejora, HO Date: 15/06/2009				
	Re-excavation of Mekurjani Khali	4.20	2,212,355	Main
	Re-excavation of Charigaon Para Khali	0.80	432,585	Main
	Mekurjani Khali WRS at Ch. 0+800Km	5 Vent-1.5mX1.8m 0.00	5,713,374	Main
	O & M Shed	Size: 12.0mX6.0m 0.00	289,690	Main
	Re-sectioning of Approach Embankment	0.05	63,454	Main
SSWRDP-JICA				
SP33089, Bijoypur Bawaipara Subproject, WC, Union : Kullagora, HO Date: 03/11/2015				
	Re-excavation of Bawaipara Khali & Resectioning of Bawaij	3.78	2,551,607	Main
	Part-C: Buried Pipe Line	Length = 625m 0.00	3,101,221	Main
	Part-A: Bawaipara WRS-1 at Ch.3+828Km (Khali)	3 Vent-1.5mX1.8m 0.00	6,725,453	Main
	Part-B: Bawaipara WRS-2 at Ch.1+413Km (Khali)	4 Vent-1.5mX1.8m 0.00	9,790,895	Main
	Construction of Dyke on Jongkhol Khali	0.65	260,103	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,276,258	Main
Kalmakanda SSWRDP-JICA				
SP31008, Pukuria-Uziakhali Khali Subproject, FM, Union : Kailati, HO Date: 04/09/2013				
	Part-A: Regulator at Outfall of Loliar Khali	2 Vent-1.5mX1.8m 0.00	6,209,404	Main
	Part-B: WMCA Office and Related Items	Size: 12mX6m 0.00	1,082,043	Main
	Re-sectioning of Left Bank Embankment of Boghai Kh	5.40	2,273,741	Main
	Re-sectioning of Right Bank Embankment of Boghai K	7.00	2,962,236	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: Re-sectioning of Embankment	4.50	0	SSWRDP-JICA-2
	Part-B: Re-sectioning of Existing Left Bank Embankment	2.70	0	SSWRDP-JICA-2
SP34105, Dheknai Khal Subproject, FMD, Union : Kharnai, HO Date: 18/05/2015				
	Part-A: Boushamar Beel Regulator	2 Vent-1.5mX1.5m 0.00	4,460,635	Main
	Part-B: Mora Khal Regulator	2 Vent-1.5mX1.5m 0.00	4,427,936	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,256,203	Main
	Reexcavation of Dheknai Khal	3.20	5,486,813	Main
SP35198, Dosdar-Ranigaon Subproject, FM&WC, Union : Pogla, HO Date: 24/03/2016				
	Reexcavation of Kalakona-Mandarua Khal	1.50	1,324,033	Main
	Reexcavation of Bain Khal	0.80	765,612	Main
	Re-sectioning of Dosdar-Ranigaon Embankment	9.42	7,059,924	Main
	Part-A: Kalakona Mandarua Khal Regulator at Ch. 1+740Kl	2 Vent-1.5mX1.8m 0.00	8,488,559	Main
	Part-B: Bain Khal Regulator at Ch.6+565Km (Embkt)	1 Vent-1.5mX1.8m 0.00	5,977,216	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,739,153	Main
	Part-A: Re-excavation of Dosdhar-Ranigaon Embankment	10.10	0	SSWRDP-JICA-2
SP35209, Bakla-Hatshira Subproject, FMD&WC, Union : Nazirpur, HO Date: 08/12/2015				
	Re-excavation of Doulatkhali Khal	1.10	311,565	Main
	Re-excavation of Pubdhuli Khal	0.50	140,534	Main
	Resectioning of Bakla-Hatshira Embankment	9.32	15,438,531	Main
	Part-A: Doulatkhali Khal Regulator at Ch.3+810Km	1 Vent-1.5mX1.5m 0.00	3,181,946	Main
	Part-B: Pubdhuli Khal Regulator at Ch.7+050Km	1 Vent-1.5mX1.8m 0.00	4,809,289	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,443,120	Main
Kendua SSWRDSP-2				
SP25285, Bahrail Beel Subproject, FMD&WC, Union : Naopara, HO Date: 28/09/2011				
	Re-excavation of Teli Khal	0.80	266,905	Main
	Re-sectioning of Embankment	3.70	1,326,418	Main
	O&M Shed	Size:9mx5m 0.00	375,799	Main
	Gofra Khal Regulator at Ch.1+615Km	1 Vent-1.5mX1.8m 0.00	2,639,743	Main
	Teli Khal Regulator at Ch.0+122Km	1 Vent-1.5mX1.8m 0.00	2,112,326	Main
SP25286, Gorkhai Khal Subproject, DR&WC, Union : Chirang, HO Date: 30/05/2012				
	Gorkhai Khal WRS at Ch.1+090Km (Khal)	2 Vent-1.5mX1.5m 0.00	2,689,672	Main
	Re-excavation of Main Khal	3.30	733,887	Main
	Re-excavation of Branch Khal	3.00	290,888	Main
SSWRDP-JICA				
SP35178, Sunai Haor Subproject, FMD&WC, Union : Mojaffarpur, HO Date: 21/09/2015				
	Resectioning of Embankment	3.45	5,199,104	Main
	Reexcavation of Kachua Khal	1.20	724,191	Main
	Reexcavation of Fuleswari Khal	1.20	1,037,176	Main
	Reexcavation of Kolloara Khal	0.90	157,772	Main
	Part-A: Kachuar Khal Regulator	1 Vent-1.2mX1.2m 0.00	4,882,843	Main
	Part-B: Fuleswari Khal Regulator	1 Vent-1.2mX1.2m 0.00	4,883,749	Main
	Part-C: Kolloara Khal Regulator	1 Vent-1.2mX1.2m 0.00	4,522,827	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	2,051,462	Main
Madan SSWRDSP-2				
SP24122, Chhayburia -Kuliati Subproject, FMD, Union : Madan, HO Date: 07/06/2009				
	Khalpar Khal Regulator at Ch. 0+018 Km (Khal)	1 Vent-1.5mX2.0m 0.00	2,430,272	Main
	Keya Khal Pipe Sluice at Ch. 0+000Km (Khal)	1 Vent-0.90m Dia 0.00	1,029,859	Main
	Re-sectioning of Submersible Embankment	4.90	1,296,927	Main
SP25260, Ganganagar Subproject, CAD, Union : Madan, HO Date: 19/04/2010				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Burried Pipe Network System	4740m Length 0.00	6,206,269	Main
	O&M Shed	Size: 9mX5m 0.00	315,908	Main
	Header Tank	Size:6.1mX2.6m 0.00	279,878	Main
	Part-A: Electrical estimate of Ganganagar CAD Sub-project	0.00	2,084,837	PSSWRSP
	Part-B: Construction of Pumping Palt form of Ganganagar	0.00	2,326,447	PSSWRSP
SSWRDP-JICA				
SP34119, Foring Khal Subproject, DR&IRR, Union : Gobondasree, Maghon, HO Date:				
	Reexcavation of Foring Khal	4.30	385,705	Main
Mohonganj				
SSWRDSP-2				
SP24111, Dewrajan River Subproject., WC, Union : Tentulia, HO Date: 03/02/2009				
	Re-excavation of Dewrajan River	3.83	1,738,655	Main
	Dewrajan River WRS at Ch. 2+425 Km	2 Vent-1.5mX1.8m 0.00	2,426,733	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	304,485	Main
SSWRDP-JICA				
SP35189, Kachadhor Khal Subproject, FMD&WC, Union : Gaglajur, HO Date: 15/09/2015				
	Part-A: Kachadhor Khal Regulator at Ch.1+235Km	2 Vent-1.5mX1.8m 0.00	9,364,622	Main
	Resectioning of Embankment	2.52	3,112,562	Main
	Reexcavtion of Fish Sanctuary	0.00	376,215	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,772,407	Main
	Re-excavation of Kachadhor Khal	1.10	915,027	Main
	Re-excavation of Kachadhor Branch Khal	0.70	512,645	Main
SP35204, Paleha-Sonarampur Subproject, FMD, Union : Barakashia Birampur, HO Date:				
	Re-excavation of Birbiriya Khal	1.10	628,364	Main
	Part-B: Rehabilitation of Birbiriya Khal Regulator at Ch. 1+7	2 Vent-1.5mX1.8m 0.00	362,041	Main
	Part-C: Renovation of Sonaram Pipe Culvert at Ch. 0+231r	3 Vent-0.90m Dia 0.00	437,739	Main
	Re-excavation of Gorumara Khal	0.30	167,387	Main
	Re-sectioning of Sonarampur embankment	1.78	806,724	Main
	Re-sectioning of Paleha embankment	3.40	1,832,918	Main
	Part-D: WMCA office with related facilities	Size: 12mX6m 0.00	1,788,023	Main
	Part-A: Paleha Regulator at Ch. 0+220Km (Embkt)	1 Vent-1.2mX1.2m 0.00	2,985,884	Main
SP35206, Betia Beel Subproject, FMD, Union : Maghan Siadhar, HO Date: 16/09/2015				
	Re-excavation of West Betia Khal	0.25	76,600	Main
	Part-B: Maddhya Betia Khal Box Sluice at Ch.2+408Km	1 Vent-1.0mX1.0m 0.00	1,753,813	Main
	Part-C: West Betia Khal Box Sluice at Ch.2+780Km	1 Vent-1.0mX1.0m 0.00	1,744,083	Main
	Re-excavation of Maddhya Betia Khal	0.28	62,385	Main
	Re-excavation of East Betia Khal	0.30	68,829	Main
	Re-sectioning of Betia Embankment	1.82	2,641,700	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,837,108	Main
	Part-A: East Betia Khal Box Sluice at Ch.2+255Km	1 Vent-1.0mX1.0m 0.00	1,734,021	Main
Purbadhala				
SSWRDP-JICA				
SP35205, Chitrang Beel Subproject, FMD&WC, Union : Bairati, HO Date: 07/12/2015				
	Re-excavation of Gohai Khal	1.00	436,720	Main
	Part-A: Gohai Khal Regulator at Ch.0+347Km	3 Vent-1.5mX1.8m 0.00	7,566,306	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,762,159	Main
	Re-excavation of Eran Beel Khal	0.58	192,280	Main
Sadar				
SSWRDSP-2				
SP22038, Fazar Ali Khal Subproject, DR&WC, Union : Singer Bangla, HO Date:				
	Fazar Ali Khal Re-excavation	2.60	628,035	Main
	WRS at Ch. 2+450 km	2-V(1.50mX1.80m) 0.00	2,662,317	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP23064, Owail Beel Subproject, DR&WC, Union : South Bishiura, HO Date: 30/07/2008	O&M Shed	12.00mX6.00m 0.00	317,952	Main
	Owail Beel Khal Regulator at Ch.0+045m	2 Vent-1.50mX1.80m 0.00	4,321,754	Main
	O&M Shed	9.00mX5.00m 0.00	232,840	Main
	Owail Beel Khal Re-excavation	3.20	406,910	Main
	Part-A: Re-sectioning of Embankment at Ch. 0+000 km to 0+050 km	3.00	2,563,019	PSSWRSP
SP25234, Kaerkhali Khal Subproject, DR&WC, Union : Kailati, HO Date: 03/06/2009	Re-excavation of Kaer Khal	2.00	386,896	Main
	Re-excavation of Arai Khal	4.70	595,625	Main
	Arai Khal Weir with 2 Vertical Gates at Ch.0+330Km	1 Bay-20mX1.8m 0.00	6,502,298	Main
	O&M Shed	Size: 9mX5m 0.00	501,924	Main
	Part-A: Re-sectioning of Diger beel Road-Embankment	0.90	1,892,148	PSSWRSP
	Part-B: Re-excavation of Digir Khal & reference lined Section	1.29	886,751	PSSWRSP
	Part-A: Construction of Box culvert (1v-3.mX3.0m)	(1v-3.mX3.0m) 0.00	1,461,320	PSSWRSP
SP25269, Chikerkuri Khal-Kachuduari Beel Sub-project, FMD&WC, Union : Rouha, HO	Re-excavation of Chikerkuri Khal	2.46	2,629,168	Main
	Gopalpur Khal Regulator at Ch.0+360Km (Khal)	2 Vent-1.5mx1.8m 0.00	7,521,455	Main
	Kachuduari Khal Regulator at Ch.4+800Km (Khal)	2 Vent-1.5mx1.8m 0.00	7,449,931	Main
SP25276, Gagrakhali Khal Subproject, FMD&WC, Union : Laxmiganj, HO Date: 08/10/2011	Re-excavation of Gagrakhali Khal	4.60	927,290	Main
	Re-excavation of Indaikhali Khal	0.60	184,942	Main
	Re-excavation of Fulkhali Khal	1.20	351,798	Main
	Birampur Regulator at Ch. 0+057Km	2 Vent-1.50mX1.8m 0.00	4,931,775	Main
	Gadaikandi Regulator at Ch. 4+600Km	1 vent-1.5mX1.8m 0.00	3,412,467	Main
	O&M Shed	Size:9mX5m 0.00	482,662	Main
Sherpur (Total SPs : 6 Nos.)				
Jhenaigati				
SSWRDP-JICA				
SP35158, Moharashi Subproject, WC, Union : Nolkuria Jhenaigati, HO Date: 13/03/2016				
	Part-A: Moharashi Rubber Dam	Size: 45mX4.5m 0.00	75,067,218	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,251,311	Main
	Part-B: Protective Works at U/S & D/S of Rubber Dam	0.00	4,773,114	Main
	Part-C: Bridge Works in Rubber Dam	0.00	5,393,145	Main
Nakhla				
Rubber Dam				
SP99013, Bhogai River Rubber Dam (Nakhla) Project, WC, Union : , HO Date:				
	Bhogai River Rubber Dam (Nakhla)	Size: 100mX4.5m 0.00	169,857,000	Main
	3 nos. Regulator and River Bank Repair	0.00	8,530,000	Main
Nalitabari				
SSWRDP-JICA				
SP31005, Ranjana Jharna Khal Subproject, WC, Union : Poragaon, HO Date: 25/08/2013				
	Construction of Khal Bank Dyke	1.00	171,400	Main
	Part-A: WRS-1 at Ch.1+175 Km (Khal)	6 Vent-1.5mX3.0m 0.00	7,824,087	Main
	Part-B: WRS-2 at Ch.0+350 Km (Khal)	6 Vent-1.5mX2.5m 0.00	6,573,047	Main
	Inlet Structure	1 V- 1.0 m x 2.0 m 0.00	158,273	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,575,121	Main
SP32026, Sutiar Khal Subproject, WC&CAD, Union : Kakarkandi, HO Date: 14/05/2014				
	Re-excavation of Sutiar Khal	4.80	1,327,115	Main
	Part-B: Header Tank & Service Connection from PDB/	Size:4.50mX2.75m 0.00	833,530	Main
	Part-C: Buried Pipe Networks System	300-600mm Dia,	6,385,907	Main
	Re-excavation of Garo Khal	0.80	158,289	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Reference Lined Section	0.00	237,713	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	963,814	Main
	Part-A: Sutiari Khal WRS at Ch. 0+000Km	3 Vent-1.5mX1.8m 0.00	9,517,389	Main
SP34153, Buri Bhogai Subproject, WC, Union : Kakarkandi, HO Date: 10/03/2016				
	Part-A: Intake Regulator with protective Works (Ch 0+028k	2V-1.2mX1.2m at Ch 0+028	7,430,985	Main
	Part-B: WRS_1 at Ch.4+650Km	2V-1.5mx3.0m 0.00	9,127,301	Main
	Part-C: WRS-1 at Ch.10+940Km	2V-1.5mx3.2m 0.00	9,650,163	Main
	Part-D: WMCA Office and Related Item	0.00	2,255,014	Main
	Re-excavation of Dorsha Khal	6.35	16,703,092	Main
Rubber Dam				
SP97003, Bhogai River Rubber Dam (Nalitabari) Project, WC, Union : Morichpuran,				
	Bhogai River Rubber Dam (Nalitabari)	Size: 100mX4.00M 0.00	58,720,000	Main
Bogra (Total SPs : 17 Nos.)				
Adamdighi				
PSSWRSP				
SP44107, Amail-Indail Subproject, DR&WC, Union : Chhatiagram, HO Date: 06/06/2016				
	Part-A: Construction of Amail Indail khal WRS	(2V 1.50mX1.80m) 0.00	5,988,387	Main
	Part-B: Construction of Amail Indail khal Box Culvert	(2V 3.50mX 3.50m) 0.00	2,895,634	Main
	Part-C: WMCA Office & others	12mX6m 0.00	1,377,197	Main
	Part-A: Re-excavation of Amail Indail khal	6.00	5,380,166	Main
	Part-B: Re-excavation of Branch khal-1	0.40	73,264	Main
	Part-C: Re-excavation of Branch khal-2	0.60	417,593	Main
	Part-D: Re-excavation of Branch khal-3	0.60	299,726	Main
	Part-E: Construction of Reference Lined Section	0.00	181,148	Main
SP44108, Tiloch Iramoti Subproject, DR&WC, Union : Kundagram, HO Date: 24/07/2017				
	Part-A: Construction of Tiloch Iramoti Khal Regulator	(1V1.50mX1.50m) 0.00	4,048,237	Main
	Part-B: Construction of Box Culvert-1	(1V 2.50mX2.50m) 0.00	1,514,252	Main
	Part-C: Construction of Box Culvert-2	(1V 2.50mX2.50m) 0.00	1,499,105	Main
	Part-D: Construction of Box Culvert-3	(1V 2.50mX2.50m) 0.00	1,596,558	Main
	Part-E: Construction of WMCA Office & Others	12mX6m 0.00	1,394,425	Main
	Part-A: Re-excavation of Tiloch Iramoti khal	1.20	1,011,191	Main
	Part-B: Re-excavation of Branch Khal-1	0.70	566,003	Main
	Part-C: Construction of reference lined section	0.00	44,352	Main
SP44123, Kamarpur-Adamdighi Subproject, DR&WC, Union : Chhatiagram, HO Date:				
	Part-A: Repair and Upgradating of WRS	(5v-1.250mX1.80 0.00	2,899,474	Main
	Part-B: Kamarpur Adamdighi khal Box Culvert	(2v-4.50mX4.50) 0.00	4,258,869	Main
	Part-C:WMCA Office & Others	12mX6m 0.00	1,607,132	Main
	Part-A:Re-excavation of Kamarpur Adamdighi khal	6.30	6,219,692	Main
	Part-B:Construction of Reference lined Section	0.00	160,744	Main
Kahaloo				
PSSWRSP				
SP45174, Pachim vogoil Bairadaghi Eidgaha Khal Subproject, DR&WC, Union : Paikur, HO				
	Part-A: Construction of Kalitola Shibnath Khal Regulator ((1v-1.5mX1.8m) 0.00	0	Main
	Part-B: Construction of Irrigation Drain-1 (L=100) and Draii	0.00	0	Main
	Part-C: WMCA Office & Others	0.00	0	Main
	Part-A: Re-excavation of Shibnath Kalitota khal	1.45	1,335,278	Main
	Part-B: Re-excavation of Fish Scentuary khal	0.14	759,196	Main
	Part-C: Construction of Reference Lined Section	0.00	39,352	Main
Sadar				
SSWRDSP-2				
SP25330, Barikol-Kalidah Beel Subproject, DR, Union : Namuja, HO Date: 21/05/2012				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Shahjahanpur SSWRDSP-1 SP14153, Beel Keshpathor FCD Subproject, FCD, Union : Chupinagar, HO Date:	Re-excavation of Kalidah Beel Khal	3.90	1,159,971	Main
	O&M Shed	Size: 12mX6m 0.00	585,000	Main
	Re-excavation of Kalidah Beel Br. Khal (1&2)	1.25	86,029	Main
	Part-A: Re-excavation of Khalidah Beel-1	0.39	2,494,556	PSSWRSP
	Part-B: Re-excavation of Khalidah Beel-2	0.15	838,469	PSSWRSP
SSWRDSP-2 SP23088, Khudra Fulkot-Rajarampur Subproject, DR&WC, Union : Amrul, HO Date:	Embankment Re-sectioning	4.00	2,088,758	Main
	Dumdia-Karaidah Khal Re-excavation	5.61	195,820	Main
	Beel Keshpathar Regulator at Ch.4+290m	2-V(1.2mX1.5m)	1,614,463	Main
	Piipe Sluice at Ch.0+430m	1-V(900mm Dia)	1,130,795	Main
	WRS at Ch.1+100m	2-V(1.2mX1.5m)	1,745,409	Main
	Modifying Culvert to Regulator at Ch.2+232m	3-V(1.1mX1.5m)	1,356,158	Main
Sherpur SSWRDSP-1 SP13101, Mirzapur FCD Subproject, FCD&WC, Union : Mirzapur,Sughat, HO Date:	Sholmari Regulator at Ch. 0+145Km (Khal)	1 Vent-1.50mX1.80m 0.00	2,249,641	Main
	O&M Shed	9.00mX5.00m 0.00	255,356	Main
SP13110, Simbari FCD Subproject, FCD, Union : Simbari,Sughat, HO Date: 07/01/2002	Embankment Re-sectioning	5.64	1,748,045	Main
	Shatibari WRS	2-V(1.5mX2.0m)	1,864,000	Main
	Pipe Sluice at Ch.1+166m	1-V(900mm Dia)	385,981	Main
	Pipe Sluice at Ch. 0+506m	1-V(1.05m Dia)	576,376	Main
	Pipe Culvert at Ch. 2+530m	1-V(900mm Dia)	145,989	Main
SSWRDSP-2 SP25270, Maniker Khal-Kochua Beel Subproject, DR&WC, Union : Garidaha, Khamarkandi,	Embankment Re-sectioning	7.95	1,663,153	Main
	Chaknasi Regulator	2-V(1.2mX1.8m)	2,696,307	Main
	Pipe Sluice at Ch. 6+314m	2-V(900mm Dia)	481,670	Main
	Pipe Sluice at Ch. 7+557m	2-V(900mm Dia)	599,186	Main
	Pipe Sluice at Ch. 8+463m	1-V(900mm Dia)	412,923	Main
	Pipe Sluice at Ch. 10+105m	1-V(600mm Dia)	226,819	Main
	Regulator at Ch. 10+675m	2-V(1.5mX1.5m)	1,682,660	Main
	Pipe Sluice at Ch. 12+301m	1-V(600mm Dia)	241,723	Main
	Regulator at Ch. 12+997m	2-V(1.5mX1.5m)	1,769,922	Main
	Protective Works of Chaknasi Regulator		106,714	Main
PSSWRSP SP44078, Dhankundi Subproject, FMD, Union : Simabari, HO Date: 23/03/2016	Re-excavation of Maniker Khal	3.20	639,590	Main
	Maniker Khal Regulator at Ch. 0+350Km (Khal)	2 Vent-1.5mX1.8m 0.00	6,393,296	Main
	O&M Shed	Size: 9mX5m 0.00	478,949	Main
SP44139, Bhadraboti-Tilkatala Subproject, DR&WC, Union : Kushumbi, HO Date:	Part-A: Re-excavation of Napitbari Khal	0.78	410,870	Main
	Part-A:Napitbari khal Regulator	2V-1.5mx1.8m 0.00	5,217,805	Main
	Part-B:Napitbari khal Culvert	1V-3.0mx2.5m 0.00	1,069,045	Main
	Part-C: WMCA Office & Others	12mx6m 0.00	1,394,085	Main
	Part-A: Construction of Bhadrabati-Tilkala khal WRS	(3v-1.50mX2.00) 0.00	12,274,688	Main
	Part-C: WMCA Office & others	12mX6m 0.00	1,506,197	Main
	Part-A: Re-excavation of Bhadrabati-Tilkakala khal	5.90	9,303,235	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP45207, Dublai Bhadrabati Subproject, DR&WC, Union : Bisalpur, HO Date: 29/05/2018	Part-B: Construction of Reference Lined Section	0.00	167,029	Main
	Part-A: Bhadrabati khal Structure WRS (4v-1.5mX2.0m)	(4v-1.5mX2.0m) 0.00	12,283,485	Main
	Part-B: Box culvert (4v-4.0mX4.0m)	(4v-4.0mX4.0m) 0.00	5,253,884	Main
	Part-C: Construction of WMCA Office & Others	12mX6m 0.00	1,360,737	Main
	Part-A:Re-excavation of Dublia bhadrabati khal	14.30	15,091,660	Main
SP46271, Jhanior Parbhabanipur Subproject, DR&WC, Union : Simabari, HO Date:	Part-B: Construction of Reference Lined Section	0.00	0	Main
	Part-A: Construction of Dudkumar Khal Regulator	3v - 1.5m X 2.0m 0.00	11,277,241	Main
	Part-B: Construction of Irrigation Brick Canal	0.00	1,726,727	Main
	Part-C: Construction of WMCA Office and others	12m X 6m 0.00	1,419,605	Main
	Part-A: Re-excavation of Dudkumar Khal	7.00	4,878,589	Main
Shibganj SSWRDSP-2 SP24128, Bagoil Beel Khal Subproject, DR&WC, Union : Maydanhata, HO Date:	Part-B: Re-excavation of Dyke	0.25	477,108	Main
	Part-C: Construction of reference lined section	0.00	207,690	Main
	Re-excavation of Bagoil Khal	4.10	571,183	Main
	Bagoil Khal WRS at Ch. 1+620 Km	2 Vent-1.5mX1.8m 0.00	2,556,457	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	292,671	Main
SP24140, Chitlar Khal Subproject, DR&WC, Union : Aatmul, HO Date: 20/05/2008	Chitlar Khal Re-excavation	6.35	2,121,644	Main
	Chitlar Khal WRS-1 at Ch.0+250 Km	3 Vent-1.5mX1.8m 0.00	4,063,665	Main
	Chitlar Khal WRS-2 at Ch.3+650km	2 Vent-1.5mX1.5m 0.00	2,584,008	Main
	Re-excavation of Branch Khal-1	0.79	170,147	Main
	Re-excavation of Branch Khal-2	0.80	108,343	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	348,365	Main
	Chitlar khal re-excavation(ch.00-7000m)	7.00	7,038,654	SSSWRDP
	Referenced line section(6nos)	0.00	151,366	SSSWRDP
	Bamboo Bridge(3nos)	0.09	297,639	SSSWRDP
Sonatala SSWRDSP-1 SP11003, Lohagara Khal FCD Subproject, FCD, Union : Digdiar, HO Date: 04/12/2000	Lohagara Khal Re-excavation	5.86	1,297,733	Main
	Khal Re-excavation near WCS	0.43	40,845	Main
	WRS at Ch.8+860m	4-V(1.5mx2.1m)	2,312,540	Main
	WRS at Ch.0+985m	2-V(1.5mx2.1m)	1,819,714	Main
Chapai Nawabgonj (Total SPs : 24 Nos.)				
Gomostapur SSWRDSP-1 SP14145, Baro Beel FCD Subproject, FCD, Union : Bhangabaria,Rohonpur, HO Date:	Embankment Re-sectioning	5.35	1,027,454	Main
	Khal Re-excavation	1.35	447,863	Main
	Regulator at Ch.0+000m	4-V(1.5mX1.8m)	5,327,915	Main
	Regulator at Ch.7+000m	1-V(1.5mX1.8m)	2,562,746	Main
SP15297, Pabdamari & Charal Beel FCD Subproject, FCD, Union : Alinagar,Rohonpur, HO	Embankment Re-sectioning	10.40	2,640,756	Main
	Pabdamari Khal Re-excavation	1.74	409,447	Main
	Pabdamari Regulator	4-V(1.5mX1.8m)	4,149,421	Main
	Box Culvert at Ch.0+800m	2-V(3.0mX3.2m)	460,001	Main
SSWRDSP-2				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP25195, Sonar Bangla Subproject, CAD, Union : Rohanpur, Beelsultanpur, HO Date:				
	Buried Pipe Network System	5750m 0.00	16,522,954	Main
	O&M Shed	Size: 9mX5m 0.00	504,669	Main
	Header Tank	Size: 6.5mx3m 0.00	837,378	Main
	UPVC Buried pipe and RCC Guide wall	1.43mUPVC	12,023,184	SSSWRDP
SP25237, Hogla-Damosh Subproject, CAD, Union : Gomostapur, HO Date: 28/08/2009				
	O&M Shed	Size: 9mX5m 0.00	313,462	Main
	RCC Irrigation Canal	3107m length 0.00	6,852,990	Main
	RCC U-Drain	Length=1050m 0.00	2,484,110	Main
	Part-A:- Est. for laying of 315mm dia Upvc buried pipe at C	at Ch.1+517 km to 2+187 km	1,964,880	PSSWRSP
	Part-B:- Est. for open brick canal staring from brick canal a	Ch.0+220 km to 0+480 0.00	699,810	PSSWRSP
	Part-C:- Est. for laying of 315mm dia Upvc buried pipe at C	at Ch.0+480 km to 1+150 km	2,003,510	PSSWRSP
	Part-D:- Est. for laying of 315mm dia Upvc buried pipe at C	at Ch.0+000 km to 0+290 km	874,164	PSSWRSP
	UPVC Buried pipe,RCC pumping platform with stair guide,f	2900mBur.pipe,2.4mRCC	11,688,859	SSSWRDP
SP25238, Hogla-Darabaj Subproject, CAD, Union : Gomostapur, HO Date: 20/08/2010				
	RCC Irrigation Canal (main & Br.), Burried Pipe	RCC=1600m & Buried	5,017,949	Main
	O&M Shed	Size: 9.0mX6.0m 0.00	376,052	Main
Nachol SSWRDSP-2				
SP25196, Kaloir Sabaitara Subproject, WC, Union : Kasba, HO Date: 12/01/2010				
	Weir-1 at Ch. 0+400Km on Sabaitara Khari	1 Bay-25mX2.5m 0.00	5,530,112	Main
	Weir-2 at Ch. 1+600Km on Kaloir Khari	1 Bay-15mX2m 0.00	3,115,888	Main
SP25267, Chandpara Subproject, CAD, Union : Fatehpur, HO Date: 02/01/2010				
	Header Tank	Size: 6.5mX3.0m 0.00	420,655	Main
	Buried Pipe Network System	4.005 Km Length 0.00	5,558,021	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	443,324	Main
	Extension of 300m Dia Burried Pipe	Length=350m 0.00	679,940	Main
	Part-A: Construction of RCC suction Chamber near the pur	0.00	1,721,936	PSSWRSP
	Part-B: Construction Pakai Hazi uPVC buried pipe	0.00	1,868,841	PSSWRSP
Sadar SSWRDSP-1				
SP11004, Agrani Irrigation CAD Subproject, CAD, Union : Zhilim, HO Date: 23/03/2002				
	Re-Construction of RCC open Branch cannel	2700 m 0.00	7,311,435	PSSWRSP
	Main Canal Re-excavation	0.59	482,469	Main
	Main Canal (Group I)	1.33 km	3,085,292	Main
	Main Canal (Group II)	1.65 km	3,020,033	Main
	Branch Canal	0.60 km	770,954	Main
	Syphon		670,121	Main
	Box Culvert at Ch.1+540m	1-V(1.5mX.95m)	73,970	Main
	Culvert at Ch.2+460m	1-V(1.3mX.85m)	74,085	Main
	Culvert cum Aquiduct at Ch.2+750m	2-V(3.0mX4.2m)	865,354	Main
	Culvert cum Inlet at Ch.0+000m of Br. 5		126,926	Main
	Aquiduct over Existing Culvert at Ch.2+727m		62,890	Main
	Bridge cum Aquiduct at Ch.3+120m		842,492	Main
	Aquiduct over Br. 5 at Ch.0+305m		350,644	Main
	Box Sluice at Ch.1+395m	1-V(1.0mX1.0m)	89,660	Main
	Syphon at Ch.1+540m		185,000	Main
	Repair of Irrigation Canal	0.13 km	0	Main
SP14144, Kumarer Beel FCD Subproject, FCD, Union : Baliadangi, HO Date: 07/06/2004				
	Embankment Re-sectioning	2.15	348,703	Main
	Khal Re-excavation	0.37	31,249	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP15336, Kalupur Khari DR&WC Subproject, DR&WC, Union : Jhilim, HO Date:	Regulator	1-V(1.5mX1.8m)	965,133	Main
	Kalupur Khari WRS at Ch.0+450m	8-V(1.5mX2.1m)	2,950,302	Main
SSWRDSP-2				
SP22021, Mohammadkhani Subproject, CAD, Union : Baliadanga, HO Date: 14/11/2006				
	Construction of RCC Irrigation System	Length = 12130m 0.00	16,666,034	Main
	O&M Shed	12.00mX6.00m 0.00	273,631	Main
	U-Drain	Length=1080m 0.00	2,703,744	Main
	Construction of 200mm dia uPVC buried pipe	3nos, 1220x3=3660m 0.00	3,101,258	PSSWRSP
	Over Head Tank&Barid pipe 2-300mm dia	pipe 2-300mm dia 0.00	9,579,941	SSSWRDP
SP22022, Behula Subproject, CAD, Union : Gobatala, HO Date: 14/08/2006				
	Construction of Lined Canal	1920 m 0.00	2,137,730	Main
	O&M Shed	9.00mX5.00m 0.00	195,894	Main
	Rcc Buried Pipe ,Rcc Open Cannel,Rcc Platform near the I	0.00	3,006,170	PSSWRSP
SP22023, Nayagola-Mohananda Subproject, CAD, Union : Pourasava, HO Date:				
	RCC Irrigation System	Length= 4135 m 0.00	14,308,197	Main
	O&M Shed	12.00mX6.00m 0.00	298,579	Main
	RCC U-Drain	Length=392m 0.00	2,827,843	Main
	Part-A: Construction of 03 nos. platform & Stair by the side:	03 nos. 0.00	1,420,564	PSSWRSP
	Part-B: Construction of main RCC open Cannel	at Ch. 0.00-1650.00m 0.00	6,192,576	PSSWRSP
SP25197, Chechinia Subproject, CAD, Union : Gobatala, HO Date: 20/01/2010				
	Burried Pipe Network	5650m 0.00	10,229,515	Main
	Header Tank	Size: 6.1mX2.75m 0.00	278,484	Main
SP25241, Palsha-Moheshpur Subproject, CAD, Union : Baliadanga, Gobatala, HO Date:				
	RCC & Buried Pipe Irrigation System	3294m & 1298m 0.00	8,918,000	Main
	Part-A:400mm dia uPVC Buried Pipe	at Ch.0+000km to 1+005 km	3,639,619	PSSWRSP
	Part-B: Construction of Outfall Chamber at Amarat	0.00	32,518	PSSWRSP
SP25257, Gohalbari Subproject, CAD, Union : Baliadanga, HO Date: 10/08/2009				
	O&M Shed	Size:9mX5m 0.00	328,625	Main
	RCC Irrigation Lined Canal	4486m length 0.00	10,271,375	Main
	7nos RCC branch canal,RCC cover slab and footpath,RCC	1200mBran.canal,44msl.,12.	5,538,299	SSSWRDP
SP25288, Dariapur Subproject, CAD, Union : Jilim, HO Date: 09/08/2010				
	Header Tank	Size: 6.1mX2.6m 0.00	401,072	Main
	Buried Pipe Irrigation System	Size: 6.175Km Length 0.00	10,540,048	Main
	O&M Shed	Szie: 9.0mX5.0m 0.00	490,880	Main
	RCC U-Drain	Length= 1191m 0.00	3,038,371	Main
	Re-construction of PVC buried pipe network system	300mm dia, 1200m 0.00	8,827,823	PSSWRSP
SP25289, Chapai Grameen Subproject, CAD, Union : Gobatala, HO Date: 10/08/2010				
	O&M Shed	Size: 9.0mX5.0m 0.00	487,272	Main
	Burried Pipe Network System	Size: 5.150 Km Length 0.00	9,135,087	Main
	Header Tank (River Bank)	Size: 6.5mX3.0m 0.00	577,769	Main
	Header Tank (Pond Bank)	Szie: 6.5mX3.0m 0.00	581,673	Main
	Re-excavation of Water Reservoir	0.00	106,197	Main
	RCC U-Drain	Length=702m 0.00	1,680,547	Main
	Protective Works for Header Tank	0.00	1,313,504	Main
	Part-A: Estimate for laying 400mm dia Upvc buried pipe 0+	Ch. 0+360 km to 1+510 km	5,121,656	PSSWRSP
	Part-B: Estimate for laying 400mm dia Upvc buried pipe 0+	at Ch. 0+000 km to 0+190	849,845	PSSWRSP
PSSWRSP				
SP43039, Ghoghodima Khutbatala Subproject, CAD, Union : Gobatala, HO Date:				
	Part-B: Sump including Aqueduct, Syphone, DB, Turnout	0.00	789,922	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP44087, Mohadanga Panna Beel Subproject, CAD, Union : Jhilim, HO Date:	Part-A: Lined Canal	1758m 0.00	7,995,914	Main
	Part-C: WMCA office & others	12mx6m 0.00	1,341,620	Main
	Part-F: Outlet Structure-2&3	0.00	284,508	Main
	Part-G: Outlet Structure-4,5,6&7	0.00	520,586	Main
	Part-A: Header Tank-1	6.1mx4.8m 0.00	2,374,575	Main
	Part-D: Re-excavation of Gobrapukur	0.00	1,042,721	Main
	Part-C: RCC Buried Pipe Network system	0.00	31,895,268	Main
	Part-H: WMCA Office & Others	12mx6m 0.00	1,359,517	Main
	Part-B: Header Tank-2	6.1mx3.0m 0.00	1,702,366	Main
	Part-E: Outlet Structure-1	0.00	168,346	Main
SP44121, Kalitala Kashmahal Subproject, CAD, Union : Gobratola, HO Date: 03/05/2018	Part-A: Construction of Header Tank	0.00	1,667,872	Main
	Part-B: Construction of Buried Pipe	0.00	6,846,745	Main
	Part-C: Construction of RCC Lined Canal	0.00	4,436,963	Main
	Part-D: Re-excavation of 2 nos Pukur and 2 nos pipe culve	0.00	808,031	Main
	Part-E: Costruction of WMCA Office & Others	12mX6m 0.00	1,509,733	Main
SP46261, Sreerampur Subproject, CAD, Union : Baliadanga, HO Date: 26/04/2018	Part-A: Construction of Sump, RCC Irrigation Lined Canal	0.00	12,755,369	Main
	Part-B: Construction of 2Nos. Cross Drain & RCC pipe for c	0.00	185,795	Main
	Part-C: Construction of pumping platform with Stair	0.00	2,194,793	Main
	Part-D: Construction of WMCA Office and Others	0.00	1,240,025	Main
SP46278, Gorakhonathpur CAD Subproject, CAD, Union : Baliadanga, HO Date:	Part-A: Construction of Sump and Pumping platfrom	0.00	2,282,554	Main
	Part-B: Construction of RCC Lined Canal	0.00	21,165,439	Main
	Part-C: Construction of three nos road crossing	0.00	554,552	Main
	Part-D: Construction of WMCA Office & Others	12mX6m 0.00	1,355,738	Main
Shibganj SSWRDSP-1 SP15278, Gangarampur FCD Subproject, FCD, Union : Durlavpur, HO Date: 15/03/2003	Embankment Re-sectioning	3.00	885,640	Main
	Khal Re-excavation	2.10	344,059	Main
	Regulator	2-V(1.5mX2.4m)	5,274,349	Main
Joypurhat (Total SPs : 17 Nos.)				
Akkelpur SSWRDSP-2 SP22032, Gholkuri-Kadoa Subproject, WC, Union : Tilakpur, HO Date: 16/10/2007	Gholkuri-Kadoa Khal Re-excavation	6.15	495,472	Main
	WRS at Ch.4+780 km	3-V(1.50mX2.00m) 0.00	3,284,630	Main
	O&M Shed	12.00mX6.00m 0.00	231,753	Main
PSSWRSP SP44094, Chri Khal Subproject, DR&WC, Union : Rukindipur, HO Date: 29/12/2016	Part-A: Construction of Chiri WRS	(4v-1.5mX2.0m) 0.00	10,963,818	Main
	Part-B: Construction of Box Culvert	(2v-2.5mX2.5m) 0.00	1,744,334	Main
	Part-C: Construction of Typical Drainage Outlet (4 Nos.)	(1v0.450m) 0.00	164,268	Main
	Part-A: Re-axcavation of Chiri khal	7.80	5,955,715	Main
	Part-B: Construction of Levee	0.00	69,543	Main
	Part-C: Construction of Reference Lined Section	0.00	126,976	Main
	Part-D: Construction of WMCA Office & Others	12mX6m 0.00	1,633,882	Main
SP46227, Nandahar Khal Subproject, DR&WC, Union : Gupinatpur, HO Date: 28/11/2017	Part-A: Repairing of Existing Nandahar khal Regulator	(3v-1.5mX1.8m) 0.00	769,100	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Kalai SSWRDSP-1 SP13091, Kanmona-Haraboti WCS Subproject, DR&WC, Union : Kalai,Matrai,Moslemganj,	Part-B: Repair & upgradation of WRS (6v-1.2mX1.2m)	(6v-1.2mX1.2m) 0.00	569,097	Main
	Part-C: WMCA office & others	12mX6m 0.00	1,486,823	Main
	Part-A: Re-excavation of Kuchiamara-Nandahar Khal	8.45	11,469,410	Main
	Part-B: Re-excavation of Kathalbarir Khal	2.00	2,792,454	Main
	Part-C: Construction of Reference Lined Section	0.00	372,144	Main
SSWRDSP-2 SP24143, Kadirpur-Bakhara Subproject, DR&WC, Union : Zinderpur, HO Date: 28/02/2009	Kanmona Khal Re-excavation	4.68	1,058,037	Main
	Haraboti Khal Re-excavation	11.25	1,914,523	Main
	WRS at Ch.11+418m	3-V(1.5mx1.8m)	3,087,310	Main
PSSWRSP SP41002, Purba Sarail-Madai Subproject, DR&WC, Union : Punot. Zindapur, HO Date:	Re-excavation of Kadirpur-Bakhara Khal	3.72	619,345	Main
	Re-excavation of Branch Khal	0.73	197,055	Main
	Bakhara WRS at Ch.0+070Km	3 Vent-1.5mX1.8m 0.00	2,192,956	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	419,879	Main
SP44098, Shikta Maday Nungla Khal Subproject, DR&WC, Union : Punot, HO Date:	Part-A: Re-excavation of Purba Sarail-Madai Khal	8.80	3,989,771	Main
	Part-A: Madai Khal WRS-1	4 Vent-1.5mX2.0m 0.00	6,008,561	Main
	Part-B: Madai Khal WRS-2	3 Vent-1.5mX1.5m 0.00	4,468,834	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	939,410	Main
Khetlal SSWRDSP-1 SP15220, Pathanpara-Koitahar WCS Subproject, WC, Union : Barotara, HO Date:	Part-A: Construction of Shikta Maday Khal WRS	(3v-1.5mX2.0m) 0.00	9,806,254	Main
	Part-B: Construction of Shikta Maday Khal Drainge Structui	(3v-3.5mX3.0m) 0.00	3,769,337	Main
	Part-C: Construction of WMCA Office & Others	12mX6m 0.00	1,355,233	Main
	Part-A: Re-excavation of Shikta maday Khal	4.50	3,302,580	Main
	Part-B:Construction of Reference Lined Section	0.00	117,895	Main
PSSWRSP SP44134, Haraboti Khal Subproject, DR&WC, Union : Barotara, HO Date: 03/01/2018	Khal Re-excavation	4.35	456,910	Main
	WRS at Ch.0+350m	2-V(1.5mX1.8m)	1,367,770	Main
SP45175, Amlagari-Tulshiganga Subproject, DR&WC, Union : Mamudpur, HO Date:	Part-A: Harabati Khal WRS	(3v-1.5mX2.0m) 0.00	0	Main
	Part-B: Box-Culvert (2V-3.5mX3.50m)	(2V-3.5mX3.50m) 0.00	0	Main
	Part-C: WMCA Office & others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Harabati khal	4.70	7,895,733	Main
	Part-B: Construction of Reference Lined Section	0.00	126,464	Main
Panchbibi SSWRDSP-1 SP12012, Ulshi Khal FCD Subproject, FCD&WC, Union : Ayma Rasulpur, HO Date:	Part-A: Re-excavation of Amlagari Khal	7.62	8,780,006	Main
	Part-B: Construction of Reference Lined Section	0.00	248,977	Main
	Embankment Re-sectioning	16.11	2,929,497	Main
	Argi Khal Re-excavation	0.59	23,060	Main
	Argi Regulator	2-V(1.5mx1.2m)	909,808	Main
	Ulshi Regulator	2-V(1.5mX1.8m)	1,843,700	Main
	Krisnapur Regulator	2-V(1.2mx1.5m)	949,621	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP13078, Baharampur FCD Subproject, FC, Union : Kushumba, HO Date: 04/11/2002	Modifying Culvert to Regulator	2-V(1.5mx1.5m)	389,022	Main
	Embankment Re-sectioning	11.78	2,168,256	Main
	Regulator at Ch.3+376m	1-V(1.5mX1.5m)	1,367,010	Main
	Regulator at Ch.6+644m	2-V(1.5mX1.5m)	1,620,912	Main
	Pipe Sluice at Ch.5+690m	1-V(600mm Dia)	208,447	Main
	Regulator at Ch.4+197m	2-V(1.5mX1.5m)	1,497,843	Main
SP15277, Boyra-Srikrishnapur DR & WCS Subproject, DR&WC, Union : Aolai, HO Date:				
	WMCA Office	12mX6m 0.00	0	SSSWRDP
	Boyra-Srikrishnapur khal re-excavation(ch.00-6800m)	6.80	8,521,392	SSSWRDP
	Referenced line section(5nos)	0.00	0	SSSWRDP
	Khal Re-excavation	7.80	2,369,441	Main
	Panial WRS at Ch.0+300m	3V-1.5m	2,229,022	Main
SSWRDSP-2				
SP22015, Amirpur-Barail Subproject, DR&WC, Union : Kusumba,Mohammadpur, HO Date:				
	Re-excavation of Amirpur Barail Khal	6.45	2,187,162	Main
	Re-excavation of Amirpur Barail Branch Khal-1	1.05	140,932	Main
	WRS-1 at Ch.0+185 km	1 Bay 12.80m Wide 0.00	2,188,022	Main
	WRS-2 at Ch.2+515 km	1 Bay 8.40m Wide 0.00	1,349,073	Main
	O&M Shed	9.00mX5.00m 0.00	257,512	Main
	Re-excavation of Amirpur Barail Branch Khal-2	0.88	97,434	Main
	Amirpur Borail khal & Branch khal- 1 re-excavation(ch.00-6	6.97	5,407,456	SSSWRDP
	Referenced line section(5nos)	0.00	194,261	SSSWRDP
PSSWRSP				
SP44109, Jhinaigari Khal Subproject, DR&WC, Union : Atapur, HO Date: 28/08/2017				
	Part-A: Construction of Jhinaigary Khal Regulator	(4vX1.50mX1.80m) 0.00	24,458,592	Main
	Part-B: Construction of Box Culvert	(2vX-3.50mX3.50m) 0.00	2,865,855	Main
	Part-C: Construction of WMCA Office & others	12mX6m 0.00	1,289,926	Main
	Part-B: Construction of Reference Lined Section	0.00	130,151	Main
	Part-A: Re-excavation of Jhinaigary Khal	6.25	3,113,980	Main
SP45194, Bhigram Sirota Khal Subproject, DR&WC, Union : Aolai, HO Date: 25/09/2017				
	Part-A: Construction of WRS (3v-1.5mX2.0m) on Bhigram I	(3v-1.5mX2.0m) 0.00	8,910,945	Main
	Part-B: Construction of Typical Drainage Outlet (4nos) 450m	(4nos) 450mm Dia 0.00	340,922	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	1,333,252	Main
	Part-A:Re-excavation of Bhigram-Sirota Khal	5.20	4,032,348	Main
	Part-B:Re-excavation of Laxmikul Khal	1.20	816,225	Main
	Part-C: Construction of Reference Lined Section Bhigram-	0.00	126,947	Main
	Part-D: Construction of Reference Lined Section Laxmikul	0.00	39,391	Main
Sadar				
SSWRDSP-1				
SP15221, Hatigara-Kamalpur WCS Subproject, WC, Union : Puranapail,Kusumba, HO				
	Hatigara-Kamalpur Khal Re-excavation	7.92	2,005,775	Main
	WRS AT Ch.0+120	3-V(1.5mX1.8m)	1,683,010	Main
Naogaon (Total SPs : 30 Nos.)				
Atrai				
SSWRDSP-2				
SP25327, Lalpara-Paisanta Subproject, DR&WC, Union : Moniari, HO Date: 19/04/2011				
	Re-excavation of Lalpara Khal	4.00	1,987,475	Main
SP25328, Islamgathi-Maria-Kosiabari Subproject, DR&IRR, Union : Moniari, HO Date:				
	Re-excavation of Islamgathi-Maria Khal	6.00	2,024,636	Main
	Re-excavation of Maria-Kasiabari Khal	6.50	3,907,536	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP25329, Jatamrul-Singsara Subproject, DR&WC, Union : Ahashangonj, HO Date:	O&M Shed	Size: 0.00	583,278	Main
	Re-excavation of Cheeker Beel Khal	4.50	1,906,105	Main
	Re-excavation of Dhigha-Sutkigacha Khal	3.70	1,983,128	Main
	Part-A: Construction of WMCA Office & Others	12mX6m 0.00	1,612,362	PSSWRSP
SP25332, Kachua Beel Subproject, DR, Union : Kalikapur, HO Date: 17/01/2011	Re-excavation of Kachua Khal	8.10	3,436,820	Main
	Part-A:- Re-excavation of kachua Beel khal	12.10	3,615,596	PSSWRSP
	Part-A: WMCA office and others	12mX6m 0.00	1,609,468	PSSWRSP
PSSWRSP				
SP43032, Chalk Temukh-Islamgati Subproject, FMD, Union : Bisha, HO Date: 10/09/2018	Part-B: Re-excavation of chak temukh khal	4.20	1,969,498	Main
	Part-A: Re-excav. of samaspara khal & resectioning	2.60	4,437,612	Main
	Part-A: Samaspara khal Regulator	3V-1.5mx1.8m 0.00	15,548,062	Main
	Part-B: WMCA office & others	12mx6m 0.00	1,360,379	Main
	Part-C: Construction of Reference Lined Section	6.80	340,225	Main
SP43042, Atrai-Burigonj Subproject, DR, Union : Pachupur, HO Date: 30/08/2016	Part-A: Re-excavation of Atrai river	6.73	7,436,737	Main
	Part-B: Construction of Reference Lined Section	6.73	144,554	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,420,137	Main
SP44102, Bisha-Udaypur khal Subproject, DR&WC, Union : Bisha, HO Date: 12/09/2018	Part-A: Construction of Bisha-Udoypur khal Regulator	0.00	0	Main
	Part-B: Construction of WMCA Office & othes	12mX6m 0.00	0	Main
	Part-D: Construction of Reference Line Section	0.00	52,790	Main
	Part-A: Re-excavation of Bisha-Udoypur khal	1.70	927,179	Main
	Part-B: Re-excavation of Bisha-Udoypur khal Branch Khal-	0.40	39,964	Main
	Part-C: Re-excavation of Bisha-Udoypur khal Branch Khal-	0.40	53,558	Main
Rubber Dam				
SP99003, Atrai River Rubber Dam Project, WC, Union : , HO Date:	Atrai River Rubber Dam (Naogaon)	Size: 135mX4.5m 0.00	173,936,000	Main
Badalgachi				
PSSWRSP				
SP46256, Abhaipur- Baikandapur Khal, DR&WC, Union : Badalgachi, HO Date: 22/04/2018	Part-A: Construction of a Regulator	(3v-1.5mX1.5m) 0.00	9,822,452	Main
	Part-B: Construction of a Box Culvert	(1v-3.0mX2.0m) 0.00	238,649	Main
	Part-C: Construction of WMCA Office and Others	121mX6m 0.00	1,481,013	Main
	Part-A: Re-excavation of Baikantapur Khal	1.25	879,358	Main
	Part-B: Re-excavation of Branch Khal	0.20	108,017	Main
	Part-C: Construction of a Referenced Lined Section	0.00	66,447	Main
Dhamoirhat				
SSWRDSP-1				
SP15222, Titukata Khal WCS Subproject, WC, Union : Alampur,Dhamoirhat, HO Date:	Titukata Khal Re-excavation	12.54	1,634,860	Main
	WRS at Ch.0+025m	3-V(1.5mX1.8m)	1,754,438	Main
	WRS at Ch.7+700m	2-V(1.5mX2.0m)	2,149,992	Main
SP15224, Ghukshi WCS Subproject, WC, Union : Dhamoirhat, HO Date: 15/02/2001	Ghukshi Khal Re-excavation	14.63	823,565	Main
SP15315, Lodipur-Dhananjoy DR & WCS Subproject, DR&WC, Union : Khelna,Agradigun,	Mamudpur Khal Re-excavation	11.15	1,777,772	Main
	WRS at Ch.0+050m	1-V(10.0mX1.5m)	1,464,325	Main
	WRS at Ch.7+800m	1-V(10.0mX1.m)	1,180,145	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SSWRDSP-2				
SP22005, Mongol Khal Subproject, WC, Union : Omar,Dhamoirhat, HO Date: 28/07/2008				
	WRS-1 at Ch.0+570 km	3-V(1.50mX2.00m) 0.00	2,995,640	Main
	WRS-2 at Ch.4+050 km	2-V(1.50mX2.00m) 0.00	2,483,861	Main
	Mongol Khal Re-excavation	9.84	4,504,681	Main
	O&M Shed	12.00mX6.00m 0.00	307,040	Main
	Mongol khal re-excavation(ch.00-4000m)	4.00	10,509,883	SSSWRDP
	Referenced line section(4 nos)	0.00	140,946	SSSWRDP
	Bamboo bridge(1 nos)(20m)	0.02	0	SSSWRDP
Manda				
SSWRDSP-1				
SP15226, Parkulihar Paikpara DR Subproject, DR, Union : Kanso Para, HO Date:				
	Parkurihar Paikpara Khal Re-excavation	0.58	123,223	Main
Mohadebpur				
SSWRDSP-1				
SP13074, Ramchandrapur FCD Subproject, FCD&WC, Union : Khajur, HO Date:				
	Embankment Re-sectioning	5.10	375,859	Main
	Ramchandrapur khal re-excavation(ch.00-740m)	0.74	1,652,665	SSSWRDP
	Ramchandrapur Embankment re-sectioning(ch.00-3050m)	3.05	6,225,916	SSSWRDP
	Referenced line section(1nos)	0.00	29,604	SSSWRDP
	Bamboo bridge(1nos)	0.00	44,924	SSSWRDP
	Khal Re-excavation	1.01	111,317	Main
	Ramchandrapur Regulator	2-V(1.5mX1.8m)	2,074,032	Main
	Embankment Protection Works	0.055 km	0	Main
SSWRDSP-2				
SP25205, Khorda Kalna Khal Subproject, WC, Union : Khajur, HO Date: 19/06/2009				
	WRS at Ch.1+468Km	3 Vent-1.5mX2m 0.00	2,978,101	Main
	O&M Shed	Size: 9mX5m 0.00	297,092	Main
	Re-excavation of Khorda Kalna khal	3.78	2,079,903	PSSWRSP
Niamatpur				
SSWRDSP-1				
SP14157, Niamatpur-Gahail WCS Subproject, WC, Union : Rasulpur, HO Date: 11/09/2002				
	Niamatpur Khal Re-excavation (Sec. A)	12.24	1,964,722	Main
	Niamatpur Khal Re-excavation (Sec. B)	4.90	378,894	Main
	WRS at Ch.0+060m	14m width	3,539,437	Main
	WRS at Ch.2+890m	10m width	3,147,795	Main
	WRS at Ch.6+050m	7m width	2,652,711	Main
	WRS at Ch.9+420m	5m width	2,317,236	Main
	O&M Shed		0	Main
SP15314, Ghoskura-Dadral DR & WCS Subproject, DR&WC, Union :				
	Ghoskura-Dadral Khal Re-excavation	9.10	1,793,183	Main
	WRS at Ch.0+050m	1-V(14.0mX2.0m)	2,845,513	Main
	WRS at Ch.5+400m	1-V(12.0mX2.3m)	2,430,803	Main
SSWRDSP-2				
SP25199, Pathkoil-Mohammadpur Subproject, DR&WC, Union : Hazinagar, HO Date:				
	Weir-1 at Ch.1+800Km	1 Bay-13mX2.8m 0.00	2,811,450	Main
	Weir-2 at Ch.4+900Km	1 Bay-11.5mX3m 0.00	2,975,144	Main
	Weir-3 at Ch.7+600Km	1 Bay-10.5mX3m 0.00	2,835,433	Main
	O&M Shed	Size:9mX5m 0.00	781,310	Main
	Re-excavation of Pathkoil-Mohammadpur Khal	4.75	1,861,961	Main
SP25221, Chandail-Tekharia Subproject, WC, Union : Rasulpur, HO Date: 24/06/2010				
	Re-excavation of Chandail-Tekharia Khal	3.60	1,632,000	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Branch Khal-3	1.30	0	Main
	Weir-1 at Ch. 6+950Km	1 Bay-24mX2.7m 0.00	4,493,143	Main
	Weir-2 at Ch. 9+500Km	1 Bay-22mX2.9m 0.00	6,230,064	Main
	O&M Shed	Size: 9mX5m 0.00	748,793	Main
PSSWRSP				
SP43031, Belgaur-Julupara Subproject, DR, Union : Bahadurpur, HO Date: 17/08/2016				
	Part-A: WMCA office & others	12mx6m 0.00	1,432,583	Main
	Part-A: Re-excavation of Julupara khal	8.23	13,516,709	Main
	Part-B: Construction of reference lined section	0.00	156,506	Main
SP43033, Sontospara-Chatra Subproject, DR, Union : Bhabicha, HO Date: 18/08/2016				
	Part-A: WMCA office & others	12mx6m 0.00	1,434,775	Main
	Part-A: Re-excavation Santoshpara khal	11.70	14,420,606	Main
	Part-B: Construction of reference Lined section	0.00	102,975	Main
Patnitala				
SSWRDSP-1				
SP14155, Abadia FCD Subproject, FCD, Union : Patnitala,Krishnapur, HO Date:				
	Abadia Khal Re-excavation	3.30	637,245	Main
	Abadia Khal Regulator at Ch.0+050m	3-V(1.5mX1.8m)	3,747,275	Main
SP14156, Katabari FCD Subproject, FCD, Union : Patnitala, HO Date: 17/07/2003				
	Embankment Re-sectioning	3.38	1,346,331	Main
	Part-A: WMCA Office & others	12mX6m 0.00	1,326,880	PSSWRSP
	Katabari khal re-excavation(ch.00-2800m)	2.80	3,783,799	SSSWRDP
	Embankment re-sectioning(ch.00-1200m)	1.20	1,124,339	SSSWRDP
	Referenced line section(3nos)	0.00	75,892	SSSWRDP
	Bamboo bridge(3 nos)	0.00	168,465	SSSWRDP
	Katabari Khal Re-excavation	2.80	172,364	Main
	Katabari Regulator	2-V(1.5mX1.8m)	3,226,078	Main
SP15313, Akhira-Saidpur Khal DR & WCS Subproject, DR&WC, Union :				
	Khal Re-excavation	12.72	2,379,420	Main
	WRS at Ch.0+900m	1-V(16.0mX2.0m)	2,730,999	Main
	WRS at Ch.7+700m	1-V(13.0mX2.0m)	2,317,984	Main
	WRS at Ch.14+100m	1-V(10.0mX1.5m)	1,351,682	Main
Raninagar				
PSSWRSP				
SP42025, Kujail-Raktadaha Subproject, DR&WC, Union : Kashimpur, HO Date: 22/08/2016				
	Part-A: Re-excavation of Kujail-Roktadaha khal	6.78	8,024,541	Main
	Part-B: Construction of referece lined section	0.00	172,262	Main
	Part-A: WMCA office & others	12mx6m 0.00	1,384,790	Main
SP42026, Ratandara-Sodakhali Subproject, DR&WC, Union : Gona, HO Date: 22/08/2016				
	Part-A: Re-excavation of Ratan Danra khal	5.10	6,253,592	Main
	Part-B: Construction of reference lined section	0.00	165,317	Main
	Part-A: Construction of WMCA office & Others	12mx6m 0.00	0	Main
SP44133, Gohelapur-Shafiqpur Subproject, DR&WC, Union : Baragacha, HO Date:				
	Part-A: Construction of Gohelapur WRS (2v-1.5mX1.5m) ai	(2v-1.5mX1.5m) 0.00	4,519,472	Main
	Part-E: Construction of WMCA Office & Others	12mX6m 0.00	1,500,170	Main
	Part-B: Construction of Gohelapur WRS (3v-1.5mX1.8m) ai	(3v-1.5mX1.8m) 0.00	7,754,794	Main
	Part-C: Construction ofBox culvert at ch. 4+875 km	0.00	2,280,778	Main
	Part-A: Re-excavation of Gohelapur-Shafiqpur Khal	10.50	13,002,180	Main
	Part-B: Construction of Reference Lined Section	0.00	262,884	Main

Sadar
PSSWRSP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP46232, Krishnapur-Baromashi Khal Subproject, DR&WC, Union : Hanshaigari, HO Date:				
	Part-A: Mohol Singra Khal	0.00	3,098,949	Main
	Part-B: Mohol Singra Khal Box Culvert	0.00	999,777	Main
	Part-C: Construction of WMCA office and others	12mX6m 0.00	1,420,958	Main
	Part-A: Re-excavation of Krishnapur-Baromashi Khal	7.23	9,646,270	Main
	Part-B: Re-excavation of Mohaisinga Khal	1.80	1,143,035	Main
	Part-C: Construction of reference lined section	0.00	390,756	Main
Shapahar SSWRDSP-2				
SP24164, Doharakhari-Tarachandkhari Subproject, WC, Union : Shironti, HO Date:				
	Re-excavation of Dohara Khari	6.30	4,175,090	Main
	Tarachandkhari Weir-1 at Ch. 0+600Km (Khal)	1 Bay-14.0mX1.5m 0.00	2,572,275	Main
	Tarachandkhari Weir-2 at Ch. 1+400Km (Khal)	1 bay-9.0mX1.8m 0.00	2,608,265	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	423,705	Main
	Re-excavation of Tara Chand Khari Khal	2.20	2,226,281	PSSWRSP
Natore (Total SPs : 15 Nos.)				
Baraigram SSWRDSP-1				
SP14148, Kumarkhali FCD Subproject, FCD, Union : Nagor, HO Date: 19/10/2002				
	Embankment Re-sectioning(Sec. A)	1.87	1,136,712	Main
	Embankment Re-sectioning(Sec. B)	3.85	2,508,340	Main
	Kumarkhali Khal Re-excavation	0.91	60,826	Main
	Padma Khal Re-excavation	0.83	83,930	Main
	Regulator at Ch.1+108m	2-V(1.5mX1.8m)	1,866,415	Main
	O&M Shed		233,823	Main
SP15254, Dhulai Beel DR Subproject, DR, Union : Baraigram, HO Date: 16/05/2002				
	Dhulai Beel Khal Re-excavation	6.70	600,763	Main
SSWRDSP-2				
SP24146, Beel Gorila Subproject, FMD&WC, Union : Baraigram, HO Date: 05/07/2009				
	Gorila Khal Regulator at Ch.3+197Km	2 Vent-1.5mX1.8m 0.00	5,276,144	Main
	Re-sectioning of Embankment	5.01	1,605,680	Main
	Re-excavation Gorila Khal	3.51	554,200	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	414,022	Main
SP25231, Mesoghata Beel Subproject, FMD&WC, Union : Chandai & Gopalpur, HO Date:				
	Re-excavation of Deogaon Khal	5.00	632,063	Main
	Re-sectioning of Embankment	8.00	4,849,937	Main
	Deogaon Khal Regulator at Ch.0+046Km(Khal)	3 Vent-1.5mX1.8m 0.00	3,831,091	Main
	Deogaon Khal WRS at Ch.2+330Km(Khal)	2 Vent-1.5mX1.8m 0.00	2,313,681	Main
	O&M Shed	Size: 9mX5m 0.00	541,323	Main
PSSWRSP				
SP45157, Satal Beel Subproject, DR, Union : Chandai, HO Date: 30/01/2018				
	Part-A: Construction of WMCA Office & Others	12mX6m 0.00	1,426,932	Main
	Part-A: Re-excavation of Satal Khal	4.90	4,135,543	Main
	Part-B: Construction of Re-ferece Lined Section	0.00	126,984	Main
JICA-LGED TA Project				
SP51001, Korial Beel Subproject, FMD&WC, Union : Nagor, HO Date: 31/03/2018				
	Re-excavation of Korial Beel Khal	1.65	541,199	Main
	Box Culvert in Koial Beel	3.0m x 2.0m 0.00	1,277,438	Main
	Carpetting the Road	1.2km 0.00	5,591,239	Main
	Construction of Reference Line Section (2 nos)	0.00	20,948	Main
	Construction of Earthen Road	0.95	498,347	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Gurudaspur SSWRDSP-2 SP25232, Moshinda Beel Subproject, FMD&WC, Union : Moshinda, HO Date: 31/12/2009	Improvement of Merigacha Bazar	0.00	46,200	Main
	Re-excavation of Kujail Khal	0.60	177,748	Main
	Improvement of Brick Drain in Merigacha Bazar	94.00 m long 0.00	272,033	Main
	Construction of tube Well in Merigacha Bazar	0.00	47,461	Main
	Construction of Covered Shed in Merigacha Bazar	Size: 4.0mX12m 0.00	438,480	Main
	Construction of Toilet in Merigacha Bazar	0.00	434,269	Main
	WMCA Office & Others	0.00	1,843,885	Main
	Re-shaping of Embankment	1.06	652,129	Main
	Korial Beel Regulator	1v-1.5m X 1.8m 0.00	2,404,138	Main
PSSWRSP SP45196, Dighdaria Subproject, FMD, Union : Biaghat, HO Date: 23/05/2018	Ranigram Khal Regulator at Ch. 0+080Km (Khal)	1 Vent-1.5mX1.8m 0.00	2,951,395	Main
	Kachikata Khal Regulator at Ch. 0+064Km (Khal)	2 Vent-1.5mX1.8m 0.00	3,460,953	Main
	O&M Shed	Size: 9mX5m 0.00	541,323	Main
	Approach Road-cum-Embankment	1.70	583,795	Main
Rubber Dam SP98005, Atrai River Rubber Dam Project, WC, Union : Biaghat, HO Date:	Part-A: Construction of Regulator (2v-1.5mX1.5m)	(2v-1.5mX1.5m) 0.00	6,290,106	Main
	Part-B: Construction of Regulator (1v-1.5mX1.5m)	(1v-1.5mX1.5m) 0.00	5,536,357	Main
	Part-C: Construction of Box Culvert	0.00	1,147,266	Main
	Part-D: WMCA Office & Others	12mX6m 0.00	1,354,067	Main
	Part-A: Re-sectioning of Dighdaria Embankment	3.75	10,339,610	Main
Sadar SSWRDSP-1 SP13070, Rampur FCD Subproject, FCD&WC, Union : Baro Harishpur, HO Date:	Atrai River Rubber Dam	Size: 45mX3.5m 0.00	31,675,000	Main
	Bishani khal re-excavation(ch.00-4300m)	4.30	9,254,860	SSSWRDP
	WMCA office& pump house repair	WMCA(12mX6m) 0.00	197,890	SSSWRDP
SP14146, Dighapatia FCD Subproject, FCD, Union : Dighapatia,Chatnai, HO Date:	Embankment Re-sectioning	1.40	406,056	Main
	Khal Re-excavation	1.90	66,336	Main
	Rampur Regulator	1-V(1.5mX1.5m)	1,997,000	Main
	O&M Shed		223,902	Main
SP15260, Narayanpara DR Subproject, DR, Union : Kufuria, HO Date: 15/05/2002	Dighapatia Beel Khal Re-excavation	2.18	616,775	Main
	Dighapatia Regulator at Ch.0+098m	1-V(1.5mX1.8m)	1,608,491	Main
	Rajbari Regulator	1-V(1.5mX1.5m)	1,679,165	Main
SSWRDSP-2 SP24129, Nepal Dighi Goal Dighi Subproject, DR&WC, Union : Dighapatia, HO Date:	Narayanpara Khal Re-excavation	2.20	352,973	Main
	Box Culvert at Ch. 0+125m	1-V(3.6mX2.6m)	461,225	Main
	Box Culvert at Ch. 1+135m	1-V(3.6mX2.6m)	461,225	Main
SSSWRDP	Nepal Dighi-Goal Dighi Khal Regulator at Ch. 0+175	2 Vent-1.5mX1.8m 0.00	5,029,687	Main
	Re-excavation of Nepal Dighi-Goal Dighi Khal	3.92	1,388,799	Main
	Re-excavation of Nepal Dighi-Goal Dighi Br Khal-1	0.46	35,256	Main
	Re-excavation of Nepal Dighi-Goal Dighi Br Khal-2	0.83	116,686	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	570,572	Main
	Nepal Dighi-Goal Dighi khal re-excavation(ch.00-2300m)	2.30	5,672,626	SSSWRDP
	maintenance of sluicagate(at ch.175m)	0.00	45,818	SSSWRDP

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Singra SSWRDSP-1 SP14147, Singradaha FCD Subproject, FCD, Union : Singra, HO Date: 24/10/2004	Mainnntenance of WMCA Office	12mX6m 0.00	390,813	SSSWRDP
	Referenced line section(3nos)	0.00	77,551	SSSWRDP
	Bamboo bridge(2nos)	0.00	82,361	SSSWRDP
SP15238, Dhuliadanga FCD Subproject, FCD, Union : Hatiandaha, HO Date: 12/06/2004	Embankment Re-sectioning	19.29	9,294,019	Main
	Baduri Para Khal Re-excavation	0.85	123,636	Main
	Abdul Ali Khal Re-excavation	2.32	118,538	Main
	Hanspukuria Khal Re-excavation	0.55	69,836	Main
	Abdul Ali Khal Regulator at Ch.0+000m	2-V(1.5mX1.8m)	2,406,486	Main
	Baduri Para Khal Regulator at Ch.12+380m	2-V(1.5mX1.8m)	2,390,396	Main
	Hanspukuria Khal Regulator at Ch.17+330m	2-V(1.5mX1.8m)	1,784,037	Main
Pabna (Total SPs : 7 Nos.)	Shibtala Khal Re-excavation(Sec. 1)	0.60	56,318	Main
	Sahebkata Khal Re-excavation	0.60	105,427	Main
	Shibtala Khal Re-excavation(Sec. 2)	0.60	77,613	Main
	Shibtala Khal Regulator	1-V(1.2mX1.2m)	1,226,850	Main
	Sahebkata Khal Regulator	2-V(1.2mX1.2m)	1,510,969	Main
Atghoria SSWRDSP-1 SP11005, Rameswarpur-Kachuarampur FCD Subproject, FCD, Union : Maizpara, HO	Embankment Re-sectioning	10.76	2,560,586	Main
	Box Sluice	2-V(1.37mX1.8m)	553,616	Main
	Modification of Bridge to Regulator	2-V(1.5mx1.2m)	1,238,240	Main
	Pipe Sluice at Ch. 0+925m	1-V(900mm Dia)	411,948	Main
	Pipe Sluice at Ch. 2+500m	1-V(900mm Dia)	413,029	Main
	Pipe Sluice at Ch. 3+050m	1-V(900mm Dia)	391,789	Main
	Pipe Sluice at Ch. 4+920m	1-V(900mm Dia)	398,678	Main
	Fish Screen		0	Main
PSSWRSP SP43028, Sapdanga Khal Subproject, DR&WC, Union : Debottor, HO Date: 13/09/2017	Part-A: Construction of Sabdanga khal WRS-1	3V-1.5mx1.5m 0.00	7,342,838	Main
	Part-B: Construction of Sabdanga khal WRS-2	3V-1.5mx1.8m 0.00	6,141,595	Main
	Part-C: Construction of WMCA office & others	12mx6m 0.00	1,378,756	Main
	Part-A: Re-excav. of Sampasa khal & Shamurer khal	4.35	1,402,802	Main
Bhangura SSWRDSP-1 SP13072, Astomanisha FCD Subproject, FCD, Union : Astomanisha, HO Date: 27/06/2002	Embankment Re-sectioning	7.20	4,162,336	Main
	Damaged Embankment Re-sectioning	0.07	68,541	Main
	Closure at Ch.5+540m & 6+140m	0.10	41,455	Main
	Singari Regulator	2-V(1.5mX1.5m)	2,268,397	Main
	Fish Screen at Singari Regulator		49,304	Main
Chatmohor SSWRDSP-1 SP14195, Kurulia Beel FCD Subproject, FCD, Union : Chatmohor,Haripur, HO Date:	Embankment Re-sectioning	11.49	475,958	Main
	Vadra sluicagate -Mosharaf Hossener Dip mechine porjont	2.10	2,991,670	SSSWRDP
	Dharail Khal Re-excavation	3.60	1,695,947	Main
	Mathurapur Khal Re-excavation	8.20	1,593,351	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Iswardi SSWRDSP-2 SP25261, Civil Hat-Padma Subproject, FMD&WC, Union : Pakshi, HO Date: 14/07/2010	Mathurapur Regulator at Ch.5+390m	2-V(1.5mX1.8m)	2,553,857	Main
	Dharail Regulator at Ch.0+210m	2-V(1.5mX1.8m)	3,634,209	Main
	Civilhat Khal Regulator at CH. 0+644Km	1 Vent-1.5mx1.8m 0.00	2,655,042	Main
	Re-excavation of Civilhat Khal	3.08	928,000	Main
	O&M Shed	Size: 9mX5m 0.00	390,132	Main
Santhia SSWRDSP-1 SP15255, Chinanary-Bhitapara DR & WCS Subproject, DR&WC, Union : Nagdemra, HO	Drainage Structure-1 (Box) at Ch.1+165Km (Khal)	1 Vent-2.0mX3.4m 0.00	583,999	Main
	Drainage Structure-2 (Box) at Ch.1+865Km (Khal)	1 Vent-2.0mX3.4m 0.00	1,023,827	Main
	Chinanary-Bhitapara khal re-excavation(ch.2200-3100m)	0.90	2,657,620	SSSWDRP
	Wire repair work	0.00	560,784	SSSWDRP
	Chinanary Khal Re-excavation	6.15	1,338,960	Main
Sujanagar PSSWRSP SP42027, Nuruddin Khal Subproject, DR&WC, Union : Hatkahli, HO Date: 28/03/2018	Chinanary Bhitapara WRS	1V(35m X 2m)	5,672,258	Main
	O&M Shed		0	Main
	Part-A: Re-excavation of Nuruddin khal	2.58	2,201,536	Main
	Part-B: Construction of Reference Lined Section	0.00	103,041	Main
	Part-A: Nuruddin khal WRS at ch. 0+130 km	2V-1.5mx1.8m 0.00	6,918,480	Main
Rajshahi (Total SPs : 25 Nos.) Charghat SSWRDSP-1 SP14142, Nimpara-Habibpur DR Subproject, DR, Union : Nimpara, HO Date: 31/05/2004	Part-B: Nuruddin khal box culvert at ch. 1+770 km	1V-4.50mx4.50m 0.00	2,359,825	Main
	Part-C: Construction of WMCA office & others	12mx6m 0.00	1,373,992	Main
	Nimpara Habibpur Khal Re-excavation	4.74	861,763	Main
	WRS at Ch.0+130m	3-V(1.5mX1.8m)	2,160,153	Main
	SP14143, Barkatpur Baladiar DR Subproject, DR, Union : Nimpara, HO Date: 06/06/2004			
Borkotpur-Baladia khal re-excavation(ch.1000-2300m)	Referenced line section(2nos)	1.30	2,219,512	SSSWDRP
	Bamboo bridge(2nos)	0.00	70,126	SSSWDRP
	Barkatpur-Baladiar Khal Re-excavation	0.00	104,822	SSSWDRP
	WRS at Ch.0+000m	3.64	622,365	Main
		2-V(1.5mX1.5m)	1,848,181	Main
Durgapur PSSWRSP SP44114, Isobpur Dakkin Beel-Chaipara, DR, Union : Noapara, HO Date: 27/11/2017	Part-A: Construction of Bank Protection Work in Chaipara k	Ch. 1+740 km 0.00	1,154,195	Main
	Part-B: Construction of WMCA Office	12mX6m 0.00	1,125,225	Main
	Part-A: Re-excavation of Chaipara-Kalitola Khal	4.20	1,810,350	Main
	Part-B: Construction of Reference Lined Section	0.00	53,451	Main
	SP46250, Amulia Beel -Barnai River Subproject, DR&WC, Union : Joynagar, HO Date:			
Part-A: Construction of Box Culvert	(2v-2.5mX7.0m) 0.00		0	Main
	Part-B: Construction of Drainage Outlet	(450mm dia) 0.00	0	Main
	Part-C: Construction of Box Culvert	0.00	0	Main
	Part-D: Construction of WMCA Office and others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Kushadanga khal	3.50	0	Main
Part-B: Construction of Levee	at Ch. 0+000 km to 3+400		0	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Godagari SSWRDSP-1 SP12037, Dudhai-Bhanpur Khal WCS Subproject, WC, Union : Mohonpur, HO Date:	Part-C: Construction of Reference Lined Section	0.00	0	Main
	Dudhai Bhanpur Khal Re-excavation	7.60	963,896	Main
	WRS at Ch.6+800m	3-V(1.5mX2.8m)	2,115,995	Main
	Vertical Lift Gate Over WRS		0	Main
	SSWRDSP-2			
	SP24160, Soguna-Prosadpara Subproject, DR&WC, Union : Pakri, HO Date: 28/01/2009			
	Pakri Branch Khal Re-excavation	0.90	320,091	Main
	Prasadpur Weir at Ch. 4+300 Km	1 Bay-22mX2.6m 0.00	5,776,301	Main
	Repair of existing Weir at Ch. 10+255 Km	1 Bay-17.5mX3.0m 0.00	1,317,498	Main
	SP24161, Kazipur-Babudang Khari Subproject, DR&WC, Union : Muhunpur, HO Date:			
	Kazipur Khal Re-excavation	4.00	1,776,663	Main
	Babudang WRS at Ch. 0+700Km (Km)	1 Bay-15mx3.5m 0.00	6,530,426	Main
	Repair of Existing WRS at Ch. 3+128Km (Khal)	2 Vent-1.5mX2.0m 0.00	692,630	Main
	Repair of Existing WRS at Ch. 4+675Km (Khal)	2 Vent-1.5mX2.0m 0.00	721,750	Main
	O&M Shed	Size: 9mX5m 0.00	316,249	Main
	SP24168, Joyrampur-Narayanpur Subproject, DR&WC, Union : Pakri, HO Date:			
	Re-excavation of Narayanpur Khal	3.30	1,299,909	Main
	O&M Shed	Size: 12mX6m 0.00	333,088	Main
	Narayanpur Khal Weir-1 at Ch. 0+100Km	1 Bay-13.0mX2.5m 0.00	1,024,140	Main
	Narayanpur Khal Weir-2 at Ch. 3+900Km	1 Bay-12.0mX3.0m 0.00	969,136	Main
	Narayanpur Khal Weir-3 at Ch. 8+000Km	1 Bay-11.0mX3.0m 0.00	907,350	Main
	Joyrampur Khal Weir-4 at Ch. 3+100Km	1 Bay-12.0mX3.0m 0.00	969,135	Main
	SP24176, Tulshipur Borokhari-Dariapur Sub-Project, DR&WC, Union : Gogram, HO Date:			
	Weir-1 at Ch. 5+800 km (Khal)	1 Bay-16mX2m 0.00	1,439,241	Main
	Weir-2 at Ch. 8+800 km (Khal)	1 Bay-14mX2m 0.00	1,365,824	Main
	O & M Shed	Size: 9mX5m 0.00	392,146	Main
	SP25227, Hatnabad Subproject, CAD, Union : Basudevpur, HO Date: 13/09/2010			
	Burried Pipe System	3900m 0.00	7,715,899	Main
	Re-excavation of Baliaghata Khal	0.60	736,000	Main
	Header Tank	Size: 6.5mX3m 0.00	535,097	Main
	O&M Shed	Size: 9mX5m 0.00	289,004	Main
	Construction of RCC U-Drain Buried Pipe	at Ch.0+800 km and 2+690	2,839,001	PSSWRSP
	SP25235, Kashimpur CAD Sub-project, CAD, Union : Basudevpur, HO Date: 12/10/2011			
	Header Tank	Size: 6.5mX3m 0.00	349,254	Main
	Buried Pipe Network System	4600m Length 0.00	8,204,819	Main
	Re-excavation of Charai Beel Khal	2.50	77,640	Main
	O&M Shed	Size: 9mX5m 0.00	489,928	Main
	Extension of RCC U-drain & Branch canal	uPVC 315mm 0.00	3,958,522	PSSWRSP
	SP25236, Baliaghata Subproejct, CAD, Union : Basudevpur, HO Date: 14/09/2010			
	Irrigation Canal Network System	2850m Length 0.00	7,948,146	Main
	O&M Shed	Size:9mX5m 0.00	277,854	Main
	Construction of uPVC Buried pipe and extension of 1st bra	at ch 1+650m to 1+870m	2,801,670	PSSWRSP
	Mohonpur PSSWRSP			
	SP45198, Shutki Beel Subproject, DR&WC, Union : Jahanabad, HO Date:			
	Part-A: Sukti Khal regulator (2v-1.5mX1.8m)	(2v-1.5mX1.8m) 0.00	8,030,225	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	1,059,123	Main
	Part-A: Re-excavation of Sukti Khal	5.10	5,501,658	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Construction of Closure (4mX6m)	0.00	16,340	Main
	Part-C: Construction of Reference Lined Section	0.00	71,526	Main
Puthia				
SSWRDSP-1				
SP14184, Bhalukgachi Nandanpur WCS Subproject, WC, Union : Bhalukgachi, HO Date:				
	Bhallukgachi Khal Re-excavation	5.58	2,911,051	Main
	WRS at Ch.4+400m	3-V(1.5mX1.5m)	2,583,141	Main
SP14185, Barapakhia WCS Subproject, WC, Union : Jeopara, HO Date: 30/12/2003				
	Barapakhia Khal Re-excavation	2.00	231,458	Main
	WRS at Ch.0+000m	3-V(1.2mX1.5m)	1,380,393	Main
SSWRDSP-2				
SP25188, Maria Beel Nondanpur Subproject, DR&WC, Union : Baneshwar, HO Date:				
	WRS on Maria Beel Khal at Ch. 0+110Km	4 Vent-1.5mX1.8m 0.00	3,642,255	Main
	Re-excavation of Maria Beel Khal	6.20	1,532,040	Main
	Re-excavation of Maria Beel Branch Khal	0.80	69,234	Main
PSSWRSP				
SP41011, Noapara-Hazirdhara Beel Subproject, DR&WC, Union : Bhalukgachi, HO Date:				
	Re-excavation of Haridara Khal	0.00	0	Main
	Part A: Re-excavation of Pachanipara Khal	1.87	1,229,666	Main
	Part A: Pachinpara Khal WRS	2V-1.5mX1.8m 0.00	6,541,127	Main
	Part B: Pachinpara Khal Box Culvert	2V-4.0mX5.0m 0.00	3,042,115	Main
	Part C: WMCA Office & Related works	12mX6m 0.00	979,503	Main
Tanore				
SSWRDSP-1				
SP13094, Pachandar WCS Subproject, WC, Union : Pachandar, HO Date: 28/12/2003				
	Part-A: Construction of WMCA Office & others	12mX6m 0.00	1,015,544	PSSWRSP
	Pachandar khal re-excavation(ch.7600-9500m)	1.90	7,038,364	SSSWDRP
	Pachandar branch khal re-excavation(ch.00-400m)	0.40	1,848,008	SSSWDRP
	Referenced line section(3nos)	0.00	213,663	SSSWDRP
	Bamboo bridge(2nos)	0.00	112,310	SSSWDRP
	Plantation of tree(2500nos)	0.00	231,840	SSSWDRP
	Khal Re-excavation	4.24	1,241,179	Main
	Branch Khal Re-excavation	1.20	558,348	Main
	Khal Re-excavation(Lower Reach)	1.40	544,589	Main
	Pachandar Khal Re-excavation	7.60	1,742,017	Main
	WRS at Ch.0+000m	4-V(1.5mX3.3m)	3,348,450	Main
	WRS at Ch.3+800m	3-V(1.5mX2.8m)	2,679,976	Main
	WRS at Ch.5+600m	2-V(1.5mX2.8m)	1,965,261	Main
SP13095, Malbandha WCS Subproject, WC, Union : Kalma, HO Date: 30/04/2004				
	Malbandha(Sec.1) Khal Re-excavation	0.84	317,290	Main
	Malbandha Khal(Sec.2)Re-excavation	3.00	1,055,043	Main
	Khal Re-excavation(Bed widening)	4.00	970,840	Main
	WRS	4-V(1.5m Bay)	4,087,962	Main
SP14179, Dhamdhum-Mohammadpur DR & WCS Subproject, WC, Union : Badhair, HO				
	Khal Re-excavation(Sec. 2)	5.25	1,216,148	Main
	Khal Re-excavation(Sec. 1)	4.00	1,544,845	Main
	Khal Widening	9.30	2,722,781	Main
	WRS at Ch.2+850m	8.0m X 2.5m	1,587,757	Main
SP14212, Khagrakandar-Moinpur DR & WCS Subproject, DR&WC, Union : Badhair, HO				
	Khal Re-excavation(Sec. 1)	11.60	3,071,932	Main
	Khal Re-excavation(Sec. 2)	1.80	689,760	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP15243, Bankeshor-Nabutala DR & WCS Subproject, DR&WC, Union : Kamargaon, HO	Khal Re-sectioning	12.60	3,625,087	Main
	WRS at Ch.0+200m	9.8m X 2.8m	2,308,834	Main
	Khal Re-excavation	4.60	2,586,346	Main
	WRS at Ch.0+000m	20.0m X 2.0m	4,607,092	Main
SP15244, Joranpur-Hamirpur Khal DR & WCS Subproject, DR&WC, Union : Saranjai, HO	Joranpur-Hamirpur Khal Re-excavation	4.60	576,510	Main
	WRS at Ch.0+050m	12.0m X 2.3m	2,003,862	Main
SSWRDSP-2				
SP22024, Hatisal Ghritakanchan Subproject, DR&WC, Union : Kalma,Kamargaon, HO				
	Hatisal-Ghritakanchan Khal Re-excavation	2.20	6,094,311	Main
	WRS-1 at Ch.0+200 km	1-V(14.00mX2.50m) 0.00	2,897,324	Main
	WRS-2/1 at Ch.7+500 km	1 Bay 10.00mX2.00m 0.00	662,182	Main
	WRS-2/2 at Ch.17+700 km	1 Bay-8.00mX2.00m 0.00	659,607	Main
	Part-A: Construction of WMCA Office & others	12mX6m 0.00	1,016,000	PSSWRSP
	Part-A: Re-excavation of Hatisal-Gritakanchan khal	1.90	1,786,188	PSSWRSP
SP23070, Banial-Elamdahi Khal Subproject, DR&WC, Union : Panchadhar, HO Date:				
	Banial-Elamdahi Khal Re-excavation	3.43	827,750	Main
	Banial-Elamdahi WRS at Ch. 1+600 Km (Khal)	1 Bay-8.0mX2.0m 0.00	2,040,506	Main
	O&M Shed	Size: 12mX6m 0.00	317,241	Main
	Part-A: Construction of Weir	(1-Bay 8.0m x 2.0m) 0.00	3,342,558	PSSWRSP
	Part-B: Re-excavation Banial-Elamdahi Khal	1.50	1,345,636	PSSWRSP
Sirajganj (Total SPs : 15 Nos.)				
Belkuchi				
SSWRDSP-1				
SP12025, Chandi Beel FCD Subproject, FCD, Union : Belkuchi, HO Date: 10/12/2000				
	Embankment Re-sectioning	2.01	1,628,702	Main
	Chandi Khal Re-excavation	0.90	232,092	Main
	Pipe Sluice	1-V(1000mm Dia)	68,648	Main
	Chandi Regulator	2-V(1.2mX1.8m)	2,918,932	Main
Kazipur				
SSWRDSP-1				
SP13080, Natuapara FCD Subproject, FCD, Union : Natuapara, HO Date: 25/10/2000				
	Embankment Re-sectioning	6.53	5,526,776	Main
	Sumanta Kumar Saha	1.57	66,022	Main
	Natuapara Regulator	1-V(1.5mX1.8m)	1,555,824	Main
Shajadpur				
SSWRDSP-2				
SP23101, Bachra Beel Subproject, FMD, Union : Porzona, HO Date: 13/04/2010				
	Bachra Khal Regulator at Ch.0+120 Km	2 Vent-1.50mX1.80m 0.00	4,613,631	Main
	Porjona Pipe Sluice at Ch. 6+912 Km (Embkt.)	1 Vent-0.90m dia 0.00	1,691,706	Main
	Nandalalpur Pipe Sluice at Ch. 2+550 Km (Embkt.)	1 Vent-0.90m dia 0.00	1,650,471	Main
	O&M Shed	9.00mX5.00m 0.00	315,771	Main
Tarash				
SSWRDSP-1				
SP14151, Mohisluti Baro Beel DR Subproject, DR, Union : Naogaon,Magura Binod, HO				
	Mohisluti Baro Beel khal re-excavation(ch.00-5615m)	5.62	9,765,765	SSSWRDP
	Referenced line section(6nos)	0.00	212,807	SSSWRDP
	Bamboo Bridge(6nos)	0.12	396,852	SSSWRDP
	Mohisluti Khal Re-excavation	5.47	398,772	Main
SP14183, Horisona-Kundol WCS Subproject, DR&WC, Union : Baruhash, HO Date:				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: Re-excavation of Kundoil Main khal to kata khal(bra	0.50	620,375	PSSWRSP
	Part-B: Re-excavation of Sanduria Main khal to H/O Sailul	0.35	235,041	PSSWRSP
	Part-C: Re-excavation of Kharkharia Main khal to bindopur	1.13	775,510	PSSWRSP
	Part-D: Re-excavation of Berkhali Main khal to Manikchapp	1.50	543,574	PSSWRSP
	Harisona Kundoil khal re-excavation(ch.2000-6700m)	4.70	8,702,072	SSSWRDP
	Referenced line section(5 nos)	0.00	154,241	SSSWRDP
	Bamboo bridge(5nos)	0.00	251,340	SSSWRDP
	Harisona Kundoil khal re-excavation(ch.00-2000m)	2.00	6,588,600	SSSWRDP
	Khal Re-excavation	22.35	4,677,687	Main
	WRS at Ch.0+050m	1-V(15.75mX1.2m	1,396,589	Main
	WRS at Ch.6+650m	1-V(12.90mX1.2m	1,153,080	Main
	WRS at Ch.12+000m	1-V(9.60mX1.2m)	1,075,757	Main
	O&M Shed		231,420	Main
SP15241, Duar-Nimaichara DR & WCS Subproject, DR&WC, Union :				
	Duar-Nimaichara khal re-excavation	2.10	4,569,540	SSSWRDP
	Referenced line section	0.00	117,535	SSSWRDP
	Khal Re-excavation	5.55	1,127,523	Main
	WRS at Ch.0+050m	3 bay 3.0m	1,089,870	Main
PSSWRSP				
SP42020, Ulushi Khal Subproject, DR&WC, Union : Tarash,				
	Part-A: Ulshi khal WRS	2V-1.5mx2.0m 0.00	6,870,749	Main
	Part-B: WMCA office & others	12mx6m 0.00	1,931,507	Main
	Part-A: Re-excavation of Ulshi khal	4.80	7,307,217	Main
	Part-B: Re-excavation of Ulshi Branch khal-1	0.45	147,575	Main
	Part-C: Re-excavation of Ulshi Branch khal-2	0.40	205,566	Main
SP43036, Bhadrabari South (Baruhash Khal) Subproject, DR, Union : Baruhas., HO Date:				
	Part-A: Re-excavation of Bhadraboti (south) khal	14.30	27,279,789	Main
	Part-A: Construction of WMCA office & others	12mx6m 0.00	1,612,949	Main
SP43037, Bhadrabati Khal (North) Subproject, DR, Union : Talom, Baruhas., HO Date:				
	Part-A: Re-excavation of Bhadraboti khal (North)	13.00	13,993,773	Main
	Part-A: Construction WMCA office & others	12mx6m 0.00	1,649,328	Main
SP44137, Nimaichara-Wapda khal Subproject, FMD, Union : Tarash, Magura., HO Date:				
	Part-A: Construction of 25.0m Bridge Over Nimaichara W;	0.00	11,607,520	Main
	Part-B: Construction of WMCA Office & others	12mX6m 0.00	1,515,644	Main
	Part-A: Re-excavation of Nimaichara Wapda Khal	10.90	8,016,564	Main
	Part-B: Construction of Reference Lined Section	0.00	295,244	Main
Ullapara				
SSWRDSP-1				
SP13063, Barahar FCD Subproject, FCD, Union : Barahar, HO Date: 03/04/2002				
	Embankment Re-sectioning	4.69	2,128,423	Main
	Embankment Re-sectioning	0.68	303,276	Main
	Barahar Khal Re-excavation	0.68	175,039	Main
	Barahar Regulator	1-V(1.5mX1.5m)	1,639,153	Main
SP13089, Dahapara-Goyhatta FCD Subproject, FCD, Union : Purnimagati, HO Date:				
	Embankment Re-sectioning	4.81	2,530,918	Main
	Embankment Rehabilitation(Sec. 1)	0.07	35,368	Main
	Embankment Rehabilitation(Sec. 2)	1.58	468,892	Main
	Khal Re-excavation	1.40	255,820	Main
	Regulator-1	1-V(1.5mX1.5m)	1,606,300	Main
	Regulator-2	1-V(1.5mX1.5m)	1,604,870	Main
SP15239, Puthia-Falia FCD Subproject, FCD, Union : Purnimagati, HO Date: 28/07/2004				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Embankment Re-sectioning	10.19	3,956,150	Main
	Khal Re-excavation	1.94	109,436	Main
	Regulator at Ch. 1+760m	2-V(1.2mX1.5m)	1,662,439	Main
	Regulator at Ch. 4+830m	1-V(1.2mX1.5m)	1,248,938	Main
	Regulator at Ch. 9+450m	1-V(1.2mX1.5m)	1,660,341	Main
PSSWRSP				
SP43061, Bhagalpur-Montala Subproject, FMD, Union : Durganagar, HO Date: 12/12/2013				
	Part-C: Resectioning of Embankment	13.50	25,600,962	Main
	Part-C: Modification of Existing Monohara Khal Bridge	4V-1.5mx1.8m 0.00	7,636,709	Main
	Part-D: WMCA Office & Others	12mx6m 0.00	1,349,990	Main
	Part-B: Re-excavation of Monohara Khal	1.60	808,541	Main
	Part-A: Re-excavation of Kalikandhaha Khal	3.25	299,789	Main
	Part-A: Modification of Existing kalikadhaka khal Box Culve	6V-1.5mx1.8 0.00	30,234,229	Main
	Part-B: Modification of Bahadgara Khal Box Culvert	4V-1.5mx1.8m 0.00	2,214,110	Main
SP45145, Naimuri Alidah Subproject, DR&WC, Union : Salonga, Ramkrishnapur, HO Date:				
	Part-A: Construction of Vengri Box Sluice (1v-1.2mX1.2m)	(1v-1.2mX1.2m) 0.00	0	Main
	Part-B: Construction of Mollapara Box Sluice (1v-1.2mX1.2	(1v-1.2mX1.2m) 0.00	0	Main
	Part-C: Construction of palisading	0.00	0	Main
	Part-D: Construction of WMCA office & others	12mX6m 0.00	0	Main
	Part-A: Re-sectioning Embankment (Noruthern Part)	3.87	5,349,214	Main
	Part-B: Re-sectioning Embankment (Southern Part)	3.05	6,266,986	Main
Dinajpur (Total SPs : 31 Nos.)				
Birampur				
SSWRDSP-2				
SP25297, Chiri Khal Subproject, DR&WC, Union : Jotbani, HO Date: 29/05/2012				
	WRS-1 on Chiri Khal at Ch.5+150Km (Khal)	3 Vent-1.5mX1.8m 0.00	4,537,330	Main
	WRS-2 on Chiri Khal at Ch.1+000Km (Khal)	7 Vent-1.5mX1.8m 0.00	9,890,707	Main
	O&M Shed	Size: 9mX5m 0.00	500,656	Main
	Re-excavation of Chiri Khal (Main & Link)	10.00	2,548,932	Main
PSSWRSP				
SP45208, Tulshiganga Khal Sub-project, DR&WC, Union : Deor, HO Date: 16/04/2018				
	Part-A: Construction of WRS (4v-1.5mX2.0m)	(4v-1.5mX2.0m) 0.00	0	Main
	Part-B: Construction of WRS (2v-1.5mX2.0m)	(2v-1.5mX2.0m) 0.00	0	Main
	Part-C: Construction of WMCA Office & others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Tulsiganga Khal	9.10	4,116,142	Main
	Part-B: Construction of Reference Lined Section	0.00	161,823	Main
Birganj				
PSSWRSP				
SP45191, Ghoraband Khal, DR&WC, Union : Paltapur, HO Date: 12/12/2017				
	Part-A: Regulator (3v-1.5mX1.8m)	(3v-1.5mX1.8m) 0.00	11,451,351	Main
	Part-B: Box Culvert (2v-2.0mX2.0m)	(2v-2.0mX2.0m) 0.00	1,380,234	Main
	Part-C: Construction of Drainage outlet dia 600 mm	dia 600 mm 0.00	181,849	Main
	Part-D: WMCA Office & Others	12mX6m 0.00	1,437,938	Main
	Part-A: Re-excavation of Ghoraband Khal	0.41	184,336	Main
	Part-B: Re-Sectioning of Embankment	1.02	572,815	Main
	Part-C: Construction of Reference Lined Section	0.00	0	Main
SP45192, Sanka Moni Beel Subproject, FMD, Union : Paltapur, HO Date: 22/01/2018				
	Part-A: Sanka Moni Khal	0.00	6,649,068	Main
	Part-B: Box Culvert (2v-4mX4m)	(2v-4mX4m) 0.00	2,545,667	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	1,351,350	Main
	Part-A: Re-excavation of Sanka Moni khal	4.10	2,393,185	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Birol SSWRDSP-1 SP14124, Changon Beel DR Subproject, DR, Union : Sahargram, HO Date: 25/06/2002	Part-B: Construction of Reference Lined Section	0.00	113,588	Main
	Earthwork in Ditch Filling	0.03	45,992	Main
	Changon Beel Khal Re-excavation	1.80	241,859	Main
SP15311, Okra Beel DR & WCS Subproject, DR&WC, Union : Sahargram, HO Date:	Changon Beel Regulator at Ch.1+480m	2-V(1.5mX1.8m)	1,634,075	Main
	Embankment Re-sectioning	0.77	116,810	Main
	Loop Cutting	0.35	283,008	Main
PSSWRSP SP44099, Nona River Subproject, DR&WC, Union : 5 No Birol, HO Date: 22/11/2017	Regulator	3-V(1.5mX1.5m)	3,226,214	Main
	Part-A: Construction of Nona WRS	(3v-1.5mx2.0m) 0.00	8,745,014	Main
	Part-B: Construction of 6 Nos. Intel Structure	1V-450mm dia 0.00	320,620	Main
Rubber Dam SP99012, Purnovoba River Dhonnaya Shaharghat Rubber Dam Project, WC, Union : , HO	Part-C: Construction of WMCA Office & others	12mx6m 0.00	1,238,421	Main
	Part-A: Re-excavation of Nona Khal	4.60	4,240,345	Main
	Part-C: Re-sectioning of Dyke on Bogla Khari khal	1.90	603,181	Main
Bochaganj Rubber Dam SP99006, Tangon River Ranirghat Rubber Dam Project, WC, Union : , HO Date:	Part-B: Re-excavation of Bogla Khari Khal	3.00	1,616,930	Main
	Purnovoba River Rubber Dam	Size: 80mX4.5m 0.00	124,525,000	Main
	Tangon River Ranirghat Rubber Dam	Size: 100mX4.5m 0.00	111,585,000	Main
Chirirbandar SSWRDSP-1 SP14127, Ghoramara Beel FCD Subproject, FCD, Union : Bhail, HO Date: 15/04/2003	Narail Khal Regulator	Size: 2 Vent-1.5mX1.8m 0.00	6,840,000	Main
	Sath Pukur Khal Regulator	Size: 2 Vent-1.5mX1.8m 0.00	5,314,000	Main
	Bel Dangi Khal Regulator	Szi: 1 Vent-1.5mX1.8m 0.00	3,606,000	Main
Rubber Dam SP98001, Kakra River Rubber Dame Project, WC, Union : Purba Shaitara, HO Date:	Sherail Khal Regulator 1	Size: 1 Vent-1.5mX1.8m 0.00	2,826,000	Main
	Sherail Khal Regulator 2	Size: 1.5mX1.8m 0.00	2,782,000	Main
	Re-excavation of Canal U/S of Rubber Dam	0.00	1,732,000	Main
Kaharole SSWRDSP-1 SP11001, Purba Sadipur-Sundarpur FC Subproject, FCD, Union : Sundarpur, HO Date:	Kakra River Rubber Dam	Size: 130mX4m 0.00	89,561,000	Main
	Chirir Khal River Rubber Dam	Size: 15mX3.5m 0.00	13,501,000	Main
	Embankment Re-sectioning	8.94	2,329,270	Main
Nawabganj SSWRDSP-2 SP25282, Kabulipara Subproject, FMD, Union : Mahmudpur, HO Date: 10/04/2011	Bakpur Regulator	1-V(1.5mX1.5m)	731,246	Main
	Pipe Culvert at Ch. 0+330m	2-V(900mm Dia)	220,928	Main
	Kabulipara Regulator at Ch. 0+370Km (Khal)	Size: 3 Vent-1.5mX1.8m 0.00	7,679,091	Main
	Re-sectioning of Embankment from Moharajpur Bazar	6.56	1,428,139	Main
	Re-excavation of Kabulipara Khal	2.05	730,878	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	O&M Shed	Szie: 9.0mX5.0m 0.00	645,857	Main
	Re-excavation Kabulipara Br. Khal	0.39	93,397	Main
PSSWRSP				
SP44129, Treemony Subproject, DR&WC, Union : Salkuria, HO Date: 18/12/2017				
	Part-A: Construction of Tikhur Khal WRS	0.00	7,416,158	Main
	Part-B: khuri Khari Khal WRS	0.00	4,399,884	Main
	Part-C: Remodelling of Jisgari khal Box Culvert as WRS	0.00	4,195,640	Main
	Part-D: Construction of WMCA Office & Others	12mX6m 0.00	1,492,099	Main
	Part-A: Re-excavation of Tikur Khal	5.13	4,275,773	Main
	Part-B: Re-excavation of Kurir khari Khal	2.60	1,522,497	Main
	Part-C: Re-excavation of Jiagari Khal	1.67	721,687	Main
	Part-D: Construction of Reference Lined Section	0.00	142,840	Main
SP44140, Purba Joydebpur-Kach Daha Majipara, DR&WC, Union : Binornagar, HO Date:				
	Part-A: Modification of existing Singrir khal Bridge into Gate	(3v-1.5X1.8m) 0.00	7,524,255	Main
	Part-C: Re-excavation of Majipara khal	1.18	766,792	Main
	Part-D: Re-sectioning of Embankment	5.20	5,959,932	Main
	Part-E: Construction of Reference Lined Section	0.00	64,447	Main
	Part-B: Modification of existing Ragharendrapur khal Bridg	(4v-1.5X1.8m) 0.00	8,216,850	Main
	Part-C: Modification of existing Majipara khal Box Culvert i	(6v-1.2X1.2m) 0.00	4,623,398	Main
	Part-D: Modification of existing Voterpara 2v pipe Culvert ii	(2v-1.2mX1.2m) 0.00	803,522	Main
	Part-E: Modification of existing Voterpara 1v pipe Culvert ii	(1v-1.2mX1.2m) 0.00	475,956	Main
	Part-F: Proposed Regulator (1v-1.2mX1.2m)	(1v-1.2mX1.2m) 0.00	2,267,533	Main
	Part-G: WMVA office & others	12mX6m 0.00	1,210,161	Main
	Part-A: Re-excavation of Singrir khal	0.03	475,888	Main
	Part-B: Re-excavation of Ragharendrapur Itapara khal	1.70	1,105,332	Main
SP46244, Tulshi Timohini Subproject, DR&WC, Union : Bhaduria, Salkuria, HO Date:				
	Part-A: Tulshiganga Khal WRS-01	(4v-1.50mX2.0m) 0.00	0	Main
	Part-B: Tulshiganga Khal WRS-02	(3v-1.50mX2.0m) 0.00	0	Main
	Part-C: Irrigation pacca Drain-01 & pacca Drain-02	245m 0.00	0	Main
	Part-D: Construction of WMCA office and others	0.00	0	Main
	Part-A: Re-excavation of Tulshiganga Khal	14.46	0	Main
	Part-B: Re-excavation of Maguria Khal	2.76	0	Main
	Part-C: Re-excavation of Tikur Khal	1.77	0	Main
	Part-D: Construction of reference lined section	0.00	0	Main
SP46266, Nalshisha Subproject, DR&WC, Union : Binodnagar, HO Date: 20/04/2018				
	Part-A: Construction of WRS (6v-1.5mX2.0m)	(6v-1.5mX2.0m) 0.00	0	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Nalshisha Khal	10.40	12,202,953	Main
	Part-B: Construction of Reference Lined Section	0.00	372,987	Main
Parbatipur				
SSWRDSP-1				
SP14126, Amulia Khal WCS Subproject, WC, Union : Chandipur, Manmathpur, HO Date:				
	Amulia Khal Re-excavation	6.90	1,927,580	Main
	Amulia Khal WRS at Ch.0+100m	3-V(1.5mX2.0m)	2,587,059	Main
SP15257, Charolkathi Beel FCD Subproject, FCD, Union : Chandipur, HO Date:				
	Charolkathi Khal Re-excavation	2.05	302,715	Main
	Regulator at Ch.0+115m	2-V(1.5mX1.8m)	1,748,051	Main
SSWRDSP-2				
SP24149, Hatibandha Beel Subproject, DR&WC, Union : Rampur, HO Date: 23/09/2008				
	Re-excavation of Singimari / Sekura Khal	4.00	1,818,014	Main
	Basupara WRS at Ch.2+000 Km (Khal)	6 vent-1.5mX1.8m 0.00	6,832,514	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Chandradanga WRS-2 at Ch. 5+874 Km (Khal)	4 Vent-1.5mX2.0m 0.00	4,059,101	Main
	O & M Shed	Size: 12.0mX6.0m 0.00	471,307	Main
SP25273, Talai River Subproject, WC, Union : , HO Date: 20/03/2011				
	Re-excavation of Telai Khal	4.50	3,301,602	Main
	Telai Weir & WRS at Ch. 2+250Km	2 Bay 9mX2m with 4 Vertical	11,301,984	Main
SP25274, Bangalipur-Jalkar Khal Subproject, DR&WC, Union : Palashbari, HO Date:				
	Re-excavation of Jalkar Khal	3.20	807,057	Main
	Jalkar Khal WRS at Ch. 1+400Km	3 Vent-1.5mX1.8m 0.00	4,509,226	Main
Phulbari SSWRDSP-1				
SP13055, Banhar-Kismat FCD Subproject, FCD, Union : Khayerbari,Daulatpur, HO Date:				
	Embankment Re-sectioning	2.54	332,488	Main
	Re-excavation of Khal-1	1.14	141,546	Main
	Re-excavation of Khal-2	0.69	141,902	Main
	Re-excavation of Khal-3	0.57	187,872	Main
	Regulator at Ch.8+465m	3-V(1.5mX1.8m)	4,138,440	Main
	Regulator at Ch.6+000m	2-V(1.5mX1.5m)	2,735,238	Main
	Regulator at Ch.0+430m	1-V(1.5mX1.5m)	2,517,314	Main
	Pipe Sluice at Ch.1+033m	1-V(900mm Dia)	455,000	Main
	Rehabilitation of Culvert at Ch. 7+400m	2-V(1.0mX1.5m)	97,225	Main
SSWRDSP-2				
SP25287, Akhira Khari Khal Subproject, DR&WC, Union : Eluari, HO Date: 25/05/2012				
	Re-excavation of Akhira Khari Khal	6.90	1,788,544	Main
	Akhira Khari Regulator at Ch. 0+278Km	Size: 4 Vent-1.5mX1.8m 0.00	8,447,708	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	530,743	Main
	Damodarpur WRS at Ch.4+440Km	Size: 3 Vent-1.5mX1.8m 0.00	3,655,189	Main
PSSWRSP				
SP44118, Tilai Khal Subproject, DR&WC, Union : Shibnagar, HO Date: 20/12/2017				
	Part-A: Construction of Tilai Khal	(5v 1.50mX2.0m) at	24,357,994	Main
	Part-B: Construction of WMCA Office & others	12mX6m 0.00	1,367,606	Main
	Part-A: Re-excavation of Tilai Khal	8.80	4,252,317	Main
	Part-B: Construction of Reference Lined Section	0.00	150,433	Main
Sadar SSWRDSP-1				
SP13053, Chalk Gopal FCD Subproject, FCD, Union : Shankarpur, HO Date: 15/01/2001				
	Khal Re-excavation	2.85	309,802	Main
	Chalk Gopal Regulator	5-V(1.17mX1.5m)	3,045,000	Main
SP13096, Purba Mohonpur FCD Subproject, FCD&WC, Union : Shankarpur, HO Date:				
	Khal Re-excavation	10.73	1,603,389	Main
	Purbo Mohonpur Regulator	4-V(1.5mX1.8m)	2,597,000	Main
	Utrail Regulator	1-V(1.2mx1.2m)	1,077,625	Main
	Purbo Mohonpur Regulator(Additional)	3-V(1.5mX1.8m)	2,283,487	Main
SP13100, Dhanigram-Sundarban FCD Subproject, FC, Union : Sundarban, HO Date:				
	Embankment Re-sectioning	4.38	1,342,089	Main
	Embankment Rehabilitation	0.03	52,249	Main
	Regulator at Ch.0+100	2-V(1.5mX1.8m)	2,563,263	Main
	O&M Shed		268,083	Main
	Pipe Sluice at Ch.1+662	1-V(600mm Dia)	581,500	Main
SSWRDSP-2				
SP25214, Joydevpur-Dhigan Beel Sub-project, FMD&WC, Union : Shekpura, HO Date:				
	Re-sectioning of Embankment	0.39	727,697	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Joydevpur-Dirghan Pipe Sluice at Ch.0+434Km(Embkt)	1 Vent-0.90m 0.00	2,070,984	Main
	Borodara Khal Regulator at Ch.0+240Km(Khal)	6 Vent-1.5mX1.8m 0.00	14,006,635	Main
	Re-excavation of Borodara Khal	4.10	369,578	Main
	Re-excavation of Chotodara Khal	3.65	697,500	Main
PSSWRSP				
SP41001, Nimai Khari Subproject, WC, Union : Ashkarpur, HO Date: 20/02/2014				
	Part-A: Nimai Khari WRS	7 Vent-1.5mX2.5m 0.00	11,083,209	Main
	Part-B: Nimai Khari Khal Road Crossing Box Culvert	3 Vent-4.5mX4.5m 0.00	3,552,018	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	854,137	Main
	Part-A: Re-excavation of Nimai Khari Khal	8.37	3,514,707	Main
Rubber Dam				
SP99002, Atrai River Purba Mohanpur Rubber Dam Project, WC, Union : , HO Date:				
	Atrai River Purba Mohanpur Rubber Dam Project	Size:135mX4.5m 0.00	152,009,000	Main
	Protective Work of Emankmant	Size: 135m Length 0.00	23,106,000	Main
Gaibandha (Total SPs : 15 Nos.)				
Gobindaganj				
SSWRDSP-1				
SP15338, Chatianchura DR Subproject, DR, Union : Kamdia, HO Date: 11/12/2002				
	Chatianchura Khal Re-excavation	6.60	1,639,090	Main
	O&M Shed		0	Main
PSSWRSP				
SP43035, Goalkandi-Daturbari Khal Subproject, FMD, Union : Rajahar, HO Date:				
	Part-A: Re-excavation of Goalkandi Daturbari Khal	5.30	7,635,423	Main
	Part-B: Reference Lined Section	0.00	425,991	Main
	Oart-B: WMCA office & others	12mx6m 0.00	1,461,247	Main
	Part-A: Goalkandi Daturbari Regulator	3V-1.5mx1.8m 0.00	10,105,946	Main
SP44113, Jhiry Bridge-Jangalpara Khal, FMD, Union : Shapmara, HO Date: 06/09/2017				
	Part-A: Construction of Jhirai Bridge-Jangalpara Khal WRS	(4v 1.50Mx2.0M) 0.00	12,977,580	Main
	Part-B: Construction of WMCA Office	12mX6m 0.00	1,426,238	Main
	Part-A:Re-excavation of Jhirai Bridge -Janglapara Khal	6.68	5,960,215	Main
	Part-B: Construction of Reference Lined Section	0.00	165,822	Main
SP44130, Purendar Vushan Chandrer Bari- Sharbeser Ghat, DR&WC, Union : Shapmara,				
	Part-A: Construction of Naya Khal WRS (4V 1.5mX1.8m)	(4V 1.5mX1.8m) 0.00	9,453,522	Main
	Part-B: Box Culvert	0.00	3,896,246	Main
	Part-C: Construction of WMCA Office & Others	12mX6m 0.00	1,427,341	Main
	Part-A: Re-excavation of Naya Khal	4.10	3,773,106	Main
	Part-B: Construction of Reference Lined Section	0.00	123,217	Main
SP45184, Oran Bridge Bundighi Khal Subproject, DR&WC, Union : Kamdia, HO Date:				
	Part-A: Oran Bridge WRS (2v-1.5mX1.80m) at Ch. 0+370 k	(2v-1.5mX1.80m) 0.00	0	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Oran Br.khal & Reference Lined S	2.10	2,367,979	Main
SP46255, Dewanhat Sluice gate Subproject, DR, Union : Mahimagonj, HO Date:				
	Part-A: construction of WMCA Office and others	12mX6m 0.00	1,440,899	Main
	Part-A: Re-excxavation of Nuruler khal	4.70	6,045,449	Main
	Part-B: Construction of Reference Lines Section	0.00	171,900	Main
Palasbari				
PSSWRSP				
SP44116, Nakai Beel Subproject, DR&WC, Union : Harinathpur, HO Date: 14/05/2018				
	Part-A; Construction of Alisar khal WRS	(2v1.5mX2.0m) 0.00	0	Main
	Part-B: Construction of WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Alisar Khal	1.50	394,019	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-B: Re-excavation of Alisar Khal	1.00	413,779	Main
	Part-C: Construction of Reference lined Section	1.50	22,789	Main
Sadullapur PSSWRSP	SP41004, Chakgobindapur-Aldadpur Subproject, DR&WC, Union : Faridpur, HO Date:			
	A: Re-excavation of Chakgobindapur-Aldadpur Khal	2.20	718,823	Main
	Part A: Modification of Existing Box Culvert	At Ch. 1+600 km (Khal) 0.00	2,583,246	Main
	Part B: Construction of Box Culvert	1V-4.0mx3.9m 0.00	1,729,081	Main
	Part C: WMCA Office & Related works	12.0mx6.0m 0.00	1,251,415	Main
Shaghata SSWRDSP-1	SP15280, Padumshahar FCD Subproject, FCD, Union : Padumsahar, HO Date:			
	Embankment Re-sectioning	2.55	1,204,033	Main
	Khal Re-excavation	0.11	21,065	Main
	Regulator at Ch.0+410m	1-V(1.5mX1.8m)	1,786,025	Main
	O&M Shed		244,422	Main
SP15318, Holdia FCD Subproject, FCD, Union : Guridah,Jummerbari,Shughatta, HO Date:				
	Embankment Re-sectioning	4.50	1,648,451	Main
	Holdia Regulator	2-V(1.5mX1.8m)	2,310,442	Main
	O&M Shed		244,400	Main
SSWRDSP-2	SP23092, Pachabasta-Tenachira Subproject, DR&WC, Union : Muridah, HO Date:			
	Kalapani Khal Re-excavation	6.39	851,000	Main
	Kalpani Khal WRS at Ch.1+695km (Khal)	8 Vent-1.50mX1.80m 0.00	9,137,000	Main
PSSWRSP	SP43054, Mafizan Subproject, DR&WC, Union : Padumsahar, HO Date: 21/07/2017			
	Part-A: Re-excavation of Mofizan khal	0.28	164,795	Main
	Part-B: Resectioning of Embankment	3.58	3,124,877	Main
	Part-B: Rehabilitation of Existing Culvert	0.00	1,637,160	Main
	Part-C: Construction of WMCA office & others	12mx6m 0.00	1,441,530	Main
	Part-A:Mofizan khal regulator	4V-1.5mx1.8m 0.00	3,202,087	Main
SP43055, Dholdholia Subproject, FMD, Union : Bonarpara, HO Date: 19/05/2016				
	Part-A: Re-Sectioning of Dholdholia Embankment	4.71	8,038,430	Main
	Part-A: Alai river Regulator	0.00	6,484,539	Main
	Part-B: WMCA office & others	12mx6m 0.00	1,404,533	Main
SP45182, Nilkuthi-Bhangamore FCD Subproject, DR&WC, Union : Bharatkhal, HO Date:				
	Part-A: Sankibhanga Regulator (1v-1.50mX1.80m) at Ch. 0	(1v-1.50mX1.80m) 0.00	3,405,558	Main
	Part-B: Pick Culvert-1 (1v-1500mm dia) at Earthen Spour-3	(1v-1500mm dia) 0.00	1,245,651	Main
	Part-C: Pick Culvert-2 (1v-1500mm dia) at Earthen Spour-2	(1v-1500mm dia) 0.00	1,215,892	Main
	Part-D: WMCA Office & Others	12mX6m 0.00	1,277,110	Main
	Part-A: Re-excavation of Sankibhanga Khal & Reference Li	0.40	285,918	Main
	Part-B: Re-sectioning of Embankment	2.51	6,459,754	Main
Sundarganj SSWRDSP-1	SP11002, Langa Khal FCD Subproject, FCD&WC, Union : Bamandanga,Chaprahati, HO			
	Part-A: Re-excavation of Langa Khal	6.45	0	SSWRDP-JICA-2
	Part-B: Construction of Reference Lined section	0.00	0	SSWRDP-JICA-2
	Langa Khal Re-excavation	11.90	1,393,158	Main
	Khal Re-excavation	22.75	6,895,205	Main
	Duniakura WRS	4-V(1.5m bay)	2,328,902	Main
	Bamandanga Regulator	3-V(1.5mX1.8m)	2,371,200	Main
	Repair Work of Duniakura WRS		580,803	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	O&M Shed		243,424	Main
Kurigram (Total SPs : 15 Nos.)				
Bhurungamari SSWRDSP-1 SP12013, Boldia FCD Subproject, FCD&WC, Union : Boldia, HO Date: 08/07/2004				
	Embankment Re-sectioning(Sec-1)	3.40	1,237,817	Main
	Embankment Re-sectioning(Sec-2)	2.92	1,302,846	Main
	Boldia Regulator	2V(1.5mx1.8m)	2,182,239	Main
	Pipe Culvert at Ch.2+125m	3-V(900mm Dia)	73,459	Main
SP12039, Bango Sonahat FCD Subproject, FCD, Union : Bongo Sonahat, HO Date:				
	Embankment Re-sectioning	4.93	1,945,342	Main
	Embankment Re-sectioning(damaged)	0.92	552,524	Main
	Approach Embankment	0.10	158,473	Main
	Mora Shankosh Regulator	4-V(1.5mx1.8m)	3,527,284	Main
	Fish Screen at Mora Shankosh Regulator		50,757	Main
SP15262, Char Bhurungamari FCD Subproject, FCD, Union : Char Bhurungamari, HO				
	Embankment Re-sectioning	8.25	2,985,411	Main
	Khal Re-excavation	0.18	40,563	Main
	Regulator at Ch.6+465	1-V(1.5mX1.8m)	2,565,476	Main
	Pipe Sluice at Ch.8+125m	1-V(1000mm Dia)	928,152	Main
Nageswari SSWRDSP-1 SP13045, Kedar FCD Subproject, FC, Union : Kedar,Kushakathi, HO Date: 26/06/2004				
	Embankment Re-sectioning	4.95	862,397	Main
	Pipe Sluice	1-V(900mm Dia)	412,630	Main
	Pipe Sluice	2-V(900mm Dia)	625,515	Main
	Pipe Sluice at Ch.2+900m	1-V(900mm Dia)	567,014	Main
SP13098, Sonai Khamar FCD Subproject, FC, Union : Raiganj, HO Date: 26/06/2004				
	Khal Re-excavation	1.80	230,254	Main
	Sonai Khamar Regulator	1-V(1.5mX1.8m)	1,839,133	Main
	Neparpuchi Beel Pipe Sluice	1-V(900mm Dia)	977,586	Main
SP14189, Indragar FCD Subproject, FCD, Union : Kachakata, HO Date: 28/06/2004				
	Embankment Re-sectioning(Part-A)	4.40	1,667,884	Main
	Embankment Re-sectioning(Part-B)	3.74	1,902,137	Main
	Embankment Re-sectioning(Part-B1)	1.04	209,924	Main
	Katakhali Khal Re-excavation	0.45	16,485	Main
	Indragar Khal Re-excavation	0.60	102,230	Main
	Regulator at Ch. 2+144m	1-V(1.2mX1.2m)	1,875,281	Main
	Regulator at Ch. 1+939m	4-V(1.5mX1.8m)	3,735,558	Main
Rajibpur SSWRDSP-1 SP15250, Naya Char FCD Subproject, FCD, Union : Mohonganj, HO Date: 12/04/2005				
	Embankment Re-sectioning	3.62	2,367,938	Main
	Tupa Khal Regulator at Ch.1+273m	3-V(1.5mX1.8m)	3,616,881	Main
SP15292, Balamari FCD Subproject, FCD, Union : Char Rajibpur, HO Date: 14/05/2005				
	Embankment Re-sectioning	4.30	4,421,589	Main
	Regulator at Ch.0+205m	2-V(1.5mX1.5m)	3,386,946	Main
	Pipe Sluice at Ch.2+376m	1-V(900mm Dia)	662,500	Main
Rowmari SSWRDSP-1 SP15263, Dantbhanga FCD Subproject, FCD, Union : Dantbhanga, HO Date: 15/07/2004				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Embankment Re-sectioning	11.96	5,265,170	Main
	Datbhanga Regulator	2-V(1.5mX1.8m)	3,005,180	Main
SSWRDSP-2				
SP21010, Jhagrar Char Subproject, FMD, Union : Dantbhanga, HO Date: 20/05/2007				
	Jesmin Kura Regulator at Ch.0+720 km	2-V(1.50mX1.80m) 0.00	2,514,592	Main
	Pipe Sluice at Ch.2+380 km	1-V(1.20m Dia.) 0.00	962,471	Main
	Pipe Sluice at Ch.5+050 km	1-V(0.90m Dia.) 0.00	708,575	Main
	Embankment Re-sectioning	6.20	4,153,225	Main
SP22037, Boalmari Subproject, FMD, Union : Saulmari, HO Date: 16/01/2008				
	Embankment Re-sectioning	11.03	3,965,573	Main
	Majhipara Regulator at Ch.0+650 km	3-V(1.50mX1.80m) 0.00	6,219,779	Main
	Boalmari Regulator-1 at Ch.4+905 km	1-V(1.50mX1.80m) 0.00	3,671,168	Main
	Boalmari Regulator-2 at Ch.7+280 km	1-V(1.50mX1.80m) 0.00	2,832,911	Main
	O&M Shed	12.00mX6.00m 0.00	431,048	Main
	Boalmari Khal Re-excavation	0.65	172,365	Main
SP24127, Fouzdari Subproject, FMD, Union : Bandber & Rowmari, HO Date: 10/06/2008				
	Rehabilitation of Fouzdari Regulator	1 Vent-1.5mX1.8m 0.00	254,690	Main
	Re-sectioning of Embankment	5.70	1,552,874	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	276,012	Main
SP25189, Sonavori Subproject, FMD&WC, Union : Dantbhanga, Rowmari, HO Date:				
	Re-sectioning of Embankment	7.80	2,004,930	Main
	Rehabilitation of Existing Regulator	4 Vent-1.5mX1.8m 0.00	1,005,773	Main
	O&M Shed	Size:9mX5m 0.00	245,356	Main
SP25311, Dhanar Char Subproject, FMD, Union : Jadur Char, HO Date: 04/01/2011				
	Re-sectioning of Embankment	9.85	6,641,895	Main
	O&M Shed	Size: 9mX5m 0.00	426,739	Main
	Rehabilitation of Komorbhanga Regulator at Ch. 11+	1Vent-1.2mX1.8m 0.00	236,256	Main
	Rehabilitation of Komorbhanga Pipe Culvert	1 Vent-0.9m Dia Pipe 0.00	553,369	Main
	Rehabilitation of Dhonar Char Pipe Culvert	2 Vent-1.5m dia Pipe 0.00	753,213	Main
	Rehabilitation of Dhonar Char Regulator	1 Vent-1.5mX1.8m 0.00	280,543	Main
	Part-A: Re-sectioning of Dhanar Char Embankment	8.14	0	SSWRDP-JICA-2
Rubber Dam				
SP99004, Jinjiram River Rubber Dam Project, WC, Union : , HO Date:				
	Jinjiram River Rubber Dam	Size: 85.0mX4.0m 0.00	155,804,000	Main
	Bikri Khal Regulator	Size: 2 Vent-1.5mX1.8m 0.00	8,127,000	Main
	Resectioning of Embankment	3.70	5,439,000	Main
	Re-excavation of Khal	1.56	512,000	Main
Lalmonirhat (Total SPs : 7 Nos.)				
Aditmari				
SSWRDSP-2				
SP24120, Charali Beel-Shakhowa Khal Sub-Project, DR&WC, Union : Shaptibari, HO Date:				
	Re-excavation of Charali Beel-Shakhowa Khal	4.80	559,213	Main
	Shakhowa Khal WRS at Ch.0+948	3 Vent-1.5mX1.8m 0.00	3,059,620	Main
PSSWRSP				
SP41006, Bhelabari Durgapur Subproject, WC, Union : Velabari, Durgapur, HO Date:				
	Part-B: Ratna Rubber Dam Connecting Bridge	31.0mx3m 0.00	2,750,541	Main
	Part-A: Rubber Dam with Pump house and WMCA Office	L=30.0m 0.00	42,554,328	Main
	Part-C: Construction of Bridge Approach Road	0.00	1,711,854	Main
Hatibandha				
SSWRDSP-1				
SP14159, Nawdabash-Banchuki WCS Subproject, WC, Union :				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Khal Re-excavation	6.55	1,803,577	Main
	WRS at Ch.5+810m	4-V(1.5mX1.8m)	2,958,220	Main
Rubber Dam				
SP99009, Shania Jan Rubber Dam Project, WC, Union : Barakhata, HO Date:				
	Shania Jan Rubber Dam	Size: 100mX4m 0.00	132,605,000	Main
	WAPDA Khal Regulator (East Bank)	Size: 2 Vent-1.5mX1.8m 0.00	8,023,000	Main
	WAPDA Khal Regulator (West Bank)	Size: 2 vent-1.5mX1.8 0.00	7,482,000	Main
	Tengjara Khal Regulator (West Bank)	Size: 2 Vent-1.5mX1.8m 0.00	7,151,000	Main
	Inlet/Outlet	18.60m Length (7 nos.) 0.00	703,000	Main
	Protective Work of River	size: 1910m 0.00	2,564,000	Main
Kaliganj				
SSWRDSP-2				
SP22017, Bakhari Khal Subproject, FMD, Union : Votmari, HO Date: 12/06/2006				
	Rehabilitation of Regulator at Ch.2+694 km	4-V(1.90mX1.93m) 0.00	442,226	Main
	O&M Shed	12.00mX6.00m 0.00	0	Main
Patgram				
Rubber Dam				
SP99011, Dhorla River Rubber Dam Project, WC, Union : , HO Date:				
	Dhorla River Rubber Dam	Size: 130mX3.5m 0.00	174,435,000	Main
	Regulator	Size: 1 Vent-1.5mX1.8m 0.00	4,540,000	Main
	6 nos. Inlet/outlet and 300 U-Drain	L = 300m U-Drain 0.00	3,461,000	Main
Sadar				
SSWRDSP-2				
SP24166, Khorerpul Sarkertari Subproject, DR&WC, Union : Moghalhat, HO Date:				
	Re-excavation of Sabrikhana Khal	4.20	251,071	Main
	Sabrikhana Khal WRS at Ch. 1+350Km	4 Vent-1.50mX1.8m 0.00	3,898,952	Main
Nilphamari (Total SPs : 11 Nos.)				
Dimla				
SSWRDSP-1				
SP13084, Chhatnai WCS Subproject, WC, Union : Bokaora,Chhatnai, HO Date:				
	Embankment Re-sectioning	2.00	221,151	Main
	Approach Embankment	0.90	92,331	Main
	Chhatnai WRS	2-V(1.5mX1.5m)	1,859,646	Main
	Protective Works for Embankment		412,689	Main
	Relief Culvert	1-V(3.0mX2.2m)	1,025,276	Main
	O&M Shed		229,805	Main
SSWRDSP-2				
SP24162, Miapara Ultabhanga Khal Subproject, WC, Union : Purba Chhatnai, HO Date:				
	Re-excavation of Miapara Ultabhanga Khal	5.50	1,361,000	Main
	Weir-1 at Ch. 0+900Km (Khal)	1 Bay-25.0mX1.8m 0.00	5,771,335	Main
	Weir-2 at Ch. 3+000Km (Khal)	1 Bay-15.0mX1.8m 0.00	4,045,086	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	364,812	Main
	Part-A: -Construction of Downstrem protection work of Mia	0.00	3,999,270	PSSWRSP
Domar				
SSWRDSP-1				
SP13064, Dhardura FCD Subproject, FCD&WC, Union : Harinchara,Domar,Lakmichapa,				
	Embankment Re-sectioning	0.21	161,967	Main
	Khal Re-excavation	2.70	343,639	Main
	Dhardura Regulator	2-V(1.5mX1.5m)	1,359,763	Main
	Embankment Protection Works		831,458	Main
SP13065, Haridara WCS Subproject, WC, Union : Jorabari,Ketakibari, HO Date:				
	Approach Embankment-1 Re-sectioning	0.50	86,220	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Approach Embankment-2 Re-sectioning	0.20	115,508	Main
	Khal Re-excavation	1.65	178,299	Main
	Khal Re-excavation(Loop Cutting)	0.45	51,254	Main
	Haridara WRS	2-V(1.5mX1.5m)	1,755,338	Main
	Culvert	2-V(3.0mX2.2m)	1,069,318	Main
	Protective Works for Haridara WRS		86,220	Main
	O&M Shed		264,683	Main
SP13083, Upper Chilahati WCS Subproject, WC, Union : Bhogdabari,Letonari, HO Date:				
	Embankment Re-sectioning	3.90	100,255	Main
	Khal Re-excavation	2.91	403,397	Main
	Upper Chilahati WRS	3-V(1.5mX1.8m)	1,738,144	Main
SP13085, Lower Chilahati WCS Subproject, WC, Union : Ketakibari, HO Date: 05/01/2004				
	Approach Embankment Re-sectioning	0.20	610,235	Main
	Culvert Approach Re-sectioning	0.10	246,146	Main
	Khal Re-excavation	5.01	564,117	Main
	Lower Chilahati Khal Re-excavation(Sec 1)	0.45	184,218	Main
	Lower Chilahati Khal Re-excavation(Sec 2)	3.60	584,720	Main
	Lower Chilahati WRS	5-V(1.5mX1.8m)	2,792,475	Main
	Culvert	3-V(3.0mX3.0m)	1,160,964	Main
	Protective Works for Approach Embankment		87,571	Main
SP15269, Haridara-Chekardara DR & WCS Subproject, DR&WC, Union : Boragari,Jorabari,				
	Chekardara Khal Re-excavation	7.15	1,042,470	Main
	WRS at Ch. 6+950m	6-V(1.5mX2.2m)	3,326,372	Main
Sadar				
SSWRDSP-1				
SP14216, Motiarbeel Ramkala WCS Subproject, WC, Union :				
	Khal Re-excavation	3.30	314,941	Main
	Motiar Beel-Ramkala Khal Re-excavation	4.50	153,778	Main
	WRS at Ch.1+170m	2-V(1.5mX2.0m)	1,519,986	Main
SP15305, Dhobadanga-Neechpara DR & WCS Subproject, DR&WC, Union : Gorgram, HO				
	Dhobadanga Khal Re-excavation	6.60	2,560,149	Main
	WRS at Ch.2+700m	2-V(1.5mX1.8m)	1,402,906	Main
	WRS at Ch.5+700m	3-V(1.5mX1.8m)	2,337,229	Main
SSWRDSP-2				
SP25224, Chawra Beel Subproject, DR&WC, Union : Chawra, Palashbari, Gorgram &				
	Chawra Khal WRS at Ch.9+520Km	3 Vent-1.5mX2m 0.00	2,287,281	Main
	Re-excavation of Chawra Khal	15.09	750,000	Main
	Re-excavation of Chawra Branch Khal-2	1.14	0	Main
	O&M Shed	Size: 9mX5m 0.00	305,102	Main
SP25306, Vendir Dhola Subproject, FMD, Union : Laksmichap, HO Date: 07/02/2010				
	Re-excavation of Vendir Dola Khal	0.67	222,336	Main
	Vendir Dola Regulator	3 Vent-1.5mX1.8m 0.00	6,099,778	Main
	O&M Shed	Szie: 9.0mX5.0m 0.00	401,415	Main
	Re-sectioning of Right Approach Embankment	0.34	308,367	Main
	Re-sectioning of Left Approach Embankment	0.50	206,208	Main
Panchagar (Total SPs : 13 Nos.)				
Atwari				
SSWRDSP-1				
SP13086, Baro Singia WCS Subproject, WC, Union : Alowakhawa, HO Date: 30/04/2002				
	Khal Re-excavation	3.29	833,227	Main
	WRS	5-V(1.5mX1.8m)	2,887,940	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP13087, Rosheya Canal WCS Subproject, DR&WC, Union : Mirzapur, HO Date:				
	Khal Re-excavation	2.74	245,762	Main
	Rosheya Khal Re-excavation	0.22	68,460	Main
	WRS	3-V(1.5mX1.8m)	2,164,278	Main
	Relief Culvert	2-V(3.0mX1.45m)	699,574	Main
SSWRDSP-2				
SP21004, Paharbhanga Subproject, WC, Union : Taria, HO Date: 06/08/2006				
	Petki Khal WRS at Ch.0+000m	4-V(1.50mX2.00m) 0.00	4,481,403	Main
	Box Culvert	1-V(1.00mX1.00m) 0.00	296,011	Main
	Petki Khal Re-excavation	1.95	444,911	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	258,003	Main
Debiganj				
SSWRDSP-2				
SP24136, Fulbari-Sekhbandha Subproject, WC, Union : Chillahati, HO Date: 28/07/2009				
	Teesta Weir at Ch. 11+288 Km	1 Bay-50.0mX2.0m 0.00	9,749,295	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	244,978	Main
	Re-sectioning of Fulbari-Sheikbandha Sluice Gate D	1.70	2,128,468	Main
	Part-A: Construction of RCC Lined Canal	0.00	2,082,878	PSSWRSP
Sadar				
SSWRDSP-1				
SP12034, Kuchiamur-Talmachaspara WCS Subproject, WC, Union : Kamat Kazal Dighi,				
	Embankment Re-sectioning	0.10	55,966	Main
	Mama-Bhagna Khal Re-excavation	4.02	506,498	Main
	WRS at Ch.0+500m	4-V(1.2mX2.1m)	2,090,874	Main
	WRS at Ch.1+900m	2-V(1.5mX1.8m)	1,158,715	Main
	Protective Works of WRS		814,457	Main
SP14210, Beer Bundh WCS Subproject, WC, Union : Satmara, HO Date: 06/07/2004				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,489,970	PSSWRSP
	Chilka Khal Re-excavation	1.05	28,181	Main
	Chilka Khal WRS at Ch.0+050m	4-V(1.5mX2.0m)	2,006,430	Main
SP14211, Moharani Bundh WCS Subproject, WC, Union : Magura, Garinabari, HO Date:				
	Part-A: Construction office & Others	12mX6m 0.00	1,484,970	PSSWRSP
	Tangon River Re-excavation	7.00	1,522,279	Main
	WRS	8-V(1.5mX2.0m)	6,071,636	Main
SSWRDSP-2				
SP24155, Chaklahat Subproject, WC, Union : Chaklahat, HO Date: 16/09/2009				
	Chaklahat Weir with 2 Vertical Gates at Ch0+500Km	1Bay-30mX1.8m with	8,399,185	Main
	O&M Shed	Size:12mX6m 0.00	322,023	Main
	Part-A: Enhancement of Chaklahat weir	0.00	2,163,777	PSSWRSP
	Part-B: Construction of Closure Dam (Lenght-35m)	(Lenght-35m) 0.00	1,949,296	PSSWRSP
PSSWRSP				
SP44141, Kashimpur Bundh-Bazrapara Subproject, DR&WC, Union : Hafizabad, HO Date:				
	Part-A: Sinhpara Bundh WRS	(7v-1.5mX2.0m) 0.00	0	Main
	Part-B: Kashimpur Khal WRS	(8v-1.5mX2.0m) 0.00	0	Main
	Part-C: WMCA Office & Others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Kashimpur & Reference Lined Se	1.06	101,399	Main
	Part-B: Re-sectioning of Kashimpur Embankment	1.00	207,473	Main
SP44142, Borka Khal Subproject, DR&WC, Union : Hafizabad, HO Date: 12/03/2018				
	Part-A: Borka khal WRS	8v-1.5mX2.0m 0.00	18,737,018	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	1,359,778	Main
	Part-A: Re-excavation of Borka Khal	6.50	3,378,698	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Rubber Dam SP98007, Talma Rubber Dam Project, WC, Union : , HO Date:	Part-B: Construction of Reference Lined Section	0.00	102,353	Main
	Talma River Rubber Dam	Size: 50mX4m 0.00	54,529,000	Main
	Tetulia SSWRDSP-1 SP13061, Versa WCS Subproject, WC, Union : Burabari, HO Date: 05/07/2004			
	Approach Embankment	1.46	407,053	Main
	Versa WRS	4-V(1.5mX1.8m)	4,661,149	Main
SP13062, Berung River WCS Subproject, WC, Union : Tentulia,Salbahan, HO Date:	Approach Embankment	1.02	139,515	Main
	Berung WRS	25.0mX2.0m	9,795,457	Main
	O&M Shed		268,035	Main
Rangpur (Total SPs : 12 Nos.)				
Mithapukur SSWRDSP-1 SP12036, Gilajhuki Beel FCD Subproject, FCD&WC, Union : Chengmari, HO Date:	Gilajhuki Khal Re-excavation	4.50	311,457	Main
	Gilajhuki Regulator	2-V(1.5mX1.5m)	1,352,695	Main
	O&M Shed		0	Main
SP14150, Veluar Beel FCD Subproject, FCD, Union : Balua Masimpur, HO Date:	Veluar Beel Khal Re-excavation	1.90	766,083	Main
	Regulator	2-V(1.5mX1.8m)	2,954,034	Main
SP15245, Paschim Barabala FCD Subproject, FCD, Union : Barabala, HO Date:	Embankment Re-sectioning	4.50	771,565	Main
	Taraf Bahadi Regulator at Ch.4+150m	1-V(1.2mX1.2m)	1,517,005	Main
	Baragharia Pipe Sluice at Ch.2+962m	1-V(900mm Dia)	717,725	Main
SP15246, Banderpara-Chatra Beel WCS Subproject, WC, Union : Gopalpur, HO Date:	Khal Re-excavation	5.88	316,992	Main
	Chatra Beel WRS at Ch.5+250m	8-V(1.5mX1.8m)	2,994,830	Main
SP15247, Nauerpukur-Mayenpur WCS Subproject, WC, Union : Moyenpur, HO Date:	Balua Khal Re-excavation	5.27	841,926	Main
	Chadya Sukhi Khal Re-excavation	1.57	100,530	Main
	Balua WRS	1-V(1.5mX2.0m)	1,650,492	Main
SP15248, Emadpur-Padmapukur DR Subproject, DR, Union : Emadpur, HO Date:	Emadpur-Padmapukur Khal Re-excavation	10.08	2,572,548	Main
	Bara Makim WRS	4-V(1.5mX1.8m)	3,305,917	Main
SSWRDSP-2				
SP25207, Hialer Beel Subproject, FMD, Union : Milonpur, HO Date: 19/03/2009	Re-excavation of Hialer Beel Khal	1.00	158,590	Main
	Re-sectioning of Embankment	7.20	3,261,983	Main
	Regulator on Hialer Beel Khaat Ch. 0+860Km (Khal)	2 Vent-1.5mX1.8m 0.00	3,940,247	Main
	O&M Shed	Size: 9mX5m 0.00	312,698	Main
	River Ptoection Works	Length=165.00m 0.00	624,996	Main
	Part-A: Re-sectioning of Protection of Embankment	At ch. 0+000 km to 0+165 km	1,045,111	PSSWRSP
	Part-B: Re-sectioning of Embankment	2.78	2,016,342	PSSWRSP
SP25321, Harol Beel Subproject, FMD, Union : Milonpur, HO Date: 25/10/2010	Re-excavation of Harol Beel Khal	1.00	257,377	Main
	Re-sectioning of Embankment	7.56	5,462,622	Main
	Haroler Nala (Khal) Regulator at Ch.0+080Km (Khal)	Size: 2Vent-1.5mX1.8m 0.00	6,345,398	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Pipe Sluice at Ch.5+345Km (Khal)	Size: 3 Vent-0.9m Dia 0.00	1,868,426	Main
	O&M Shed	Size: 9mx5m 0.00	517,740	Main
	River Bank Protection (6 nos. of Spours)	0.00	439,708	Main
PSSWRSP				
SP43071, Bokrabari Subproject, DR&WC, Union : Barabala, HO Date: 27/12/2016				
	Part-B: Re-sectioning of Embankment	3.70	4,964,029	Main
	Part-A: Re-excavation of Machhaper Nala	0.25	176,420	Main
	Part-A: Construction of Regulator	2v-1.2mx1.5m 0.00	7,487,385	Main
	Part-B: WMCA office & others	12mx6m 0.00	1,238,525	Main
SP44092, Faridpur Badurerjan Subproject, FMD, Union : Barabala, HO Date: 13/09/2017				
	Part-B: Re-Sectioning of an Embankment	3.86	3,543,211	Main
	Part-A: Construction of Regulator at the outfall of Badurer J	at Ch. 0+150 km 0.00	3,459,173	Main
	Part-A: Re-excavation of Faridpur -Badurer Jan Khal	0.38	55,989	Main
	Part-B: WMCA Office & Others	12mx6m 0.00	1,369,816	Main
Pirgacha				
SSWRDSP-1				
SP12035, Nakdah-Alaikumari WCS Subproject, WC, Union : Parul, HO Date: 17/01/2004				
	Embankment Re-sectioning	1.79	444,706	Main
	Nakdah Khal Re-excavation	1.01	145,227	Main
	Alaikumari Khal Re-excavation	1.16	106,741	Main
	WRS cum Bridge	6-V(1.5mX2.0m)	5,403,252	Main
Pirganj				
SSWRDSP-1				
SP13097, Moranadi WCS Subproject, DR&WC, Union : Chitrakole, HO Date: 14/10/2002				
	Khal Re-excavation	4.15	429,596	Main
	WRS	2-V(3.0mX5.15m)	2,673,444	Main
	Culvert Rehabilitation at Ch.0+850m		107,583	Main
Thakurgaon (Total SPs : 15 Nos.)				
Baliadangi				
SSWRDSP-1				
SP14191, Chochpara-Belhara WCS Subproject, WC, Union : Bara Palasbari, HO Date:				
	Part-A: WMCA Office & Others	12mX6m 0.00	1,328,231	PSSWRSP
	Chochpara WRS	5-V(1.5mX1.8m)	1,746,840	Main
SSWRDSP-2				
SP24183, Beorjari-Amandhaman Khal Subproject, DR&WC, Union : Amjankhore, HO				
	Re-excavation of Amandhaman Khal	11.10	3,285,639	Main
	WRS at Ch 3+500Km (Khal)	7 Vent-1.5mX1.8m 0.00	6,152,230	Main
	Rehabilitation of WRS at Ch 8+910Km(Khal)	4 Vent-1.5mX1.8m 0.00	869,987	Main
	O&M Shed	Size: 12mX6m 0.00	230,114	Main
	Re-sectioning of Approach Embankment of 7 Vent WRS	0.20	273,740	Main
	Earthfilling in the open area of O&M Shed	0.00	38,948	Main
PSSWRSP				
SP45146, Chotoshingia-Goalkari Subproject, DR&WC, Union : Charol, HO Date:				
	Part-A: Construction of Choto Singia -Goalkari Khal Weir	(1-BAY 14.00mX2.00m) 0.00	11,841,529	Main
	Part-B: Construction of Choto Singia -Goalkari Khal WRS	(4v-1.5mX2.0m) 0.00	12,182,290	Main
	Part-C: WMVA Office & Others	12mX6m 0.00	1,071,116	Main
	Part-A: Re-excavation of Choto Singia -Goalkari Khal	7.32	6,522,999	Main
	Part-B: Re-excavation of Levee Khal	0.70	1,340,282	Main
	Part-C: Construction of Reference Lined Section	0.00	121,137	Main
Haripur				
PSSWRSP				
SP45149, Kishoree Beel Subproject, DR&WC, Union : Gedhura, HO Date: 14/06/2017				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Pirganj SSWRDSP-2 SP24165, Kachna Beel Subproject, WC, Union : Bhomradoha, HO Date: 26/04/2009	Part-A: Kishoree Khal Regulator	(2v-1.5mX1.8m) 0.00	0	Main
	Part-B: WMCA Office & others	12mX6m 0.00	0	Main
	Part-A: Re-excavation of Kishoree Khal	1.95	2,217,416	Main
PSSWRSP SP44110, Bokradara Khal Subproject, DR&WC, Union : Kosha Ranigonj, HO Date:	Re-excavation of Lachhi Khal	4.60	2,165,693	Main
	Lachhi Khal WRS at Ch.3+960Km	7 Vent-1.5mX2.0m 0.00	6,117,200	Main
	O&M Shed	Size: 9.0mX5.0m 0.00	261,223	Main
	8 Nos. Pipe Culvert at Ch.4090Km,4+300Km,4+750Km &	1 Vent-0.9m Dia Pipe Culvert	759,949	Main
SP44122, Kahani Beel Subproject, DR&WC, Union : Sengaon, HO Date: 12/06/2017	Part-A: Construction of Regulator	0.00	7,821,103	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	1,041,640	Main
	Part-A: Re-excavation of Bokradhara Khal	3.70	1,537,357	Main
	Part-B: Construction of Reference Lined Section	0.00	77,768	Main
Rubber Dam SP99010, Tangon Rive Rubber Dam Project, WC, Union : , HO Date:	Part-A: Kahalua River WRS	(9v-1.5m X 1.8m) Ch.0+028	21,685,791	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	1,311,211	Main
	Part-A: Re-excavation of kahalua River	7.60	4,554,137	Main
	Part-B: Re-excavation of Jolui River	2.80	1,979,553	Main
	Part-C: Construction of Reference Lined Section	0.00	114,958	Main
Ranisankail SSWRDSP-1 SP12033, Pamol Beel FCD Subproject, FCD&WC, Union : Dharmagar, HO Date:	Tangon Rive Rubber Dam	Size: 90mX4.5m 0.00	90,895,000	Main
	Regulator on Left Bank of River (U/S)	Size: 1 Vent-1.5mX1.8m 0.00	1,764,000	Main
	Surface Drain	Size: 200m 0.00	426,000	Main
	Re-construction of Embankment	0.00	3,179,000	Main
SP13046, Lehemba FCD Subproject, FCD, Union : Lehemba, HO Date: 31/01/2000	Embankment Re-sectioning	0.20	15,088	Main
	Pamol Khal Re-excavation	0.99	172,278	Main
	Khal Re-excavation	0.30	82,533	Main
	Pamol Regulator	2-V(1.2mX1.8m)	923,427	Main
	Fish Screen at Pamol Regulator		32,888	Main
SP13047, Kashipur WCS Subproject, WC, Union : Dharmagar, HO Date: 08/05/2001	Khal Re-excavation	0.59	152,035	Main
	Lehemba Regulator	5-V(1.5mX1.5m)	2,108,380	Main
	Fish Screen at Lehemba Regulator		60,338	Main
Sadar SSWRDSP-1 SP14128, Angila Khal WCS Subproject, WC, Union : Rajagaon, HO Date: 11/05/2003	Kashipur WRS	1-V(1.5mX1.5m)	1,334,602	Main
	Angila Khal Re-excavation	1.20	38,177	Main
SP14129, Bakamoni WCS Subproject, WC, Union : Ruhea, HO Date: 09/03/2003	Angila Khal WRS at Ch.0+220m	1-V(1.5mX1.5m)	1,072,606	Main
	Syphon under Canal at Ch. 0+150m	1-V(1.5mX1.5m)	456,564	Main
	Bakamoni Khal Re-excavation & Closure	1.20	94,303	Main
	Bakamoni Khal WRS at Ch.0+170m	2-V(1.5mX1.8m)	1,061,519	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP14188, Nawafali WCS Subproject, WC, Union : Akcha, HO Date: 03/04/2003				
	Embankment Re-sectioning	0.77	63,235	Main
	Akcha WRS at Ch.0+530m	1-V(1.5mX1.5m)	916,288	Main
PSSWRSP				
SP44086, Sonnashipara Subproject, WC, Union : Rajagaon, HO Date: 15/06/2017				
	Part-A: Re-excavaion of Khal	0.27	109,826	Main
	Part-A: Construction of Sannashipara khal WRS (1V-1.5mX	(1V-1.5mX1.5m) 0.00	2,809,469	Main
	Part-B: WMCA Office & Others	12mX6m 0.00	1,016,516	Main
Habiganj (Total SPs : 35 Nos.)				
Ajmiriganj				
SSWRDP-JICA				
SP35180, Hirabari-Monsur Khal Subproject, DR&WC, Union : Sibpasa, HO Date:				
	Reexcavation of Hirabari Khal	7.00	2,684,560	Main
	Reexcavation of Monsur Khal	1.80	3,137,810	Main
	Reexcavation of Hukura Khal	1.40	2,144,570	Main
	Reexcavation of Kechura Khal	6.60	12,362,860	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,769,857	Main
	Part-A: Re-excavation of Khechura Khal	3.41	0	SSWRDP-JICA-2
	Part-B: Construction of Reference Lined Section	0.00	0	SSWRDP-JICA-2
Bahubal				
SSWRDSP-2				
SP23063, Sundrateki-Kamai Chhara Subproject, WC, Union : Bhadeshwar, HO Date:				
	Sundrateki Kamaichara WRS at Ch.3+700km (Khal)	8 Vent-1.50mX1.80m 0.00	5,862,407	Main
	O&M Shed	9.00mX5.00m 0.00	301,965	Main
	Re-excavation of Kamaichara Khal	0.50	149,944	Main
	RCC Pipe Culvert	2 nos. 0.00	78,414	Main
	Part-A:- Cons. of RCC Lined Canal	0.00	1,459,125	PSSWRSP
	Part-B:- Improvement of HBB Road	0.00	671,696	PSSWRSP
	Part-C:- Cons. of RCC U-Drain	0.00	56,993	PSSWRSP
SSWRDP-JICA				
SP34150, Dholia Chhara Subproject, WC, Union : Bahubal Sadar, HO Date: 21/04/2016				
	Re-excavation of Dholia Chhara	1.70	3,896,654	Main
	Reference Lined Section (2 nos.)	0.00	101,181	Main
	Part-A; WRS	3V- 1.5mX2.5m, Ch 2+130	8,124,661	Main
	Part-B; WMCA Office and Related Item	0.00	1,457,788	Main
SP35171, Newar Khal Subproject, DR&WC, Union : Snanghat, Putijuri, HO Date:				
	Re-excavation of Newar Khal	4.60	2,453,996	Main
	Re-excavation of Branch Khal-1	1.40	1,680,330	Main
	Re-excavation of Branch Khal-2	1.90	2,118,189	Main
	Re-excavation of Branch Khal-3	1.00	648,596	Main
	Re-excavation of Branch Khal-4	0.41	463,503	Main
	Fish Sanctuary	0.00	242,957	Main
	Part-A: Newar Khal WRS-1 at Ch.1+125Km	2 Vent-1.5mX1.8m 0.00	6,158,782	Main
	Part-B: Newar Khal WRS-2 at Ch.0+800Km	1 Vent-1.5mX1.8m 0.00	1,910,224	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	2,176,689	Main
Baniachang				
SSWRDSP-2				
SP23049, Katiar Bon Subproject, DR&WC, Union : Baroiuri, HO Date: 21/04/2011				
	Saluka Dhayer Khal WRSat Ch.1+812 Km	2 Vent-1.50mX2.0m 0.00	4,326,615	Main
	O&M Shed	9.00mX5.00m 0.00	488,504	Main
	Pilu Khali Khal Khal WRS at Ch.1+031Km	2 Vent-1.5mX2.0m 0.00	4,377,445	Main
	Re-excavation of Saluka Dhayer Khal	1.80	222,260	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Pilu Khali Khal	1.00	430,942	Main
	Construction of RCC Drain Culvert	0.00	823,172	PSSWRSP
	Re-excavation of Pilukhali Khal	0.95	895,621	PSSWRSP
	Re-excavation of Salukadyer khal	1.30	2,208,515	PSSWRSP
	Re-sectioning of Approach road raising both sides of WRS	0.00	193,394	PSSWRSP
SSWRDP-JICA				
SP34127, Borak Khal-Kata Khal (Khagaura) Subproject, DR&IRR, Union : Baroiuri,				
	Re-excavation of Borak Khal	9.00	12,793,791	Main
	Refernece Lined Sections (10nos)	0.00	235,964	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,313,620	Main
SP34134, Protappur-Andhaura Beel Subproject, FMD&WC, Union : Subidpur, HO Date:				
	Resectioning of Protappur Embankment	1.80	3,630,624	Main
	Part-A: Protappur Regulator at Ch.0+430Km (Embkt)	2 Vent-1.5mX1.8m 0.00	7,677,720	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,664,361	Main
	Part-B: Box Sluice at Ch.0+700km(Embk)	1 Vent-1.0mX1.0m 0.00	1,870,802	Main
SP35181, Borak Khal (Pukra) Subproject, DR&IRR, Union : Pukra, HO Date: 05/10/2015				
	Re-excavation of Borak Khal	7.50	14,519,341	Main
	Fish Sanctuary in Bailla Beel	0.00	307,170	Main
	Fish Sanctuary in Dhania Beel	0.00	37,600	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,235,765	Main
SP35192, Tutiar Khal-Chatal Beel Subproject, DR&WC, Union : Mackrumpur, HO Date:				
	Rexcavation of Tutiar Khal	8.58	6,210,417	Main
	Part-B: Renewable Earthfilled WRS at Ch.7+300 Km(Khal)	1 Vent-3mX1.5m 0.00	687,049	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,709,716	Main
Chunarughat				
SSWRDSP-2				
SP24134, Jibdhar Chara Subproject, WC, Union : Ranigaon, HO Date: 31/08/2009				
	Jibdhar Chhara WRS-1 at Ch.0+672km(Km)	2 Vent-1.5mX1.8m 0.00	2,689,934	Main
	Jibdhar Chhara WRS-2 at Ch.1+644km (Khal)	2 Vent-1.5mX1.8m 0.00	2,495,240	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	340,159	Main
	Re-excavation of Jibdhar Chhara	2.33	294,798	Main
	Re-excavation of Khawaitita Chhara	0.80	185,424	Main
SP25266, Kurungi Subproject, WC, Union : Ranigaon, HO Date: 08/08/2010				
	Syphone on Brick Lined Channel-1	28.5m Length 0.00	346,101	Main
	Re-excavation of Khal-1	1.06	60,015	Main
	Re-excavation of Khal-2	0.66	128,300	Main
	Rubber Dam	Size: 25.0mX2.5m 0.00	18,859,241	Main
	Sump-1 for Lined Channel-1	Size:1.6mX1.6m 0.00	22,461	Main
	Sump-2 for Lined Channel-2	Size:1.6mX1.6m 0.00	27,401	Main
	O&M Shed	Size: 9mX5m 0.00	469,389	Main
	Procurement of Rubber Bag	0.00	3,800,000	Main
SP25303, Sutang Chhara Subproject, WC, Union : Ahmedabad, HO Date: 19/03/2014				
	Sutang Chhara WRS-A at Vhhayasree Near Kalam's Hou	3 Vent-1.5mX1.8m 0.00	3,988,082	Main
	Sutang Chhara WRS-B at Kalamondal Near Jalil's Hao	4 Vent-1.5mX1.8m 0.00	5,892,096	Main
	O&M Shed	Size: 9mX5m 0.00	487,781	Main
Lakhai				
SSWRDSP-2				
SP23050, Kufa Beel Subproject, DR&IRR, Union : Bamai, HO Date: 30/08/2009				
	Dalakandi Khal Re-excavation	2.90	2,002,017	Main
	Mandirpalla Khal Re-excavation	3.50	2,342,121	Main
	Nengti Khal Re-excavation	0.60	445,705	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SSWRDP-JICA				
SP32031, Dhanchari Khal Subproject, DR&IRR, Union : Bulla, HO Date: 28/05/2014				
	Re-excavation of Dhanchari Khal	2.10	1,493,753	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,399,279	Main
	Reference Lined Section	0.00	10,015	Main
SP33085, Gajaria Khal Subproject, DR&IRR, Union : Bamai, Lakhai, HO Date: 29/05/2014				
	Reexcavation of Gajaria Khal	4.20	3,400,005	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,399,297	Main
SP33087, Ferani Beel-Shakhati Khal Subproject, DR&IRR, Union : Bulla, HO Date:				
	Reexcavation of Pirali Khal-Shakhati Khal	8.50	6,139,346	Main
	Reference Lined Section (6 nos.)	0.00	37,600	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,404,734	Main
	Reexcavation of Punni Bari Khal	3.80	8,535,210	Main
Madhabpur				
SSWRDP-JICA				
SP34138, Jangal Khal Subproject, DR, Union : Chhatian, HO Date: 28/05/2014				
	Re-excavation of Bogajan Khal	2.35	1,359,102	Main
	Re-excavation of Jangal Khal	1.50	768,274	Main
	Re-excavation of Uttarer Khal	1.90	895,041	Main
	Re-excavation of Jangal Khal Branch-1	0.53	42,354	Main
	Re-excavation of Jangal Khal Branch-2	0.30	19,261	Main
	Reference Lined Sections (7 nos.)	0.00	27,000	Main
	WMCA Office and Related Item	Size:12mX6m 0.00	1,405,678	Main
SP34142, Baksair Beel Subproject, DR, Union : Andhiur, HO Date: 25/05/2014				
	Re-excavation of Baksair Beel Khal	2.60	2,397,387	Main
	Re-excavation of Fish Sanctuary in Baksair Beel	0.00	898,167	Main
	Reference Lined Sections (3 Nos.)	0.00	117,870	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,266,564	Main
SP34143, Boalia-Kamar Khal Subproject, DR&WC, Union : Andhiur, HO Date: 17/09/2015				
	Re-excavation of Boalia Khal	6.60	6,035,887	Main
	Re-excavation of Kamar Khal	1.11	1,026,095	Main
	Re-excavation of Kamar Branch Khal	0.80	601,912	Main
	Reference Lined Sections (5 nos.)	0.00	256,437	Main
	Part-A: Boalia Khal WRS at Ch.1+100Km	3 Vent-1.5mX3.0m 0.00	9,502,466	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,462,791	Main
Rubber Dam				
SP98008, Sonai River Rubber Dam Project, WC, Union : Choumuhani, HO Date:				
	Chowmohoni Rubber Dam	Size: 45mX4m 0.00	26,762,000	Main
	Bohora Rubber Dam	Size: 28mX3m 0.00	16,444,000	Main
Nabiganj				
SSWRDP-JICA				
SP31004, Arua Kalkalia Subproject, WC, Union : Bausha, HO Date: 18/12/2013				
	Re-excavation of Bijakhali Khal	1.40	1,642,265	Main
	Re-excavation of Kalkalia Khal	3.06	3,411,396	Main
	Re-excavation of Kalkalia Gang	1.71	3,450,339	Main
	Part-A: Kalkalia Khal WRS at Ch.0+025Km	3 Vent-1.5mX2.5m 0.00	4,963,720	Main
	Part-B: WMCA Office and Related Items	Size: 12mX6m 0.00	967,768	Main
	Reference Lined Section	0.00	171,736	Main
	Additional E/W for Approach Filling	0.00	847,160	Main
	Additional Work to increase Water Retention Level of Kalka	0.00	4,034,623	Main
	Part-A: Re-excavation of Arua-Kalkalia Khal	3.88	12,620,764	SSWRDP-JICA-2

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP32023, Raiarpur Boro Khal Subproject, FMD&WC, Union : Kurshi, Kargaon, HO Date:	Part-B: Reference Bed Block	0.00	65,034	SSWRDP-JICA-2
	Re-excavation of Boro Khal	5.70	1,502,166	Main
	Additional E/W for Approach Filling	0.00	910,815	Main
	Part-A: Modification of Box Culvert into Gated Str	6 Vent-1.5mX1.8m 0.00	5,726,356	Main
	Part-B: WMCA Office and Related Items	Size: 12mX6m 0.00	1,084,172	Main
	Re-excavation of Radhakharar Khal	0.67	287,299	Main
	Re-excavation of Banderdubi Khal	1.00	153,516	Main
SP33074, Sherpur Katakhal Khal Subproject, DR&WC, Union : Kargaon, HO Date:	Re-excavation of Haldurer Khal	1.50	393,430	Main
	Reexcavation of Jaukara Khal	3.50	3,132,207	Main
	Reexcavation of Dighalia Khal	3.83	4,687,784	Main
	Reexcavation of Katakhal Khal	2.08	1,515,485	Main
	Reexcavation of Erakita Khal	1.87	1,514,201	Main
	Reexcavation of Barukandi Khal	0.90	437,918	Main
	Reference Lined Section (10 nos.)	0.00	166,000	Main
SP34116, Rashukhal Khal Subproject, DR&IRR, Union : Kargaon, HO Date: 05/10/2015	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,416,288	Main
	Reexcavation of Rashukhal Khal	4.50	5,475,036	Main
	Reexcavation of Ramerbari Khal	0.90	949,090	Main
	Reference Lined Sections (6 nos.)	0.00	19,900	Main
SP34123, Muktahar Khal Subproject, DR&WC, Union : Korgaon, HO Date: 20/12/2015	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,678,482	Main
	Re-excavation of Muktahar Khal	4.25	4,660,602	Main
	Re-excavation of Darer Palla Khal	1.40	1,685,960	Main
	Reference Lined Sections (5 nos.)	0.00	154,000	Main
	Part-A: Muktahar Khal WRS at 4+000 Km	3 Vent-1.5mX3.5m 0.00	7,485,949	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,504,276	Main
SP34124, Bara Chhara (Nabiganj) Subproject, WC, Union : Paniumda, HO Date:	Earth Filling of WMCA Office	0.00	182,509	Main
	Part-A: Barachhara WRS at Ch.1+600Km (Khal)	2 Vent-1.5mX2.0m 0.00	5,222,739	Main
	Part-C: Outlet Pipe Regulator-1 at R/B of Khal	1 Vent-0.30m Dia 0.00	323,309	Main
	Part-D: Outlet Pipe Regulator-2 at L/B of Khal	1 Vent-0.30m Dia 0.00	323,309	Main
	Part-E: Outlet Pipe Regulator-3 at L/B of Khal	1 Vent-0.30m Dia 0.00	323,309	Main
	Part-F: Outlet Pipe Regulator-4 at R/B of Khal	1 Vent-0.30m Dia 0.00	323,309	Main
	Re-excavation of Barachhara Khal (Additional)	1.95	1,234,663	Main
	Part-G: WMCA Office and Related Items	Size: 12mX6m 0.00	1,488,280	Main
	Re-excavation of Barachhara Khal	5.30	7,864,322	Main
	Excavation of Fish Refuge	0.00	587,375	Main
	Reference Lined Sections	0.00	123,900	Main
	Part-B: Barachhara Culvert at Ch. 4+100Km (Khal)	2 Vent-4.0mX3.0m 0.00	1,287,573	Main
SP35168, Chandpur-Katerkona Khal Subproject, DR&WC, Union : Kaliar Bhanga, HO	Re-excavation of Chandpur-Katerkona khal	8.25	7,973,949	Main
	Part-A: Katerkona WRS at Ch.3+775Km	2 Vent-1.5mX1.8m 0.00	6,848,004	Main
	Part-D: Rehabilitation of Existing BWDB Regulator	2 Vent-1.8mX1.8m 0.00	603,600	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	1,469,718	Main
	Part-B: Box Culvert-1 at Ch.2+490Km	2 Vent-3.0mX3.0m 0.00	1,946,227	Main
	Part-C: Box Culvert-2 at Ch.4+978Km	2 Vent-2.5mX3.0m 0.00	1,818,886	Main
SP35172, Anowarkhal Khal Subproject, WC, Union : Bausha, Debpara, HO Date:	Re-excavation of Anowarkhal Khal	8.00	4,869,737	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Branch Khal-2	2.30	2,917,903	Main
	Re-excavation of Branch Khal-1	0.35	467,949	Main
	Part-A: Anowarkhali Khal WRS at Ch. 0+050Km	4 Vent-1.5mX2.5m 0.00	10,588,476	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,320,371	Main
Sadar				
SSWRDP-JICA				
SP34135, Morabotai-Longlapur Khal Subproject, DR, Union : Lokra, Richi, HO Date:				
	Re-excavation of Morabotai Langlapur Khal	6.60	9,094,012	Main
	Re-excavation of Okai Khal	4.86	974,418	Main
	Reference Line Sections	0.00	158,369	Main
	Part-A: WMCA Office and Related Item	Size: 12mX6m 0.00	1,235,095	Main
	Re-excavation of Morabotai Langlapur Khal (addll.)	4.18	12,616,750	Main
SP34151, Moti Khal Subproject, DR&WC, Union : Teghoria, Poil, HO Date: 05/03/2015				
	Reexcavation of Moti Khal	3.50	4,919,098	Main
	Reexcavation of Kurer Khal	1.55	2,249,495	Main
	Reference Lined Sections (5 nos.)	0.00	223,791	Main
	Part-A: Moti Khal WRS at Ch.0+060Km	3 Vent-1.5mX2.0m 0.00	8,318,873	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	2,023,716	Main
	Reexcavation of Kamai Khal	2.20	5,180,470	Main
SP35159, Boiragi-Langla Khal Subproject, DR&WC, Union : Gopaya, Richi, HO Date:				
	Re-excavation of Tetoya Khal	2.85	3,118,801	Main
	Part-A: Boiragi Khal WRS	3 Vent-1.5mX2.5m 0.00	8,793,352	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,414,931	Main
	Part-B: Pipe Inlet Structure	1 Vent-0.30m Dia 0.00	426,024	Main
SP35161, Naimullah Khal Subproject, CAD, Union : Laskarpur, HO Date: 05/05/2016				
	Part-A: Header Tank	Size: 6.1mX5.0m 0.00	3,250,138	Main
	Supply of Electric Motor	3 nos. 0.00	1,241,230	Main
	Site Development for WMCA Office	0.00	431,300	Main
	Part-B&D: Buried Pipe Network System	Length= 8.72Km 0.00	17,260,023	Main
	Part-E: Teli Khal WRS	2 Vent-1.5mX2.5m 0.00	6,479,502	Main
	Part-F: WMCA Office and Related Item	Size: 12mX6m 0.00	1,493,460	Main
	Re-excavation of Khal	2.48	999,052	Main
	Reference Lined Sections z(2 nos.)	0.00	11,400	Main
	Part-C: Discharge Box and Khal Pipe Crossing	0.00	183,815	Main
	Part-G: Supply of Accessories of Pump House	0.00	2,022,966	Main
SP35217, Balishwari Khal Subproject, DR&WC, Union : Nurpur, HO Date: 10/03/2016				
	Reexcavation of Baliswari Khal	9.00	2,922,531	Main
	Reexcavation of Someswar Khal	1.75	786,526	Main
	Reexcavation of Akra Khal	0.88	288,298	Main
	Reexcavation of Agarpur Khal	1.08	358,001	Main
	Reexcavation of Harinakona Khal	1.10	86,291	Main
	Reexcavation of Moddamura Khal	0.70	246,537	Main
	Reexcavation of Bisaura Khal	0.70	135,999	Main
	Part-A: Balishwari Khal WRS at Ch.0+500Km	3 Vent-1.5mX2.5m 0.00	10,566,038	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,262,670	Main
SP35220, PerabhangaGhoria Khal Subproject, DR&WC, Union : Rajiura, HO Date:				
	Reexcavation of Perabhanga Khal	3.65	5,050,580	Main
	Reexcavation of Ghoria Khal	1.50	1,744,027	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,603,109	Main
	Part-B: Gorla Khal Regulator by Modification of Existing Bo	2 Vent-1.5mX1.8m 0.00	6,157,613	Main
	Reexcavation of Perabhanga Branch Khal	1.55	8,114,353	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP35233, Shailjura Khal Subproject, DR&WC, Union : Rajiura, HO Date: 24/04/2016				
	Re-excavation of Shailjura Khal	5.50	2,909,779	Main
	Re-excavation of Dogar Barir Khal	1.10	632,169	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,404,434	Main
	Part-A: Shaljura Khal WRS at Ch.0+100Km (Khal)	2 Vent-1.5mX2.0m 0.00	5,573,641	Main
Moulavibazar (Total SPs : 33 Nos.)				
Baralekha SSWRDP-JICA				
SP34154, Dhal Chhara Subproject, WC, Union : Dakshinkag (S), HO Date: 22/12/2015				
	Reexcavation of Dhal Chhara	3.13	1,227,009	Main
	Reference Lined Section (4 nos.)	0.00	209,478	Main
	Part-A: WRS at Ch.1+160Km	3 Vent-1.5mX3.3m 0.00	9,252,765	Main
	Part-B: WRS at Ch.2+700Km	3 Vent-1.5mX2.3m 0.00	6,425,025	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,613,292	Main
SP35169, Dew Chhara Subproject, FMD&WC, Union : Nij Bahadurpur, Dakshin				
	Reexcavation of Munshir Khal	2.14	3,378,244	Main
	Reexcavation of Khamari Khal	3.25	2,340,075	Main
	Part-A: Munshir Khal Regulator	5 Vent-1.5mX1.8m 0.00	18,662,843	Main
	Part-B: Chhatur Khal WRS	3 Vent-1.5mX2.0m 0.00	10,411,797	Main
	Part-D: Rehabilitation of Dew Chhara WRS-1	2 Vent-1.4mX1.5m 0.00	1,136,666	Main
	Part-F: WMCA Office and Related Item	0.00	1,511,712	Main
	Bank Raising of Dew Chhara	0.50	168,010	Main
	Part-C: Dew Chhara WRS-2	2 Vent-1.5mX2.2m 0.00	6,217,224	Main
Juri SSWRDP-JICA				
SP34120, Baraitali-Sagornal-Somai Khal Subproject, DR&WC, Union : Goalbari, Sagarnal,				
	Part-A: Somai Khal WRS at Ch.2+815Km	5 Vent-1.5mX2.3m 0.00	10,822,162	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,557,969	Main
	Re-excavation of Somai Khal	3.70	2,380,829	Main
	Re-excavation of Iroli Khal	2.70	953,863	Main
	Re-excavation of Mora Somai Khal	0.65	654,451	Main
	Reference Lined Sections (7 nos.)	0.00	519,265	Main
	Re-excavation of Puti Chhara Khal	4.00	4,599,225	Main
SP34140, Saran Ray Nala Subproject, FMD&WC, Union : Paschim Juri, HO Date:				
	Reexcavation of Saran Ray Nala	8.10	14,237,534	Main
	Part-C: WRS-1 at Ch.0+100Km (Khal)	3 Vent-1.5mX2.00m 0.00	8,098,945	Main
	Part-D: Hinanghat WRS-2	3 Vent-1.5mX2.00m 0.00	7,012,541	Main
	Part-E: Box Sluice-1 at Ch.5+400Km (Khal)	1 Vent-1.2mX1.2m 0.00	3,092,680	Main
	Part-F: Box Sluice-2 at Ch.6+030Km (Khal)	1 Vent-1.2mX1.2m 0.00	3,025,668	Main
	Reference Lined Sections	0.00	623,457	Main
	Part-G: WMCA Office and Related Items	Size: 12mX6m 0.00	1,391,974	Main
	Part-A: Regulator-1 at Ch.8+076Km (Khal)	2 Vent-1.5mX1.8m 0.00	8,249,240	Main
	Part-B: Regulator-2 at Ch.4+600Km (Khal)	2 Vent-1.5mX2.00m 0.00	7,925,597	Main
SP34157, Kawli Chhara Subproject, FMD&WC, Union : Purba Juri, HO Date: 21/12/2015				
	Re-excavation of Kawli Chhar	5.30	3,012,028	Main
	Re-sectioning of Road-Embankment	0.90	1,733,097	Main
	Re-excavation of Ratua Chhara	2.50	3,948,124	Main
	Part-A: Kawli Chhara Regulator at Ch.1+405Km	3 Vent-1.5mX2.2m 0.00	9,033,558	Main
	Part-B: WMCA Office & Related Item	Size: 12mX6m 0.00	1,481,000	Main

Rubber Dam

SP98011, Kontinala Nadi Rubber Project, WC, Union : Kontinala, HO Date:

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
Kamalganj SSWRDSP-2 SP22044, Chayakhali Haor Subproject, FMD, Union : Kamalganj, HO Date: 20/07/2009	Kantinala Khal Rubber Dam	Size: 45mX4m 0.00	47,696,000	Main
	Embankment Resectioning	7.55	3,951,713	Main
	Chayakhali Regulator at Ch. 0+340 km	3-V(1.50mX1.80m) 0.00	6,329,771	Main
	Jalai Chara & Mara Jalai Chara Khal Re-excavation	7.30	1,974,019	Main
	O&M Shed	12.00mX6.00m 0.00	318,435	Main
SP24117, Langu Chhara Subproject, FMD&WC, Union : Kamalganj, HO Date: 30/04/2009				
	Langu Chhara Khal WRS at Ch 1+900Km	2 Vent-1.5mX2.0m 0.00	2,697,457	Main
	Langu Chhara Khal Regulator at Ch.0+070Km	3 Vent-1.5mX1.8m 0.00	5,109,997	Main
	Resectioning of Langu Chhara Embankment	8.50	2,458,354	Main
	O&M Shed	Size: 12.0mX6.0m 0.00	294,173	Main
SP24172, Jaffa-Batua Chhara Subproject, FMD&WC, Union : Madhabpur, HO Date:				
	Jaffa Chhara Khal Regulator at Ch. 0+100Km(Khal)	3 Vent-1.5mX1.8m 0.00	5,171,194	Main
	Re-excavation of Batua Chhara	3.15	954,500	Main
	Re-sectioning of Jaffa Batua Embankment	5.02	2,438,530	Main
	Batua Chhara Pipe Sluise at Ch. 2+649Km	1 Vent-0.9m Dia Pipe 0.00	784,719	Main
	O&M Shed	Size: 12mX6m 0.00	264,070	Main
	Jaffa Chhara WRS at Ch. 2+100Km (Khal)	2 Vent-1.5mX1.8m 0.00	2,365,095	Main
SP25248, Lawa Chhara Subproject, WC, Union : Adampur, HO Date: 30/04/2009				
	Re-excavation of Lawa Chhara Khal	4.10	2,541,374	Main
	Lawa Chhara WRS-2 at Ch.2+987Km	4 Vent-1.5mX2m 0.00	5,101,941	Main
	Lawa Chhara WRS-1 at Ch.6+100Km	3 Vent-1.5mX2.0m 0.00	3,840,496	Main
	O&M Shed	Size: 9mX5m 0.00	403,290	Main
SSWRDP-JICA SP32021, Laghata Chhara Subproject, WC, Union : Shamsheer Nagar, HO Date:				
	Part-A: Laghata Chhara WRS	6 Vent-1.5mX2.2m 0.00	8,110,361	Main
	Part-B: WMCA Office and Related Item	Size:12mX6m 0.00	1,004,643	Main
	Re-excavation of Soknia Chhara	2.05	1,719,449	Main
	Reference Lined Section	0.00	28,814	Main
	Laghata Chhara Dyke	3.20	338,132	Main
SP33039, Kurma Chhara Subproject, WC, Union : Islampur, HO Date: 07/05/2015				
	Part-A: Kurma Chhara WRS at 0+880Km (Khal)	5 Vent-1.5mX2.0m 0.00	9,095,542	Main
	Excavation of Irrigation Canal	3.10	855,256	Main
	Kurma Chhara Dyke	1.40	166,845	Main
	Re-excavation of Bagha Chhara Khal i/c dyke	3.70	1,871,515	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	1,170,982	Main
	Part-B: Bagha Chhara WRS by Modification of Culver	4 Vent-1.8mX2.0m 0.00	3,784,303	Main
	Part-C: Inlet Structures at Ch.2+700Km	1 Vent-1.2mX1.2m 0.00	1,059,974	Main
SP33047, Shial Chhara Subproject, FMD&WC, Union : Patan usher, HO Date: 15/09/2015				
	Part-A: Shial Chhara Regulator at Ch.0+030Km	2 Vent-1.5mX1.8m 0.00	6,326,723	Main
	Part-B Jalni Chhara Check Structure at Ch.0+300Km	2 Vent-1.2mX1.5m 0.00	1,952,154	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,287,294	Main
	Re-excavation of Shial Chhara Khal	3.10	1,431,038	Main
	Re-excavation of Jalni Chhara Khal	0.30	198,711	Main
	Reference Lined Section	0.00	73,192	Main
SP33068, Kala Chhara Subproject, FMD&WC, Union : Rahimpur, HO Date: 23/12/2015				
	Part-A: Kala Chhara Regulator at Ch.0+150Km	4 Vent-1.5mX1.8m 0.00	11,419,912	Main
	Re-sectioning of Both Bank Dyke	1.50	520,130	Main
	Part-B: Kala Chhara WRS at Ch. 2+300Km	2 Vent-1.5mX2.0m 0.00	5,028,168	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-C: Majer Chhara WRS at Ch.2+300Km	1 Vent-1.5mX1.8m 0.00	3,345,080	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	911,840	Main
	Re-excavation of Kala Chhara Khal & Re-sectioning	3.00	1,584,017	Main
SP35261, Forkanala Subproject, WC, Union : Rahimpur, Patanusher, HO Date: 19/03/2016				
	Part-A: WRS atr5 Ch.2+168Km	3 Vent-1.5mX2.0m 0.00	4,987,464	Main
	Part-B: WRS atr5 Ch.4+735Km	3 Vent-1.5mX2.2m 0.00	5,626,503	Main
	Re-excavation of Forkanala Khal i/c Reference Bed Block	5.30	11,486,450	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	781,018	Main
Kulaura SSWRDP-JICA				
SP35229, Koularashi Subproject, WC, Union : Kadipur, HO Date: 22/12/2015				
	Part-A: Fanaigang WRS at Ch.2+575Km	2 Vent-1.5mX2.5m 0.00	6,793,182	Main
	Part-B: Outlet Pipe Regulator-1 on L/B of Fanaigang at Ch.	1 Vent-0.30m 0.00	335,730	Main
	Part-C: Outlet Pipe Regulator-2 on R/B of Fanaigang at Ch	1 Vent-0.30m 0.00	335,730	Main
	Part-D: Outlet Pipe Regulator-3 on R/B of Fanaigang at Ch	1 Vent-0.30m 0.00	335,730	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	1,191,374	Main
	Re-excavation of Fanaigang i/c Resectioing of Dyke	8.80	9,636,971	Main
Rajnagar SSWRDSP-2				
SP23080, Udna Chara Subproject, WC, Union : Rajnagar, HO Date: 23/06/2008				
	Udna Chara Khal Re-excavation	3.43	2,665,016	Main
	Udna Chhara WRS at Ch.2+370 Km (Khal)	3 Vent-1.50mX1.80m 0.00	3,385,567	Main
SP24169, Marua Chhara Subproject, WC, Union : Uttarbagn, HO Date: 13/11/2009				
	Marua Chhara WRS at Ch. 1+545Km (Khal)	4 Vent-1.5mx2.0m 0.00	3,823,429	Main
SSWRDP-JICA				
SP35165, Foru Beel Subproject, FMD, Union : Uttarbagn, HO Date: 07/05/2015				
	Part-A: Safar Khal Regulator	1 Vent-1.5mX1.8m 0.00	4,486,899	Main
	Re-sectioning of Embankment	2.40	1,012,172	Main
	Re-excavation of Safar Khali Khal	0.70	223,848	Main
SP35197, Dhameswari Khal Subproject, WC, Union : Uttarbagn, HO Date: 18/01/2016				
	Reexcavation of Mothura Khal	0.80	69,346	Main
	Part-A: Dhameswari WRS-1 at Ch. 0+000Km (Khal)	4 Vent-1.5mX3.8m 0.00	15,279,479	Main
	Part-B: Dhameswari WRS-2 at Ch. 2+010Km (Khal)	4 Vent-1.5mX2.0m 0.00	9,954,882	Main
	Part-C: Outlet Structure (Typical)	1 Vent-0.30m Dia 0.00	737,039	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	1,274,157	Main
	Part-D: Water Supply Pipe Line with Sump and Other Relat	300mm Dia PVC Pipe of	3,130,658	Main
SP35211, Borajan Chhara Subproject, FMD&WC, Union : Kamar Chak, HO Date:				
	Resectioning of Embankment	1.70	2,193,515	Main
	Re-excavation of Borjan Chhara	1.40	1,521,408	Main
	Re-excavation of Borjan Chhara Branch	0.20	55,754	Main
	Part-A: Borajan Chhara Regulator at Ch.0+780 Km (Embkt)	1 Vent-1.5mX1.8m 0.00	6,668,321	Main
	Part-B: Borajan Chhara Culvert Ch.0+790 Km (Embkt)	1 Vent-3.5mX3.5m 0.00	2,111,184	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,200,120	Main
SP35214, Kolima Chhara Subproject, DR&WC, Union : Kamar Chak, HO Date: 07/05/2015				
	Re-excavation of Kolima Chhara including Reference Bed I	3.40	3,291,803	Main
	Part-A: Kolima Chhara WRS-1 at Ch.1+060Km (Khal)	2 Vent-1.5mX2.2m 0.00	7,187,389	Main
	Part-B: Kolima Chhara WRS-2 at Ch.3+470Km (Khal)	1 Vent-1.5mX1.5m 0.00	3,305,898	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,250,059	Main
Sadar SSWRDSP-2				
SP23100, Bager Kiar Baular Beel Subproject, DR&WC, Union : Giasnagar, HO Date:				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Moura Chhara Khal	1.40	227,600	Main
	Re-excavation of Gabur Chhara Khal	2.56	410,866	Main
	Re-excavation of Dewa Chhara Khal	2.10	438,417	Main
	Re-excavation of Alkata Chhara Khal	3.42	881,197	Main
	Dewa Chara WRS at Ch. 1+890 Km (Khal)	2 Vent-1.50mX1.80m 0.00	3,455,551	Main
	Maura Chara WRS at Ch.1+050 Km	2 Vent-1.50mX1.80m 0.00	2,509,764	Main
	Dewa Chara Outlet at Ch. 1+970 Km (L/B of Khal)	1 Vent-0.60m Dia 0.00	126,932	Main
	Dewa Chara Outlet at Ch. 1+970 Km (R/B of Khal)	1 Vent-0.60m Dia 0.00	126,932	Main
SSWRDP-JICA				
SP33058, Lekha Beel Subproject, DR&WC, Union : Kamalpur, HO Date: 03/02/2014				
	Re-excavation of Talir Khal	0.90	146,667	Main
	Re-excavation of Lekha Khal	3.35	1,549,892	Main
	Re-excavation of Kamarkhali Khal	1.80	279,080	Main
	Re-excavation of Chalta Khal	2.56	394,710	Main
	Re-excavation of Puran Khal	0.80	138,897	Main
	Part-B: WMCA Office and Related Items	Size: 12mX6m 0.00	1,725,029	Main
	Part-A: Chalta Khal WRS at Ch.0+050Km (Khal)	3 Vent-1.5mX1.8m 0.00	6,954,376	Main
SP34109, Kachuar Khal Subproject, DR&WC, Union : Kagabola & Nazirabad, HO Date:				
	Part-B: Kachuar Khal WRS-1 at Ch.0+230Km	3 Vent-1.5mX2.1m 0.00	8,385,253	Main
	Part-C: Kachuar Khal WRS-2 at Ch.3+230Km	2 Vent-1.5mX2.1m 0.00	6,741,086	Main
	Part-A: Intake Regulator at Ch.6+125Km	1 Vent-1.5mX1.8m 0.00	6,582,410	Main
	Reference Lined Section	0.00	30,484	Main
	Re-excavation of Kachuar Khal	6.13	4,248,763	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	1,649,727	Main
SP34128, Kodali Chhara Subproject, DR&WC, Union : Mostafapur, HO Date: 21/12/2014				
	Re-excavation of Kodali Chhara Khal	6.80	3,987,487	Main
	Reference Lined Sections (4 nos.)	0.00	15,380	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,432,744	Main
	Re-excavation of Dud Chhara Khal	1.00	268,264	Main
	Re-excavation of Meghna Chhara Khal	1.00	163,419	Main
	Part-A: Kodali Chhara WRS at Ch. 0+250Km	3 Vent-1.5mX2.0m 0.00	7,799,536	Main
SP35246, Andhamanu-Puli Khal Subproject, FMD&WC, Union : Nazirabad, HO Date:				
	Part-A: Andhamanu Khal Regulator at Ch.0+010Km	1 Vent-1.5mX1.8m 0.00	5,557,094	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,228,417	Main
	Re-excavation of Andhimanu Khal including Reference Bec	6.29	7,811,225	Main
	Re-excavation of Khara Khal including Reference Bed Bloc	2.09	2,840,083	Main
	Re-excavation of Suta Kamla Khal	0.90	1,774,099	Main
Rubber Dam				
SP98010, Gopla River Rubber Dam Project, WC, Union : Kagabala, HO Date:				
	Gopla River Rubber Dam	Size: 65mX3.5m 0.00	65,175,000	Main
Sreemongal				
SSWRDSP-2				
SP23046, Bara Chara Subproject, WC, Union : Mirzapur, HO Date: 06/07/2011				
	Re-excavation of Gobar Khal	1.51	216,378	Main
	Diversion Structure on Barachara Khal at Ch. 3+000	8 Vent-1.500mX1.50m 0.00	6,614,221	Main
	O&M Shed	9.00mX5.00m 0.00	328,081	Main
	Rehabilitation of Left Bank Approach of Diversion	0.00	592,678	Main
	Enhancement works of existing	(8 Vent-1.50mx1.50m) 0.00	5,211,941	PSSWRSP
SP23075, Banguachara Subproject, WC, Union : Mirzapur, HO Date: 12/01/2009				
	Bangua Chhara Khal Re-excavation	2.30	513,283	Main
	Bangua Chhara Dyke	0.39	141,389	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SSWRDP-JICA SP33053, Lunglia Chhara Subproject, WC, Union : Sindurkhan, HO Date: 01/07/2015	Bangua Chhara WRS at Ch.1+840 Km (Khal)	2 Vent-1.5mX1.5m 0.00	2,257,238	Main
	Part-A: Lunglia Chhara WRS-1 at Ch.1+450Km	8 Vent-1.5mX2.5m 0.00	14,898,301	Main
	Part-B: Lunglia Chhara WRS-2 at Ch.3+800Km	8 Vent-1.5mX2.5m 0.00	14,623,559	Main
	Part-C: Puskari Chhara Check Structure at Ch.1+600	2 Vent-1.2mX1.8m 0.00	2,378,435	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	1,703,996	Main
	Re-excavation of Puskuri Chhara	2.92	817,221	Main
	Re-excavation of Link Khal	1.50	711,736	Main
SP33101, Jag Chhara Subproject, WC, Union : Srimongol, HO Date: 07/05/2015	Part-D: Intake Regulator at Link Khal Ch.1+400Km	1 Vent-0.30m Dia 0.00	452,274	Main
	Part-A: Jag Chhara WRS at Ch.1+050Km	3 Vent-1.5mX2.5m 0.00	10,053,363	Main
	Part-C: Pucca Supply Canal	Length = 1115m 0.00	5,144,842	Main
	Part-E: WMCA Office and Related Item	Size: 12mX6m 0.00	1,473,532	Main
	Re-excavation of Akhalakhi Chhara	1.20	325,468	Main
	Re-excavation of Supply Canal i/c Dyke	1.21	1,381,943	Main
	Part-B: Akhalki Chhara Check Structu at Ch.1+200Km	1 Vent-1.5mX1.5m 0.00	2,347,001	Main
Rubber Dam SP99008, Longla River Rubber Dam Project, WC, Union : , HO Date:	Part-D: Khai Chhara Check Structure	1 Vent-1.5mX1.3m 0.00	1,407,435	Main
	Longla River Rubber Dam	Size: 28mX4m 0.00	56,562,000	Main
	2 Vent Regulator	Size: 2 Vent-1.5mX1.8m 0.00	3,200,000	Main
	Embankment Protective Works	Size: 210 m 0.00	2,144,000	Main
	U-Drain	Size: 125m 0.00	1,600,000	Main
	Kodali Khal Regulator	Size: 1 Vent-1.5mX1.8m 0.00	503,000	Main
	Re-excavation of Kodali Khal	0.00	324,000	Main
Sunamgonj (Total SPs : 27 Nos.)				
Biswambarpur SSWRDSP-2 SP25298, Mukti khola Khal Subproject, FMD&WC, Union : Polash, HO Date: 27/08/2009	Banderghat WRS at Ch.0+700Km	6 Vent-1.5mX2.0m 0.00	12,555,570	Main
	Check Structure on Br. Sandhankhali at Ch.1+200Km	3 Vent-1.5mX1.2m 0.00	1,592,000	Main
	Re-sectioning of Mukti khola Canal Dyke	0.65	144,441	Main
	Re-excavation of Br. Sundhankhali Khal	0.70	380,231	Main
Rubber Dam SP99014, Ghagotia Khal Rubber Dam Project, WC, Union : , HO Date:	Ghagotia Khal Rubber Dam	Size: 30mX4.5m 0.00	64,099,000	Main
SP99015, Gozaria Khal Rubber Dam Project, WC, Union : , HO Date:	Gozaria Khal Rubber Dam	Size: 150.0mX4.5m 0.00	292,411,000	Main
Chhatak SSWRDSP-2 SP25226, Patar Haor-Bheribund Subproject, FMD&WC, Union : Bhatgaon, HO Date:	Re-sectioning of Patar Haor Embankment	1.15	474,701	Main
	Re-excavation of Majer Gopat Khal	0.50	85,615	Main
	Regulator on Masua Khal at Ch.0+100Km (Khal)	6 Vent-1.5mX1.8m 0.00	10,739,650	Main
	Re-excavation of Masua Khal	1.00	879,587	Main
	Re-excavation of Jara Khal	1.40	688,117	Main
	Re-excavation of Hardarpur Khal	0.30	31,335	Main
	Re-excavation of Tin Beela Khal	1.00	105,749	Main
	Re-excavation of Ilamer Khal	0.70	80,154	Main

SSWRDP-JICA

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP32029, Teli Haor Subproject, FMD&WC, Union : Dholar Bazar, HO Date: 15/07/2013				
	Part-A: Putiara Khal Regulator at Ch.0+030Km	2 Vent-1.5mX1.8m 0.00	5,786,571	Main
	Part-B: Teli Haor WRS at Ch.2+250Km	2 vent-1.5mX1.5m 0.00	2,416,451	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	971,187	Main
	Re-excavation of Putiara Khal	2.50	2,364,495	Main
	Reference Lined Section	0.00	89,859	Main
SP33075, Khanjanpur Subproject, FMD&WC, Union : Bhatgaon, HO Date: 08/04/2015				
	Part-A: Regulator at Naya Beel Khal at Ch.0+050Km	2 Vent-1.5mX1.8m 0.00	7,085,475	Main
	Part-B: Regulator at Amdahuk Beel Khal at Ch.0+110	2 Vent-1.5mX1.8m 0.00	7,148,677	Main
	Re-excavation of Naya Beel Khal	1.94	828,028	Main
	Re-excavation of Amdahuka Beel Khal	1.10	397,928	Main
	Resectioning of Embankment	3.43	2,254,211	Main
SP33098, Kakarkuri Subproject, FMD&WC, Union : Bhatgaon, HO Date: 22/05/2014				
	Re-excavation of Fish Refugee	0.00	261,957	Main
	Part-A: Mokambari Regulator	1 V-1.5mX1.8m &1	6,104,386	Main
	Re-excavation of Mokambari Khal	1.58	524,701	Main
	Re-excavation of Bazubari Ditch-Cum-Bund	1.20	588,257	Main
	Re-excavation of Chotozai Ditch-Cum-Bund	1.41	629,530	Main
	Part-B: Culvert Modification into Gated Structure	2 V-1.5mX2.5m & 1	9,601,881	Main
	Re-excavation of Suparipota Khal	0.05	97,221	Main
SP35258, Bhatgaon-Kandanala Subproject, FM&WC, Union : Bhatgaon, HO Date:				
	Resectioning of Approach Road upto Regulator	0.17	363,039	Main
	Re-excavation of Elongir Khal	0.30	194,357	Main
	Re-excavation of Boro Kandi Nala	0.90	749,764	Main
	Re-excavation of Gulbon Nala	0.60	437,319	Main
	Re-excavation of Kandanala Beel Fish Shelter	0.47	176,225	Main
	Part-A: Kandanala Regulator at Ch. 0+050Km (From Bridge)	2 Vent-1.5mX1.8m 0.00	7,251,419	Main
	Re-excavation of Fish Sanctuary	0.00	245,925	Main
Dherai SSWRDP-JICA				
SP35221, Kaliakuta Haor Subproject, FM&WC, Union : Bhatipara, Ejatpur, HO Date:				
	Part-A: Jalaldi Beel Regulator at Ch. 3+108Km (Embkt)	1 Vent-1.5mX1.8m 0.00	5,255,440	Main
	Part-B: Chatlar Beel Regulator at Ch. 5+915Km (Embkt)	1 Vent2.5mX3.5m 0.00	4,858,522	Main
	Part-C: Khamar Bari Khal Regulator at Ch. 1+230Km (Emb)	1 Vent-1.5mX1.8m 0.00	4,062,301	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,474,446	Main
	Resectioning of Kaliakuta Haor	6.00	10,065,116	Main
Doarabazar SSWRDSP-2				
SP23074, Banglabazar Subproject, FM, Union : Banglabazar, HO Date: 09/03/2008				
	Embankment Re-sectioning	6.14	3,556,278	Main
	Banglabazar Regulator at Ch.0+030Km (Khal)	3 Vent-1.50mX1.80m 0.00	4,528,457	Main
	O&M Shed	9.00mX5.00m 0.00	308,811	Main
	Part-A: Construction of RCC L.Canal at ch.0+000 km to 0+580 km	at ch.0+000 km to 0+580 km	4,192,925	PSSWRSP
SP23110, Haque Nagar Subproject, WC, Union : Banglabazar, HO Date: 27/07/2009				
	Mayla River WRS	13 V-1.5mx2.0m & 1	14,759,743	Main
	O&M Shed	9.00mX5.00m 0.00	394,077	Main
	Part-A: Construction of Box Culvert	(1v.75mX.75m) 0.00	1,266,968	PSSWRSP
	Part-B: Construction of irrigation drain	0.00	1,176,229	PSSWRSP
	Part-C: CC Block &relative work of Haque Nagar SP	0.00	1,371,388	PSSWRSP
SP25305, Sakua Khal Subproject, WC, Union : Lakkipur, HO Date: 12/10/2009				
	Sakua Khal WRS at Ch.3+080Km	5 Vent-1.5mX1.8m 0.00	8,147,311	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-sectioning of Canal Dyke	1.91	605,775	Main
	O&M Shed	Size: 9mX5m 0.00	612,719	Main
	Sakua Khal Outlet Structure (R/B) at Ch. 3+236Km	1 Vent-0.9m Dia 0.00	120,600	Main
	Sakua Khal Outlet Structure (L/B) at Ch. 3+236Km	1 Vent-0.9m Dia 0.00	143,543	Main
SSWRDP-JICA				
SP33096, Shaheber Gaon Subproject, CAD, Union : Pandargaon, HO Date: 23/12/2015				
	Re-excavation of Mora Surma River	1.30	2,194,054	Main
	Re-excavation of Mora Surma River (U/S)	1.60	3,285,258	Main
	Re-sectioning of Embankment on Gutumanik Haor	2.90	3,131,235	Main
	Part-A: Header Tank and Service Connection from PD	Size: 6.1mX3.7m 0.00	3,789,331	Main
	Part-B: PVC Buried Pipe Network System	Length= 6285m 0.00	17,628,251	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,832,093	Main
	Part-D: Construction of Pump House	Size: 4.9mX4.5m 0.00	314,752	Main
	Part-E: Supply of Accessories of Pump House	0.00	494,035	Main
	Part-F: Supply of 2 nos. Disel Pumps	0.00	200,545	Main
	Protection Work of Pump House	0.00	499,801	Main
SP33097, Mongalpur Subproject, CAD, Union : Pandargaon, HO Date: 23/12/2015				
	Part-A: Header Tank	Size: 6.10mX3.25m 0.00	2,771,085	Main
	Part-D: WMCA Office and Related Item	Size: 12mX6m 0.00	1,269,734	Main
	Part-C: Buried Pipe Network System	Length=8.335Km 0.00	23,873,669	Main
	Part-B: Flow Control Structure at Junction Point	Size: 3.75mX2.25m 0.00	817,289	Main
	Part-E: Pumphouse, Pumps and its Accessories	0.00	559,463	Main
Rubber Dam				
SP98004, Khasiamara Khal Rubber Dam Project, WC, Union : Laxmipur, HO Date:				
	Khasiamara Khal Rubber Dam	Size: 45mX3.5m 0.00	24,617,000	Main
Jaggannathpur				
SSWRDP-JICA				
SP32013, Roail-Helalpur Subproject, FMD&WC, Union : Raniganj, HO Date: 04/11/2013				
	Re-excavation of Roail Khal	2.80	2,030,378	Main
	Resectioning of Embankment (Ch 2+092 to 2+670 km)	0.00	243,940	Main
	Gap Filling (remaining) Kushari-Roail Embk	0.00	83,169	Main
	Eath Filling of WMCA Office	0.00	71,848	Main
	Resectioning of Embankment Sanitganj Bazar (Helalpur) to	0.70	1,251,179	Main
	Re-excavation of Helalpur Khal	1.00	414,584	Main
	Re-sectioning of Embankment	7.70	4,663,524	Main
	Part-A: Roail Regulator at Ch.0+168Km (Khal)	4 Vent-1.5mX1.8m 0.00	12,304,047	Main
	Part-B: Helalpur Regulator at Ch. 0+176km (Khal)	1 Vent-1.5mX1.8m 0.00	4,442,959	Main
	Part-C: Modification of Existing Culvert to Gated	2 Vent-1.5mX1.5m 0.00	2,670,910	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	813,867	Main
	Gap Filling of Existing Road/Embankment	0.00	948,367	Main
Jamalganj				
SSWRDP-JICA				
SP34110, Kalagang Roar Haor Subproject, FMD&WC, Union : Behuli, HO Date:				
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,210,314	Main
	Reference Lined Section (5 nos.)	0.00	299,514	Main
	Re-excavation of Kalagang Khal	0.90	1,651,675	Main
	Re-excavation of Roar Khara Khal	2.00	777,664	Main
	Part-A: Kalagang Regulator at Ch.0+200Km	3 Vent-1.5mX1.8m 0.00	9,681,850	Main
	Gap Filling	0.05	195,515	Main
Sadar				
SSWRDSP-2				
SP23105, Uttma Beel Subproject, FMD, Union : Mollapara, HO Date: 30/07/2009				

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Utma Khal	1.25	241,737	Main
	Embankment Re-sectioning	4.72	1,712,699	Main
	Utma Regulator at Ch. 0+030 Km (Khal)	2 Vent-1.50mX1.80m 0.00	2,508,554	Main
	O&M Shed	9.00mX5.00m 0.00	308,279	Main
SP25222, Shialmara Beel Subproject, FMD&WC, Union : Mollapara, HO Date: 25/10/2009				
	Re-sectioning of Embankment	5.25	2,298,987	Main
	Shialmara Beel Regulator at Ch. 1+510Km(Embkt)	4 Vent-1.5mX1.80m 0.00	9,091,987	Main
SP25291, Janigaon-Painda Subproject, CAD, Union : Mohanpur, Laxmansree, HO Date:				
	O&M Shed	Size: 9.0mX5.0m 0.00	510,333	Main
	Header Tank	Size: 6.1mX3.0m 0.00	517,190	Main
	Burried Pipe Irrigation Networks System	Length=5100m 0.00	9,979,912	Main
	Re-sctioning of Embankment (South Side)	1.20	675,240	Main
	Re-sctioning of Embankment (North Side)	0.80	440,135	Main
	Part-B: Construction of Pumping Plat form of Janigaon Pan	0.00	1,113,280	PSSWRSP
	Part-A: Construction of Pumping Plat form of Janigaon Pan	0.00	2,257,870	PSSWRSP
SP25302, Dhalai Subproject, WC, Union : Jahangir Nagar, HO Date: 27/06/2009				
	Rubber Dam over Dhalai River at Ch.1+460Km	20m widthX3.5m ht. 0.00	26,034,270	Main
	Outlet Structure at Ch. 1+970Km	1 Vent-0.60m Dia 0.00	207,464	Main
	Irrigation Outlet Structure at Ch. 4+900Km	1 Vent-0.60m Dia 0.00	205,752	Main
	Canal Dyke at Dhalai Chhara	0.02	285,108	Main
	Dhalai Dyke (L/S)	2.21	1,007,520	Main
	Re-excavation of Islampur Khal	0.50	215,967	Main
	Procurement of Rubber Bag	0.00	3,800,000	Main
	Dhalai Irrigation Outlet at Ch. 2+100Km	1 Vent-0.60m 0.00	205,351	Main
	Dhalai Dyke (R/S)	2.21	1,377,855	Main
	Head Regulator at 1+470Km	1 Vent-0.90m Dia 0.00	2,688,079	Main
	O&M Shed	0.00	651,561	Main
	Islampur Khal Irrigation Outlet at Ch. 2+550Km	1 Vent-0.60m Dia 0.00	207,464	Main
	Outlet Structure at Ch. 3+180Km	1 Vent-0.30m Dia 0.00	196,111	Main
	Part-A: Constructon of 10.0m long Dam on Dhalaipar out p:	at Ch. 1300.00m 0.00	1,397,946	PSSWRSP
	Part-B: Re-Sectining of Embankment	0.00	1,368,068	PSSWRSP
	Part-A: Re-excavation of Dhalai River Khal	1.30	1,651,963	PSSWRSP
SSWRDP-JICA				
SP32033, Mugai Khal Subproject, WC, Union : Surma, HO Date: 14/07/2013				
	Part-A: Mugai Khal WRS	12 Vent-1.5mX2.75m 0.00	15,969,745	Main
	Part-B: WMCA Office with Allied Items	Size:12mX6m 0.00	1,333,516	Main
	Re-excavation of Mugai Khal	3.60	3,677,777	Main
SP33092, Nokhorier Chhara Subproject, WC, Union : Ronger Char, HO Date: 15/10/2014				
	Part-E: Outlet Pipe Regulator-3 on Left Bank of C	1 Vent-0.30m Dia 0.00	326,996	Main
	Part-F: Outlet Pipe Regulator-4 on Left Bank of C	1 Vent-0.30m Dia 0.00	326,963	Main
	Re-sectioing of Nokhoriar Chhara West Bank	1.80	995,169	Main
	Re-sectioing of Nokhoriar Chhara East Bank	1.06	926,375	Main
	Supplying and fixing underground pipe	300mm Dia 0.00	313,964	Main
	Construction of outlet on East Bank at Ch.1+215Km	1 no. 0.00	500,000	Main
	Site Development work around WMCA Office Buildings	0.00	144,757	Main
	Part-G: WMCA Office and Related Item	Size: 12mX6m 0.00	1,826,651	Main
	Reexcavation of Nokhorier Chhara	3.50	1,737,383	Main
	Refernece Lined Section (4 nos.)	0.00	88,201	Main
	Part-A: Nokhorier Chhara WRS at Ch. 1+010Km (Khal)	4 Vent-1.5mX2.0m 0.00	9,856,107	Main
	Part-B: Outlet Pipe Regulator-1 on Right Bank of C	1 Vent-0.30m Dia 0.00	326,963	Main
	Part-C: Outlet Pipe Regulator-2 on Right Bank of C	1 Vent-0.30m Dia 0.00	326,953	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
SP34104, Bongaon Chhara Subproject, WC, Union : Ronger Char, HO Date: 22/12/2015	Part-D: Outlet Pipe Regulator-3 on Right Bank of C	1 Vent-0.30m Dia 0.00	326,963	Main
	Re-excavation of Bongaon Chhara	0.60	754,673	Main
	Resectioning of Embankment/Dyke	0.84	344,295	Main
	Part-A: Bongaon Chhara WRS at Ch 2+100Km	10 Vent-1.5mX2.5m 0.00	14,903,423	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,600,532	Main
	Part-B: Pipe Inlet Structures (8 nos.)	1-v 0.30m 0.00	3,400,828	Main
	Re-sectioning of Approac and its Protection of Bongaon Ch	0.05	1,729,490	Main
SP34156, Hasaura Subproject, WC, Union : Ronger Char, HO Date: 22/12/2015	Part-A: Hasura Chhara WRS at Ch.2+35Km	5 Vent-1.5mX2.2m 0.00	12,433,536	Main
	Part-B: 4 nos. Outlet Structures	1 Vent-0.30m Dia (4 nos.)	1,786,323	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,217,545	Main
	Resectioning of Embankment	0.70	372,007	Main
	Reexcavation of Khal	0.50	112,530	Main
	Reexcavation of Baronali Khal	0.95	146,993	Main
Taherpur SSWRDP-JICA SP34106, Samsar Haor-Chunkhola Beel Subproject, FMD&WC, Union : Uttar Shripur, HO	Part-B: WMCA Office with Related Item	Size: 12mX6m 0.00	1,399,600	Main
	Re-excavation of Chunkhola Khal	3.00	3,411,931	Main
	Re-excavation of Golok Khali Khal	2.00	1,724,366	Main
	Re-sectioning of Submersible Embankment	9.60	11,686,249	Main
	Refrence Lined Sections (6 nos)	0.00	205,495	Main
	Part-A: Golok Khali Regulator at Ch.0+030Km	5 Vent-1.5m X1.8m 0.00	16,232,077	Main
	Re-construction of Beri bundh cum Road	2.80	3,709,100	Main
SP34125, Baradal Uttar Koraigara Chhara Subproject, WC, Union : Uttar Borodal, HO	Part-A: Uttar Koraigara Chhara WRS-1 at Ch1+675Km	4 Vent-1.5mX2.5m 0.00	8,558,183	Main
	Part-F: Outlet Pipe Regulator-4 on Koraigara Chhara	1 Vent-0.30m Dia 0.00	344,725	Main
	Part-G: Outlet Pipe Regulator-5 on Koraigara Chhara	1 Vent-0.30m Dia 0.00	342,878	Main
	Part-H: Outlet Pipe Regulator-6 on Koraigara Chhara	1 Vent-0.30m Dia 0.00	342,567	Main
	Re-sectioning of Dykes U/S of Koraigara Chhara WRS-2.	0.00	0	Main
	Part-B: Koraigara Chhara WRS-2 at Ch.0+850Km	4 Vent-1.5mX1.5m 0.00	5,336,014	Main
	Part-I: WMCA Office and Related Item	Size: 12mX6m 0.00	1,253,538	Main
	Part-C: Outlet Pipe Regulator-1 on Koraigara Chhara	1 Vent-0.30m Dia 0.00	364,845	Main
	Part-D: Outlet Pipe Regulator-2 on Koraigara Chhara	1 Vent-0.30m Dia 0.00	344,727	Main
	Part-E: Outlet Pipe Regulator-3 on Koraigara Chhara	1 Vent-0.30m Dia 0.00	344,549	Main
Sylhet (Total SPs : 28 Nos.)				
Balaganj SSWRDP-JICA SP35166, Haonia-Sonia Haor Subproject, FMD&WC, Union : Osmanpur, HO Date:	Re-excavation of Alike Khal	2.69	4,871,573	Main
	Re-excavation of New Alike Khal	1.20	1,351,135	Main
	Re-excavation of Kata Khal	2.01	5,137,422	Main
	Re-excavation of Ainakhali Khal	1.55	2,238,586	Main
	Re-excavation of Jung Khal	1.00	824,471	Main
	Part-A: Alike Khal Regulator	3 Vent-1.5mX1.8m 0.00	13,532,339	Main
	Part-B: Kata Khal WRS	2 Vent-1.5mX1.8m 0.00	3,214,696	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,526,167	Main
	SP35167, Kalma Khal-Magria Khal Subproject, FMD&WC, Union : Burunga, HO Date:			
	Re-excavation of Kalma Khal	1.79	1,055,993	Main
	Re-excavation of Magria Khal	1.20	1,251,670	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Fish Sanctuary in Three Beels	0.00	1,254,744	Main
	Part-A: Magria Khal Regulator at Ch.1+050Km	2 Vent-1.5mX1.8m 0.00	6,867,664	Main
	Part-B: Kalma Khal WRS at Ch.0+150Km	2 Vent-1.5mX1.8m 0.00	4,797,272	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,979,492	Main
SP35215, Dhaolong Horua-Merua Haor Subproject, DR&WC, Union : Omarpur, HO Date:				
	Re-excavation of Dhaolong Boro Khal	3.21	4,135,878	Main
	Re-excavation of Barang Khal	1.48	1,031,716	Main
	Re-excavation of Alongi-Daser Khal	1.95	2,369,662	Main
	Re-excavation of Dalar Khal	1.50	751,158	Main
	Part-B: Alongi-Daser Khal WRS at. Ch.0+150Km	2 Vent-1.5mX1.8m 0.00	2,513,084	Main
	Part-A: Kamalpur WRS on Dhaolong Boro Khal at Ch.0+87	3 Vent-1.5mX2.0m 0.00	6,672,910	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,532,702	Main
	Re-excavation of Daser Khal	2.20	1,438,864	Main
Beanibazar SSWRDP-JICA				
SP34147, Charkhai-Dakshin Haor Subproject, FMD&WC, Union : Charkai, Alinagar, HO				
	Reexcavation of Shakpara Khal	0.88	399,186	Main
	Reexcavation of Modhurchak Khal	0.70	634,875	Main
	Reexcavation of Yusunkhani Khal	1.20	962,603	Main
	Resectioning of East Embankment	2.70	3,645,242	Main
	Resectioning of West Embankment	1.24	1,002,165	Main
	Part-A: Adinabad Khal Regulator	2 Vent-1.5mX1.8m Ch 0+030	7,083,263	Main
	Part-D: WMCA Office and Related Item	Size:12mX6m 0.00	1,419,479	Main
	Part-B: Box Sluice at Ch. 0+573Km	1 Vent-0.9mX0.9m 0.00	2,063,365	Main
	Part-C: Box Sluice at Ch. 1+413Km	1 Vent-0.9mX0.9m 0.00	1,820,356	Main
	Reexcavation of Adinabad Khal	2.20	2,454,812	Main
Biswanath SSWRDSP-2				
SP23073, Angura Subproject, FMD&WC, Union : Bishwanath, HO Date: 26/12/2011				
	Angura Khal Re-excavation	3.60	1,138,167	Main
	Angura Khal Regulator at Ch.0+250km(Khal)	4 Vent-1.50mX1.80m 0.00	6,358,902	Main
	Bela Sourav Khal Re-excavation	2.44	223,310	Main
	Bela Ekram Sonjug Khal Re-excavation	1.69	204,814	Main
SP25220, Madai Khal Subproject, FMD&WC, Union : Biswanath, HO Date: 16/11/2009				
	Regulator over Madai Khal at Ch. 0+000Km (Khal)	3 Vent-1.5mX1.8m 0.00	5,283,378	Main
Companyganj SSWRDSP-2				
SP23104, Dulia Satbila Subproject, FMD&WC, Union : Islampur, HO Date: 27/08/2009				
	Re-excavation of Dulia Khal	1.50	185,628	Main
	Regulator on Chikar Khal at Ch.0+600km (Embk)	2 Vent-1.50mX1.80m 0.00	4,345,293	Main
	Regulator on Dulia Khal at Ch.0+040km (Khal)	1 Vent-1.50mX1.80m 0.00	3,497,989	Main
	Re-sectioning of road cum Embankment	4.92	1,196,142	Main
	Closure on Rajar Khal	65 m 0.00	555,151	Main
	O&M Shed	9.00mX5.00m 0.00	308,698	Main
	Re-excavation of Chikar Khal	4.20	815,476	Main
SP25200, Borom Chhara Subproject, WC, Union : North Ranikhai, HO Date: 16/10/2012				
	Re-sectioning of Canal Dyke	0.70	260,446	Main
	WRS on Boron Chhara	6 Vent-1.5mX2m 0.00	6,732,673	Main
	O&M Shed	Size:9mX5m 0.00	406,875	Main
	Borom Chhara Outlet at Ch. 3+640Km (L/B)	1 Vent-0.60m dia 0.00	87,215	Main
	Borom Chhara Outlet at Ch. 3+640Km (R/B)	1 Vent-0.60m dia 0.00	87,215	Main
	Borom Chhara Outlet Near H/O Babul Mia	1 Vent-0.60m dia 0.00	87,215	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: Re-sectioning of Borom Chhara Embankment (R/S	1.03	2,172,274	PSSWRSP
	Part-B: Re-sectioning of Borom Chhara Embankment (L/S	1.03	1,803,310	PSSWRSP
SSWRDP-JICA				
SP35179, Sutadhari-Raikhal Subproject, FM&WC, Union : Dakshin Ronikhai, HO Date:				
	Reexcavation of Sutadhari Khal	0.40	320,024	Main
	Part-B: Raikhal WRS by Modification of Existing Girder Bric	3 Vent-1.5mX1.8m 0.00	3,464,495	Main
	Part-C: Chamachi Khal WRS at Ch.3+700Km (Khal)	2 Vent-1.5mX1.8m 0.00	7,941,621	Main
	Part-D: WMCA Office and Related Item	Size-12mX6m 0.00	1,589,634	Main
	Reexcavation of Kalenga Khal (East)	0.70	995,360	Main
	Reexcavation of Denga Khal	1.60	1,288,390	Main
	Reexcavation of Denga Branch Khal	0.70	703,256	Main
	Reexcavation of Noa Khal	1.60	1,173,972	Main
	Reexcavation of Purar Khal	2.20	1,344,482	Main
	Reexcavation of Chamachi Khal	3.50	3,609,035	Main
	Resectioning of Sutadhari Embankment	2.04	1,258,200	Main
	Part-A: Sutadhari Khal Regulator at Ch.0+250Km (Khal)	3 Vent-1.5mX1.8m 0.00	12,557,311	Main
Fenchuganj				
SSWRDSP-2				
SP25208, Paglachara-Bialibazar Subprject, WC, Union : Fenchuganj, Gillachura &				
	Re-sectioning of Banks of Khal	0.78	360,174	Main
	Paglachhara WRS at CH. 3+325Km	4 Vent-1.5mX2m 0.00	6,267,473	Main
	O&M Shed	Size: 9mX5m 0.00	377,127	Main
	Paglachara Irrigation Outlet at Ch.3+360Km(L/B)	1 Vent-0.60m Dia Pipe 0.00	100,419	Main
	Paglachara Irrigation Outlet at Ch.3+360Km(R/B)	1 Vent-0.60m Dia Pipe 0.00	100,419	Main
	Paglachara Irrigation Outlet at Ch.0+300Km(L/B)	1 Vent-0.60m Dia Pipe 0.00	101,605	Main
	Paglachara Irrigation Outlet at Ch.0+300Km(R/B)	1 Vent-0.60m Dia Pipe 0.00	101,605	Main
SP25307, Chatal Beel Subproject, FM, Union : Maizgaon, HO Date: 20/02/2012				
	Chatal Khari Regulator at Ch.0+025Km	2 Vent-1.5mX1.8m 0.00	5,393,540	Main
	O&M Shed	Size: 9mX5m 0.00	487,832	Main
	Aula Chhara Dyke	1.52	926,916	Main
SSWRDP-JICA				
SP34152, Pukuria Beel Subproject, FMD, Union : Narayanpur, Mollikpur, HO Date:				
	Part-A: Pukuria Khal Regulator	2 Vent-1.5mX1.8m 0.00	7,709,616	Main
	Part-B: Batai Khal Regulator	2 Vent-1.5mX1.8m 0.00	7,700,625	Main
	Re-excavation of Pukuria Beel Khal (Ch 0+000 to 0+450 kr	0.45	239,867	Main
	Resectioning of Embankment	4.05	8,189,359	Main
	Re-excavation of Fish Refuge Pakuria Beel, Batia B	0.00	600,178	Main
	Part-D: WMCA Office and Related Item	Size:12.0mX6.0m 0.00	1,786,988	Main
	Re-excavation of Batia Khal (Ch 0+000 to 0+900km)	0.90	1,068,629	Main
	Part-C: Inward Drainage Sluice	1 Vent-1.0mX1.0m 0.00	1,784,738	Main
SP35208, Chilua Beel Subproject, FMD&WC, Union : Maizgaon, HO Date: 19/01/2016				
	Re-excavation of Hafizkhali Khal	1.12	1,958,980	Main
	Part-A: Hafizkhali Khal Reulator at Ch.0+050Km	2 Vent-1.5mX1.8m 0.00	10,142,140	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,648,054	Main
	Resectioning of Embankment	2.68	801,829	Main
Golapganj				
SSWRDSP-2				
SP23071, Kandibari Khal Subproject, WC, Union : West Amura, HO Date: 02/03/2009				
	Kandibari Khal WRS at Ch.0+050 Km (Khal)	2 Vent-1.50mX1.80m 0.00	2,788,901	Main
	Canal Dyke on Right & Left Bank	0.50	57,812	Main
	Kandibari khal Outlet at Ch 0+095Km (R/B)	1 Vent-0.60m dia 0.00	172,453	Main
	Kandibari Khal Outlet at Ch.0+115 Km (L/B of Khal)	1 Vent-0.60m Dia 0.00	130,030	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Kandibari Khal Outlet at Ch.0+150Km (R/B of Khal)	1 Vent-0.60m Dia 0.00	152,157	Main
	Kandibari Khal Outlet at Ch.0+165 Km (L/B of Khal)	1 Vent-0.60m Dia 0.00	130,030	Main
	O&M Shed	12mX6m 0.00	3,749,634	Main
SP25211, Bagha Beel Subproject, FM, Union : Bagha, HO Date: 17/10/2009				
	Bagha Khal Regulator at Ch.0+044Km (Khal)	3 Vent-1.5mX1.8m 0.00	6,599,560	Main
	Re-sectioning of Embankment	6.12	2,827,618	Main
	Part-A: Construction for Drainage Out-let Structure (1V-900r	(1V-900m dia) 0.00	1,362,483	PSSWRSP
	Part-B: Field irrigation cannel	at Ch.0+000 km to 1+200 km	2,690,659	PSSWRSP
	Part-C: Road crossing cross Drain	at ch. 0+000 km 0+777 km	105,123	PSSWRSP
SSWRDP-JICA				
SP34133, Tola Khal Subproject, WC, Union : Fulbari, HO Date: 22/02/2015				
	Re-excavation of Tola Khal	3.65	2,998,255	Main
	Re-excavation of Teli Khal	1.05	1,677,561	Main
	Re-excavation of Digir Khara Khal	0.20	191,449	Main
	Part-A: Tola Khal WRS at 0+010Km(Khal)	2 Vent-1.5mX3.5m 0.00	11,076,398	Main
	Reference Lined Sections	0.00	34,200	Main
	Part-B: WMCA Office and Related Item	Size: 12mX6m 0.00	1,522,164	Main
SP35191, Makri Beel Subproject, FMD&WC, Union : Paschim Amura, HO Date:				
	Re-sectioning of Makri Beel Embankment	1.70	3,959,504	Main
	Re-excavation of Makri Khal	0.50	297,911	Main
	Part-A: Makri Khal Regulator by Modification of Existing Bo	2 Vent-1.5mX1.8m 0.00	6,345,599	Main
	Renovation of Makri Beel Embankment at Ch. 11+050Km t	0.00	0	Main
Gowainghat				
SSWRDSP-2				
SP23072, Shialichara Subproject, WC, Union : Fatehpur, HO Date: 28/03/2009				
	Shialichara WRS at Ch.0+820 Km (Khal)	3 Vent-1.50mX1.80m 0.00	2,918,456	Main
	O&M Shed	12mX6m 0.00	323,996	Main
	Shialichara Outlet (Left) at Ch.0+870 Km (Khal)	1 Vent-0.60m Dia 0.00	108,318	Main
	Shialichara Outlet (Right) at Ch.0+890 Km (Khal)	1 Vent-0.60m Dia 0.00	108,318	Main
	Canal Dyke on Left Bank	1.22	200,578	Main
	Canal Dyke on Right Bank	1.22	173,370	Main
	Re-excavation of Shialichhara Khal	1.50	195,717	Main
	Part-A: Construction of RCC Lined Cannal	L=900 m 0.00	4,431,841	PSSWRSP
SSWRDP-JICA				
SP33054, Shialar Haor Subproject, FMD, Union : Nandigaon, HO Date: 16/02/2015				
	Part-A: Shialar Haor Regulator	5 Vent-1.5mX1.8m 0.00	16,503,794	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	1,813,331	Main
	Part-B: Binnakona Khal Regulator	1 Vent-1.5mX1.8m 0.00	6,527,041	Main
	Resectioning of North-East Embankment	5.30	2,461,843	Main
	Resectioning of South-East Embankment	4.80	3,910,801	Main
	Part-A: Re-sectioning of North East Embankment	1.70	1,187,897	SSWRDP-JICA-2
	Part-B: Re-sectioning of South West Embankment	2.10	1,945,739	SSWRDP-JICA-2
SP34107, Binnakandi Subproject, WC, Union : Fatehpur, HO Date: 18/08/2015				
	Part-C: Outlet Pipe Regulator-2 Ch.1+600Km	1 Vent-0.3m 0.00	372,349	Main
	Part-D: Outlet Pipe Regulator-3 Ch.2+100Km	1 Vent-0.3m 0.00	372,809	Main
	Part-E: Outlet Pipe Regulator-4 Ch.2+100Km	1 Vent-0.3m 0.00	372,266	Main
	Part-F: WMCA Office and Related Item	Size: 12mX6m 0.00	1,709,104	Main
	Reexcavation of Binna Chhara & Construct. of Dykes	2.40	1,990,818	Main
	Reference Lined Section (2 nos.)	0.00	11,400	Main
	Part-A: Binna Chhari WRS at Ch.1+575Km (Khal)	4 Vent-1.5mX2.0m 0.00	10,739,813	Main
	Part-B: Outlet Pipe Regulator-1 Ch.1+600Km	1 Vent-0.3m 0.00	372,301	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Part-A: Construction of RCC Irrigation Chanal	550 m 0.00	0	SSWRDP-JICA-2
	Part-B: Modification of Binna Chhara WRS	4 Vent 1.5mX2.0m 0.00	0	SSWRDP-JICA-2
	Part-C: Construction of WMCA Office	50m 0.00	0	SSWRDP-JICA-2
	Part-A: Re-sectioning of Embankment and Loop Cutting	2.68	0	SSWRDP-JICA-2
SP34115, Naljuri Khal Subproject, FM&WC, Union : Purba Jaflong, HO Date: 05/06/2016				
	Re-excavation of Dhaleswari Khal	3.90	3,505,054	Main
	Part-A: Naljuri Khal WRS at Ch.1+130Km(Khal)	8 Vent-1.5mX2.5m 0.00	20,791,139	Main
	Part-D: Shanki Bhanga Khal Sluice at Ch.0+110Km(Kh	1 Vent-1.2mX1.2m 0.00	2,282,594	Main
	Part-B: Boali Khal Regulator at Ch.0+110Km (Khal)	2 Vent-1.5mX1.8m 0.00	6,480,271	Main
	Part-C: Satkuri Khal Regulator at Ch.0+075Km(Khal)	1 Vent-1.5mX1.8m 0.00	4,782,648	Main
	Part-E: WMCA Office and Related Items	Size: 12mX6m 0.00	1,421,025	Main
	Re-Sectioning of Naljuri Khal Dyke	5.80	4,923,717	Main
SP34122, Dakshin Gachhpala Chhara Subproject, DR&WC, Union : Fatehpur, HO Date:				
	Re-excavation of Pala Chhara	1.10	827,226	Main
	Part-A: Pala Chhara WRS at Ch.1+175Km	4 Vent-1.5mX2.2m 0.00	8,291,860	Main
	Part-B: Pipe Intlet Structure	1 Vent-0.3m Dia (4 nos) 0.00	1,780,686	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,586,592	Main
Kanaighat SSWRDP-JICA				
SP33065, Surai Khal Subproject, WC, Union : Laxmi Prasad(Poshchim), HO Date:				
	Part-A: Surai Khal WRS at Ch. 2+600Km	5 Vent-1.5mX4.5m (Double	10,970,114	Main
	Part-D: WMCA Office and Related Items	Size: 12mX6m 0.00	1,749,656	Main
	Part-C: Irrigation Outlets (6 nos)	1 Vent-0.30m Dia 0.00	2,751,179	Main
	Re-sectioning of Embankment	3.58	2,927,579	Main
	Re-sectioning of Dyke	1.41	771,192	Main
	Part-B: Kafrangi Khal Pipe Sluice at Ch.1+260Km	1 Vent-0.90m Dia 0.00	1,130,157	Main
	Re-sectioning of Left Bank Dyke Ch. 0+000Km to Ch. 1+08	0.00	0	Main
Sadar SSWRDSP-2				
SP25192, Chirchiri Chara Subproject, WC, Union : Khadim Nagar, HO Date: 19/02/2012				
	Chirchiri Chara WRS at Ch. 1+569Km	4 Vent-1.5mx1.8m 0.00	4,517,657	Main
	Chirchiri Charalrrigation Outlet at Ch1+600Km(L/B	1 Vent-0.60m Dia. 0.00	117,158	Main
	Chirchiri Charalrrigation Outlet at Ch1+600Km(R/B	1 Vent-0.60m Dia. 0.00	117,158	Main
	Chirchiri Charalrrigation Outlet at Ch2+100Km(L/B	1 Vent-0.60m Dia. 0.00	117,158	Main
	Chirchiri Chara Dyke	0.83	167,324	Main
	Part-A: Construction of WMCA Office & Others	12mx6m 0.00	1,359,105	PSSWRSP
	Part-B: RCC Lined Canal at Ch. 0+000 km to 0+700 km L=	at Ch. 0+000 km to 0+700	2,304,063	PSSWRSP
SSWRDP-JICA				
SP31006, Bawa-Chamurakandi Boro Haor Subproject, FM&WC, Union : Kandigoan, HO				
	Part-B: Bawa Khal Regulator at Ch. 0+029Km	Size: 1 Vent-1.20mX1.50m	3,549,903	Main
	Part-C: WMCA Office and Related Items	Size: 12mX6m 0.00	871,558	Main
	Re-sectioning of Baowa Regulator Approach	0.98	148,279	Main
	Re-sectioning of Chamurakandi Regulator Approach	0.98	134,686	Main
	Re-sectioning of Embankment	3.85	3,948,845	Main
	Re-excavation of Chamurakandi Beel Khal	2.00	1,719,540	Main
	Reference Lined Section	0.00	11,400	Main
	Re-excavation of Bawa Beel Khal	0.30	138,895	Main
	Part-A: Chamurakandi Khal Regulator at Ch. 0+046Km	Size: 1 Vent-1.20mX1.5m	3,491,950	Main
Zakiganj SSWRDP-JICA				
SP34148, Biabail Barjan Khal Subproject, WC, Union : Kashkanakpur, HO Date:				
	Part-A: Barjan Khal WRS	2 Vent-1.5mX2.5m 0.00	7,043,396	Main

District / Upazila / Project / SP	Component	Size / Length (Km.)	Implementation Cost (Tk.)	Enhancement / Main
	Re-excavation of Nazirer Khal	2.35	2,753,984	Main
	Re-excavation of Pukuria Khal	1.50	1,148,009	Main
	Fish Scentuary	0.00	372,563	Main
	Reference Line Sections (8 nos.)	0.00	195,898	Main
	Re-excavation of Barjan Khal	2.40	1,432,300	Main
	Re-excavation of Hanigram Khal	2.20	1,971,527	Main
	Re-excavation of Biabail Khal	2.10	1,730,261	Main
SP35253, Morai Khal Subproject, DR&WC, Union : Manikpur, HO Date: 06/06/2016				
	Re-excavation of Morai Khal including Reference Bed Blocl	7.50	5,838,775	Main
	Re-excavation of Kazir Gopat Khal including Reference Be	3.50	568,058	Main
	Part-A: Morai Khal WRS at Ch.6+460Km (Morai Khal)	2 Vent-1.5mX2.2m 0.00	5,047,194	Main
	Part-B: Kazir Gopat Khal WRS at Ch.2+900Km (Kazir Gop	1 Vent-1.5mX1.8m 0.00	3,360,136	Main
	Part-C: WMCA Office and Related Item	Size: 12mX6m 0.00	1,096,337	Main
SSWRDP-JICA-2				
SP71001, Keshri Beel Subproject, CAD&DR, Union : Zakiganj, Kahalchhara, HO Date:				
	Part-A: Construction of Header Tank	0.00	0	Main
	Part-B: Buried Pipe Network System	0.00	0	Main
	Part-C: Construction of Pump House	0.00	0	Main
	Part-D: Supply of Pump Accessories	0.00	0	Main
	Part-E: Pump and Power Connection	0.00	0	Main
	Part-F: Pump and Power Connection	0.00	0	Main
Total SPs : 6,684 Nos.				