Government of the People's Republic of Bangladesh

Ministry of Local Government, Rural Development & Cooperatives

Local Government Division

GAURANADI PAURASHAVA

MASTER PLAN: 2011-2031

November, 2014

Technical Assistance: Local Government Engineering Department (LGED)

Government of the People's Republic of Bangladesh

Ministry of Local Government, Rural Development & Cooperatives

Local Government Division

GAURANADI PAURASHAVA MASTER PLAN: 2011-2031

STRUCTURE PLAN

URBAN AREA PLAN:

- **Landuse Plan**
- **Transportation & Traffic Management Plan**
- **Drainage & Environmental Management Plan**

WARD ACTION PLAN

November, 2014

GAURANADI PAURASHAVA

GAURANADI, BARISAL

GAURANADI PAURASHAVA MASTER PLAN: 2011-2031

Published by:

GAURANADI PAURASHAVA

Supported by Upazila Towns Infrastructure Development Project (UTIDP)

Local Government Engineering Department (LGED)

Local Government Division

Consultant :

Sheltech Consultants (Pvt.) Ltd.
1/E/2 Paribagh (Mazar Road), Shahbagh, Dhaka-1000
in association with
Design Planning and Management Consultants Ltd.

Copyright: Gauranadi Paurashava
Local Government Division (LGD),
Ministry of Local Government, Rural Development & Cooperatives

First Edition: November, 2014

Price: BDT 1500.00
USD 20.00

EXECUTIVE SUMMARY

The presentation of this Master Plan Report is in compliance to the Terms of Reference for the preparation of Master plan for Gauranadi Paurashava under the project titled “Upazila Town Infrastructure Development Project”. Gauranadi was upgraded as B category Paurashava in 2001. It occupies an area of 17.41 sq. km and consists of 9 wards and 17 mauzas. At present the total population is almost 42438 of which 21205 are male and 21233 are female. Density of population is about 2438 persons per sq. km and literacy rate is about 68.9%.It has moderate level of economic activities and economic potentials to flourish as an urban centre in near future. Under such circumstances a development plan can help creating advantages for living and working in the Paurashava that would indirectly help attracting investment for economic growth leading to employment generation. The current development plan of the Gauranadi Paurashava focuses mainly on infrastructure development and control of haphazard spatial development through the instrument of land use zoning.

The plan aims of preparing the master plan is to identify the infrastructural facilities needed for socio economic and physical development and activities of the people living in the Paurashava so to improve their living condition.

The Master plan has the three components- the Structure Plan, the Urban Area Plan and the Ward Action Plan. The **Structure Plan** basically concerned with the physical development of broad strategies for managing and promoting efficient urban development over the long term (2011-2031) and attempts to integrate economic, physical and environmental objectives. It also identifies the basic strategic options available to accommodate the anticipated growth. The Structure Plan also outlines major sector wise policies to guide development in the desired manner over a longer period of time (for 20 years).

Second Component is the **Urban Area Plan** which is synthesized with upper tier of the Plan, the Structure Plan. The Urban Area plan provide an interim mid-term strategy for 10 years (2011-2021) for the development, of the Paurashava following the broad guidelines set by the longer term structure plan. The plans can be prepared for specific sections of the urban area identified in the structure plan for rapid development or for special projects and improvements. It gives detailed information on the preferred development pattern, showing location of roads, infrastructure, community facilities and land use zones. Considering the development growth trends, an estimated growth rate for Gauranadi Paurashava has been fixed at 1.19% using Exponential formula. Urban Area Plan is comprised of four components that is Land use Plan, Transportation and Traffic Management Plan, Drainage and Environmental Management Plan and Plan for Urban Services.

Land Use Plan is mainly confined to the land use zoning. Total 19 categories of landuse zones have been identified in Gauranadi Paurashava. About 25.88% lands are preserved for residential purpose and around 40% of total built up area and new urban area is reserved as Urban deferred for further need of area to establish or provide facilities for upcoming demand. Relevant land development control regulations and necessary implementation guidelines have also been incorporated.

Transportation and Traffic Management Plan includes existing condition of transportation facilities, intensity of traffic volume, travel demand forecasting for next 20 years, future traffic volume and transportation development plan. The plan proposed 28.23 km of new road network with adequate width and hierarchy. Proposal has also been made for widening of existing narrow

roads which is about 161.03 km and linking the missing links. Here is also proposal of two bus terminals (6.14 acre), two truck terminals (2.72 acre), rickshaw stand (0.40 acre), fuel station (1.21 acre), and tempo stand (3.88 acre) respectively in ward no. 6, 9, 2, 3, 1, 4, 1, and 9 . Moreover transportation system management and plan implementation strategies are also described in this plan.

Drainage and Environmental Management Plan is third part and subdivided into two segments- Drainage and Environment. Existing drainage network, land level, plan for drainage management and flood control, plan implementation strategies are also described in this plan. Existing environmental condition, solid waste management, environmental pollution, plan for environmental management and plan implementation strategies are also included. Projection on existing and proposed urban services, have been provided in this plan. To promote future drainage management, proposals have been made to create hierarchical drainage network throughout the future town with recovery of encroached khals to serve as primary drains and excavation of filled in areas of the natural khals. To ease water crisis overhead tank (1.76 acre in ward no. 3), and Water treatment plant (4.13 acre in ward no. 6) has been proposed in the plan. Besides, preserving the major ponds as alternatives sources of water, have been suggested. CBO based local waste collection system will have to be introduced at local level for waste management including establishment of a disposal site (5.64 acre in ward no. 9), and a number of transfer stations in every ward with a total area of 3.38 acres to collect waste for transportation to the dumping site.

The Third component is **Ward Action Plan (WAP)** where ward wise priority schemes, phasing of the schemes is made. Prioritization of no. of wards based on existing development pattern and need of development is also identified.

It is also mentioned here that the final plan has been prepared on the basis of comments made by the PMO and the Paurashava. It is suggested that to follow up the plan proposals and recommendations of different sectors to keep balance with demand and supply of citizens' requirements. The Master Plan will facilitate the agglomeration of people with the view to provide all facilities that will be help full for boosting up their socioeconomic condition. It should be kept in mind that master plan is a guideline for development and control of growth in a systematic manner. Without proper regulation or rules it would not be possible to manage the Master Plan. However appropriate authority must be obligatory for the execution of the Master Plan. Recommendations have been made to strengthen the financial and managerial capacity of the Paurashava including creation of a planning section to handle preparation and implementation of the town plans and manage development control system. Suggestions have been made to reduce dependency on the central government for financing development and improve its own financial capacity by strengthening its own sources of revenue earning, particularly focusing on the holding tax.

Table of Content

Page No.

Preface i
Executive Summary ii-iii
Table of Contents iv-xv
List of Tables xi
List of Maps xiii
List of Figures xiv
List of Abbreviations and Acronyms xv

PART A: STRUCTURE PLAN

Chapter 1: Introduction
1.1 Introduction 1
1.2 Philosophy of the Master Plan 1
1.3 Objectives of the Master Plan 2
1.4 Conceptualization 2
1.5 Approach and Methodology 3
1.5.1 Demarcation of the Planning area 4
1.5.2 Preparation of Base Map 4
1.5.3 Surveys 4
1.5.4 Data and Information Management 6
1.5.5 Adopted Planning Standard 6
1.5.6 Stake holder's consultation 6
1.6 Scope of the Work 6

Chapter 2: Structure Plan
2.1 Background of the Paurashava 7
2.2 Vision of the Structure Plan 7
2.3 Objectives of the Structure Plan 7
2.4 Content and Format of Structure Plan 7

Chapter 3: Existing Trend and Growth
3.1 Social Development 10
3.2 Economic Development 10
3.3 Physical Infrastructure Development 10
3.4 Environmental Growth 11
3.5 Population 11
3.6 Institutional Capacity 11
3.7 Urban Growth Area 12
3.8 Catchments Area 12
3.9 Land Use and Urban Services 12
3.10 Paurashava Functional Linkage with Regional and National Network 13
3.11 Role of Agencies for Different Sectoral Activities 15

Chapter 4: Critical Planning Issues
4.1 Physical Infrastructure 17

4.2 Socio-Economic 17
4.3 Environment 17
4.4 Transport and Communication 18
4.5 Landuse Control 18
4.6 Disaster 19
4.7 Laws and Regulations 19

Chapter 5: Paurashava Development Related Policies, Laws and Regulations
5.1 General 20
5.1.1 Local Government (Paurashava) Act 2009 20
5.1.2 Urban Management Policy, 1999 23
5.1.3 National Housing Policy, 2008 23
5.1.4 Population Policy, 2004 24
5.1.5 National Land Use Policy, 2001 24
5.1.6 National Agriculture Policy, 1999 25
5.1.7 Transportation Policy 26
5.1.8 Environment Policy 26
5.1.9 Coastal Zone Policy, 2005 27
5.1.10 Industrial Policy, 2005 32
5.1.11 Health Policy 32
5.1.12 National Urban Policy 33
5.1.13 Rural Development Policy 33
5.1.14 Disaster Management and Climate Change Policy 34
5.2 Laws and Regulations 34
5.2.1 Urban Development Control 34
5.2.2 Building Construction Rules, 1996 35
5.3 Strength and weaknesses of the Existing Policies 36

Chapter 6: Projection of Future Growth by 2031
6.1 Introduction 38
6.2 Projection of Population 38
6.3 Identifications of Future Economic Opportunities 39
6.4 Projection of Land uses 39

Chapter 7: Land Use Development Strategies
7.1 Strategies for Optimum use of Urban Land Resources 40
7.1.1 Land Use Zoning 40
7.1.2 Land Acquisition and Requisition 41
7.1.3 Policy Formulation 41
7.1.4 Different Fiscal Measures 42
7.2 Plans for New Area Development 44
7.3 Areas for Conservation and Protection 46

Chapter 8: Strategies and Policies for Sectoral Development of the Paurashava
8.1 Socio- Economic Sectors 47
8.1.1 Landuse Control 47
8.1.2 Economic Development 47
8.1.3 Employment Generation 48
8.1.4 Housing and Slum Improvement 48
8.1.5 Social amenities and Community Facilities 49

8.1.6 Recreational Facilities 49
8.1.7 Safely and Security 50
8.2 Physical Infrastructure Sectors 50
8.2.1 Traffic and Transportation 50
8.2.2 River Erosion Control & Drainage 51
8.2.3 Utility Services 52
8.3 Environmental Issues 52

Chapter 9: Implementation Issues
9.1 Institutional Capacity Building of the Paurashava 54
9.1.1 Staffing and Training 54
9.1.2 Lack of Automation 55
9.1.3 Town Planning Capacity 55
9.1.3.1 Institutional Framework (Proposed by UGIIP, LGED) 55
9.1.3.2 Lack of Paurashava Town Planning Capacity 57
9.1.4 Legal Aspects 58
9.1.5 Good Governance in Legal Provisions 58
9.1.6 Financial Issues 58
9.1.7 Monitoring, Evaluation and Updating 59
9.1.8 Periodic Review and Updating 59
9.2 Resource Mobilization 60
9.3 Concluding Remarks 60

PART B: URBAN AREA PLAN

Chapter 10: Introduction
10.1 Introduction 61
10.2 Goals and Objectives 61
10.3 Delineation of Planning Areas 62

Chapter 11: Land Use Plan
11.1 Existing and Projected Land Use and Land Use Proposals 63
11.1.1 Existing Land use 63
11.1.2 Estimation on the Requirement of Different Land Uses 63
11.1.2.1 Land Use Standards 63
11.1.2.2 Land Requirement and Proposal 63
11.2 Land Use Zoning 81
11.2.1 Area / Use Zoning 81
11.2.2 Density / Bulk Zoning 81
11.2.3 Height Zoning 82
11.3 Plan Implementation Strategy 82
11.3.1 Land Development Regulations to Implement the Land Use Plan 82
11.3.2 Implementation, Monitoring and Evaluation of the Land Use Plan 84

Chapter 12: Transportation and Traffic Management Plan
12.1 Introduction 87
12.2 Approach and Methodology 87
12. 3 Existing Conditions of Transportation Facilities 87
12.3.1 Road Network 88
12.3.1.1 Roadway Characteristics and Functional Classification 88

12.3.1.2 Mode of Transport 88
12.3.1.3 Intensity of Traffic Volume 88
12.3.1.4 Level of Service: Degree of Traffic Congestion and Delay 89
12.3.1.5 Facilities of Pedestrians 89
12.3.1.6 Primary Considering Issues for Planning 89
12.3.2 Condition Water Transport 90
12.3.3 Condition of Other Transport 90
12.4 Future Projections 90
12.4.1 Travel Demand Forecasting for Next 20 Years 90
12.4.2 Transportation Network Considered 91
12.4.3 Future Traffic Volume and Level of Service 91
12.5 Transportation Development Plan 93
12.5.1 Road Network Plan 93
12.5.2 Design Principle and Standard 93
12.5.3 Proposal for Improvement of the Existing Road Network 96
12.5.4 Proposal for New Road 111
12.6 Plan for Other Transportation Facilities 112
12.6.1 Parking and Terminal Facilities 112
12.6.2 Development of Facilities for Pedestrians, Bicycles and Rickshaws 113
12.6.3 Other Transportation Facilities 113
12.7 Waterway Development/Improvement Option 113
12.8 Transportation System Management (TSM) 115
12.8.1 Strategies for Facility Operations 115
12.8.2 Strategies for Traffic Flow and Safety 115
12.8.3 Strategies for Traffic Management 116
12.9 Plan Implementation Strategies 116

Chapter 13: Drainage and Environnemental Management Plan
13.1 Drainage Management Plan 121
13.1.1 Goals and Objectives 121
13.1.2 Methodology and Approach to Planning 121
13.2 Existing Drainage System Network 122
13.2.1 Man-made Drains 122
13.2.2 Natural Canal and River 124
13.2.3 Topographic Condition of Existing Drainage Network 125
13.2.4 Analysis of Peak Hour Run Off Discharge and Identification of Drainage Outfalls 125
13.3 Plans for Drainage Management and Flood Control 131
13.3.1 Plan for Drain Network Development Drainage Network Plan 131
13.3.2 Proposal for Improvement of the Existing Drain Networks 132
13.3.3 Outfall of Drains 132
13.3.3.1 List of Proposed New Drains 132
13.3.3.2 List of Infrastructure measures for Drainage and Flood Control Network 143
13.4 Implementation Strategies & Principles 145
13.4.1 Plan Implementation Strategies 145
13.4.2 Regulations to Implement the Drainage & Flood Plan 145
13.5 Environmental Management Plan 146
13.5.1 Introduction 146
13.5.2 Goals and Objectives 146
13.5.3 Methodology and Approach to Planning 146
13.5.4 Existing Environmental Condition 146

13.5.4.1 Geo-morphology Geology, Soil, Sub soil Condition 146
13.5.4.2 Climate 146
13.5.4.3 Temperature 147
13.5.4.4 Humidity 147
13.5.4.5 Rainfall 147
13.5.4.6 Wind Directions 147
13.5.4.7 Hydrology 147
13.5.5 Solid Waste and Garbage Disposal 149
13.5.6 Pollutions 149
13.5.7 Natural Calamities and Localized Hazards 150
13.6 Plans for Environmental Management and Pollution Control 151
13.6.1 Proposals for Environmental Issues 151
13.6.1.1 Solid waste management Plan 151
13.6.1.2 Open space, wet-land and relevant features protection Plan 151
13.6.1.3 Ground Water Pollution 152
13.6.1.4 Surface Water Pollution 152
13.6.2 Natural calamities and regular hazard mitigation proposals 153
13.6.2.1 Cyclone 153
13.6.2.2 Flood Protection 153
13.6.2.3 Earth Quake 153
13.6.2.4 Fire Hazard 153
13.6.2.5 Protection Plan addressing encroachment and other relevant issues 154
13.7 Plan Implementation Strategies 154
13.7.1 Regulations to Implement the Drainage and Flood Plan 154
13.7.2 Implementation, Monitoring, Evaluation and Coordination of the Plan 155

Chapter 14: Plan for Urban Services
14.1 Introduction 158
14.2 Consideration for the Preparation of Urban Service 158
14.3 Range and Content of the Urban Service 158
14.3.1 Water Supply 158
14.3.2 Solid Waste 159
14.3.3 Telecommunication 159
14.3.4 Sanitation 159
14.4 Regulations to Address the Proposals 159
14.5 Implementation, Monitoring and Evaluation 160

PART C: WARD ACTION PLAN

Chapter 15: Ward Action Plan
15.1 Introduction 164
15.1.1 Background 164
15.1.2 Content and Form of Ward Action Plan 164
15.1.3 Linkage with Structure and Urban Area Plan 164
15.2 Derivation of Ward Action Plan 164
15.2.1 Revisiting Structure Plan and Urban Area Plan 164
15.2.2 Prioritization 165
15.2.3 Ward Wise Action Plan 165
15.3 Ward Action Plan for Ward No. 01 166
15.3.1 Demography 166

15.3.2 Ward Action Plan Proposals 166
15.3.2.1 Review of Existing Land Use 166
15.3.2.2 Proposed Land Use Zoning 166
15.3.2.3 Proposed Road Infrastructure Development 168
15.3.2.4 Drainage Development Plan 170
15.3.2.5 Urban Services 174
15.4 Ward Action Plan for Ward No. 02 176
15.4.1 Demography 176
15.4.2 Ward Action Plan Proposals 176
15.4.2.1 Review of Existing Land Use 176
15.4.2.2 Proposed Land Use Zoning 176
15.4.2.3 Proposed Road Infrastructure Development 178
15.4.2.4 Drainage Development Plan 179
15.4.2.5 Urban Services 180
15.5 Ward Action Plan for Ward No. 03 183
15.5.1 Demography 183
15.5.2 Ward Action Plan Proposals 183
15.5.2.1 Review of Existing Land Use 183
15.5.2.2 Proposed Land Use Zoning 183
15.5.2.3 Proposed Road Infrastructure Development 185
15.5.2.4 Drainage Development Plan 186
15.5.2.5 Urban Services 189
15.6 Ward Action Plan for Ward No. 04 191
15.6.1 Demography 191
15.6.2 Ward Action Plan Proposals 191
15.6.2.1 Review of Existing Land Use 191
15.6.2.2 Proposed Land Use Zoning 191
15.6.2.3 Proposed Road Infrastructure Development 193
15.6.2.4 Drainage Development Plan 194
15.6.2.5 Urban Services 197
15.7 Ward Action Plan for Ward No. 05 199
15.7.1 Demography 199
15.7.2 Ward Action Plan Proposals 199
15.7.2.1 Review of Existing Land Use 199
15.7.2.2 Proposed Land Use Zoning 199
15.7.2.3 Proposed Road Infrastructure Development 201
15.7.2.4 Drainage Development Plan 203
15.7.2.5 Urban Services 206
15.8 Ward Action Plan for Ward No. 06 208
15.8.1 Demography 208
15.8.2 Ward Action Plan Proposals 208
15.8.2.1 Review of Existing Land Use 208
15.8.2.2 Proposed Land Use Zoning 208
15.8.2.3 Proposed Road Infrastructure Development 210
15.8.2.4 Drainage Development Plan 212
15.8.2.5 Urban Services 215
15.9 Ward Action Plan for Ward No. 07 217
15.9.1 Demography 217
15.9.2 Ward Action Plan Proposals 217
15.9.2.1 Review of Existing Land Use 217
15.9.2.2 Proposed Land Use Zoning 217
15.9.2.3 Proposed Road Infrastructure Development 219
15.9.2.4 Drainage Development Plan 221
15.9.2.5 Urban Services 224

15.10 Ward Action Plan for Ward No. 08 226
15.10.1 Demography 226
15.10.2 Ward Action Plan Proposals 226
15.10.2.1 Review of Existing Land Use 226
15.10.2.2 Proposed Land Use Zoning 226
15.10.2.3 Proposed Road Infrastructure Development 228
15.10.2.4 Drainage Development Plan 229
15.10.2.5 Urban Services 231
15.11 Ward Action Plan for Ward No. 09 234
15.11.1 Demography 234
15.11.2 Ward Action Plan Proposals 234
15.11.2.1 Review of Existing Land Use 234
15.11.2.2 Proposed Land Use Zoning 234
15.11.2.3 Proposed Road Infrastructure Development 236
15.11.2.4 Drainage Development Plan 237
15.11.2.5 Urban Services 240
15.12 Implementation Guidelines 242
15.12.1 Proposals for Mitigation of Identified Issues 242
15.12.2 Comparative Advantage of Master Plan 242
15.13 Conclusion 242

Annexure

Annex-A Team Composition of Master Plan Preparation
Annex-B Paurashava Gazette
Annex-C Permitted Land Use

Annex-D
1. Meeting Minutes
2. Attendance Sheet

Annex-E Proposed Road Inventory
Annex-F Proposed Drain Inventory
Annex-G Mouza Schedule of Waterbody

Annex-H
1. Structure Plan Map
2. Land Use Plan Map
3. Transportation and Traffic Management Plan
4. Drainage and Environmental Management Plan

LIST OF TABLES

		Page No.
Table 2.1	Mouza wise area of GauranadiPaurashava	8
Table 3.1	Population distribution of Gauranadi Paurashava Area	11
Table 5.1	Functions in brief prescribed in the Local Government (Paurashava) Act, 2009	20
Table 6.1	Projected Population during the Year 2015-2031	39
Table 7.1	Broad Land use Zones	40
Table 11.1	Existing Land use of Gauranadi Paurashava	63
Table 11.2	Proposed Major Land use of Gauranadi Paurashava	64
Table 11.3	Development Proposal for Residential Zone of Gauranadi Paurashava	68
Table 11.4	Development Proposal for Commercial Zone of Gauranadi Paurashava	68
Table 11.5	Development Proposal for Industrial Zone of Gauranadi Paurashava	69
Table 11.6	Development Proposal for Government Services of Gauranadi Paurashava	70
Table 11.7	Development Proposal for Open Spaces of Gauranadi Paurashava	71
Table 11.8	Development Proposal for Recreational Facilities of Gauranadi Paurashava	71
Table 11.9	Development Proposal for Health Facilities of Gauranadi Paurashava	72
Table 11.10	Development Proposal for Community Facilities of Gauranadi Paurashava	73
Table 11.11	Development Proposal for Education and Research Zone of Gauranadi Paurashava	73
Table 11.12	Development Proposal for Transportation Facilities of Gauranadi Paurashava	75
Table 11.13	Development Proposal for Utility Services of Gauranadi Paurashava	75
Table 11.14	Land Requirement, Existing and Proposed Land use of Gauranadi Paurashava for the year 2031	77
Table 12.1	Type wise length and area of Road	88
Table 12.2	Standard of Roads Proposed by PMO	93
Table 12.3	Standard for Future Development of the Road Network	93
Table 12.4	Phase wise Road widening Proposals of Existing Road	97
Table 12.5	Proposed Roads of Gauranadi Paurashava According to Hierarchy	111
Table 12.6	Phase wise Newly Proposed Road	111
Table 13.1	Existing Inventory of Drains	122
Table 13. 2	Drainage Coverage of Existing Khals in Gauranadi Paurashava	124
Table 13.3	Ward wise Area Coverage of existing waterbodies at Gauranadi Paurashava	125
Table 13.4	Manning's "N" Values for Channel Flow	127
Table 13.5	Storage Coefficients for Flat Land	127
Table 13.6	Modified Rationale Method Runoff Coefficients	127
Table 13.7	Summary of proposed drain	132
Table 13.8	Proposals of new drain	132
Table 15.1	Population Statistics of Ward No. 01	166
Table 15.2	Comparative Scenario of Existing and Proposed Land Uses of Ward No. 1	166
Table 15.3	Road Network Proposal at Ward no. 01	168
Table 15.4	Drainage Development Plan Proposals for ward 01	170
Table 15.5	Urban Service Development Proposals for ward 01	174
Table 15.6	Population Statistics of Ward No. 02	176
Table 15.7	Comparative Scenario of Existing and Proposed Land Uses of Ward No. 2	176
Table 15.8	Road Network Proposal at Ward no. 02	178
Table 15.9	Drainage Development Plan Proposals for ward 02	179
Table 15.10	Urban Service Development Proposals for ward 02	180
Table 15.11	Population Statistics of Ward No. 03	183
Table 15.12	Comparative Scenario of Existing and Proposed Land Uses of Ward No. 3	183

Table 15.13 Road Network Proposal at Ward no. 03 185
Table 15.14 Drainage Development Plan Proposals for ward 03 186
Table 15.15 Urban Service Development Proposals for ward 03 189
Table 15.16 Population Statistics of Ward No. 04 191
Table 15.17 Comparative Scenario of Existing and Proposed Land Uses of Ward No. 4 191
Table 15.18 Road Network Proposal at Ward no. 04 193
Table 15.19 Drainage Development Plan Proposals for ward 04 194
Table 15.20 Urban Service Development Proposals for ward 04 197
Table 15.21 Population Statistics of Ward No. 05 199
Table 15.22 Comparative Scenario of Existing and Proposed Land Uses of Ward No. 5 199
Table 15.23 Road Network Proposal at Ward no. 05 201
Table 15.24 Drainage Development Plan Proposals for ward 05 203
Table 15.25 Urban Service Development Proposals for ward 05 206
Table 15.26 Population Statistics of Ward No. 06 208
Table 15.27 Comparative Scenario of Existing and Proposed Land Uses of Ward No. 6 208
Table 15.28 Road Network Proposal at Ward no. 06 210
Table 15.29 Drainage Development Plan Proposals for ward 06 212
Table 15.30 Urban Service Development Proposals for ward 06 215
Table 15.31 Population Statistics of Ward No. 07 217
Table 15.32 Comparative Scenario of Existing and Proposed Land Uses of Ward No. 7 217
Table 15.33 Road Network Proposal at Ward no. 07 219
Table 15.34 Drainage Development Plan Proposals for ward 07 221
Table 15.35 Urban Service Development Proposals for ward 07 224
Table 15.36 Population Statistics of Ward No. 08 226
Table 15.37 Comparative Scenario of Existing and Proposed Land Uses of Ward No. 8 226
Table 15.38 Road Network Proposal at Ward no. 08 228
Table 15.39 Drainage Development Plan Proposals for ward 08 229
Table 15.40 Urban Service Development Proposals for ward 08 231
Table 15.41 Population Statistics of Ward No. 09 234
Table 15.42 Comparative Scenario of Existing and Proposed Land Uses of Ward No. 9 234
Table 15.43 Road Network Proposal at Ward no. 09 236
Table 15.44 Drainage Development Plan Proposals for ward 09 237
Table 15.45 Urban Service Development Proposals for ward 09 240

LIST OF MAPS

		Page No.
Map 3.1	Regional Linkage of Gauranadi Paurashava	14
Map 7.1	Structure Plan of Gauranadi Paurashava	43
Map 11.1	Existing Land use of Gauranadi Paurashava	66
Map 11.2	Proposed Land use Plan of Gauranadi Paurashava	67
Map 12.1	Existing Road Network of Gauranadi Paurashava	92
Map 12.2	Proposed Road Network of Gauranadi Paurashava	114
Map 13.1	Existing Drainage Network of Gauranadi Paurashava	123
Map 13.2	Proposed Drainage Network of Gauranadi Paurashava	144
Map 14.1	Proposed Urban Services of Gauranadi Paurashava	163
Map 15.1	Proposed land use of ward No. 01	167
Map 15.2	Proposed Road and Drainage Network of ward No. 01	173
Map 15.3	Development Proposals of ward No. 01	175
Map 15.4	Proposed land use of ward No. 02	177
Map 15.5	Proposed Road and Drainage Network of ward No. 02	181
Map 15.6	Development Proposals of ward No. 02	182
Map 15.7	Proposed land use of ward No. 03	184
Map 15.8	Proposed Road and Drainage Network of ward No. 03	188
Map 15.9	Development Proposals of ward No. 03	190
Map 15.10	Proposed land use of ward No. 04	192
Map 15.11	Proposed Road and Drainage Network of ward No. 04	196
Map 15.12	Development Proposals of ward No. 04	198
Map 15.13	Proposed land use of ward No. 05	200
Map 15.14	Proposed Road and Drainage Network of ward No. 05	205
Map 15.15	Development Proposals of ward No. 05	207
Map 15.16	Proposed land use of ward No. 06	209
Map 15.17	Proposed Road and Drainage Network of ward No. 06	214
Map 15.18	Development Proposals of ward No. 06	216
Map 15.19	Proposed land use of ward No. 07	218
Map 15.20	Proposed Road and Drainage Network of ward No. 07	223
Map 15.21	Development Proposals of ward No. 07	225
Map 15.22	Proposed land use of ward No. 08	227
Map 15.23	Proposed Road and Drainage Network of ward No. 08	232
Map 15.24	Development Proposals of ward No. 08	233
Map 15.25	Proposed land use of ward No. 09	235
Map 15.26	Proposed Road and Drainage Network of ward No. 09	239
Map 15.27	Development Proposals of ward No. 09	241

LIST OF FIGURES

		Page No.
Fig 1.1	Diagram of Master Plan Preparation	3
Fig 2.1	Content of Structure Plan	9
Fig 9.1	Scope of Work for Planning Division	56
Fig 9.2	Organogram for a "B" Class Paurashava	57
Fig 9.3	Proposed Urban Planning Division for "B" Class Paurashava	57
Fig 12.1	Channelization Measures at Major Intersections	93
Fig 12.2	Corner Plot Widening at Intersections	94
Fig 12.3	Typical Cross-Section of Various Types of Roads	96
Fig 13.1	Earthen Primary Drain	129
Fig 13.2	Typical RCC Primary Drain	129
Fig 13.3	Typical Secondary Drain	129
Fig 13.4	Typical Tertiary Drain	130
Fig 13.5	Plot and Block Drain	130
Fig 13.6	Bridge and Culvert	131
Fig 13.7	A schematic view of Drainage sluice, pipe sluice and siphon on embankment which relieve drainage congestion	131
Fig 13.8	Wind Speed Data of Several Years in Barguna	147
Fig 13.9	Cyclone, Flood, and Earthquake Condition in Gauranadi Paurashava	148

List of Abbreviations and Acronyms

BBS	:	Bangladesh Bureau of Statistics
BDT	:	Bangladeshi Taka (Currency)
BM	:	Bench Mark
BTCL	:	Bangladesh Telecommunication Company Limited
BWDB	:	Bangladesh Water Development Board
CBO	:	Community Based organization
CS	:	Cadastral Survey
DGPS	:	Differential Global Positioning System
EMP	:	Environmental Management Plan
EPA	:	Environment Protection Authority
GCP	:	Ground Control Points
GIS	:	Geographic information System
Govt.	:	Government
GPS	:	Global Positioning System
H.Q.	:	Head Quarter
H/hold	:	Household
JICA	:	Japan International Cooperative Agency
KM/ km	:	Kilometer
LAN	:	Local Area Network
LCC	:	Lambert Conformal Conic
LGED	:	Local Government Engineering Department
LPG	:	Liquid Petroleum Gas
MV	:	Motorized Vehicle
NGO	:	Non-Government Organizations
NMV	:	Non Motorized Vehicle
O-D	:	Origin – Destination
Orgs.	:	Organizations
PCU	:	Passenger Car Unit
PD	:	Project Director
PMO	:	Project Management Office
R.F.	:	Representative Fraction
RHD	:	Roads and Highways Department
RoW	:	Right of Way
RS	:	Revenue Survey
RTK-GPS	:	Real Time Kinematics Global Positioning System
SoB	:	Survey of Bangladesh
SPSS	:	Statistical Package for Social Science
TCP	:	Temporary Control Point
TIN	:	Triangulated Irregular Network
ToR	:	Terms of Reference

Part A. Structure Plan

1.1 Introduction

A massive program to prepare master plan of 223 Paurashavas and Kuakata Tourism Centre under the project titled "Upazilla Towns Infrastructure Development Project' (UTIDP) funded by the Government of Bangladesh has been taken by Local Government Engineering Department (LGED), Ministry of Local Government, Rural Development and Cooperatives, Government of the People's Republic of Bangladesh. The aim of master plans for the Paurashavas is to identify the infrastructural facilitates needed for overall socio-economic and physical development and activities of the people living in the respective Paurashava so as to improve their living conditions.

However, the main rationale of preparing master plan of Gauranadi Paurashava is to prepare Land Use Plan, Ward Action Plan, and related Infrastructural Plans as visualized in the Terms of Reference (TOR). The Master Plan of Gauranadi Paurashava is to be prepared based on the topography survey, physical feature survey, land use survey, socio-economic survey and other different types of sector surveys/studies. However, the plan consists of three volumes known as Master Plan. These are:

- **Structure Plan**
- **Urban Area Plan**
  - Landuse Plan;
  - Transportation and Traffic Management Plan;
  -Drainage and Environmental Management Plan; and
  -Plan for Urban Services.
- **Ward Action Plan**

The following features have been addressed in preparing the master plan for Gauranadi Paurashava:

- Guide/regulate planned development of infrastructure and facilities;
- Facilitate socio-economic development activities;
- Ensure conservation of natural streams and addressing properly environmental concerns;
- Apprehend existing unplanned growth;
- Stop further encroachment of the fertile agricultural lands and potential beach areas;
- Proper and optimal use of land;
- Facilitate provision of utilities, services and facilities for the resident population;
- Spatial layout for public sector, private sector and public- private sector investments; and
- Facilitate conservation of bio-diversity.

1.2 Philosophy of the Master Plan

The master plan will facilitate among the people of a defined place for improving their socio-economic condition by providing all supportive facilities for them. Moreover, considerable care has to be given to improve their quality of life through providing some other facilities such as recreational, municipal facilities etc. But it should be kept in mind that master plan is a guideline for development and control of growth in a systematic manner. Without proper regulation or rules it would not be possible to manage the master plan. However, appropriate authority will be obligatory for the execution of the master plan.

1.3 Objectives of the Master Plan

According to the Terms of Reference (TOR) the objectives of the Master Plan are as follows:

- Find out problems and potentialities of developing various sectors;
- Facilitating the provision for all types of infrastructure and service facilities needed for development as well as socio-economic facilities and infrastructure for the local people;
- Supporting protection of the local environment/ecology;
- Preparing a 20-year Master Plan used as tool to guide and regulate planned physical growth and development;
- Facilitating job opportunities for the local people so as to address the issue of poverty reduction in line with the national policy of poverty reduction; and
- Keeping provision for short, medium and long-term investment plans by the public sector, the private sector and the PPP in implementing the Gauranadi Paurashava plan.

1.4 Conceptualization

Structure Plan

The term Structure Plan includes a full analysis of the existing scenarios, emphasize the existing condition of different sectoral infrastructures, identification of sectoral issues and interventions, recommendation of solution for each sector and setting proposal and recommendations for the future action to be taken within the mentioned period, say 20 years. This is a longer-term plan.

Urban Area Plan

The term Urban Area Plan (UAP) is prepared for managing and promoting development over medium term on the basis of the strategies set by the longer-term structure plan. Basically the UAP is an interpretation of the Structure Plan over the medium term (10 years). The coverage of the UAP is existing urban areas and their immediate surroundings with the purpose of providing development guidance in these areas where most of the urban development activities are expected to take place over the next 10 years. Delineation of the Urban Area Plan should be based on the urban growth area as identified in the Structure Plan. It will contain more details about specific programs and policies that require to be implemented over the medium term. The UAP is consisted with the Land Use plan, Transportation and traffic Management plan, Drainage and Environmental Management Plan and Community Services Plan.

Ward Action Plan

This is called short-term plan, say 5 years. Individual Ward of the Paurashava is deserved scope of this plan. In the Paurashava, 9 Ward Action Plan is being prepared. The plan includes review of the existing situation of the Ward with respect to land use, community facilities, public services, utilities, infrastructures, etc. Problems need immediate attention and scope of development is the basis of this plan. The problems and their recommendations as prescribed in the Urban Area Plan are being emphasized for immediate implementation with the help of ward Action Plan

1.5 Approach and Methodology

The project is aimed for development of infrastructure and services for the Paurashava with optimum provision of opportunities for local people and extending services to surrounding areas.




Fig 1.1: Diagram of Master Plan Preparation

1.5.1 Demarcation of the Planning Area

The demarcation of the study area is an important task in order to gather information and data. As per TOR, the study area or the planning area should be determined by the consultants reviewing its growth potential, geographical and geological context, tourism aspects and other relevant issues. Determining the planning area for Gauranadi Paurashava, the consultants had exercised above issues and fixed the area of the Paurashava. The total area of the Gauranadi Planning Area is 4303.20 acres (17.41 sq km) and there is no extended area in the structure plan. However, in demarcating the study area, the following aspects have been considered:

- the existing and future road linkages;
- physical growth directions; and
- physical features of the area and the surrounding areas.

1.5.2 Preparation of the Base Map

The following steps have been followed to prepare the base map:

- Collection of RS Mouza Maps;
- Identification of GCP (TIC) on Digitized Maps;
- Scanning of Mouza Maps;
- Edge Matching and Preparation of Study Area Map;
- Digitization of RS Mouza Maps;
- Edit Plot Check of Digitized Coverage; and
- Geo-referencing of Mouza Maps.

1.5.3 Surveys

1.5.3.1 Topographic Survey

Topography survey was conducted by using RTK-GPS and Total Station (TS) survey technique. Topographic survey has included the following features:

- Land levels/spot levels for contours at 50m intervals with denser intervals for undulations;
- Alignment and crest levels (not exceeding 50m) of roads, embankments, dykes and other drainage divides;
- Alignment of rivers, lake, canal, drainage channels etc;
- Outline of bazars, water body, swamps and forest, etc;
- Type, width, length and name of road above flood level;
- For closed boundary/outline of homestead, water bodies, swamps, forest etc. junctions, spot heights or land levels will be taken roughly at 10m intervals in normal cases and contour will be at 0.3 meter interval; and
- Crest levels will not exceed 50m along all dyke, roads and drainage divide.

1.5.3.2 Physical Feature Survey

Physical feature surveys have provided the basis for understanding many planning problems. To know existing information about physical features of Gauranadi Paurashava, physical feature survey was carried out. The physical features map was prepared on RS/CS map on 1''=165´ scale showing the following features:

- Cross Section, long section, type, width, length and name of road, road level above datum, slopes, flooding lands, slopes, borrow pit;

- Identification of any bridge or culvert on the road with their length & width and span of the bridge, condition of abutments, condition of the deck, wing walls abutments;
- Type, size, inlet and outlet location of drain along with flow direction, width of the canal, place of encroachment;
- Type of sewer system, size, type and location of sewerage line, location of bins, identification of any other sewerage collection system;
- Identification of the water supply system, location of overhead water tank and its capacity, catchments area of overhead tank;
- Identification, location and capacity of electricity, telephone service; and
- If any, new items identified during the survey period will also be surveyed;

1.5.3.3 Land use Survey

Utilizing the Base Map, (physical features survey overlay on survey map) the land use map was prepared indicating the broad categories of land uses. And it described using a suitable land use code reference. The characteristics of each land use area were described in the survey report. The Land Use Maps were prepared on the Base Map.

1.5.3.4 Socio-economic Survey

The planning principle directs towards people and their needs concerning housing, shopping, recreational, employment, education, and health services, etc. Detail information on population is essential for estimation of land requirement for future needs. It is also essential for allocating land between various competing uses.

A socio-economic survey for collection of primary data was conducted at Gauranadi Paurashava. The sample size of socio-economic survey was 5% as per ToR. It is clearly understood that the purpose of this socio-economic survey is to obtain the project related socio-economic data on households in the project area. All data were collected from the primary sources through a specially designed socio-economic questionnaire survey.

1.5.3.5 Drainage and Environmental Study

The consultants have undertaken a drainage survey and environmental study at Gauranadi Paurashava. The preparation of master plan for the next 20 years for the Paurashava seeks environmental investigation of development activities that will be undertaken in next 20 years. The issues/aspects that were investigated as per the TOR are as follows:

Existing Infrastructure

- Drainage
  - Man-made (drainage network, gradient, attachment area, out let)
  - Natural (flow direction, hydrology, usability)
- Water supply (network, coverage)
- Sewerage (location/network, condition)
- Solid waste management-existing system, location of garbage disposal, management aspect

Environmental Aspects

- Humidity, rainfall and temperature of the study area;
- Climatic and Disaster Condition, Soil and topographic Condition;
- Environmental Pollution (air, water and noise pollution);
- Identification of hazards;

- Existing mitigation/coping measures, if any; and
- Identification of environmental protection laws/regulations.

1.5.4 Data and Information Management

All the data and information collected from the primary and secondary sources have been sorted/edited and computerized and analyzed. Projections were done in the case of populations so as to estimate the spatial requirements of different services and facilities for the resident population. All these were accomplished in line with the objectives of the plan so as to estimate the land requirements for different service and facilities. Elaborate information regarding projection and estimation of land requirements are available in the following concern chapters.

1.5.5 Adopted Planning Standards

The planning standard provided by the PMO office of UTIDP has followed to prepare the Master Plan.

1.5.6 Stakeholders' Consultations

After preparation of a draft plan, a consultation meeting has conducted with the concerned authority and local people of Gauranadi Paurashava to acquire aspirations, demand, problems and prospects of the area and community as well as the views of service proving agencies and local administration and share the master plan with them. After incorporating their views and demands, the master plan has prepared.

1.6 Scope of Work

The scope of the work is to cover all aspects related to the preparation of Master Plan / Urban Area Plan which include Land Use Plan, Traffic Management Plan, Drainage and Environment Plan and Ward Action Plan. Prepare a plan to set out proposed Master Plan at three levels namely Structural Plan, Master Plan / Urban Area Plan and Ward Action Plan. In order to prepare these plans following activities has been conducted:

- Visits to the Gauranadi Paurashava have been made in different stages for the preparation of Master plan;
- An inception meeting at the Paurashava level has been conducted to inform Paurashava about the scope of work for the preparation of Master Plan for 20 years development vision;
- The study area has been determined on the basis of existing condition demand of the Paurashava and the potentiality for future development;
- Different types of survey activities have been conducted from primary and secondary source;
- A comprehensive drainage master plan for a period of 20 years has been prepared;
- Assessing existing condition an integrated transportation plan is proposed for next 20 years;
- Ward action plan with list of priority schemes for the development of roads parks and other social facilities are proposed which need to implement during the first five years of the plan period;
- Consultation meeting has been organized with the help of concerned Paurashava and local stakeholders; and
- Master plan and report with required standard have been prepared and submitted as required TOR.

2.1 Background of the Paurashava

Gauranadi upazila is situated in Barisal district. It is located between $22^0 53'$ and $23^0 04'$ north latitudes and between $90^0 08'$ and $90^0 22'$ east longitudes. It is bounded on the north by Kalkini Upazila of Madaripur Zila, on the east by Muladi Upazila, on the south by Wazirpur and Babuganj Upazilas and on the west by Agailjhara Upazila. Gauranadi Paurashava occupies an area of 17.41 sq. km. It consists of 9 Wards.

Gauranadi is the second smallest Thana of Barisal district is located at the southern part of the country. Gauranadi became thana in 1806. Gauranadi Paurashava consists of 9 Wards and 17 mauzas. The Paurashava was established in 2nd October 1996. However, Gauranadi Paurashava consists of 9 wards with an area of 17.41 sq.km (Field Survey, 2010).

2.2 Vision of the Structure Plan

The vision of the Structure Plan is oriented with the policy development for the project area in relation with national and regional policies or framework through close liaison between planning authority and government departments. In a word, it will provide the basis of Co-coordinating decisions. It will be considered as the upper level planning guideline component for next two levels of planning i.e. Urban Area Plan and Ward Action Plan. Structure Plan will identify the urban growth area based on which the Master Plan area will be delineated. It will set policy framework which will be more detailed in Urban Area Plan. Moreover, it will provide the basis of development control in pursuing the Urban Area Plan. Subsequently, the indication of action areas and the nature of treatment in different sectors will also be considered here. It will define the location of action areas but not the boundaries, also the priority, possible effect of actions proposed. Pertaining with Action Area Plan, the combination of Public and Private Agency or individuals' involvement to implement the proposed actions will be stated here.

2.3 Objectives of the Structure Plan

The main objectives of preparing master plan of Gauranadi Paurashava are to prepare Structure Plan, Urban Area Plan and Ward Action Plan as envisaged in the Terms of Reference (TOR). The structure plan has the following objectives:

- To identify the main development issues facing the Paurashava (town) with major opportunities and constraints;
- To identify the growth and possible physical expansion of the city as foreseen considering economic base and Trend;
- To provide a view of required and suitable lands for future physical expansion;
- To develop the sector wise strategies pursuing the future development control in a desirable direction; and
- To identify the resources which are needed to strengthen the financial resources of the town
  - Establishment of inter sectoral goals, policies and general proposals for urban spatial development, and
  - Provide framework for the next hierarchy of Gauranadi Paurashava Master Plan and Ward action plan.

2.4 Content and Format of Structure Plan

As per Terms of References (TORs) the Structure Plan of Gauranadi Paurashava has been prepared for 20 years in long term. The Urban Area Plan (UAP) will be an interpretation of

Structure Plan in Medium Term and Ward Action Plan in Short Term. Figure 2.1 shows the content of structure plan.

Demarcation of Structure Plan Area

The issues have been adopted for demarcating the study area for Gauranadi Paurashava comprises the following:

- Study the existing Paurashava boundary with existing growth trend and pattern Analysis of the physical development constraints and potentialities;
- Study of the existing and future national, regional and local linkages with Gauranadi;
- Consultation with local governments; and
- Consultation with local people, members of civil societies and other stakeholders.

According to the gazette notification, the Gauranadi Paurashava comprises 17 mouzas. The total Paurashava area is about 4303.20 acre (about 17.41 sq.km). The following table shows mouza wise area of Gauranadi Paurashava. **Map 1.1** delineates the structure plan area of Gauranadi Paurashava.

Table 2.1: Mouza Wise Area of Gauranadi Paurashava

Name of Mouza	J.L. No	Sheet No.	Map Category	Area	
				in Acre	in Sq.km
Asokati	138	0	RS	271.47	1.10
Baniasuri	75	0	RS	192.61	0.78
Bara Kasba	69	1	RS	156.76	0.63
		2	RS	231.27	0.94
Char Gadhatali	72	0	RS	106.49	0.43
Dakshin Bijoypur	134	0	RS	264.52	1.07
Dakshin Palardi	71	0	RS	196.81	0.80
Diasur	152	0	RS	280.61	1.14
Gerakul	140	0	RS	247.97	1.00
Harisana(Kasemabad)	141	1	RS	464.94	1.88
		2	RS	299.09	1.21
Lakherajkasba	66	0	RS	133.81	0.54
Saora	133	0	RS	174.26	0.71
Sundardi	63	1	RS	482.87	1.95
		2	RS	20.12	0.08
Tarkir Char	62	0	RS	120.24	0.49
Tikhasar	139	0	RS	192.30	0.78
Uttar Bijaypur	73	0	RS	191.71	0.78
Uttar Palardi	70	0	RS	144.31	0.58
Gobardhan	74	0	RS	131.05	0.53
Total				**4303.20**	**17.41**

Source: Paurashava, 2012.




Fig 2.1: Content of Structure Plan

3.1 Social Development

In Gauranadi Paurashava, about 66.8% and 24.5% households concentrated in the fringe area and potential core area. This indicates that Gauranadi is not urbanized area where mainly commercial development concentrated on core area, influential or affluent people live in the potential core area and the urban poor those are always likely to live in fringe area.

The educational status of an area is the major determinant of society building. As per BBS 2011, in Gauranadi Paurashava the literacy rate is about 68.9% where the national level the literacy rate is about 51.8%.

It is seen that almost all the wards have similarity in occupation, and small business is dominant in every ward. As regards, 5.2% of the people are unemployed (Socio Economic Survey, 2010).

Most of the households (95.5%) own their house by inheritance whereas about 3.7% of the households purchased their house. Considering other assets it has been observed that according to BBS 2001, about 54.95% households have own agricultural lands.

There are different types of income groups of people living at Gauranadi Paurashava area. About 38.9% of the households' incomes are within the range of Tk 5001.00 – Tk.10, 000.00 per month. Further, 30.2% of the household have income per month Tk. 2500.00 – Tk. 5000.00; 14.9% Tk. 10,001.00 - Tk. 15,000.00 and 5.7% Tk. 15,001.00 – Tk. 20,000.00.

3.2 Economic Development

In Bangladesh, the economy is composed of formal and informal sectors. But statistics on the size of the informal economy in Bangladesh are difficult to find out. Formal economic activities sector of Gauranadi Paurashava mainly comprises Trade and Commerce, Agriculture, Service Sector, Industry, Transport and so on. The major occupational group is involved in agricultural activity (Socio Economic Survey, 2010). About 61.9% of all the households' members irrespective of sexes of Gauranadi Paurashava are within the age group of 16-57 years. This indicates majority of the household members are economically active group. Besides, the Torki River which has been passed beside the Paurashava area can be used for the development of fishing industry.

3.3 Physical Infrastructure Development

There are some segmented and sporadic physical developments occurred over the years in different parts of the Gauranadi Paurashava. There is a river called Torki River and many khals with total area of 68.89 acre within Paurashava boundary. Among them, the Rizia Khal divides Gauranadi Paurashava into three parts such as north, west and south. Most of the lands in the northern part of the Paurashava at the intersection point of Ward No. 1, 2 and 3 are developed as residential and commercial areas. Most of the commercial areas are concentrated at the middle part of the Paurashava at the intersection point of Ward No. 4, 5, 6 and 7 at the right side of Torky Bondor road.

In the planning area, highest percentage of lands is devoted for agricultural purpose, major concentration is observed in Ward No. 1, 6, 7, 8 and 9. Residential structures are mostly developed in core and potential core areas. Every Ward preserves more or less residential land and Ward No. 1, 3, 5, 6, 7 and 8 have relatively high concentrated residential areas.

Most of the roads in all the Wards are pucca and the overall condition is moderate, except access roads. All the areas are well linked with road network but some roads are narrow (especially access roads), need to be widened. Existing natural features having khals are playing vital waterways in connecting the area with the Bay of Bengal through Torki River.

3.4 Environmental Growth

Gauranadi Paurashava is located in the southern part of Bangladesh. It is very close to the Bay of Bengal. It enjoys generally a sub-tropical monsoon climate. While there are six seasons in a year, three namely, the Winter, the Summer and the Monsoon are prominent. Winter which is quite pleasant begins in December and ends in February which ranges from of 7.8^{o}-14° C. Establishment of Water Treatment Plant beside the River will be required for ensuring the good drinking water. In addition, it is possible to preserve the environment before any advanced development as industrial development is very low.

3.5 Population

Gauranadi Paurashava is about 17.41 sq. kilometers and comprises around 42438 numbers of people (male 21205 and female 21233). Area of Gauranadi Paurashava is not a high density area compared to upazila density. The average population density of Gauranadi Planning area is 2438 person /sq.km.

Table 3.1: Population Distribution of Gauranadi Paurashava Area at 2011

Ward	Population at 2011	Area (acre)	Density (person per acre)
Ward 1	6376	502.99	13
Ward 2	4298	405.86	11
Ward 3	4114	428.83	10
Ward 4	3971	341.12	12
Ward 5	5737	298.79	19
Ward 6	4987	497.02	10
Ward 7	4776	535.98	9
Ward 8	4428	528.58	8
Ward 9	3751	764.03	5
Total	**42438**	**4303.20**	**10**

Source: BBS 2011, Community Series, Zila: Barisal, 2012, BBS 2011 and Field Survey, 2010

3.6 Institutional Capacity

In Gauranadi Paurashava, the plan implementation and main power executing authority will be the Paurashava itself. Therefore, effective execution capacity in terms of revenue generation, manpower capacity of the Paurashava is required to evaluate to implement the plan. There are two major component of income generation. These are: 1) Revenue, 2) Development.

In most of the Paurashavas of Bangladesh the main income source is Revenues from different sources. But in Gauranadi Paurashava, in last 5 years the income from development section has contributed about 72% on an average to the overall income of Paurashava whereas revenue sector has contributed about 28% on an average to the overall income.

Analyses reveal that highest income expenditure ratio (1.09) is observed in 2008-09 year and lowest ratio (0.94) is observed in 2006-07. It indicates that in 2006-07, the expenditure was greater than income and in 2008-09 the income was higher than the expenditure. Besides, in the year 2010-11, the income expenditure ratio shows a balanced condition (1.00).
Existing Manpower of Gauranadi Paurashava is consisted of 1 elected Mayor, 12 councilors (9 male and 3 female), and 3 Departments. These are:

1. Engineering Department;
2. Administrative Department; and
3. Health, Family Planning & Conservancy Department.

These three departments comprised of 27, 26 and 16 persons respectively. The manpower of Gauranadi Paurashava is not so much capable to implement the Paurashava Master Plan. The Existing posts are not fulfilled by the required manpower. Besides, it may require more efficient, technical and experienced manpower to implement the master plan. It has been observed that in Engineering Department about 35% posts are vacant, in Administration Department about 33% posts are vacant and in Health and Family Planning Department the percentage of vacant posts are 20%.

Moreover at present, there is no town planning unit at Gauranadi Paurashava. Engineering Department is responsible for monitoring the development control issues of this Paurashava.

3.7 Urban Growth Area

As per as the physical growth directions, the Paurashava is expanding along the Torky Bondor Road. This is the important network connect northern and southern part of the Paurashava and also links the Paurashava with other areas of Gauranadi Upazila. Canals play a vital role in the development of Gauranadi Paurashava as major concentration of the commercial areas. Commercial development is already expanding along with the canals. Moreover, agricultural use spreads all over the Paurashava sporadically.

Existing growth agglomerations along the potential core area accommodate mostly the residential development. Specially for getting advantage of high lands, residential areas developed on those areas that are accelerating growth of the Paurashava on the central part.

Scattered industrial development is found in the Paurashava. It is required to concentrate industrial development in a specific area rather than expanding towards other areas. The industrial development should not be mixed-up with residential development. On the other hand, existing industrial area is being mixed with the commercial area.

Educational, religious and other community facilities should be provided in consideration of Ward-wise population as explained in Chapter-4. Potentialities of zoning for important landuse can be considered in determining the present growth of Paurashava.

Moreover, present and proposed road network would be a major determinant for growth of the Paurashava.

3.8 Catchments Area

Catchment area of the Gauranadi Paurashava is calculated according to the agriculture commodities and movement of dwellers for rendering services. From Gauranadi Paurashava, agriculture commodities marketed to the Dhaka, Barisal, Khulna and Pirojpur. Rice, jute, mustard and sugarcane are the major agriculture products marketed in those areas. Except agriculture production, fish and poultry productions also distributes in those areas. The Paurashava dwellers for rendering their services go to the Dhaka, Barisal and Pirojpur.

3.9 Land Use and Urban Services

Land use is one of major determinant of planning especially in a developing country where technical component is being upgraded still. Suitable land use planning not only controls the development but also it can affect the traffic generation and degeneration of a particular area. At Gauranadi Paurashava, there is dominance of agricultural land (about 65.00% of the total) followed by residential land (about 18.57%) and 11.14% water bodies.

Each ward is more or less covered by residential land use. Most of the ward area shares more than 19% residential land use except ward no. 2, 8 and ward no. 9. The highest residential land

use (30.72%) is observed in ward no. 5. Most of the wards have commercial land use in some extent. Among them, ward no. 2, 3, 5, 8 and 9 have only 0.5 to 0.8% uses which are negligible. The major commercial and administrative development has been observed in ward no. 5 with 7.66% coverage. In Gauranadi Paurashava area there is little industrial activities. Ward no.1, 2, 3, 4, 6, 8, and 9 shares 0.01 to 0.56% land for industrial purpose.

The condition of recreational facilities in Paurashava area is not good enough. At present, ward no. 3 (0.07%) and ward no. 6 (0.05%) have potentiality of recreational facility though lands are still available as open space.

3.10 Paurashava Functional Linkage with Regional and National Network

Barisal district is located at the southern part of Bangladesh. The district is bounded by Madaripiur, Shariatpur, Chandpur and Lakshmipur districts on the north, Patuakhali, Barguna and Jhalokati districts on the south, Bhola and Lakshmipur districts on the east and Jhalokati, Pirojpur and Gopalganj districts on the west

There is an airport located just outside the Paurashava town. It has frequent air services to Dhaka run by different private airlines. Due to its location and easy access to both riverine and marine navigation channels, Barisal has become a transshipment center for rice, hides and pulses. Bakery, textile, pharmaceutical products are the output of few industrial installation.


In the eastern part of the Gauranadi Paurashava, there is a river called Torki River (a branch of Areal Kha River). This river is the outfall of the Paurashava.


Road network of Gauranadi Paurashava presents both the internal road network of the Paurashava and the regional linkage. A regional highway flows through Gauranadi Paurashava and connects other districts of Barisal Region. This regional highway connects Dhaka, Barisal and Patuakhali and intersects Gauranadi. So, regular inter-district bus services are available from Gauranadi to the following destinations:


Gauranadi to Barisal
Gauranadi to Khulna
Gauranadi to Barguna
Gauranadi to Patuakhali
Gauranadi to Dhaka

Most of the trading activities are concentrated in the bazar areas of the Paurashava. People from different locations come here for daily necessities. A well-defined master plan is needed for the Paurashavas to accommodate all physical developments enhancing socio-economic developmental so as to boost up living condition of the people.

Map 3.1: Regional Linkage Map of Gauranadi Paurashava







3.11 Role of Agencies for Different Sectoral Activities

Gauranadi is a B Class Paurashava. The collaboration among different agencies is essential to execute the plan and make a linkage with national plan and investment. Therefore, the role of different agencies or organizations is required to identify and understand.

LGED

The major functions of LGED can be broadly categorized as follows:

- Rural infrastructure development;
- Urban infrastructure development; and
- Small scale water resources development

Urban Infrastructure Development consists of Planning and implementation of integrated town centre (bus terminals, markets etc.), municipal roads, bridge/culverts, drainage, water supply and sanitation projects, solid waste management projects, slum upgrading projects, development of Land use plan, improve planning & management capacity and resources mobilization & management, Institutional development of municipalities through training and computerizations, preparation of district and upazila town master plan, Development of technical specifications and manuals for construction of urban infrastructures.

RHD

RHD is responsible for the construction and the maintenance of the major road and bridge network of Bangladesh. It has a sustainable capacity to plan, manage and deliver its full range of responsibilities in respect of the main road and bridge network and to be accountable for these duties.

PWD

Public Works Department (PWD) plays a pivotal role in the implementation of government construction projects. It also undertakes projects for autonomous bodies as deposit works. The specific functions are:

- Construction of Buildings for Other Agencies on a Deposit Work Basis;
- Maintenance of Public Parks;
- Design and Construction of Public Buildings except those of RHD, T&T, Postal Department;
- Construction of National Monuments;
- Repair and Maintenance of Public Buildings;
- Preparation of Book of Specifications and Code of Practice;
- Acquisition and Requisition of Land for construction Work;
- Procurement of Materials & Equipment Required for Construction Work; and
- Valuation of Land and Property and Fixing of Standard Rent.

BWDB

Bangladesh Water Development Board (BWDB) is the principal agency of the government for managing water resources of the country. It was given the responsibility of accomplishing the tasks of executing flood control, drainage and irrigation projects to increase productivity in agriculture and fisheries.

DPHE

The Department of Public Health Engineering (DPHE) with its development partners is trying to ameliorate the sufferings caused by the lack of safe water. Alternative options for safe water supply are being catered in worse affected areas. Similarly for excreta and other waste management DPHE is implementing different projects to achieve an improved environment. Besides, ensuring water supply and sanitation services/ facilities during and after the natural disasters/ calamities is another major function of DPHE.

PDB

Major roles of Bangladesh Power Development Board (BPDB) are

- To deliver quality electricity at reasonable and affordable prices with professional service excellence;
- To make electricity available to all citizens on demand by the year 2020;
- To provide specialized skilled services in Operation and Maintenance with outstanding performance in Generation, Transmission and
- Distribution for promoting competition among various power sector entities; and also
- To reach self sufficiency by increasing of its income and reduction of expenditure.

BIWTA

An advisory committee has subsequently been constituted to advise the authority in respect of all matters related to development, maintenance and operation of inland water transport and of inland waterways in Bangladesh.

- Draw up programmers of dredging requirements and priorities for efficient maintenance of existing navigable waterways and for resuscitation of dead or dying rivers, channels, or canals, including development of new channels and canals for navigation;
- Develop, maintain and operate inland river ports, landing/ferry ghats and terminal facilities in such ports or ghats;
- Carry out removal of wrecks and obstruction in inland navigable waterways; and
- Ensure co-ordination of Inland Water Transport with other forms of transport, with major sea ports, and with trade and agricultural interests for the optimum utilization of the available transport capacity.

Regulatory functions

a) Fixation of maximum and minimum fares and freight rates for Inland Water Transport on behalf of the Government;
b) Approve time tables for passenger launch services; and
c) Act as the Competent Authority of Bangladesh for the protocol on Inland Water Transit and Trade, looking after the use of waterways of Bangladesh on behalf of the Govt. of Bangladesh for the purpose of trade and transit between Bangladesh and India as provided in the Protocol

Land Registration Department

Land Registration Committee responsible for land registration. This Registration department records land mutations arising through sale, inheritance or other forms of transfer, reports changes to the Ministry of Land, and collects the Immovable Property Transfer Tax.

4.1 Physical Infrastructure

Following are the physical development constraints for preparing the master plan for Gauranadi Planning area:

- The Paurashava is located in a disaster prone area, its geographical location itself a constraint to develop the infrastructure.
- Low land elevation and the distribution of water bodies make it difficult to provide the utility services, road network and well-investment to encourage industrial development.
- Internal roads are being developed in an unplanned way and most of the access roads are katcha and narrow. Moreover, absence of traffic management system causes lack of planning in transport network development. This situation hinders economic development also the potentiality of physical development of the Paurashava.
- Lack of maintenance and lack of urban facilities creating negative impact on physical development.
- Gas supply and sewerage disposal facilities are absent in the Paurashava including inadequate electricity supply. These are the major hindrances in economic and physical development.
- Lack of drainage network makes it difficult to drain out the flood and rain water. As a result, water-logging problem is common in the planning area.

4.2 Socio-Economic

The overall condition of different available urban utilities/civic services at Gauranadi Paurashava area is not satisfactory. No gas supply facility is available for the households of Gauranadi Paurashava which is one of the fundamental urban facilities for the residents living there. At present there is no dustbin and waste disposal facility at Gauranadi Paurashava. It appears that wastes are thrown here and there which pollute the area and create environmental problems. The people of this area also suffer for disaster problems such as flood, water logging, cyclone, etc. people also face some pollution problems like water pollution, noise pollution, beach pollution, etc. There is also lack of recreational facility at the Gauranadi Paurashava. The households of Gauranadi Paurashava face some communication problems in their daily life such as narrow road problem, flood erosion problem, road jam problem and lacking of town bus service. However, this aspect needs vital consideration.

Most of the economic activities in Gauranadi area are rudimentary in nature. Poor technology, unskilled labor force, low investment makes such economic activities uncompetitive with other cities and towns. Public investment in Gauranadi area is not enough to generate growth impulses. Public investment in appropriate areas is a must for revitalizing its economy. The local people, particularly those who are rich usually apathetic toward investment. The main reason can be explained in two points: first, the investment is not safe and the second the rich must in big cities where there investments are safe. Lack of availability of funding sources/agencies viz. bank, etc is also acting as hindrance for economic development.

4.3 Environment

Climatic and disaster condition of the Paurashava is very rough. Floods and water-logging are comparatively low in the Planning area.

Saline water intrusion is mostly seasonal in Bangladesh; in winter months the saline front begins to penetrate inland and the affected areas rise sharply from 10 percent in the monsoon to over 40 percent in the dry season. As the impact of climate change, the sealevel rise cause severe impacts on coastal areas in Satkhira, Khulna, Bagerhat, Barguna, Patuakhli and Barisal are the victims of salinity intrusion. Agricultural production, fisheries, livestock and mangrove forests are being affected by higher salinity in the dry season. Following figure shows the impact of sea level rise and the probability of rising salinity intrusion in coastal region.

4.4 Transport and Communication

Van and rickshaw are two major transport vehicles in the planning area. Bicycle is the main mode for private users. Movement of motorcycle is also identified as major private mode. Inadequacy of bus service found normal scenario in the Paurashava. The peak hour traffic movement is found in morning from 9am to 10am and in the afternoon from 4pm to 5pm in general. Overall traffic congestion is low, let it should not be increased. The movements of Nosimon which is very risky need to restrict to keep the urban area risk free, clean and sound. Establishment of bus route within the planning area is another prior demand of the people.

The hat / bazar in the planning area serves by bituminous and brick soling roads. But the area is not served by well defined road hierarchy, nor is required now due to sparse use of roads by motorized vehicles. However, the induced activities due to the prospects of upward economic change may need to provide road network befitting with the need.

Highway traffic is comparatively low dominated by mixed type of vehicles including non-motorized. Generally, surface of the highways excepting for a larger part is excellent. The road network is not facilitated by designated parking area, bus terminal and bus bay. As a result, sometimes congestions and chaotic situation occurs for a little while. In spite of this situation, present road network is functioning well. But it has to be upgraded to accommodate the future increase of traffic volume that is expected to increase due to the implementation of master plan.

4.5 Landuse Control

At the present time, there is no control over land development at Gauranadi Paurashava. The master plan is intended to prove a broad guideline to control the future development and to organize all types of development in a planned manner.

Major aim of the Landuse Policy 2001 was to prevent indiscriminate conversion of agricultural land in to non-agricultural use, because such conversion may be threatened for food security of the country. During implementation of Urban Area Plan / Ward Action Plan, necessary control should be imposed according to the following manner.

- High value agriculture land should be preserved only for agriculture purposes.
- Water body should be preserved to maintain the natural drainage system of the area.
- Easy accessibility with the surrounding upazila and regional linkage has to be ensured.
- Rural characteristics of the rural settlement have to be strictly maintained.
- All the municipal services have to be designed covering all the residents of the planning area.
- Land encroachment should be strictly outlawed.
- Agricultural lands can be used for other purposes considering the importance of the use and considering the quality of land in terms of its production.

4.6 Disaster

Disaster is the tragedy of a natural or man-made hazard that negatively affects society or environment. Disaster can be classified into two categories: natural disaster and man-made disaster. Natural disaster is the effect of flood, volcanic eruption, earthquake or landslide, draught, epidemic, etc. that affects environment and leads to financial, environmental or human losses. Man-made disasters is resulting from human intent, negligence or error, or involving a failure of a man-made system.

The Paurashava including the Gauranadi Upazila has affected by the several major natural disasters ranging from Cyclone, Flood to Water-logging and Draughts, etc. The periods of those disasters are 1998, 2000, 2004, 2007 and 2008. Very scanty attempt has been made by the government to rehabilitate people after the natural disaster.

Urbanization is converting lands for residential use. Agricultural lands and water bodies are being chosen most frequently and the lands are being converted into urban settlement. In the Gauranadi Paurashava, wet lands are being filled up and agricultural lands are being converted. This has been identified as the major man-made disaster accelerating the degree of conversion year to year. Use of poisonous insecticides on the agricultural land is another man-made disaster which will affect in the long-run.

4.7 Laws and Regulations

The laws and regulations prescribed (mentioned in Chapter 5 section 5.2) are not directly related with the physical development activities and their control. The East Bengal Building Construction Act, 1952 is called the mother regulation to control all type of physical development but no instruction is being included in the Paurashava Ordinance, 2009 regarding EBBC Act, 1952. The Paurashava authority approves the building plan and excavation of tank without any regulatory control.

The regulation prescribed in the Local Government (Paurashava) Act, 2009 on the preparation of master plan is called traditional regulation. In the modern world, the concept of master plan became obsolete. In this project, the so called master plan, as mentioned in the Paurashava and Surrounding Area Ordinance, 2009 considered as a package and the plan included in this package named Structure Plan, Urban Area Plan and Ward Action Plan, though there is no regulation in the country on the preparation and implementation of those plans. However, eligible development authority will be required to exercise proper rules and regulations for controlling the development considering various related issues.

5.1 General

Planning law must clearly define the extent and content of the rights of the Government and the people. Thus, legislative measures can help to frame policies for best use of land and its policies to control. Law should aim at a clear definition of the responsibilities and functions of various Government departments and its respective powers. For urban development, law has profound implications. It defines the system of urban Government, establishes the system of urban planning and regulation of urban development.

5.1.1 Local Government (Paurashava) Act, 2009

After the independence (1971), all local government systems were abolished by the Presidential Order No. 7 in the year 1972 and appointed an administrator in each of the Municipality. After this Order, name of the Local Governments were changed as Town Panchayat instead of Union Committee, Shahar Committee instead of Town Committee and Pourashava instead of Municipal Committee. Shahar Committee was renamed as Pourashava in the year 1973 with a Presidential Order No. 22 and introduced election procedure for the Chairman and Vice-chairman. Thana Parishad Ordinance, 1976 (Ordinance No. XXXII of 1976) was enacted in 21st May 1976 to provide for the constitution of Thana Parishad. Pourashava Ordinance was enacted and notified in the year 1977. Nine Commissioner and selection of female Commissioner in every Pourashava was provisioned in the Ordinance. According to the Pourashava (amendment) Ordinance, 1998, re-distribution of Pourashava Wards was introduced and the Pourashava belongs with 3 Wards proposed for 9 Wards and 12 Wards instead of 4 Wards. One Commissioner for every Ward and one-third Ward of every Pourashava was reserved for female Commissioner who was elected by the general election of the country. Local Government (Pourashava) Ordinance, 2008 (Ordinance No. XVII of 2008) was provisioned 9 Wards, one Mayor and 3 female Councilors for every Pourashava. Mayor and Councilors will be elected through general election. The provision remains in the Local Government (Pourashava) Act, 2009.

From the year 1977 to 2009, Pourashava Ordinance, 1977 enforces by the Pourashava authority and the name of the statute was Pourashava Ordinance, 1977. After promulgation of the same statute, name of the Ordinance has changed as Local Government (Pourashava) Act, 2009. Generally, people call it Pourashava Ordinance, 2009.

For the management of all physical development activities, a wide range of functions have been prescribed in the Second Schedule of the Ordinance. For efficient management of development, three major activities are prescribed and they are – Town Planning, Building Construction and Development. According to the Second Schedule, functions in brief are presented in the following table.

Table-5.1: Functions in brief prescribed in the Local Govt. (Pourashava) Act, 2009

Major activity	Specific functions	Functions in brief
Town planning	Master plan	The Pourashava shall draw up a master plan for the city which shall provide for a survey of the Pourashava including its history, statistics, public services and other prescribed particulars. Development, expansion and improvement of any area within the city; and restrictions; regulation and prohibitions to be imposed with regard to the development of sites, and the erection and re-erection of buildings within the Pourashava.
	Site development schemes	Where a master plan has been drawn up and approved by the government, no owner of lands exceeding such area as may be specified in this behalf in the master plan, shall develop the site or errect a building or any plot of land covered by the provisions of a site development scheme sactioned to area in the prescribed manner. Among other matters, a site development scheme may provide for- (a) the division of the site into plots;

Major activity	Specific functions	Functions in brief
		(b) the street, drains and open spaces to be provided; (c) the land to be reserved for public purposes and to be transferred to the Pourashava; (d) the land to be aquired by the Pourashava; (e) the price of plots; (f) the works that shall be excuted at the costof the owner or owners of the site or sites; and (g) the period during which the area shall be developed.
	Execution of Site Development Schemes	If any area is developed or otherwise dealt with in contravention of the provisions of the sanctioned Site Development Scheme, the Pourashava may by notice require the owner of such area or the person who has contravened the provisions to make such alteration in the site may be specified in the notice as where such alteration is not made or for any reason cannot be carried out, the Pourashava may, in the prescribed manner require and enforce the demolition of the offending structure; and notwithstanding anything to the country contained in any law, no compensation shall be payable for such demolition.
Building construction	Building construction and re-construction	Without approval of the building site and plan by the Pourashava, nobody can construct, re-construct any building in the Pourashava area. The Pourashava will approve the plan within sixty days or refund it within that specified time frame; otherwise the plan will be considered as approved.
	Completion of construction and change, etc.	After completion of the approved building, the owner will notify to the Pourashava within 15 days. The Pourashava may inspect the building and if found any violation of the provision prescribed in the Master Plan or in the Site Development Scheme, the Pourashava may demolish the building and the demolishing cost may be incurred from the building owner.
	Building control	If any building or anything fixed thereon, be deemed by the Pourashava to be in a ruinous state or likely to fall or in any way dangerous to any inhabitant of such building or any neighboring building or to any occupier thereof or to passers-by, the Pourashava may be notice required the owner or occupier of such building to take such action in regard to the building as may be specified in the notice, and if there is default, the Pourashava may take the necessary steps itself and the cost incurred thereon by the Pourashava shall be deemed to be a tax levied on the owner or occupier of the building. If a building is in dangerous condition, or otherwise unfit for human habitation, the Pourashava may prohibit the occupation of such building till it has been suitable repaired to the satisfaction of the Pourashava.
Development	Development plans	The Pourashava shall prepare and implement development plans for specific time. Such Plans shall provide for- (a) the promotion, improvement and development of such function or functions of the Pourashava as may be specified; (b) the manner in which the plans shall be financed, executed, implemented and supervised; (c) the agency through which the plans shall be executed and implemented; and (d) such other matters as may be necessary.
	Community Development Projects	The Pourashava may, sponsor or promote community development projects for the Pourashava or any part thereof and may in this behalf perform such functions as may be prescribed.
	Commercial schemes	The Pourashava may, with the previous sanction of the Government, promote, administer, execute and implement schemes for undertaking any commercial or business enterprise.
Street	Public streets	The Pourashava shall provide and maintain such public street and other means of public commutation as may be necessary for the comfort and convenience of the inhabitants of the Pourashava and of the visitors thereto.
	Streets	No new street shall be laid out except with the previous sanction of the Pourashava. The Pourashava may by notice required that any street may be paved, matalled, drained, channeled, improved or lighted in such manner as may be specified in the notice, and in the event of default, the

Major activity	Specific functions	Functions in brief
	Streets	Pourashava may have the necessary work done through its agency, and the cost incurred thereon by the Pourashava shall be deemed to be a tax levied on the person concerned.
	General provisions about streets	The Pourashava may assign names to streets and paint the names or fix the nameplates on or at conspicuous places at or near the end corner or entrance of the street. No person shall destroy, deface or in any way injure any street, name or name plate, or without the previous permission of the Pourashava, remove the same.
	Street lighting	The Pourashava shall take such measures as may be necessary for the proper lighting of the public streets and other public places vesting in the Pourashava.
	Street watering	The Pourashava shall take such measures as may be necessary for the watering of public streets for the comfort and convenience of the public, and for this purpose, maintain such vehicles, staff and other apparatus necessary.
	Traffic control	The Pourashava shall make such arrangements for the control and regulation of traffic necessary to prevent danger and ensure the safety, convenience and comfort of the public.
	Public vehicles	No person shall keep or let for hire or drive or propel within the limits of the Pourashava any public vehicle other than a motor vehicle except under a license granted by the Pourashava, and in conformity with the conditions of such license. No horse or other animal shall be used for drawing a public vehicle within the limits of the Pourashava except under a license granted by the Pourashava.
Water supply and drainage	Water supply	The Pourashava may provide supply of wholesome water sufficient for public and private purposes. Frame and execute water supply scheme for the construction and maintenance of such works for storage and distribution of water.
	Private sources of water supply	All private sources of water supply within the Pourashava shall be subject to control, regulation and inspection by the Pourashava. No new well, water pump or any other source of water for drinking purposes shall be dug, constructed or provided except with the sanction of the Pourashava.
	Drainage	The Pourashava shall provide an adequate system of public drains in the and all such drains shall be constructed, maintained, kept, cleared and emptied with due regard to the heal and convenience of the public. All private drains shall be subject to control, regulation and inspection by the Pourashava
	Drainage scheme	The Pourashava may prepare a drainage scheme in the prescribed manner of the construction of drains at public and private expense. The drainage scheme as approved by the government shall be executed and implemented within specified period.
	Bathing and washing place	The Pourashava may from time to time set a suitable place for use by the public for bathing, washing cloths, or for drying cloth. Specify the time at which and the sex of persons by whom such places may be used. No person shall establish, maintain or run a bath for public use except under a license granted by the Pourashava.
	Dhobi ghat and washer men	The Pourashava may provide dhobi ghats for the exercise of their calling by washer men, and may regulate the use of dhobi ghats and levy fees for their use.
	Public water-course	The Pourashava may declare any source of water, spring, river, tank, pond, or public stream, or any part thereof within the Pourashava, which is not private property, to be a public watercourse.
	Public ferries	The Pourashava may by by-laws provide for the licensing of boats and other vassals plying for hire in a public water-course to be a public ferry and may entrust the management thereof to the Pourashava, and there upon the Pourashava shall manage and operate the public ferry in such manner and levy such tolls as prescribed.
	Public fisheries	The Pourashava may declare any public watercourse as a public fishery, and there upon the right of fishing in such water course shall vest in the Pourashava which may exercise such right in such manner as may be prescribed.

5.1.2 Urban Management Policy, 1999

The adopted policies under the policy statement are:

- Paurashavas shall provide and maintain the following services to their constituents: (i) Water supply, (ii) storm water drainage (iii) solid waste disposal, (iv) public sanitation, (v) roads and traffic control systems, (vi) public markets, (vii) public transport terminals, (viii) recreational parks and reserves, (ix) community centres, (x) street lighting, etc**.**
- Municipalities shall develop Public Investment Programs (PIP) which will reflect the priority infrastructure needs and appropriate fiscal practices needed to accomplish these;
- The capital budgeting process by municipalities and project selection shall be made transparent;
- Land use plans shall be prepared by Paurashavas in consultations with local communities and shall be periodically updated. Such plan shall form the basis for all property and land development and the assessment of taxes. Each Paurashava and Surrounding Area shall endeavor to appoint a full time qualified Urban Planner to its staff for this purpose, and until such appointment is executed; such services shall be contracted out;
- All external financing extended either directly to Paurashavas by multilateral or bilateral sources or on-lent via the MDF for municipal investments shall be provided on comparable terms;
- Paurashava and Surrounding Area will adopt as early as possible a double entry accounting system on a cash basis. Training and technical assistance shall be provided on a priority basis to facilitate computerization in the transition to double entry accounting;
- Paurashavas shall generate sufficient revenues from their own sources to meet, at a minimum, all of their operating expenses;
- The Government shall review in consultation with municipalities the current intergovernmental revenue transfer system and make appropriate changes to make it transparent, rational, and predictable and to some extent performance based;
- Paurashavas shall endeavor to contract out service provision in whole or in part to private providers in areas such as solid waste disposal, public sanitation, and road maintenance;
- Paurashavas shall conduct periodic public meetings to advise their constituents regarding their activities as well as to engage the public in consultations regarding investment choices, decisions and priorities. As part of this increased transparency; and
- Maximizing the participation of women shall be accorded high priority.

5.1.3 National Housing Policy, 2008

The salient features of the housing strategy envisaged in the National Housing Policy are:

- The role of the government in housing will be to supply serviced land at reasonable price and to help create and promote housing financing institution;
- Efforts will be made to increases affordability of the disadvantaged and the low income groups through providing credit for income generation;
- Improvement and rehabilitation of the existing housing stock will be given priority by the government alongside new housing;
- Encroachment on public land and unauthorized constructions will be discouraged;
- Facilities incremental house building and ensure wider application resources; and
- Conservation of the natural environment and preservation of cultural heritage in new housing projects.

In this policy, there are some specifications are illustrated for Urban and Rural Housing. As the urban and rural context in Bangladesh is different, so the strategies and policies of these sectors are also different. Though the context is different but rural area and urban area are economically, socially and environmentally dependent on each other.

Rural Housing

Clause 5.9 of the Housing Policy describes about the rural housing. In the Housing Policy, following measures are suggested to improve rural housing:

- Avoiding unnecessary displacement of rural settlements due to development projects and where unavoidable, makes proper rehabilitation of the households, with full community involvement;
- Encroachment on agricultural land by proliferation of homestead should be discouraged. Efforts should be made for planned densification of rural homesteads. Subject to availability of khas lands, programs similar to 'Adarsha Gram' program of the Ministry of land will be undertaken in rural areas;
- The coordinated provision of water supply, sanitation, electricity, roads and other basic infrastructure services to existing and new habitations;
- Providing assistance by way of providing credit, dissemination of appropriate technology and delivery system for promoting housing;
- Initiating schemes for increased employment opportunities and income generation by extending appropriate credits and advice, so that housing affordability is enhanced;
- Establishing suitable institutional structure including strengthening of existing organizations at district and local level, with the responsibility for planning, financing, implementation, supervision and monitoring of rural housing schemes, and with the full involvement of beneficiaries, NGOs and CBOs, giving special attention to the needs of the poorest segments, specially women and disadvantaged persons; and
- Linking the development of housing sites and the up gradation of rural housing with the activities under the Bangladesh Rural Development Board (BRDB) and other programs for the creation of rural assets and employment.

5.1.4 Population Policy, 2004

The following strategies will be adopted to slow down the growth of urban population:

- Satellite towns and growth centers should be established with adequate facilities to provide alternative destinations to rural migrants. Roads and communication systems should be linked with the growth centers; along with health, education housing and other welfare services created in those places. Headquarters of important Government and non-Government Organizations, educational institutions and industrial units may also be shifted or relocated to other cities;
- Relax rules relating to going abroad of skilled workers and make provision for dual citizenship;
- Impart education and skill training to the young men and women to become competent and skillful to handle many new and emerging fields in the cities and towns; and
- Create skilled manpower for overseas employment.

5.1.5 National Land Use Policy, 2001

Main Components of the Policy

- use as much as required for agriculture purposes and land use cannot be changed with permission of the appropriate authority;

- ensure use of land owned by the land lord absentee;
- keep limit the process of division of agricultural land into small pieces;
- identification of zones for land uses by Paurashavas and other places of Upazilas;
- provision of assistance by the Revenue Office of District Administration in preparing zoning maps by the local government organizations;
- existence of zoning law in the country; Abide this law to implement the zoning map prepared by the local government organizations;
- encouragement to construct multi-storied buildings instead of single storied in the rural and urban areas so as to ensure optimum use land for residential purposes;
- identification of the forest land by the Ministry of Forest and Environment;
- undertake measures for protection, maintenance and expansion of the existing forest land;
- encouragement for development of the social forestry;
- keep open the exiting water bodies and those are not to be filled in. Entrust the responsibility of maintaining small ponds by the owners and large water bodies such as river, channels, haor, baor and beel by the community people and the Government. To this effect, these water bodies are to be re-excavated regularly;
- use of embankments for controlling flood as roads as far as possible;
- planned tree plantation on the embankments;
- use ditches and other water bodies for fish production and rearing ducks created during cutting of earth for constructing embankments. Not to dig new land as much as possible during constructing embankments rather re-excavate the existing filled in water bodies;
- ensure not to create water-logging by constructing embankments;
- no acquisition of land for the purpose of road construction other than/except national highways, regional and district to Upazila roads, Upazila to Upazila connecting roads. Avoid human settlements and fertile agricultural land to acquire land wherever land acquisition is of utmost need. Construct inter and intra village roads in planned manner;
- construct/establish industries in the designated places keeping view on the availability of support services for industrialization;
- not to pollute/infect land or environment through discharging waste from the industries and follow strictly to treat industrial waste;
- construct service roads along the main roads of the country so as to ensure safe movement of traffic as well as set aside 10 feet to 20 feet of land for plantation trees on the both sides of roads;
- discourage construction of small and cottage industries within 10 kilometers of radius if industries are accommodated within the BSCIC industrial area; and
- protection of social rights of possessing land by the indigenous people living in the different parts of the country following their traditional laws.

5.1.6 National Agriculture Policy, 1999

The following steps will be taken to ensure planned utilization of land for crop production:

- Land zoning program will be taken up by the Soil Resources Development Institute (SRDI) on a priority basis. Integrated approach of SRDI will be further strengthened for this purpose;
- To ensure maximum utilization of land, bottom up planning through people's participation and its implementation will be started from the mouza or village level;
- In most areas the same land is suitable for more than one crop. Therefore, farmers will be encouraged to grow more profitable crops as an alternative to only rice-rice cropping pattern;

- Fertile agricultural land is going out of cultivation due to its use for non-agricultural purposes such as private construction, house building, brickfield, etc. Appropriate measures will be taken to stop this trend in the light of the Land Policy of the government;
- Maximum utilization of land will be ensured through promotion of inter-cropping with the main crops;
- Acquisition of land in excess of requirement for non-agricultural purposes will be discouraged; and
- Programs will be taken up to motivate the landowners not to keep their land unused without any acceptable reason.

5.1.7 Transportation Policy

At present there is no standard design and national unit cost for construction and maintenance of various roads and bridges and culverts. As a result substantial cost difference has been proposed by the agencies for same type of road / bridges for the same area. Following tasks of a road projects will be adopted:

- The Committee reviewed the design standards for the Union, Upazila, Zila Roads, and concluded that the key design criteria for all roads should be traffic and axle loads, and not the classification of the roads;
- The six design standards agreed by the Committee to form a logical progression in terms of road width and pavement thickness, all based on traffic considerations. They are not directly related to road classification;
- The agreed design standards are to be used by all road agencies. Road agencies will be required to use appropriate standards for roads according to traffic criteria;
- Reconstruction- full pavement reconstruction on an existing embankment;
- New road Construction - completely new embankment and road pavement, including bridges, culverts and any necessary slope protection. This is likely to prove a rare category of road project in Bangladesh;
- Widening- road widening and upgrading, including full re-construction of the existing pavement; and
- Strengthening- removing existing road surfacing and providing a new base layer of Base Type-1 and surfacing.

5.1.8 Environment Policy

Bangladesh National Environment Policy was approved and published in 1992. Key elements of the Policy are –

- Maintain ecological balance and overall physical development progress of the country through protection and development of different sectors. Protection from natural disaster is one of them;
- Identification and regulation all type of activities which pollutes and degrade the environment;
- Ensuring proper Environment Impact Assessment prior to undertaking of industrial and other development projects; and
- Ensuring sustainable use of natural resources.

5.1.9 Coastal Zone Policy, 2005

The following are the broad components of the policy:

Economic growth

- Efforts shall be made to enhance annual growth rate to a level required to achieve national goal for poverty reduction and economic growth;
- Available opportunities of the coastal zone will be used through sustainable management to enhance standard of living of coastal communities by investing in different sectors;
- A strategy shall be formulated covering all routes to development taking multidimensional nature of poverty;
- Emphasis will be given on building efficient power, transportation and telecommunication links, particularly with islands;
- Special emphasis will be given to utilize gas-based power, manufacturing and processing industries;
- Settled isolated chars and islands will be brought under 'special rural development programs';
- Necessary measures will be taken to increase the flow of investments in the coastal zone including direct foreign investment (DFI), especially by setting up more export processing zones (EPZ); and
- Steps will be taken for medium and small private investments for coastal development.

Basic needs and opportunities for livelihoods

To meet basic needs of the coastal people and enhance livelihood opportunities, the Government policy will be as follows:

- Alleviation of poverty through creation of job opportunities and finding options for diversified livelihoods would be the major principles of all economic activities. Economic opportunities based on local resources will be explored to enhance income of the people;
- The intensity of coverage of primary education, health care, sanitation and safe drinking water facilities will be increased;
- Food production will be continued at the self-sufficiency level and of higher production of diversified high-value export goods;
- Private sector and the non-governmental organizations (NGO) will be encouraged to implement activities for the poor people;
- Collateral-free credit under easy terms will be arranged as part of all livelihood enhancement programs and activities;
- No alteration or stoppage of an existing employment opportunity shall be made without creating opportunities for alternative employment;
- Special measures will be taken during the period of disaster;
- *Khas* land will be distributed among the landless and a more transparent process of land settlement will be ensured;
- An effective program for land reclamation will be developed;
- Provide facilitate for the coastal navigation;
- An integrated network of communication including roads and waterways will be developed;
- The law and order situation will be improved by setting up police outposts in remote and far flung areas; and
- Free flow of information for the people will be ensured.

Reduction of vulnerabilities

In order to reduce the vulnerabilities of the coastal poor from disasters like cyclone, drainage congestion, land erosion, drought, etc, the Government policy is as follows:

- Reduction to vulnerability to natural disasters would be an integral aspect of the national strategies for poverty reduction;
- Integration will be made with 'Comprehensive Disaster Management Plan' on aspects concerning the coastal zone;
- Effective measures will be taken to enhance coping capacity of the poor during the period of disaster and to initiate insurance scheme for improving their social security;
- Effective measures will be taken for protection against erosion and for rehabilitation of the victims of erosion;
- Safety measures will be enhanced by combining cyclone shelters, multi-purpose embankments, road system and disaster warning system. It should include special measures for children, women, the disabled and the old;
- Earthquake management will be strengthened and capacity to cope with earthquakes will be enhanced;
- Adequate provision will be made for safety of livestock during disaster and post-disaster period;
- Programs shall be taken to encourage all for tree plantation in a planned manner in the coastal zone. Emphasis will be given to social forestry and other forms of plantations, plant care and maintenance; and
- The asset base of the poor, with special focus on women, shall be improved through ownership or access so that their coping capacity improves.

Sustainable management of natural resources

The Government policy to ensure sustainable management of both biotic and abiotic coastal resources will be as follows:

- Every possible steps shall be taken to secure just share from all international rivers reaching the coastal zone and the Bay of Bengal;
- Suitable measures will be taken for sustainable use of renewable resources and, to that end, limit harvesting, extraction or utilization to the corresponding cycles of their regeneration;
- Sustainable use of coastal resources shall be ensured. Combination of resource use, e.g. agriculture, forestry and fishing including aquaculture is often the major economic activity. Efforts will be given to make this sustainable;
- Optimum utilization of resources will be ensured by taking advantage of the complementarities and trade-offs between competing uses;
- Rigid enforcement of conservation regulations will affect the livelihoods of many people and such conservation efforts will be linked, as far as possible, with alternative opportunities of employment; and
- Initiation of plan and its implementation will be ensured by participation of people of all sectors.

Land

- Planning will be done under land use policy to control unplanned and indiscriminate use of land resources. Strategies for new chars will be developed. Zoning regulations would be formulated and enforced in due course; and
- Through its responsible agencies, the Government will proper plan and implement schemes for reclamation of balanced land from the sea and rivers.

Water

- Adequate upland flow shall be ensured in water channels to preserve the coastal estuary ecosystem threatened by the intrusion of soil salinity from the sea;
- Small water reservoirs shall be built to capture tidal water in order to enhance minor irrigation in coastal areas. Appropriate water management system within the polder utilizing existing infrastructures will be established for freshwater storage and other water utilization;
- Rainwater harvesting and conservation shall be promoted;
- Ponds and tanks will be excavated for conservation of water and local technology for water treatment (such as, pond sand filtering - P.S.F.) will be used for the supply of safe water; and
- Step will be taken to ensure sustainable use and management of ground water.

Capture fisheries

- Comprehensive policies, as dealt in the National Fish Policy, in relation to exploitation, conservation and management of marine fisheries resources will be followed; and
- Fishers' right will be established on open water bodies for sustainable fisheries management

Aquaculture

- Environmentally adopted and socially responsive shrimp farming will be encouraged. In this regard, internationally accepted quality control measures will be introduced; and
- All opportunities and potentials of aquaculture will be utilized in the coastal zone. Crab culture, pearl culture, sea grass will be encouraged.

Agriculture

- Programs for intensification of agriculture and crop diversification for improving the economic conditions of both male and female farmers and increasing food security at local and regional level shall be supported;
- Special development programs will be taken-up with a view to increasing the production of crops suitable for the coastal area with attention to maintenance of soil health;
- Use of chemical fertilizers and pesticides will be reduced, while organic manure and integrated pest management will be encouraged;
- Salt-tolerant crop varieties will be developed and extended along with possible measures to resist salinity; and
- The scope of irrigation facilities will be explored and / or extended and a comprehensive water management for agriculture will be implemented.

Livestock

- Grazing land for livestock will be arranged. Facilities for livestock development will be enhanced; and
- Facilities for rearing of poultry of different species including the local ones will be enhanced.

Energy

- Assessments shall be made on the prospect of tidal and wave power in coastal areas' as potential energy source;
- An assessment of all types of energy resources (e.g., oil, gas, coal, nuclear minerals, hydropower, biomass fuels, solar, wind and tidal waves) will be undertaken on a regular/continuous basis by the appropriate authorities. Special measures will be undertaken

- for exploration and appraisal of petroleum resources in the offshore areas without undermining the nature;
- Potentials of area-based renewable sources of energy will be assessed;
- Remote and isolated areas including offshore islands, which are not likely to be brought under the networks of commercial fuels in a foreseeable future, are to be considered as potential sites for implementing renewable energy technologies, in spite of their high capital cost. Solar photovoltaic will be used for cyclone shelters; and
- Special projects will be identified, for example power plants in the offshore islands. Plans for the generation of electricity in isolated and remote areas like offshore islands will be prepared separately.

Equitable distribution

To ensure right of the neglected and disadvantaged groups, the Government policy is as follows:

- Actions will be designed to reach the poorest and the remote rural areas (including the cyclone prone coastal regions, chars and river erosion affected areas), which are vulnerable to adverse ecological processes and those with high concentrations of socially disadvantaged;
- In order to ensure equitable distribution of national economic benefits, priority will be given to exposed Upazilas and coastal islands;
- In order to ensure equity, the thrust should be on human development of the poor for raising their capability through education, health, nutrition, employment-oriented skill training and social interventions; and
- Measures will be adopted that increase access to natural resources for the poor and the disadvantaged (on which they are dependent for their livelihood).

Empowerment of communities

Mainstreaming of the coastal people will be done by enhancing their safety and capacity. In this context, Government policy will be as follows:

- Equal participation of all stakeholders shall be ensured and establishing effective co-operation between the government agencies, local government institutions and non-governmental organizations;
- Co-management procedures shall be established that will bring decision-making power to the grass root levels;
- Specific vulnerabilities of the coastal communities shall be addressed: like farmers in the saline zone, marine fishers, salt producers, dry fish processors, people living on forestry resources, ship breaking workers, vulnerable ethnic communities and so forth;
- Vesting on local government institutions, at the union, upazila and district levels, the power and responsibilities for design, formulation and implementation of local level development programs and projects;
- An awareness campaign shall be mounted about the long-term benefits of ICZM, recent initiatives in the coastal zone, and coastal development strategy among the NGOs, private sector, civil society and coastal communities; and
- Initiatives will be taken to keep up the cultural heritage of different communities living in the coastal zone.

Women's development and gender equity

In this respect, the Government policy will be as follows:

- A gender sensitive and participatory approach will be adopted that focuses at the reduction of gender inequalities and that takes into account differences in needs and interests between men and women;

- Efforts will be made to close the gender gap, giving priority to women's education, training and employment and special support for broadening their coping capacity;
- Special attention will be paid towards employment generation for women, the promotion of women entrepreneurs as well as the removal of restrictions on women's employment and economic opportunities;
- During distribution of newly accreted khas lands, special attention will be paid to the allocation of land titles to women;
- Special projects will be implemented exclusively addressed to livelihoods enhancement and empowerment of disadvantaged women; and
- Necessary institutional measures including mass awareness and motivation on violence against women will be taken.

Conservation and enhancement of critical ecosystems

The Government policy will be as follows:

Conserving the ecosystems

- Meaningful conservation shall be enforced of critical ecosystems including ECAs, heritage sites and marine reserves;
- Special measures will be taken for conservation and development of the natural environment of Sundarbans;
- The programs for institutional strengthening and capacity building shall be supported along with further development of the regulatory framework for the protection of the environment;
- The role of the Coast Guard will be acknowledged with emphasis and its capacity will be enhanced so that it can be used on behalf of all relevant institutions as a common resource for enforcement of different regulations applicable to the coastal zone;
- For activities that have direct adverse consequences on bio-diversity, steps will be taken to stop those activities and specific mitigation measures will be taken to minimize those effects;
- To protect the environment, all commitments shall be honored as signatory to different international protocols and guidelines in planning and implementation;
- Efforts shall be made to harmonize in the provisions of different existing laws and enact new laws, where required, to protect and preserve the coastal environment and its resources;
- Special measures will be taken for bio-diversity conservation; and
- Measures will be taken for hill management including prohibition of hill cutting.

Pollution Control

- Zoning regulations will be established for location of new industries in consideration of fresh and safe water availability and effluent discharge possibilities;
- All industrial units will be required to install built-in safeguards against pollution within a given timeframe and will help them in obtaining financial support from international bodies to carry out the adjustments. Units failing to comply with the pollution standards will be required to pay "green tax" for cleanup of the environment polluted by them;
- Sewage treatment plants will be set up for the major cities like Chittagong, Khulna and Barisal and gradually in other urban centers;
- Steps will be taken to handle the issue of discharge of bilge water from ships and oil-spill according to international conventions to which Bangladesh is a signatory; and
- A review of the desirability of supporting ship breaking as an industry `will be done and, in the event of its continuation, environmental standards will be prescribed under which it has to conduct its activities.

Climate Change

- Existing institutional arrangements for monitoring of climate change in Bangladesh will continue. Steps will be taken to support upgrading of technology and institutional strengthening for enhancing their capacity for generation of better data and more accurate long-term prediction and risk related to climate change;
- Implementation of adaptive measures identified in relation to climate change for coastal zone and resources shall be gradually undertaken;
- Efforts shall be made to continuously maintain sea-dykes along the coastline as first line of defense against predicted sea-level rise; and
- An institutional framework for monitoring/detecting sea level rise shall be made and a contingency plans for coping with its impact.

5.1.10 Industrial Policy, 2005

Bangladesh is a developing country, and the present government is striving relentlessly to attain rapid economic development in the country. Despite a lack of resources faced by the Government, development programs in the key sectors have continued. Therefore, the Government in the Ministry of Industries has taken the role of a facilitator. In order to establish economically prospective industries in industrial sub-sectors, there are plans to set up industrial parks and special economic zones so that huge amount of unused and abandoned land can be utilized. All this is aimed at fostering industrialization and economic development and generating employment opportunities in the country. To reduce poverty and generate employment opportunities, more efforts are needed to establish agro-based industries as well as to raise agricultural production. This will ensure the protection and fair price of agricultural products and employment of a huge number of unemployed people. In order to create further employment opportunities beyond the agricultural sector, initiatives should be taken to set up small, medium and large industries across the country. In order to attain this growth in this sector, special importance has been given in the Industrial Policy on agro-based and agro - processing industries and on steps to overcome possible adverse conditions in the export-oriented garment sector. Importance has also been given on considering the SMEs and cottage industries as one of the major driving forces, providing assistance to women entrepreneurs on a priority basis, setting up special economic zones in different parts of the country, improving the quality of industrial products to world standard, marketing of goods at competitive prices, and enhancing productivity in the industrial sector.

5.1.11 Health Policy

National Health Policy was approved and published by the government in the year 2000. Aim of the Health Policy is:

- To develop a system to ensure easy and availability of health services for the people living in urban and rural areas;
- To ensure optimum quality, acceptance and availability of primary health care including government medical services at the Upazila and Union level;
- To adopt satisfactory measures for ensuring improved maternal and child health at the Union level and install facilities for safe child delivery in each village;
- To improve overall reproductive health resources and services;
- To ensure the presence of full-time doctors, nurses and other officers / staffs, provide and maintain necessary equipment and supplies at each of the Upazila Health Complexes and Union Health and Family Welfare Centres;
- To formulate specific policies for medical colleges and private clinics, and to introduce appropriate laws and regulations for the control and management of such institutions including maintenance of service quality;

- To explore ways to make the family planning program more acceptable, easily available and effective among the extremely poor and low-income communities; and
- To arrange special health services for mentally retarded, physical disabled and for elderly population.

5.1.12 National Urban Policy

The major objectives of national urban policy will aim to:

- Ensure regionally balanced urbanization through diffused development and hierarchically structured urban system;
- Facilitate economic development, employment generation, reduction of inequality and poverty eradication through appropriate regulatory frameworks and infrastructure provisions;
- Ensure optimum utilization of land resources and meet increased demand for housing and urban services through public-private partnerships;
- Protect, preserve and enhance urban environment, especially water bodies;
- Devolve authority at the local urban level and strengthen local governments through appropriate powers, resources and capabilities so that these can take effective responsibility for a wide range of planning, infrastructure provision, service delivery and regulatory functions;
- Involve all sectors of the community, in participatory decision-making and implementation processes;
- Ensure social justice and inclusion by measures designed to increase the security of poor people through their access to varied livelihood opportunities, secure tenure and basic affordable services;
- Take in to account, particular needs of women, men, children, youth, elderly and the disabled in developing policy responses and implementation;
- Assure health, safety and security of all citizens through multifaceted initiatives to reduce crime and violence;
- Protect, preserve and enhance the historical and cultural heritage of cities and enhance their aesthetic beauty;
- Develop and implement urban management strategies and governance arrangements for enhancing complementary roles of urban and rural areas in sustainable development; and
- Ensure good governance by enhancing transparency and establishing accountability.

5.1.13 Rural Development Policy

The projects and programs as mentioned in the Rural Development Policy of Bangladesh are:

(i) Food for Works Program, (ii) G.R Program (Gratuitous Relief Program), (iii) T.R Program (Test Relief Program), (iv)V.G.D Program (Vulnerable Group Development Program), (v)V.G.F Program (Vulnerable Group Feeding Program), (vi) Single-House Single-Farm Program, (vii) Back to home Program, (viii) Food for Education Program, (ix) Rural Occupational Project, (x) Poverty Reduction Project, (xi) Self-employment Program for Women, (xii) Women Empowerment Program, (xiii) Coordinated Women Development Program, (xiv) Peace Home Program, (xv)Shelter Support Program, (xvi) Educational Allowance Program, (xvii) Aged-allowance Program, (xviii) Micro-credit Program and (xix)Allowances for Widowed, Poor and Husband-renouncement Women Program, etc.

Some of the aims and objectives of the Rural Development Policy is presented here:

- To increase the income and provision of jobs for the Villagers, especially for women and people under low-living standard in the rural areas;

- To confirm sustainable economic and social development through poverty reduction;
- To encourage self-employment opportunities in the rural areas;
- To emphasize for the development of rural wealth according to the equal distribution of economy and national development as prescribed in the Constitution of Bangladesh;
- To give confirmation to the rural people about infrastructural development, equal distribution of wealth and marketing of the agricultural production;
- To produce technologically efficient people about education, technical education and trainings in rural areas;
- Identification of demand and their fulfillment for socio-economic development of rural poor, persons involved with the production, especially small farmers and landless people; and
- To reduce distances between towns and villages about services prevail through collective efforts and develop gradually.

5.1.14 Disaster Management and Climate Change Policy

The issues prescribed under Climate Change Policy are:

- Mitigation, adaptation and technology transfer is a must measure to fight climate change enhanced vulnerabilities of poor;
- The complementarily of current policy regime in relation to adapting to climate change should be analyzed in order to define which aspects of adaptation are already in place. This would not only advance national (also regional and local) development processes, but also would reduce vulnerability of people to climate change;
- A micro-level climate change risk reduction plan should be developed by the communities. The process should initiate local level action ensuring the participation of grassroots people, NGOs, civil societies, academic and research institutes etc.
- A community centered approach should be taken to develop policies which should address development as well. The policy action plan should also promote appropriate technologies such as resilient crop varieties, irrigation schemes, and renewable energy sources, so that they are available and affordable for low-income communities of Bangladesh; and
- It's been believed by the economists that climate change is the greatest market failure of the history of mankind. Climate is natural, therefore a common property. For this reason, climate change related economic does not follow the prevailing market mechanism. Therefore, it should be understood that, the rich countries which are polluting should start paying for adaptation for the LDC and also start paying for mitigation within their countries. Bangladesh should make its position clear in favor of this logic in all negations and raise its voice.

5.2 Laws and Regulations

5.2.1 Urban Development Control

The president of Pakistan in the year of 1960 was enacted the Municipal Administration Ordinance, 1960. In the year 1977 through the Pourashava Ordinance, 1977 some of the Municipalities were upgraded as Pourashava and in the year 2009 Pourashava Ordinance is renamed as local government Ordinance 2009. The Pourashava may provide the function as prescribed in the Ordinance but no provision is being outlined to control and manage those functions. The Pourashava may enforce those regulations according to their capacity. The Ordinance proves that the Pourashava is independent and self regularity body, but due to absence of necessary man power technical support staff and the government initiative in financial matter, the Pourashava is dependent and control by central government.

5.2.2 Building Construction rules 1996

Land use planning Rules

These are statutory rules to control land use according to planning standard. It is based on land use policies including Local Plans, such as residential density, road standard, provision of infrastructure and services. The relevant Acts, Local Government (Paurashava) Act, 2009, Building Construction Act, 1952 and BNBC, 1993) and Master Plans of the cities are the main legal instruments, which is in force with regard to exercise planning control and standards.

Control of public estates

Different government agencies have developed some housing, commercial and industrial estates in different urban areas and they have leased them out. Terms and conditions of lease deed reflected control provisions included in them.

Non-compliance of development control by some government and semi-government agencies

A portion of urban lands of the urban area are owned by different government and Autonomous agencies including universities, colleges. According to Building Construction Act, 1952 (amended in 1996, followed by Paurashava) each public building needs approval from the concerned development agencies. It is observed that most of the agencies are still ignoring the regulations and they construct their buildings within their premises.

Control of private housing estates

Large numbers of pockets of urban infill and privately owned low lying peripheral lands have been developed by private companies. In some cases small scale real estate development permission is obtained occasionally but deviations from the approved plan are most common practice of the developers.

Control of informal Development

A number of unregulated or informal settlements are taking place in urban area as urbanization proceeds. Paurashava can hardly control these haphazard development activities. The Slum Up-gradation Projects, Slum Improvement Projects (SIPs), provision of basic needs etc. are taken up at time when the problems had already overtaken the situation.

Density Control

Density Control is considered as an important development control tool. It includes the number of units, people allowed per parcel of plot size, unit limitation, height of the building etc. In the Government and Semi Government institutions, building permission is hardly obtained and therefore, density control rules and regulations are not in practice. At present, Paurashava follows Building Construction Rule, 1952 (amended in 1996) which restricts the height of Building in respect of adjacent road. Therefore, density control is possible to exercise in practical.

Taxation

Urban taxation is another effective development control tool. Different types of taxation policies may to change urban land use and urban character. As an example, the industrial estates are encouraged to set up outside the city areas for tax holiday and other ancillary facilities. On the other hand, exemption of tax on urban vacant land encourages growing unauthorized settlements like slums and squatters.

Payment of Betterment fee

For every town planning scheme for an existing town, some owners of the property will be affected and as such they will have to be paid some amount as compensation. In the same time, some owners will be benefited by the proposed scheme. The share of increase in the value of the properties of such owners to be paid to the Paurashava is known as Betterment fees.

5.3 Strength and weaknesses of the Existing Policies

Local Government (Paurashava) Act 2009

Although the Paurashava has been given the rights to prepare Master Plan and implement them, prepare development plans and projects for systematic development of Poura- city, building control, roads and streets plans etc. Besides, the replacement of Ordinance amended in 2008 by Paurashava Act 2009 ensures the citizen participation in a new way. But there are some drawbacks or weaknesses in this which are as follows:

- The engineering department has been given the responsibility to implement the Master Plan, but this department is not equipped enough to implement it properly;
- To implement the Master Plan/ Land Use Plan, the staff requires professional training, but no one has received any training regarding implementation activities;
- Central Government does not exert any pressure to implement the Land use Plan;
- Paurashavas do not enjoy real autonomy to solve local problems; and
- More critical problem is the weak or even non-existent co-ordination amongst development partners.

Urban Management Policy

The Policy statement recognized the decentralization could enhance efficiency of public expenditures by allowing local governments to be more responsive to local needs and preferences. The policy also envisions strengthening the beneficial aspects of urbanization and at the same time effectively dealing with its negative consequences so as to achieve sustainable urbanization, keeping in view the multi-dimensional nature of the urbanization process. On the other hand, the policy principles gave emphasis more on physical aspect of development rather than on social, environmental. Besides, issues on poverty reduction are missing in the policy outlines.

Land Use Policy, 2001

The National Land Use Policy, 2001 of the Ministry of Land highlights the Need, the importance and modalities of land zoning for integrated planning and management of land resources of the country. It also mentioned the need of formulating a Zoning Law and Village Improvement Act for materializing the identified land zoning area. The National Land Use Policy specially highlights the need for land zoning for the coastal area of Bangladesh. It describes about the need for definite guidelines and raises the possibility of doing coastal land zoning through an inter-ministerial task force. The policy observes that maximum utilization of lands and water resources depends on the effective land use plan. But there is no policy prescription for any specific area as context requires and also the proper methodology, technology to be used, institutional capacity are not designated. Besides, the policy is strong on conservation of khas lands but not clear on distribution of khas land distribution program.

Industrial Policy, 2005

One of the foremost objectives of the Industrial Policy 2005 is to set up planned industries considering the real domestic demand, prospect of exporting goods abroad, and discouraging unplanned industries in the light of past experience. The policy also encourages the agro-based industries and involvement of Women Entrepreneurs in Industrial sector, equal profit distribution

among workers, owners and government. But the interests of small farmers, small business owners, artisans, and workers, are generally not well represented. This limits the benefits of trade expansion for small businesses, small farmers, artisans, and workers consequently create impacts on the key export industries. These groups are involved in import and export activities of the country indirectly. In addition, no specific mention has been made on protection of coastal environment from industrial pollution.

Coastal Zone Policy, 2005

The strong point of Coastal zone policy is that it provides integration among all sectoral policies such as land use, industrial, fisheries etc. It defines specific objectives for coastal development and the jurisdiction and extent of the coastal zone. The main stakeholders in coastal development are identified, along with their role in the development process.

Agriculture Policy, 1999

The key point of the National Agriculture Policy in relation to ICZM is its simultaneous recognition of the importance of shrimp farming as foreign exchange earning activity and its environmental consequences. However, the policy does not mention conflicts between farmer and shrimp-gher owners and thus fails to indicate any mitigation measures. Land use zoning may offer instruments to reduce conflicts. Bio-saline agriculture, practiced elsewhere, could be tried in the coastal zone.

Population Policy, 2004

It defines the strategy of population declination but no detailing has been given on the instruments that are required to reduce the population growth. Also, the responsible stakeholders that are directly and indirectly linked to this sector are not identified. A general policy prescription is given without specific group identification.

National Housing Policy, 2008

The policy provides prescription for urban and rural area individually considering the context. Though one of the major objectives of the Housing Policy was to ensure housing for all with particular emphasis on the disadvantaged, destitute, the shelter less poor and the low and middle-income groups of people, yet very little efforts have been taken on the part of the government in providing housing loans to the low-income strata of the population. Nationalized commercial banks introduced housing loans also limited for the high income group. There is virtually no credit financial mechanism for housing of low-income people in urban areas. Besides, there is no specification for private developers. No direction is given for future housing demand and supply.

6.1 Introduction

Population growth rates in developing countries are much more than of the developed countries of the world. Moreover, migration to urban areas in the developing countries has been increasing over the years. Due to increased urbanization trend in the coming years, the cities in the developing country will face housing and settlement problems, infrastructural deficiencies for increased number of populations, slum and squatter settlements, environmental degradation, etc. In practical, it is difficult to attain the actual number of population but more accuracy in population projection will encourage the future investment as projection shows the population demand. It is assumed that Gauranadi Paurashava, as a Paurashava will face such influx of job seekers in the coming days. As such, besides natural population growth immigrants will increase the population significantly in the coming decades.

6.2 Projection of Population

In order to get an idea about the population growth rate of Gauranadi Planning area, the population data of 2001 has been compared to 2011 data of population. Urban and rural growth rate is different. But in case of Gauranadi Paurashava, difference between rural & urban growth rate is not considered due to lack of data. Normally growth rate has been calculated on the basis of population data 2001 to 2011. As urban growth rate of Gauranadi is very low, average of zila growth rate and upazila growth rate is considered as medium growth rate. From this it has been observed that the annual growth rate is 1.19% that is parallel with both national growth rate and urban growth rate. Total population in the area on the basis of exponential growth the population will be 45017, 47193, 50061, and 53104 in the years of 2016, 2021, 2026 and 2031.

Basic Assumptions

- The characteristics of the more recent periods of development for the local are expected to continue into the future;
- The existing density of population, major activities of Paurashava i.e., Trade, Commerce and Service and higher sex ratio reveals the flourishing economic development of the Paurashava in recent years.

Methods Used

Population projection has been conducted on the basis of following determined methods and techniques:

- The base year for such above mentioned projection is 2011 as per available census data
- Future population is estimated for the future year 2016, 2021, 2026 and 2031 considering 20 years planning period
- Finally, Exponential Population Projection is used to conduct the Population Projection. Projected growth rate is 1.19%.

According to Population projection, population of Gauranadi Paurashava will be 53104 in the year 2031. Table 6.1 depicts ward wise projected population (2016-2031) of Gauranadi Paurashava based on medium growth rate.

Table 6.1: Projected Population during the Year 2016-2031

Ward No.	Population at 2011	Projected Population at Different Years			
		2016	2021	2026	2031
1	6376	6764	7090	7521	7979
2	4298	4559	4780	5070	5378
3	4114	4364	4575	4853	5148
4	3971	4212	4416	4684	4969
5	5737	6086	6380	6768	7179
6	4987	5290	5546	5883	6240
7	4776	5066	5311	5634	5976
8	4428	4697	4924	5223	5541
9	3751	3979	4171	4425	4694
Total	**42438**	**45017**	**47193**	**50061**	**53104**

Source: Consultants Estimation

6.3 Identification of Future Economic Opportunities

The city of Gauranadi must thrive on its own potential natural resources. Fish resource is very much potential for the area. Food industries can be initialized based on fish resources. There are a number of areas where such prospects can be managed. First, catching fish has to be increased. Second, freezing facilities has to be enhanced. Third fish drugging facilities to be expanded and finally, small and low investment plants for processing fish resources can be initialized. Bangladesh Fisheries Development Corporation (BFDC) has taken effective projects aiming to develop the country's fisheries sector and boost export. Fish landing centers, fish preserving and fish marketing centers for traders would be set up. Warehouse facilities and ice supply for traders would also be extended under this project and ice factories in Gauranadi, Barisal would also be built. According to the Fishermen, a great numbers of fishing trawlers were engaged in hilsa fishing in Gauranadi. Therefore, fish merchants have urged development of processing industry, setting up of cold storage and ensuring electricity and ice supply for preservation and availability of hilsa round the year.

About 65.00% of the total lands of Gauranadi Paurashava are devoted for agricultural purposes. So emphasize have to be given on the scientific procedure of agricultural production and these productions may be used as input of agro-based industries.

Economically active labor forces are not being properly used in production sector. This labor force can be utilized in those fishing or agro-based sector.

6.4 Projection of Land Uses

Future landuse of Gauranadi Paurashava has been calculated on the basis of projected population. After population projection, it has been observed that in the year of 2031, resident population will be around 53104. In some cases, landuse projection may vary considering landuse characteristics of the area.

At present, the landuse of Gauranadi Paurashava is not appropriate and has not developed following standard. Therefore, this master plan has addressed the issue and efforts have been done to formulize required standards for various facilities that should be followed in preparing the master plan. As per planning standard, future demand of land in various sectors is discussed in table 11.14, chapter 11-Land use Plan, Part B.

7.1 Strategies for Optimum Use of Urban Land Resources

Gauranadi Paurashava is peri-urban area with urban infrastructures and also valuable agricultural lands, water resources. Therefore, in identifying the strategies or possible techniques for optimum use of Urban Land Resources, it is required to understand the urban land characteristics. According to town Improvement Act 1953 it is required to identify the strategies for optimum use of urban land resources as there exist competition amongst agriculture, urbanization and industrial development.

7.1.1 Land use Zoning

Land use Zoning can be a very powerful planning tool as it permits the government to select which type of land use should be allowed. The term differs from the 'general plan' that Zoning plan regulates the private developments and general plan controls both public and private developers. Zoning plan is integral part of general plan.

Total area of Gauranadi Paurashava is segregated under some broad classes that will basically guide future growth with wide aspects. Definitions of the broad classes are given below for conceptualizing focus of the future magnitude as well as illustration of the policies and strategies.

A. Agriculture
B. Core Area
C. Peripheral Area
D. Fringe Area
E. New Urban Area
F. Major Circulation Network
G. Water Body

Table 7.1: Broad Land use Zones

Zoning	Description of Zones	Area (acre)	%
Agriculture	Agricultural land (also *agricultural area*) denotes the land suitable for agricultural production, both crops and livestock. It is one of the main resources in agriculture. The land under annual crops, such as cereals, other technical crops, potatoes, vegetables, and melons; also includes land left temporarily fallow; land under permanent crops (e.g., fruit plantations); areas for natural grasses and grazing of livestock.	1825.47	42.42
Core Area	This area is also known as built-up area. This is defined as the area which has the highest concentration of services; it also has the highest population concentration and density. It will absorb most population growth during the Land use Plan (2011-2021) period.	176.03	4.09
Peripheral Area	This is the zone where a slow trend of urbanization is continuing in unplanned manner. The area identified in the Structure Plan as the likely choice for new urban development beyond the core area. Ideally, it might be reasonable to provide primary infrastructure networks in this area to foster development and encouraged to enable a more rapid urbanization in a planned way	1059.84	24.63

Zoning	Description of Zones	Area (acre)	%
Fringe Area	This zone is developing areas which will take further decades to reach the population densities of the urban core area. Low initial densities in these areas do not justify supply of a full range of services as they will initially be underused. However, it is essential that planning and reservation of rights of way, at least for primary networks, be undertaken soon to enable provision when justified by increased density levels and allowed by resources.	312.01	7.25
New Urban Area	This zone will be the required additional area for future planned urban development as per population projection. New facilities and services like road, drains, footpath, waste transfer station and other civic services will be provided. This area is proposed to grow within 2031.	104.97	2.44
Major Circulation Network	Major circulation contains major road network and railways linkage with regional and national settings.	372.13	8.65
Water body	Water body containing an area equals to or more than 0.25 acres excluding those of khal, irrigation canal and river will be treated as this category.	452.75	10.52
Total		**4303.20**	**100.00**

Source: Consultants Estimation

Map 7.1 shows the structure plan of Gauranadi Paurashava.

7.1.2 Land Acquisition and Requisition

Land acquisition is a process in which a public agency or non-profit land conservation organization purchase all the ownership rights vested to the land from a willing seller. In every case, land acquisition must mean the transfer of ownership. For implementation of any urban development program, availability of land and its control are necessary not only for future growth but also for a large number of public uses. In Bangladesh, Land Acquisition Act, 1894 is one of the most important legal tools. But as the law failed to meet the emergency needs for requisition of lands, the Acquisition and (emergency) Requisition of Immovable Property Ordinance, 1982 has been come in forth.

7.1.3 Policy Formulation

Apart from this the recommendations for Road networks can be adopted from the recommendation from national relevant policies. This will direct the future land use pattern.

7.1.3A Planned Development of Undeveloped Areas

Land Readjustment

It is a community building project of resident or for residents where: Land for public facilities is contributed fairly from land owners and lease holders. Where part of development benefits are provided by land owners to an implementing body to finance project cost, not in cash but in the form of reverse land.

Guided Land Development

It is a land management technique for accelerating the provision of serviced land through partnership between public sector and local communities. Its main objectives were to ensure;

1. fair return on investment to the private owner/developer;
2. a relatively large proportion of serviced sites for allotment to low income families; and at the same time;
3. recover at least part of offsite infrastructure cost for the public agency.

Site and Service

This sort of design provides the low-income people or target group with a plot and basic infrastructure. The beneficiaries either buy or lease the allocated land. Often they are provided with loan for the construction of houses.

7.1.3B Redevelopment of Developed Areas

Land Sharing

The principle behind this has been that the land is shared equitably between the land owner and the tenants (quasi). The land owner develops the land in such a manner that the original inhabitants in that area are given shelter in the very same area, lands for public facilities is made available to the planning agency and the remaining area is developed and sold freely in the market.

Slum Improvement

It provides land or housing to the urban poor near their work place. The scheme is also applicable to land reserved for public purposes on the condition that land on reduced scale is made available for the reserved purpose.

7.1.4 Different Fiscal Measures

Property Tax


Property tax has been the principal tax related to land and buildings. This tax according to provisions of Paurashava Act, 2009 is levied on the annual ratable value which is to be determined on the basis of area of lands or buildings.

Betterment Levy

The policy measures which can achieve optimum use of urban land use in practice still remain to be sharpened and coordinated. The measures can be classified as a) direct government investment b) legal and regulatory; and c) fiscal. Examples of these are:

1) Direct government investment in land development for provision of infrastructure, housing or overall town development through large scale compulsory land acquisition or other land development scheme
2) Statutory provisions for compulsory acquisition of land at less than market price, regulations regarding land use zoning, development control and building codes for health and safety
3) Fiscal measures in the form of appropriate taxation that can help achieve the land policy

Map 7.1: Structure Plan of Gauranadi Paurashava



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary
- Agriculture
- Circulation Network
- Core Area
- Fringe Area
- New Urban Area
- Periphery Area
- Waterbody

0 195 390 780 1,170 1,560 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com

In Association with

7.2 Plans for New Urban Area Development

The Pourashava is not an ideal township due to the agriculture domination. Agriculture based township should be encouraged in the preparation of Urban Area Plan. Growth of population is the natural trend and at the sametime, expansion of non-agricultural use on agriculture land is also natural tendency of the people. This will be controlled through the Compact Township concept with the encouragement of vertical development. In case of government services, specific building may accommodate different type of offices.

Future landuse will be calculated according to the development control for the masses. In case of public land, existing use and khas land will be emphasized. Willingness and participation of the people in development activities will be the key factor for future landuse demarcation. Slow change of landuse will be emphasized rather than rapid change. Let the people do whatever he likes on own land – such concept should not be considered for future projection of landuses. Three parts of the projection are landuse change, landuse control and landuse restriction will be included in the Master Plan. In any case, river front areas should be restricted for human habitation. As a result, river water will safe from contamination.

The agriculture land should be preserved (according to the Agriculture Policy) from any type of physical development. It should not be decreased with the expansion of habitable area or formation of new settlement, may be increased with the formation of char lands. In case of road, embankment, drainage and new urban area, the agriculture land may be used but such use should be guided according to this plan. For the development of pisciculture, all ponds (not lower than 0.15 acres) and ditches may be preserved, in some exceptional cases; small number of ditches and ponds may be used for physical development activities.

People's willingness will be considered as important base for the projection because the Master Plan is for the inhabitants of the Paurashava. They will be the beneficiary group of that Master Plan. Their willingness in case of use and land allocation, location, expansion provision will be the important consideration. On the basis of fulfillment of their demand, they will like to involve them willingly in the implementation procedure of the Master Plan.

Policies and Strategies

A large number of constraints are involved with the development of new area. Following strategies are involved with the development of new areas:

- Low incomes;
- Difficulties associated with assembling parcels of land which are large enough to make viable development sites;
- Disputes over ownership;
- Absence of private sector land developers;
- Lack of access (capable of resolution often only by works on land under the control of others); and
- The need in most cases for land to be prepared in some way prior development either by filling where it is subject to flooding or by earth moving where it is too steep to develop. In both cases, drainage works have to form an essential part of the land preparation task.

The policies and strategies of the Paurashava related to new area development are –

Explore and Implement means of increasing the number and pace of public sector land development projects: This is one area where government can have a direct influence on accelerating the rate of conversion of non-urban to urban land.

Explore and Implement, with the private sector, means of increasing the number and pace of private sector land development projects: In moving towards realization of the objective of government supporting the private sector in its development role (i.e. acting as an enabler rather than a provider), the Paurashava will examine, with the private sector, the means of overcoming the constraints to new area development.

Realization of the above two strategies is likely to require changes in legislation and administrative procedures at the national level. The other strategies of the Paurashava relating to new area development are set out below.

Promote upgrading of the existing urban area: As densities within the existing Paurashava Town increase, there will be growing pressure for upgrading to ensure that infrastructure provision is adequate and that living conditions are acceptable.

Most of the parts of the Paurashava are in agriculture practice and few parts are in urban area will require no upgrading at all. Accordingly the Paurashava will set priorities throughout the study area and ensure, through its own efforts or the efforts of others, that upgrading projects are necessary. Obvious areas for early consideration will be slum and squatter settlements. Local community and NGOs may involve with the upgrading projects.

Ensure that land is available for all income groups: In accordance with Government's commitment to poverty alleviation, as expressed in the Poverty Reduction Strategy and the objectives of the National Housing Policy, a further major task facing the Paurashava is to ensure that land is made available for all income groups.

Reconsider the role that development control plays in the planning and management of new area: Where development control is institutionally well-established (with adequate legislation, administrative resources and enforcement power) it can be a very effective 'tool' in restricting new area development where it is considered unsuitable; encouraging it in areas where it is considered suitable; and influencing the type of development that takes place in any particular location. It can attempt to strengthen development control institutionally to enable it to perform its role more adequately. On the other hand, it can consider restricting the role of development control to those functions which it considers critical such as ensuring that development does not take place in corridors required for new road construction or road widening, or ensuring that polluting industry takes place only in areas which are suitable for it.

Encourage the development of unused or underutilized land rather than new areas: The Paurashava is characterized by having much unused or underutilized land within the heart of the town. This land represents a wasting asset. If maximum use is to be made of the existing investment in infrastructure and if journey times are to be kept short, then fuller utilization of this land is essential. The Paurashava will examine the reasons why such land remains unused or underutilized and will endeavour to overcome the constraints to its development.

7.3 Areas for Conservation and Protection

In Gauranadi Paurashava, there are no heritage sites under Paurashava area. One of the major land uses of the Paurashava area is the agriculture which covers about 65% of total area. The agricultural land is direct and indirect source of income and has a great contribution to trade and commerce of Paurashava. It has been observed that among all wards, ward no. 7, ward no 8 and ward no. 9 have about 12.23%, 13.56% and 22.19% coverage of total agricultural land area & about 63.78%, 71.07% and 81.21% of total land area of respective wards. In ward no. 1, 4 and 6 about 13.30%, 13.99% and 13.28% lands of total ward area are covered under water bodies. So these show that about 67.94%, 72.28%, and 72.88% lands are covered under agriculture and water bodies at ward no. 1, 4, and 6.

Other feature which requires protection is the water bodies of the Paurashava. Though encroachment rate of the Khals/drains by the unauthorized construction and unauthorized cultivation on the bed of khals including aqua-culture is very low. But due to lack of regulations encroachment may occur in near future. Besides with the appropriate use and management of these natural lines, it might be possible to manage the drainage situation of the area. In addition, Water Reservoir Act, 2000 should be followed in preservation of these water bodies as per requirement. Most of water bodies are using at present for fishing purpose. So, the preservation of these water bodies not only required for drainage but also it will be potential for economic activities.

Chapter-8

STRATEGIES AND POLICIES FOR SECTORAL DEVELOPMENT OF THE PAURASHAVA

8.1 Socio- Economic Sectors

Once Gauranadi was a prosperous and rich area in the island; fish, and rice was main exportable item from upazila. Recently river erosion has appeared as a silent killer and disordered everything in the upazila. The area is now an out migrant prone, and losing its population.

From the population projection it has been observed that about 10666 additional population has to be accommodated in the existing planning area during the plan period. Present density of population is 10 persons per acre. At the end of the plan period, the estimated density would be 12 persons per acre.

8.1.1 Land use Control

Policy-01: Ensure best possible use of land

Reason: To contribute to the land for economic development and employment generation proper landuse is necessary. In Gauranadi Paurashava, plots devoted to agriculture purpose can be utilized for economically more profitable manner. Within Paurashava area, land is limited and agriculture has been discouraged.

Promotion: Prevent indiscriminate and misuse of land and initiate the relevant development projects.

Controls: Preservation and identification of resource based lands are as follows:

- Agricultural land for other urban uses.
- Inland Water bodies for fishery purpose and recreational purpose.
- Khas land will be distributed among the landless and a more transparent process of land settlement will be ensured

Implementation Agency: Paurashava**,** DOA, Settlement Office (Land Office), BWDB.

8.1.2 Economic Development

Gauranadi Upazila is dependent on service activity and fisheries through direct or indirect involvement. Cyclone, water logging and subsequently salinity problem is common in Gauranadi. Emphasis is given to accelerating the economic development by restoring the economic base of the Paurashava.

Policy-01: Creation of storage facilities and cold storage

Promotion: Emphasis should be given to the following issues:

- Establishment of cold storage
- Inland Open Water preservation

Implementation Agency: DOF, BFDC, LGED.

Policy-02: Light Industries need to be developed to flourish the industrial sector development

Reason: To accelerate the economic development of Gauranadi Paurashava in the long run, it is required to encourage the industrial establishment within Paurashava area.

Control: To control the haphazard industrial development measures will be undertaken:

- Follow the category of industries as categorized by DOE (Green Category) and Bangladesh National Building Code (low and medium category hazards)

- Follow Bangladesh National Building Code, 1993 and Building Construction Regulation, 1952 (amendment in 1996) for providing Road, setback before construction of any industrial structures
- Following the Coastal Zone Management Policy, 2005 all industrial units will be required to install built-in safeguards against pollution within a given time-frame. Units failing to comply with the pollution standards will be required to pay "green tax" for cleanup of the environment polluted by them

Implementation Agency: DOE, BSCIC.

8.1.3: Employment Generation

Policy-01: Encourage investment in business

Justification: Local people can be encouraged to invest in business.

Implementing Agency: Paurashava, Private Sector.

Policy-02: Reduce cost of doing business

Justification: Authority can reduce cost, revenue on business to encourage people.

Implementing Agency: Paurashava, Private Sector.

Policy 03: Employment Generation through Development of Potential Sectors

Reason: To sustain economic activity of Paurashava people for longer period. The economic activity of existing Gauranadi Paurashava is oriented with mainly Agriculture, Fishing and Water-way Transport Sector in some extent. Proper planning and co-ordination among these sectors and future potential sectors it would be possible to engage active labor force.

Promotion: Following measures will be encouraged to implement this policy implication:

- Industrial Zone declaration in Land Use Zone (mainly light industries)
- Infrastructure development to flourish fishing industry (Market, Ice Factory, Storage facility, electricity supply etc.)
- Water-way network development (more trawlers, launches, etc.)
- Involvement of active labor force and community participation in different management activities of Paurashava such as solid waste management in transferring the wastes from Solid-waste transfer sites, road maintenance, public sanitation

Implementation Agency: Paurashava**,** DOA, Settlement Office (Land Office), BIWTA.

8.1.4 Housing and Resettlement Zone Development

Pourahava, NHA and other public agencies can pursue the following policies to develop housing facilities and planned development for housing units. But there is no local office of the NHA to execute housing program at upazila level. Paurashava can facilitate housing areas with site and services in designated housing zones including resettlement areas.

Policy-01: Making provision of affordable housing for the low income people

Justification: Paurashava has to think about housing facilities for the low income people. Private sector will be operated for profit earning, the low income people will not access to these scheme. Thus to reduce unplanned development, the development authority may take initiative for low income people. Also by providing services the general people can be encouraged to build their own houses.

Implementing Agency: Paurashava. NHA.

Policy-02: Establishing resettlement zone for erosion affected people

Justification: Paurashava has to think about the erosion affected people & also about the people who are affected by any type of development project. Affected people will not be able to access to the schemes offered by private sector.

Implementing Agency: Paurashava**,** NHA.

Policy-03: Continuous monitoring of land and housing market

Justification: The authority should monitor the main aspects of land and housing market through data base. The Paurashava and land registry office can maintain data base and can undertake studies from time to time using GIS.

Implementing Agency: The Paurashava and land Registry office.

8.1.5 Social Amenities and Community Facilities

All social and community facilities like health, education, religious, community centre and other facilities are included in this category. In terms of number and size of facilities the allocation land with approximate location can be determined by analyzing the pattern of existing facilities and the calculation of the requirements in future. In addition some policies recommendations were made on health, education and other facilities.

Policy-01: Social amenities and community facility to be provided as per requirement of existing and forecasted population

Justification: To enhance access to land with secure tenure and to promote a social lively environment for an increasing population. Both Public and private sector investments are encouraged.

Provision of standards, rules and regulations are followed in allocating Educational Religious, Community Centre and Other components in Land Use Plan of Urban Area Plan.

Implementing Agency: Paurashava, NGO, CBO.

Policy-02: Creation of Training facilities at the grassroots level family planning workers for motivational activities

Justification: Grassroots workers can give door-to-door motivational services to the local people.

Implementing Agency: Ministry of health and family planning, Ministry of Mass Education, NGO.

8.1.6 Recreational Facilities

Policy: Ensuring community level recreational facilities like open space, park, and play ground etc.

Justification: To provide a livable environment for the Paurashava people, community level recreational facilities should be preserved. In the long run, preservation of recreational lands for future generations should be ensured. At present, only 0.17 acre is devoted for Recreational facilities. Parks should be created at central and at neighborhood level through Master Plan and Ward Action plan.

Both public and private sectors investment is encouraged.

Standard wise recreational facilities such as Play ground, Neighborhood parks, Stadium, Cinema hall will be provided as described in Land Use Plan of Volume II.

Implementing Agency: Paurashava, Public / Private sector.

8.1.7 Safety and Security

Considering the present law and order situation and its impact on the urban life it is necessary to face the challenge of restoring law and order. The major responsibility of these tasks goes to police department. Law and order in the Paurashava and its surrounding has to be ensured.

Policy: Improvement of law and order services for all citizens

Justification: Improvement of law and order is a national issue. Anyway local level community policing can be organized for ensuring security at local level.

Implementing Agency: Paurashava, Home Ministry.

8.2 Physical Infrastructure Sectors

8.2.1 Traffic and Transportation

Traffic is the function of landuse. It is also mention here that traffic network and the traffic generated induces the growth of landuse. Road networks will play strategic role in opening up undeveloped areas of the future term and shape up its structure. There is an interrelation between road network and utility services which together play key role to guide physical development in the town and Paurashava.

Policy-01: Develop efficient inter town communication facilities

Justification: To avoid traffic congestion within the Paurashava, the roads have to be widened. The main artery of the Paurashava has to be kept free from any development.

Implementing Agencies: Paurashava, RHD.

Policy-02: Maintenance or repairing of roads

Justification: To develop and facilitate easy means of transport, the authority should give emphasis on the maintenance or repairing of existing roads where needed.

Implementing Agencies: Paurashava.

Policy-03: Development of missing linkages

Justification: For easy, convenient, and safe movement, it is recommended that all missing linkages on roads are to be linked.

Implementing Agencies: Paurashava, RHD.

Policy-04: For better accessibility transport terminals should be located at major roads of the Paurashava

Justification: To develop and facilitate easy means of transport consultant suggest that the promotion of public transport is to be encouraged.

Implementing Agencies: Paurashava, RHD.

Policy-05: Functional and hierarchical road network development

Justification: Road Network has been developed without following any planned pattern.

Controls: Following the existing condition, of Gauranadi Paurashava, some strategies will be persuaded before incepting the Transportation Development Plan.

- Make a priority for in space allocation of ROW for better space utilization and promoting non-motorized traffic avoiding interruption, ensuring speed with motorized traffic.
- 10-20 ft. plantation at road side will be proposed.
- The Road Hierarchy of Gauranadi Paurashava will be modified and proposed on the basis of Road width Standards as described Chapter 3, Transportation and Traffic Management Plan, Volume-II.
- Follow up the basic rules mentioned in Building Construction Act, 1996 at Major Intersections of the Paurashava. Some basic rules are:
    - ✓ In each Corner plot of major intersection 1m×1m land area has to be open for traffic movement.
    - ✓ At the cross section of two or three roads within 50 meter distance, construction of commercial complex, Cinema Hall etc. are prohibited. But, 500 square meter area in total is permitted for commercial purpose (Shopping Complex), road width is 23 meter or greater.
- Promote efficient traffic management system within Paurashava by pursuing Regulatory measures (parking control and speed control in Highway Road, access control of trucks in Paurashava area,) and Design measures (Details of lay-out of Proposed Primary Road and Secondary Road in Paurashava area, use of lighting equipment etc.) in Paurashava Road Transportation System

Implementing Agency: RHD, LGED, Paurashava.

Role of Bangladesh Inland Water Transport Authority
The Torki River is flowing on the eastern part of the Paurashava from north to south. Bangladesh Inland Water Transport Authority (BIWTA) is responsible for maintaining its navigable character. Unauthorized encroachment in different locations of this river is performing by the dwellers. At present, the BIWTA is not performing any responsibility regarding this river. Apparently no major problem in the area of water transport services is found.

8.2.2 River Erosion Control and Drainage

Policy: Incepting drainage network plan in response of water logging problems

Justification: Lack of adequate and planned drainage facility in Gauranadi causes Water logging problem. The depth of maximum internal inundation ranges from 2-5 ft and duration varies 3 to 4 hours.

Following strategies should be reflected in Drainage Network Plan:

- A planned Drainage network will be provided in Drainage and Environment management Plan considering the standards, appropriate method and formula
- Regular maintenance of existing man-made and natural drainage network with Community involvement
- Illegal encroachment of Water bodies by Water Reservoir Conservation Act, 2000 ensuring storm water drainage
- Scattered throw of solid waste in water bodies by proper solid waste management activities

Implementing Agency: Paurashava, BWDB.

8.2.3 Utility Services

Policy-01: Facilitating access for all citizens to basic level of services in water supply and sanitation

Justification: To reduce the incidence of water borne diseases and increasing the present coverage of safe drinking water by lowering the average number of users per tube well.

- Facilitate safe drinking water supply and safe sanitation to each household as per demand in 2031 through various means, including:

  - Piped Water Supply System
  - Water treatment plant, Overhead Tank
  - Rainwater Harvesting and Conservation

Prescribed Standards have to be followed in providing facilities as mentioned in Urban Area Plan under Plan for Urban Services.

Implementing Agency: DPHE, Paurashava.

Policy-02: Facilitating access for all citizens to electricity supply

Justification: According to BBS, community series 2011-Barisal, at Gauranadi Paurashava, about 85.0% (9273 households) of the total households has electricity connection. Besides, to accelerate the industrial development (Agri-based, fishery) in Gauranadi Paurashava electricity, gas supply must be ensured.

Consumption of wood and other natural resources based fuel will be reduced. Also alternative energy sources will be encouraged (biomass, solar etc.)

Implementing Agency: PDB, REB.

8.3 Environmental Issues

The Policies will strike a realistic balance between the existing livelihood requirements of the people and round environmental resources management that can ensure the livelihood in long term.

Policy-01: Preservation of ponds

Justification: To ensure natural water bodies and fish resources which are crucial to sustain the livelihood and to retain the eco-system.

Small and large sale fisheries Communities/Groups will be given incentives, training program will be developed on new and modern fish harvest techniques, conservation, distribution, pursing.
Permitted land use will be maintained in the demarcated areas that are as follows:

- Irrigation
- Provision of water way transportation in wet season
- Fishing/Fish Culture

Implementing Agency: BIWTA, BWDB, Paurashava, DOA.

Policy-02: Identifying the erosion risk zones

Justification: As Gauranadi Upazila is an island, Cyclone is the frequent hazard and flood is the secondary impact and most apparent impact accrued from Cyclone Hazard. During Cyclonic hazard the level of water is raised up to 8-10 ft (<=3.05 m) (maximum). Therefore, strengthening

disaster preventing and mitigating mechanisms to enhance the coping capability to the Poor in times of natural disaster is vital in this Paurashava context.

Environmental Management Plan will be prepared under Urban Area Plan for all possible hazards (Cyclone, Flood, River Erosion, etc.). The Plan will provide the adaptation, prevention (structural/non-structural measures), mitigation, Preparedness techniques against a natural disaster through comprehensive disaster risk management.

To reduce the impact of hazards same manures will be undertaken which are as follows:

- Embankment, flood control sluice gates and other structural measures
- Early Warning System
- providing of multi-purpose cyclone shelter

Implementing Agency: Paurashava, BWDB, LGED.

Policy-03: Ensuring safe sanitation for citizen

Justification: In Gauranadi Paurashava, the sanitation condition of Paurashava is not so much satisfactory. There exist two types of latrine viz. katcha and Pucca. Besides, dumping of solid wastes in a scattered way is a common phenomenon.

Following strategies should be promoted in ensuring sanitation:

- Dumping Site and solid waste transfer sites demarcation in Land Use Plan of Paurashava area ensuring effective management including community participation
- Proposal of Solid Waste Dumping site
- Installing public toilets in schools, bus stations, launch Terminal, Markets, important public places and community latrines in densely populated poor communities or slums

The illegal connection of existing latrines with drains needs to be controlled through proper monitoring and in future

Implementing Agency: Paurashava, DPHE, LGED.

Policy-04: Pollution Control

Justification: Pollution level such as water, air and soil pollution rate is very low. As the area is located in coastal region, saline and iron also contaminate the water but at negligible rate. Besides air and soil pollution rate is also negligible. But this should not allow increasing pollution rate. To ensure safe environment for the Paurashava area, maintenance of the surface water quality is vital.

To control pollution following measures will be required:

- Make free surface waters form domestic wastes and other types of wastes which require proper solid waste management
- Riverside dumping needs to be restricted and dumping site has to be located through prescribed land use planning
- Discourage the high hazarders industries (Only Green Category Industries of DOE)
- Excessive pesticides and fertilizers use in Agriculture field cause soil pollution, therefore it is required to follow the Pesticides law, 1985

Implementing Agency: Paurashava, DPHE, DOE, DOA.

Chapter-9

IMPLEMENTATION ISSUES

This chapter deals with the issues of implementation of the Master Plan. Here, recommendations have been made about capacity building and resource mobilization for the implementation of the plan.

9.1 Institutional Capacity Building of the Paurashava

In the present context of spatial and legal jurisdiction of the Paurashava for planned development of its area, some recommendations are made here. Also, observing the financial and Institutional strength of individual stakeholders in relation to their liabilities and identifying their shortages and absence of any perfect coordinating body, some suggestions have been made as remedial measures as a whole.

- All urban local governments including Upazila level Paurashavas must be given more independence and autonomy to perform their responsibilities. At the same time, their accountability to the government and people regarding their performance has to be ensured. For this purpose the legal framework of the urban local governments has to be reviewed and updated. The legal provisions have to be consolidated and simplified and make them compatible to changing circumstances. Opportunities must be created in the Act allowing scope for privatization of service providing activities.
- To avoid duplication of development functions, there should be clear line of separation between central government and the urban local government.
- A double entry cash accounting system has to be introduced to modernize the accounting system. For this purpose, massive training programme has to be arranged for the relevant municipal staff.
- To improve revenue collection, the urban local governments should be given more power and responsibilities. Measures should be taken for strengthening the Paurashava administration for municipal development.
- Section-50 of the Local Government (Paurashava) Act, 2009 needs to be revised and more power should be given to the Executive Officer for appointment of employees.

It cannot virtually function effectively as a Paurashava under such a stringent financial condition. To function, effectively, it must raise its revenue earning. But it is reported that the Paurashava cannot collect all its holding tax from the citizens. Holding tax is the most important source of its own revenue earning. It must take care to ensure 100% recovery of holding tax. The Paurashava cannot function effectively depending upon government grant only. The existing manpower position of the Engineering, Development control and Accounts should be substantially raised to handle future volume of work. Moreover, additional staff especially for the implementation of Master Plan will soon be required.

The present plan package imposes a large number of development projects on Gauranadi Paurashava for implementation. Paurashava will not only be the custodian of the plan, it will also directly implement much of the development projects. Besides, it will also be responsible for monitoring and implementation of the development projects by other urban development and service giving agencies. This situation calls for strengthening of the existing capability of Paurashava.

9.1.1 Staffing and Training

As a traditional system of the Paurashava, engineer and secretary are appointed directly by the Ministry of Local Government and other staffs are appointed locally through the approval of the Ministry after the advertisement on the newspapers. In Gauranadi Paurashava, the revenue income is too low. That's why it is not capable to pay the salary of all the officials and staffs. The salary is recovered from the government grant and BMDF allocation. This is the main reason for under staffing of the Paurashava.

There is no proper arrangement for staff training. As a result, the staffs are mostly unskilled. They cannot deliver proper service to the citizens. Besides, most of them are not qualified enough to render proper services.

9.1.2 Lack of Automation

Most works in the Paurashava are done manually. Such practice delays works and deprives the citizens from services. This is also a source of mal-practice and corruption. Modern office and working equipment should be installed. Use of modern technology will increase efficiency in planning and record keeping, finally expedite decision making process.

9.1.3 Town Planning Capacity

9.1.3.1 Institutional Framework (Proposed by UGIIP, LGED)

To rearrange the institutional framework for the Paurashavas recently the government has made a committee for the categorization of all the Paurashavas of Bangladesh. According to the clause no. 72-78 (Paurashava Officer & staff, provident fund etc) of Local Government (Paurashava) Act 2009 and on the basis of the type and category of works, the committee suggested 5 divisions within the Paurashava framework. Afterward on the basis of the type of works, similarities and technicalities each division is further subdivided into some sections accordingly. The suggested divisions and sections are as follows:

1. Engineering Div:	a) Development, maintenance & quality control Section b) Water supply, sewerage, drainage and waste disposal Section
2. Planning Div:	a) IT Section b) Planning Section c) Beautification and recreation Section
3. Administrative Div:	a) Administrative Section b) Revenue Section
4. Accounts Div:	a) Budget, accounts and Audit Section
5. Public Health Div:	a) Food and Beverage Control Section b) Health and Public Welfare Section c) Poura Hospital and Clinic Section (optional)

According to the divisions and their relevant sections the manpower should be set up for each category of Paurashava.

The above committee has also chalked out the detail scope of work for each division. The scope of proposed Planning Division is given in **Figure 9.1**.




Fig 9.1: Scope of Work for Planning Division

9.1.3.2 Lack of Paurashava Town Planning Capacity

At present, the Paurashava has no town planning section or any appropriate manpower to prepare and implement the Master Plan. For proper implementation of the Master Plan for each Paurashava under UTIDP, establishment of a separate planning unit is indispensable. The Paurashava must strengthen its capacity to implement its Master Plan when it will be completed. It will otherwise be in trouble for implementation, monitoring and updating the Master Plan.

Gauranadi is a 'B' class Paurashava. For the 'B' class Paurashava Government approved an organogram/ manpower requirement. If we compare the existing manpower with the approved organogram we find that there is a huge gap between the two. Many positions have been vacant since the inception of Paurashava. However, strengthening of the Town Planning Division is a pre-requisite for successful implementation of the Structure Plan. Following organogram of the Town Planning Division is proposed for staffing capacity building of this Unit.




Fig 9.2: Organogram for a "B" Class Paurashava.

Again, **Figure 9.3** shows Urban planning Division for a "B" class Paurashava. Here four posts for professional personnel, urban planners are created. Urban planner will be the head of the division and three other planners will appointed as assistant urban planners. These four planners will play the leading role in Town Planning Division for the Paurashava. And ensure the planned development of the Paurashava planning.




Fig 9.3: Proposed Urban Planning Division for "B" Class Paurashava

9.1.4 Legal Aspects

The drive to establish strong urban local governance in the Paurashava is yet to be legalized. The governance programs at present are operated project wise based on the formulated policies of the implementing agencies of the national government. The Laws that the country inherited are mostly prepared during the colonial rule to serve its own interests. Even after independence from the British, the issue of good governance was not infused into the new Acts formulated.

9.1.5 Good Governance in Legal Provisions

There is hardly any Act where the elements of good governance are clearly visible. The consultant has identified some Acts, where some elements of good governance can be traced.

The Paurashava/Municipal Act/Ordinances prepared at different times since 1960's have iterated for the preparation of Master Plan by the Paurashava/Municipality for its planned development. So far urban local government Ordinances/Acts made in 1967, 1977, 2008 and 2009, all suggested for planned development. The Local Government (Paurashava) Act, 2009 has made the provision of having a Master Plan prepared by a Paurashava within five years of its inception. The function of the Paurashava also includes that it ensures planned development following the rules of the Ordinance. But there is no provision for public participation in the Local Government (Paurashava) Act, 2009. In all these legal documents, people's role has been ignored which is the violation of the norms of good governance.

The constitution of the Peoples' republic of Bangladesh clearly spells out that the Government should work to minimize the gap between urban and rural areas. A planned Paurashava development in that pursuit can provide necessary services to improve quality of life in both urban and rural areas within the Upazila.

9.1.6 Financial Issues

Governance in Gauranadi Paurashava

Financial governance refers to transparency and accountability of financial matters. All financial matters must be transparent to all. People must know about the policies and programs of the Paurashava, how much revenue is collected each year and the amount of expenditure made on annual development. They must also be answerable to the people on how the public money is being spent and accounts being maintained.

The Ministry of LGRD and Cooperative has undertaken a number of projects in respect of establishing governance in upgrading Paurashava accounts system, like, UGIIP, STIFPP. Computer and accessories are supplied under these projects for automation of the accounts system. Besides, trainings are also offered to the Paurashava accounts staff for enabling introduction of automation in accounts system. But all these services have not yet reached Gauranadi Paurashava.

Revenue Management

The Paurashava still follows a traditional management system in tax collection and revenue management though a scheme of computerized automotive financial system has already been introduced in this Paurashava. Assessment section is responsible to assess the tax of the Paurashava and tax collection, and license and bazar section are responsible to collect the tax of the Paurashava. The public is mainly informed about tax collection during the presentation of annual budget. They may, however, get information from the councilor or Paurashava accounts office.

Paurashava's Financial Capacity and Plan Execution

The main focus of Paurashava financial governance is to establish automation in entire financial management. This includes computerization of accounts system, holding tax management, and billing of different service charges. Software for above functions have been supplied and installed

in the Paurashavas covered by financial automotive projects. The projects also provided training to the relevant staffs for functioning of the systems. With the implementation of these projects people can now instantly know about the status of their tax payment, bill payment, and licensing. This has not only made the functions of the Paurashava easy, but also has freed the citizens for paying bribe, and experiencing hassle.

The size of annual budgets of the Paurashavas indicates the poor financial status of the Paurashavas. With low income, Gauranadi Paurashava will have to depend substantially on the government funding for implementing the development projects. But the government has limitations of its resources. In such a situation, if the Paurashava cannot raise its own revenue adequately, it will not be able to execute much of the development projects under the Master Plan.

9.1.7 Monitoring, Evaluation and Updating

Monitoring and evaluation is a very important part of plan implementation. Monitoring helps check if the plan is being implemented properly. It also measures the level of implementation of the plan. If the plan implementation is not on track, corrective measures can be taken to put execution on the track. After expiry of any plan, evaluation is made about the errors and omissions. Such evaluation helps take corrective measures in the next plan. Such monitoring and evaluation must be carried out from within the Paurashava. But Gauranadi Paurashava is not equipped with qualified manpower to make such evaluation. Monitoring and evaluation of a plan is essentially, the responsibility of qualified and experienced planners. As there is no planner in the Paurashava, monitoring of plan implementation will be seriously affected. However, plan evaluation can be accomplished by means of out sourcing as and when it is required.

9.1.8 Periodic Review and Updating

The plan package needs to be updated regularly to make it respond to the spatial changes over time. But such updating would require relevant technical professionals and requisite fund that are highly lacking in Gauranadi Paurashava. As there is no planner or planning section in the Paurashava, review and updating of the Master Plan will require service of senior level planners that Paurashava might not be able to provide. This service will have to be procured by out sourcing and the Paurashava is not even capable to accomplish this financially either. This will create problem when the plans or its components gets obsolete or need to be changed. Another problem would arise when the duration of plans ends. It is necessary that the entire plan document (including all planning and land use proposals) should be reviewed every 4th year of the plan period and will come into execution from the 5th year. The aim of the review will be to analyze the status of implementation of plan provisions, the changing physical growth pattern, infrastructure development, and the trend of public and private physical development including growth direction.

A new set of plans will have to be prepared replacing the old ones. This problem, however, can be overcome by undertaking another planning project by LGED. So, for regular updating and changes, and plan implementation monitoring, the Paurashava should immediately set up a planning section with a number of planners and other staff. The section will not only look after planning, but will also be responsible for development control, estate management, and project preparation. Since the planners would be qualified and skilled in computer operation, they can also help achieving automation of the Paurashava functions.

9.2 Resource Mobilization

Resource mobilization will be one of the most challenging tasks in implementing the current plan package. Though the development proposals are said to be executed by a large number of development agencies, but it is beyond doubt that the heaviest burdens will have to be shouldered by the Paurashava. As a local government agency, it suffers from resource constraint due to low level of urbanization and investment by both public and private sectors. The land value will maintain perpetually low growth rate in the town. Therefore, prospect of mobilization of substantial resource from sale of serviced land is extremely meager. For the same reason, revenue earning from betterment fee, planning permission and other sources may also remain low. Paurashava is heavily dependent on the government for executing its development projects as it is unable to collect sufficient revenue from its tax and non-tax sources. Therefore, it is clear that execution of development projects under the current plan will depend heavily on the government response to supply adequate fund. This situation calls for increasing revenue earning by generating new revenue sources.

9.3 Concluding Remarks

From the past experience, it has been observed that plans are prepared for organized development, but development control has been subject to negligence. In most cases, execution has been piece-meal. It is unfortunate that town planning has not yet become a part of our urban development culture. Individuals develop lands and construct buildings with a little respect for planned development, and the concerned authority is also unable to exercise full control on development. Some strict measures are necessary to make stakeholders follow up plans and development rules. Awareness is to be built among the people to follow the Master Plan provisions and plan. Government agencies must be compelled to follow plans. Existing laws in this regard must be updated incorporating provisions of plan execution.

Part B. Urban Area Plan

10.1 Introduction

The Land use Plan is one of the four components of Urban Area Plan. Land use Planning rules are statutory rules to control land use according to planning standard. It is based on land use policies including Local Plans, such as residential density, road standard, provision of infrastructure and services. The relevant Acts and Master Plans of the cities are the legal instruments, which is in force with regard to exercise planning control and standards. Therefore, future land use of Gauranadi Paurashava is shaped by intermingling relation between existing and proposed land use.

The Terms of Reference (TOR) specify that the Urban Area Plan (UAP) / Multi- sector Investment Plan (MSIP) will consist of the following plans:

- Land use Plan
- Transportation and Traffic Management Plan
- Drainage and Environmental Management Plan
- Plan for Urban Services

10.2 Goals and Objectives

The overall land use plan makes an approach that balances economic, environmental and aesthetic concerns which preserve the natural resources and quality of life in Gauranadi Paurashava. Moreover, this plan will also make recommendations for the plan's implementation to guide Paurashava Town Planner and other officials when managing future growth and development of Gauranadi Paurashava. The specific goals and objectives of land use plan are described below:

Goal A: Provide a well-balanced mix of residential, commercial, recreational, and other urban services uses to serve the future needs of the community and to maintain the Paurashava as a desirable place to live

Objectives:

- Guide the development considering density standards including High, Medium and Low Density area
- Guide new development within or adjacent to existing development
- Explore possibilities to support industrial, business and commercial growth within Paurashava area by demarcating industrial, commercial zone that operates in a manner that protects the environment and uses our natural resources efficiently
- Recognize the need to accommodate all age groups in recreational pursuits
- Provide basic urban services to the Paurashava people

Goal B: Preserve and protect the aesthetic, ecological quality, function, and other values of the Paurashava's land and natural resources

Objectives:

- Discourage development within environmentally sensitive areas such as wetlands, floodplain and lowlands
- Require natural buffers where they exist, and require native tree planting or tree replacement in areas without natural buffers to minimize the potential of land use conflicts.

Goal C: Increase community awareness, support, and involvement in growth management and land and natural resource conservation efforts

Objectives:

- Improve public access and understanding of available land use, planning, zoning and environmental information
- Balance community improvements with available funding sources to ensure equitable taxation

Goal D: Provide and maintain a safe and reliable transportation network

Objectives:

- Ensure that new roads can connect to future streets on abutting properties, whenever possible
- Ensure practice of relevant laws and regulations to control the development of city pertaining with land use and road development

10.3 Delineation of Planning Areas

For determining the existing planning area, consultants have discussed with honorable Mayor, Councilors and the local people and they expressed their valuable opinion about this issue. Moreover, consultants have dully considered several issues such as population growth rate, direction of existing growth potentials, location and distance of Upazila and District Headquarter in respect of Paurashava location, land value within and surrounding the Paurashava, tax collection status, socio-economic status, other future national development plan, if any, etc. Considering the all issues, the planning area of Gauranadi has been considered 17.41 sq. kilometers.

11.1 Existing and Projected Land Use and Land Use Proposals

Land use Planning rules are statutory rules to control land use according to planning standard. It is based on land use policies including Local Plans, such as residential density, road standard, provision of infrastructure and services. The relevant Acts and Master Plans of the cities are the legal instruments, which is in force with regard to exercise planning control and standards. Therefore, future land use of Gauranadi Paurashava is shaped by intermingling relation between existing and proposed land use.

11.1.1 Existing Land Use

The existing land uses of the project area are shown in Table 11.1. In the land use pattern of the Paurashava, 15 types of land uses are found. It is clearly evident from the table that agricultural landuse (62.98%) dominates the Paurashava area; followed by residential landuse (21.58%), water body (10.70%), circulation network (1.48%) and Commercial (0.79%). **Map 11.1** shows the existing landuse of Gauranadi Paurashava.

Table 11.1: Existing Land use of Gauranadi Paurashava

Landuse	Area (acre)	%
Administrative	33.86	0.79
Agricultural	2710.33	62.98
Circulation Network	63.87	1.48
Commercial Activity	34.03	0.79
Community Facility	11.46	0.27
Education & Research	25.07	0.58
Health Facility	3.63	0.08
Industrial	5.91	0.14
Mixed Use	6.3	0.15
Open Space	17.87	0.42
Recreational Facilities	0.52	0.01
Transport & Communication	1.12	0.03
Residential area	928.74	21.58
Utility Service	0.01	0.00
Waterbody	460.48	10.70
Total	**4303.2**	**100.00**

Source: Land Use Survey, 2012.

11.1.2 Estimation on the Requirement of Different Land Uses

This section proposes land use zoning plan for different land uses of the future town. The estimations have been made according to the Planning Standard approved by the client.

11.1.2.1 Land Use Standards

According to the projected population density it has been observed that in 2031, this area will not be a high density area. On the basis of projected population and considered the planning standard additional demands for land had been calculated for various facilities such as residential, commercial, industrial, educational, public land, etc.

Agricultural lands, Water bodies will be preserved as existed unless lack of land availability is observed in providing urban services. In that case, non-productive agricultural lands can be devoted for specific urban services and also to control the density of the Paurashava area.

11.1.2.2 Land Requirement and Proposal

After the projection for the target year and analyses of existing Land Use, designation of different land uses is the foremost vital step to prepare Land Use Plan as the first component of Urban Area Plan. Before incepting the Land Use Plan for the year 2031, basic principles for different

category of Land Uses have been considered. In precedence, future land use designation and land use zoning have been identified. Finally, Implementation, Monitoring and Evaluation issues have been discussed as the steps after the plan completion to make the Land Use Plan perpetual through plan period.

To allocate the land in Urban Area Plan, one uniform planning standards has been followed and also some basic assumptions have been identified considering Land use Category. The population growth, existing growth direction, economic sector and overall Paurashava Context have been emphasized in Urban Area Plan. The assumptions are mainly reflection of Building Construction Act, 1952 (amendment 1996) which is the practiced law in Gauranadi Paurashava for approving Building plan or site plan. Fifteen Land use categories had been considered for Survey and interim phase but for Land use plan nineteen categories have been considered. Detail analysis of required land based on the standard provided by PMO, LGED is presented in the Table 11.2. Detail Land use plan has presented on **Map 11.2**.


Table 11.2: Proposed Major Land use of Gauranadi Paurashava

Sl. No.	Land use Category	Remarks	Area (Acre)	%
1	Administrative	All Government Offices except large scale service based offices as Civil Surgeon Office, DC Office, Police Box, Police Fari, Police Station, LGED Office, Paurashava Office, Settlement Office, Union Parishad Office, Upazila Headquarter, BADC Office, Fisheries Office, Ansar/VDP Office, Agriculture Office, Zila Parishad Office, Post Office, Telephone Exchange Office and Other Government Offices.	48.09	1.12
2	Agriculture	Agricultural land denotes the land suitable for agricultural production, both crops and livestock. It is one of the main resources in agriculture. It includes productive land (single, double and triple cropped), seed bed, fisheries, poultry farm, dairy farm, nursery, horticulture etc.	1826.27	42.44
3	Circulation Network	Road and Rail communication	373.13	8.67
4	Commercial Zone	The land used for commercial activities is considered as commercial land use. These activities include the buying and selling of goods and services in retail businesses, wholesale buying and selling, financial establishments, and wide variety of services that are broadly classified as "business". Even though these commercial activities use only a small amount of land, they are extremely important to a community's economy. Commercial land includes established markets and areas earmarked for markets.	54.39	1.26
5	Community Facilities	All community facilities including funeral places and other religious uses	22.24	0.52
6	Education & Research	All kinds of educational institutes like Primary/secondary/other Schools/ Colleges etc are mentioned to calculate the land use for education and research purpose.	57.93	1.35
7	Health Facility	Health Facilities include Upazila Hospital, Health Center, Maternity Clinic, Clinic etc.	17.66	0.41
8	General Industry Zone	Green and Orange A categories as per The Environment Conservation Rules, 1997	18.78	0.44
9	Open Space	Playground, Botanical Garden, Stadium, Zoo etc. (Facilities without or with minimum building structure)	77.27	1.80

Sl. No.	Land use Category	Remarks	Area (Acre)	%
10	Recreational Facility	Facilities other than those mentioned to Open Space and indoor based facilities with designated building structure i.e. Cinema Hall, Theater Hall etc.	8.36	0.19
11	Rural Settlement	Rural settlement includes the low dense residential area which is scattered and rural in nature. It may permit only low density uses. Aiming to control the growth of this zone, less service and facilities will be provided.	133.34	3.10
12	Transport Facilities	Under transport and communication land use both transport and communication services are considered. This category includes airport, bus terminal/ stand, ferry ghat, filling station, garage, launch terminal, post office, passenger shed, telephone exchange, ticket counter, transport office etc.	15.47	0.36
13	Urban Deferred	Optional depending on the Paurashava and the Consultant's judgment	130.60	3.03
14	Urban Residential	Urban Residential area is a land use in which housing predominates. These include single family housing, multi-family residential, or mobile homes. Zoning for residential use may permit some services or work opportunities or may totally exclude business and industry. It may permit high density land use	980.25	22.78
15	Utility Services	Utility services include Overhead Tank, Power Office/Control Room, Public Toilet, Sewerage Office, Waste Disposal ,Fire Service, Water Pump House ,Water Reservoir, Water Treatment Plant etc.	16.35	0.38
16	Mixed use	Mixed use means those lands which serve both the residential and commercial purpose.	70.35	1.63
17	Overlay Zone	If the consultant justify any area that should not be defined as other given definitions but the facility(s) may not be avoidable, they may use this category	Not applicable	-
18	Forest	Forest Designated Forest Area	Not applicable	-
19	Beach	Sea Beach	Not applicable	-
20	Historical and Heritage Site	The entire mentionable historical and heritage site.	Not applicable	-
21	Water Body	Equal or More than 0.25 acre and justification by the consultant and wet land will merge with water body	452.74	10.52
Total			**4303.20**	**100.00**

Source: Consultants Estimation

Map 11.1: Existing Landuse of Gauranadi Paurashava



Legend

- BG_Paurashava_Boundary
- BG_Mouza_Boundary
- BG_Ward_Boundary
- Agriculture
- Commercial
- Community Facilities
- Education
- Governmental Service
- Industry
- Mixed Use
- NGO
- Recreational
- Residential
- Road
- Services Activities
- Transport & Communication
- Urban Green Space
- Waterbody

0 220 440 880 1,320 1,760 Meters


Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

Map 11.2: Proposed Landuse Plan of Gauranadi Paurashava



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 180360 720 1,080 1,440 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com

In Association with

A) Residential Zone

Residential zone refers to all categories of urban residential areas, including exiting ones and the residential land use proposed under the present Master Plan. Here, residential zone comprises urban residential area. In order to accommodate the projected urban resident population in the study area, around 531.04 acres of land would be required up to the year 2031. On the other hand, 928.74 acres of land have already existed as residential plots in the Gauranadi area. There is surplus of urban residential land of 397.7 acre. The list of plot number and Mouza are given below:

Table 11.3: Development Proposal for Residential Zone

Landuse Name	Area (acre)	Ward No	Plot No	Mouza Name
Resettlement Zone	6.67	6	13, 15-28, 54, 56-58, 65, 391	Gobardhan
Low Income Housing	10.91	8	405, 413-38, 442, 546, 551	Diasur
Housing Area	33.93	9	885-86, 888-91, 893-94, 897-08, 910-923, 925-26, 956, 958-62, 979,1660-67, 1669-88, 1694-99, 1702-03	Harisana(Kasemabad)
Total	**51.51**			

B) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails and wholesale can be set up and function without creating hazards to surrounding land uses. In order to accommodate the commercial land in the year 2031, about 61.17 acres land will be required. On the other hand, 34.03 acres of land have already existed as commercial plots in the Gauranadi area. In response to the requirement, about 20.36 acres of land is proposed in the Master Plan. Table 11.4 shows the distribution of commercial land in the study area.

Table 11.4: Development Proposal for Commercial Zone

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Kitchen Market	3.94	2	70-71,176-77, 180-82, 188-92	Bara Kasba	Land Acquisition and establish	Continue the development	
		6	121,124-27, 132, 386	Uttar Bijaypur and Gobardhan			
		8	365-67, 508,	Diasur			
Katcha Bazar	0.36	7	534	Dakshin Bijoypur	Land Acquisition and establish	Continue the development	
Super Market	1.92	7	180-81, 191, 193-96, 198, 204,564	Asokati	Land Acquisition and establish	Continue the development	
Shopping Complex	2.79	9	679-87,689-90, 694-95	Harisana(Kasemabad)	Land Acquisition and establish	Continue the development	
Slaughter House	1.84	2	149, 157, 159, 165, 234, 236-37	Bara Kasba	Land Acquisition and establish	Continue the development	

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Wholesale Market	4.44	1	2123	Sundardi	Land Acquisition and established	Continue The development	
Neighborhood Market	1.23	9	572,574,591-92, 984	Harisana(Kasemabad)	Land Acquisition and establish	Continue the development	
Pauro Market	0.42	5	252-55, 257, 275,312	Char Gadhatali	Land Acquisition and establish	Continue the development	
Retailsale Market	3.42		228-41, 243, 277-78	Lakherajkasba	Land Acquisition and establish	Continue the development	
Total	**20.36**						

C) Industrial Zone

Small business, agriculture and fishing are the main base of the economy of the area. The plan needs to accommodate such industries those have growth potentiality related to the base of economy of Gauranadi Paurashava. Due to the environmental and ecological condition, the plan discourages growth of heavy industries in the planning area. The plan segregated industries generally in to two classes; (I) General Industrial Zone in where processing units, small scale and harmless medium scale industries can be placed and, (II) Heavy industries in where all type of medium, heavy and toxic industries can be placed. To allow industrial set up in the demarcated zone of Gauranadi, the plan will follow two norms:

I) For categorizing, allocating land and providing guideline to set up industries, the plan will strictly follow the “The Environment Conservation Rule, 1997”.

II) For allocating land to set up industries, the plan will prioritize environmental & ecological condition and base of the economy of Gauranadi Paurashava.

According to the standard industrial land about 132.87 acres land will be required in the year 2031. But the amount is too large for a Paurashava. Considering location, economic condition od Gauranadi the planning team proposed about 12.87 acres of land for industrial set up in Gauranadi Paurashava.

Table 11.5: Development Proposal for Industrial Zone

Type of facility	Area (Acre)	Ward no	Plot No	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Industrial zone	12.87	3	266-67,270-75, 329-46,348-51, 353-56,387	Baniasuri	Land acquisition and development all facilities	Development Infrastructure	Full function Activity

D) Agricultural Zone

Agricultural zone denotes the land suitable for agricultural production, both crops and livestock. It is one of the main resources in agriculture. Out of the total area (4303.20 acres) of Gauranadi Paurashava, the areas need to preserve from unplanned development to fulfill objectives sited in various national policies along with the Master Plan. Agricultural zone covers activities related to agriculture and agriculture related production activities; farm, fisheries, pasture, horticulture etc.

E) Administrative

Government Office refers such areas encompass accommodation of the offices of various government authorities along with semi-government and autonomous bodies. A few number of private bodies formed especially for public services can also be accommodated in this zone.

According to the projection, about 24.16 acres land will be required for this purpose to meet the administrative demand of projected people in the year of 2031 whereas at present 33.86 acres land is used for administrative purpose. In case of Paurashava Office 5 acres of land will have to be proposed respectively based on the standard. It is expected that in near future the authority will expand Paurashava area to meet its standard requirements. Other uses have been proposed in accordance with the standards. Table 11.6 reveals the distribution of proposed land of government offices at Gauranadi Paurashava.

Table 11.6: Development Proposal for Government Services

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Toll Center	0.31	3	213,247,280-81	Baniasuri	Land acquisition	Development Infrastructure	
Ward center	13.92	1	201,204-11,222-24, 728-29,731,733	Sundardi	Land acquisition	Development Infrastructure	
		2	14,73,75,77-78, 82, 84,1319,1321-22, 1370, 1373-77, 1395-98	Bara Kasba			
		3	208,210-13,280-86	Baniasuri			
		4	97,109	Dakshin Palardi			
		5	92,165-166	Char Gadhatali			
		6	140-44,180-81,214	Uttar Bijaypur			
		7	365-69	Dakshin Bijoypur			
		8	300-01,304,307	Diasur			
		9	730-33,1616,1619-20,1622	Harisana(Kasemabad)			
Total	**14.23**						

F) Recreational Facilities

There exists 0.52 acres of land for recreational facilities. According to the standard 7.66 acre of land is required for this purpose in the year 2031. Considering future need about 7.84 acres of land is proposed for recreational purpose. A stadium with 5.35 acres of land is proposed at ward no 9.

Table 11.7: Development Proposal for Recreational Facilities

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Stadium	5.35	9	843-44,846-52, 856-59,987	Harisana (Kasemabad)	Land acquisition	Development Infrastructure	
Shishu Park	2.49	4	160,174-89, 662	Dakshin Palardi	Land acquisition and development all facilities	Development Infrastructure	Full function Activity
		5	50,427,429	Tikhasar			
Total	**7.84**						

G) Open Space

Open space includes play field / play ground, park, neighborhood park, etc. according to the standard about 114.19 acres of land is required for projected population in the year 2031 while at present only 17.87 acres of land is used for this purpose. Table 11.8 shows the proposed lands to meet up the demand of projected people.

Table 11.8: Development Proposal for Open Spaces

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Linear Park	1.95	2	265,268-69, 277,357-58, 360,366,375 ,378	Bara Kasba	Land acquisition and development all facilities	Development Infrastructure	Full function Activity
Round About	0.07	6	346,370,405 -07	Uttar Bijaypur	Land acquisition and development all facilities	Development Infrastructure	Full function Activity
Playground	23.06	1	1746-52, 1765-67, 1769-80	Sundardi	Land acquisition and development all facilities	Development Infrastructure	Full function Activity
		3	821,824-27	Bara Kasba			
			245,252-58, 262	Baniasuri			
		4	32,34-37,39-46,51-53	Dakshin Palardi			
			398-99,402-07	Uttar Palardi			
		5	54,56-57,59-60	Tikhasar			
			195,197-99, 214-15,223	Char Gadhatali			
		6	226,344-48, 357	Saora			
		7	222,235-40, 253-55,258-59,262-65	Dakshin Bijoypur			
		9	783-84,875-	Harisana(K			

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
			80,882-88	asemabad)			
Park	31.79	1	2123	Sundardi			
		2	133,136	Tarkir Char			
		3	12-16,38-53, 363,99999	Lakherajka sba			
		4	121,124-26, 129-30,651-52	Dakshin Palardi			
		5	95-96,99-06, 108,115,118 ,222-24,414, 419, 421-23	Tikhasar			
		6	191,196-02, 261	Saora			
		7	278-81,284-87	Asokati			
			491,493-95, 498	Dakshin Bijoypur			
		8	102-09, 405, 550	Diasur			
		9	956-59, 961, 964-68, 973, 1428-29, 1431-32, 1434-35, 1438-39	Harisana(K asemabad)			
Total	**56.80**						

H) Health Facilities

Health Facilities includes Upazila Health complex, health center or maternity clinic. Considering projected population in the year 2031, about 20.62 acres of land is required for various Health facilities whereas only 3.63 acres land is used in recent. To accommodate unanticipated spatial requirement of Health facilities about 14.03acres of land is proposed in the master plan. Table 11.9 shows the proposed lands to meet up the demand of projected people.

Table 11.9: Development Proposal for Health Facilities

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Clinic	9.77	1	636-37,649-58,753	Sundardi	Land acquisition	Development Infrastructure	
		5	60-61,147-48	Tikhasar			
			215-16,222	Char Gadhatali			
		6	71-73,186-88,191	Saora			
		9	769,771-75,778-80, 885,891-95	Harisana(kasema bad)			
Hospital	4.26	8	127-30,132,135-39, 142	Diasur	Land acquisition	Development Infrastructure	
Total	**14.03**						

I) Community Facilities

Community Facilities includes Masjid/Temple/Church, Eidgah, Community Center and Graveyard. Considering projected population in the year 2031, about 11.97 acres of land is required for various Community Facilities whereas 11.46 acres land is used in recent. 10.78

acres land is proposed in the master plan for this purpose. Table 11.10 shows the proposed lands to meet up the demand of projected people.

Table 11.10: Development Proposal for Community Facilities

Type of facility	Area (Acre)	Ward No.	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Community Center	0.98	7	40-42,68-70	Asokati	Land acquisition	Development Infrastructure	
Pauro Library	0.14	5	134,156	Char Gadhatali	Land acquisition	Development Infrastructure	
Proposed Gausia Madrasa Graveyard	0.56	1	38,51-52	Sundardi	Land acquisition	Development Infrastructure	
Graveyard	5.70	6	349,352,354-55, 357	Uttar Bijaypur	Land acquisition	Development Infrastructure	
		9	1296-04, 1306, 1316-17	Harisana(Kase mabad)			
Shamshan ghat	3.40	2	133,136	Tarkir Char	Land acquisition	Development Infrastructure	
		5	96,225-31,238-41, 243,278,417-18	Tikhasar			
Total	**10.78**						

J) Education and Research Zone

Educational zone refers all kind of educational set up; School, Colleges, Madrasha and even such institutions operated for education like; training institutions, research institutions etc. In order to meet up the demand of projected population (2031), about 82.01 acres lands will be required. In the proposal 32.86 acres of land is given for educational purpose. Most of the primary schools are proposed in the residential areas. Table 11.11 presents the distribution of proposed land under education and research institutions.

Table 11.11: Development Proposal for Education and Research Zone

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Girls College	4.48	7	251,253-54, 256,265-69, 289-95,308-10	Dakshin Bijoypur		Land acquisition and development all facilities	
College cum Cyclone Shelter	8.49	1	1739-46,1748-52,1754,1758	Sundardi			
		4	261,264,268-74, 276-78,	Dakshin Palardi			

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
			280, 318,660				
Girls School	3.07	9	770-71,896-97, 1645,1648-51, 1654-58,1661-62	Harisana (Kasemabad)		Land acquisition and development all facilities	
Secondary School cum Cyclone Shelter cum Cyclone Shelter	9.66	3	242-53,259	Baniasuri		Land acquisition and development all facilities	
		4	331,333-46, 398	Uttar Palardi			
		6	177-78,224-25	Saora			
		8	36-39,51-54, 142-43	Diasur			
Primary School cum Cyclone Shelter	4.70	3	823-24,826-27, 829,836-39	Bara Kasba		Continue the develop ment	
		7	86-91	Asokati			
Vocational Training Center cum Cyclone Shelter	2.45	2	1244-46,1248-54,1305-07, 1317	Bara Kasba		Land acquisition and development all facilities	
Total	**32.86**						

K) Water Body

Water body contains all natural streams; canals, khals, irrigation canal, depressions like; beel, wetland, low laying areas and ponds. No standard is being prescribed for water body from the UTIDP. The Paurashava is rural-based urban area. In the proposal about 452.74 acres of water body are being preserved though existing total water body is 460.48 acres. These waterbodies have been preserved under the Water body Act 2000. The rest of the lands have been used to meet up the requirements of other facilities at Paurashava.

L) Circulation Network

Circulation Network refers all kind of public roads along with related facilities; footpaths, walkways etc. and embankment, railway (if exist in the area). According to the Traffic and Transportation Management Plan, about 373.13 acres of land have been proposed for circulation network at Gauranadi Paurashava area whereas at present only 63.87 acres land has been used for these purposes.

M) Transportation Facilities

Transportation facilities include Bus / Truck Terminals, Launch Terminal, Other Vehicle Parking Space, Gas/ Fuel Station, etc. Considering projected population in the year 2031, about 8.73 acres of land is required for various transportation and communication facilities whereas only 1.12 acre is used in recent. To accommodate unanticipated spatial requirement of transportation and communication sectors about 14.35 acres of land is proposed in the master plan including various facilities such as bus terminal, truck terminal, launch terminal, other vehicle parking, etc. Table 11.12 shows the proposed lands to meet up the demand of projected people.

Table 11.12: Development Proposal for Transportation Facilities

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Bus Terminal	0.92	6	451	Uttar Bijaypur			
	5.22	9	1488-96,1787-92, 1795	Harisana (Kasemabad)			
Rickshaw stand	0.40	1	30-31,52,54-55	Sundardi			
Fuel station	1.21	4	163-66,169-70	Dakshin Palardi		Land acquisition and development all facilities	
Tempo Stand	3.88	1	316-17,321-27, 329-30, 332-35	Sundardi		Land acquisition and development all facilities	
		9	1493,1496-03, 1525	Harisana (Kasemabad)			
Truck Terminal	1.09	2	101-03	Tarkir Char	Land acquisition	Development Infrastructure	
	1.63	3	268-71,275-76, 283	Baniasuri	Land acquisition	Development Infrastructure	
Total	**14.35**						

N) Utility Service

Utility Service includes Solid waste disposal site, waste transfer station, Water Treatment Plant and fire service. Considering projected population in the year 2031, about 18.22 acres of land is required for various Utility Services whereas no land is used in recent. To accommodate unanticipated spatial requirement of Utility Services about 16.35 acres of land including Electric Sub-Station is proposed in the master plan. Table 11.13 shows the proposed lands to meet up the demand of projected people.

Table 11.13: Development Proposal for Utility Services

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
Overhead Tank	1.54	3	597,600-01, 603-04,606-07	Baniasuri	Land acquisition	Development Infrastructure	
Water Treatment Plant	3.91	6	122-23,126-27, 195-03	Gobardhan			
Waste Disposal Site	5.43	9	1783-87,1792-95, 1799-01	Harisana(Kasemabad)		Land acquisition and development all facilities	
Waste transfer station	3.16	1	1998,2015	Sundardi		Land acquisition and development all facilities	
		2	317,1136	Bara Kasba			
		3	524-27	Baniasuri			
		4	152,194,197-98, 249, 255, 326-27	Uttar Palardi			
		5	184,186-87	Tikhasar			
		6	14-18	Saora			
		7	54,186,191-93,	Dakshin Bijoypur			

Type of facility	Area (Acre)	Ward no	Plot no	Mouza Name	Phase-wise development		
					1st Phase (1st to 5th year)	2nd Phase (6th to 10th year)	3rd Phase 11th to last 10 year)
			365-66				
		8	254-55	Gerakul			
		9	706	Harisana(Kasemabad)			
Total	**14.04**						

O) Restricted Area

Restricted Area includes Electric substation and Sub jail. Considering projected population in the year 2031, about 12.66 acres of land is required for Restricted Area, whereas no land is used in recent. To accommodate unanticipated spatial requirement of the Area about 2.31 acres of land has been proposed for Electric Sub-Station consisting plot no. 357-58,403,407-12, 99999 is proposed at Ward No.01.

P) Urban Deferred

Urban deferred area includes potential land reserved for future use. Standard shows 10% of total build up land and new urban land should be used as Urban Deferred area. According to it, 130.60 acres land has been conserved for this purpose.

Table 11.14: Land Requirement, Existing and Proposed Land use of Gauranadi Paurashava for the Year 2031

Sl. No.	Landuse Categories	Types of Landuses	Recommended Standard	Projected Required Land for 2031(Acre)	Existing Land (Acre)	Deficiency/ Surplus (Acre)	Proposed Land (acre)
1	Residential	General residential	100 – 150 persons/1 acre	531.04	928.74	-397.7	51.51
		Real Estate – Public/Private	200 population/ 1 acre				
		Total		***531.04***	***928.74***	***397.7***	***51.51***
2	Education and Research	Nursery	0.5 acre/10,000 population	2.66			
		Primary School/ kindergarten	2.00 acres/5000 population	21.24			
		Secondary/High School	5.00 acres /20,000 population	13.28			
		College	10.00 acres/20,000 population	26.55			
		Vocational Training Centre	5 - 10 acres / Upazila	5			
		Other	5.00 acres / 20,000 population	13.28			
		Total		***82.01***	***25.07***	***56.94***	***32.86***
3	Open Space	Play field/ground	3.00 acres/20,000 population	7.97			
		Park	1.00 acre /1000 population	53.11			
		Neighborhood park	1.00 acre /1000 population	53.11			
		Central Park					
		Total		***114.19***	***17.87***	***96.32***	***56.80***
4	Recreational Facility	Stadium/sports complex	5 – 10 acres/ Upazila HQ	5			
		Cinema/ Theatre	1.0 acre /20,000 population	2.66			
		Total		***7.66***	***0.52***	***7.14***	***7.84***
5	Health Service	Upazila health complex/ hospital	10 -20 acres/ Upazila HQ	10			
		health centre/Maternity clinic	1.00 acre/ 5,000 population	10.62			
		Total		***20.62***	***3.63***	***16.99***	***14.03***
6	Community Facilities	Mosque/Church/Temple	0.5 acre /20,000 population	1.33			
		Eidgah	1.0 acre/20,000 population	2.66			

Sl. No.	Landuse Categories	Types of Landuses	Recommended Standard	Projected Required Land for 2031(Acre)	Existing Land (Acre)	Deficiency/ Surplus (Acre)	Proposed Land (acre)
		Graveyard	1.00 acre /20,000 population	2.66			
		Community centre	1.00 acre /20,000 population	2.66			
		Cremation Place	1.00 acre /20,000 population	2.66			
		Total		***11.97***	***11.46***	***0.51***	***10.78***
7	Commercial	Wholesale market	1.0 acres/ 10000 population	5.31			
		Retail sale market	1.0 acres/ 1000 population	53.11			
		Corner shops	0.25 acre/per corner shop	0.25			
		Neighborhood market	1.00 acre/per neighborhood market	1			
		Super Market	1.50 – 2.50 acres/per super market	1.5			
		Total		***61.17***	***34.03***	***27.14***	***20.36***
8	Utility Services	Drainage	As per local requirement				
		Water supply	1.00 acre /20,000 population	2.66			
		Gas	1.00 acre /20,000 population	2.66			
		Solid waste disposal site	4-10 acres/Upazila HQ	4			
		Waste transfer station (9 nos)	0.25 acres/per waste transfer station	2.25			
		Fire Service	1.00 acre/20,000 population	2.66			
		Telephone exchange	0.5 acre/20,000 population	1.33			
		Water Treatment Plant	1.00 acre/20,000 population	2.66			
		Overhead tank					
		Total		***18.22***	***0.01***	***18.21***	***16.35***

Sl. No.	Landuse Categories	Types of Landuses	Recommended Standard	Projected Required Land for 2031(Acre)	Existing Land (Acre)	Deficiency/ Surplus (Acre)	Proposed Land (acre)
9	Industrial	Small scale	1.50 acres /1000 population	79.66			
		Cottage/agro-based	1.00 acre /1000 population	53.10			
		Total		***132.76***	***5.91***	***126.85***	***12.87***
10	Transportation Facilities	Bus terminal	1.0 acre /20,000 population	2.66			
		Truck terminal	0.50 acre /20,000 population	1.33			
		Launch/steamer terminal	1.00 acre /20,000 population	2.66			
		Railway station	4.00 acre / per Station				
		Baby taxi/tempo stand	0.25 acre /one baby taxi/tempo stand	0.25			
		Rickshaw/van stand	0.25 acre /one baby taxi/tempo stand	0.25			
		Passenger Shed	0.25 acre /one baby taxi/tempo stand	0.25			
		Fuel Station	0.5 acre/20,000 population	1.33			
		Total		***8.73***	***1.12***	***7.61***	***14.35***
11	Administrative	Upazila complex	15.00 acres	15			
		Paurashava office (Ward Councilor's Office)	3 – 5 acres	3			
		Police Station	3 – 5 acres/Upazila HQ	3			
		Police Box/outpost	0.5 acre/ per box	0.5			
		Post office	0.5 acre /20,000 population	1.33			
		Telephone Exchange Office	0.5 acre /20,000 population	1.33			
		Total		***24.16***	***33.86***	***-9.7***	***14.23***
12	Circulation Networks	Paurashava primary roads	150 – 100 feet				
		Paurashava secondary roads	100 – 60 feet				

Sl. No.	Landuse Categories	Types of Landuses	Recommended Standard	Projected Required Land for 2031(Acre)	Existing Land (Acre)	Deficiency/ Surplus (Acre)	Proposed Land (acre)
		Paurashava local roads	40 - 20 feet				
		Total			***63.87***		***309.26***
13	Agriculture	Agri-extension Farm	10 acres/Upazila HQ	10	2710.33	-2700.33	-874.06
		Total		***10***	***2710.33***	***2700.33***	***874.06***
14	Restricted Area	Jail/Sub Jail	10 acres/Upazila HQ	10	**0**	10	0
		Electric Sub station	1.00 acre /20,000 population	2.66	**0**	2.66	2.31
		Total		***12.66***	***0***	***12.66***	***2.31***
15	Urban Deferred	Urban Deferred	10 percent of the total build up area and new urban area	52.91	0	52.91	130.60
		Total		***52.91***	***0***	***52.91***	***130.60***

Source: The Consultants' Estimation

* Here – indicates surplus of land, * indicates estimated by the consultants

11.2 Land Use Zoning

Zoning is a classification of land use that limits what activities can or cannot take place on a parcel of land by establishing a range of development options. Zoning has been defined as an action through legislation provided to a development authority/Paurashava to control a) heights to which buildings may be erected; b) the area of lots that must be left un-built upon; and c) the uses to which buildings may be constructed.

11.2.1 Area / Use Zoning

The objective of area zoning is to specify which types of land use are considered appropriate for different areas or 'zones', and it therefore indicates the planning control objectives of the authority or municipality for its administrative area. The authority is obliged under the planning acts to designate in its development plan objectives for the use solely and primarily of particular areas for particular purposes.

The zoning is defined as the regulation by law of the use of land and buildings and of the height and density of buildings in specific areas for the purpose of securing convenience, health, safety and general welfare of the community. Thus, the term zoning is used to include two aspects of planning- allocation of land for specific purposes and control of the use, height and construction of the buildings.

Though the future land requirements are the first priority of planning for a city but considering the existing land use there should be provision of zoning. The zoning will demarcate specific land use for a specific zone or area. The zones are usually classified into the following four categories with suitable sub-divisions in each zone:

a. **Residential zone:** the character and location of this zone will depend on various factors such as nearness to the markets; freedom from nuisance, noise and smoke; nearness to parks and playgrounds etc.
b. **Commercial zone:** this zone should be near the centers of traffic and preferably it should about the roads. It includes the uses of land for banks, offices, godowns, shops etc.
c. **Industrial zone:** great care should be exercised in providing units of industrial zone in various part of the town. The light industries and factories running on electric power and causing no nuisance to nearby areas may be allowed to be set close to residential areas. On the other hand, the heavy industries giving out obnoxious gases and fumes and developing noisy atmosphere may be placed on the outskirts of the town.
d. **Recreational zone:** This zone includes mainly parks and playgrounds and in a broad sense, it may be considered to include various recreational centers such as cinemas, theatres, town halls, clubs, libraries, restaurants, stadium and other community needs.

Besides these any special land use can get special emphasis on the basis of its intensity, significance on local, national economy etc.

11.2.2 Density / Bulk Zoning

Aim of the density zoning is to provide an acceptable density which is related to the designed facilities and amenities especially for the residential areas. This will ensure a healthy community and enjoyable community life. In a particular area, how much number of buildings will be permitted and constructed, the decision is under the density zoning. Provisioning of setback rule and percent of land uses for different purposes is the prime consideration of density zoning. The proposed percentage mentioned in the land use table is the only tool to control building density in the Paurashava.

11.2.3 Height Zoning

This zoning provides height limits for structures and objects of natural growth and standards for use of an area which encourage and promote the proper and sound development of areas. It is also applicable to height restrictions for flight safety around airports or other similar purposes.

For effective development control, in addition land use zoning individual facility and the structures therein is complied certain regulations imposed to ensure desirable end. Relation between ground cover of buildings and the land parcel that house it, minimum setback of building from the adjoining plot boundaries and the maximum floor area that can be constructed in relation to plot size and the connecting road among many other details, are controlled by Building Construction Rules 1996.

According to the Building Construction Rule, 1996, minimum permissible road width for obtaining plan permission is to shown, construction is allowed on plots connected by narrow roads provided the plot owner leaves formally half of the addition area needed to make the road 6m for widening the road to the permitted minimum. Perhaps the intension behind this was that gradually the whole road would rise up to 6m in short time and it is true for new areas. But congested unplanned area represents an alarming picture. In commercial area, most of the plots are occupied almost entirely by pucca structures covering the property line connected by the narrow pathways. Those owners did not bother for Paurashava's plan permission and a handful of those who obtained plan permission did not care to follow them. It is suggested that existing rules need to be modified to tackle the environmental problems created by illegal building construction.

11.3 Plan Implementation Strategy

11.3.1 Land Development Regulations to Implement the Land use Plan

Effective implementation of a plan is the most important part of the planning process. The process of Implementation needs to be carried out with care and efficiency in order to produce best outcomes. This chapter highlights various measures needed to be taken in order to implement the land use plan proposals.

Implementation of the Land use Plan depends on successful pursuit of the policies specified in the Structure Plan. Those policies represent a significant challenge face with the responsibility of planning and managing the development of the Paurashava area. However, at present no authority is responsible for planning and managing physical development activities in the Paurashava and no regulation except Local Government (Paurashava) Ordinance, 2009 for controlling physical development. This poses a serious constraint to the implementation of the Land use Plan and in fact any other form of development plans.

The factors that have been taken into account in deciding the priority include such things as – the importance of the issue that the policy addresses, its potential impact on the lives of the population, the ease with which it can be implemented, its urgency and its interdependence with other policies.
Prior to introduction of the regulations to implement the land use plan, legislative involvement is recommended here.

1. To control the air, water, noise and soil pollution, Conservation of Environment and Pollution Control Act, 1995 (Act No. I of 1995) was enacted. In the Paurashava, there is no authority for enforcing the provisions prescribed in the said Act. The pollution related with the implementation of land use component may be controlled with this Act.
2. Impose control on all type of buildings in the Paurashava according to the setback rule prescribed in the Building Construction (Amendment) Rules, 1996 (Notification No. S. R. O. No. 112-L/96). Building permission for extended areas shall be according to the land use provision prescribed in the plan. Any permission for building construction, front road width

shall not be less than 16 ft. and the construction must follow the Building Construction (Amendment) Rules, 1996.

3. Haphazard development of commercial activities is the general scenario of the Paurashava. It is necessary to impose control on commercial activities provisioned in the Shops and Establishments Act, 1965 (Act No. VII of 1965).
4. In case of man-made canal, regulations prescribed in the Canal and Drainage Act, 1873 (Act No. VIII of 1873) is the best weapon. For the linking of canal with others and river considering drainage facilities the Act may be enforced.
5. For the conservation of archeological monuments or structures or historical development the Ancient Monuments Preservation Act, 1904 (Act No. VII of 1904) may be enforced. Archeological Department of Bangladesh and Paurashava authority through a partnership process may preserve such type of development.
6. To control air pollution due to brick burning with the establishment of brick field, Brick Burning Control Ordinance, 1989 (Ordinance No. VIII of 1989) is the appropriate regulation. The Paurashava authority may enforce this Ordinance with the authorization given by the government to him.
7. To control the medical practitioner, establishment of private clinics and pathological laboratories, the statute named Medical Practice, Private Clinics and Laboratories (Regulation) Ordinance, 1982 (Ordinance No. IV of 1982) was enacted. For efficient enforcement of the Ordinance, the Paurashava authority may execute the Ordinance with the authorization of government.
8. The Paurashava will have to exercise strictly Playfield, Open space, Garden and Natural Tank in Urban Areas Preservation Act, 2000 (Act No. XXXVI of 2000) to some specially important areas like, riverfront and water bodies, drainage channels, low land below certain level, designated open space, etc. Development restrictions are needed around security and key point installations. The provision of restriction will strengthen the power of the plan to safeguard its development proposals and land use provisions.
9. The government is authorized for establishment of hat and bazar with the acquisition of land through the statute named Hat and Bazar (Establishment and Acquisition) Ordinance, 1959 (No. XIX of 1959). In case of private hat and bazar, a management body is being empowered through the Bangladesh Hats and Bazars (Management) Order, 1973 (P.O. 73/72). The Paurashava authority is also empowered establishing hat and bazar in his jurisdiction through the Local Government (Paurashava) Ordinance, 2009. Coordination may be framed among the government (Upazila Parishad), Paurashava and private owner for the establishment, development and management of the hat and bazar located in the Paurashava premises.
10. In the Paurashava premises, industrial development is controlled by the Bangladesh Cottage Industries Corporation through Bangladesh Cottage Industries Corporation Act, 1973 (Act No. XXVIII of 1973), Industrial Development Corporation through East Pakistan Industrial Development Corporation Rules, 1965 (No. EPIDC / 2A-2/63/354) and Factory Inspector through Factories Act, 1965 (Act No. IV of 1965). Locational aspects and issuing of trade license is controlled by the Paurashava authority. A joint coordination cell among those four authorities may control the establishment of factories and industries in the Paurashava.
11. In the Paurashava, for rain water harvesting, some specific ponds / tanks will needed to be preserved. A number of derelict tanks may be improved through tank improvement project and in this case Tanks Improvement Act, 1939 (Act No. XV of 1939) will support the Paurashava is regulatory aspects.
12. Except Khas land, a considerable amount of public land in the Paurashava may be identified as fallow land or unproductive land. In regulatory term those lands are considered as cultivable waste land and those lands are being fallow during five consecutive years. Those lands may be utilized under the guidance of Cultivable Waste Land (Utilization) Ordinance, 1959 (Ordinance No. E.P. XIII of 1959).

13. The Paurashava should raise its efforts on the imposition and realization of betterment fees to raise its income. In this case, East Bengal Betterment Fees Act, 1953 may be enforced.

11.3.2 Implementation, Monitoring and Evaluation of the Land use Plan

Implementation through Multi-Sectoral Investment Program: Major infrastructure development works such as primary roads, water supply, drainage, etc., will largely be controlled by Government. Public works requires efficient co-ordination through the Multi-Sectoral Investment Programme (MSIP).

Objective of a Multi-Sectoral Investment Programme (MSIP) will match a list of the development projects with the funding stream necessary to implement them. There are two basic activities that would determine the contents of MSIP. One activity would be to prioritize and schedule the investment projects of all public agencies so they will collectively help to achieve the development goals and objectives of the Land use Plan. Second activity would be to analyze the source and availability of fund for the prioritized list of development projects.

Implementation through Action Plans and Projects: Action Plans and Projects will be the implementation plans to solve problems at the local level. Action plans will take a direct approach toward plan implementation with a minimum of research, reports or elaborate planning methods. These projects will be easily identifiable and will require minimum resource.

Implementation through Development Control: Land use zoning is one of several methods of plan implementation to be considered. In all cases where some form of development, land use control may be applied; careful consideration requires the following ideologies:

- purpose to be achieved by the development controls;
- where controls should be applied;
- what aspect of development needs to be controlled;
- what type of development controls are required;
- what degree or level of development control is required;
- who will be affected by the required control;
- who will be affected by the controls and in what manner;
- when the controls should be applied;
- what will be the likely impact of the controls;
- how and by whom will the controls be administered and enforced.

Development control as an instrument of plan implementation may be selectively applied within the Land use Plan. Development controls would also be varied in intensity and detail to suit the particular circumstances. It is important that they should be clear and easily understood by all parties concerned. Since the entire Paurashava Master Plan 'package' has become statutory, development controls associated with its component plans would also be statutory.

Implementation by Facilitating Private Investment: Another approach that would be taken by government toward plan implementation will be to guide and facilitate investments made by the private sector. Government can achieve this with relative ease and at very low cost by setting up a legal and operational framework, coupled with suitable incentives, to facilitate land consolidation, plot boundary readjustment, efficient lay out of plots and provision of local infrastructure by the private sector. The benefits of this approach would be:

- increased efficiently of the urban land market would make, more private land available to urban households;

- would pass much of the development costs for local infrastructure to the private sector and land market mechanisms;
- would increase in land for development without large cash outlays by government to purchase land for development schemes; and
- would keep provision of land for community facilities virtually no cost to government.

Plan Monitoring

The Land use Plan would simply be tools for guiding and encouraging the growth and development of the Paurashava in a preferred manner. In a rapidly changing urban environment, the Land use Plan would require to keep up to date. If this is not done, within a few years it will be obsolete. Therefore, it is imperative that the requirement for regular updating of the Land use Plan be made a legal requirement.

For implementation of the various program components of the Land use Plan appropriate administrative measures will have to be undertaken. This will essentially include project preparation and monitoring of their execution and evaluation. For carrying out all these activities appropriate institutional measures are also be needed.

Evaluation

Monitoring and evaluation of on going and implemented projects is essential to keep the future course of action on the right track. An on going project should be regularly monitored and handicaps identified to enable taking appropriate measures at the right time.

Post implementation evaluation is also needed to take appropriate measures correcting past errors-from project preparation to implementation.

The top level supervision has to be done by a high level supervisory committee headed by Paurashava Mayor, LGED representative and Local Government Ministry. Other members of the committee will be local Ward Councilors, local community leader/social workers and the Town Planner of the Paurashava. The committee will supervise implementation works regularly and issue necessary instructions to expedite the works of implementation.

Co-ordination

A Planning Section of Paurashava should have close interaction with the citizen of Paurashava at large in order to make people aware of the benefits of a good plan and, therefore, their social responsibility to promote plan implementation in one hand and also resist contraventions on the other. A specific interactive cell is recommended to operate in this regard with following responsibilities:

- Provide pre-application advice to residents, consultants and developers about land use management issues and application procedures for the submission of development applications.
- Enforce planning and land use management related legislation and zoning scheme regulations.
- Issue of property zoning certificates.
- Investigate and resolve land use management complaints, illegal land use and prosecuting contraventions.

Such interactive windows may be opened in various convenient locations to ensure ease of the answers to commonly asked questions may be shown in the internet. Besides, those may be shown in the print and electronic media time to time.

In spontaneous areas, while all out people's co-operation is needed for project implementation; there will also be some elements of negotiation. Negotiation will be particularly needed in case of road widening projects. It will be a crucial task for Paurashava to convince the affected people to give up their land for road use. Efforts should be made to convince the land owners on the ground of enhancement of property value due to road widening. In case people refuse to offer land free of cost necessary arrangements may have to be made for payment of compensation. This process of negotiation will be very critical, cumbersome and time consuming, and therefore, has to be handled with utmost care and patience. The best results can be accrued only by wining people's confidence. In case the authority fails to get peoples co-operation they should exercise power of compulsory acquisition of land. Attempts may be made to engage NGOs / CBOs to work as catalysts in negotiation.

12.1 Introduction

Transportation occupies a high place in modern life. Transportation has great influence in the advancement of all spheres of life. Transport planning is a science that seeks to study the problems that arise in providing transportation facilities in an urban, regional or national setting and to prepare a systematic basis for planning such facilities. Town and country planning is a science that deals with the study of the urban or country “system” communications through channels. Transport planning is an important part of overall Town and Country Planning, since it deals with the transport network which is an important channel of a communication. Transportation and Traffic Management Plan is one of the Components of Urban Area Plan.

In Bangladesh, Transport Planning is not in practice still. Recently, government has developed the National Land Transport Policy, 2004 in order to provide a safe, integrated, effective transport system. Also, attempt has been taken to link relationship with land, economic activities and road network development. In preparing the Traffic and Transport Management Plan (Component-2) for Gauranadi Paurashava under Urban Area Plan (Volume-II), the Survey Phase and Interim phase has been completed successfully. In precedence of these activities, this plan is incepted.

12.2 Approach and Methodology

Transport study provides special attention to urban transportation planning as it greatly influences the location decisions and travel behavior of people, goods and services. Transportation is critical for the efficiency of towns contributing to their productivity and economic growth. A good network of roads and other transportation mode coupled with an efficient transport management system makes a substantial contribution to the "working efficiency" of cities and towns and enables them to become catalysts for social and economic development. On the other hand, the impact of a poorly designed urban transport system is manifested in terms of traffic congestion, delays, accidents, high energy consumption, high pollution of the environment and inequitable access to services. A well-planned transportation system results in orderly urban growth, greater use of urban public transport, lower vehicular pollution, and shorter auto trips.

A comprehensive transportation study is undertaken to investigate the existing transportation infrastructure, transportation modes and modal share scenario of Gauranadi Paurashava and to estimate the anticipated transportation needs of the town up to the year 2031. Accordingly, the transportation study is conducted to determine the present travel patterns and the characteristics of existing transportation facilities to forecast the future travel demand and develop a transportation plan.

Traffic volume survey has been conducted to find out the scenario of average daily traffic, peak hour traffic and off-peak hour traffic. Origin-Destination survey has been carried out to know the pattern of traffic generation, traffic distribution, modal split etc. Speed and delay survey has been conducted at 2 points on major local roads.

Bus and tempo fleet data were collected from local transport owners’ offices like, Bus Owners’ Association, Tempo Owners’ Association. They also provided information about routes, trips and movement data. Information about bus station and tempo station were collected from the respective owners’ association and the Paurashava/District Administration. Year wise data of non-motorized traffic were collected from the Gauranadi Paurashava, where these vehicles are registered.

12.3 Existing Conditions of Transportation Facilities

This section describes existing transportation facilities namely roadway and water way characteristics, modal share of vehicular traffic, level of service which incorporate degree of

traffic congestion and delay and analysis existing deficiencies in transport sector of Gauranadi Paurashava.

12.3.1 Road Network

12.3.1.1 Roadway Characteristics and Functional Classification

The primary roads are the urban highways whose function is to channelize the longer movement from one place to another and beyond. The primary road of Gauranadi Paurashava is connected in north and south (Madaripur and Barisal Sadar) directions and these roads maintain connectivity with the outside areas of Paurashava. Moreover, the primary roads are also connected with secondary and access roads and all these roads maintain good connectivity within the Paurashava area. Secondary road cannot provide access to individual buildings because the consequent frequency of interruptions would give rise to traffic dangers. Tertiary road connect secondary road with access road. But in Gauranadi Paurashava most of the roads cannot be defined according to road hierarchy.

From the physical feature survey it has been observed that about 23.19% (79100.30 sq.m) of the roads are Katcha, 46.09% (157238.40 sq.m) roads Pucca and the rest of the roads are Semi-pucca 30.72% (104784.37 sq.m). There are 26 bridges at Gauranadi Paurashava. All the bridges are pucca and condition of pavement are good. There are 111 culverts exist at Gauranadi Paurashava.The rest of the roads are primary roads. **Map 12.1** shows existing road network of Gauranadi Paurashava.

Table 12.1: Type Wise Length and Area of Existing Road

Types of road	Length (in km)	%	Area (in sq.m)	%
Katcha Road	34.81	27.53	79100.30	23.19
Pucca Road	45.38	35.89	157238.40	46.09
Semi pucca Road	46.25	36.58	104784.37	30.72
Total	**126.43**	**100.00**	**341123.07**	**100.00**

Source: Physical Feature Survey, 2011.

Traffic volume survey has been conducted at Turki Bondor More (comprising four links namely: Barisal Highway, Taslima Aktar Memorial Road, Gaurnadi Sadar Road and Agailjhara Road), and Gaurnadi Bus Stand More (comprising three road links such as Abdur Rob Serniabad Road, Bir Muktijoddha Syed Abul Hossain Road and Bir Muktijoddha Parimal Mondol Sharak) Beside this about 116.93 km access roads provide access to all the wards. Width of access road varies 1-4.5 m. Mainly LGED is responsible for construction and maintenance of most of the roads within the Paurashava.

12.3.1.2 Mode of Road Transport

There is no public or private bus service available for intra-zonal movement within Gauranadi Paurashava. Intra-zonal movement among the Paurashava area is mostly done through the non-motorized vehicles such as rickshaw, bi-cycle, van, etc. People also use some motorized vehicles such as motorcycle, Auto Rickshaw, etc. Additionally, van is used for carrying both passengers and goods. Rickshaw is the most dominant transport for intra zonal movement. The average percentages of traffic composition are Truck 2.44%, Bus 2.40%, Car/micro-bus/Jeep 3.88%, Auto rickshaw 11.12%, Motor cycle 11.50%, Rickshaw/van 52.5% and Bi-cycle 16.62%.

12.3.1.3 Intensity of Traffic Volume

Traffic volume survey has been conducted to find out total discharging traffic volume both in peak hour and off peak hour at there is no bus stand in Gauranadi Paurashava.

Peak Hour has been considered from 8.00 to 12.00 and 16.00 to 20.00 because most of the educational and commercial movement has been accomplished within the time periods and traffic characteristics of these time periods is different and higher than other time periods.

As there is a designated day as hat day in Gauranadi Paurashava, working day, weekend and Hat day traffic volume is counted for transportation survey. Survey result shows that non-motorized vehicle (68.66%) acts dominant role in Gauranadi Paurashava.

Survey result shows that Barisal Highway has the highest Peak Hour Traffic Volume (1472.0 PCUs) per hour and Bir Muktijoddha Abul Hossain Road has the lowest Peak Hour Traffic Volume (478.0 PCUs) per hour. Barisal Highway has the highest Off Peak Hour Traffic Volume (444.3 PCUs) per hour and Shahid abdur Rob Serniabad Road has the lowest Off Peak Hour Traffic Volume (147.6 PCUs) per hour.

Analyzing the characteristics of Peak Hour and Off Peak Hour traffics, it has been observed that the Peak Hour Traffic is more than 3 times higher than Off Peak Hour Traffic in all of the surveyed road sections.

There is also traffic volume variation at hat day and non-hat day. Generally hat time starts from afternoon. So, variation of traffic volume also exists. In case of hat day it has been observed that specially the two road links that are connected with bazaar area face peak hour traffic volume 8.00-12.00 and 16.00-20.00.

12.3.1.4 Level of Service: Degree of Traffic Congestion and Delay

In order to prepare a fruitful traffic management plan, it is really important to evaluate the level of service of the road sections. Level of service of the surveyed road sections has been evaluated using the ratio of volume and capacity. The V/C ratio is defined as the ratio of maximum actual volume of traffic in the peak hour in a road way, expressed in PCUs per hour to capacity of that roadway expressed in PCUS per hour. Capacity of roadway largely depends on number of lane, road width and roadway condition. In Gauranadi Paurashava area all the surveyed road sections are one lane road.

In Gauranadi Paurashava all the roads have free flow and transport density is low. The major inter sections are not signalized so no delay is exist here.

12.3.1.5 Facilities of Pedestrians

Pedestrian facility is one of the Transportation facilities which are required to create a pedestrian friendly environment. Most of the roads at Gauranadi Paurashava do not have foot-path. So, pedestrian facility is very poor at Gauranadi Paurashava. But this facility is one of the vital needs for urban life.

12.3.1.6 Primary Considering Issues for Planning

Major deficiencies of transportation and traffic management are below:

- Present road network has developed without maintaining any hierarchy or planning rules.
- Poor and damaged road conditions are the most dominant transportation problem of Gauranadi Paurashava.
- Narrow road and lack of transport modes are another transportation problems of the area
- Absence of stand and proper parking spaces grounds haphazard condition and congestion.
- Lack of traffic management system and low quality transports result low quality of service to the residents of Gauranadi Paurashava.
- Absence of signalized crossing.
- The Paurashava has no pedestrian facility that directly hampers the safety of the people
- Lack of traffic control aids, street furniture, street lighting, etc.
- Water transport vehicles are not adequate and service quality is not satisfactory

Roadway Capacity Deficiency

Roadway Capacity deficiencies occur wherever the travel demand on a road is close to or higher than the vehicle capacity of that roadway. In order to identify the road capacity deficiency, it is required to make a comparison between existing Level of service (LOS) of major roads with the standard one. By comparing those it has observed that all the surveyed roads of Gauranadi Paurashava have free flow and transport density is low. Existing capacity of major roads are not consistent with standard capacity limit and the future traffic flow and demand may exceed the limit.

Moreover, the average width of the primary roads and secondary roads of Gauranadi Paurashava are 4 meter and 3.5 meter and 3.75 meter respectively whereas according to the PMO standard the right of way of primary road, secondary road and access road will be 18-24 meter, 13-16 meter and 6-8 meter respectively. So these roads have designed without maintaining any standards. However, these roads have to be widened where possible and essential.

Operational, Safety, Signal and other Deficiencies

- At present, there is no selected authority for the management of traffic at Gauranadi Paurashava. Generally The Police Department's Traffic wings are the main eligible.
- As the roads of Gauranadi Paurashava have free flow of traffic and most of the traffic are non-motorized both in hat and non-hat day, road safety exists naturally in the Paurashava.
- Traffic signaling system is totally absent in the Paurashava. On some specific point of primary and secondary roads, traffic signaling may be needed.

12.3.1 Condition of Water Transport

In the Gauranadi Paurashava area there is two Launch ghat are existing for carrying both passenger and commodity. They are located at Turki River adjacent to Bazar Area. Water transport network of Gauranadi Paurashava has significant importance in carrying goods. Launch and trawler are used for carrying both passenger and commodity frequently.

12.3.2 Condition of other Transport

At this stage there is no need to propose car way, rail way in this Paurashava.

12.4 Future Projections

With the increase of population, demand on travel will be increase with the time. Estimating the demand for transportation facilities and services is one of the most important analysis tasks in transportation planning. The demand includes not only passenger travel but also the movement of goods. Whether conducting a regional transportation planning study or examining the impacts of transportation of a new development site, estimating expected travel demand at some future date is critical point of departure for transportation planning.

12.4.1 Travel Demand Forecasting for Next 20 Years

At Gauranadi Paurashava, the existing road network is quite sufficient for accommodating present volume of traffic. At Gauranadi Paurashava about 27.53% of the roads are katcha and needs to be constructed as pucca or at least semi-pucca. Moreover, most of the roads are narrow. Road Alignment should be straight in main road for improving transport quality. Widening of these roads and new construction of some roads will act as a vital role for accommodating future traffic volume. Moreover, the people of Gauranadi Paurashava depend on both road network and water transport network. This will also help to reduce pressure on road transport network. Forecasting travel demand requires variety of data such as historical data on traffic,

missing link, economic importance, trip generation and distribution pattern, routes choice, modal spilt, etc. Growth direction is also a considerable component for the demand analysis of the road.

12.4.2 Transportation Network Considered

The primary road of Gauranadi Paurashava is well connected in both north and south directions within the Upazila areas and the primary roads are also connected with secondary and access roads and all these roads maintain good connectivity within the Paurashava area. But these roads are not wide enough on the basis of standard. So, the narrow roads have to be widened on the basis of standards and katcha roads will be improved with the time and also traffic management system will be improved. Besides, some new roads also have been proposed to accommodate the future travel demand. Moreover, footpath facilities have to be introduced to meet up the demand of pedestrians.


12.4.3 Future Traffic Volume and Level of Service

In the year 2011, the population of Gauranadi Paurashava is about 42438 and after 20 years it will be 53104 (2031). At present highest PCU/hr is about 1472.0 at non-hat day and at hat day is about 5770. It means traffic congestion is not alarming.

It is expected that gradual implementation of the components prescribed in the Master Plan will increase traffic volume. But at the same time the roads will be widened and new roads will be constructed. So, the increase traffic will be accommodated by these roads.

After the improvement of roads, commercial and industrial activities will also be boost up. This may increase traffic volume of the area. The proposed transport network and traffic management system will make it possible to remain the traffic scenario stable for next 20 years.

Map 12.1: Existing Road Network of Gauranadi Paurashava



Legend

- BG_Paurashava_Boundary
- BG_Mouza_Boundary
- BG_Ward_Boundary
- Bridge
- Culvert
- Waterbody
- Katcha
- Pucca
- Semipucca

0 187.5 375 750 1,125 1,500 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT
SCPL Sheltech Consultants (Pvt.) Ltd.
1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

12.5 Transportation Development Plan

The current chapter of the report is about Transport Development Plan covering its development plan proposals and management of the proposed project area up to the year 2031. The report describes existing transportation facilities and proposal on the important facilities such as, bus terminal, rickshaw stand, fuel station and passenger sheds.

12.5.1 Road Network Plan

The standards are meant for use by UTIDP, LGED and other planning and development agencies. The standards have been adopted by the consultants to draw up the transportation development plan. Following are the suggested planning standards (Table 12.2) for road network development. These road hierarchies are proposed based on the functional linkage of the road of Gauranadi Paurashava:

Table 12.2: Standards of Roads proposed by PMO

Landuse Category	Hierarchy of Roads	Right of Way (ROW)
Circulation Network	Primary Roads	150-100 feet
	Secondary Roads	100-60 feet
	Tertiary Road	20-40 feet

Source: UTIDP, PMO, LGED.

Gauranadi is a town with a very low volume of internal and external traffic movement. Considering traffic volume and discussion with Paurashava authority and local stakeholders consultants have established a road hierarchy based on the functional area within the Paurashava as well as the internal and external linkage. Existing Access roads will be connected with Tertiary and Secondary roads for better mobility. Following table shows the standard of future development of road network.

Table 12.3: Standard for future development of the Road Network of Gauranadi Paurashava

Landuse Category	Hierarchy of Roads	Right of Way (ROW)
Circulation Network	Paurashava Primary Roads	60-80 feet
	Paurashava Secondary Roads	40-50 feet
	Paurashava Local Roads	20-30 feet

Source: Proposed by Consultants

12.5.2 Design Principals and Standards

In preparing detail design some basic principals have been followed:

- Road Hierarchy Standards provided by PMO
- Relevant regulations of Building construction Act, 1952 (amendment in 1996), followed by Paurashava
- follow up the National Urban Land Transport Policy, 2004
- follow up the Transport planning relevant Books, articles and papers (Ref: Traffic Engineering and Transport Planning, Dr. L.R. Kadiyali)



Fig 12.1: Channelization Measures at Major Intersections

A) Intersection improvement

This measures can be categorized into 2 types, are as follows:

a. Channelization
b. Improvement of Intersection geometry




Fig 12.2: Corner Plot Widening at Intersections

a. Channelization

Channelization of intersection at grade is the separation or regulation of conflicting traffic movements into definite paths of travel by the use of pavement markings, raised islands, or other suitable means to facilitate the safe and orderly movements of both vehicles and pedestrians. Channelization is done for:

- Separation of conflicts (by using roundabout, raised island, etc.)
- Reduction of conflict points
- Reduction of excessive pavement areas

b. Improvement of intersection geometry includes:

- Corner Plot widening
- Establishment of Traffic islands

According to Building Construction Act, 1996, in each Corner plot of major intersection, 1m×1m land area has to be open for traffic movement.

B) Land use Proposals at the Major Intersections

According to Building Construction Act, 1996, the construction permission of Shopping Complex, Cinema Hall or similar type of buildings are restricted within 50 m (164 ft) from major road intersections to avoid traffic congestion.

C) Prioritization in ROW Space Allocation according to Road Hierarchy

In pertaining with the National Land Transport Policy, 2004, for promoting an efficient road transport system, provision of Motorized and Non-motorized vehicles is prioritized. Therefore, effective road space allocation and utilization is also emphasized in national policy. At first, a uniform priority has been fixed for designing the whole Road Network Development.

Basis of Prioritization

Prioritization has been formed in light of National Land Transport Policy, 2004.


- To promote the speed and mobilize the activities, motorized vehicles (especially Bus lane) are encouraged
- To make a environmental and economical balance (employment pattern and Income level), provision of non-motorized vehicles are kept
- To ensure safe movement of citizens, footway should be provided


Though, uniform space allocation is formed but Right Of Way (ROW), land use and the demand of different type of vehicles are not same throughout the whole Paurashava area. So, the design priority has been differed at road hierarchy as follows:

Space Allocation at ROW considering Road Hierarchy

Priority	Primary Road	Secondary Road	Tertiary Road	Access Road
1	Provide one lane (3.0m) for motorized vehicles including Bus, Car and Jeep etc. The width of each lane is minimum 3 m depending on the availability of space.	Provide one lane (3.0 m) for motorized vehicles including Bus, Car and Jeep etc. The width of each lane is minimum 2.5 m depending on the availability of space.	Provide one lane (3 m) for motorized and non-motorized vehicles including Car, Jeep, Motorcycle and Rickshaws etc. The width of each lane is minimum 2.5 m depending on the availability of space.	Provide one lane (3 m) for motorized and non- motorized vehicles including Car, Jeep, Motorcycle and Rickshaws etc. The width of each lane is minimum 2.5 m depending on the availability of space.
2	Non-motorized vehicle paths (Service lane), 2.5m wide in each direction with over-taking lane including physical segregation of .5ft wide and 1ft height concrete block.	Non-motorized vehicle paths (Service lane), 2.5m wide in each direction with over-taking lane including physical segregation of .5ft wide and 1ft height concrete block.	Pedestrian paths as per existing demand (minimum 1.5 m)	Pedestrian paths as per existing demand (minimum 1.5 m)
3	Pedestrian paths as per existing demand (minimum 1.5 m)	Pedestrian paths as per existing demand (minimum 1.5 m)	Provide one lane for motorized and non-motorized vehicles including Car, Jeep, Motorcycle and Rickshaws etc. depending on the availability of space.	
4	2 to 3 or more lanes for motorized vehicles. The width of each lane is minimum 2.5m depending on the availability of space.	2 to 3 lanes for motorized vehicles. The width of each lane is minimum 2.5m depending on the availability of space.		

Figure 12.3 shows the cross section of different types of roads.








Fig 12.3: Typical Cross-Section of Various Types of Roads

12.5.3 Proposal for Improvement of the Existing Road Networks

The improvement plan for existing road network has been prepared considering two categories, which are as follows:

A. Roads connect Paurashava with Regional Road Network
B. Roads provide internal network of the Paurashava

All of the road should be developed in 20 years implementation time. It will be done in three phases; 1st phase (1st 5 years), 2nd phase (2nd 5 year) and 3rd phase (last 10 year). In the master plan, about 161.03 kilometers roads have been proposed for widening. Phase wise road widening proposal has been shown in Table 12.4.

Table 12.4 Phase Wise Road Widening Proposal for Existing Road

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
PR-1	Primary Road	100	8287.76	1st
PR-2	Primary Road	100	8027.51	1st
SR-1	Secondary Road	40	1856.42	1st
SR-2	Secondary Road	60	1921.08	1st
SR-3	Secondary Road	40	2796.88	1st
SR-4	Secondary Road	40	1621.59	1st
SR-5	Secondary Road	60	1001.92	1st
SR-6	Secondary Road	40	1500.85	1st
SR-7	Secondary Road	40	2090.05	1st
SR-8	Secondary Road	40	2482.92	1st
SR-9	Secondary Road	40	1219.10	1st
SR-10	Secondary Road	40	735.67	1st
SR-11	Secondary Road	40	1463.13	1st
SR-12	Secondary Road	60	1177.09	1st
SR-13	Secondary Road	40	1709.13	1st
SR-14	Secondary Road	40	703.70	1st
SR-15	Secondary Road	40	1664.35	1st
SR-16	Secondary Road	60	1439.90	1st
SR-20	Secondary Road	60	1384.41	1st
SR-21	Secondary Road	40	1083.78	1st
SR-22	Secondary Road	60	1725.06	1st
SR-23	Secondary Road	60	721.30	1st
TR-1	Tertiary Road	20	0.00	1st
TR-2	Tertiary Road	20	0.00	1st
TR-3	Tertiary Road	20	4.24	1st
TR-4	Tertiary Road	20	26.63	1st
TR-5	Tertiary Road	20	98.97	1st
TR-6	Tertiary Road	20	3.40	1st
TR-7	Tertiary Road	20	0.00	1st
TR-8	Tertiary Road	20	279.07	1st
TR-9	Tertiary Road	20	110.27	1st
TR-10	Tertiary Road	20	125.21	1st
TR-11	Tertiary Road	20	0.00	1st
TR-12	Tertiary Road	20	10.30	1st
TR-13	Tertiary Road	20	159.87	1st
TR-14	Tertiary Road	20	33.94	1st
TR-15	Tertiary Road	20	293.33	1st
TR-16	Tertiary Road	20	0.00	1st
TR-17	Tertiary Road	20	4.16	1st
TR-18	Tertiary Road	20	449.99	1st
TR-19	Tertiary Road	20	0.00	1st
TR-20	Tertiary Road	20	2.39	1st
TR-21	Tertiary Road	20	333.30	1st
TR-22	Tertiary Road	20	61.29	1st
TR-23	Tertiary Road	20	46.54	1st
TR-24	Tertiary Road	20	59.59	1st
TR-25	Tertiary Road	20	0.00	1st
TR-26	Tertiary Road	20	83.65	1st
TR-27	Tertiary Road	20	384.35	1st
TR-28	Tertiary Road	20	418.06	1st
TR-29	Tertiary Road	20	0.00	1st
TR-30	Tertiary Road	20	19.72	1st
TR-31	Tertiary Road	20	22.58	1st
TR-32	Tertiary Road	20	117.42	1st
TR-33	Tertiary Road	20	0.00	1st
TR-34	Tertiary Road	20	256.92	1st
TR-35	Tertiary Road	20	648.40	1st
TR-36	Tertiary Road	20	57.23	1st
TR-37	Tertiary Road	20	0.00	1st
TR-38	Tertiary Road	20	3.27	1st

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-39	Tertiary Road	20	50.90	1st
TR-40	Tertiary Road	20	337.53	1st
TR-41	Tertiary Road	20	35.10	1st
TR-42	Tertiary Road	20	52.43	1st
TR-43	Tertiary Road	20	386.87	1st
TR-44	Tertiary Road	20	115.69	2nd
TR-45	Tertiary Road	20	35.45	2nd
TR-46	Tertiary Road	20	271.93	2nd
TR-47	Tertiary Road	20	62.38	2nd
TR-48	Tertiary Road	20	36.91	2nd
TR-49	Tertiary Road	20	23.08	2nd
TR-50	Tertiary Road	20	29.72	2nd
TR-51	Tertiary Road	20	25.64	2nd
TR-52	Tertiary Road	20	29.19	2nd
TR-53	Tertiary Road	20	1186.93	2nd
TR-54	Tertiary Road	20	66.16	2nd
TR-55	Tertiary Road	20	0.00	2nd
TR-56	Tertiary Road	20	20.06	2nd
TR-57	Tertiary Road	20	628.84	2nd
TR-58	Tertiary Road	20	35.48	2nd
TR-59	Tertiary Road	20	19.93	2nd
TR-60	Tertiary Road	20	15.01	2nd
TR-61	Tertiary Road	20	75.87	2nd
TR-62	Tertiary Road	20	16.96	2nd
TR-63	Tertiary Road	20	40.99	2nd
TR-64	Tertiary Road	20	16.68	2nd
TR-65	Tertiary Road	20	514.70	2nd
TR-66	Tertiary Road	20	34.53	2nd
TR-67	Tertiary Road	20	31.07	2nd
TR-68	Tertiary Road	20	48.83	2nd
TR-69	Tertiary Road	20	2.59	2nd
TR-70	Tertiary Road	20	119.35	2nd
TR-71	Tertiary Road	20	169.28	2nd
TR-72	Tertiary Road	20	535.96	2nd
TR-73	Tertiary Road	20	150.92	2nd
TR-74	Tertiary Road	20	300.11	2nd
TR-75	Tertiary Road	20	325.36	2nd
TR-76	Tertiary Road	20	166.89	2nd
TR-77	Tertiary Road	20	42.06	2nd
TR-78	Tertiary Road	20	60.08	2nd
TR-79	Tertiary Road	20	272.29	1st
TR-80	Tertiary Road	20	29.89	2nd
TR-81	Tertiary Road	20	501.46	2nd
TR-82	Tertiary Road	20	80.90	2nd
TR-83	Tertiary Road	20	10.16	2nd
TR-84	Tertiary Road	20	168.86	2nd
TR-85	Tertiary Road	20	42.53	2nd
TR-86	Tertiary Road	20	894.48	2nd
TR-87	Tertiary Road	20	469.67	2nd
TR-88	Tertiary Road	20	256.23	2nd
TR-89	Tertiary Road	20	280.29	2nd
TR-90	Tertiary Road	20	85.30	2nd
TR-91	Tertiary Road	20	735.37	2nd
TR-92	Tertiary Road	20	12.88	2nd
TR-93	Tertiary Road	20	25.82	2nd
TR-94	Tertiary Road	20	67.51	2nd
TR-95	Tertiary Road	20	125.25	2nd
TR-96	Tertiary Road	20	62.20	2nd
TR-97	Tertiary Road	20	76.57	2nd
TR-98	Tertiary Road	20	125.25	2nd
TR-99	Tertiary Road	20	200.55	2nd
TR-100	Tertiary Road	20	80.10	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-101	Tertiary Road	20	17.13	2nd
TR-102	Tertiary Road	20	47.10	2nd
TR-103	Tertiary Road	20	22.53	2nd
TR-104	Tertiary Road	20	94.47	2nd
TR-105	Tertiary Road	20	615.38	2nd
TR-106	Tertiary Road	20	76.85	2nd
TR-107	Tertiary Road	20	128.12	2nd
TR-108	Tertiary Road	20	287.69	2nd
TR-109	Tertiary Road	20	9.20	2nd
TR-110	Tertiary Road	20	25.17	2nd
TR-111	Tertiary Road	20	287.18	2nd
TR-112	Tertiary Road	20	24.87	2nd
TR-113	Tertiary Road	20	1042.63	2nd
TR-114	Tertiary Road	20	0.00	2nd
TR-115	Tertiary Road	20	75.95	2nd
TR-116	Tertiary Road	20	12.97	2nd
TR-117	Tertiary Road	20	13.36	2nd
TR-118	Tertiary Road	20	97.90	2nd
TR-119	Tertiary Road	20	159.13	2nd
TR-120	Tertiary Road	20	0.00	2nd
TR-121	Tertiary Road	20	33.24	2nd
TR-122	Tertiary Road	20	45.98	2nd
TR-123	Tertiary Road	20	79.10	2nd
TR-124	Tertiary Road	20	51.50	2nd
TR-125	Tertiary Road	20	294.18	2nd
TR-126	Tertiary Road	20	47.58	2nd
TR-127	Tertiary Road	20	29.21	2nd
TR-128	Tertiary Road	20	82.67	2nd
TR-129	Tertiary Road	20	0.00	2nd
TR-130	Tertiary Road	20	0.00	2nd
TR-131	Tertiary Road	20	48.06	2nd
TR-132	Tertiary Road	20	50.58	2nd
TR-133	Tertiary Road	20	203.15	2nd
TR-134	Tertiary Road	20	216.83	2nd
TR-135	Tertiary Road	20	144.05	2nd
TR-136	Tertiary Road	20	732.85	2nd
TR-137	Tertiary Road	20	48.53	2nd
TR-138	Tertiary Road	20	43.25	2nd
TR-139	Tertiary Road	20	373.59	3rd
TR-140	Tertiary Road	20	0.00	3rd
TR-141	Tertiary Road	20	2.72	3rd
TR-142	Tertiary Road	20	0.00	3rd
TR-143	Tertiary Road	20	608.54	3rd
TR-144	Tertiary Road	20	15.49	3rd
TR-145	Tertiary Road	20	262.57	3rd
TR-146	Tertiary Road	20	3.97	3rd
TR-147	Tertiary Road	20	0.00	3rd
TR-148	Tertiary Road	20	108.72	3rd
TR-149	Tertiary Road	20	33.79	3rd
TR-150	Tertiary Road	20	138.51	3rd
TR-151	Tertiary Road	20	68.37	3rd
TR-152	Tertiary Road	20	15.11	3rd
TR-153	Tertiary Road	20	155.13	3rd
TR-154	Tertiary Road	20	20.90	3rd
TR-155	Tertiary Road	20	51.56	3rd
TR-156	Tertiary Road	20	176.75	2nd
TR-157	Tertiary Road	20	148.29	2nd
TR-158	Tertiary Road	20	38.44	2nd
TR-159	Tertiary Road	20	46.97	2nd
TR-160	Tertiary Road	20	156.30	2nd
TR-161	Tertiary Road	20	32.16	2nd
TR-162	Tertiary Road	20	39.89	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-163	Tertiary Road	20	506.11	2nd
TR-164	Tertiary Road	20	95.22	2nd
TR-165	Tertiary Road	20	68.03	2nd
TR-166	Tertiary Road	20	17.46	2nd
TR-167	Tertiary Road	20	26.33	2nd
TR-168	Tertiary Road	20	610.70	2nd
TR-169	Tertiary Road	20	329.25	2nd
TR-170	Tertiary Road	20	66.52	2nd
TR-171	Tertiary Road	20	583.32	2nd
TR-172	Tertiary Road	20	188.36	2nd
TR-173	Tertiary Road	20	156.54	2nd
TR-174	Tertiary Road	20	95.98	2nd
TR-175	Tertiary Road	20	68.89	2nd
TR-176	Tertiary Road	20	91.46	2nd
TR-177	Tertiary Road	20	153.65	2nd
TR-178	Tertiary Road	20	150.99	2nd
TR-179	Tertiary Road	20	37.64	2nd
TR-180	Tertiary Road	20	28.48	2nd
TR-181	Tertiary Road	20	23.57	2nd
TR-182	Tertiary Road	20	0.00	2nd
TR-183	Tertiary Road	20	117.73	2nd
TR-184	Tertiary Road	20	81.74	2nd
TR-185	Tertiary Road	20	141.78	2nd
TR-186	Tertiary Road	20	0.00	2nd
TR-187	Tertiary Road	20	84.71	2nd
TR-188	Tertiary Road	20	50.24	2nd
TR-189	Tertiary Road	20	86.54	2nd
TR-190	Tertiary Road	20	73.66	2nd
TR-191	Tertiary Road	20	63.81	2nd
TR-192	Tertiary Road	20	66.79	2nd
TR-193	Tertiary Road	20	36.99	2nd
TR-194	Tertiary Road	20	181.88	2nd
TR-195	Tertiary Road	20	174.65	2nd
TR-196	Tertiary Road	20	366.97	2nd
TR-197	Tertiary Road	20	176.12	2nd
TR-198	Tertiary Road	20	61.52	2nd
TR-199	Tertiary Road	20	17.27	2nd
TR-200	Tertiary Road	20	1.42	2nd
TR-201	Tertiary Road	20	165.55	2nd
TR-202	Tertiary Road	20	99.06	2nd
TR-203	Tertiary Road	20	29.69	2nd
TR-204	Tertiary Road	20	27.80	2nd
TR-205	Tertiary Road	20	20.10	2nd
TR-206	Tertiary Road	20	55.33	2nd
TR-207	Tertiary Road	20	50.96	2nd
TR-208	Tertiary Road	20	150.86	2nd
TR-209	Tertiary Road	20	129.42	2nd
TR-210	Tertiary Road	20	96.49	2nd
TR-211	Tertiary Road	20	43.24	2nd
TR-212	Tertiary Road	20	243.41	2nd
TR-213	Tertiary Road	20	36.98	2nd
TR-214	Tertiary Road	20	34.93	2nd
TR-215	Tertiary Road	20	92.92	2nd
TR-216	Tertiary Road	20	17.36	3rd
TR-217	Tertiary Road	20	109.69	3rd
TR-218	Tertiary Road	20	924.85	3rd
TR-219	Tertiary Road	20	36.42	3rd
TR-220	Tertiary Road	20	22.98	3rd
TR-221	Tertiary Road	20	29.46	3rd
TR-222	Tertiary Road	20	329.53	3rd
TR-223	Tertiary Road	20	168.83	3rd
TR-224	Tertiary Road	20	134.64	3rd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-225	Tertiary Road	20	45.51	3rd
TR-226	Tertiary Road	20	85.45	3rd
TR-227	Tertiary Road	20	246.39	3rd
TR-228	Tertiary Road	20	27.46	3rd
TR-229	Tertiary Road	20	94.41	3rd
TR-230	Tertiary Road	20	27.39	3rd
TR-231	Tertiary Road	20	0.00	3rd
TR-232	Tertiary Road	20	645.13	2nd
TR-233	Tertiary Road	20	112.19	2nd
TR-234	Tertiary Road	20	127.78	2nd
TR-235	Tertiary Road	20	30.08	2nd
TR-236	Tertiary Road	20	428.06	2nd
TR-237	Tertiary Road	20	42.35	2nd
TR-238	Tertiary Road	20	51.88	2nd
TR-239	Tertiary Road	20	90.59	2nd
TR-240	Tertiary Road	20	62.76	2nd
TR-241	Tertiary Road	20	111.53	2nd
TR-242	Tertiary Road	20	8.42	2nd
TR-243	Tertiary Road	20	370.13	2nd
TR-244	Tertiary Road	20	113.55	2nd
TR-245	Tertiary Road	20	105.84	2nd
TR-246	Tertiary Road	20	70.04	2nd
TR-247	Tertiary Road	20	99.26	2nd
TR-248	Tertiary Road	20	107.59	2nd
TR-249	Tertiary Road	20	14.73	2nd
TR-250	Tertiary Road	20	0.00	2nd
TR-251	Tertiary Road	20	74.34	2nd
TR-252	Tertiary Road	20	0.00	2nd
TR-253	Tertiary Road	20	0.63	2nd
TR-254	Tertiary Road	20	136.94	2nd
TR-255	Tertiary Road	20	0.24	3rd
TR-256	Tertiary Road	20	139.02	3rd
TR-257	Tertiary Road	20	49.49	3rd
TR-258	Tertiary Road	20	0.41	3rd
TR-259	Tertiary Road	20	441.43	3rd
TR-260	Tertiary Road	20	40.01	3rd
TR-261	Tertiary Road	20	40.07	3rd
TR-262	Tertiary Road	20	0.00	3rd
TR-263	Tertiary Road	20	203.14	3rd
TR-264	Tertiary Road	20	88.26	3rd
TR-265	Tertiary Road	20	71.69	3rd
TR-266	Tertiary Road	20	40.56	3rd
TR-267	Tertiary Road	20	68.89	3rd
TR-268	Tertiary Road	20	337.89	3rd
TR-269	Tertiary Road	20	181.63	3rd
TR-270	Tertiary Road	20	304.86	3rd
TR-271	Tertiary Road	20	221.75	3rd
TR-272	Tertiary Road	20	258.51	3rd
TR-273	Tertiary Road	20	43.44	3rd
TR-274	Tertiary Road	20	176.34	3rd
TR-275	Tertiary Road	20	533.69	3rd
TR-276	Tertiary Road	20	0.00	3rd
TR-277	Tertiary Road	20	1.16	3rd
TR-278	Tertiary Road	20	0.00	3rd
TR-279	Tertiary Road	20	84.77	3rd
TR-280	Tertiary Road	20	91.81	3rd
TR-281	Tertiary Road	20	387.86	3rd
TR-282	Tertiary Road	20	63.35	3rd
TR-283	Tertiary Road	20	408.93	3rd
TR-284	Tertiary Road	20	42.45	3rd
TR-285	Tertiary Road	20	242.60	3rd
TR-286	Tertiary Road	20	0.00	3rd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-287	Tertiary Road	20	1.74	3rd
TR-288	Tertiary Road	20	59.48	3rd
TR-289	Tertiary Road	20	43.24	3rd
TR-290	Tertiary Road	20	31.71	3rd
TR-291	Tertiary Road	20	34.39	2nd
TR-292	Tertiary Road	20	360.64	2nd
TR-293	Tertiary Road	20	28.56	2nd
TR-294	Tertiary Road	20	42.89	2nd
TR-295	Tertiary Road	20	38.58	2nd
TR-296	Tertiary Road	20	39.61	2nd
TR-297	Tertiary Road	20	35.24	2nd
TR-298	Tertiary Road	20	27.23	2nd
TR-299	Tertiary Road	20	653.28	2nd
TR-300	Tertiary Road	20	0.00	2nd
TR-301	Tertiary Road	20	0.29	2nd
TR-302	Tertiary Road	20	47.56	2nd
TR-303	Tertiary Road	20	36.95	2nd
TR-304	Tertiary Road	20	35.84	2nd
TR-305	Tertiary Road	20	55.89	2nd
TR-306	Tertiary Road	20	29.27	2nd
TR-307	Tertiary Road	20	42.81	2nd
TR-308	Tertiary Road	20	65.03	2nd
TR-309	Tertiary Road	20	50.91	2nd
TR-310	Tertiary Road	20	385.44	2nd
TR-311	Tertiary Road	20	37.07	2nd
TR-312	Tertiary Road	20	127.01	2nd
TR-313	Tertiary Road	20	197.04	2nd
TR-314	Tertiary Road	20	30.22	2nd
TR-315	Tertiary Road	20	30.17	2nd
TR-316	Tertiary Road	20	54.17	2nd
TR-317	Tertiary Road	20	112.22	2nd
TR-318	Tertiary Road	20	20.02	2nd
TR-319	Tertiary Road	20	18.79	2nd
TR-320	Tertiary Road	20	35.39	2nd
TR-321	Tertiary Road	20	256.43	3rd
TR-322	Tertiary Road	20	81.83	3rd
TR-323	Tertiary Road	20	85.07	3rd
TR-324	Tertiary Road	20	156.07	3rd
TR-325	Tertiary Road	20	81.93	3rd
TR-326	Tertiary Road	20	36.98	3rd
TR-327	Tertiary Road	20	65.68	3rd
TR-328	Tertiary Road	20	36.35	3rd
TR-329	Tertiary Road	20	45.00	3rd
TR-330	Tertiary Road	20	1018.52	3rd
TR-331	Tertiary Road	20	0.00	3rd
TR-332	Tertiary Road	20	8.49	3rd
TR-333	Tertiary Road	20	239.25	3rd
TR-334	Tertiary Road	20	33.74	3rd
TR-335	Tertiary Road	20	97.79	3rd
TR-336	Tertiary Road	20	60.14	3rd
TR-337	Tertiary Road	20	76.46	3rd
TR-338	Tertiary Road	20	66.40	3rd
TR-339	Tertiary Road	20	84.74	3rd
TR-340	Tertiary Road	20	502.60	3rd
TR-341	Tertiary Road	20	701.88	3rd
TR-342	Tertiary Road	20	497.15	3rd
TR-343	Tertiary Road	20	490.29	3rd
TR-344	Tertiary Road	20	195.74	3rd
TR-345	Tertiary Road	20	508.17	3rd
TR-346	Tertiary Road	20	54.90	3rd
TR-347	Tertiary Road	20	19.09	3rd
TR-348	Tertiary Road	20	21.67	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-349	Tertiary Road	20	276.11	2nd
TR-350	Tertiary Road	20	70.20	2nd
TR-351	Tertiary Road	20	101.61	2nd
TR-352	Tertiary Road	20	61.28	2nd
TR-353	Tertiary Road	20	215.53	2nd
TR-354	Tertiary Road	20	37.90	2nd
TR-355	Tertiary Road	20	274.71	2nd
TR-356	Tertiary Road	20	36.41	2nd
TR-357	Tertiary Road	20	34.13	2nd
TR-358	Tertiary Road	20	37.74	2nd
TR-359	Tertiary Road	20	39.01	2nd
TR-360	Tertiary Road	20	209.43	2nd
TR-361	Tertiary Road	20	125.44	2nd
TR-362	Tertiary Road	20	47.53	2nd
TR-363	Tertiary Road	20	38.78	3rd
TR-364	Tertiary Road	20	201.67	3rd
TR-365	Tertiary Road	20	71.37	3rd
TR-366	Tertiary Road	20	68.56	3rd
TR-367	Tertiary Road	20	913.56	3rd
TR-368	Tertiary Road	20	58.23	2nd
TR-369	Tertiary Road	20	91.03	2nd
TR-370	Tertiary Road	20	174.03	2nd
TR-371	Tertiary Road	20	611.49	2nd
TR-372	Tertiary Road	20	42.11	2nd
TR-373	Tertiary Road	20	126.18	2nd
TR-374	Tertiary Road	20	300.36	2nd
TR-375	Tertiary Road	20	0.00	2nd
TR-376	Tertiary Road	20	0.00	2nd
TR-377	Tertiary Road	20	0.00	2nd
TR-378	Tertiary Road	20	30.65	2nd
TR-379	Tertiary Road	20	27.20	2nd
TR-380	Tertiary Road	20	315.59	2nd
TR-381	Tertiary Road	20	90.27	3rd
TR-382	Tertiary Road	20	97.66	3rd
TR-383	Tertiary Road	20	239.52	3rd
TR-384	Tertiary Road	20	57.37	3rd
TR-385	Tertiary Road	20	81.91	3rd
TR-386	Tertiary Road	20	81.29	3rd
TR-387	Tertiary Road	20	69.58	3rd
TR-388	Tertiary Road	20	91.49	3rd
TR-389	Tertiary Road	20	151.52	2nd
TR-390	Tertiary Road	20	37.89	2nd
TR-391	Tertiary Road	20	49.28	2nd
TR-392	Tertiary Road	20	40.86	2nd
TR-393	Tertiary Road	20	460.19	2nd
TR-394	Tertiary Road	20	23.34	2nd
TR-395	Tertiary Road	20	699.97	2nd
TR-396	Tertiary Road	20	278.76	2nd
TR-397	Tertiary Road	20	74.50	2nd
TR-398	Tertiary Road	20	209.87	2nd
TR-399	Tertiary Road	20	14.98	2nd
TR-400	Tertiary Road	20	291.92	2nd
TR-401	Tertiary Road	20	73.75	2nd
TR-402	Tertiary Road	20	70.79	2nd
TR-403	Tertiary Road	20	78.42	2nd
TR-404	Tertiary Road	20	209.51	2nd
TR-405	Tertiary Road	20	97.64	2nd
TR-406	Tertiary Road	20	105.85	2nd
TR-407	Tertiary Road	20	220.11	2nd
TR-408	Tertiary Road	20	66.56	2nd
TR-409	Tertiary Road	20	0.00	2nd
TR-410	Tertiary Road	20	283.13	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-411	Tertiary Road	20	118.86	2nd
TR-412	Tertiary Road	20	308.83	2nd
TR-413	Tertiary Road	20	123.93	2nd
TR-414	Tertiary Road	20	55.80	3rd
TR-415	Tertiary Road	20	127.38	3rd
TR-416	Tertiary Road	20	25.35	3rd
TR-417	Tertiary Road	20	0.00	3rd
TR-418	Tertiary Road	20	77.32	3rd
TR-419	Tertiary Road	20	107.78	3rd
TR-420	Tertiary Road	20	43.91	3rd
TR-421	Tertiary Road	20	917.50	3rd
TR-422	Tertiary Road	20	27.65	3rd
TR-423	Tertiary Road	20	1048.51	3rd
TR-424	Tertiary Road	20	26.24	3rd
TR-425	Tertiary Road	20	251.58	3rd
TR-426	Tertiary Road	20	178.40	3rd
TR-427	Tertiary Road	20	123.80	3rd
TR-428	Tertiary Road	20	28.79	3rd
TR-429	Tertiary Road	20	277.06	3rd
TR-430	Tertiary Road	20	94.86	3rd
TR-431	Tertiary Road	20	566.26	3rd
TR-432	Tertiary Road	20	972.58	3rd
TR-433	Tertiary Road	20	174.65	3rd
TR-434	Tertiary Road	20	23.68	3rd
TR-435	Tertiary Road	20	191.58	3rd
TR-436	Tertiary Road	20	38.46	3rd
TR-437	Tertiary Road	20	154.99	3rd
TR-438	Tertiary Road	20	181.55	3rd
TR-439	Tertiary Road	20	24.70	3rd
TR-440	Tertiary Road	20	75.36	3rd
TR-441	Tertiary Road	20	269.61	3rd
TR-442	Tertiary Road	20	0.00	3rd
TR-443	Tertiary Road	20	70.82	3rd
TR-444	Tertiary Road	20	121.16	3rd
TR-445	Tertiary Road	20	86.10	3rd
TR-446	Tertiary Road	20	0.00	3rd
TR-447	Tertiary Road	20	62.41	3rd
TR-448	Tertiary Road	20	126.62	3rd
TR-449	Tertiary Road	20	44.85	3rd
TR-450	Tertiary Road	20	152.98	3rd
TR-451	Tertiary Road	20	30.85	3rd
TR-452	Tertiary Road	20	0.00	3rd
TR-453	Tertiary Road	20	0.00	3rd
TR-454	Tertiary Road	20	686.97	3rd
TR-455	Tertiary Road	20	52.95	3rd
TR-456	Tertiary Road	20	72.31	3rd
TR-457	Tertiary Road	20	208.83	3rd
TR-458	Tertiary Road	20	171.33	3rd
TR-459	Tertiary Road	20	166.22	3rd
TR-460	Tertiary Road	20	25.54	3rd
TR-461	Tertiary Road	20	36.60	3rd
TR-462	Tertiary Road	20	1.05	3rd
TR-463	Tertiary Road	20	0.00	3rd
TR-464	Tertiary Road	20	65.28	3rd
TR-465	Tertiary Road	20	25.30	3rd
TR-466	Tertiary Road	20	199.49	3rd
TR-467	Tertiary Road	20	24.32	3rd
TR-468	Tertiary Road	20	34.10	3rd
TR-469	Tertiary Road	20	12.17	3rd
TR-470	Tertiary Road	20	181.41	3rd
TR-471	Tertiary Road	20	163.52	3rd
TR-472	Tertiary Road	20	712.59	3rd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-473	Tertiary Road	20	42.86	3rd
TR-474	Tertiary Road	20	669.92	3rd
TR-475	Tertiary Road	20	44.40	3rd
TR-476	Tertiary Road	20	33.04	3rd
TR-477	Tertiary Road	20	215.26	3rd
TR-478	Tertiary Road	20	50.57	3rd
TR-479	Tertiary Road	20	165.23	3rd
TR-480	Tertiary Road	20	0.00	3rd
TR-481	Tertiary Road	20	9.29	3rd
TR-482	Tertiary Road	20	73.53	3rd
TR-483	Tertiary Road	20	0.09	3rd
TR-484	Tertiary Road	20	670.24	3rd
TR-485	Tertiary Road	20	71.56	3rd
TR-486	Tertiary Road	20	0.01	3rd
TR-487	Tertiary Road	20	85.17	3rd
TR-488	Tertiary Road	20	624.55	3rd
TR-489	Tertiary Road	20	31.80	3rd
TR-490	Tertiary Road	20	401.69	3rd
TR-491	Tertiary Road	20	834.28	3rd
TR-492	Tertiary Road	20	70.93	3rd
TR-493	Tertiary Road	20	275.65	3rd
TR-494	Tertiary Road	20	22.52	3rd
TR-495	Tertiary Road	20	298.19	3rd
TR-496	Tertiary Road	20	49.48	2nd
TR-497	Tertiary Road	20	71.22	2nd
TR-498	Tertiary Road	20	176.23	2nd
TR-499	Tertiary Road	20	43.20	2nd
TR-500	Tertiary Road	20	539.57	2nd
TR-501	Tertiary Road	20	0.00	2nd
TR-502	Tertiary Road	20	0.05	2nd
TR-503	Tertiary Road	20	213.69	2nd
TR-504	Tertiary Road	20	29.42	2nd
TR-505	Tertiary Road	20	24.30	2nd
TR-506	Tertiary Road	20	261.50	2nd
TR-507	Tertiary Road	20	35.34	2nd
TR-508	Tertiary Road	20	62.68	2nd
TR-509	Tertiary Road	20	33.37	2nd
TR-510	Tertiary Road	20	52.25	2nd
TR-511	Tertiary Road	20	67.33	2nd
TR-512	Tertiary Road	20	423.82	2nd
TR-513	Tertiary Road	20	59.88	2nd
TR-514	Tertiary Road	20	1.83	2nd
TR-515	Tertiary Road	20	144.80	2nd
TR-516	Tertiary Road	20	165.91	2nd
TR-517	Tertiary Road	20	141.48	2nd
TR-518	Tertiary Road	20	35.90	2nd
TR-519	Tertiary Road	20	93.57	2nd
TR-520	Tertiary Road	20	680.79	2nd
TR-521	Tertiary Road	20	47.01	2nd
TR-522	Tertiary Road	20	0.00	2nd
TR-523	Tertiary Road	20	0.00	2nd
TR-524	Tertiary Road	20	69.25	2nd
TR-525	Tertiary Road	20	0.00	2nd
TR-526	Tertiary Road	20	4.39	2nd
TR-527	Tertiary Road	20	35.50	2nd
TR-528	Tertiary Road	20	61.85	2nd
TR-529	Tertiary Road	20	58.12	2nd
TR-530	Tertiary Road	20	17.81	2nd
TR-531	Tertiary Road	20	53.64	2nd
TR-532	Tertiary Road	20	52.59	2nd
TR-533	Tertiary Road	20	0.00	2nd
TR-534	Tertiary Road	20	0.00	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-535	Tertiary Road	20	207.92	2nd
TR-536	Tertiary Road	20	0.00	2nd
TR-537	Tertiary Road	20	0.00	2nd
TR-538	Tertiary Road	20	266.84	2nd
TR-539	Tertiary Road	20	60.84	2nd
TR-540	Tertiary Road	20	1.82	2nd
TR-541	Tertiary Road	20	54.29	3rd
TR-542	Tertiary Road	20	3.27	3rd
TR-543	Tertiary Road	20	17.95	3rd
TR-544	Tertiary Road	20	5.76	3rd
TR-545	Tertiary Road	20	0.00	3rd
TR-546	Tertiary Road	20	305.67	3rd
TR-547	Tertiary Road	20	5.71	2nd
TR-548	Tertiary Road	20	234.91	2nd
TR-549	Tertiary Road	20	40.14	2nd
TR-550	Tertiary Road	20	0.00	2nd
TR-551	Tertiary Road	20	0.96	2nd
TR-552	Tertiary Road	20	39.04	2nd
TR-553	Tertiary Road	20	607.46	2nd
TR-554	Tertiary Road	20	462.42	2nd
TR-555	Tertiary Road	20	248.96	2nd
TR-556	Tertiary Road	20	616.10	2nd
TR-557	Tertiary Road	20	79.38	2nd
TR-558	Tertiary Road	20	198.04	2nd
TR-559	Tertiary Road	20	0.00	2nd
TR-560	Tertiary Road	20	135.64	2nd
TR-561	Tertiary Road	20	384.86	2nd
TR-562	Tertiary Road	20	37.88	2nd
TR-563	Tertiary Road	20	46.96	2nd
TR-564	Tertiary Road	20	55.45	3rd
TR-565	Tertiary Road	20	452.63	3rd
TR-566	Tertiary Road	20	254.50	3rd
TR-567	Tertiary Road	20	42.67	3rd
TR-568	Tertiary Road	20	51.86	3rd
TR-569	Tertiary Road	20	188.03	3rd
TR-570	Tertiary Road	20	76.78	3rd
TR-571	Tertiary Road	20	0.32	3rd
TR-572	Tertiary Road	20	0.00	3rd
TR-573	Tertiary Road	20	158.48	3rd
TR-574	Tertiary Road	20	29.39	3rd
TR-575	Tertiary Road	20	78.98	3rd
TR-576	Tertiary Road	20	50.29	3rd
TR-577	Tertiary Road	20	25.34	3rd
TR-578	Tertiary Road	20	849.60	3rd
TR-579	Tertiary Road	20	35.57	3rd
TR-580	Tertiary Road	20	35.92	3rd
TR-581	Tertiary Road	20	35.52	3rd
TR-582	Tertiary Road	20	278.46	3rd
TR-583	Tertiary Road	20	459.11	3rd
TR-584	Tertiary Road	20	47.14	3rd
TR-585	Tertiary Road	20	263.14	3rd
TR-586	Tertiary Road	20	34.05	3rd
TR-587	Tertiary Road	20	63.39	3rd
TR-588	Tertiary Road	20	144.81	3rd
TR-589	Tertiary Road	20	285.07	3rd
TR-590	Tertiary Road	20	63.95	3rd
TR-591	Tertiary Road	20	79.60	3rd
TR-592	Tertiary Road	20	35.87	3rd
TR-593	Tertiary Road	20	32.95	3rd
TR-594	Tertiary Road	20	216.67	3rd
TR-595	Tertiary Road	20	23.28	3rd
TR-596	Tertiary Road	20	33.60	3rd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-597	Tertiary Road	20	39.75	3rd
TR-598	Tertiary Road	20	388.88	3rd
TR-599	Tertiary Road	20	194.67	3rd
TR-600	Tertiary Road	20	461.57	3rd
TR-601	Tertiary Road	20	0.00	3rd
TR-602	Tertiary Road	20	336.59	3rd
TR-603	Tertiary Road	20	196.66	3rd
TR-604	Tertiary Road	20	193.52	3rd
TR-605	Tertiary Road	20	48.29	3rd
TR-606	Tertiary Road	20	28.25	3rd
TR-607	Tertiary Road	20	65.13	3rd
TR-608	Tertiary Road	20	13.63	3rd
TR-609	Tertiary Road	20	3.21	3rd
TR-610	Tertiary Road	20	0.00	3rd
TR-611	Tertiary Road	20	701.03	3rd
TR-612	Tertiary Road	20	0.00	3rd
TR-613	Tertiary Road	20	82.46	3rd
TR-614	Tertiary Road	20	69.84	3rd
TR-615	Tertiary Road	20	1.34	3rd
TR-616	Tertiary Road	20	42.70	3rd
TR-617	Tertiary Road	20	557.13	3rd
TR-618	Tertiary Road	20	230.34	3rd
TR-619	Tertiary Road	20	290.93	3rd
TR-620	Tertiary Road	20	37.92	3rd
TR-621	Tertiary Road	20	319.71	3rd
TR-622	Tertiary Road	20	161.23	3rd
TR-623	Tertiary Road	20	60.76	3rd
TR-624	Tertiary Road	20	45.04	3rd
TR-625	Tertiary Road	20	29.52	3rd
TR-626	Tertiary Road	20	426.11	3rd
TR-627	Tertiary Road	20	960.73	3rd
TR-628	Tertiary Road	20	0.00	3rd
TR-629	Tertiary Road	20	0.00	3rd
TR-630	Tertiary Road	20	57.21	3rd
TR-631	Tertiary Road	20	432.64	3rd
TR-632	Tertiary Road	20	49.55	3rd
TR-633	Tertiary Road	20	662.54	3rd
TR-634	Tertiary Road	20	43.19	3rd
TR-635	Tertiary Road	20	573.68	3rd
TR-636	Tertiary Road	20	31.98	3rd
TR-637	Tertiary Road	20	469.36	3rd
TR-638	Tertiary Road	20	119.73	3rd
TR-639	Tertiary Road	20	43.17	3rd
TR-640	Tertiary Road	20	48.01	3rd
TR-641	Tertiary Road	20	191.96	3rd
TR-642	Tertiary Road	20	215.86	3rd
TR-643	Tertiary Road	20	191.76	3rd
TR-644	Tertiary Road	20	77.27	3rd
TR-645	Tertiary Road	20	214.31	3rd
TR-646	Tertiary Road	20	40.57	3rd
TR-647	Tertiary Road	20	279.81	3rd
TR-648	Tertiary Road	20	426.02	3rd
TR-649	Tertiary Road	20	70.47	3rd
TR-650	Tertiary Road	20	24.44	2nd
TR-651	Tertiary Road	20	31.80	2nd
TR-652	Tertiary Road	20	14.76	2nd
TR-653	Tertiary Road	20	131.20	2nd
TR-654	Tertiary Road	20	71.61	2nd
TR-655	Tertiary Road	20	41.65	2nd
TR-656	Tertiary Road	20	25.43	2nd
TR-657	Tertiary Road	20	28.01	2nd
TR-658	Tertiary Road	20	40.53	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-659	Tertiary Road	20	23.60	2nd
TR-660	Tertiary Road	20	59.64	2nd
TR-661	Tertiary Road	20	368.17	2nd
TR-662	Tertiary Road	20	389.05	2nd
TR-663	Tertiary Road	20	90.24	3rd
TR-664	Tertiary Road	20	23.81	3rd
TR-665	Tertiary Road	20	26.93	3rd
TR-666	Tertiary Road	20	45.01	3rd
TR-667	Tertiary Road	20	32.76	3rd
TR-668	Tertiary Road	20	92.06	3rd
TR-669	Tertiary Road	20	450.70	3rd
TR-670	Tertiary Road	20	43.96	3rd
TR-671	Tertiary Road	20	36.47	3rd
TR-672	Tertiary Road	20	328.44	3rd
TR-673	Tertiary Road	20	505.61	3rd
TR-674	Tertiary Road	20	455.72	3rd
TR-675	Tertiary Road	20	35.18	3rd
TR-676	Tertiary Road	20	30.27	3rd
TR-677	Tertiary Road	20	57.04	3rd
TR-678	Tertiary Road	20	113.09	3rd
TR-679	Tertiary Road	20	2.27	3rd
TR-680	Tertiary Road	20	478.53	3rd
TR-681	Tertiary Road	20	0.00	3rd
TR-682	Tertiary Road	20	198.92	3rd
TR-683	Tertiary Road	20	0.00	3rd
TR-684	Tertiary Road	20	85.53	3rd
TR-685	Tertiary Road	20	4.60	3rd
TR-686	Tertiary Road	20	0.00	3rd
TR-687	Tertiary Road	20	48.70	3rd
TR-688	Tertiary Road	20	214.78	3rd
TR-689	Tertiary Road	20	174.86	3rd
TR-690	Tertiary Road	20	13.88	3rd
TR-691	Tertiary Road	20	75.57	3rd
TR-692	Tertiary Road	20	297.68	3rd
TR-693	Tertiary Road	20	46.25	3rd
TR-694	Tertiary Road	20	0.00	3rd
TR-695	Tertiary Road	20	4.04	3rd
TR-696	Tertiary Road	20	87.30	3rd
TR-697	Tertiary Road	20	46.60	3rd
TR-698	Tertiary Road	20	32.15	3rd
TR-699	Tertiary Road	20	1065.61	3rd
TR-700	Tertiary Road	20	21.61	3rd
TR-701	Tertiary Road	20	32.19	3rd
TR-702	Tertiary Road	20	42.36	3rd
TR-703	Tertiary Road	20	216.15	3rd
TR-704	Tertiary Road	20	47.81	3rd
TR-705	Tertiary Road	20	292.73	3rd
TR-706	Tertiary Road	20	64.41	3rd
TR-707	Tertiary Road	20	1079.79	3rd
TR-708	Tertiary Road	20	17.02	3rd
TR-709	Tertiary Road	20	34.32	3rd
TR-710	Tertiary Road	20	46.52	3rd
TR-711	Tertiary Road	20	37.04	3rd
TR-712	Tertiary Road	20	170.61	3rd
TR-713	Tertiary Road	20	0.00	3rd
TR-714	Tertiary Road	20	99.19	3rd
TR-715	Tertiary Road	20	95.28	3rd
TR-716	Tertiary Road	20	9.08	2nd
TR-717	Tertiary Road	20	53.94	2nd
TR-718	Tertiary Road	20	16.82	2nd
TR-719	Tertiary Road	20	82.52	2nd
TR-720	Tertiary Road	20	320.86	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-721	Tertiary Road	20	28.05	2nd
TR-722	Tertiary Road	20	890.42	2nd
TR-723	Tertiary Road	20	0.00	2nd
TR-724	Tertiary Road	20	1060.34	2nd
TR-725	Tertiary Road	20	12.62	2nd
TR-726	Tertiary Road	20	36.16	2nd
TR-727	Tertiary Road	20	514.14	2nd
TR-728	Tertiary Road	20	97.77	2nd
TR-729	Tertiary Road	20	125.86	3rd
TR-730	Tertiary Road	20	473.30	3rd
TR-731	Tertiary Road	20	0.00	3rd
TR-732	Tertiary Road	20	275.01	3rd
TR-733	Tertiary Road	20	0.01	3rd
TR-734	Tertiary Road	20	413.19	3rd
TR-735	Tertiary Road	20	159.27	3rd
TR-736	Tertiary Road	20	85.85	3rd
TR-737	Tertiary Road	20	38.30	3rd
TR-738	Tertiary Road	20	52.49	3rd
TR-739	Tertiary Road	20	49.92	3rd
TR-740	Tertiary Road	20	115.82	3rd
TR-741	Tertiary Road	20	0.00	3rd
TR-742	Tertiary Road	20	139.53	3rd
TR-743	Tertiary Road	20	44.97	3rd
TR-744	Tertiary Road	20	24.20	3rd
TR-745	Tertiary Road	20	232.12	3rd
TR-746	Tertiary Road	20	200.92	3rd
TR-747	Tertiary Road	20	289.48	3rd
TR-748	Tertiary Road	20	14.73	3rd
TR-749	Tertiary Road	20	535.33	3rd
TR-750	Tertiary Road	20	14.41	3rd
TR-751	Tertiary Road	20	279.30	3rd
TR-752	Tertiary Road	20	33.34	3rd
TR-753	Tertiary Road	20	9.98	3rd
TR-754	Tertiary Road	20	69.63	3rd
TR-755	Tertiary Road	20	32.70	3rd
TR-756	Tertiary Road	20	29.09	3rd
TR-757	Tertiary Road	20	17.80	3rd
TR-758	Tertiary Road	20	42.12	3rd
TR-759	Tertiary Road	20	68.98	3rd
TR-760	Tertiary Road	20	40.63	3rd
TR-761	Tertiary Road	20	19.10	3rd
TR-762	Tertiary Road	20	0.00	3rd
TR-763	Tertiary Road	20	270.77	3rd
TR-764	Tertiary Road	20	0.00	3rd
TR-765	Tertiary Road	20	0.00	3rd
TR-766	Tertiary Road	20	0.00	3rd
TR-767	Tertiary Road	20	16.30	3rd
TR-768	Tertiary Road	20	0.00	3rd
TR-769	Tertiary Road	20	0.00	3rd
TR-770	Tertiary Road	20	0.00	3rd
TR-771	Tertiary Road	20	0.00	3rd
TR-772	Tertiary Road	20	0.00	3rd
TR-773	Tertiary Road	20	0.00	3rd
TR-774	Tertiary Road	20	0.00	3rd
TR-775	Tertiary Road	20	0.00	3rd
TR-776	Tertiary Road	20	0.00	3rd
TR-777	Tertiary Road	20	0.00	3rd
TR-778	Tertiary Road	20	0.00	3rd
TR-779	Tertiary Road	20	0.00	3rd
TR-780	Tertiary Road	20	0.00	3rd
TR-781	Tertiary Road	20	0.00	3rd
TR-782	Tertiary Road	20	0.00	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-783	Tertiary Road	20	0.00	2nd
TR-784	Tertiary Road	20	0.00	2nd
TR-785	Tertiary Road	20	0.00	2nd
TR-786	Tertiary Road	20	0.00	2nd
TR-787	Tertiary Road	20	0.00	2nd
TR-788	Tertiary Road	20	0.00	2nd
TR-789	Tertiary Road	20	0.00	2nd
TR-790	Tertiary Road	20	0.00	2nd
TR-791	Tertiary Road	20	0.00	2nd
TR-792	Tertiary Road	20	0.00	2nd
TR-793	Tertiary Road	20	0.00	2nd
TR-796	Tertiary Road	20	97.72	2nd
TR-797	Tertiary Road	20	361.28	3rd
TR-798	Tertiary Road	20	201.30	3rd
TR-799	Tertiary Road	20	293.63	3rd
TR-807	Tertiary Road	20	280.71	3rd
TR-808	Tertiary Road	20	119.08	3rd
TR-809	Tertiary Road	20	6.39	3rd
TR-810	Tertiary Road	20	146.00	3rd
TR-811	Tertiary Road	20	243.74	3rd
TR-826	Tertiary Road	20	206.35	3rd
TR-838	Tertiary Road	20	140.83	3rd
TR-839	Tertiary Road	20	37.17	3rd
TR-840	Tertiary Road	20	43.24	3rd
TR-841	Tertiary Road	20	16.87	3rd
TR-842	Tertiary Road	20	64.64	3rd
TR-843	Tertiary Road	20	79.67	3rd
TR-844	Tertiary Road	20	192.05	3rd
TR-845	Tertiary Road	20	358.54	3rd
TR-871	Tertiary Road	20	66.23	3rd
TR-872	Tertiary Road	20	8.38	3rd
TR-873	Tertiary Road	20	129.64	3rd
TR-874	Tertiary Road	20	105.50	3rd
TR-875	Tertiary Road	20	4.57	3rd
TR-876	Tertiary Road	20	27.03	3rd
TR-877	Tertiary Road	20	7.63	3rd
TR-878	Tertiary Road	20	213.92	3rd
TR-879	Tertiary Road	20	76.13	3rd
TR-880	Tertiary Road	20	29.69	3rd
TR-881	Tertiary Road	20	3.38	3rd
TR-882	Tertiary Road	20	517.43	3rd
TR-883	Tertiary Road	20	41.21	3rd
TR-884	Tertiary Road	20	103.75	3rd
TR-885	Tertiary Road	20	343.09	3rd
TR-886	Tertiary Road	20	203.39	3rd
TR-887	Tertiary Road	20	209.25	3rd

A. Roads connect Paurashava with Regional Road Network

To avoid traffic congestion within the Paurashava, the road has been widened to 100 feet that goes to Barisal Sadar towards North-South direction. This road has considered the primary entrance of the Paurashava. Secondary road has proposed to connect east west direction of the area.

Hierarchically, the following types of roads have been proposed in the plan:

- major road having rights of way from 100 feet
- secondary road having rights of way from 40 to 60 feet of the right of way

B. Internal Network of the Paurashava

The above mentioned roads would be linked up with the proposed road so that eventually all parts of Gauranadi Paurashava would be well connected.

Here, two types of roads have been proposed to cater the needs of the internal circulation of the Paurashava area. These are:

- secondary road having rights of way 40 to 60 feet
- local road having rights of way from 20 to 30 feet

Table 12.5: Proposed Roads of Gauranadi Paurashava according to Hierarchy

Types of Road	Road Width (ft)	Number of Roads	Length (km)
Paurashava Secondary Road	40	2	0.47
	60	1	1.07
Sub-Total		**3**	**1.54**
Paurashava Tertiary Road	20	59	26.70
Sub-Total		**59**	**26.70**
Total		**62**	**28.23**

Source: Proposed by Consultants

In the road network plan, more than 85% of the roads (according to road length) have proposed for widening.

12.5.4 Proposals for New Roads

To accommodate the traffic volumes about 10-15% land has been considered of total planning area. About 28.23 kilometers new roads have been proposed to ensure accessibility in the area. Phase wise newly proposed Road has been shown in Table 12.6.

Proposed Road Network of Gauranadi Paurashava has been presented on **Map 12.2**.

Table 12.6: Phase wise Newly Proposed Road in Gauranadi Paurashava

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
SR-17	Secondary Road	60	1068.91	1st
SR-18	Secondary Road	40	41.73	1st
SR-19	Secondary Road	40	424.59	1st
TR-794	Tertiary Road	20	499.55	1st
TR-795	Tertiary Road	20	387.78	1st
TR-800	Tertiary Road	20	235.72	1st
TR-801	Tertiary Road	20	517.97	1st
TR-802	Tertiary Road	20	460.98	1st
TR-803	Tertiary Road	20	159.94	1st
TR-804	Tertiary Road	20	283.33	1st
TR-805	Tertiary Road	20	324.26	1st
TR-806	Tertiary Road	20	574.45	1st
TR-812	Tertiary Road	20	332.68	1st
TR-813	Tertiary Road	20	164.64	1st
TR-814	Tertiary Road	20	556.51	1st
TR-815	Tertiary Road	20	254.03	1st
TR-816	Tertiary Road	20	188.06	1st
TR-817	Tertiary Road	20	355.26	1st
TR-818	Tertiary Road	20	374.48	1st
TR-819	Tertiary Road	20	163.20	1st
TR-820	Tertiary Road	20	494.62	1st
TR-821	Tertiary Road	20	1050.16	1st
TR-822	Tertiary Road	20	626.70	1st
TR-823	Tertiary Road	20	406.97	2nd
TR-824	Tertiary Road	20	263.38	2nd

Road ID	Road Type	Width (in ft)	Length (in m)	Development Phase
TR-825	Tertiary Road	20	136.47	2nd
TR-827	Tertiary Road	20	471.19	2nd
TR-828	Tertiary Road	20	1192.89	2nd
TR-829	Tertiary Road	20	316.30	2nd
TR-830	Tertiary Road	20	505.58	2nd
TR-831	Tertiary Road	20	193.87	2nd
TR-832	Tertiary Road	20	104.13	2nd
TR-833	Tertiary Road	20	654.49	2nd
TR-834	Tertiary Road	20	328.79	2nd
TR-835	Tertiary Road	20	153.84	2nd
TR-836	Tertiary Road	20	762.99	2nd
TR-837	Tertiary Road	20	317.76	2nd
TR-846	Tertiary Road	20	792.09	2nd
TR-847	Tertiary Road	20	319.87	2nd
TR-848	Tertiary Road	20	231.18	2nd
TR-849	Tertiary Road	20	707.03	2nd
TR-850	Tertiary Road	20	433.65	2nd
TR-851	Tertiary Road	20	228.27	2nd
TR-852	Tertiary Road	20	1281.12	2nd
TR-853	Tertiary Road	20	1062.40	2nd
TR-854	Tertiary Road	20	488.99	2nd
TR-855	Tertiary Road	20	81.51	3rd
TR-856	Tertiary Road	20	1209.38	3rd
TR-857	Tertiary Road	20	326.50	3rd
TR-858	Tertiary Road	20	420.54	3rd
TR-859	Tertiary Road	20	249.27	3rd
TR-860	Tertiary Road	20	113.79	3rd
TR-861	Tertiary Road	20	478.02	3rd
TR-862	Tertiary Road	20	1129.46	3rd
TR-863	Tertiary Road	20	292.63	2nd
TR-864	Tertiary Road	20	924.93	2nd
TR-865	Tertiary Road	20	406.69	3rd
TR-866	Tertiary Road	20	334.80	3rd
TR-867	Tertiary Road	20	281.17	2nd
TR-868	Tertiary Road	20	276.36	2nd
TR-869	Tertiary Road	20	593.23	3rd
TR-870	Tertiary Road	20	220.03	3rd

12.6 Plans for Other Transportation Facilities

In the field of transportation facilities, the consultant has proposed such facilities as, bus terminal, truck terminal, rickshaw stands, baby taxi/tempo stands and passenger shed for local bus users.

12.6.1 Parking and Terminal Facilities

A) Parking Facilities

Parking facilities at Gauranadi Paurashava has been provided considering two parameters:

- Individual Building: In this context, it is recommended to follow the Building Construction Act, 1996 (Sub-section 2&3, Section-13).
- Area wise Parking Facilities: As per area wise context, it is recommended to provide parking facilities in Commercial and Industrial area. As per Building Construction Act 1996, total 1st 0.26 acre land and 0.80 acre land will be declared as parking zone at commercial area and industrial area of Gauranadi Paurashava.

B) Terminal Facilities

Considering future travel demand in next 20 years; Terminal facilities for Bus, Truck, Motorcycle, Rickshaw and other existing transports have been proposed.

- **Bus Terminal:** One bus terminal has been proposed at ward no 9 and one bus stand has been proposed at ward no. 6. The proposed terminal will comprise about 1st 5.22 acre areas and bus stand occupies 0.60 acre area. Detail has been given in table 2.12, chapter 2, Landuse Plan, Volume II.

- **Other Vehicle Parking:** At Gauranadi Paurashava, no Parking area will be proposed. But every important intersection has sufficient on street parking area in rights of way.

- **Launch Terminal & Ferry Ghat:** No new launch terminal and no new ferry ghat has been proposed rather the existing terminal and ghat has been proposed for expansion.

12.6.2 Development of Facilities for Pedestrians, Bicycles and Rickshaws

A) Pedestrians

Proposals regarding pedestrian walkway have been already depicted in proposed road network plan by providing separate walkway as per priority of facilities. About 1st .5m footpath has been already shown in primary and secondary roads.

B) Bicycles and Rickshaws

Facility provision of bicycles and rickshaws has been already depicted in space allocation of Right of Way (ROW). Separate Service lane of 2.5 m has been already shown in Primary road and 18.m lane in Secondary Roads in figure 12.3.

12.6.3 Other Transportation Facilities


One fuel station has been proposed at ward no 4 comprising about 1.21 acre of land.

12.7 Waterway Development / Improvement Options

At present, water transport facility has significant importance for carrying passenger and commodity. If waterway network can be developed, this will reduce pressure on road network and will also boost up the economic development of the area. Therefore, some measures should be taken to promote the water transport network in Gauranadi Paurashava area:

- Development of infrastructural facilities
- Dredging and maintenance of existing navigable waterways and for resuscitation of dead or dying rivers, channels, or canals, including development of new channels and canals for navigation
- Carry out removal of wrecks and obstruction in inland navigable waterways
- Ensure co-ordination of Inland Water Transport with other forms of transport and with trade and agricultural interests for the optimum utilization of the available transport capacity
- Promote good quality launch services
- Develop, maintain and operate landing/station and terminal facilities
- Prepare plans or schemes for carrying out any of the above mentioned functions by BIWTA.

Map 12.2: Transportation & Traffic Management Plan of Gauranadi Paurashava



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary
- Culvert
- Bridge
- Existing Road
- Proposed Tempo Stand
- Proposed Fuel Station
- Proposed Bus Terminal
- Truck Terminal
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody

0 185370 740 1,110 1,480 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

12.8 TRANSPORTATION SYSTEM MANAGEMENT (TSM)

Fundamental traffic management (TM) regulations have been in practice from the very beginning for example, rules to use a particular side (left or right) of the road. However, the modern objectives of traffic management also include operational efficiency of traffic and improvement of environment.

The main purposes of traffic management are:

- To ensure safe movement of all vehicular and pedestrian traffic
- To improve operational efficiency (junction and network links) in terms of traffic flow
- To improve the environment

The most important aspect of traffic management is its major involvement in its efficient use of basically existing facilities. These may be in the form of:

- Rules and regulations governing the use of facilities. For example, right of use of a roadway, speed limit etc. and
- New works and improvements of limited scale like flow control and segregation measures and devices

12.8.1Strategies for Facility Operations

Parking Management

In Gauranadi Paurashava, parking measures are considered for:

- Bus Stand
- Truck Terminal

To provide parking space, following regulations mentioned in Building Construction Rule, 1996 should be provided:

- Parking functions should be maintained with the Parking or Stand lot, Roads cannot used for maneuvering the vehicles
- For entrance and exit of Bus and Truck in the Terminal minimum 4.5 meter width should be provided
- On-Street Parking is applicable if:
    - Angular Parking should be provided within 45°
    - Within 25 meter of Pedestrian Crossing or Intersection, no parking would be allowed
    - No parking will be allowed over the Highway

12.8.2 Strategies for Traffic Flow and Safety

Following strategies will be adopted to implement circulation network in the planning area:

- A comprehensive road network plan has been prepared for the Paurashava using the hierarchy of road network. Implementation will also be followed following this hierarchy.
- Proposed roads in those areas will be chosen for immediate construction that is needed to promote growth in that area.
- Service roads will be constructed along with the major roads to allow free flow of long distance traffic.

- Bill board should be installed conveying road safety messages and instructions.
- Speed breaker should be provided at the in-front school, colleges and hospitals etc.

12.8.3 Strategies for Traffic Management

- Connect the missing links of primary, secondary and access roads on priority basis.
- Separate lane for non-motorized vehicles should be provisioned on the primary and secondary roads.
- Widen the narrow roads to make networks for efficient circulation.
- Right of Way (ROW) should be kept free from any type of development activities.
- Provide adequate pedestrian facilities and off-street parking wherever needed.
- If requires, tidal flow operation method can be applied in case of some roads. For instance, the morning peak results heavy flow of traffic towards city centre and evening peak results heavy flow towards the outside from the City Centre. In this case, half of other side lane can be utilized for one direction traffic during peak hour.

12.9 Plan Implementation Strategies

The section describes the plan implementation strategies of transportation plan of Gauranadi Paurashava. This also describes the regulation to implement transport pan, evaluation and coordination to implement the transport plan in the Paurashava.

Regulations to Implement the Transportation Plan

Following regulations will be needed for implementation of the plan.

Public Roads Act, 2004: Objectives of the Public Roads Act, 2004 is prescribed in the section 2. Those objectives are to:

(a) Establish ownership and responsibilities for roads;

(b) Establish the framework for managing the road network;

(c) Establish general principles for road management;

(d) Provide for general design and planning principles for roads;

(e) Confer powers and responsibilities on road authorities;

(f) Commit road authorities to provide and maintain safe roads, and to do so using resources efficiently;

(g) Provide for the establishment and classification of public roads;

(h) Provide for data bases of public roads, and public access to them;

(i) set out rights and duties of road users;

(j) Control activities on roads;

(k) Make special provision for restriction on access to roads;

(l) Identify characteristics of new road types;

(m) Provide a legal framework for private sector participation in road construction, operation and maintenance, including tolling of roads;

(n) Establish defenses for civil liabilities; and

(o) Create offences and provide for penalties.

Section 5 of the Public Roads Act, 2004 has defined public roads as-

(1st) The Government may declare a public road.

(2) The declaration may be made in relation to land, whether or not it is currently used for passage by members of the public.

(3) In the declaration, the Government shall classify the public road as:

(a) a national road; (b) a regional road; (c) a Zila road; (d) an urban road; (e) an Upazila road; (f) a union road; (g) a village road.

Motor Vehicles Ordinance, 1983 (Ordinance No. LV of 1983) was enacted in 22nd September, 1983. The Ordinance will be needed mostly for the registration of motor vehicles and issuing of driving license.

Stage Carriages Act, 1861 (Act No. XVI of 1861) was enacted in 7thJuly 1861. Section 1st of the Act has defined the term Stage Carriage and said, "every carriage drawn by one or more horses which shall ordinarily be used for the purpose of conveying passengers for hire to or from any place in Bangladesh shall, without regard to the form or construction of such carriage, be deemed to be a Stage Carriages within the meaning of this Act." Again, according to the section 2, no carriage shall be used as a Stage Carriage unless licensed by a Magistrate.

The Paurashava may, in communication with the RHD and LGED and with the prime approval from the Government may enforce the regulations as mentioned above. Again, some of the relevant regulations of developed countries may be enforced by the appropriate authority for the betterment of accessibility, road safety and road management. In connection with this concept, **Highways Act of England and Wales** may be followed.

According to the section 70(1a) of the **Highways Act of England and Wales**, the owner or occupier of any structure and the owner or occupier of any land on which a structure is situated shall take all reasonable steps to ensure that the structure or the use of the structure is not a hazard or potential hazard to persons using a public road and that it does not obstruct or interfere with the safe use of a public road or the maintenance of a public road.

(b) Where a structure or the use of a structure is a hazard or potential hazard to persons using a public road or where it obstructs or interferes with the safe use of a public road or with the maintenance of a public road, a road authority may serve a notice in writing on the owner or occupier of the structure or on the owner or occupier of any land on which the structure is situated to remove, modify or carry out specified works in relation to the structure within the period stated in the notice.

(2 a) The owner or occupier of land shall take all reasonable steps to ensure that a tree, shrub, hedge or other vegetation on the land is not a hazard or potential hazard to persons using a public road and that it does not obstruct or interfere with the safe use of a public road or the maintenance of a public road.

(b) Where a tree, shrub, hedge or other vegetation is a hazard or potential hazard to persons using a public road or where it obstructs or interferes with the safe use of a public road or with the maintenance of a public road, a road authority may serve a notice in writing on the owner or occupier of the land on which such tree, shrub, hedge or other vegetation is situated requiring the preservation, felling, cutting, lopping, trimming or removal of such tree, shrub, hedge or other vegetation within the period stated in the notice.

Again, section 71(1a) said that, any person who, without lawful authority or the consent of a road authority-

(i) erects, places or retains a sign on a public road, or

(ii) erects, places or retains on a public road any caravan, vehicle or other structure or thing (whether on wheels or not) used for the purposes of advertising, the sale of goods, the provision of services or other similar purpose, shall be guilty of an offence.

Section 76(1st) of the **Highways Act of England and Wales** have provisioned regulations for a road authority and said, a road authority may-

(a) construct and maintain drains in, on, under, through or to any land for the purpose of draining water from, or preventing water flowing onto, a public road,

(b) use any land for the temporary storage or the preparation of any gravel, stone, sand, earth or other material required for the construction or maintenance of a public road.

Implementation, Monitoring, Evaluation and Coordination of the Plan

Implementation through Multi- Sectoral Investment Program: Major infrastructure development works such as primary roads, secondary roads, transportation facilities etc., will largely be controlled by Government. Public works requires efficient co-ordination through the Multi-Sectoral Investment Program (MSIP).

Objective of a Multi-Sectoral Investment Program (MSIP) will match a list of the development projects with the funding stream necessary to implement them. There are two basic activities that would determine the contents of MSIP. One activity would be to prioritize and schedule the investment projects of all public agencies so they will collectively help to achieve the development goals and objectives of the Transportation and Traffic Management Plan. Second activity would be to analyze the source and availability of fund for the prioritized list of development projects.

Implementation through Action Plans and Projects: Action Plans and Projects will be the implementation plans to solve problems at the local level. Action plans will take a direct approach toward plan implementation with a minimum of research, reports or elaborate planning methods. These projects will be easily identifiable and will require minimum resource.

Implementation through Development Control: Landuse zoning is one of several methods of plan implementation to be considered. In all cases where some form of development, landuse control may be applied; careful consideration requires the following ideologies:

- the purpose to be achieved by the development controls;
- where controls should be applied;
- what aspect of development needs to be controlled;
- what type of development controls are required;
- what degree or level of development control is required;
- who will be affected by the required control;
- who will be affected by the controls and in what manner;
- when the controls should be applied;
- what will be the likely impact of the controls;
- how and by whom will the controls be administered and enforced.

Development control as an instrument of plan implementation may be selectively applied within the Urban Area Plans. Development controls would also be varied in intensity and detail to suit the particular circumstances. It is important that they should be clear and easily understood by all parties concerned. Since the entire Paurashava Master Plan ‘package’ has become statutory, development controls associated with its component plans would also be statutory.

Implementation by Facilitating Private Investment: Another approach that would be taken by government toward plan implementation will be to guide and facilitate investments made by the private sector. Government can achieve this with relative ease and at very low cost by setting up a legal and operational framework, coupled with suitable incentives, to facilitate land consolidation plot boundary readjustment, efficient layout of plots and provision of local infrastructure by the private sector. The benefits of this approach would be:

- increased efficiently of the urban land market would make, more private land available to urban households;
- would pass much of the development costs for local infrastructure to the private sector and land market mechanisms;
- would increase in land for development without large cash outlays by government to purchase land for development schemes; and
- would keep provision of land for community facilities virtually no cost to government.

Plan Monitoring

The Transportation and Traffic Management Plan would simply be tools for guiding and encouraging the growth and development of an urban area in a preferred manner. In a rapidly changing urban environment, the Transportation and Traffic Management Plan would require to keep up to date. If this is not done, within a few years it will be obsolete. Therefore, it is imperative that the requirement for regular updating of the Transportation and Traffic Management Plan be made a legal requirement.

For implementation of the various program components of the Transportation and Traffic Management Plan appropriate administrative measures will have to be undertaken. This will essentially include project preparation and monitoring of their execution and evaluation. For carrying out all these activities appropriate institutional measures are also be needed.

Evaluation

Monitoring and evaluation of ongoing and implemented projects is essential to keep the future course of action on the right track. An ongoing project should be regularly monitored and handicaps identified to enable taking appropriate measures at the right time. Post implementation evaluation is also needed to take appropriate measures correcting past errors-from project preparation to implementation.

The top level supervision has to be done by a high level supervisory committee headed by the Paurashava Mayor, LGED representative, RHD and Local Government Ministry. Other members of the committee will be local Ward Councilors, local community leader/social workers and the Town Planner of the Paurashava. The committee will supervise implementation works regularly and issue necessary instructions to expedite the works of implementation.

Co-ordination

A Planning Section of Paurashava should have close interaction with the citizen of Paurashava at large in order to make people aware of the benefits of a good plan and, therefore, their social responsibility to promote plan implementation in one hand and also resist contraventions on the other. A specific interactive cell is recommended to operate in this regard with following responsibilities:

- Provide pre-application advice to residents, consultants and developers about landuse management issues and application procedures for the submission of development applications.

- Enforce planning and landuse management related legislation and zoning scheme regulations.
- Issue of property zoning certificates.
- Investigate and resolve landuse management complaints, illegal landuse and prosecuting contraventions.

Such interactive windows may be opened in various convenient locations to ensure ease of the answers to commonly asked questions may be shown in the internet. Besides, those may be shown in the print and electronic media time to time.

In spontaneous areas, while all out people's co-operation is needed for project implementation; there will also be some elements of negotiation. Negotiation will be particularly needed in case of road widening projects. It will be a crucial task for Paurashava to convince the affected people to give up their land for road use. Efforts should be made to convince the land owners on the ground of enhancement of property value due to road widening. In case people refuse to offer land free of cost necessary arrangements may have to be made for payment of compensation. This process of negotiation will be very critical, cumbersome and time consuming, and therefore, has to be handled with utmost care and patience. The best results can be accrued only by wining people's confidence. In case the authority fails to get peoples co-operation they should exercise power of compulsory acquisition of land through Acquisition of Requisition of Immovable Property Ordinance, 1982. Attempts may be made to engage NGOs / CBOs / RHD / LGED to work as catalysts in negotiation.

13.1 Drainage Management Plan

This chapter states about goals and objectives, and methodology of Drainage Development Plan. An inventory of the existing drainage system of Gauranadi has been made as a part of the comprehensive topographical survey to be taken-up under this project. While assessing the drainage conditions, the serviceability, structural conditions, obstruction, siltation, blockages are taken into consideration. And finally describe the drainage and environmental management plan, and its implementation strategies.

13.1.1 Goals and Objectives

Provision of drainage facilities are important concern to human settlements to create better living environment. Failure to provide the adequate drainage facilities results in flooding and detrimental environmental quality. Drainage of high rainfall region particularly in the context of Barisal region is very important. The objectives of drainage planning are described as follows:

- To analyze drainage aspects in the planning of the Paurashava.
- To study geological fault and lineament of the project area and its surroundings.
- To study the existing water development, flood protection and flood control project (if any) in the area and their impacts in the Paurashava plan.
- To present planning options for drainage of the future Paurashava area.
- To study conservation of the natural resources like parks, open space, water bodies, existing ponds etc.
- To conserve place of historical, architectural (if any) and agricultural importance including natural fisheries.

13.1.2 Methodology and Approach to Planning

Drainage Network Survey for Gauranadi Paurashava has been carried out through the guideline of ToR .In this survey explore the existing drainage network system at Gauranadi Paurashava. The main vision of this survey is explored the length, depth, flow direction, coverage area and satisfactory level of the Paurashava inhabitants. The information of drainage network gathered from topographic, socioeconomic and physical feature survey (detail was given in Chapter 6, Section 6.2 of Gauranadi Survey Report). Major feature of drainage and environment survey are as follow:

- Survey the main drainage channels from their heads to the outfalls and to estimate their capacity to discharge water.
- Collect and analyze meteorological data over time in the area to determine the meteorological conditions and predict storm surges.
- Determine the efficiency of the present drainage systems and make recommendation to government.
- Organize a public enlightenment campaign to expose the adverse effects of dumping refuse in drainage channels, through a mass media meeting.
- Drainage channels were surveyed by leveling from the head of the channels to the outfall using a surveyor's level. A zero datum was chosen at the head of each channel. This zero height was then used to level the channel from the head to the toe or outfall. In areas where water flow was observed, the velocity of the flow was recorded. The flow velocity was calculated by timing the flow rate within a 3-5m length of channel. In areas where sediment or refuse was observed to accumulate in the bottom of the channel, the thickness of such sediment or refuse was measured.

- A questionnaire was administered to local residents to collect information about flooding, refuse disposal and drainage channel patterns from local residents along flood prone areas. The answers to the questionnaire were statistically analyzed and use to decipher resident's opinion on the problem of flooding.

13.2 Existing Drainage System/ Network

13.2.1 Man Made Drains

Drainage network is very much insufficient at the study area. During survey drainage outlets and reservoir are found insufficient in the study area. Very few men made drains are found to drain out waste water and storm water. Table 13.1 shows inventory of major drain in Gauranadi Paurashava.


Table 13.1: Existing Inventory of Drains

Id No.	Type of Drain	length in (m)	width in ft	Ward_Name	Connectivity	
					Start point	End point
D-1	Pucca	250.75	0.33	Ward No. 07	Ward No. 07	Ward No. 07
D-2	Pucca	41.9	0.35	Ward No. 05	Ward No. 05	Ward No. 05
D-3	Pucca	47.05	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-4	Pucca	110.4	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-5	Pucca	79.14	0.5	Ward No. 06	Ward No. 06	Ward No. 06
D-6	Pucca	77.2	0.5	Ward No. 04	Ward No. 04	Ward No. 04
D-7	Pucca	16.25	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-8	Pucca	58.15	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-9	Pucca	88.33	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-10	Pucca	88.84	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-11	Pucca	110.02	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-12	Pucca	110.5	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-13	Pucca	131.83	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-14	Pucca	138.4	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-15	Pucca	295.75	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-16	Pucca	476.08	0.5	Ward No. 01	Ward No. 01	Ward No. 01
D-17	Pucca	16.9	0.5	Ward No. 02	Ward No. 02	Ward No. 02
D-18	Pucca	29.68	0.5	Ward No. 02	Ward No. 02	Ward No. 02
D-19	Pucca	42.35	0.5	Ward No. 02	Ward No. 02	Ward No. 02
D-20	Pucca	45.61	0.5	Ward No. 02	Ward No. 02	Ward No. 02
D-21	Pucca	128.15	0.5	Ward No. 02	Ward No. 02	Ward No. 02
D-22	Pucca	2.04	0.5	Ward No. 04	Ward No. 04	Ward No. 04
D-23	Pucca	76.13	0.5	Ward No. 04	Ward No. 04	Ward No. 04
D-24	Pucca	83.48	0.5	Ward No. 04	Ward No. 04	Ward No. 04
D-25	Pucca	127.03	0.5	Ward No. 04	Ward No. 04	Ward No. 04
D-26	Pucca	136.97	0.5	Ward No. 04	Ward No. 04	Ward No. 04
D-27	Pucca	146.22	0.5	Ward No. 04	Ward No. 04	Ward No. 04
D-28	Pucca	48.29	0.5	Ward No. 05	Ward No. 05	Ward No. 05
D-29	Pucca	121.27	0.5	Ward No. 05	Ward No. 05	Ward No. 05
D-30	Pucca	333.52	0.5	Ward No. 05	Ward No. 05	Ward No. 05
D-31	Pucca	15.14	0.5	Ward No. 06	Ward No. 06	Ward No. 06
D-32	Pucca	221.2	0.5	Ward No. 07	Ward No. 07	Ward No. 07
Total		**4169.9**				

Source: Physical Feature Survey, 2012

Table 13.1 shows the ward wise manmade drainage coverage in Gauranadi Paurashava. Total length of manmade drainage in Gauranadi Paurashava is 4169.9 meter and it covers all Ward. **Map 13.1** Shows the existing Drainage Network of Gauranadi Paurashava.

Map 13.1: Existing Drainage Network of Gauranadi Paurashava



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Existing Drain
- Existing Road
- Waterbody

0 190380 760 1,140 1,520 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

13.2.2 Natural Canal and River

General Description of Natural Canals

The existing natural canal network is spread like tree roots in total Paurashava area. In some portion of the area the condition of the khal and irrigation canal are being encroached by the local people and also by local authority and the situation is deteriorating day by day. So, it should be given much concern to sustain the natural canal.

At Gauranadi Paurashava canals have an important role in drainage system. Total area of khal/canal at Gauranadi is 68.89 acres. Table 13.2 shows the length and connectivity of Khals of Gauranadi Paurashava. and ward wise area coverage of the canals are presented in table 13.2.

Table 13.2: Drainage Coverage of Existing Khals/Canals in Gauranadi Paurashava

Name	Width (in m)	Length (in m)	Starting Point Connection	End Point Connection
Rizia Canal	8.41	1944.29	Ward No. 06	Canal 16
Canal 1	5.03	224.08	Ward No. 01	Ward No. 01
Canal 2	6.24	159.03	Ward No. 01	Ward No. 01
Canal 3	1.41	21555.57	Ward No. 01	Ward No. 01
Canal 4	9.86	332.16	Ward No. 02	Ward No. 02
Canal 5	6.08	202.12	Ward No. 01	Ward No. 01
Canal 6	6.45	604.87	Ward No. 01	Ward No. 01
Canal 7	5.98	757.65	Canal 3	Ward No. 01
Canal 8	7.07	1353.06	Ward No. 01	Ward No. 01
Canal 9	5.76	138.32	Ward No. 01	Ward No. 01
Canal 10	12.56	2994.67	Ward No. 03	Ward No. 01
Canal 11	4.77	127.9	Ward No. 02	Ward No. 02
Canal 12	5.76	1479.7	Ward No. 02	Ward No. 02
Canal 13	2.65	330.09	Ward No. 03	Ward No. 03
Canal 14	4.56	259.56	Ward No. 04	Ward No. 04
Canal 15	5.62	292.21	Rizia Canal	Ward No. 03
Canal 16	25.01	3083.87	Ward No. 07	Ward No. 04
Canal 17	5.08	1783.55	Ward No. 06	Ward No. 07
Canal 18	6.38	5324.94	Ward No. 08	Ward No. 09
Canal 19	4.00	242.27	Ward No. 08	Ward No. 08
Canal 20	7.40	939.99	Canal 24	Ward No. 08
Canal 21	4.43	1087.9	Ward No. 08	Ward No. 08
Canal 22	5.30	3221.67	Ward No. 09	Ward No. 08
Canal 23	6.06	346.59	Ward No. 09	Ward No. 09
Canal 24	4.43	825.58	Ward No. 08	Ward No. 08

Source: Physical Feature Survey, 2012

River

Gaurnadi Paurashava comprises one river namely Torky River (a branch of Areal Kha River) which encloses about 66.76 acre of the Paurashava area covering ward no. 1, 2, 4, 5 and 8. The river serves as primary drainage and is connected with the canals/khals at the Gaurnadi Paurashava.

Other Water Bodies (Pond-Dighi-Ditch and Dyke)

At Gauranadi Paurashava, about 344.43 acre areas are under water bodies comprising ditch and pond. There are about 327 ditches covering 27.73 acres area and 1281 ponds comprising 316.7 acres area. Among the all wards ward no. 6 and 7 has the highest number of ditches and ponds whereas ward 2 has the highest numbers of ponds.

Table 13.3: Ward-Wise Area Coverage of Existing waterbodies at Gauranadi

Ward No.	Ditch		Pond		Total	
	Number	Area (acre)	Number	Area (acre)	Number	Area (acre)
W-1	45	4.73	161	37.16	206	41.89
W-2	19	1.5	55	13.43	74	14.93
W-3	37	3.13	143	44.91	180	48.04
W-4	22	2.21	127	29.36	149	31.57
W-5	26	1.44	80	20.57	106	22.01
W-6	38	3	199	55.33	237	58.33
W-7	48	4.1	185	39.61	233	43.71
W-8	46	3.48	176	34.12	222	37.6
W-9	46	4.14	155	42.21	201	46.35
Total	**327**	**27.73**	**1281**	**316.7**	**1608**	**344.43**

Source: Physical Feature Survey, 2012

13.2.3 Topographic Condition of Existing Drainage Network

Existing natural drainage network and direction of natural flow depends on the elevation of the area. The minimum and maximum ground level varies from 0.1 m to 4.0 m and average height is 1.36 m. From the survey, lowest land elevation is found in the Ward No. 8 and highest in the Ward No. 5. Height of the high land is varied from 2 meter to 4 meter. The flow of storm water will be from the high land to the lowlands and the ultimate destination is the river, cannels and ponds.

13.2.4 Analysis of Peak Hour Run Off Discharge and Identification of Drainage Outfalls

Drain as the structure is generally develops to free our living area from household waste water and rain water of storm water. The daily waste water discharge from a household is negligible so for the drainage design it is necessary to calculate the storm water. Urban storm drainage primarily concerns this surface run-off. The primary objective of urban drainage system design is to drain out this storm water either through open surface drains or through underground sewers. An important parameter for the design of storm water systems is the rate and volume of run-off to be conveyed through the system as a consequence of storms. Run-off estimates are carried out based on knowledge of the occurrences of heavy rainstorms and a relation between rainfall and the corresponding run-off. The quantity of run-off again depends on the geometry and physical properties of the catchments.

Rainfall occurs at irregular intervals, and intensities, and frequency and duration vary within catchments. Due to this random nature of occurrence of rain events, the storm drainage system is designed considering estimated run-off based on the analyses of past rainfall records. A widely used statistical description of heavy rainfall is that of intensity–duration–frequency curves that are developed by processing the data for a large number of storm events observed over a number of years, considering the time variation of the rainfall intensity.

Method Used

Storm and used water: The drains are designed to collect excess rainfall that comes as surface runoff from urban area, convey the runoff and finally discharge them to outfalls. The design of drains involves hydrological computations of rainfall intensity, its frequency of occurrence, duration etc., and the total run off of a particular area. The modified rational method shall be used for calculation of peak runoff for a definite frequency and duration from particular drainage basin. One limitation of this method is that it cannot be used for catchment area greater than 320 acres. The Natural Resources Conservation Service (NRCS) method formerly the US Soil Conservation Service (SCS) method shall be used.

In Modified Rational Method, the overall watershed is divided into zones that contribute to hydraulically significant points of concentration. The boundary of the zones is established based upon local topographic boundaries such as streets, existing drainage systems, etc., using good engineering practice. The design flow rate by Modified Rational Formula is :

$Q = CsC\ r\ IA$

Q = Design runoff flow rate (cfs)

I = Rainfall intensity (in/hr)

Cs = Storage coefficient

Cr = Runoff coefficient

A = Drainage area (acres)

Rainfall Intensity (I): The rainfall intensity is the average rainfall rate for a particular drainage basin or sub-basin. The intensity is selected on the basis of the design rainfall duration and return period. The return period is established by design standards as a design parameter. Rainfall intensity with 5 years return period is generally employed for design of primary drains and canal improvement. Rainfall intensity with 3 years return period is employed for design of secondary drains. The design duration is equal to the time of concentration for the drainage area under consideration. Time of concentration is a critical parameter both for the Modified Rational Equation and SCS method. Time of concentration is generally defined as the longest runoff travel time for contributing flow to reach the outlet or design point, or other point of interest. It is frequently calculated along the longest flow path physically.

Estimating the time of concentration involves identification of an appropriate flow path or paths and estimating runoff travel times along the flow paths. Where post-development conditions include significant pervious surfaces, the time of concentration for just impervious portions of the basin may be required to calculate and compare peak flow response for the basin as a whole against that of the more rapidly-draining impervious surfaces alone. The Time of Concentration composed of the Initial Time of Concentration, sometimes referred to as the Inlet Time or Time of Entry and the Travel Time. Initial Time of Concentration is that time required for runoff to travel from the most remote point in the drainage area to the first point of concentration. This can be determined using the Kirpitch equation. The Initial Time of Concentration must be five minutes or longer. In instances where Initial Times of Concentration are estimated to be shorter than five minutes, five minutes shall be applied.

The second part of the Time of Concentration is the Travel Time that takes the flow to travel along the drain. Channel flow occurs in channels carrying integrated flows, pipes (flowing partially full), and streams. Where storage is not significant, Travel Times can be estimated by applying Manning's Equation, and using estimates of channel characteristics and appropriate roughness values for pipe, channel, or stream features as tabulated in Table 13.4.

$V=[1.49/n]\ [R^{2/3}]\ [S^{1/2}]$

V = Velocity of flow, feet/second
N = Manning's roughness coefficient for channel flow
S = Slope, feet/foot
R = Hydraulic radius, feet

And

$T_t = V / (60L)$

T_t = Travel time, minutes
V = Velocity, feet/second
L = Length, feet

Table 13.4: Manning's "N" Values for Channel Flow

Conduit Material	Manning's "n"	Conduit Material	Manning's "n"
Closed conduits		Pipes	0.011-0.015
Asbestos-cement pipe	0.011-0.015	Liner plates	0.013-0.017
Brick	0.013-0.017	Open Channels	
Cement-lined & seal coated	0.011-0.015	Lined channels	
Concrete pipe	0.011-0.015	Asphalt	0.013-0.017
Helically corrugated metal pipe (12" – 48")	0.013-0.023	Brick	0.012-0.018
Paved invert	0.018-0.022	Vegetation	0.030-0.400
Spun asphalt lined	0.011-0.015	Earth, straight and uniform	0.020-0.030
Spiral metal pipe (smooth)	0.012-0.015	Earth, winding, fairly uniform	0.025-0.040
3 – 8 in. diameter	0.014-0.016	Rock	0.030-0.045
10 – 12 in. diameter	0.016-0.018	Un maintained	0.050-0.140
Larger than 12 in. diameter	0.019-0.021	Fairly regular section	0.030-0.070
Plastic pipe (smooth interior)	0.01.-0.015	Irregular section with pools	0.040-0.100

Source: Municipality of Anchorage. Drainage Design Guideline, March 2007 ver.4.08 pp-62.

Storage Coefficient (Cs): Due to very flat topography of Bangladesh, the runoff is significantly slow. The rainfall after evaporation and infiltration accumulates first in the depressions, until these have been reached their capacity and then runoff. To take these effects a storage coefficient is used. The value of the storage coefficient is based on average ground slope and the nature of the ground surface. Some of the storage coefficients are listed in Table 13.5

Table 13.5: Storage Coefficients for flat land

Characteristics of surface	Storage Coefficient		
	Slope < 1: 1000	Slope < 1: 500	Slope < 1: 500
Residential urban	0.70	0.80	0.90
Commercial	0.80	0.90	1.00
Industrial	0.70	0.80	0.90
Residential Rural nature	0.60	0.70	0.80
Agricultural	0.50	0.60	0.70
Forest/woodland	0.30	0.40	0.50
Aquatic land	0.30	0.40	0.50
Paved area/road	0.80	0.90	1.00

Source: Countywide Comprehensive Plan (Master Drainage Plan) Exhibit-VIII.

Runoff Coefficient (Cr): The runoff coefficient (Cr) values shall be assigned to the various land use zoning classifications. The runoff coefficient values are based on the slope of the land surface, degree of imperviousness and the infiltration capacity of the land surface. The type of land use can greatly affect the amount of runoff. The quantity of runoff and peak flow rates are increased when the land is developed because the impervious surface area increases with the addition of roads, driveways, roofs, etc. The values of the runoff coefficient (Cr) for each land use classification are listed in Table 13.6

Table 13.6: Modified Rational Method Runoff Coefficients

Land use designation	Runoff Coefficient Cr	Land use designation	Runoff Coefficient Cr
Residential rural	0.30	Agricultural exclusive	0.25
Residential semi urban	0.40	Forest and watershed	0.20-0.25

Residential urban	0.5-0.60	Public facilities	0.30-0.60
Apartment professional	0.70	Forest/ woodland	0.25
Neighborhood Commercial	0.85	Paved area/road	0.99
Community Commercial	0.85	Slum area	0.50-0.55
Industrial	0.70-0.75		

Source: Countywide Comprehensive Plan (Master Drainage Plan) Exhibit-VIII.

Catchment Area: The size and shape of the catchment or sub-catchment for each drain shall be determined by plan metering topographic maps and by field survey. In determining the total runoff of a catchment area the following assumptions to be made:

a. The peak rate of runoff at any point is a direct function of the average rainfall for the time of concentration to that point.

b. The recurrence interval of the peak discharge is same as the recurrence interval of the average rainfall intensity.

c. The Time of Concentration is the time required for the runoff to become established and flow from the most distant point of the drainage area to the point of discharge.


Projection

In implementing various infrastructures for development, drainage is generally given less priority and is normally considered to be the last or final steps for development. Such scenario is particularly true for Bangladesh; although different types of drainage infrastructures are among others by far the heaviest impact on physical infrastructure network. As a result, physical environment, health, hygiene and standard of living suffer seriously. In development projects, Government, Semi-government and Public sector allocated funds are mostly spent on buildings, roads and other more visible infrastructures and drainage comes as the last item of development. By the time, drainage development begins to start, there appears shortage of fund, consequently as a matter of policy-do little or do-nothing situation appears and as eyewash very little is done for drainage development. In case of urban development, if drainage is not given priority, sufferings of the inhabitants will continuously increase with the passage of time.


Drainage development for urbanization should start with drains. Drains can be classified as Plot drains, Block drains, Tertiary drains, Secondary drains and Primary drains. Other natural drainage infrastructure is lowland, outfall areas, khals and rivers. Man-made drains are Plot, Block, Tertiary, Secondary and Primary drains and others are natural drainage infrastructures. In planning for drainage network, care will be given on road network in terms of conflict of drainage and waterways with roads. In the following and subsequent sections major element, their principle, purpose and function of drainage infrastructures are discussed and presented in lower to higher order which will be considered as a method for drainage planning.

Primary Drain

Primary drains are called as the main drains. Primary drains cover larger storm drainage area than above discussed tertiary and secondary drains. In ascending order its position is third. Its cross-section is larger than other types; carrying capacity is high and is constructed of brick, cement concrete and sometimes reinforced concrete. Primary drains may be of earthen structure provided sufficient land is available and land value is low. Contributing drainage water comes from tertiary and secondary drains. Primary drains discharge its drainage water to outfall, natural khal, river or large lowland area/ Beels. Figure 13.1 and 13.2 show the typical cross-section of the primary drain.




A Typical Earthen Primary Drain (Dimensions in mm)
Fig 13.1: Earthen Primary Drain



A Typical RCC Primary Drain (Dimensions in mm)
Fig 13.2: Typical RCC Primary Drain

Secondary Drain

Secondary drains collect discharge from tertiary drains. One secondary drain may receive drainage discharges from several tertiary drains in its course. Size and capacity of secondary drain is much bigger than tertiary drains, its catchment area is also bigger than tertiary drains. Like tertiary drains, it may run parallel to bigger roads. Secondary drains may run along and through the middle of its storm water contributing area. The typical cross-section, size and shape, and its construction material are shown in figure 13.3.



A Typical Secondary Drain (Dimensions in mm)
Fig 13.3: A Typical Secondary Drain

Tertiary Drain

Tertiary drain carry run-off or storm water received from the above mentioned plot drains and block or Mohallah drains. Their catchment area or storm water contributing area is bigger than Mohallah drains. Tertiary drains generally are the under jurisdiction of municipality and city corporation. These drains or drainage networks are constructed and maintained directly by municipalities and City Corporation. These drains are constructed by brick, cement concrete and sometimes by excavating earth in their alignments. These drains may run parallel to road or across the catchment area. Sometimes borrow pits of the road serves as drains provided borrow pits are uniformly and continuously excavated. Borrow pits that serve as drains may be channeled or lined by brick works. Tertiary drains deliver its discharge usually to secondary drains. A typical tertiary drain is shown in figure 13.4.

Other kinds of drainage infrastructure are lowland, outfall areas, khals and rivers. Manmade drains are Plot, Block, Tertiary, Secondary and Primary drains and others are natural drainage infrastructures. In planning for drainage network, care should be given for road network in terms of conflict of drainage and waterways with roads. In the following and subsequent sections major element, their principle, purpose and function are discussed and presented in lower to higher order:





Fig 13.4: A Typical Tertiary Drain

Plot Drains

Plot drains are provided around a building on a plot. In most cases, the drain is made of bricks and rectangular in shape that can carry storm water generated in the plot and from the building. Plot drain is connected to the Block or Mohallah drain. Figure 13.5 below gives an impression of plot drain usually constructed in a plot and block drains that follow plot drain.



A Sketch Showing Plot and Block Drain

Fig 13.5: Plot and Block Drain

Block Drain

A block drain is provided at the outside of a block that accommodates several buildings of the block. The block drains are made of bricks like plots drains but bigger in size so that it can serve the storm water generated within the block and the buildings and open areas within the block. Sometimes the block drain may serve few neighboring blocks or Mohallahs. Block drains carry storm water coming from the plot drains. The shape of the block drain is also rectangular, but bigger than plot drains and its bottom is lower than plot drain. The sketch of the plot drain above also shows the block or Mohallah drain under plot drain.


Other Drainage Related Infrastructures

In order to facilitate or mitigate drainage issues some infrastructures are provided or used, these are namely

- Bridges, culverts, box culverts
- Drainage sluices, pipe sluices, siphons
- Flood protection embankments and flood walls
- Sluice gates, Regulators, Navigation lock
- Flood protection and drainage structures.

Bridges, Culverts and Box Culverts

These structures are provided at places wherever roads cross the drainage network system. Such structures are built on the roads to free passage of drainage water and sometimes to provide navigation/ boat passages. Consequently the conflict between drainage and road networks is mitigated. Figures below show bridge and culverts in such system.



Definition Sketch Bridge Definition Sketch Culvert
Fig 13.6: Bridge and Culvert

Drainage sluices, pipe sluices and siphons

Drainage sluices, pipe sluices and siphons are provided on the embankments. Embankments protect the area from floods coming from outside rivers and make the project area flood free.

However storm water from rainfall-runoff within the area causes localized flood, drainage congestion and submergence. A sketch below shows a few of such structures.




Fig 13.7: A schematic view of Drainage sluice, pipe sluice and siphon on embankment which relieve drainage congestion.

13.3 Plans for Drainage Management and Flood Control

13.3.1 Plan for Drain Network Development Drainage Network Plan

The Paurashava needs a hierarchical drainage system for easy and smooth discharge of storm and waste water comprising tertiary, secondary and primary drains. The existing natural khals will serve as primary drains.

13.3.2 Proposal for Improvement of the Existing Drain Networks

Gauranadi paurashava has only 4.20 km pucca drainage network. A narrow portion of the paurashava is served by this network system. Based on the results of drainage study it is recommended for the existing drain that:

- Rehabilitate broken drains;
- Cover the open drains based on budget allocation.
- Construction of new channels and rehabilitation of old ones with enough drainage head.
- Construct a new pump drainage network for the area towards Paira River.
- Remove all un-authorized structures, which developed on drainage structures.
- Regular cleaning and maintenance by the concerned authorities.
- Embarking on a sustained public enlightenment to discourage residents from dumping their refuse into drainage channels.

13.3.3 Outfall of Drains

Maximum drainage out fall exists at Gauranadi Paurashava are in river, canal/ khals in different ward and low lying areas.

13.3.3.1 List of Proposed New Drains

One river and one khal namely Torkey river, and Rizia khal are flowing through the Paurashava and these can play as natural drainage. To give emphasis on natural drainage practices there propose fewer primary drains. Total 4.83 km will be served as primary drain. Based on this primary drain drainage network system of Gauranadi Paurashava will be established. And also canal flowing beside the Barisal-Dhaka Highway is proposed to be linked with the Rizia khal od ward no. 9 to ward no. 6. Table 13.7 shows the summary of proposed drainage facilities at Gauranadi Paurashava. And Map 13.2 shows the drainage network proposal for Gauranadi Paurashava. In additional the torky River flowing through the Gauranadi Paurashava will serve as the main out fall and main natural drainage network. Phasing of proposed drains has been shown in Table 13.8. **Map 13.2** represents the proposed drains in Paurashava.

Table 13.7: Summary of Proposed Drain

Type of Drain	Length (in m)	Length (in km)	%
Primary	4828.81	4.83	2.86
Secondary	26635.95	26.64	15.77
Tertiary	137488.2	137.49	81.38
Grand Total	**168952.95**	**168.95**	**100.00**

Table 13.8: Proposals of New Drain

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
PD-1	Primary Drain	521.49	4.50-5.50	2.00-3.00	1st
PD-1	Primary Drain	199.81	4.50-5.50	2.00-3.00	1st
PD-2	Primary Drain	788.88	4.50-5.50	2.00-3.00	1st
PD-3	Primary Drain	26.46	4.50-5.50	2.00-3.00	1st
PD-3	Primary Drain	1565.18	4.50-5.50	2.00-3.00	1st
PD-4	Primary Drain	1.36	4.50-5.50	2.00-3.00	1st
PD-5	Primary Drain	516.03	4.50-5.50	2.00-3.00	1st
PD-5	Primary Drain	33.66	4.50-5.50	2.00-3.00	1st
PD-6	Primary Drain	234.38	4.50-5.50	2.00-3.00	1st
PD-7	Primary Drain	429.07	4.50-5.50	2.00-3.00	1st
PD-7	Primary Drain	512.50	4.50-5.50	2.00-3.00	1st

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
SD-1	Secondary Drain	1151.51	3.50-4.50	1.25-3.00	1st
SD-2	Secondary Drain	847.51	3.50-4.50	1.25-3.00	1st
SD-3	Secondary Drain	859.24	3.50-4.50	1.25-3.00	1st
SD-3	Secondary Drain	569.99	3.50-4.50	1.25-3.00	1st
SD-4	Secondary Drain	408.93	3.50-4.50	1.25-3.00	1st
SD-5	Secondary Drain	479.95	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	1003.49	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	1383.25	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	123.07	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	123.07	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	1088.99	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	1130.37	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	543.99	3.50-4.50	1.25-3.00	1st
SD-7	Secondary Drain	489.19	3.50-4.50	1.25-3.00	1st
SD-8	Secondary Drain	866.22	3.50-4.50	1.25-3.00	1st
SD-8	Secondary Drain	92.18	3.50-4.50	1.25-3.00	1st
SD-8	Secondary Drain	712.57	3.50-4.50	1.25-3.00	1st
SD-8	Secondary Drain	38.15	3.50-4.50	1.25-3.00	1st
SD-9	Secondary Drain	426.02	3.50-4.50	1.25-3.00	1st
SD-10	Secondary Drain	260.98	3.50-4.50	1.25-3.00	1st
SD-22	Secondary Drain	461.99	3.50-4.50	1.25-3.00	1st
SD-22	Secondary Drain	123.36	3.50-4.50	1.25-3.00	1st
SD-23	Secondary Drain	0.62	3.50-4.50	1.25-3.00	1st
SD-24	Secondary Drain	276.74	3.50-4.50	1.25-3.00	1st
SD-25	Secondary Drain	365.22	3.50-4.50	1.25-3.00	1st
SD-26	Secondary Drain	34.45	3.50-4.50	1.25-3.00	1st
SD-27	Secondary Drain	1229.46	3.50-4.50	1.25-3.00	1st
SD-27	Secondary Drain	602.09	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	19.10	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	19.10	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	16.30	3.50-4.50	1.25-3.00	1st
SD-6	Secondary Drain	16.30	3.50-4.50	1.25-3.00	1st
SD-11	Secondary Drain	212.13	3.50-4.50	1.25-3.00	2nd
SD-11	Secondary Drain	882.98	3.50-4.50	1.25-3.00	2nd
SD-12	Secondary Drain	1354.75	3.50-4.50	1.25-3.00	2nd
SD-13	Secondary Drain	146.47	3.50-4.50	1.25-3.00	2nd
SD-13	Secondary Drain	410.04	3.50-4.50	1.25-3.00	2nd
SD-14	Secondary Drain	832.82	3.50-4.50	1.25-3.00	2nd
SD-14	Secondary Drain	1503.92	3.50-4.50	1.25-3.00	2nd
SD-15	Secondary Drain	927.49	3.50-4.50	1.25-3.00	2nd
SD-16	Secondary Drain	669.63	3.50-4.50	1.25-3.00	2nd
SD-16	Secondary Drain	2092.13	3.50-4.50	1.25-3.00	2nd
SD-17	Secondary Drain	1656.15	3.50-4.50	1.25-3.00	2nd
SD-18	Secondary Drain	1.04	3.50-4.50	1.25-3.00	2nd
SD-19	Secondary Drain	2.56	3.50-4.50	1.25-3.00	2nd
SD-20	Secondary Drain	2.62	3.50-4.50	1.25-3.00	2nd
SD-21	Secondary Drain	177.81	3.50-4.50	1.25-3.00	2nd
TD-3	Tertiary Drain	4.24	2.5-3.5	0.64-1.25	2nd
TD-3	Tertiary Drain	4.24	2.5-3.5	0.64-1.25	2nd
TD-4	Tertiary Drain	26.63	2.5-3.5	0.64-1.25	2nd
TD-5	Tertiary Drain	98.97	2.5-3.5	0.64-1.25	2nd
TD-6	Tertiary Drain	3.40	2.5-3.5	0.64-1.25	2nd
TD-8	Tertiary Drain	279.07	2.5-3.5	0.64-1.25	2nd
TD-9	Tertiary Drain	110.27	2.5-3.5	0.64-1.25	2nd
TD-10	Tertiary Drain	125.21	2.5-3.5	0.64-1.25	2nd
TD-12	Tertiary Drain	10.30	2.5-3.5	0.64-1.25	2nd
TD-13	Tertiary Drain	159.87	2.5-3.5	0.64-1.25	2nd
TD-14	Tertiary Drain	33.94	2.5-3.5	0.64-1.25	2nd
TD-15	Tertiary Drain	293.33	2.5-3.5	0.64-1.25	2nd
TD-17	Tertiary Drain	4.16	2.5-3.5	0.64-1.25	2nd
TD-18	Tertiary Drain	576.05	2.5-3.5	0.64-1.25	2nd
TD-18	Tertiary Drain	475.51	2.5-3.5	0.64-1.25	2nd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-20	Tertiary Drain	2.39	2.5-3.5	0.64-1.25	2nd
TD-21	Tertiary Drain	333.30	2.5-3.5	0.64-1.25	2nd
TD-22	Tertiary Drain	61.29	2.5-3.5	0.64-1.25	2nd
TD-23	Tertiary Drain	46.54	2.5-3.5	0.64-1.25	2nd
TD-24	Tertiary Drain	59.59	2.5-3.5	0.64-1.25	2nd
TD-26	Tertiary Drain	83.65	2.5-3.5	0.64-1.25	2nd
TD-27	Tertiary Drain	384.35	2.5-3.5	0.64-1.25	2nd
TD-28	Tertiary Drain	418.06	2.5-3.5	0.64-1.25	2nd
TD-30	Tertiary Drain	117.42	2.5-3.5	0.64-1.25	2nd
TD-32	Tertiary Drain	256.92	2.5-3.5	0.64-1.25	2nd
TD-33	Tertiary Drain	648.40	2.5-3.5	0.64-1.25	2nd
TD-34	Tertiary Drain	57.23	2.5-3.5	0.64-1.25	2nd
TD-36	Tertiary Drain	3.27	2.5-3.5	0.64-1.25	2nd
TD-37	Tertiary Drain	337.53	2.5-3.5	0.64-1.25	2nd
TD-38	Tertiary Drain	386.87	2.5-3.5	0.64-1.25	2nd
TD-39	Tertiary Drain	115.69	2.5-3.5	0.64-1.25	2nd
TD-40	Tertiary Drain	271.93	2.5-3.5	0.64-1.25	2nd
TD-42	Tertiary Drain	66.16	2.5-3.5	0.64-1.25	2nd
TD-43	Tertiary Drain	0.00	2.5-3.5	0.64-1.25	2nd
TD-43	Tertiary Drain	0.00	2.5-3.5	0.64-1.25	2nd
TD-44	Tertiary Drain	20.06	2.5-3.5	0.64-1.25	2nd
TD-45	Tertiary Drain	476.56	2.5-3.5	0.64-1.25	2nd
TD-45	Tertiary Drain	152.28	2.5-3.5	0.64-1.25	2nd
TD-48	Tertiary Drain	348.69	2.5-3.5	0.64-1.25	2nd
TD-48	Tertiary Drain	166.01	2.5-3.5	0.64-1.25	2nd
TD-50	Tertiary Drain	1921.08	2.5-3.5	0.64-1.25	2nd
TD-51	Tertiary Drain	1037.05	2.5-3.5	0.64-1.25	2nd
TD-52	Tertiary Drain	48.83	2.5-3.5	0.64-1.25	2nd
TD-53	Tertiary Drain	2.59	2.5-3.5	0.64-1.25	2nd
TD-54	Tertiary Drain	302.52	2.5-3.5	0.64-1.25	2nd
TD-55	Tertiary Drain	150.92	2.5-3.5	0.64-1.25	2nd
TD-56	Tertiary Drain	300.11	2.5-3.5	0.64-1.25	2nd
TD-57	Tertiary Drain	325.36	2.5-3.5	0.64-1.25	2nd
TD-58	Tertiary Drain	166.89	2.5-3.5	0.64-1.25	2nd
TD-59	Tertiary Drain	42.06	2.5-3.5	0.64-1.25	2nd
TD-60	Tertiary Drain	60.08	2.5-3.5	0.64-1.25	2nd
TD-61	Tertiary Drain	272.29	2.5-3.5	0.64-1.25	2nd
TD-62	Tertiary Drain	488.54	2.5-3.5	0.64-1.25	2nd
TD-63	Tertiary Drain	80.90	2.5-3.5	0.64-1.25	2nd
TD-64	Tertiary Drain	168.86	2.5-3.5	0.64-1.25	2nd
TD-65	Tertiary Drain	894.48	2.5-3.5	0.64-1.25	2nd
TD-66	Tertiary Drain	469.67	2.5-3.5	0.64-1.25	2nd
TD-67	Tertiary Drain	701.79	2.5-3.5	0.64-1.25	2nd
TD-68	Tertiary Drain	280.29	2.5-3.5	0.64-1.25	2nd
TD-69	Tertiary Drain	85.30	2.5-3.5	0.64-1.25	2nd
TD-70	Tertiary Drain	735.37	2.5-3.5	0.64-1.25	2nd
TD-71	Tertiary Drain	12.88	2.5-3.5	0.64-1.25	2nd
TD-73	Tertiary Drain	125.25	2.5-3.5	0.64-1.25	2nd
TD-74	Tertiary Drain	62.20	2.5-3.5	0.64-1.25	2nd
TD-75	Tertiary Drain	76.57	2.5-3.5	0.64-1.25	2nd
TD-76	Tertiary Drain	125.25	2.5-3.5	0.64-1.25	2nd
TD-77	Tertiary Drain	200.55	2.5-3.5	0.64-1.25	2nd
TD-78	Tertiary Drain	80.10	2.5-3.5	0.64-1.25	2nd
TD-79	Tertiary Drain	17.13	2.5-3.5	0.64-1.25	2nd
TD-80	Tertiary Drain	47.10	2.5-3.5	0.64-1.25	2nd
TD-81	Tertiary Drain	22.53	2.5-3.5	0.64-1.25	2nd
TD-82	Tertiary Drain	94.47	2.5-3.5	0.64-1.25	2nd
TD-83	Tertiary Drain	76.85	2.5-3.5	0.64-1.25	2nd
TD-84	Tertiary Drain	128.12	2.5-3.5	0.64-1.25	2nd
TD-85	Tertiary Drain	275.00	2.5-3.5	0.64-1.25	2nd
TD-86	Tertiary Drain	9.20	2.5-3.5	0.64-1.25	2nd
TD-87	Tertiary Drain	287.18	2.5-3.5	0.64-1.25	2nd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-88	Tertiary Drain	1042.63	2.5-3.5	0.64-1.25	2nd
TD-90	Tertiary Drain	75.95	2.5-3.5	0.64-1.25	2nd
TD-91	Tertiary Drain	97.90	2.5-3.5	0.64-1.25	2nd
TD-92	Tertiary Drain	159.13	2.5-3.5	0.64-1.25	2nd
TD-94	Tertiary Drain	33.24	2.5-3.5	0.64-1.25	2nd
TD-96	Tertiary Drain	382.10	2.5-3.5	0.64-1.25	2nd
TD-96	Tertiary Drain	544.15	2.5-3.5	0.64-1.25	2nd
TD-96	Tertiary Drain	570.94	2.5-3.5	0.64-1.25	2nd
TD-97	Tertiary Drain	51.50	2.5-3.5	0.64-1.25	2nd
TD-98	Tertiary Drain	294.18	2.5-3.5	0.64-1.25	2nd
TD-99	Tertiary Drain	47.58	2.5-3.5	0.64-1.25	2nd
TD-100	Tertiary Drain	29.21	2.5-3.5	0.64-1.25	2nd
TD-101	Tertiary Drain	82.67	2.5-3.5	0.64-1.25	2nd
TD-104	Tertiary Drain	48.06	2.5-3.5	0.64-1.25	2nd
TD-105	Tertiary Drain	50.58	2.5-3.5	0.64-1.25	2nd
TD-106	Tertiary Drain	203.15	2.5-3.5	0.64-1.25	2nd
TD-107	Tertiary Drain	216.83	2.5-3.5	0.64-1.25	2nd
TD-108	Tertiary Drain	144.05	2.5-3.5	0.64-1.25	2nd
TD-109	Tertiary Drain	732.85	2.5-3.5	0.64-1.25	2nd
TD-110	Tertiary Drain	373.59	2.5-3.5	0.64-1.25	2nd
TD-112	Tertiary Drain	2.72	2.5-3.5	0.64-1.25	2nd
TD-115	Tertiary Drain	262.57	2.5-3.5	0.64-1.25	2nd
TD-116	Tertiary Drain	3.97	2.5-3.5	0.64-1.25	2nd
TD-118	Tertiary Drain	108.72	2.5-3.5	0.64-1.25	2nd
TD-119	Tertiary Drain	33.79	2.5-3.5	0.64-1.25	2nd
TD-120	Tertiary Drain	138.51	2.5-3.5	0.64-1.25	2nd
TD-121	Tertiary Drain	68.37	2.5-3.5	0.64-1.25	2nd
TD-122	Tertiary Drain	15.11	2.5-3.5	0.64-1.25	2nd
TD-123	Tertiary Drain	155.13	2.5-3.5	0.64-1.25	2nd
TD-126	Tertiary Drain	176.75	2.5-3.5	0.64-1.25	2nd
TD-127	Tertiary Drain	148.29	2.5-3.5	0.64-1.25	2nd
TD-128	Tertiary Drain	46.97	2.5-3.5	0.64-1.25	2nd
TD-129	Tertiary Drain	156.30	2.5-3.5	0.64-1.25	2nd
TD-132	Tertiary Drain	506.11	2.5-3.5	0.64-1.25	2nd
TD-133	Tertiary Drain	95.22	2.5-3.5	0.64-1.25	2nd
TD-134	Tertiary Drain	68.03	2.5-3.5	0.64-1.25	2nd
TD-135	Tertiary Drain	610.70	2.5-3.5	0.64-1.25	2nd
TD-136	Tertiary Drain	329.25	2.5-3.5	0.64-1.25	2nd
TD-137	Tertiary Drain	66.52	2.5-3.5	0.64-1.25	2nd
TD-138	Tertiary Drain	583.32	2.5-3.5	0.64-1.25	2nd
TD-139	Tertiary Drain	188.36	2.5-3.5	0.64-1.25	2nd
TD-140	Tertiary Drain	156.54	2.5-3.5	0.64-1.25	2nd
TD-141	Tertiary Drain	95.98	2.5-3.5	0.64-1.25	2nd
TD-143	Tertiary Drain	91.46	2.5-3.5	0.64-1.25	2nd
TD-144	Tertiary Drain	153.65	2.5-3.5	0.64-1.25	2nd
TD-145	Tertiary Drain	153.41	2.5-3.5	0.64-1.25	2nd
TD-145	Tertiary Drain	4.47	2.5-3.5	0.64-1.25	2nd
TD-146	Tertiary Drain	37.64	2.5-3.5	0.64-1.25	2nd
TD-147	Tertiary Drain	23.57	2.5-3.5	0.64-1.25	2nd
TD-149	Tertiary Drain	117.73	2.5-3.5	0.64-1.25	2nd
TD-150	Tertiary Drain	81.74	2.5-3.5	0.64-1.25	2nd
TD-151	Tertiary Drain	141.78	2.5-3.5	0.64-1.25	2nd
TD-153	Tertiary Drain	84.71	2.5-3.5	0.64-1.25	2nd
TD-154	Tertiary Drain	50.24	2.5-3.5	0.64-1.25	2nd
TD-155	Tertiary Drain	86.54	2.5-3.5	0.64-1.25	2nd
TD-156	Tertiary Drain	73.66	2.5-3.5	0.64-1.25	2nd
TD-157	Tertiary Drain	63.81	2.5-3.5	0.64-1.25	2nd
TD-158	Tertiary Drain	66.79	2.5-3.5	0.64-1.25	2nd
TD-159	Tertiary Drain	36.99	2.5-3.5	0.64-1.25	2nd
TD-160	Tertiary Drain	181.88	2.5-3.5	0.64-1.25	2nd
TD-161	Tertiary Drain	243.57	2.5-3.5	0.64-1.25	2nd
TD-161	Tertiary Drain	1741.01	2.5-3.5	0.64-1.25	2nd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-161	Tertiary Drain	260.89	2.5-3.5	0.64-1.25	2nd
TD-162	Tertiary Drain	366.97	2.5-3.5	0.64-1.25	2nd
TD-163	Tertiary Drain	176.12	2.5-3.5	0.64-1.25	2nd
TD-164	Tertiary Drain	61.52	2.5-3.5	0.64-1.25	2nd
TD-165	Tertiary Drain	17.27	2.5-3.5	0.64-1.25	2nd
TD-166	Tertiary Drain	1.42	2.5-3.5	0.64-1.25	2nd
TD-167	Tertiary Drain	165.55	2.5-3.5	0.64-1.25	2nd
TD-168	Tertiary Drain	99.06	2.5-3.5	0.64-1.25	2nd
TD-169	Tertiary Drain	29.69	2.5-3.5	0.64-1.25	2nd
TD-170	Tertiary Drain	27.80	2.5-3.5	0.64-1.25	2nd
TD-171	Tertiary Drain	20.10	2.5-3.5	0.64-1.25	2nd
TD-172	Tertiary Drain	55.33	2.5-3.5	0.64-1.25	2nd
TD-173	Tertiary Drain	50.96	2.5-3.5	0.64-1.25	2nd
TD-174	Tertiary Drain	129.42	2.5-3.5	0.64-1.25	2nd
TD-175	Tertiary Drain	96.49	2.5-3.5	0.64-1.25	2nd
TD-177	Tertiary Drain	243.41	2.5-3.5	0.64-1.25	2nd
TD-180	Tertiary Drain	92.92	2.5-3.5	0.64-1.25	2nd
TD-181	Tertiary Drain	109.69	2.5-3.5	0.64-1.25	2nd
TD-182	Tertiary Drain	924.85	2.5-3.5	0.64-1.25	2nd
TD-184	Tertiary Drain	329.53	2.5-3.5	0.64-1.25	2nd
TD-185	Tertiary Drain	168.83	2.5-3.5	0.64-1.25	2nd
TD-186	Tertiary Drain	134.64	2.5-3.5	0.64-1.25	2nd
TD-187	Tertiary Drain	45.51	2.5-3.5	0.64-1.25	2nd
TD-188	Tertiary Drain	37.23	2.5-3.5	0.64-1.25	2nd
TD-188	Tertiary Drain	1051.25	2.5-3.5	0.64-1.25	2nd
TD-188	Tertiary Drain	912.50	2.5-3.5	0.64-1.25	2nd
TD-189	Tertiary Drain	246.39	2.5-3.5	0.64-1.25	2nd
TD-190	Tertiary Drain	94.41	2.5-3.5	0.64-1.25	2nd
TD-191	Tertiary Drain	27.39	2.5-3.5	0.64-1.25	2nd
TD-193	Tertiary Drain	645.13	2.5-3.5	0.64-1.25	2nd
TD-194	Tertiary Drain	112.19	2.5-3.5	0.64-1.25	2nd
TD-195	Tertiary Drain	127.78	2.5-3.5	0.64-1.25	2nd
TD-196	Tertiary Drain	428.06	2.5-3.5	0.64-1.25	2nd
TD-197	Tertiary Drain	42.35	2.5-3.5	0.64-1.25	2nd
TD-198	Tertiary Drain	879.37	2.5-3.5	0.64-1.25	2nd
TD-199	Tertiary Drain	62.76	2.5-3.5	0.64-1.25	2nd
TD-200	Tertiary Drain	111.53	2.5-3.5	0.64-1.25	2nd
TD-201	Tertiary Drain	8.42	2.5-3.5	0.64-1.25	2nd
TD-202	Tertiary Drain	370.13	2.5-3.5	0.64-1.25	2nd
TD-203	Tertiary Drain	113.55	2.5-3.5	0.64-1.25	2nd
TD-204	Tertiary Drain	105.84	2.5-3.5	0.64-1.25	2nd
TD-205	Tertiary Drain	70.04	2.5-3.5	0.64-1.25	2nd
TD-206	Tertiary Drain	99.26	2.5-3.5	0.64-1.25	2nd
TD-207	Tertiary Drain	107.59	2.5-3.5	0.64-1.25	2nd
TD-208	Tertiary Drain	14.73	2.5-3.5	0.64-1.25	2nd
TD-210	Tertiary Drain	74.34	2.5-3.5	0.64-1.25	2nd
TD-212	Tertiary Drain	0.63	2.5-3.5	0.64-1.25	2nd
TD-213	Tertiary Drain	136.94	2.5-3.5	0.64-1.25	2nd
TD-214	Tertiary Drain	0.24	2.5-3.5	0.64-1.25	2nd
TD-215	Tertiary Drain	139.02	2.5-3.5	0.64-1.25	2nd
TD-216	Tertiary Drain	49.49	2.5-3.5	0.64-1.25	2nd
TD-217	Tertiary Drain	0.41	2.5-3.5	0.64-1.25	2nd
TD-218	Tertiary Drain	441.43	2.5-3.5	0.64-1.25	2nd
TD-219	Tertiary Drain	40.01	2.5-3.5	0.64-1.25	2nd
TD-220	Tertiary Drain	40.07	2.5-3.5	0.64-1.25	2nd
TD-222	Tertiary Drain	203.14	2.5-3.5	0.64-1.25	2nd
TD-223	Tertiary Drain	88.26	2.5-3.5	0.64-1.25	2nd
TD-224	Tertiary Drain	71.69	2.5-3.5	0.64-1.25	2nd
TD-225	Tertiary Drain	68.89	2.5-3.5	0.64-1.25	2nd
TD-226	Tertiary Drain	337.89	2.5-3.5	0.64-1.25	3rd
TD-227	Tertiary Drain	181.63	2.5-3.5	0.64-1.25	3rd
TD-228	Tertiary Drain	304.86	2.5-3.5	0.64-1.25	3rd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-229	Tertiary Drain	221.75	2.5-3.5	0.64-1.25	3rd
TD-230	Tertiary Drain	258.51	2.5-3.5	0.64-1.25	3rd
TD-231	Tertiary Drain	176.34	2.5-3.5	0.64-1.25	3rd
TD-232	Tertiary Drain	533.69	2.5-3.5	0.64-1.25	3rd
TD-234	Tertiary Drain	1.16	2.5-3.5	0.64-1.25	3rd
TD-236	Tertiary Drain	84.77	2.5-3.5	0.64-1.25	3rd
TD-237	Tertiary Drain	91.81	2.5-3.5	0.64-1.25	3rd
TD-238	Tertiary Drain	387.86	2.5-3.5	0.64-1.25	3rd
TD-240	Tertiary Drain	42.45	2.5-3.5	0.64-1.25	3rd
TD-242	Tertiary Drain	1.74	2.5-3.5	0.64-1.25	3rd
TD-243	Tertiary Drain	59.48	2.5-3.5	0.64-1.25	3rd
TD-244	Tertiary Drain	43.24	2.5-3.5	0.64-1.25	3rd
TD-247	Tertiary Drain	360.64	2.5-3.5	0.64-1.25	3rd
TD-248	Tertiary Drain	28.56	2.5-3.5	0.64-1.25	3rd
TD-254	Tertiary Drain	621.35	2.5-3.5	0.64-1.25	3rd
TD-254	Tertiary Drain	31.93	2.5-3.5	0.64-1.25	3rd
TD-256	Tertiary Drain	0.29	2.5-3.5	0.64-1.25	3rd
TD-257	Tertiary Drain	47.56	2.5-3.5	0.64-1.25	3rd
TD-259	Tertiary Drain	55.89	2.5-3.5	0.64-1.25	3rd
TD-260	Tertiary Drain	29.27	2.5-3.5	0.64-1.25	3rd
TD-263	Tertiary Drain	519.41	2.5-3.5	0.64-1.25	3rd
TD-264	Tertiary Drain	197.04	2.5-3.5	0.64-1.25	3rd
TD-265	Tertiary Drain	30.22	2.5-3.5	0.64-1.25	3rd
TD-267	Tertiary Drain	112.22	2.5-3.5	0.64-1.25	3rd
TD-268	Tertiary Drain	20.02	2.5-3.5	0.64-1.25	3rd
TD-269	Tertiary Drain	256.43	2.5-3.5	0.64-1.25	3rd
TD-270	Tertiary Drain	81.83	2.5-3.5	0.64-1.25	3rd
TD-271	Tertiary Drain	85.07	2.5-3.5	0.64-1.25	3rd
TD-275	Tertiary Drain	1018.52	2.5-3.5	0.64-1.25	3rd
TD-277	Tertiary Drain	8.49	2.5-3.5	0.64-1.25	3rd
TD-278	Tertiary Drain	239.25	2.5-3.5	0.64-1.25	3rd
TD-279	Tertiary Drain	97.79	2.5-3.5	0.64-1.25	3rd
TD-280	Tertiary Drain	60.14	2.5-3.5	0.64-1.25	3rd
TD-281	Tertiary Drain	76.46	2.5-3.5	0.64-1.25	3rd
TD-282	Tertiary Drain	66.40	2.5-3.5	0.64-1.25	3rd
TD-283	Tertiary Drain	84.74	2.5-3.5	0.64-1.25	3rd
TD-284	Tertiary Drain	502.60	2.5-3.5	0.64-1.25	3rd
TD-285	Tertiary Drain	670.07	2.5-3.5	0.64-1.25	3rd
TD-286	Tertiary Drain	490.29	2.5-3.5	0.64-1.25	3rd
TD-287	Tertiary Drain	195.74	2.5-3.5	0.64-1.25	3rd
TD-288	Tertiary Drain	506.43	2.5-3.5	0.64-1.25	3rd
TD-289	Tertiary Drain	54.90	2.5-3.5	0.64-1.25	3rd
TD-290	Tertiary Drain	276.11	2.5-3.5	0.64-1.25	3rd
TD-291	Tertiary Drain	101.61	2.5-3.5	0.64-1.25	3rd
TD-292	Tertiary Drain	215.53	2.5-3.5	0.64-1.25	3rd
TD-293	Tertiary Drain	1546.91	2.5-3.5	0.64-1.25	3rd
TD-293	Tertiary Drain	509.76	2.5-3.5	0.64-1.25	3rd
TD-294	Tertiary Drain	209.43	2.5-3.5	0.64-1.25	3rd
TD-295	Tertiary Drain	47.53	2.5-3.5	0.64-1.25	3rd
TD-296	Tertiary Drain	986.12	2.5-3.5	0.64-1.25	3rd
TD-297	Tertiary Drain	201.67	2.5-3.5	0.64-1.25	3rd
TD-298	Tertiary Drain	71.37	2.5-3.5	0.64-1.25	3rd
TD-299	Tertiary Drain	68.56	2.5-3.5	0.64-1.25	3rd
TD-300	Tertiary Drain	913.56	2.5-3.5	0.64-1.25	3rd
TD-301	Tertiary Drain	174.03	2.5-3.5	0.64-1.25	3rd
TD-302	Tertiary Drain	42.11	2.5-3.5	0.64-1.25	3rd
TD-303	Tertiary Drain	126.18	2.5-3.5	0.64-1.25	3rd
TD-307	Tertiary Drain	315.59	2.5-3.5	0.64-1.25	3rd
TD-308	Tertiary Drain	735.67	2.5-3.5	0.64-1.25	3rd
TD-309	Tertiary Drain	90.27	2.5-3.5	0.64-1.25	3rd
TD-310	Tertiary Drain	239.52	2.5-3.5	0.64-1.25	3rd
TD-311	Tertiary Drain	57.37	2.5-3.5	0.64-1.25	3rd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-312	Tertiary Drain	81.91	2.5-3.5	0.64-1.25	3rd
TD-313	Tertiary Drain	81.29	2.5-3.5	0.64-1.25	3rd
TD-314	Tertiary Drain	69.58	2.5-3.5	0.64-1.25	3rd
TD-315	Tertiary Drain	91.49	2.5-3.5	0.64-1.25	3rd
TD-316	Tertiary Drain	151.52	2.5-3.5	0.64-1.25	3rd
TD-317	Tertiary Drain	460.19	2.5-3.5	0.64-1.25	3rd
TD-318	Tertiary Drain	278.76	2.5-3.5	0.64-1.25	3rd
TD-320	Tertiary Drain	209.87	2.5-3.5	0.64-1.25	3rd
TD-321	Tertiary Drain	14.98	2.5-3.5	0.64-1.25	3rd
TD-322	Tertiary Drain	291.92	2.5-3.5	0.64-1.25	3rd
TD-323	Tertiary Drain	73.75	2.5-3.5	0.64-1.25	3rd
TD-324	Tertiary Drain	70.79	2.5-3.5	0.64-1.25	3rd
TD-325	Tertiary Drain	78.42	2.5-3.5	0.64-1.25	3rd
TD-326	Tertiary Drain	209.51	2.5-3.5	0.64-1.25	3rd
TD-327	Tertiary Drain	97.64	2.5-3.5	0.64-1.25	3rd
TD-328	Tertiary Drain	105.85	2.5-3.5	0.64-1.25	3rd
TD-329	Tertiary Drain	220.11	2.5-3.5	0.64-1.25	3rd
TD-330	Tertiary Drain	66.56	2.5-3.5	0.64-1.25	3rd
TD-332	Tertiary Drain	283.13	2.5-3.5	0.64-1.25	3rd
TD-333	Tertiary Drain	118.86	2.5-3.5	0.64-1.25	3rd
TD-334	Tertiary Drain	308.83	2.5-3.5	0.64-1.25	3rd
TD-335	Tertiary Drain	123.93	2.5-3.5	0.64-1.25	3rd
TD-336	Tertiary Drain	127.38	2.5-3.5	0.64-1.25	3rd
TD-337	Tertiary Drain	25.35	2.5-3.5	0.64-1.25	3rd
TD-339	Tertiary Drain	77.32	2.5-3.5	0.64-1.25	3rd
TD-340	Tertiary Drain	107.78	2.5-3.5	0.64-1.25	3rd
TD-341	Tertiary Drain	917.50	2.5-3.5	0.64-1.25	3rd
TD-343	Tertiary Drain	5.94	2.5-3.5	0.64-1.25	3rd
TD-343	Tertiary Drain	1399.69	2.5-3.5	0.64-1.25	3rd
TD-344	Tertiary Drain	26.24	2.5-3.5	0.64-1.25	3rd
TD-345	Tertiary Drain	251.58	2.5-3.5	0.64-1.25	3rd
TD-346	Tertiary Drain	178.40	2.5-3.5	0.64-1.25	3rd
TD-347	Tertiary Drain	831.83	2.5-3.5	0.64-1.25	3rd
TD-348	Tertiary Drain	123.80	2.5-3.5	0.64-1.25	3rd
TD-349	Tertiary Drain	277.06	2.5-3.5	0.64-1.25	3rd
TD-350	Tertiary Drain	94.86	2.5-3.5	0.64-1.25	3rd
TD-351	Tertiary Drain	319.50	2.5-3.5	0.64-1.25	3rd
TD-351	Tertiary Drain	246.77	2.5-3.5	0.64-1.25	3rd
TD-352	Tertiary Drain	590.84	2.5-3.5	0.64-1.25	3rd
TD-353	Tertiary Drain	174.65	2.5-3.5	0.64-1.25	3rd
TD-354	Tertiary Drain	191.58	2.5-3.5	0.64-1.25	3rd
TD-355	Tertiary Drain	38.46	2.5-3.5	0.64-1.25	3rd
TD-356	Tertiary Drain	154.99	2.5-3.5	0.64-1.25	3rd
TD-357	Tertiary Drain	1177.09	2.5-3.5	0.64-1.25	3rd
TD-358	Tertiary Drain	181.55	2.5-3.5	0.64-1.25	3rd
TD-359	Tertiary Drain	24.70	2.5-3.5	0.64-1.25	3rd
TD-360	Tertiary Drain	75.36	2.5-3.5	0.64-1.25	3rd
TD-362	Tertiary Drain	175.95	2.5-3.5	0.64-1.25	3rd
TD-362	Tertiary Drain	70.82	2.5-3.5	0.64-1.25	3rd
TD-363	Tertiary Drain	121.16	2.5-3.5	0.64-1.25	3rd
TD-364	Tertiary Drain	86.10	2.5-3.5	0.64-1.25	3rd
TD-366	Tertiary Drain	62.41	2.5-3.5	0.64-1.25	3rd
TD-367	Tertiary Drain	126.62	2.5-3.5	0.64-1.25	3rd
TD-368	Tertiary Drain	152.98	2.5-3.5	0.64-1.25	3rd
TD-369	Tertiary Drain	30.85	2.5-3.5	0.64-1.25	3rd
TD-372	Tertiary Drain	686.97	2.5-3.5	0.64-1.25	3rd
TD-373	Tertiary Drain	52.95	2.5-3.5	0.64-1.25	3rd
TD-374	Tertiary Drain	72.31	2.5-3.5	0.64-1.25	3rd
TD-375	Tertiary Drain	208.83	2.5-3.5	0.64-1.25	3rd
TD-376	Tertiary Drain	171.33	2.5-3.5	0.64-1.25	3rd
TD-377	Tertiary Drain	166.22	2.5-3.5	0.64-1.25	3rd
TD-378	Tertiary Drain	25.54	2.5-3.5	0.64-1.25	3rd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-380	Tertiary Drain	1.05	2.5-3.5	0.64-1.25	3rd
TD-382	Tertiary Drain	65.28	2.5-3.5	0.64-1.25	3rd
TD-383	Tertiary Drain	25.30	2.5-3.5	0.64-1.25	3rd
TD-384	Tertiary Drain	199.49	2.5-3.5	0.64-1.25	3rd
TD-386	Tertiary Drain	34.10	2.5-3.5	0.64-1.25	3rd
TD-387	Tertiary Drain	12.17	2.5-3.5	0.64-1.25	3rd
TD-388	Tertiary Drain	181.41	2.5-3.5	0.64-1.25	3rd
TD-389	Tertiary Drain	163.52	2.5-3.5	0.64-1.25	3rd
TD-390	Tertiary Drain	42.86	2.5-3.5	0.64-1.25	3rd
TD-391	Tertiary Drain	669.92	2.5-3.5	0.64-1.25	3rd
TD-394	Tertiary Drain	215.26	2.5-3.5	0.64-1.25	3rd
TD-395	Tertiary Drain	50.57	2.5-3.5	0.64-1.25	3rd
TD-396	Tertiary Drain	165.23	2.5-3.5	0.64-1.25	3rd
TD-398	Tertiary Drain	9.29	2.5-3.5	0.64-1.25	3rd
TD-399	Tertiary Drain	0.09	2.5-3.5	0.64-1.25	3rd
TD-400	Tertiary Drain	0.01	2.5-3.5	0.64-1.25	3rd
TD-401	Tertiary Drain	816.14	2.5-3.5	0.64-1.25	3rd
TD-402	Tertiary Drain	208.90	2.5-3.5	0.64-1.25	3rd
TD-402	Tertiary Drain	192.79	2.5-3.5	0.64-1.25	3rd
TD-403	Tertiary Drain	834.28	2.5-3.5	0.64-1.25	3rd
TD-404	Tertiary Drain	275.65	2.5-3.5	0.64-1.25	3rd
TD-406	Tertiary Drain	298.19	2.5-3.5	0.64-1.25	3rd
TD-407	Tertiary Drain	71.22	2.5-3.5	0.64-1.25	3rd
TD-408	Tertiary Drain	176.23	2.5-3.5	0.64-1.25	3rd
TD-409	Tertiary Drain	539.57	2.5-3.5	0.64-1.25	3rd
TD-411	Tertiary Drain	0.05	2.5-3.5	0.64-1.25	3rd
TD-412	Tertiary Drain	213.69	2.5-3.5	0.64-1.25	3rd
TD-413	Tertiary Drain	261.50	2.5-3.5	0.64-1.25	3rd
TD-415	Tertiary Drain	423.82	2.5-3.5	0.64-1.25	3rd
TD-416	Tertiary Drain	59.88	2.5-3.5	0.64-1.25	3rd
TD-417	Tertiary Drain	1.83	2.5-3.5	0.64-1.25	3rd
TD-418	Tertiary Drain	1.09	2.5-3.5	0.64-1.25	3rd
TD-418	Tertiary Drain	143.71	2.5-3.5	0.64-1.25	3rd
TD-419	Tertiary Drain	165.91	2.5-3.5	0.64-1.25	3rd
TD-420	Tertiary Drain	141.48	2.5-3.5	0.64-1.25	3rd
TD-421	Tertiary Drain	93.57	2.5-3.5	0.64-1.25	3rd
TD-424	Tertiary Drain	69.25	2.5-3.5	0.64-1.25	3rd
TD-426	Tertiary Drain	4.39	2.5-3.5	0.64-1.25	3rd
TD-427	Tertiary Drain	61.85	2.5-3.5	0.64-1.25	3rd
TD-428	Tertiary Drain	58.12	2.5-3.5	0.64-1.25	3rd
TD-429	Tertiary Drain	53.64	2.5-3.5	0.64-1.25	3rd
TD-430	Tertiary Drain	52.59	2.5-3.5	0.64-1.25	3rd
TD-433	Tertiary Drain	207.92	2.5-3.5	0.64-1.25	3rd
TD-436	Tertiary Drain	236.82	2.5-3.5	0.64-1.25	3rd
TD-437	Tertiary Drain	1.82	2.5-3.5	0.64-1.25	3rd
TD-438	Tertiary Drain	54.29	2.5-3.5	0.64-1.25	3rd
TD-439	Tertiary Drain	3.27	2.5-3.5	0.64-1.25	3rd
TD-440	Tertiary Drain	5.76	2.5-3.5	0.64-1.25	3rd
TD-442	Tertiary Drain	305.67	2.5-3.5	0.64-1.25	3rd
TD-443	Tertiary Drain	5.71	2.5-3.5	0.64-1.25	3rd
TD-444	Tertiary Drain	234.91	2.5-3.5	0.64-1.25	3rd
TD-446	Tertiary Drain	0.96	2.5-3.5	0.64-1.25	3rd
TD-447	Tertiary Drain	607.46	2.5-3.5	0.64-1.25	3rd
TD-448	Tertiary Drain	462.42	2.5-3.5	0.64-1.25	3rd
TD-449	Tertiary Drain	248.96	2.5-3.5	0.64-1.25	3rd
TD-450	Tertiary Drain	616.10	2.5-3.5	0.64-1.25	3rd
TD-451	Tertiary Drain	79.38	2.5-3.5	0.64-1.25	3rd
TD-452	Tertiary Drain	198.04	2.5-3.5	0.64-1.25	3rd
TD-454	Tertiary Drain	135.64	2.5-3.5	0.64-1.25	3rd
TD-455	Tertiary Drain	384.86	2.5-3.5	0.64-1.25	3rd
TD-457	Tertiary Drain	452.63	2.5-3.5	0.64-1.25	3rd
TD-458	Tertiary Drain	254.50	2.5-3.5	0.64-1.25	3rd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-459	Tertiary Drain	51.86	2.5-3.5	0.64-1.25	3rd
TD-460	Tertiary Drain	188.03	2.5-3.5	0.64-1.25	3rd
TD-461	Tertiary Drain	76.78	2.5-3.5	0.64-1.25	3rd
TD-462	Tertiary Drain	0.32	2.5-3.5	0.64-1.25	3rd
TD-464	Tertiary Drain	158.48	2.5-3.5	0.64-1.25	3rd
TD-465	Tertiary Drain	29.39	2.5-3.5	0.64-1.25	3rd
TD-466	Tertiary Drain	78.98	2.5-3.5	0.64-1.25	3rd
TD-467	Tertiary Drain	50.29	2.5-3.5	0.64-1.25	3rd
TD-468	Tertiary Drain	849.60	2.5-3.5	0.64-1.25	3rd
TD-470	Tertiary Drain	278.46	2.5-3.5	0.64-1.25	3rd
TD-471	Tertiary Drain	459.11	2.5-3.5	0.64-1.25	3rd
TD-472	Tertiary Drain	47.14	2.5-3.5	0.64-1.25	3rd
TD-473	Tertiary Drain	263.14	2.5-3.5	0.64-1.25	3rd
TD-475	Tertiary Drain	144.81	2.5-3.5	0.64-1.25	3rd
TD-476	Tertiary Drain	285.07	2.5-3.5	0.64-1.25	3rd
TD-478	Tertiary Drain	79.60	2.5-3.5	0.64-1.25	3rd
TD-479	Tertiary Drain	216.67	2.5-3.5	0.64-1.25	3rd
TD-480	Tertiary Drain	583.55	2.5-3.5	0.64-1.25	3rd
TD-481	Tertiary Drain	461.57	2.5-3.5	0.64-1.25	3rd
TD-483	Tertiary Drain	336.59	2.5-3.5	0.64-1.25	3rd
TD-484	Tertiary Drain	196.66	2.5-3.5	0.64-1.25	3rd
TD-485	Tertiary Drain	193.52	2.5-3.5	0.64-1.25	3rd
TD-486	Tertiary Drain	48.29	2.5-3.5	0.64-1.25	3rd
TD-487	Tertiary Drain	65.13	2.5-3.5	0.64-1.25	3rd
TD-488	Tertiary Drain	13.63	2.5-3.5	0.64-1.25	3rd
TD-489	Tertiary Drain	3.21	2.5-3.5	0.64-1.25	3rd
TD-492	Tertiary Drain	82.46	2.5-3.5	0.64-1.25	3rd
TD-493	Tertiary Drain	1.34	2.5-3.5	0.64-1.25	3rd
TD-494	Tertiary Drain	230.34	2.5-3.5	0.64-1.25	3rd
TD-495	Tertiary Drain	290.93	2.5-3.5	0.64-1.25	3rd
TD-496	Tertiary Drain	318.76	2.5-3.5	0.64-1.25	3rd
TD-496	Tertiary Drain	0.96	2.5-3.5	0.64-1.25	3rd
TD-497	Tertiary Drain	161.23	2.5-3.5	0.64-1.25	3rd
TD-499	Tertiary Drain	45.04	2.5-3.5	0.64-1.25	3rd
TD-500	Tertiary Drain	862.12	2.5-3.5	0.64-1.25	3rd
TD-500	Tertiary Drain	98.62	2.5-3.5	0.64-1.25	3rd
TD-503	Tertiary Drain	57.21	2.5-3.5	0.64-1.25	3rd
TD-504	Tertiary Drain	432.64	2.5-3.5	0.64-1.25	3rd
TD-505	Tertiary Drain	662.54	2.5-3.5	0.64-1.25	3rd
TD-507	Tertiary Drain	469.36	2.5-3.5	0.64-1.25	3rd
TD-508	Tertiary Drain	119.73	2.5-3.5	0.64-1.25	3rd
TD-509	Tertiary Drain	191.96	2.5-3.5	0.64-1.25	3rd
TD-510	Tertiary Drain	215.86	2.5-3.5	0.64-1.25	3rd
TD-511	Tertiary Drain	191.76	2.5-3.5	0.64-1.25	3rd
TD-512	Tertiary Drain	77.27	2.5-3.5	0.64-1.25	3rd
TD-513	Tertiary Drain	214.31	2.5-3.5	0.64-1.25	3rd
TD-514	Tertiary Drain	279.81	2.5-3.5	0.64-1.25	3rd
TD-515	Tertiary Drain	131.20	2.5-3.5	0.64-1.25	3rd
TD-516	Tertiary Drain	71.61	2.5-3.5	0.64-1.25	3rd
TD-519	Tertiary Drain	368.17	2.5-3.5	0.64-1.25	3rd
TD-520	Tertiary Drain	389.05	2.5-3.5	0.64-1.25	3rd
TD-521	Tertiary Drain	90.24	2.5-3.5	0.64-1.25	3rd
TD-522	Tertiary Drain	45.01	2.5-3.5	0.64-1.25	3rd
TD-523	Tertiary Drain	92.06	2.5-3.5	0.64-1.25	3rd
TD-524	Tertiary Drain	450.70	2.5-3.5	0.64-1.25	3rd
TD-527	Tertiary Drain	328.44	2.5-3.5	0.64-1.25	3rd
TD-528	Tertiary Drain	505.61	2.5-3.5	0.64-1.25	3rd
TD-529	Tertiary Drain	455.72	2.5-3.5	0.64-1.25	3rd
TD-531	Tertiary Drain	57.04	2.5-3.5	0.64-1.25	3rd
TD-532	Tertiary Drain	113.09	2.5-3.5	0.64-1.25	3rd
TD-533	Tertiary Drain	2.27	2.5-3.5	0.64-1.25	3rd
TD-534	Tertiary Drain	478.53	2.5-3.5	0.64-1.25	3rd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-536	Tertiary Drain	198.92	2.5-3.5	0.64-1.25	3rd
TD-538	Tertiary Drain	85.53	2.5-3.5	0.64-1.25	3rd
TD-539	Tertiary Drain	4.60	2.5-3.5	0.64-1.25	3rd
TD-541	Tertiary Drain	48.70	2.5-3.5	0.64-1.25	3rd
TD-542	Tertiary Drain	214.78	2.5-3.5	0.64-1.25	3rd
TD-543	Tertiary Drain	25.17	2.5-3.5	0.64-1.25	3rd
TD-543	Tertiary Drain	149.69	2.5-3.5	0.64-1.25	3rd
TD-544	Tertiary Drain	297.68	2.5-3.5	0.64-1.25	3rd
TD-547	Tertiary Drain	4.04	2.5-3.5	0.64-1.25	3rd
TD-548	Tertiary Drain	87.30	2.5-3.5	0.64-1.25	3rd
TD-550	Tertiary Drain	1065.61	2.5-3.5	0.64-1.25	3rd
TD-551	Tertiary Drain	216.15	2.5-3.5	0.64-1.25	3rd
TD-552	Tertiary Drain	47.81	2.5-3.5	0.64-1.25	3rd
TD-553	Tertiary Drain	292.73	2.5-3.5	0.64-1.25	3rd
TD-555	Tertiary Drain	922.48	2.5-3.5	0.64-1.25	3rd
TD-556	Tertiary Drain	34.32	2.5-3.5	0.64-1.25	3rd
TD-558	Tertiary Drain	37.04	2.5-3.5	0.64-1.25	3rd
TD-559	Tertiary Drain	170.61	2.5-3.5	0.64-1.25	3rd
TD-561	Tertiary Drain	99.19	2.5-3.5	0.64-1.25	3rd
TD-562	Tertiary Drain	9.08	2.5-3.5	0.64-1.25	3rd
TD-563	Tertiary Drain	53.94	2.5-3.5	0.64-1.25	3rd
TD-564	Tertiary Drain	82.52	2.5-3.5	0.64-1.25	3rd
TD-565	Tertiary Drain	320.86	2.5-3.5	0.64-1.25	3rd
TD-566	Tertiary Drain	890.42	2.5-3.5	0.64-1.25	3rd
TD-568	Tertiary Drain	12.62	2.5-3.5	0.64-1.25	3rd
TD-569	Tertiary Drain	36.16	2.5-3.5	0.64-1.25	3rd
TD-570	Tertiary Drain	97.77	2.5-3.5	0.64-1.25	3rd
TD-571	Tertiary Drain	125.86	2.5-3.5	0.64-1.25	3rd
TD-572	Tertiary Drain	473.30	2.5-3.5	0.64-1.25	3rd
TD-574	Tertiary Drain	275.01	2.5-3.5	0.64-1.25	3rd
TD-575	Tertiary Drain	0.01	2.5-3.5	0.64-1.25	3rd
TD-576	Tertiary Drain	413.19	2.5-3.5	0.64-1.25	3rd
TD-577	Tertiary Drain	159.27	2.5-3.5	0.64-1.25	3rd
TD-578	Tertiary Drain	85.85	2.5-3.5	0.64-1.25	3rd
TD-580	Tertiary Drain	49.92	2.5-3.5	0.64-1.25	3rd
TD-581	Tertiary Drain	115.82	2.5-3.5	0.64-1.25	3rd
TD-583	Tertiary Drain	108.95	2.5-3.5	0.64-1.25	3rd
TD-584	Tertiary Drain	44.97	2.5-3.5	0.64-1.25	3rd
TD-585	Tertiary Drain	24.20	2.5-3.5	0.64-1.25	3rd
TD-586	Tertiary Drain	232.12	2.5-3.5	0.64-1.25	3rd
TD-587	Tertiary Drain	200.92	2.5-3.5	0.64-1.25	3rd
TD-588	Tertiary Drain	289.48	2.5-3.5	0.64-1.25	3rd
TD-590	Tertiary Drain	535.33	2.5-3.5	0.64-1.25	3rd
TD-592	Tertiary Drain	279.30	2.5-3.5	0.64-1.25	3rd
TD-593	Tertiary Drain	9.98	2.5-3.5	0.64-1.25	3rd
TD-594	Tertiary Drain	69.63	2.5-3.5	0.64-1.25	3rd
TD-598	Tertiary Drain	42.12	2.5-3.5	0.64-1.25	3rd
TD-599	Tertiary Drain	68.98	2.5-3.5	0.64-1.25	3rd
TD-600	Tertiary Drain	40.63	2.5-3.5	0.64-1.25	3rd
TD-603	Tertiary Drain	270.77	2.5-3.5	0.64-1.25	3rd
TD-634	Tertiary Drain	499.50	2.5-3.5	0.64-1.25	3rd
TD-635	Tertiary Drain	387.78	2.5-3.5	0.64-1.25	3rd
TD-636	Tertiary Drain	97.72	2.5-3.5	0.64-1.25	3rd
TD-637	Tertiary Drain	361.28	2.5-3.5	0.64-1.25	3rd
TD-638	Tertiary Drain	201.30	2.5-3.5	0.64-1.25	3rd
TD-639	Tertiary Drain	293.63	2.5-3.5	0.64-1.25	3rd
TD-640	Tertiary Drain	235.72	2.5-3.5	0.64-1.25	3rd
TD-641	Tertiary Drain	517.97	2.5-3.5	0.64-1.25	3rd
TD-642	Tertiary Drain	159.94	2.5-3.5	0.64-1.25	3rd
TD-643	Tertiary Drain	186.25	2.5-3.5	0.64-1.25	3rd
TD-643	Tertiary Drain	97.08	2.5-3.5	0.64-1.25	3rd
TD-644	Tertiary Drain	324.26	2.5-3.5	0.64-1.25	3rd


Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-645	Tertiary Drain	842.94	2.5-3.5	0.64-1.25	3rd
TD-646	Tertiary Drain	280.71	2.5-3.5	0.64-1.25	3rd
TD-647	Tertiary Drain	119.08	2.5-3.5	0.64-1.25	3rd
TD-648	Tertiary Drain	6.39	2.5-3.5	0.64-1.25	3rd
TD-649	Tertiary Drain	146.00	2.5-3.5	0.64-1.25	3rd
TD-650	Tertiary Drain	243.74	2.5-3.5	0.64-1.25	3rd
TD-651	Tertiary Drain	332.68	2.5-3.5	0.64-1.25	3rd
TD-652	Tertiary Drain	164.64	2.5-3.5	0.64-1.25	3rd
TD-653	Tertiary Drain	254.03	2.5-3.5	0.64-1.25	3rd
TD-654	Tertiary Drain	188.06	2.5-3.5	0.64-1.25	3rd
TD-655	Tertiary Drain	355.26	2.5-3.5	0.64-1.25	3rd
TD-656	Tertiary Drain	374.48	2.5-3.5	0.64-1.25	3rd
TD-657	Tertiary Drain	163.20	2.5-3.5	0.64-1.25	3rd
TD-658	Tertiary Drain	494.62	2.5-3.5	0.64-1.25	3rd
TD-659	Tertiary Drain	626.70	2.5-3.5	0.64-1.25	3rd
TD-660	Tertiary Drain	321.37	2.5-3.5	0.64-1.25	3rd
TD-660	Tertiary Drain	85.60	2.5-3.5	0.64-1.25	3rd
TD-661	Tertiary Drain	263.38	2.5-3.5	0.64-1.25	3rd
TD-662	Tertiary Drain	136.47	2.5-3.5	0.64-1.25	3rd
TD-663	Tertiary Drain	206.35	2.5-3.5	0.64-1.25	3rd
TD-664	Tertiary Drain	471.19	2.5-3.5	0.64-1.25	3rd
TD-665	Tertiary Drain	1192.89	2.5-3.5	0.64-1.25	3rd
TD-666	Tertiary Drain	246.89	2.5-3.5	0.64-1.25	3rd
TD-666	Tertiary Drain	69.41	2.5-3.5	0.64-1.25	3rd
TD-667	Tertiary Drain	505.58	2.5-3.5	0.64-1.25	3rd
TD-668	Tertiary Drain	193.87	2.5-3.5	0.64-1.25	3rd
TD-669	Tertiary Drain	104.13	2.5-3.5	0.64-1.25	3rd
TD-670	Tertiary Drain	654.49	2.5-3.5	0.64-1.25	3rd
TD-671	Tertiary Drain	328.79	2.5-3.5	0.64-1.25	3rd
TD-672	Tertiary Drain	153.84	2.5-3.5	0.64-1.25	3rd
TD-673	Tertiary Drain	317.76	2.5-3.5	0.64-1.25	3rd
TD-674	Tertiary Drain	140.83	2.5-3.5	0.64-1.25	3rd
TD-675	Tertiary Drain	37.17	2.5-3.5	0.64-1.25	3rd
TD-676	Tertiary Drain	43.24	2.5-3.5	0.64-1.25	3rd
TD-677	Tertiary Drain	16.87	2.5-3.5	0.64-1.25	3rd
TD-678	Tertiary Drain	64.64	2.5-3.5	0.64-1.25	3rd
TD-679	Tertiary Drain	79.67	2.5-3.5	0.64-1.25	3rd
TD-680	Tertiary Drain	192.05	2.5-3.5	0.64-1.25	3rd
TD-681	Tertiary Drain	358.54	2.5-3.5	0.64-1.25	3rd
TD-682	Tertiary Drain	791.96	2.5-3.5	0.64-1.25	3rd
TD-683	Tertiary Drain	319.87	2.5-3.5	0.64-1.25	3rd
TD-684	Tertiary Drain	231.18	2.5-3.5	0.64-1.25	3rd
TD-685	Tertiary Drain	623.30	2.5-3.5	0.64-1.25	3rd
TD-686	Tertiary Drain	431.39	2.5-3.5	0.64-1.25	3rd
TD-687	Tertiary Drain	566.38	2.5-3.5	0.64-1.25	3rd
TD-688	Tertiary Drain	1281.12	2.5-3.5	0.64-1.25	3rd
TD-689	Tertiary Drain	284.19	2.5-3.5	0.64-1.25	3rd
TD-689	Tertiary Drain	778.21	2.5-3.5	0.64-1.25	3rd
TD-690	Tertiary Drain	488.43	2.5-3.5	0.64-1.25	3rd
TD-691	Tertiary Drain	81.51	2.5-3.5	0.64-1.25	3rd
TD-692	Tertiary Drain	1166.27	2.5-3.5	0.64-1.25	3rd
TD-692	Tertiary Drain	43.11	2.5-3.5	0.64-1.25	3rd
TD-693	Tertiary Drain	326.50	2.5-3.5	0.64-1.25	3rd
TD-694	Tertiary Drain	420.54	2.5-3.5	0.64-1.25	3rd
TD-695	Tertiary Drain	249.27	2.5-3.5	0.64-1.25	3rd
TD-696	Tertiary Drain	113.79	2.5-3.5	0.64-1.25	3rd
TD-697	Tertiary Drain	289.58	2.5-3.5	0.64-1.25	3rd
TD-697	Tertiary Drain	188.44	2.5-3.5	0.64-1.25	3rd
TD-698	Tertiary Drain	292.63	2.5-3.5	0.64-1.25	3rd
TD-699	Tertiary Drain	531.27	2.5-3.5	0.64-1.25	3rd
TD-699	Tertiary Drain	393.66	2.5-3.5	0.64-1.25	3rd
TD-700	Tertiary Drain	406.69	2.5-3.5	0.64-1.25	3rd

Drain_ID	Drain Type	Length (in m)	Width (in ft)	Depth (in m)	Phase
TD-701	Tertiary Drain	332.70	2.5-3.5	0.64-1.25	3rd
TD-702	Tertiary Drain	281.17	2.5-3.5	0.64-1.25	3rd
TD-703	Tertiary Drain	276.36	2.5-3.5	0.64-1.25	3rd
TD-704	Tertiary Drain	593.23	2.5-3.5	0.64-1.25	3rd
TD-705	Tertiary Drain	220.03	2.5-3.5	0.64-1.25	3rd
TD-706	Tertiary Drain	5.23	2.5-3.5	0.64-1.25	3rd
TD-706	Tertiary Drain	36.51	2.5-3.5	0.64-1.25	3rd
TD-707	Tertiary Drain	424.59	2.5-3.5	0.64-1.25	3rd
TD-708	Tertiary Drain	66.23	2.5-3.5	0.64-1.25	3rd
TD-709	Tertiary Drain	8.38	2.5-3.5	0.64-1.25	3rd
TD-710	Tertiary Drain	129.64	2.5-3.5	0.64-1.25	3rd
TD-711	Tertiary Drain	105.50	2.5-3.5	0.64-1.25	3rd
TD-712	Tertiary Drain	1384.41	2.5-3.5	0.64-1.25	3rd
TD-713	Tertiary Drain	4.57	2.5-3.5	0.64-1.25	3rd
TD-714	Tertiary Drain	27.03	2.5-3.5	0.64-1.25	3rd
TD-715	Tertiary Drain	7.63	2.5-3.5	0.64-1.25	3rd
TD-716	Tertiary Drain	213.92	2.5-3.5	0.64-1.25	3rd
TD-716	Tertiary Drain	236.49	2.5-3.5	0.64-1.25	3rd
TD-717	Tertiary Drain	76.13	2.5-3.5	0.64-1.25	3rd
TD-718	Tertiary Drain	29.69	2.5-3.5	0.64-1.25	3rd
TD-719	Tertiary Drain	3.38	2.5-3.5	0.64-1.25	3rd
TD-720	Tertiary Drain	517.43	2.5-3.5	0.64-1.25	3rd
TD-721	Tertiary Drain	103.75	2.5-3.5	0.64-1.25	3rd
TD-722	Tertiary Drain	343.09	2.5-3.5	0.64-1.25	3rd
TD-723	Tertiary Drain	203.39	2.5-3.5	0.64-1.25	3rd
TD-724	Tertiary Drain	209.25	2.5-3.5	0.64-1.25	3rd
TD-725	Tertiary Drain	169.83	2.5-3.5	0.64-1.25	3rd
TD-726	Tertiary Drain	963.82	2.5-3.5	0.64-1.25	3rd
TD-727	Tertiary Drain	8.20	2.5-3.5	0.64-1.25	3rd
TD-728	Tertiary Drain	20.05	2.5-3.5	0.64-1.25	3rd
TD-729	Tertiary Drain	186.76	2.5-3.5	0.64-1.25	3rd
TD-730	Tertiary Drain	0.66	2.5-3.5	0.64-1.25	3rd
TD-731	Tertiary Drain	335.65	2.5-3.5	0.64-1.25	3rd
TD-732	Tertiary Drain	1.86	2.5-3.5	0.64-1.25	3rd
TD-733	Tertiary Drain	212.17	2.5-3.5	0.64-1.25	3rd
TD-734	Tertiary Drain	30.09	2.5-3.5	0.64-1.25	3rd
TD-735	Tertiary Drain	88.41	2.5-3.5	0.64-1.25	3rd
TD-736	Tertiary Drain	152.70	2.5-3.5	0.64-1.25	3rd
TD-737	Tertiary Drain	268.81	2.5-3.5	0.64-1.25	3rd
TD-601	Tertiary Drain	19.10	2.5-3.5	0.64-1.25	3rd
TD-601	Tertiary Drain	19.10	2.5-3.5	0.64-1.25	3rd
TD-607	Tertiary Drain	16.30	2.5-3.5	0.64-1.25	3rd
TD-607	Tertiary Drain	16.30	2.5-3.5	0.64-1.25	3rd

13.3.3.2 List of Infrastructure measures for Drainage and Flood Control Network

Total 27 bridges and 112 culverts will be established for drainage and flood control network of Gauranadi Paurashava.

Map 13.2:Drainage & Environment Management Plan of Gauranadi Paurashava



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall
- Waterbody

0 195390 780 1,170 1,560 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

13.4 Implementation Strategies and Principles

13.4.1 Plan Implementation Strategies

Management of a drainage system is more difficult than its construction. It requires not only an institutional set up but also huge resources for regular maintenance. The present engineering set up of the Paurashava is highly inadequate to manage the future drainage network. It must be equipped not only with adequate manpower but also sufficient number of logistics and equipment will be necessary for sound maintenance of the drainage system. For Gauranadi Pourashava with its meager revenue earning it will be extremely difficult to go for regular maintenance of the drainage system without government assistance. So, the Paurashava must be provided with sufficient budget allocation to maintenance going on regularly. The next strategy will be to create awareness among the citizens not to dispose of solid waste in the drains and get them clogged. This can be done by regular publicity, engaging NGOs for motivation and the last imposing punitive measures like, fine on the waste disposer.

13.4.2 Regulations to implement the drainage and flood plan

Regulations in Bangladesh which are related to drainage and flood management:

1. **The Acquisition and Requisition of Immovable Property Ordinance, 1982,** for acquisition of land to construct drainage and flood control structures. The Bangladesh Water Development Board is main executing organization to implement drainage and flood control activities.
2. **National Water Policy (NWP)-1999,** regulatory policy to construct structures for flood control and drainage management. The Bangladesh Water Development Board is the executing and regulatory organization.
3. **National Water Management Plan (NWMP)-2004,** regulatory plan for management of flood, drainage and water resources of Bangladesh. The Bangladesh Water Development Board is the executing and regulatory organization. Local Government Engineering Department (LGED) is responsible for management of small scale water resources in Bangladesh.
4. **Canal and Drainage Act, 1872** has enacted for excavation of canal and removal of drainage congestion from agriculture land.
5. **Public Health (Emergency Provision) Ordinance, 1944** has enacted for the improvement of drainage and sanitation facilities. Department of Public Health Engineering (DPHE) is authorized to enforce the regulations.
6. **Water Body Reservoir Act 2000** has enacted for the provision to control the illegal development activities on natural water body of Metropolitan city, Divisional town, District town and all other Paurashava area. The act also enacts that Natural Streams (River, khal, Beel, Large pond/ Lake, Waterfall or water bodies which is identified in Master Plan or any place as flood flow area, rain water or other natural drainage water reservoir area proclaimed by Government, Local Government or any organization

13.5 Environmental Management Plan

13.5.1 Introduction

Environment is an important consideration during preparation of a Master Plan of an area. During the preparation of Master Plan of Gauranadi Paurashava, different environmental issues have been analyzed and information has been collected accordingly. Information on drainage, sewerage (location/network, condition) and solid waste management system (existing and proposed plan), pollution sources and types also have been analyzed.

13.5.2 Goals and Objectives

The objectives of environmental study are as follows:

- to study the existing ecological system and environmental problems in the project area;
- to suggest the mitigation measures for all environmental problems;
- to provide the guidelines and assist the planners, engineers and consultants involved in this
- project in preparing environmentally sound Plan for Gauranadi Town and
- to prepare an Environmental Management Plan (EMP) for future environmental management in the area.

13.5.3 Methodology and Approach to Planning

In environmental study, a multi-disciplinary approach is used for studying development project. The present environmental study is based on data collection and sharing with drainage and geology, transport engineering, socio-economic, economic and topographical survey components. A structured questionnaire prepared by LGED for environmental survey has been followed. Environmental study has been carried out through survey of biodiversity of flora and fauna, water pollution, local air pollution problem, drinking water sources, renewable energy, diseases, and major local environmental issues as well as secondary data has been considered.

13.5.4 Existing Environmental Condition

13.5.4.1 Geo-morphology Geology, Soil, Sub soil Condition

Gaurnadi Paurashava has five main types of soils with different qualities such as non-calcareous alluvium, peat, non-calcareous and calcareous grey floodplain and non-calcareous dark grey floodplain soils. Non-calcareous alluvium soils are raw sandy and silty alluvial deposits and generally neutral to alkaline in reaction. Peat soils are highly organic dark colored soils. Non-calcareous grey floodplain soils are prismatic and/or blocky structured whereas calcareous grey floodplain soils are structured grey silt loams to silty clays, calcareous from the surface or at shallow depths. Generally non-calcareous dark grey floodplain soils are structured dark grey loamy soils on old flood plain ridges and clay in basins. The basin clays have heavy consistence. However, soil condition of Gaurnadi Paurashava comprises diversified characteristics.

13.5.4.2 Climate

The Climate of an area is comprised of its Temperature, Average Humidity (%), Rainfall, Wind Speed and Hydrology. This zila bears a hot summer and a mild winter. But almost all the area of the zila is occasionally affected by cyclonic storm surges and tidal bores that originate over the Bay of Bengal during monsoon.

13.5.4.3 Temperature

Temperature rises steadily from January to April, remains fairly steady from April to October and then falls to reach the lowest in January. The maximum average monthly temperature is 29.5^{o}c in August and minimum average monthly temperature is 7.4 ^{o} C in January. The monsoon starts from June and maximum rainfall is experienced from July to September.

13.5.4.4 Humidity

Weather of Gaurnadi Planning area is not more contradictory from the natural weather of Bangladesh. Due to coastal characteristics, weather of this area has few special characteristics. Humidity is comparatively high in the coastal region rather than other districts of Bangladesh.

13.5.4.5 Rainfall

The monsoon starts from June and maximum rainfall is experienced in 2004 and lowest in 2003. Annual rainfall as recorded from 2003 to 2010, maximum was 180.72 mm in 2004 and lowest 122.04 mm in 2003. It is recorded that during June to October there are high volume of rainfall.

13.5.4.6 Wind directions

Monthly Prevailing Wind speed in knots and direction of Gauranadi Planning area for the years of 1977 to 2007 has been presented below in Figure 13.8. It shows that wind direction in is mainly towards south and most of the time wind is calm (61.5 %) which is followed by 1-2.5 m/s wind speed (21.9%) and 2.5-5 m/s wind speed (14.7%).






Fig 13.8: Wind Speed Data of Several Years in Barisal.
Source: Bangladesh Metrological Department, 2011.

13.5.4.7 Hydrology

Hydrology can be defined as the scientific study of the waters of the earth, especially with relation to the effects of precipitation and evaporation upon the occurrence and character of water in streams, lakes, and on or below the land surface. The hydrological condition of Gauranadi Planning area is getting of inferior quality day by day.








Fig 13.9: Cyclone, Flood and Earthquake condition in Gauranadi Paurashava.

Gauranadi Paurashanva is mainly affected by the cyclone storm and comparatively less vulnerable for flood and earthquake as it is geographically positioned in the coastal belt of Bangladesh.

13.5.5 Solid Waste and Garbage disposal

Condition of solid waste management at Gauranadi Paurashava is very poor. According to the opinion of surveyed households, there is no solid waste management system at Gauranadi Paurashava. Most of the people throw their garbage here and there and especially dump to the river, canal and khal which cause serious environmental pollution and also sometimes clogged the existing drainage network. From the field survey it is also found that there is no clinical waste management system. The standard demand rate of solid waste generation is 0.03 kg/ per capita/ per day which will be estimated in Interim phase.

House Hold Waste

According to the opinion of surveyed households, there is no dustbin at Gauranadi Paurashava. Most of the people throw their garbage here and there and specially dump to the canal and khal which cause environmental pollution and also sometimes clogged the existing drainage network. From the field survey it is also found that there is no clinical waste management system.

Industrial Waste

There is no severe environmental pollution generating industrial unit situated within and/or nearby Gauranadi Paurashava area. 9 saw mills, 11 rice mills, and 3 oil mills are situated in Gauranadi Paurashava area.

Kitchen Market Waste

At present there is no dustbin at Gauranadi Paurashava to collect kitchen market wastes. Generally people throw their garbage here and there which cause environmental pollution and also sometimes clogged the existing drainage network.

Existing Waste Management System

At present, there is no solid waste management system at Gauranadi Paurashava. Most of the people threw garbage here and there, which causes serious environmental pollution and also sometimes clogged the existing drainage network.

13.5.6 Pollutions

Water Pollutions

Water pollution is one of the major phenomenons in Gauranadi Paurashava. Many causes have been identified for surface water pollution. Maximum surface water are polluted by domestic source and chemical fertilizer used in agriculture field. However, as the area is in coastal region, saline and iron have been contaminated the water. Marine vehicles are also responsible for water pollution of rivers and khals.

Sound Pollution

Noise pollution is a minor phenomenon in Gauranadi Paurashava. However such type of pollution problem is occurring by the road vehicles. But it has been identified that this is not a major problem for all over the area. It is a problem for some particular road side areas.

Land Pollution

Land pollution is a vital problem. Flood and river erosion is responsible for land erosion. During floods and river erosion, the loss of soil from farmland may be reflected in reduced crop production potential, lower surface water quality and damaged drainage networks.

Air Pollution

The households of Gauranadi Paurashava face the problem of air pollution. There are industries inside the Gauranadi Paurashava. These industries have been identified as main source of air

pollution. No treatment plant is available in the Paurashava. A number of heavy vehicles (Highway bus and truck) move through the road and extract some pollutant particle that also causes air pollution.

Arsenic

In Gauranadi Paurashava arsenic contamination rate is as low as negligible.

13.5.7 Natural Calamities and Localized Hazards

Water Logging

Another undesirable phenomenon is water logging. It refers to as both manmade and natural. Ground may be regarded as waterlogged when the water table of the ground water is too high to conveniently permit an anticipated activity. Different causes are responsible for water logging. Poor drainage system is one of the most important causes of water logging in the study area. There is no fixed location where water logged frequently. Most of the areas suffer water logging during heavy rainfall.

Flood

A flood is not a common natural disaster at Gauranadi Paurashava. The area hardly faces flash flood. In 1955, 1974, and 1988 year most of the area of Bangladesh affected by flood but Gauranadi was not affected in that time. The Paurashava was affected only in the flood of 1998.

Cyclone

Cyclone is another common disaster at Gauranadi Paurashava. Every year Gauranadi Paurashava is affected by cyclone. Among them the identifiable disaster was cyclone SIDR in 2007 and Aila in 2009. The disaster SIDR and Aila were a big hazard for their natural climatic condition. It also damages many lives, forests, agricultures and infrastructures. For the help of cyclone affected peoples and livestock during and after cyclone there are cyclone centers at Gauranadi Paurashava. Mainly primary schools are serving as cyclone centers.

Earthquake

Earthquake is a natural hazard and the southern area of Bangladesh is not so vulnerable. So, Gauranadi Paurashava is not vulnerable for earthquake.

River Erosion

The Torki River sides are erosion prone caused by seepage of water from countryside towards the river along the banks during post-monsoon period and during high flood period. Water waves created during the storm surge, cyclone and heavy rainfall are causes of erosion. The seepage of water may create unbalanced pore pressure producing severe bank scouring in loose sandy riverbank resulting river erosion

Soil Erosion

Soil erosion is a naturally occurring process on all land. The agents of soil erosion are water and wind, each contributing a significant amount of soil loss each year at Gauranadi Paurashava. The loss of soil from farmland may be reflected in reduced crop production potential, lower surface water quality and damaged drainage networks. The soil removed by runoff from the land, for example during a large storm, accumulates below the eroded areas, in severe cases blocking roadways or drainage channels and inundating buildings.

Fire Hazard

The residents of Gauranadi Paurashava do not normally face the problem of fire.

Land Filling

Land filling creates problem in natural runoff and drainage system. The soil removed by runoff from the land accumulates below the eroded areas, in severe cases blocking roadways or drainage channels and inundating buildings.

Encroachment

Amount of land encroachment at Gauranadi is very little but land encroachment beside river interrupts the natural flow of river and is responsible for river erosion. Encroachment by the side of the canals interrupts the natural drainage system. This may be responsible for the inundation of the Paurashava.

13.6 Plans for Environmental Management and Pollution Control

13.6.1 Proposals for Environmental Issues

13.6.1.1 Solid waste management Plan

No waste collection system is available in Gauranadi Paurashava to handle / manage household/ kitchen market/clinical waste. Most of the people throw their garbage here and there and especially dump to canal and khal which environmental pollution and also sometimes clogged the existing drainage network. Although at present, environmental pollution due to solid waste not a serious problem on Gauranadi Paurashava good solid waste management practice should be implemented for better environment at Gauranadi Paurashava. To fulfill that aim some suggestions are recommended as Solid Waste Management Plan.

Criteria for Selection of Solid Waste Dumping Site

Usually the Paurashava does not have its own solid waste disposal site. For selection of solid waste dumping site, the following criteria should be considered.

- Site should not be situated just beside any river and canal
- Site should be located to minimum fuel distance
- Site should not create any nuisance to the residential areas as well as to the commercial and administrative areas.
- Site should be connected with main road and have sufficient width for truck movement.
- Infiltration of water into the dump should be prevented by covering the wastes with a layer of soil and sloping surface of the dump.

13.6.1.2 Open space, wet-land and relevant features protection Plan

The river Torki is a great asset of Gauranadi that plays multifaceted role for the town. It could be a navigation route to some extent, a source of water and also a source of recreation. Detail land use information of Open spaces is given in Table 11.8, Chapter 11, and Volume II of this report.

Mitigation Measures:

- The river should be preserved for future sustainable source of surface water supply for the City when the city's ground water would be depleted.
- Its banks can serve as breathing space and recreation for the town dwellers.
- The river should be kept pollution free applying regulatory measures based on environmental regulations
- No industry should be allowed within 100 m of the river bank.

Loss of Wetlands

Wetlands are mainly affected first by the urbanization process. Earth filling fills up the ponds and ditches. Waste water affects the aquatic ecosystem and makes the ponds and ditches unproductive and as a result the aquatic plants, fishes and animals have to die or migrate to other places. There is no strict regulation on earth filling of ponds. The Paurashava can fine only Tk.500 if someone fills the ponds. However, Wetlands Conversation Act exists in Bangladesh,

which is applicable only to natural beels and khals. Wetlands play an important role as a reservoir of rain and flood water. They are also important to maintain the balance of ecosystems and for replenishing the ground water level through seepage.

Mitigation Measures:

- Designate all ponds in Master Plan Map and protect the large ones according to the ecological importance and public interest.
- Protect the ponds as per regulatory framework of Master Plan.
- Avoiding wetlands during road alignment fixation.
- Stopping housing, industries and other development works in wetlands through earth filling.
- Stopping earth filling of ponds in the area through creation of public awareness.
- Strict implementation of Wetland Conversation Act, 2000.
- Strict implementation of Environment Conversation Act(ECA), 1885
- Create new laws if existing one fails to stop land filling of ponds.

13.6.1.3 Ground Water Pollution

Though ground water is not a major source of drinking water supply in the study area, yet ground water pollution by salinity and arsenic is a serious problem for future water supply. Arsenic is geological problem. But experts view that it arises due excessive extraction of ground water. So in future, when population rises further excessive ground water extraction will aggravate contamination situation.

Mitigation Measures:

- Expand use of surface water by protecting existing ponds and excavating new ponds.
- Introduce and popularize rain water harvesting system.
- Reduce dependency on ground water.

13.6.1.4 Surface Water Pollution

Various surface water sources of the town are regularly polluted by deliberate drainage of waste water in respect of pH, turbidity and coli form bacteria when compared with national standard. But present pollution level is low due to low density of population and no industrial agglomeration. The main sources of surface water pollution are urban waste water, sanitary sewage and solid waste dumping. With the implementation of this plan the pollution level may further increase as population and activity will increase leading to increase in waste water, sanitary sewage and solid waste dumping.

Mitigation Measures:

- Abolish katcha and hanging latrines.
- Encourage practice of sanitary latrines.
- Take measures against indiscriminate dumping of solid waste.
- Improve sanitation conditions of slaughter house, fish market and katcha bazar.
- Propaganda for public awareness.
- In future set up sewerage treatment plant to treat waste water.

13.6.2 Natural calamities and regular hazard mitigation proposals

13.6.2.1 Cyclone

Cyclone is a regular natural calamity in the study area. It affects the poor people mostly who cannot build houses with permanent materials. Cyclones also destroy trees and other establishments causing economic losses. It is not possible to prevent cyclones, but it is possible to reduce the losses by cyclones.

Mitigation Measures:

- Construction of cyclone shelter in coastal area.
- Provide housing loan to build houses with permanent materials.
- Take measures to promote employment and reduce poverty.
- Take appropriate measures for post disaster loss mitigation.

13.6.2.2 Flood Protection

The Torki River is subject to bank erosion, but it is not continuous. The road along the river has eroded to some extent. With implementation of Master Plan (MP) Project, the whole project area will be protected from flooding.

Enhancement Activities:

- Arrangement of pump drainage to Torki River during high flood when gravitational drainage fails.
- Pump of excess water will save the area from internal flooding.

Responsible Organizations: BWDB and Paurashava.

13.6.2.3 Earthquake

Although Gauranadi is not Earthquake prone area, however unplanned and unregulated urbanization and disregard to BNBC rules in building construction may cause it vulnerable in future. With the implementation of SMP the planned urbanization will strictly follow the actual zoning plan and following of BNBC rule will minimize the earthquake damage. In DMDP Urban Area Plan Volume-II, (Part-3, Interim Planning Rules) development restriction considering the geological fault line areas states **"**Structures above 2 storeys situated within 500 meters of a geological fault is not allowed unless built to the BNBC standards for Seismic Zone 3 (BNBC Section 6 Chapter 2.25)"**.**

Enhancement Activities:

- Ensure all new buildings are designed and constructed following the guideline of BNBC.
- Development of a comprehensive plan for managing post-earthquake situation.
- Train community workers who would carry out the initial search and rescue efforts.
- Launch a massive public awareness campaign.

Responsible Organizations: Paurashava, MOFDM, Civil Defense, Fire Service and DO.

13.6.2.4 Fire Hazard

Though fire hazard is low in the town it might increase in future with increased urbanization. Fire hazard will be severe when katcha housing will be built by low income poor people of the town. To avoid fire hazard following mitigation measures are recommended.

Mitigation Measures:

- Set up modern fire extinguishing devises.
- Discourage people from using low quality electrical wire in building and industries.
- Ensure periodical checking of electrical lines.
- Advise low income dwellers about cooking safety.
- Create awareness among people about the dangers of fire hazard.

13.6.2.5 Protection Plan addressing encroachment and other relevant issues

Implementation of SMP activities like roads, drainage, bridge/culvert, housing and industrial estates and bazars will radically change the natural topography and land use pattern of the area. The agricultural area will be converted into urban and semi-urban area. The present green scenic beauty will disappear; water bodies will be lost due to rapid urbanization.

Mitigation Measures:

- Careful planning to minimize the change of the area.
- Avoid water bodies during construction of roads, housing and industrial estates.
- Practice good architectural/engineering design during planning of housing estates, buildings and the intersections of main roads.
- Enhancement of plantation and gardening to increase the scenic beauty of the town.
- Preserve the ponds, chhoras and large water bodies.
- Strict implementation of Environment Conversation Act(ECA), 1885
- Propaganda for public awareness

Responsible Organizations: Paurashava, DOE and Forest Department.

13.7 Plan Implementation Strategies

13.7.1 Regulations to Implement the Environment Management Plan

Related rules and regulations for urban environment management to protect environment for sustainable urban development:

1. **Local Government (Paurashava) Ordinance 2009**, Pourashava's responsibility to concern solid wastes and sustainable development.

2. **Environmental Conservation Act 1995**, to concern water quality, air quality, noise abatement and solid wastes etc. The Department of Environment is the law enforcing organization.

3. **Environmental Conservation Rules 1997,** to concern water quality, air quality, noise abatement and solid wastes etc. The Department of Environment is the law enforcing organization.

4. **Acquisition and Requisition of Immovable Property Ordinance, 1982** is needed for acquisition of land in view to construct environmental components. The authority, according to the demand, will apply to the Deputy Commissioner for such acquisition.

5. **Conservation of Environment Act, 1995** have prescribed duties and responsibilities of the Director. Most of those responsibilities are on the control of pollution.

6. **Playfield, Open space, Garden and Natural Tank in Urban Areas Preservation Act, 2000** will be needed for the preservation of playfield, garden, open space and natural tank of the Paurashava.

7. **Water Hyacinth Act, 1936** was enacted for preventing the spread of water hyacinth in Bangladesh and for its destruction. It is said in the section 5 that, no person shall grow or cultivate water hyacinth in any garden or in any ornamental water or receptacle. Again, according to the section 8(1) said, with a view to facilitating the discovery or destruction of water hyacinth, an Authorized Officer may, subject to any rules made under this Act, by a notice served in the prescribed manner, direct an occupier of any land, premises or water within a notified area to cause-

    (a) any branches of trees or shrubs on any such land or premises which overhang the edge of any river, stream, waterway, ditch, marsh, bil, lake, tank, pond, pool or pit to be cut back and any undergrowth or jungle thereon to be removed from such edge, within a distance specified in the notice, or

    (b) any vegetation appearing above the surface of any such water to be removed from the water, within such period as may be specified in the notice.

13.7.2 Plan Implementation Strategy

Implementation through Multi-Sectoral Investment Programme: Major infrastructure development works such as primary roads, water supply, drainage, etc., will largely be controlled by Government. Public works requires efficient co-ordination through the Multi-Sectoral Investment Programme (MSIP).

Objective of a Multi-Sectoral Investment Programme (MSIP) will match a list of the development projects with the funding stream necessary to implement them. There are two basic activities that

would determine the contents of MSIP. Firstly, activity would be to prioritize and schedule the investment projects of all public agencies so they will collectively help to achieve the development goals and objectives of the Urban Area Plan. Second activity would be to analyze the source and availability of fund for the prioritized list of development projects.

Implementation through Action Plans and Projects: Action Plans and Projects will be the implementation plans to solve problems at the local level. Action plans will take a direct approach toward plan implementation with a minimum of research, reports or elaborate planning methods. These projects will be easily identifiable and will require minimum resource.

Implementation through Development Control: Landuse zoning is one of several methods of plan implementation to be considered. In all cases where some form of development, landuse control may be applied; careful consideration requires the following ideologies:

Development control as an instrument of plan implementation may be selectively applied within the Urban Area Plans. Development controls would also be varied in intensity and detail to suit the particular circumstances. It is important that they should be clear and easily understood by all parties concerned. Since the entire Paurashava Master Plan 'package' has become statutory, development controls associated with its component plans would also be statutory.

Implementation by Facilitating Private Investment: Another approach that would be taken by government toward plan implementation will be to guide and facilitate investments made by the private sector. Government can achieve this with relative ease and at very low cost by setting up a legal and operational framework, coupled with suitable incentives, to facilitate land consolidation, plot boundary readjustment, efficient layout of plots and provision of local infrastructure by the private sector. The benefits of this approach would be:

- increased efficiently of the urban land market would make, more private land available to urban households;

- would pass much of the development costs for local infrastructure to the private sector and land market mechanisms;
- would increase in land for development without large cash outlays by government to purchase land for development schemes; and
- would keep provision of land for community facilities virtually no cost to government.

Plan Monitoring

The Urban Area Plan would simply be tools for guiding and encouraging the growth and development of an urban area in a preferred manner. In a rapidly changing urban environment, the Urban Area Plan would require to keep up to date. If this is not done, within a few years it will be obsolete. Therefore, it is imperative that the requirement for regular updating of the Urban Area Plan be made a legal requirement.

For implementation of the various program components of the Urban Area Plan appropriate administrative measures will have to be undertaken. This will essentially include project preparation and monitoring of their execution and evaluation. For carrying out all these activities appropriate institutional measures are also be needed.

Evaluation

Monitoring and evaluation of ongoing and implemented projects is essential to keep the future course of action on the right track. An ongoing project should be regularly monitored and handicaps identified to enable taking appropriate measures at the right time.
Post implementation evaluation is also needed to take appropriate measures correcting past errors-from project preparation to implementation.

The top level supervision has to be done by a high level supervisory committee headed by Paurashava Mayor, LGED representative and Local Government Ministry. Other members of the committee will be local Ward Councilors, local community leader/social workers and the Town Planner of the Paurashava. The committee will supervise implementation works

Co-ordination

A Planning Section of Paurashava should have close interaction with the citizen of Paurashava at large in order to make people aware of the benefits of a good plan and, therefore, their social responsibility to promote plan implementation in one hand and also resist contraventions on the other. In this way it will be possible to ensure governance at Paurashava level. A specific interactive cell is recommended to operate in this regard with following responsibilities:

- Provide pre-application advice to residents, consultants and developers about landuse management issues and application procedures for the submission of development applications.
- Enforce planning and landuse management related legislation and zoning scheme regulations.
- Issue of property zoning certificates.
- Investigate and resolve landuse management complaints, illegal landuse and prosecuting contraventions.

Such interactive windows may be opened in various convenient locations to ensure ease of the answers to commonly asked questions may be shown in the internet. Besides, those may be shown in the print and electronic media time to time.

In spontaneous areas, while all out people's co-operation is needed for project implementation; there will also be some elements of negotiation. Negotiation will be particularly needed in case of road widening projects. It will be a crucial task for Paurashava to convince the affected people to give up their land for road use. Efforts should be made to convince the land owners on the ground of enhancement of property value due to road widening. In case people refuse to offer land free of cost necessary arrangements may have to be made for payment of compensation. This process of negotiation will be very critical, cumbersome and time consuming, and therefore, has to be handled with utmost care and patience. The best results can be accrued only by wining people's confidence. In case the authority fails to get peoples co-operation they should exercise power of compulsory acquisition of land. Attempts may be made to engage NGOs / CBOs to work as catalysts in negotiation.

14.1 Introduction

Urban planning is critical to the healthy growth of cities. Unplanned growth leads a number of problems, creating misery for urban dwellers and making remedying of those difficulties. Yet flawed urban planning is little better, or perhaps worse, than no urban planning at all. It is thus important, when taking on such an enormous task as the drafting of an Urban Area Plan for a Paurashava, to ensure that the plan is well considered and likely to be conducive to good health and well-being of the urban dwellers.

14.2 Consideration for the Preparation of Urban Service

- Specify whether the urban service will be provided in the future by a city, county, district, authority or a combination of one or more cities, counties, districts or authorities.
- Set forth the functional role of each service provider in the future provision of the urban service.
- Determine the future service area for each provider of the urban service.
- Assign responsibilities for:
    - Planning and coordinating provision of the urban service with other urban services;
    - Planning, constructing and maintaining service facilities; and
    - Managing and administering provision of services to urban users.

14.3 Range and Content of the Urban Service

The Plan for Urban Services covers planning area of Gauranadi Paurashava for ten years' time-frame (from 2011 to 2021). It also comprises with report and maps.

The Plan in concerned where services will be located (expected development). It also indicates how the Structure Plan policies will govern the areas and the standard for services calculated based on the population projection.

Outline of the Plan gives guidance to the Paurashava how the urban services will be developed and be promoted, maintained with a coordinated manner.

This chapter describes the urban basic services development proposals for future development of the Paurashava. The proposals have been made at the town level, under the urban area plan. The local level development proposals will be addressed in the Ward Action Plan. The development proposals deal with the basic urban services, like, water supply, drainage, sanitation, solid waste, telecommunication, electricity and community facilities, education and health.

14.3.1 Water Supply

According to BBS, it has been observed that about 1.15% households of Gauranadi Paurashava is connected to Paurashava supplied water supply system whereas about 63.3% households use well as a source of drinking water. Additionally, about 35.0% households have tube-well and the rest of the households use pond water for their drinking purpose.

Quality of the supply system is not so satisfactory. All the surveyed households affirmed that there is no water supply facility available for them.

Considering the above issues a water treatment plant has been proposed in ward no.06 with an area of 3.91 acres land. This location is the most suitable place according to consultant because both surface and ground water is available here and no drain outfall is being proposed within its

0.39 Sq km perimeter area. An overhead tank has been also proposed for above issue with an area of 1.54 acre land in ward no. 03. Details have been given in table 11.13, chapter 11, Landuse Plan, Part B.

14.3.2 Solid Waste

There will be waste transfer stations in every ward with an area of 3.38 acres for collection of solid waste located at suitable locations. A waste disposal site will be developed over an area of 5.65 acres for final disposal of the solid waste. The waste dumping site is located in Ward no. 09 of the Paurashava. Details have been given in table 11.13, chapter 11, Landuse Plan, Part B.

14.3.3 Telecommunication

The town enjoys the networks of all mobile companies operating in the country. Due to easy and cheaper access to mobile, there is actually no demand for BTCL network.

14.3.4 Sanitation

The BBS data shows that about 94.3% of the households have sanitary toilet whereas about 0.69% households have no toilet facilities. Furthermore, about 5.03% of the households have other type of toilet facilities such as kutcha toilet, hanging toilet, etc.

The socio-economic survey results indicate that about 92.6% of the toilets are Pucca, and 7.4% Katcha. However, the condition of toilet facilities is good at Gauranadi Paurashava

Due to prohibitive expenditure one should not expect establishing network and treatment plant based sewerage system in the town by the Paurashava. So, for long the sanitary system of the Paurashava will remain on site. To promote healthy sanitation, Paurashava should promote low cost sanitary latrines in the town together with awareness building for healthy sanitation. It is proposed to set up public toilets in public gathering areas, like, existing and proposed bus stand, bazar and the main town center.

Map 14.1 shows the proposed Utility Services in Gauranadi Paurashava.

14.4 Regulations to Address the Proposals

Local Government (Paurashava) Act, 2009 (Ordinance No. XLXVIII of 2009)

According to the 2nd Schedule, Sl. No. 10, the Paurashava may provide supply of water sufficient for public and private purposes. Frame and execute water supply scheme for the construction and maintenance of such works for storage and distribution of water. In case of private sources of water supply, it is said that, all private sources of water supply within the Paurashava shall be subject to control, regulation and inspection by the Paurashava. No new well, water pump or any other source of water for drinking purposes will be dug, constructed or provided except with the sanction of the Paurashava.

The regulations, as discussed above, will be needed for provision of drinking water supplies both Paurashava and private sources in the Paurashava.

The sewerage facilities may be provided by the Paurashava and Department of Public Health Engineering (DPHE). According to the 2nd Schedule, Sl. No. 12, of the Local Government (Paurashava) Ordinance, 2009, Paurashava provide an adequate system of public drains and all such drains shall be constructed, maintained, kept, cleared and emptied with due regard to the heal and convenience of the public. All private drains shall be subject to control, regulation and inspection by the Paurashava.

Public Health (Emergency Provisions) Ordinance, 1944 (Ordinance No. XXI of 1944)

According to the **s**ection 2(e) "public health services" and "public health establishment" include respectively sanitary, water-supply, vaccination, sewage disposal, drainage and conservancy services and establishment maintained for the purposes of such services, and any other service or establishment of a local authority which the Government may by notification in the Official Gazette declare to be a public health service or public health establishment for any purpose of this Ordinance.

The Department of Public Health Engineering (DPHE) is performing activities for drinking water supply. At Paurashava level If DPHE likes to render their service according to the water supply network as presented in this plan, the regulation will be the safeguard for them.

East Pakistan Water and Power Development Authority Rules, 1965 (No. 4-1(E)

The Power Development Board (PDB) is empowered for power generation under the guidance of Electricity Act, 1910. At present, PDB and Rural Electrification Board (under the Rural Electrification Board Ordinance, 1977) is performing the role relevant with the electrification of the Paurashava. The existing authorities will be needed for electrification of the Paurashava according to the guidelines presented in the plan.

Telegraph and Telephone Board Ordinance, 1975 (Ordinance No. XLVII of 1975)

A Telegraph and Telephone Board (T&T Board) was composed through this Ordinance. Section 6(1) of the Ordinance has prescribed the functions of the Board and said, it shall be the function of the Board to provide efficient telegraph and telephone services and to do all acts and things necessary for the development of telegraphs and telephones. In the Paurashava, at present, a T & T Board is performing the functions prescribed in the section 6(1). T & T Board is the sole authority for performing the same and it will be continued in future also. But, the Mobile telephone system generates a revolution in the society. Most of the people are depended on the Mobile phone system. The plan does not consider this system.

East Pakistan Water and Power Development Authority Rules, 1965 (No. 4-1(E)

The Power Development Board (PDB) is empowered for power generation under the guidance of Electricity Act, 1910. At present, PDB and Rural Electrification Board (under the Rural Electrification Board Ordinance, 1977) is performing the role relevant with the electrification of the Paurashava. The existing authorities will be needed for electrification of the Paurashava according to the guidelines presented in the plan.

14.5 Implementation, Monitoring and Evaluation

Implementation, Monitoring and Evaluation of the Urban Services Plan

Implementation through Multi-Sectoral Investment Program: Major infrastructure development works such as primary roads, water supply, drainage, etc., will largely be controlled by Government. Public works requires efficient co-ordination through the Multi-Sectoral Investment Program (MSIP).

Objective of a Multi-Sectoral Investment Program (MSIP) will match a list of the development projects with the funding stream necessary to implement them. There are two basic activities that would determine the contents of MSIP. One activity would be to prioritize and schedule the investment projects of all public agencies so they will collectively help to achieve the development goals and objectives of the Urban Services Plan. Second activity would be to analyze the source and availability of fund for the prioritized list of development projects.

Implementation through Action Plans and Projects: Action Plans and Projects will be the implementation plans to solve problems at the local level. Action plans will take a direct approach toward plan implementation with a minimum of research, reports or elaborate planning methods. These projects will be easily identifiable and will require minimum resource.

Implementation through Development Control: Landuse zoning is one of several methods of plan implementation to be considered. In all cases where some form of development, landuse control may be applied; careful consideration requires the following ideologies:

- the purpose to be achieved by the development controls;
- where controls should be applied;
- what aspect of development needs to be controlled;
- what type of development controls are required;
- what degree or level of development control is required;
- who will be affected by the required control;
- who will be affected by the controls and in what manner;
- when the controls should be applied;
- what will be the likely impact of the controls;
- how and by whom will the controls be administered and enforced.

Development control as an instrument of plan implementation may be selectively applied within the Urban Services Plans. Development controls would also be varied in intensity and detail to suit the particular circumstances. It is important that they should be clear and easily understood by all parties concerned. Since the entire Paurashava Master Plan 'package' has become statutory, development controls associated with its component plans would also be statutory.

Implementation by Facilitating Private Investment: Another approach that would be taken by government toward plan implementation will be to guide and facilitate investments made by the private sector. Government can achieve this with relative ease and at very low cost by setting up a legal and operational framework, coupled with suitable incentives, to facilitate land consolidation, plot boundary readjustment, efficient lay out of plots and provision of local infrastructure by the private sector. The benefits of this approach would be:

- increased efficiently of the urban land market would make, more private land available to urban households;
- would pass much of the development costs for local infrastructure to the private sector and land market mechanisms;
- would increase in land for development without large cash outlays by government to purchase land for development schemes; and
- would keep provision of land for community facilities virtually no cost to government.

Plan Monitoring

The Urban Services Plan would simply be tools for guiding and encouraging the growth and development of an urban area in a preferred manner. In a rapidly changing urban environment, the Urban Services Plan would require to keep up to date. If this is not done, within a few years it will be obsolete. Therefore, it is imperative that the requirement for regular updating of the Urban Services Plan be made a legal requirement.


For implementation of the various program components of the Urban Services Plan appropriate administrative measures will have to be undertaken. This will essentially include project preparation and monitoring of their execution and evaluation. For carrying out all these activities appropriate institutional measures are also be needed.

Evaluation

Monitoring and evaluation of ongoing and implemented projects is essential to keep the future course of action on the right track. An ongoing project should be regularly monitored and handicaps identified to enable taking appropriate measures at the right time.
Post implementation evaluation is also needed to take appropriate measures correcting past errors-from project preparation to implementation.

The top level supervision has to be done by a high level supervisory committee headed by the Paurashava Mayor, representatives of the service giving agencies and Local Government Ministry. Other members of the committee will be local Ward Councilors, local community leader/social workers and the Town Planner of the Paurashava. The committee will supervise implementation works regularly and issue necessary instructions to expedite the works of implementation.

Map 14.1: Proposed Urban Services of Gauranadi Paurashava



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Ward Center
- Proposed Playground
- Proposed Bus Terminal
- Proposed Dumping Site
- Proposed Fuel Station
- Proposed Park
- Water Treatment Plant
- Proposed Tempo Stand
- Rickshaw Stand
- Tempo Stand
- Truck Terminal
- Electric Sub-Station

0 205 410 820 1,230 1,640 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

Part C. Ward Action Plan

Chapter-15

WARD ACTION PLAN

15.1 Introduction

This chapter contains Ward Action Plan of each individual Ward. First, the issues prevailing in different Wards have been briefly described followed by description of Development Proposals in first ward action plan (1st to 5th year of planning period) for each Ward.

15.1.1 Background

The Ward Action Plans are prepared under the framework of Structure Plan and Urban Area Plan. The Ward Action Plans contain details of development proposals at Ward level including the problems and opportunities existing therein and also include the proposals made in the upper level plan that is in the Urban Area Plan. The Ward Action Plans have been formulated for execution within a period of 5 years.

Ward Action Plan is a vital part of the current plan package as far as spatial development and development control is concerned. Absence of Ward Action Plan not only hampers undertaking of development projects by planning authority, but also leads to uncontrolled and unwanted spatial development in the private sector. Land use zoning is also provided in the Ward Action Plan to enable detailed view of proposed land use and development.

15.1.2 Content and Form of Ward Action Plan

The Ward Action Plan is detailed area plan based on the policy framework, guideline indication of Structure Plan and more detailed guideline of Urban Area Plan. The provision of Ward Action Plan is inherent in the Structure Plan with some specific purposes. The Ward Action Plan is to:

a. Provide basic micro level infrastructure and services in the study area through systematic planning, under the framework of Structure Plan and proposals of the Urban Area Plan;
b. Create congenial environment to promote economic activities;
c. Improve drainage system and protect natural water channels from encroachment; and
d. Create service centers to promote urban growth.

15.1.3 Linkage with Structure and Urban Area Plan

Ward Action Plan is the 3rd component of the Master Plan package. The other two upper level components are Structure Plan and Urban Area Plan. Structure Plan lay down the framework of the future plan including strategy and the sectoral policies. The Urban Area Plan and the Ward Action Plan detail out development proposals under the framework of Structure Plan.

15.2 Derivation of Ward Action Plan

The Ward Action Plan is derived from the conceptual framework, and guidelines and strategies for development under Structure Plan and detailed proposals of Urban Area Plan. Ward Action Plan is aimed to provide detailed infrastructure plan to guide the physical development of Gauranadi upazila including its all economic and social activities. This plan adheres to the policy directives spelled out in the Structure Plan.

15.2.1 Revisiting Structure Plan and Urban Area Plan

To guide long term growth of the Paurashava, potential locations of major development areas are identified and the Structure Plan Area is broadly classified into nine categories, namely Established Urban Area, Sub Urban Area, New Urban Area, Recreational Facility, Circulation

Network, Restricted Area, Urban Peripheral Area, Agriculture Area and Water Retention Area. The Urban Area Plan is prepared under the framework of Structure Plan and the infrastructure identified for improvement and development are listed as proposals in the Urban Area Plan. The broad classification of lands in the Structure Plan and detailed proposals in the Urban Area Plan form the basis for Ward Action Plan.

15.2.2 Prioritization

The prioritization of project proposals in Ward wise Action Plan are made on the basis of urgency for development depending on the needs of people and the town's requirement for infrastructure development.

15.2.3 Ward Wise Action Plan

The Ward Action Plan is prepared for each of the nine Wards and is presented in order of their serial number. The Ward Action Plans are a series of detailed spatial development plans of different use and facilities. The plans comprise maps of appropriate scale supported by explanatory report. The Ward Action Plans have been formulated for execution within a period of 5 years. They do not initially cover the entire Structure Plan area. While all sub-areas will eventually require Ward Action Plan, only priority areas are to be dealt with initially. The aim of a Ward Action Plan is to prevent haphazard urban development and ensure livable environment in areas that are likely to be urbanized soon. Initially Detailed Area Plan should be covered for only those areas where action is needed immediately or where development pressure is high.

15.3 Ward Action Plan for Ward No. 01

15.3.1 Demography

Ward No.1 is located on the Northern part of the Paurashava. Population projection shows 7979 populations for the year 2031. For the same year, it will be 16 persons per acre in 2031. Table 15.1 shows the detail.

Table 15.1: Population Statistics of Ward No. 01

Item	Year			
	2016	2021	2026	2031
Area (acre)	502.99	502.99	502.99	502.99
Population	6764	7090	7521	7979
Density of Population (acre)	13	14	15	16

15.3.2 Ward Action Plan Proposals

15.3.2.1 Review of Existing Land Use

Out of total 502.99 acres of land of this ward, more than 274 acres of land i.e. 54.64% is used in agricultural purpose. The residential use with 120.35 acres, occupies 23.93% of total land, water bodies 13.30%, commercial use 3.38%, and circulation network 2.42%. There is no land for educational facility.


15.3.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.2 shows the amount of land existing and proposed uses in Ward no. 1. **Map 15.1** shows proposed land use of Ward 01. Table 15.2 shows the detail.

Table 15.2: Comparative Scenario of Existing and Proposed Land Uses of Ward No. 01

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agricultural	274.82	54.64	1	Administrative	2.03	0.40
2	Circulation Network	12.16	2.42	2	Agricultural	112.90	22.45
3	Commercial Activities	16.99	3.38	3	Circulation Network	49.47	9.84
4	Community Facilities	2.06	0.41	4	Commercial Activities	17.22	3.42
5	Education & Research	5.13	1.02	5	Community Facilities	2.33	0.46
6	Government Office	0.2	0.04	6	Education & Research	7.86	1.56
7	Health facilities	0.41	0.08	7	Health Facilities	1.23	0.24
8	Industrial	2.88	0.57	8	Industrial Facilities	2.90	0.58
9	Mixed Use	0.39	0.08	9	Mixed Use	8.65	1.72
10	NGO office	0.1	0.02	10	Open Space	8.47	1.68
11	Open space	0.49	0.10	11	Rural Settlement	34.15	6.79
12	Recreational facilities	-	-	12	Transportation & Communication	2.22	0.44
13	Residential area	120.35	23.93	13	Urban Settlement	147.22	29.27
14	Transportation and Communication	0.12	0.02	14	Urban Deferred	50.76	10.09
15	Water Body	66.89	13.30	15	Utility Service	2.47	0.49
				16	Waterbody	53.12	10.56
	Total	**502.99**	**100**		**Total**	**502.99**	**100**

Map 15.1: Landuse Plan of ward no.1



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 50 100 200 300 400 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com

In Association with

15.3.2.3 Proposed Road Infrastructure Development

A total of 22.69 km of road development has been proposed in first ward action plan for Ward no. 01 of Gauranadi Paurashava. Total length of secondary road will be 3.59 km and width will be 40 to 60 ft for this ward. Total length of tertiary road of this ward will be 17.50 km. The rest 1.59 km primary road will be developed and its width will be 100 ft. The detailed scenario of road network development proposal is given in Table 15.3.

Table 15.3: Road Network Proposal at Ward no. 01

Type	Proposed Road ID	Length in m	Remark	Phase
Primary Road	PR-1	1565.18	Widening	1st
Primary Road	PR-2	28.87	Widening	1st
Secondary Road	SR-8	692.61	Widening	1st
Secondary Road	SR-9	986.12	Widening	1st
Secondary Road	SR-10	735.67	Widening	1st
Secondary Road	SR-12	1177.09	Widening	1st
Tertiary Road	TR-350	70.20	Widening	1st
Tertiary Road	TR-351	101.61	Widening	1st
Tertiary Road	TR-352	61.28	Widening	2nd
Tertiary Road	TR-353	215.53	Widening	2nd
Tertiary Road	TR-354	37.90	Widening	2nd
Tertiary Road	TR-355	274.71	Widening	2nd
Tertiary Road	TR-356	36.41	Widening	2nd
Tertiary Road	TR-357	34.13	Widening	2nd
Tertiary Road	TR-358	37.74	Widening	2nd
Tertiary Road	TR-359	39.01	Widening	2nd
Tertiary Road	TR-360	209.43	Widening	2nd
Tertiary Road	TR-361	125.44	Widening	2nd
Tertiary Road	TR-362	47.53	Widening	2nd
Tertiary Road	TR-363	38.78	Widening	2nd
Tertiary Road	TR-364	201.67	Widening	2nd
Tertiary Road	TR-365	71.37	Widening	3rd
Tertiary Road	TR-366	68.56	Widening	3rd
Tertiary Road	TR-367	913.56	Widening	3rd
Tertiary Road	TR-368	58.23	Widening	3rd
Tertiary Road	TR-369	91.03	Widening	3rd
Tertiary Road	TR-370	174.03	Widening	3rd
Tertiary Road	TR-371	611.49	Widening	3rd
Tertiary Road	TR-372	42.11	Widening	3rd
Tertiary Road	TR-378	30.65	Widening	3rd
Tertiary Road	TR-379	27.20	Widening	3rd
Tertiary Road	TR-380	315.59	Widening	3rd
Tertiary Road	TR-381	90.27	Widening	2nd
Tertiary Road	TR-382	97.66	Widening	1st
Tertiary Road	TR-383	239.52	Widening	1st
Tertiary Road	TR-384	57.37	Widening	1st
Tertiary Road	TR-385	81.91	Widening	1st
Tertiary Road	TR-386	81.29	Widening	1st
Tertiary Road	TR-387	69.58	Widening	1st
Tertiary Road	TR-388	91.49	Widening	1st
Tertiary Road	TR-389	151.52	Widening	1st
Tertiary Road	TR-390	37.89	Widening	2nd
Tertiary Road	TR-391	49.28	Widening	2nd
Tertiary Road	TR-392	40.86	Widening	2nd
Tertiary Road	TR-393	460.19	Widening	2nd
Tertiary Road	TR-394	23.34	Widening	2nd
Tertiary Road	TR-395	699.97	Widening	2nd
Tertiary Road	TR-396	278.76	Widening	2nd
Tertiary Road	TR-397	74.50	Widening	2nd
Tertiary Road	TR-398	209.87	Widening	2nd
Tertiary Road	TR-411	118.86	Widening	2nd
Tertiary Road	TR-412	308.83	Widening	2nd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-413	123.93	Widening	2nd
Tertiary Road	TR-414	55.80	Widening	2nd
Tertiary Road	TR-415	127.38	Widening	3rd
Tertiary Road	TR-418	77.32	Widening	3rd
Tertiary Road	TR-419	107.78	Widening	3rd
Tertiary Road	TR-420	43.91	Widening	3rd
Tertiary Road	TR-421	917.50	Widening	3rd
Tertiary Road	TR-422	27.65	Widening	3rd
Tertiary Road	TR-423	942.13	Widening	3rd
Tertiary Road	TR-424	26.24	Widening	3rd
Tertiary Road	TR-425	251.58	Widening	3rd
Tertiary Road	TR-426	178.40	Widening	3rd
Tertiary Road	TR-431	246.77	Widening	3rd
Tertiary Road	TR-435	191.58	Widening	2nd
Tertiary Road	TR-436	38.46	Widening	1st
Tertiary Road	TR-437	154.99	Widening	1st
Tertiary Road	TR-438	181.55	Widening	1st
Tertiary Road	TR-439	24.70	Widening	1st
Tertiary Road	TR-440	75.36	Widening	1st
Tertiary Road	TR-443	70.82	Widening	1st
Tertiary Road	TR-444	121.16	Widening	1st
Tertiary Road	TR-447	62.41	Widening	1st
Tertiary Road	TR-450	152.98	Widening	2nd
Tertiary Road	TR-451	30.85	Widening	2nd
Tertiary Road	TR-455	52.95	Widening	2nd
Tertiary Road	TR-456	72.31	Widening	2nd
Tertiary Road	TR-457	208.83	Widening	2nd
Tertiary Road	TR-458	171.33	Widening	2nd
Tertiary Road	TR-459	166.22	Widening	2nd
Tertiary Road	TR-460	25.54	Widening	2nd
Tertiary Road	TR-461	36.60	Widening	2nd
Tertiary Road	TR-464	65.28	Widening	2nd
Tertiary Road	TR-465	25.30	Widening	2nd
Tertiary Road	TR-466	199.49	Widening	2nd
Tertiary Road	TR-467	24.32	Widening	2nd
Tertiary Road	TR-468	34.10	Widening	3rd
Tertiary Road	TR-469	12.17	Widening	3rd
Tertiary Road	TR-470	181.41	Widening	3rd
Tertiary Road	TR-709	34.32	Widening	3rd
Tertiary Road	TR-710	46.52	Widening	3rd
Tertiary Road	TR-727	260.98	Widening	3rd
Tertiary Road	TR-728	97.77	Widening	3rd
Tertiary Road	TR-729	125.86	Widening	3rd
Tertiary Road	TR-750	14.41	Widening	3rd
Tertiary Road	TR-751	279.30	Widening	3rd
Tertiary Road	TR-752	33.34	Widening	3rd
Tertiary Road	TR-753	9.98	Widening	2nd
Tertiary Road	TR-754	69.63	Widening	1st
Tertiary Road	TR-755	32.70	Widening	1st
Tertiary Road	TR-756	29.09	Widening	1st
Tertiary Road	TR-757	17.80	Widening	1st
Tertiary Road	TR-759	68.98	Widening	1st
Tertiary Road	TR-760	40.63	Widening	1st
Tertiary Road	TR-794	499.50	New	1st
Tertiary Road	TR-795	387.78	New	1st
Tertiary Road	TR-796	97.72	Widening	2nd
Tertiary Road	TR-797	361.28	Widening	2nd
Tertiary Road	TR-798	201.30	Widening	2nd
Tertiary Road	TR-799	293.63	Widening	2nd
Tertiary Road	TR-800	235.72	New	2nd
Tertiary Road	TR-801	517.97	New	2nd
Tertiary Road	TR-802	460.98	New	2nd
Tertiary Road	TR-803	159.94	New	2nd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-804	97.08	New	2nd
Tertiary Road	TR-805	324.26	New	2nd

- "TR" for tertiary road, "SR" for secondary road, and "PR" for primary road.

15.3.2.4 Drainage Development Plan

There is both natural and man-made drainage system at Ward no. 01. The existing drainage of the ward mainly depends on the natural drainage facilities. There is proposal for manmade drainage facilities in Ward Action Plan. The proposed drainage facilities will be developed based on these natural channels. Table 15.4 shows the details. **Map 15.2** represents the proposed road and drainage network for Gauranadi Paurashava.


Table15.4: Drainage Development Plan Proposals for ward 01

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
PD-3	Primary Drain	1565.18	4.50-5.50	2.00-3.00	New Drain	1st
SD-10	Secondary Drain	260.98	3.50-4.50	1.25-3.00	New Drain	1st
SD-12	Secondary Drain	1354.75	3.50-4.50	1.25-3.00	New Drain	2nd
TD-291	Tertiary Drain	101.61	2.5-3.5	0.64-1.25	New Drain	3rd
TD-292	Tertiary Drain	215.53	2.5-3.5	0.64-1.25	New Drain	3rd
TD-293	Tertiary Drain	509.76	2.5-3.5	0.64-1.25	New Drain	3rd
TD-294	Tertiary Drain	209.43	2.5-3.5	0.64-1.25	New Drain	3rd
TD-295	Tertiary Drain	47.53	2.5-3.5	0.64-1.25	New Drain	3rd
TD-296	Tertiary Drain	986.12	2.5-3.5	0.64-1.25	New Drain	3rd
TD-297	Tertiary Drain	201.67	2.5-3.5	0.64-1.25	New Drain	3rd
TD-298	Tertiary Drain	71.37	2.5-3.5	0.64-1.25	New Drain	3rd
TD-299	Tertiary Drain	68.56	2.5-3.5	0.64-1.25	New Drain	3rd
TD-300	Tertiary Drain	913.56	2.5-3.5	0.64-1.25	New Drain	3rd
TD-301	Tertiary Drain	174.03	2.5-3.5	0.64-1.25	New Drain	3rd
TD-302	Tertiary Drain	42.11	2.5-3.5	0.64-1.25	New Drain	3rd
TD-307	Tertiary Drain	315.59	2.5-3.5	0.64-1.25	New Drain	3rd
TD-308	Tertiary Drain	735.67	2.5-3.5	0.64-1.25	New Drain	3rd
TD-309	Tertiary Drain	90.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-310	Tertiary Drain	239.52	2.5-3.5	0.64-1.25	New Drain	3rd
TD-311	Tertiary Drain	57.37	2.5-3.5	0.64-1.25	New Drain	3rd
TD-312	Tertiary Drain	81.91	2.5-3.5	0.64-1.25	New Drain	3rd
TD-313	Tertiary Drain	81.29	2.5-3.5	0.64-1.25	New Drain	3rd
TD-314	Tertiary Drain	69.58	2.5-3.5	0.64-1.25	New Drain	3rd
TD-315	Tertiary Drain	91.49	2.5-3.5	0.64-1.25	New Drain	3rd
TD-316	Tertiary Drain	151.52	2.5-3.5	0.64-1.25	New Drain	3rd
TD-317	Tertiary Drain	460.19	2.5-3.5	0.64-1.25	New Drain	3rd
TD-318	Tertiary Drain	278.76	2.5-3.5	0.64-1.25	New Drain	3rd
TD-320	Tertiary Drain	209.87	2.5-3.5	0.64-1.25	New Drain	3rd
TD-333	Tertiary Drain	118.86	2.5-3.5	0.64-1.25	New Drain	3rd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-334	Tertiary Drain	308.83	2.5-3.5	0.64-1.25	New Drain	3rd
TD-335	Tertiary Drain	123.93	2.5-3.5	0.64-1.25	New Drain	3rd
TD-336	Tertiary Drain	127.38	2.5-3.5	0.64-1.25	New Drain	3rd
TD-339	Tertiary Drain	77.32	2.5-3.5	0.64-1.25	New Drain	3rd
TD-340	Tertiary Drain	107.78	2.5-3.5	0.64-1.25	New Drain	3rd
TD-341	Tertiary Drain	917.50	2.5-3.5	0.64-1.25	New Drain	3rd
TD-343	Tertiary Drain	1399.69	2.5-3.5	0.64-1.25	New Drain	3rd
TD-344	Tertiary Drain	26.24	2.5-3.5	0.64-1.25	New Drain	3rd
TD-345	Tertiary Drain	251.58	2.5-3.5	0.64-1.25	New Drain	3rd
TD-346	Tertiary Drain	178.40	2.5-3.5	0.64-1.25	New Drain	3rd
TD-351	Tertiary Drain	246.77	2.5-3.5	0.64-1.25	New Drain	3rd
TD-354	Tertiary Drain	191.58	2.5-3.5	0.64-1.25	New Drain	3rd
TD-355	Tertiary Drain	38.46	2.5-3.5	0.64-1.25	New Drain	3rd
TD-356	Tertiary Drain	154.99	2.5-3.5	0.64-1.25	New Drain	3rd
TD-357	Tertiary Drain	1177.09	2.5-3.5	0.64-1.25	New Drain	3rd
TD-358	Tertiary Drain	181.55	2.5-3.5	0.64-1.25	New Drain	3rd
TD-359	Tertiary Drain	24.70	2.5-3.5	0.64-1.25	New Drain	3rd
TD-360	Tertiary Drain	75.36	2.5-3.5	0.64-1.25	New Drain	3rd
TD-362	Tertiary Drain	70.82	2.5-3.5	0.64-1.25	New Drain	3rd
TD-363	Tertiary Drain	121.16	2.5-3.5	0.64-1.25	New Drain	3rd
TD-366	Tertiary Drain	62.41	2.5-3.5	0.64-1.25	New Drain	3rd
TD-368	Tertiary Drain	152.98	2.5-3.5	0.64-1.25	New Drain	3rd
TD-369	Tertiary Drain	30.85	2.5-3.5	0.64-1.25	New Drain	3rd
TD-373	Tertiary Drain	52.95	2.5-3.5	0.64-1.25	New Drain	3rd
TD-374	Tertiary Drain	72.31	2.5-3.5	0.64-1.25	New Drain	3rd
TD-375	Tertiary Drain	208.83	2.5-3.5	0.64-1.25	New Drain	3rd
TD-376	Tertiary Drain	171.33	2.5-3.5	0.64-1.25	New Drain	3rd
TD-377	Tertiary Drain	166.22	2.5-3.5	0.64-1.25	New Drain	3rd
TD-378	Tertiary Drain	25.54	2.5-3.5	0.64-1.25	New Drain	3rd
TD-382	Tertiary Drain	65.28	2.5-3.5	0.64-1.25	New Drain	3rd
TD-383	Tertiary Drain	25.30	2.5-3.5	0.64-1.25	New Drain	3rd
TD-384	Tertiary Drain	199.49	2.5-3.5	0.64-1.25	New Drain	3rd
TD-386	Tertiary Drain	34.10	2.5-3.5	0.64-1.25	New Drain	3rd
TD-387	Tertiary Drain	12.17	2.5-3.5	0.64-1.25	New Drain	3rd
TD-388	Tertiary Drain	181.41	2.5-3.5	0.64-1.25	New Drain	3rd
TD-556	Tertiary Drain	34.32	2.5-3.5	0.64-1.25	New Drain	3rd
TD-570	Tertiary Drain	97.77	2.5-3.5	0.64-1.25	New Drain	3rd
TD-571	Tertiary Drain	125.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-592	Tertiary Drain	279.30	2.5-3.5	0.64-1.25	New Drain	3rd
TD-593	Tertiary Drain	9.98	2.5-3.5	0.64-1.25	New Drain	3rd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-594	Tertiary Drain	69.63	2.5-3.5	0.64-1.25	New Drain	3rd
TD-599	Tertiary Drain	68.98	2.5-3.5	0.64-1.25	New Drain	3rd
TD-600	Tertiary Drain	40.63	2.5-3.5	0.64-1.25	New Drain	3rd
TD-634	Tertiary Drain	499.50	2.5-3.5	0.64-1.25	New Drain	3rd
TD-635	Tertiary Drain	387.78	2.5-3.5	0.64-1.25	New Drain	3rd
TD-636	Tertiary Drain	97.72	2.5-3.5	0.64-1.25	New Drain	3rd
TD-637	Tertiary Drain	361.28	2.5-3.5	0.64-1.25	New Drain	3rd
TD-638	Tertiary Drain	201.30	2.5-3.5	0.64-1.25	New Drain	3rd
TD-639	Tertiary Drain	293.63	2.5-3.5	0.64-1.25	New Drain	3rd
TD-640	Tertiary Drain	235.72	2.5-3.5	0.64-1.25	New Drain	3rd
TD-641	Tertiary Drain	517.97	2.5-3.5	0.64-1.25	New Drain	3rd
TD-642	Tertiary Drain	159.94	2.5-3.5	0.64-1.25	New Drain	3rd
TD-643	Tertiary Drain	97.08	2.5-3.5	0.64-1.25	New Drain	3rd
TD-644	Tertiary Drain	324.26	2.5-3.5	0.64-1.25	New Drain	3rd
TD-728	Tertiary Drain	20.05	2.5-3.5	0.64-1.25	New Drain	3rd
TD-729	Tertiary Drain	186.76	2.5-3.5	0.64-1.25	New Drain	3rd
TD-730	Tertiary Drain	0.66	2.5-3.5	0.64-1.25	New Drain	3rd
TD-731	Tertiary Drain	335.65	2.5-3.5	0.64-1.25	New Drain	3rd

Map 15.2: Proposed Road & Drainage Network of ward no.1



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Bridge
- Culvert
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall

Meters
0 45 90 180 270 360

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT
SCPL Sheltech Consultants (Pvt.) Ltd.
1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.3.2.5 Urban Services

a. Solid Waste Management

Solid waste management is an important urban service. As density of population increases the volume of solid waste also increases proportionately. This ward will be developed as an industrial area. However, the income level is also another major factor influencing the volume of solid waste. Population and the volume of waste in the town is yet to be large enough to become a problem for it. But the present management system is not satisfactory and it might be led to problem in future. The consultant proposes one solid waste transfer stations in this ward at on an area of 0.16 acre. It is recommended that home collection system is introduced in the ward by creation of local CBOs. This will cause organized collection of waste and prevent indiscriminate littering.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the Torkey River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement.

c. Sanitation


It is apprehended that the government would not be able to provide network and treatment based sanitation system for the town. So the present system of sanitation will continue. However, the Paurashava must try to promote hygienic sanitation to ensure better public health. There is hardly any public toilet in the town to serve the visitors and the local people. The existing toilet of bus terminal area has to be developed as public toilet is required for the town people and as well as for the passengers waiting for departure. **Map 15.3** represents proposed urban services for ward 01.

Table15.5: Urban Service Development Proposals for ward 01

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	1.66
Commercial Activity	Wholesale Market	1	4.44
Community Facility	Gausia Madrasa Graveyard	1	0.56
Education & Research	College	1	3.18
Health Facility	Clinic	1	0.98
Open Space	Park	1	4.39
	Playground	1	3.67
Transportation Facilities	Tempo Stand	1	1.71
	Rickshaw Stand	1	0.40
Utility Service	Waste Transfer Station	1	0.16
	Electricity Line	As per existing program of PDB	-
	Electric Sub-Station	1	2.31

Map 15.3 proposed urban services for ward no. 01.

Map 15.3: Development Proposal of ward no.1



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

Meters
0 45 90 180 270 360

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL **Sheltech Consultants (Pvt.) Ltd.**

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.4 Ward Action Plan for Ward No. 02

15.4.1 Demography

Ward no. 02 is located on the East-Northern part of the town. It has a moderate density of population. Table 15.6 shows the detail.

Table 15.6: Population Statistics of Ward No. 02

Item	Year			
	2016	2021	2026	2031
Area (acre)	405.86	405.86	405.86	405.86
Population	4559	4780	5070	5378
Density of Population (acre)	11	12	12	13

15.4.2 Ward Action Plan Proposals

15.4.2.1 Review of Existing Land Use

The maximum land of this ward at present is used for agricultural purpose. It occupies 284.17 acres of land covering more than 70.02% of the total land. Residential land occupies about 15.02% of the land of the ward. About 47.51 acres of land is under Water bodies, 0.13% is used for education, 1.44% for circulation network, and only 0.05% of land is used as open spaces. Table 1.8 shows the existing land use pattern of Gauranadi Paurashava.


15.4.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.7 shows the amount of land existing and proposed uses in Ward no. 02. **Map 15.4** shows proposed land use of Ward 02.

Table 15.7: Comparative Scenario of Existing and Proposed Land Uses of Ward No. 02

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agriculture	284.17	70.02	1	Administrative	3.09	0.76
2	Circulation Network	5.84	1.44	2	Agriculture	210.00	51.74
3	Commercial Activities	3.08	0.76	3	Circulation Network	29.76	7.33
4	Community Facilities	0.93	0.23	4	Commercial Activities	5.97	1.47
5	Education & Research	0.54	0.13	5	Community Facilities	2.06	0.51
6	Government Office	0.18	0.04	6	Educational & Research	2.88	0.71
7	Health facilities	0.55	0.14	7	Health Facilities	0.51	0.13
8	Industrial	1.65	0.41	8	Industrial Facilities	1.59	0.39
9	Mixed Use	0.05	0.01	9	Mixed Use	0.04	0.01
10	Open space	0.2	0.05	10	Open Space	17.06	4.20
11	Residential area	60.94	15.02	11	Transportation & Communication	1.30	0.32
12	Transportation and Communication	0.22	0.05	12	Urban Settlement	76.77	18.91
13	Water Body	47.51	11.71	13	Utility Service	0.16	0.04
				14	Waterbody	54.69	13.48
	Total	**405.86**	**100**		**Total**	**405.86**	**100**

Map 15.4: Landuse Plan of ward no.2



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 90 180 360 540 720 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com

In Association with

15.4.2.3 Proposed Road Infrastructure Development

A total of 13.69 km of road development proposal have been made for Ward no. 02 of Gauranadi Paurashava. The total length of tertiary road will be 11.01 km and width of these roads will be 20 ft for this Ward. The total length of secondary road will be 2.15 km and width of these roads will be 60 ft. Primary road length is 0.53 km and width is 100 ft. The detailed scenario of road network development proposal is given in Table 15.8.

Table 15.8: Road Network Proposal at Ward no. 02

Type	Proposed Road ID	Length in m	Remark	Phase
Primary Road	PR-1	123.07	Widening	1st
Primary Road	PR-1	375.61	Widening	1st
Primary Road	PR-1	19.10	Widening	1st
Primary Road	PR-1	16.30	Widening	1st
Secondary Road	SR-17	243.57	New	1st
Secondary Road	SR-20	1384.41	Widening	1st
Secondary Road	SR-23	521.49	Widening	2nd
Tertiary Road	TR-3	4.24	Widening	2nd
Tertiary Road	TR-53	461.99	Widening	2nd
Tertiary Road	TR-57	476.56	Widening	2nd
Tertiary Road	TR-59	19.93	Widening	2nd
Tertiary Road	TR-61	75.87	Widening	2nd
Tertiary Road	TR-63	40.99	Widening	2nd
Tertiary Road	TR-65	348.69	Widening	2nd
Tertiary Road	TR-373	126.18	Widening	2nd
Tertiary Road	TR-374	300.36	Widening	2nd
Tertiary Road	TR-410	283.13	Widening	3rd
Tertiary Road	TR-432	972.58	Widening	3rd
Tertiary Road	TR-433	174.65	Widening	3rd
Tertiary Road	TR-434	23.68	Widening	3rd
Tertiary Road	TR-441	269.61	Widening	3rd
Tertiary Road	TR-445	86.10	Widening	3rd
Tertiary Road	TR-448	126.62	Widening	3rd
Tertiary Road	TR-449	44.85	Widening	1st
Tertiary Road	TR-462	1.05	Widening	1st
Tertiary Road	TR-478	50.57	Widening	1st
Tertiary Road	TR-481	9.29	Widening	1st
Tertiary Road	TR-484	670.24	Widening	1st
Tertiary Road	TR-485	71.56	Widening	1st
Tertiary Road	TR-487	85.17	Widening	2nd
Tertiary Road	TR-488	624.55	Widening	2nd
Tertiary Road	TR-490	192.79	Widening	2nd
Tertiary Road	TR-491	834.28	Widening	2nd
Tertiary Road	TR-494	22.52	Widening	2nd
Tertiary Road	TR-495	298.19	Widening	2nd
Tertiary Road	TR-496	49.48	Widening	2nd
Tertiary Road	TR-502	0.05	Widening	2nd
Tertiary Road	TR-506	261.50	Widening	2nd
Tertiary Road	TR-507	35.34	Widening	2nd
Tertiary Road	TR-508	62.68	Widening	3rd
Tertiary Road	TR-509	33.37	Widening	3rd
Tertiary Road	TR-510	52.25	Widening	3rd
Tertiary Road	TR-511	67.33	Widening	3rd
Tertiary Road	TR-512	423.82	Widening	3rd
Tertiary Road	TR-514	1.83	Widening	3rd
Tertiary Road	TR-515	1.09	Widening	3rd
Tertiary Road	TR-519	93.57	Widening	1st
Tertiary Road	TR-520	680.79	Widening	1st
Tertiary Road	TR-521	47.01	Widening	1st
Tertiary Road	TR-524	69.25	Widening	1st
Tertiary Road	TR-527	35.50	Widening	1st
Tertiary Road	TR-708	17.02	Widening	1st

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-730	473.30	Widening	2nd
Tertiary Road	TR-749	535.33	Widening	2nd
Tertiary Road	TR-804	186.25	New	2nd
Tertiary Road	TR-813	164.64	New	2nd
Tertiary Road	TR-814	146.47	New	2nd
Tertiary Road	TR-864	531.27	New	2nd
Tertiary Road	TR-871	66.23	Widening	2nd
Tertiary Road	TR-872	8.38	Widening	2nd
Tertiary Road	TR-873	129.64	Widening	2nd
Tertiary Road	TR-874	105.50	Widening	2nd
Tertiary Road	TR-761	19.10	Widening	3rd
Tertiary Road	TR-767	16.30	Widening	3rd

- "TR" for tertiary road, "SR" for secondary road, and "PR" for primary road.

15.4.2.4 Drainage Development Plan

Existing drainage is mostly depending on natural drainage facilities. The proposed drainage facilities will be developed based on these natural channels. Primary drain will be connected by 2.35 km secondary drain and 9.31 km tertiary drain. Table 15.9 shows the details. **Map 15.5** represents proposed Road and Drainage Network of Ward 2.

Table15.9: Drainage Development Plan Proposals for ward 02

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
PD-1	Primary Drain	521.49	4.50-5.50	2.00-3.00	New Drain	1st
SD-6	Secondary Drain	123.07	3.50-4.50	1.25-3.00	New Drain	1st
SD-6	Secondary Drain	1088.99	3.50-4.50	1.25-3.00	New Drain	1st
SD-7	Secondary Drain	489.19	3.50-4.50	1.25-3.00	New Drain	1st
SD-22	Secondary Drain	461.99	3.50-4.50	1.25-3.00	New Drain	1st
SD-6	Secondary Drain	19.10	3.50-4.50	1.25-3.00	New Drain	1st
SD-6	Secondary Drain	16.30	3.50-4.50	1.25-3.00	New Drain	1st
SD-13	Secondary Drain	146.47	3.50-4.50	1.25-3.00	New Drain	2nd
TD-3	Tertiary Drain	4.24	2.5-3.5	0.64-1.25	New Drain	2nd
TD-45	Tertiary Drain	476.56	2.5-3.5	0.64-1.25	New Drain	2nd
TD-48	Tertiary Drain	348.69	2.5-3.5	0.64-1.25	New Drain	2nd
TD-161	Tertiary Drain	243.57	2.5-3.5	0.64-1.25	New Drain	2nd
TD-303	Tertiary Drain	126.18	2.5-3.5	0.64-1.25	New Drain	3rd
TD-332	Tertiary Drain	283.13	2.5-3.5	0.64-1.25	New Drain	3rd
TD-352	Tertiary Drain	590.84	2.5-3.5	0.64-1.25	New Drain	3rd
TD-353	Tertiary Drain	174.65	2.5-3.5	0.64-1.25	New Drain	3rd
TD-362	Tertiary Drain	175.95	2.5-3.5	0.64-1.25	New Drain	3rd
TD-364	Tertiary Drain	86.10	2.5-3.5	0.64-1.25	New Drain	3rd
TD-367	Tertiary Drain	126.62	2.5-3.5	0.64-1.25	New Drain	3rd
TD-380	Tertiary Drain	1.05	2.5-3.5	0.64-1.25	New Drain	3rd
TD-395	Tertiary Drain	50.57	2.5-3.5	0.64-1.25	New Drain	3rd
TD-398	Tertiary Drain	9.29	2.5-3.5	0.64-1.25	New Drain	3rd
TD-401	Tertiary Drain	816.14	2.5-3.5	0.64-1.25	New Drain	3rd
TD-402	Tertiary Drain	192.79	2.5-3.5	0.64-1.25	New Drain	3rd
TD-403	Tertiary Drain	834.28	2.5-3.5	0.64-1.25	New Drain	3rd
TD-406	Tertiary Drain	298.19	2.5-3.5	0.64-1.25	New Drain	3rd
TD-411	Tertiary Drain	0.05	2.5-3.5	0.64-1.25	New Drain	3rd
TD-413	Tertiary Drain	261.50	2.5-3.5	0.64-1.25	New Drain	3rd
TD-415	Tertiary Drain	423.82	2.5-3.5	0.64-1.25	New Drain	3rd
TD-417	Tertiary Drain	1.83	2.5-3.5	0.64-1.25	New Drain	3rd
TD-418	Tertiary Drain	1.09	2.5-3.5	0.64-1.25	New Drain	3rd
TD-421	Tertiary Drain	93.57	2.5-3.5	0.64-1.25	New Drain	3rd
TD-424	Tertiary Drain	69.25	2.5-3.5	0.64-1.25	New Drain	3rd
TD-572	Tertiary Drain	473.30	2.5-3.5	0.64-1.25	New Drain	3rd
TD-590	Tertiary Drain	535.33	2.5-3.5	0.64-1.25	New Drain	3rd
TD-643	Tertiary Drain	186.25	2.5-3.5	0.64-1.25	New Drain	3rd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-652	Tertiary Drain	164.64	2.5-3.5	0.64-1.25	New Drain	3rd
TD-699	Tertiary Drain	531.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-708	Tertiary Drain	66.23	2.5-3.5	0.64-1.25	New Drain	3rd
TD-709	Tertiary Drain	8.38	2.5-3.5	0.64-1.25	New Drain	3rd
TD-710	Tertiary Drain	129.64	2.5-3.5	0.64-1.25	New Drain	3rd
TD-711	Tertiary Drain	105.50	2.5-3.5	0.64-1.25	New Drain	3rd
TD-712	Tertiary Drain	1384.41	2.5-3.5	0.64-1.25	New Drain	3rd
TD-601	Tertiary Drain	19.10	2.5-3.5	0.64-1.25	New Drain	3rd
TD-607	Tertiary Drain	16.30	2.5-3.5	0.64-1.25	New Drain	3rd

Besides, it will be necessary to re-excavate all the encroached khals that serve as primary drains. The consultants have identified all existing khals that need to be re-excavated to allow smooth flow of water through them.

15.4.2.5 Urban Services

a. Solid Waste Management

The present management system as in the other wards is not satisfactory and it might lead to problem in future. 0.16 acre land is proposed as waste transfer station. It is recommended that home collection system is introduced in the ward by creation of local CBOs. This will cause organized collection of waste and prevent indiscriminate littering.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the Torkey River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement.

c. Sanitation


The Paurashava must try to promote hygienic sanitation for the whole Paurashavsa to ensure better public health.

Table15.10: Urban Service Development Proposals for ward 02

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	0.94
	Ward Center	1	1.98
Commercial Activity	Kitchen Market	1	1.45
	Slaughter House	1	1.84
Community Facility	Shamshan Ghat	1	1.27
Education & Research	Vocational Training Center	1	2.45
Open Space	Park	1	1.94
	Linear Park	1	1.95
Transportation Facilities	Truck Terminal	1	1.10
Utility Service	Electricity Line	As per existing program of PDB	-
	Waste Transfer Station	1	0.16

Map 15.6 represents proposed urban services for ward 2.

Map 15.5: Proposed Road & Drainage Network of ward no.2



Legend


- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Bridge
- Culvert
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall

Meters
0 75150 300 450 600

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT
SCPL Sheltech Consultants (Pvt.) Ltd.
1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

Map 15.6: Development Proposal of ward no.2



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

0 90 180 360 540 720 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.5 Ward Action Plan for Ward No. 03

15.5.1 Demography

Ward No. 03 is located on the West-Northern part of the town. Estimated population for the year 2031 will be 5148 in the ward with a density of 12 persons per acre. Table 15.11 shows the detail.

Table 15.11: Population Statistics of Ward No. 03

Item	Year			
	2016	2021	2026	2031
Area (acre)	428.83	428.83	428.83	428.83
Population	4364	4575	4853	5148
Density of Population (acre)	10	11	11	12

15.5.2 Ward Action Plan Proposals

15.5.2.1 Review of Existing Land Use

The maximum land of this ward at present is used for agricultural purpose. It occupies 273.18 acres of land covering more than 63.70% of the total land. Residential lands occupy about 19.61% of the land of the ward. About 55.34 acres of land is under Water bodies, 0.49% is used for commercial facilities, 1.84% circulation network. 0.28% land is utilized for educational purpose. Only 2.6 acres of land is used as community facilities with negligible percentage of urban green space (0.29%).


15.5.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.12 shows the amount of land existing and proposed uses in Ward no. 03. **Map 15.7** shows proposed land use of Ward 03.

Table15.12: Comparative Scenario of Existing and Proposed Land Use of Ward No. 03

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agriculture	273.18	63.70	1	Administrative	2.31	0.54
2	Circulation Network	7.89	1.84	2	Agriculture	184.62	43.05
3	Commercial Activities	2.09	0.49	3	Circulation Network	32.72	7.63
4	Community Facilities	2.6	0.61	4	Commercial Activities	4.93	1.15
5	Education & Research	1.19	0.28	5	Community Facilities	2.32	0.54
6	Government Office	0.13	0.03	6	Education & Research	5.66	1.32
7	Industrial	0.78	0.18	7	Industrial Facilities	13.61	3.17
8	Open space	1.24	0.29	8	Mixed use	2.08	0.48
9	Recreational facilities	0.31	0.07	9	Open Space	10.00	2.33
10	Residential area	84.08	19.61	10	Recreational Facilities	0.29	0.07
11	Water Body	55.34	12.90	11	Rural Settlement	30.74	7.17
				12	Transportation & Communication	1.63	0.38
				13	Urban Settlement	83.52	19.48
				14	Utility Service	1.99	0.46
				15	Waterbody	52.40	12.22
	Total	**428.83**	**100**		**Total**	**428.83**	**100**

Map 15.7: Landuse Plan of ward no.3



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 62.5 125 250 375 500 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com

In Association with

15.5.2.3 Proposed Road Infrastructure Development

Total 15.62 km road development proposal have been proposed for Ward no. 03. Total length of tertiary road will be 10.83 km and width of these roads will be 20 ft Total length of secondary road will be 3.92 km and width of these roads will be 40 ft. There is a primary road proposal in ward no. 03 which length is 0.87 km. Detail scenario of road network development proposal is given in table 15.13.

Table 15.13: Road Network Proposal at Ward no. 03

Type	Proposed Road ID	Length in m	Remark	Phase
Primary Road	PR-1	710.33	Widening	1st
Primary Road	PR-1	123.07	Widening	1st
Primary Road	PR-1	19.10	Widening	1st
Primary Road	PR-1	16.30	Widening	1st
Secondary Road	SR-1	771.11	Widening	1st
Secondary Road	SR-3	746.43	Widening	1st
Secondary Road	SR-8	1573.61	Widening	1st
Secondary Road	SR-11	831.83	Widening	2nd
Tertiary Road	TR-3	4.24	Widening	2nd
Tertiary Road	TR-4	26.63	Widening	2nd
Tertiary Road	TR-5	98.97	Widening	2nd
Tertiary Road	TR-6	3.40	Widening	2nd
Tertiary Road	TR-9	110.27	Widening	2nd
Tertiary Road	TR-13	159.87	Widening	2nd
Tertiary Road	TR-14	33.94	Widening	2nd
Tertiary Road	TR-15	293.33	Widening	2nd
Tertiary Road	TR-18	449.99	Widening	2nd
Tertiary Road	TR-21	333.30	Widening	2nd
Tertiary Road	TR-22	61.29	Widening	2nd
Tertiary Road	TR-23	46.54	Widening	2nd
Tertiary Road	TR-24	59.59	Widening	2nd
Tertiary Road	TR-31	22.58	Widening	2nd
Tertiary Road	TR-32	117.42	Widening	2nd
Tertiary Road	TR-36	57.23	Widening	2nd
Tertiary Road	TR-53	126.06	Widening	2nd
Tertiary Road	TR-54	66.16	Widening	2nd
Tertiary Road	TR-55	0.00	Widening	2nd
Tertiary Road	TR-68	48.83	Widening	3rd
Tertiary Road	TR-69	2.59	Widening	3rd
Tertiary Road	TR-71	169.28	Widening	3rd
Tertiary Road	TR-399	14.98	Widening	3rd
Tertiary Road	TR-400	291.92	Widening	3rd
Tertiary Road	TR-401	73.75	Widening	3rd
Tertiary Road	TR-402	70.79	Widening	3rd
Tertiary Road	TR-403	78.42	Widening	3rd
Tertiary Road	TR-404	209.51	Widening	3rd
Tertiary Road	TR-405	97.64	Widening	3rd
Tertiary Road	TR-406	105.85	Widening	3rd
Tertiary Road	TR-407	220.11	Widening	3rd
Tertiary Road	TR-408	66.56	Widening	3rd
Tertiary Road	TR-416	25.35	Widening	3rd
Tertiary Road	TR-427	123.80	Widening	3rd
Tertiary Road	TR-428	28.79	Widening	3rd
Tertiary Road	TR-429	277.06	Widening	3rd
Tertiary Road	TR-430	94.86	Widening	3rd
Tertiary Road	TR-431	319.50	Widening	3rd
Tertiary Road	TR-471	163.52	Widening	3rd
Tertiary Road	TR-472	712.59	Widening	3rd
Tertiary Road	TR-473	42.86	Widening	3rd
Tertiary Road	TR-474	669.92	Widening	3rd
Tertiary Road	TR-475	44.40	Widening	3rd
Tertiary Road	TR-476	33.04	Widening	1st

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-477	215.26	Widening	1st
Tertiary Road	TR-479	165.23	Widening	1st
Tertiary Road	TR-482	73.53	Widening	1st
Tertiary Road	TR-483	0.09	Widening	1st
Tertiary Road	TR-486	0.01	Widening	1st
Tertiary Road	TR-489	31.80	Widening	1st
Tertiary Road	TR-490	208.90	Widening	2nd
Tertiary Road	TR-492	70.93	Widening	2nd
Tertiary Road	TR-493	275.65	Widening	2nd
Tertiary Road	TR-497	71.22	Widening	2nd
Tertiary Road	TR-498	176.23	Widening	2nd
Tertiary Road	TR-499	43.20	Widening	2nd
Tertiary Road	TR-500	539.57	Widening	2nd
Tertiary Road	TR-503	213.69	Widening	2nd
Tertiary Road	TR-504	29.42	Widening	2nd
Tertiary Road	TR-505	24.30	Widening	2nd
Tertiary Road	TR-715	95.28	Widening	2nd
Tertiary Road	TR-726	36.16	Widening	2nd
Tertiary Road	TR-806	574.45	New	2nd
Tertiary Road	TR-807	280.71	Widening	2nd
Tertiary Road	TR-808	119.08	Widening	2nd
Tertiary Road	TR-809	6.39	Widening	2nd
Tertiary Road	TR-810	146.00	Widening	2nd
Tertiary Road	TR-811	243.74	Widening	2nd
Tertiary Road	TR-862	212.82	New	2nd
Tertiary Road	TR-876	27.03	Widening	2nd
Tertiary Road	TR-884	103.75	Widening	3rd
Tertiary Road	TR-885	343.09	Widening	3rd
Tertiary Road	TR-886	203.39	Widening	3rd
Tertiary Road	TR-887	209.25	Widening	3rd
Tertiary Road	TR-761	19.10	Widening	3rd
Tertiary Road	TR-767	16.30	Widening	3rd

- "TR" for tertiary road, "SR" for secondary road, and "PR" for primary road

15.5.2.4 Drainage Development Plan

Existing drainage is mostly depending on natural drainage facilities. The proposed drainage facilities will be developed based on these natural channels. These will serve as primary drain for the ward which will be connected by 2.77 km secondary drain and 12.28 km tertiary drain. Table 15.14 shows the detail.


Table 15.14: Drainage Development Plan Proposals for ward 03

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
PD-3	Primary Drain	26.46	4.50-5.50	2.00-3.00	New Drain	1st
SD-6	Secondary Drain	1383.25	3.50-4.50	1.25-3.00	New Drain	1st
SD-6	Secondary Drain	123.07	3.50-4.50	1.25-3.00	New Drain	1st
SD-27	Secondary Drain	1229.46	3.50-4.50	1.25-3.00	New Drain	1st
SD-6	Secondary Drain	19.10	3.50-4.50	1.25-3.00	New Drain	1st
SD-6	Secondary Drain	16.30	3.50-4.50	1.25-3.00	New Drain	1st
TD-3	Tertiary Drain	4.24	2.5-3.5	0.64-1.25	New Drain	2nd
TD-4	Tertiary Drain	26.63	2.5-3.5	0.64-1.25	New Drain	2nd
TD-5	Tertiary Drain	98.97	2.5-3.5	0.64-1.25	New Drain	2nd
TD-6	Tertiary Drain	3.40	2.5-3.5	0.64-1.25	New Drain	2nd
TD-9	Tertiary Drain	110.27	2.5-3.5	0.64-1.25	New Drain	2nd
TD-13	Tertiary Drain	159.87	2.5-3.5	0.64-1.25	New Drain	2nd
TD-14	Tertiary Drain	33.94	2.5-3.5	0.64-1.25	New Drain	2nd
TD-15	Tertiary Drain	293.33	2.5-3.5	0.64-1.25	New Drain	2nd
TD-18	Tertiary Drain	576.05	2.5-3.5	0.64-1.25	New Drain	2nd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-21	Tertiary Drain	333.30	2.5-3.5	0.64-1.25	New Drain	2nd
TD-22	Tertiary Drain	61.29	2.5-3.5	0.64-1.25	New Drain	2nd
TD-23	Tertiary Drain	46.54	2.5-3.5	0.64-1.25	New Drain	2nd
TD-24	Tertiary Drain	59.59	2.5-3.5	0.64-1.25	New Drain	2nd
TD-30	Tertiary Drain	117.42	2.5-3.5	0.64-1.25	New Drain	2nd
TD-34	Tertiary Drain	57.23	2.5-3.5	0.64-1.25	New Drain	2nd
TD-42	Tertiary Drain	66.16	2.5-3.5	0.64-1.25	New Drain	2nd
TD-43	Tertiary Drain	0.00	2.5-3.5	0.64-1.25	New Drain	2nd
TD-52	Tertiary Drain	48.83	2.5-3.5	0.64-1.25	New Drain	2nd
TD-53	Tertiary Drain	2.59	2.5-3.5	0.64-1.25	New Drain	2nd
TD-96	Tertiary Drain	382.10	2.5-3.5	0.64-1.25	New Drain	2nd
TD-293	Tertiary Drain	1546.91	2.5-3.5	0.64-1.25	New Drain	3rd
TD-321	Tertiary Drain	14.98	2.5-3.5	0.64-1.25	New Drain	3rd
TD-322	Tertiary Drain	291.92	2.5-3.5	0.64-1.25	New Drain	3rd
TD-323	Tertiary Drain	73.75	2.5-3.5	0.64-1.25	New Drain	3rd
TD-324	Tertiary Drain	70.79	2.5-3.5	0.64-1.25	New Drain	3rd
TD-325	Tertiary Drain	78.42	2.5-3.5	0.64-1.25	New Drain	3rd
TD-326	Tertiary Drain	209.51	2.5-3.5	0.64-1.25	New Drain	3rd
TD-327	Tertiary Drain	97.64	2.5-3.5	0.64-1.25	New Drain	3rd
TD-328	Tertiary Drain	105.85	2.5-3.5	0.64-1.25	New Drain	3rd
TD-329	Tertiary Drain	220.11	2.5-3.5	0.64-1.25	New Drain	3rd
TD-330	Tertiary Drain	66.56	2.5-3.5	0.64-1.25	New Drain	3rd
TD-337	Tertiary Drain	25.35	2.5-3.5	0.64-1.25	New Drain	3rd
TD-343	Tertiary Drain	5.94	2.5-3.5	0.64-1.25	New Drain	3rd
TD-347	Tertiary Drain	831.83	2.5-3.5	0.64-1.25	New Drain	3rd
TD-348	Tertiary Drain	123.80	2.5-3.5	0.64-1.25	New Drain	3rd
TD-349	Tertiary Drain	277.06	2.5-3.5	0.64-1.25	New Drain	3rd
TD-350	Tertiary Drain	94.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-351	Tertiary Drain	319.50	2.5-3.5	0.64-1.25	New Drain	3rd
TD-389	Tertiary Drain	163.52	2.5-3.5	0.64-1.25	New Drain	3rd
TD-390	Tertiary Drain	42.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-391	Tertiary Drain	669.92	2.5-3.5	0.64-1.25	New Drain	3rd
TD-394	Tertiary Drain	215.26	2.5-3.5	0.64-1.25	New Drain	3rd
TD-396	Tertiary Drain	165.23	2.5-3.5	0.64-1.25	New Drain	3rd
TD-399	Tertiary Drain	0.09	2.5-3.5	0.64-1.25	New Drain	3rd
TD-400	Tertiary Drain	0.01	2.5-3.5	0.64-1.25	New Drain	3rd
TD-402	Tertiary Drain	208.90	2.5-3.5	0.64-1.25	New Drain	3rd
TD-404	Tertiary Drain	275.65	2.5-3.5	0.64-1.25	New Drain	3rd
TD-407	Tertiary Drain	71.22	2.5-3.5	0.64-1.25	New Drain	3rd
TD-408	Tertiary Drain	176.23	2.5-3.5	0.64-1.25	New Drain	3rd
TD-409	Tertiary Drain	539.57	2.5-3.5	0.64-1.25	New Drain	3rd
TD-412	Tertiary Drain	213.69	2.5-3.5	0.64-1.25	New Drain	3rd
TD-569	Tertiary Drain	36.16	2.5-3.5	0.64-1.25	New Drain	3rd
TD-645	Tertiary Drain	842.94	2.5-3.5	0.64-1.25	New Drain	3rd
TD-646	Tertiary Drain	280.71	2.5-3.5	0.64-1.25	New Drain	3rd
TD-647	Tertiary Drain	119.08	2.5-3.5	0.64-1.25	New Drain	3rd
TD-648	Tertiary Drain	6.39	2.5-3.5	0.64-1.25	New Drain	3rd
TD-649	Tertiary Drain	146.00	2.5-3.5	0.64-1.25	New Drain	3rd
TD-650	Tertiary Drain	243.74	2.5-3.5	0.64-1.25	New Drain	3rd
TD-714	Tertiary Drain	27.03	2.5-3.5	0.64-1.25	New Drain	3rd
TD-721	Tertiary Drain	103.75	2.5-3.5	0.64-1.25	New Drain	3rd
TD-722	Tertiary Drain	343.09	2.5-3.5	0.64-1.25	New Drain	3rd
TD-723	Tertiary Drain	203.39	2.5-3.5	0.64-1.25	New Drain	3rd
TD-724	Tertiary Drain	209.25	2.5-3.5	0.64-1.25	New Drain	3rd
TD-601	Tertiary Drain	19.10	2.5-3.5	0.64-1.25	New Drain	3rd
TD-607	Tertiary Drain	16.30	2.5-3.5	0.64-1.25	New Drain	3rd

Map 15.8 represents Road and Drainage Network for ward 3.

Map 15.8: Proposed Road & Drainage Network of ward no.3



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Bridge
- Culvert
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall

Meters
0 55110 220 330 440

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT
SCPL Sheltech Consultants (Pvt.) Ltd.
1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.5.2.5 Urban Services

a. Solid Waste Management

The consultant proposes a waste transfer station with 0.44 acre. It is recommended that home collection system is introduced in the ward by creation of local CBOs. This will create organized collection of waste and prevent indiscriminate littering.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the Torkey River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement. An Overhead Tank of 1.54 acre land has been proposed.

c. Sanitation


The Paurashava must try to promote hygienic sanitation for the whole Paurashavsa to ensure better public health.

Table 15.15: Urban Service Development Proposals for ward 03

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	1.88
	Toll Center	1	0.31
Commercial Activity	Retailsale Market	1	3.42
Education & Research	Primary School	1	2.82
	Secondary School	1	1.75
Industrial	Industrial Zone	1	12.87
Open Space	Park	1	3.40
	Playground	2	4.88
Transportation Facilities	Truck Terminal	1	1.63
Utility Service	Electricity Line	As per existing program of PDB	-
	Waste Transfer Station	1	0.44
	Overhead Tank	1	1.54

Map 15.9 represents proposed urban services for ward 3.

Map 15.9: Development Proposal of ward no.3



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

0 62.5 125 250 375 500 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.6 Ward Action Plan for Ward No. 04

15.6.1 Demography

Ward no. 4 is located on the middle part of the town. Population projection shows that 4969 people would be living in the ward in the year 2031 with a very density of 15 persons per acre. Table 15.16 shows the detail.

Table 15.16: Population Statistics of Ward No. 04

Item	Year			
	2016	2021	2026	2031
Area (acre)	341.12	341.12	341.12	341.12
Population	4212	4416	4684	4969
Density of Population (acre)	12	13	14	15

15.6.2 Ward Action Plan Proposals

15.6.2.1 Review of Existing Land Use

Out of total 341.12 acre 198.81 acre of land i.e. 58.28% is used as agricultural use. The next use is residential; 69.45 acres are used in this purpose. It occupies more than 20% of total land. Water bodies occupy 13.99% land of the ward. Almost 0.49 acre of land is used for educational purpose. At present 4.82 acres of land are used in commercial purpose. About 2.19% is used as circulation network.


15.6.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.17 shows the amount of land existing and proposed uses in Ward no. 04. **Map 15.10** shows proposed land use of Ward 04.

Table 15.17: Comparative Scenario of Existing and Proposed Land Uses of Ward No. 04

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agriculture	198.81	58.28	1	Administrative	9.50	2.78
2	Circulation Network	7.48	2.19	2	Agriculture	73.03	21.41
3	Commercial Activities	4.82	1.41	3	Circulation Network	35.39	10.38
4	Community Facilities	0.76	0.22	4	Commercial Activities	4.27	1.25
5	Education & Research	0.49	0.14	5	Community Facilities	0.61	0.18
6	Government Office	9.46	2.77	6	Educational & Research	8.68	2.55
7	Health facilities	0.63	0.18	7	Health Facilities	0.56	0.16
8	Industrial	0.31	0.09	8	Industrial Facilities	0.21	0.06
9	Mixed Use	0.42	0.12	9	Mixed Use	17.83	5.23
10	NGO office	0.16	0.05	10	Open Space	5.68	1.67
11	Open space	0.62	0.18	11	Recreational	2.09	0.61
12	Residential area	69.45	20.36	12	Rural Settlement	39.45	11.56
13	Water Body	47.71	13.99	13	Transportation & Communication	1.21	0.35
				14	Urban Settlement	90.26	26.46
				15	Utility Service	0.35	0.10
				16	Waterbody	52.01	15.25
	Total	**341.12**	**100**		**Total**	**341.12**	**100**

Map 15.10: Landuse Plan of ward no.4



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 60 120 240 360 480 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.6.2.3 Proposed Road Infrastructure Development

Total 15.43 km road development proposal have been proposed for Ward no. 04. Total length of tertiary road will be 11.93 km and width of these roads will be 20 ft. Total length of secondary road will be 2.37 km and width of these roads will be 40 to 60 ft for this ward and total length of primary road will be 1.13 km and width of these roads will be 100 ft. Detail scenario of road network development proposal was given in Table 15.18.

Table 15.18: Road Network Proposal at Ward no. 04

Type	Proposed Road ID	Length in m	Remark	Phase
Primary Road	PR-1	1130.37	Widening	1st
Secondary Road	SR-1	602.09	Widening	1st
Secondary Road	SR-5	741.02	Widening	1st
Secondary Road	SR-17	825.34	New	1st
Secondary Road	SR-23	199.81	Widening	2nd
Tertiary Road	TR-20	2.39	Widening	2nd
Tertiary Road	TR-26	83.65	Widening	2nd
Tertiary Road	TR-27	384.35	Widening	2nd
Tertiary Road	TR-28	418.06	Widening	2nd
Tertiary Road	TR-34	256.92	Widening	2nd
Tertiary Road	TR-35	648.40	Widening	2nd
Tertiary Road	TR-38	3.27	Widening	2nd
Tertiary Road	TR-39	50.90	Widening	2nd
Tertiary Road	TR-40	337.53	Widening	2nd
Tertiary Road	TR-41	35.10	Widening	2nd
Tertiary Road	TR-42	52.43	Widening	2nd
Tertiary Road	TR-43	386.87	Widening	2nd
Tertiary Road	TR-44	115.69	Widening	2nd
Tertiary Road	TR-45	35.45	Widening	2nd
Tertiary Road	TR-46	271.93	Widening	2nd
Tertiary Road	TR-47	62.38	Widening	2nd
Tertiary Road	TR-48	36.91	Widening	2nd
Tertiary Road	TR-49	23.08	Widening	2nd
Tertiary Road	TR-50	29.72	Widening	2nd
Tertiary Road	TR-51	25.64	Widening	2nd
Tertiary Road	TR-52	29.19	Widening	2nd
Tertiary Road	TR-53	598.88	Widening	2nd
Tertiary Road	TR-55	0.00	Widening	2nd
Tertiary Road	TR-56	20.06	Widening	2nd
Tertiary Road	TR-57	152.28	Widening	2nd
Tertiary Road	TR-58	35.48	Widening	2nd
Tertiary Road	TR-60	15.01	Widening	2nd
Tertiary Road	TR-62	16.96	Widening	2nd
Tertiary Road	TR-64	16.68	Widening	2nd
Tertiary Road	TR-65	166.01	Widening	3rd
Tertiary Road	TR-66	34.53	Widening	3rd
Tertiary Road	TR-67	31.07	Widening	3rd
Tertiary Road	TR-108	287.69	Widening	3rd
Tertiary Road	TR-110	25.17	Widening	3rd
Tertiary Road	TR-111	287.18	Widening	3rd
Tertiary Road	TR-112	24.87	Widening	3rd
Tertiary Road	TR-113	1042.63	Widening	3rd
Tertiary Road	TR-116	12.97	Widening	3rd
Tertiary Road	TR-117	13.36	Widening	3rd
Tertiary Road	TR-118	97.90	Widening	3rd
Tertiary Road	TR-119	159.13	Widening	3rd
Tertiary Road	TR-121	33.24	Widening	1st
Tertiary Road	TR-128	82.67	Widening	1st
Tertiary Road	TR-188	50.24	Widening	1st
Tertiary Road	TR-189	86.54	Widening	1st
Tertiary Road	TR-190	73.66	Widening	2nd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-191	63.81	Widening	2nd
Tertiary Road	TR-192	66.79	Widening	2nd
Tertiary Road	TR-193	36.99	Widening	2nd
Tertiary Road	TR-195	174.65	Widening	2nd
Tertiary Road	TR-199	17.27	Widening	2nd
Tertiary Road	TR-201	165.55	Widening	2nd
Tertiary Road	TR-202	99.06	Widening	2nd
Tertiary Road	TR-203	29.69	Widening	2nd
Tertiary Road	TR-204	27.80	Widening	2nd
Tertiary Road	TR-205	20.10	Widening	2nd
Tertiary Road	TR-206	55.33	Widening	2nd
Tertiary Road	TR-207	50.96	Widening	2nd
Tertiary Road	TR-454	686.97	Widening	2nd
Tertiary Road	TR-513	59.88	Widening	2nd
Tertiary Road	TR-515	143.71	Widening	2nd
Tertiary Road	TR-516	165.91	Widening	2nd
Tertiary Road	TR-517	141.48	Widening	2nd
Tertiary Road	TR-518	35.90	Widening	2nd
Tertiary Road	TR-526	4.39	Widening	2nd
Tertiary Road	TR-711	37.04	Widening	2nd
Tertiary Road	TR-712	170.61	Widening	2nd
Tertiary Road	TR-740	115.82	Widening	2nd
Tertiary Road	TR-812	332.68	New	2nd
Tertiary Road	TR-814	410.04	New	2nd
Tertiary Road	TR-815	254.03	New	2nd
Tertiary Road	TR-816	188.06	New	2nd
Tertiary Road	TR-855	81.51	New	2nd
Tertiary Road	TR-862	544.14	New	2nd
Tertiary Road	TR-863	292.63	New	2nd
Tertiary Road	TR-864	393.66	New	3rd
Tertiary Road	TR-865	406.69	New	3rd
Tertiary Road	TR-877	7.63	Widening	3rd

- "TR" for tertiary road, "SR" for secondary road, and "PR" for primary road

15.6.2.4 Drainage Development Plan

There is manmade drainage facility at Ward no. 04 of Gauranadi Paurashava. Existing drainage is mostly depending on natural drainage facilities. Table 15.19 shows the detail.

Table 15.19: Drainage Development Plan Proposals for ward 04


Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
PD-1	Primary Drain	199.81	4.50-5.50	2.00-3.00	New Drain	1st
SD-6	Secondary Drain	1130.37	3.50-4.50	1.25-3.00	New Drain	1st
SD-22	Secondary Drain	123.36	3.50-4.50	1.25-3.00	New Drain	1st
SD-27	Secondary Drain	602.09	3.50-4.50	1.25-3.00	New Drain	1st
SD-13	Secondary Drain	410.04	3.50-4.50	1.25-3.00	New Drain	2nd
TD-18	Tertiary Drain	475.51	2.5-3.5	0.64-1.25	New Drain	2nd
TD-20	Tertiary Drain	2.39	2.5-3.5	0.64-1.25	New Drain	2nd
TD-26	Tertiary Drain	83.65	2.5-3.5	0.64-1.25	New Drain	2nd
TD-27	Tertiary Drain	384.35	2.5-3.5	0.64-1.25	New Drain	2nd
TD-28	Tertiary Drain	418.06	2.5-3.5	0.64-1.25	New Drain	2nd
TD-32	Tertiary Drain	256.92	2.5-3.5	0.64-1.25	New Drain	2nd
TD-33	Tertiary Drain	648.40	2.5-3.5	0.64-1.25	New Drain	2nd
TD-36	Tertiary Drain	3.27	2.5-3.5	0.64-1.25	New Drain	2nd
TD-37	Tertiary Drain	337.53	2.5-3.5	0.64-1.25	New Drain	2nd
TD-38	Tertiary Drain	386.87	2.5-3.5	0.64-1.25	New Drain	2nd
TD-39	Tertiary Drain	115.69	2.5-3.5	0.64-1.25	New Drain	2nd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-40	Tertiary Drain	271.93	2.5-3.5	0.64-1.25	New Drain	2nd
TD-43	Tertiary Drain	0.00	2.5-3.5	0.64-1.25	New Drain	2nd
TD-44	Tertiary Drain	20.06	2.5-3.5	0.64-1.25	New Drain	2nd
TD-45	Tertiary Drain	152.28	2.5-3.5	0.64-1.25	New Drain	2nd
TD-48	Tertiary Drain	166.01	2.5-3.5	0.64-1.25	New Drain	2nd
TD-85	Tertiary Drain	275.00	2.5-3.5	0.64-1.25	New Drain	2nd
TD-87	Tertiary Drain	287.18	2.5-3.5	0.64-1.25	New Drain	2nd
TD-88	Tertiary Drain	1042.63	2.5-3.5	0.64-1.25	New Drain	2nd
TD-91	Tertiary Drain	97.90	2.5-3.5	0.64-1.25	New Drain	2nd
TD-92	Tertiary Drain	159.13	2.5-3.5	0.64-1.25	New Drain	2nd
TD-94	Tertiary Drain	33.24	2.5-3.5	0.64-1.25	New Drain	2nd
TD-96	Tertiary Drain	544.15	2.5-3.5	0.64-1.25	New Drain	2nd
TD-101	Tertiary Drain	82.67	2.5-3.5	0.64-1.25	New Drain	2nd
TD-154	Tertiary Drain	50.24	2.5-3.5	0.64-1.25	New Drain	2nd
TD-155	Tertiary Drain	86.54	2.5-3.5	0.64-1.25	New Drain	2nd
TD-156	Tertiary Drain	73.66	2.5-3.5	0.64-1.25	New Drain	2nd
TD-157	Tertiary Drain	63.81	2.5-3.5	0.64-1.25	New Drain	2nd
TD-158	Tertiary Drain	66.79	2.5-3.5	0.64-1.25	New Drain	2nd
TD-159	Tertiary Drain	36.99	2.5-3.5	0.64-1.25	New Drain	2nd
TD-161	Tertiary Drain	1741.01	2.5-3.5	0.64-1.25	New Drain	2nd
TD-165	Tertiary Drain	17.27	2.5-3.5	0.64-1.25	New Drain	2nd
TD-167	Tertiary Drain	165.55	2.5-3.5	0.64-1.25	New Drain	2nd
TD-168	Tertiary Drain	99.06	2.5-3.5	0.64-1.25	New Drain	2nd
TD-169	Tertiary Drain	29.69	2.5-3.5	0.64-1.25	New Drain	2nd
TD-170	Tertiary Drain	27.80	2.5-3.5	0.64-1.25	New Drain	2nd
TD-171	Tertiary Drain	20.10	2.5-3.5	0.64-1.25	New Drain	2nd
TD-172	Tertiary Drain	55.33	2.5-3.5	0.64-1.25	New Drain	2nd
TD-173	Tertiary Drain	50.96	2.5-3.5	0.64-1.25	New Drain	2nd
TD-372	Tertiary Drain	686.97	2.5-3.5	0.64-1.25	New Drain	3rd
TD-416	Tertiary Drain	59.88	2.5-3.5	0.64-1.25	New Drain	3rd
TD-418	Tertiary Drain	143.71	2.5-3.5	0.64-1.25	New Drain	3rd
TD-419	Tertiary Drain	165.91	2.5-3.5	0.64-1.25	New Drain	3rd
TD-420	Tertiary Drain	141.48	2.5-3.5	0.64-1.25	New Drain	3rd
TD-426	Tertiary Drain	4.39	2.5-3.5	0.64-1.25	New Drain	3rd
TD-558	Tertiary Drain	37.04	2.5-3.5	0.64-1.25	New Drain	3rd
TD-559	Tertiary Drain	170.61	2.5-3.5	0.64-1.25	New Drain	3rd
TD-581	Tertiary Drain	115.82	2.5-3.5	0.64-1.25	New Drain	3rd
TD-651	Tertiary Drain	332.68	2.5-3.5	0.64-1.25	New Drain	3rd
TD-653	Tertiary Drain	254.03	2.5-3.5	0.64-1.25	New Drain	3rd
TD-654	Tertiary Drain	188.06	2.5-3.5	0.64-1.25	New Drain	3rd
TD-691	Tertiary Drain	81.51	2.5-3.5	0.64-1.25	New Drain	3rd
TD-698	Tertiary Drain	292.63	2.5-3.5	0.64-1.25	New Drain	3rd
TD-699	Tertiary Drain	393.66	2.5-3.5	0.64-1.25	New Drain	3rd
TD-700	Tertiary Drain	406.69	2.5-3.5	0.64-1.25	New Drain	3rd
TD-715	Tertiary Drain	7.63	2.5-3.5	0.64-1.25	New Drain	3rd

Besides, it will be necessary to re-excavate the khals that serve as primary drains.

Map 15.11 represents proposed Road and Drainage Network for Ward 4.

Map 15.11: Proposed Road & Drainage Network of ward no.4



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Bridge
- Culvert
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall

0 50100 200 300 400 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.6.2.5 Urban Services

a. Solid Waste Management

The consultant proposes two solid waste transfer stations at ward 4 consisting of 0.21 acre and 0.14 acre land.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the nearest River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement.

c. Sanitation


The Paurashava must try to promote hygienic sanitation for the whole Paurashavsa to ensure better public health.

Table 15.20: Urban Service Development Proposals for ward 04

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	0.50
Education & Research	College	1	5.31
	High School	1	2.97
Open Space	Park	1	1.75
	Playground	1	2.67
Recreational Facilities	Shishu Park	1	2.09
Transportation Facilities	Fuel Station	1	1.21
Utility Service	Electricity Line	As per existing program of PDB	
	Waste Transfer Station	2	0.35

Map 15.12 represents proposed urban services for ward 4.

Map 15.12: Development Proposal of ward no.4



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

0 60 120 240 360 480 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.7 Ward Action Plan for Ward No. 05

15.7.1 Demography

Ward No. 5 is located on the Eastern part of the town. It is the smallest ward with a high density of 24 persons per acre in the year 2031 with a total population of 7179. Table 15.21 shows the detail.

Table 15.21: Population Statistics of Ward No. 05

Item	Year			
	2016	2021	2026	2031
Area (acre)	298.79	298.79	298.79	298.79
Population	6086	6380	6768	7179
Density of Population (acre)	20	21	23	24

15.7.2 Ward Action Plan Proposals

15.7.2.1 Review of Existing Land Use

Out of total 298.19 acres of land i.e. 44.47% is used as agricultural land and 30.71% is for residential use. Water bodies occupy 12.32% land of the ward. At present only 0.81 acres of land are used in commercial purpose whereas only 2.76% is used as circulation network. Only 0.20 acre of land is used as open space.


15.7.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.22 shows the amount of land existing and proposed uses in Ward no. 5. **Map 15.13** shows proposed land use of Ward 05.

Table 15.22: Comparative Scenario of Existing and Proposed Land Use of Ward No. 05

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agriculture	132.62	44.47	1	Administrative	18.98	6.37
2	Circulation Network	8.24	2.76	2	Agriculture	57.46	19.27
3	Commercial Activities	2.41	0.81	3	Circulation Network	29.08	9.75
4	Community Facilities	0.76	0.25	4	Commercial Activities	2.60	0.87
5	Education & Research	4.33	1.45	5	Community Facilities	2.92	0.98
6	Government Office	20.19	6.77	6	Education & Research	4.12	1.38
7	Health facilities	0.3	0.10	7	Health Facilities	3.47	1.16
8	Mixed Use	0.59	0.20	8	Mixed Use	18.44	6.18
9	NGO office	0.23	0.08	9	Open Space	8.55	2.87
10	Open space	0.2	0.07	10	Recreational	0.40	0.13
11	Residential area	91.57	30.71	11	Urban Settlement	116.18	38.96
12	Water Body	36.74	12.32	12	Utility Service	0.52	0.17
				13	Waterbody	35.46	11.89
	Total	**298.19**	**100**		**Total**	**298.19**	**100**

Map 15.13: Landuse Plan of ward no.5



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 45 90 180 270 360 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com

In Association with

15.7.2.3 Proposed Road Infrastructure Development

Total 16.53 km road development proposal have been proposed in first Ward Action Plan for Ward no. 05. Tertiary road covers 14.20 km having width of 20 ft. Secondary road covers 2.33 km having width of 40 to 60 ft. Detail scenario of road network development proposal was given in table 15.23.

Table 15.23: Road Network Proposal at Ward no. 05

Type	Proposed Road ID	Length in m	Remark	Phase
Secondary Road	SR-7	763.57	Widening	2nd
Secondary Road	SR-13	38.15	Widening	2nd
Secondary Road	SR-14	703.70	Widening	2nd
Secondary Road	SR-22	827.05	Widening	2nd
Tertiary Road	TR-115	75.95	Widening	2nd
Tertiary Road	TR-133	203.15	Widening	2nd
Tertiary Road	TR-134	216.83	Widening	2nd
Tertiary Road	TR-135	144.05	Widening	2nd
Tertiary Road	TR-136	732.85	Widening	2nd
Tertiary Road	TR-137	48.53	Widening	2nd
Tertiary Road	TR-138	43.25	Widening	2nd
Tertiary Road	TR-143	608.54	Widening	2nd
Tertiary Road	TR-144	15.49	Widening	2nd
Tertiary Road	TR-163	506.11	Widening	2nd
Tertiary Road	TR-164	95.22	Widening	2nd
Tertiary Road	TR-165	68.03	Widening	2nd
Tertiary Road	TR-166	17.46	Widening	2nd
Tertiary Road	TR-167	26.33	Widening	3rd
Tertiary Road	TR-169	329.25	Widening	3rd
Tertiary Road	TR-170	66.52	Widening	3rd
Tertiary Road	TR-194	181.88	Widening	3rd
Tertiary Road	TR-196	366.97	Widening	3rd
Tertiary Road	TR-197	176.12	Widening	3rd
Tertiary Road	TR-198	61.52	Widening	3rd
Tertiary Road	TR-200	1.42	Widening	3rd
Tertiary Road	TR-208	150.86	Widening	3rd
Tertiary Road	TR-209	129.42	Widening	3rd
Tertiary Road	TR-210	96.49	Widening	3rd
Tertiary Road	TR-211	43.24	Widening	3rd
Tertiary Road	TR-212	243.41	Widening	3rd
Tertiary Road	TR-213	36.98	Widening	3rd
Tertiary Road	TR-214	34.93	Widening	3rd
Tertiary Road	TR-215	92.92	Widening	3rd
Tertiary Road	TR-216	17.36	Widening	3rd
Tertiary Road	TR-217	109.69	Widening	3rd
Tertiary Road	TR-218	924.85	Widening	2nd
Tertiary Road	TR-219	36.42	Widening	2nd
Tertiary Road	TR-220	22.98	Widening	2nd
Tertiary Road	TR-221	29.46	Widening	2nd
Tertiary Road	TR-222	329.53	Widening	2nd
Tertiary Road	TR-223	168.83	Widening	2nd
Tertiary Road	TR-224	134.64	Widening	2nd
Tertiary Road	TR-225	45.51	Widening	2nd
Tertiary Road	TR-226	85.45	Widening	2nd
Tertiary Road	TR-227	246.39	Widening	2nd
Tertiary Road	TR-228	27.46	Widening	2nd
Tertiary Road	TR-229	94.41	Widening	2nd
Tertiary Road	TR-232	645.13	Widening	2nd
Tertiary Road	TR-233	112.19	Widening	2nd
Tertiary Road	TR-234	127.78	Widening	2nd
Tertiary Road	TR-235	30.08	Widening	2nd
Tertiary Road	TR-236	428.06	Widening	2nd
Tertiary Road	TR-237	42.35	Widening	3rd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-238	51.88	Widening	3rd
Tertiary Road	TR-239	90.59	Widening	3rd
Tertiary Road	TR-240	62.76	Widening	3rd
Tertiary Road	TR-241	111.53	Widening	3rd
Tertiary Road	TR-288	59.48	Widening	3rd
Tertiary Road	TR-289	43.24	Widening	3rd
Tertiary Road	TR-290	31.71	Widening	3rd
Tertiary Road	TR-332	8.49	Widening	3rd
Tertiary Road	TR-528	61.85	Widening	3rd
Tertiary Road	TR-529	58.12	Widening	3rd
Tertiary Road	TR-530	17.81	Widening	3rd
Tertiary Road	TR-531	53.64	Widening	3rd
Tertiary Road	TR-532	52.59	Widening	3rd
Tertiary Road	TR-538	266.84	Widening	3rd
Tertiary Road	TR-551	0.96	Widening	3rd
Tertiary Road	TR-557	79.38	Widening	3rd
Tertiary Road	TR-560	135.64	Widening	3rd
Tertiary Road	TR-561	384.86	Widening	2nd
Tertiary Road	TR-562	37.88	Widening	2nd
Tertiary Road	TR-563	46.96	Widening	2nd
Tertiary Road	TR-569	188.03	Widening	2nd
Tertiary Road	TR-570	76.78	Widening	2nd
Tertiary Road	TR-573	158.48	Widening	2nd
Tertiary Road	TR-613	82.46	Widening	2nd
Tertiary Road	TR-627	98.62	Widening	2nd
Tertiary Road	TR-630	57.21	Widening	2nd
Tertiary Road	TR-714	99.19	Widening	2nd
Tertiary Road	TR-716	9.08	Widening	2nd
Tertiary Road	TR-717	53.94	Widening	2nd
Tertiary Road	TR-718	16.82	Widening	2nd
Tertiary Road	TR-719	82.52	Widening	2nd
Tertiary Road	TR-724	1060.34	Widening	2nd
Tertiary Road	TR-737	38.30	Widening	2nd
Tertiary Road	TR-738	52.49	Widening	2nd
Tertiary Road	TR-739	49.92	Widening	3rd
Tertiary Road	TR-742	139.53	Widening	3rd
Tertiary Road	TR-743	44.97	Widening	3rd
Tertiary Road	TR-758	42.12	Widening	3rd
Tertiary Road	TR-829	69.41	New	3rd
Tertiary Road	TR-832	104.13	New	3rd
Tertiary Road	TR-833	654.49	New	3rd
Tertiary Road	TR-856	43.11	New	3rd
Tertiary Road	TR-857	326.50	New	3rd
Tertiary Road	TR-881	3.38	Widening	3rd
Tertiary Road	TR-882	517.43	Widening	3rd

- “TR” for tertiary road, and “SR” for secondary road.

15.7.2.4 Drainage Development Plan

There are both natural and manmade drainage facilities at ward no. 05. Existing drainage is mostly depending on natural drainage facilities; the proposed drainage facilities will be developed based on this natural channel. These will be served as primary drain which will be connected with 1.56 km secondary drain and 13.45 km tertiary drain in first Ward Action Plan. Table 1.24 shows the detail.

Table 15.24: Drainage Development Plan Proposals for ward 05


Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
PD-4	Primary Drain	1.36	4.50-5.50	2.00-3.00	New Drain	1st
PD-5	Primary Drain	33.66	4.50-5.50	2.00-3.00	New Drain	1st
PD-6	Primary Drain	234.38	4.50-5.50	2.00-3.00	New Drain	1st
PD-7	Primary Drain	512.50	4.50-5.50	2.00-3.00	New Drain	1st
SD-2	Secondary Drain	847.51	3.50-4.50	1.25-3.00	New Drain	1st
SD-8	Secondary Drain	38.15	3.50-4.50	1.25-3.00	New Drain	1st
SD-23	Secondary Drain	0.62	3.50-4.50	1.25-3.00	New Drain	1st
SD-24	Secondary Drain	276.74	3.50-4.50	1.25-3.00	New Drain	1st
SD-25	Secondary Drain	365.22	3.50-4.50	1.25-3.00	New Drain	1st
SD-26	Secondary Drain	34.45	3.50-4.50	1.25-3.00	New Drain	1st
SD-18	Secondary Drain	1.04	3.50-4.50	1.25-3.00	New Drain	2nd
SD-19	Secondary Drain	2.56	3.50-4.50	1.25-3.00	New Drain	2nd
SD-20	Secondary Drain	2.62	3.50-4.50	1.25-3.00	New Drain	2nd
TD-90	Tertiary Drain	75.95	2.5-3.5	0.64-1.25	New Drain	2nd
TD-106	Tertiary Drain	203.15	2.5-3.5	0.64-1.25	New Drain	2nd
TD-107	Tertiary Drain	216.83	2.5-3.5	0.64-1.25	New Drain	2nd
TD-108	Tertiary Drain	144.05	2.5-3.5	0.64-1.25	New Drain	2nd
TD-109	Tertiary Drain	732.85	2.5-3.5	0.64-1.25	New Drain	2nd
TD-132	Tertiary Drain	506.11	2.5-3.5	0.64-1.25	New Drain	2nd
TD-133	Tertiary Drain	95.22	2.5-3.5	0.64-1.25	New Drain	2nd
TD-134	Tertiary Drain	68.03	2.5-3.5	0.64-1.25	New Drain	2nd
TD-136	Tertiary Drain	329.25	2.5-3.5	0.64-1.25	New Drain	2nd
TD-137	Tertiary Drain	66.52	2.5-3.5	0.64-1.25	New Drain	2nd
TD-160	Tertiary Drain	181.88	2.5-3.5	0.64-1.25	New Drain	2nd
TD-162	Tertiary Drain	366.97	2.5-3.5	0.64-1.25	New Drain	2nd
TD-163	Tertiary Drain	176.12	2.5-3.5	0.64-1.25	New Drain	2nd
TD-164	Tertiary Drain	61.52	2.5-3.5	0.64-1.25	New Drain	2nd
TD-166	Tertiary Drain	1.42	2.5-3.5	0.64-1.25	New Drain	2nd
TD-174	Tertiary Drain	129.42	2.5-3.5	0.64-1.25	New Drain	2nd
TD-175	Tertiary Drain	96.49	2.5-3.5	0.64-1.25	New Drain	2nd
TD-177	Tertiary Drain	243.41	2.5-3.5	0.64-1.25	New Drain	2nd
TD-180	Tertiary Drain	92.92	2.5-3.5	0.64-1.25	New Drain	2nd
TD-181	Tertiary Drain	109.69	2.5-3.5	0.64-1.25	New Drain	2nd
TD-182	Tertiary Drain	924.85	2.5-3.5	0.64-1.25	New Drain	2nd
TD-184	Tertiary Drain	329.53	2.5-3.5	0.64-1.25	New Drain	2nd
TD-185	Tertiary Drain	168.83	2.5-3.5	0.64-1.25	New Drain	2nd
TD-186	Tertiary Drain	134.64	2.5-3.5	0.64-1.25	New Drain	2nd
TD-187	Tertiary Drain	45.51	2.5-3.5	0.64-1.25	New Drain	2nd
TD-188	Tertiary Drain	912.50	2.5-3.5	0.64-1.25	New Drain	2nd
TD-189	Tertiary Drain	246.39	2.5-3.5	0.64-1.25	New Drain	2nd
TD-190	Tertiary Drain	94.41	2.5-3.5	0.64-1.25	New Drain	2nd
TD-193	Tertiary Drain	645.13	2.5-3.5	0.64-1.25	New Drain	2nd
TD-194	Tertiary Drain	112.19	2.5-3.5	0.64-1.25	New Drain	2nd
TD-195	Tertiary Drain	127.78	2.5-3.5	0.64-1.25	New Drain	2nd
TD-196	Tertiary Drain	428.06	2.5-3.5	0.64-1.25	New Drain	2nd
TD-197	Tertiary Drain	42.35	2.5-3.5	0.64-1.25	New Drain	2nd
TD-198	Tertiary Drain	879.37	2.5-3.5	0.64-1.25	New Drain	2nd
TD-199	Tertiary Drain	62.76	2.5-3.5	0.64-1.25	New Drain	2nd
TD-200	Tertiary Drain	111.53	2.5-3.5	0.64-1.25	New Drain	2nd
TD-243	Tertiary Drain	59.48	2.5-3.5	0.64-1.25	New Drain	3rd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-244	Tertiary Drain	43.24	2.5-3.5	0.64-1.25	New Drain	3rd
TD-277	Tertiary Drain	8.49	2.5-3.5	0.64-1.25	New Drain	3rd
TD-427	Tertiary Drain	61.85	2.5-3.5	0.64-1.25	New Drain	3rd
TD-428	Tertiary Drain	58.12	2.5-3.5	0.64-1.25	New Drain	3rd
TD-429	Tertiary Drain	53.64	2.5-3.5	0.64-1.25	New Drain	3rd
TD-430	Tertiary Drain	52.59	2.5-3.5	0.64-1.25	New Drain	3rd
TD-436	Tertiary Drain	236.82	2.5-3.5	0.64-1.25	New Drain	3rd
TD-446	Tertiary Drain	0.96	2.5-3.5	0.64-1.25	New Drain	3rd
TD-451	Tertiary Drain	79.38	2.5-3.5	0.64-1.25	New Drain	3rd
TD-454	Tertiary Drain	135.64	2.5-3.5	0.64-1.25	New Drain	3rd
TD-455	Tertiary Drain	384.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-460	Tertiary Drain	188.03	2.5-3.5	0.64-1.25	New Drain	3rd
TD-461	Tertiary Drain	76.78	2.5-3.5	0.64-1.25	New Drain	3rd
TD-464	Tertiary Drain	158.48	2.5-3.5	0.64-1.25	New Drain	3rd
TD-492	Tertiary Drain	82.46	2.5-3.5	0.64-1.25	New Drain	3rd
TD-500	Tertiary Drain	98.62	2.5-3.5	0.64-1.25	New Drain	3rd
TD-503	Tertiary Drain	57.21	2.5-3.5	0.64-1.25	New Drain	3rd
TD-561	Tertiary Drain	99.19	2.5-3.5	0.64-1.25	New Drain	3rd
TD-562	Tertiary Drain	9.08	2.5-3.5	0.64-1.25	New Drain	3rd
TD-563	Tertiary Drain	53.94	2.5-3.5	0.64-1.25	New Drain	3rd
TD-564	Tertiary Drain	82.52	2.5-3.5	0.64-1.25	New Drain	3rd
TD-580	Tertiary Drain	49.92	2.5-3.5	0.64-1.25	New Drain	3rd
TD-583	Tertiary Drain	108.95	2.5-3.5	0.64-1.25	New Drain	3rd
TD-584	Tertiary Drain	44.97	2.5-3.5	0.64-1.25	New Drain	3rd
TD-598	Tertiary Drain	42.12	2.5-3.5	0.64-1.25	New Drain	3rd
TD-666	Tertiary Drain	69.41	2.5-3.5	0.64-1.25	New Drain	3rd
TD-669	Tertiary Drain	104.13	2.5-3.5	0.64-1.25	New Drain	3rd
TD-670	Tertiary Drain	654.49	2.5-3.5	0.64-1.25	New Drain	3rd
TD-692	Tertiary Drain	43.11	2.5-3.5	0.64-1.25	New Drain	3rd
TD-693	Tertiary Drain	326.50	2.5-3.5	0.64-1.25	New Drain	3rd
TD-716	Tertiary Drain	236.49	2.5-3.5	0.64-1.25	New Drain	3rd
TD-719	Tertiary Drain	3.38	2.5-3.5	0.64-1.25	New Drain	3rd
TD-720	Tertiary Drain	517.43	2.5-3.5	0.64-1.25	New Drain	3rd

Besides, it will be necessary to re-excavate the khals that serve as primary drains.

Map 15.14 represents proposed Road and Drainage Network for ward 5.

Map 15.14: Proposed Road & Drainage Network of ward no.5



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Bridge
- Culvert
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall

Meters
0 37.5 75 150 225 300

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT
SCPL Sheltech Consultants (Pvt.) Ltd.
1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.7.2.5 Urban Services

a. Solid Waste Management

The plan proposes one solid waste transfer stations at ward 05 with an area 0.52 acre. It also is recommended that home collection system is introduced in the ward by creation of local CBOs.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the Torkey River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement.

c. Sanitation


The Paurashava must try to promote hygienic sanitation for the whole Paurashava to ensure better public health.

Table 15.25: Urban Services Development Proposals for ward 05

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	0.86
Commercial Activity	Pauro Market	1	0.42
Community Facility	Shamshan Ghat	1	2.13
	Pauro Library	1	0.14
Health Facility	Clinic	1	3.34
Open Space	Park	1	5.50
	Playgrund	1	2.62
Recreational Facilities	Children Park	1	0.40
Utility Service	Electricity Line	As per existing program of PDB	
	Waste Transfer Station	1	0.52

Map 15.15 represents proposed urban services for ward 5

Map 15.15: Development Proposal of ward no.5



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

0 45 90 180 270 360 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL **Sheltech Consultants (Pvt.) Ltd.**

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com

In Association with

15.8 Ward Action Plan for Ward No. 06

15.8.1 Demography

Ward No. 6 is located on the Western part of the town. It has the moderate density of population within the Paurashava. Table 15.26 shows detail.

Table 15.26: Population Statistics of Ward No. 06

Item	Year			
	2016	2021	2026	2031
Area (acre)	497.02	497.02	497.02	497.02
Population	5290	5546	5883	6240
Density of Population (acre)	11	11	12	13

15.8.2 Ward Action Plan Proposals

15.8.2.1 Review of Existing Land Use

Out of total 497.02 acres of land i.e. about 59.60% is used as agricultural land and 19.86% land is used as residential use. Water bodies occupy more than 13% land of the ward. At present 7.7 acres of land are used in commercial purpose. About 2.30% is used as circulation network. Only 2.05 acre of land is used as community facilities.


15.8.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.26 shows the amount of land existing and proposed uses in Ward no. 06. **Map 15.16** shows proposed land use of Ward 06.

Table 15.27: Comparative Scenario of Existing and Proposed Land Uses of Ward no. 06

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agriculture	296.22	59.60	1	Administrative	2.55	0.51
2	Circulation Network	11.44	2.30	2	Agriculture	206.04	41.46
3	Commercial Activities	7.7	1.55	3	Circulation Network	49.26	9.91
4	Community Facilities	2.05	0.41	4	Commercial Activities	7.18	1.45
5	Education & Research	8.56	1.72	5	Community Facilities	3.00	0.60
6	Government Office	0.55	0.11	6	Education & Research	10.59	2.13
7	Health facilities	1.56	0.31	7	Health Facilities	1.78	0.36
8	Industrial	0.4	0.08	8	Industrial Facilities	0.24	0.05
9	Mixed Use	1.72	0.35	9	Mixed Use	8.04	1.62
10	NGO office	0.15	0.03	10	Open Space	3.75	0.75
11	Open space	1.61	0.32	11	Recreational	0.23	0.05
12	Recreational facilities	0.23	0.05	12	Rural Settlement	12.04	2.42
13	Residential area	98.73	19.86	13	Transportation & Communication	1.01	0.20
14	Transportation and Communication	0.1	0.02	14	Urban Settlement	124.01	24.95
15	Water Body	66	13.28	15	Utility Service	4.49	0.90
				16	Waterbody	62.80	12.64
	Total	**497.02**	**100**		**Total**	**497.02**	**100**

Map 15.16: Landuse Plan of ward no.6



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 60 120 240 360 480 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.8.2.3 Proposed Road Infrastructure Development

Total 23.65 km road development proposal have been proposed for Ward no. 06 Length of tertiary road is 17.22 km and width is 20 ft. The total length of Secondary road is 5.73 km and width is 40 to 60 ft. The total length of primary road is 0.70 km and width is 100 ft. Detail scenario of road network development proposal was given in table 15.28.

Table 15.28: Road Network Proposal at Ward no. 06

Type	Proposed Road ID	Length in m	Remark	Phase
Primary Road	PR-1	543.99	Widening	1st
Primary Road	PR-2	157.07	Widening	1st
Secondary Road	SR-2	1921.08	Widening	1st
Secondary Road	SR-3	1825.93	Widening	1st
Secondary Road	SR-4	1151.51	Widening	1st
Secondary Road	SR-5	260.89	Widening	1st
Secondary Road	SR-6	569.99	Widening	1st
Tertiary Road	TR-8	279.07	Widening	1st
Tertiary Road	TR-10	125.21	Widening	1st
Tertiary Road	TR-12	10.30	Widening	1st
Tertiary Road	TR-17	4.16	Widening	2nd
Tertiary Road	TR-30	19.72	Widening	2nd
Tertiary Road	TR-70	119.35	Widening	2nd
Tertiary Road	TR-72	302.52	Widening	2nd
Tertiary Road	TR-73	150.92	Widening	2nd
Tertiary Road	TR-74	300.11	Widening	2nd
Tertiary Road	TR-75	325.36	Widening	2nd
Tertiary Road	TR-76	166.89	Widening	2nd
Tertiary Road	TR-77	42.06	Widening	2nd
Tertiary Road	TR-78	60.08	Widening	2nd
Tertiary Road	TR-79	272.29	Widening	2nd
Tertiary Road	TR-80	29.89	Widening	2nd
Tertiary Road	TR-81	488.54	Widening	2nd
Tertiary Road	TR-82	80.90	Widening	2nd
Tertiary Road	TR-83	10.16	Widening	2nd
Tertiary Road	TR-84	168.86	Widening	2nd
Tertiary Road	TR-85	42.53	Widening	2nd
Tertiary Road	TR-86	894.48	Widening	2nd
Tertiary Road	TR-87	469.67	Widening	2nd
Tertiary Road	TR-88	256.23	Widening	2nd
Tertiary Road	TR-89	280.29	Widening	2nd
Tertiary Road	TR-90	85.30	Widening	2nd
Tertiary Road	TR-91	735.37	Widening	2nd
Tertiary Road	TR-92	12.88	Widening	2nd
Tertiary Road	TR-93	25.82	Widening	2nd
Tertiary Road	TR-94	67.51	Widening	2nd
Tertiary Road	TR-95	125.25	Widening	2nd
Tertiary Road	TR-96	62.20	Widening	2nd
Tertiary Road	TR-97	76.57	Widening	2nd
Tertiary Road	TR-98	125.25	Widening	2nd
Tertiary Road	TR-99	200.55	Widening	2nd
Tertiary Road	TR-100	80.10	Widening	2nd
Tertiary Road	TR-101	17.13	Widening	3rd
Tertiary Road	TR-102	47.10	Widening	3rd
Tertiary Road	TR-103	22.53	Widening	3rd
Tertiary Road	TR-104	94.47	Widening	3rd
Tertiary Road	TR-105	615.38	Widening	3rd
Tertiary Road	TR-106	76.85	Widening	3rd
Tertiary Road	TR-107	128.12	Widening	3rd
Tertiary Road	TR-109	9.20	Widening	3rd
Tertiary Road	TR-122	45.98	Widening	3rd
Tertiary Road	TR-123	79.10	Widening	3rd
Tertiary Road	TR-124	51.50	Widening	3rd
Tertiary Road	TR-125	294.18	Widening	3rd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-126	47.58	Widening	3rd
Tertiary Road	TR-127	29.21	Widening	3rd
Tertiary Road	TR-131	48.06	Widening	3rd
Tertiary Road	TR-132	50.58	Widening	3rd
Tertiary Road	TR-141	2.72	Widening	3rd
Tertiary Road	TR-145	262.57	Widening	3rd
Tertiary Road	TR-148	108.72	Widening	3rd
Tertiary Road	TR-149	33.79	Widening	3rd
Tertiary Road	TR-150	138.51	Widening	3rd
Tertiary Road	TR-151	68.37	Widening	3rd
Tertiary Road	TR-152	15.11	Widening	3rd
Tertiary Road	TR-153	155.13	Widening	3rd
Tertiary Road	TR-154	20.90	Widening	1st
Tertiary Road	TR-155	51.56	Widening	1st
Tertiary Road	TR-156	176.75	Widening	1st
Tertiary Road	TR-157	148.29	Widening	1st
Tertiary Road	TR-158	38.44	Widening	1st
Tertiary Road	TR-159	46.97	Widening	1st
Tertiary Road	TR-160	156.30	Widening	1st
Tertiary Road	TR-161	32.16	Widening	1st
Tertiary Road	TR-162	39.89	Widening	1st
Tertiary Road	TR-180	28.48	Widening	1st
Tertiary Road	TR-183	117.73	Widening	2nd
Tertiary Road	TR-187	84.71	Widening	2nd
Tertiary Road	TR-242	8.42	Widening	2nd
Tertiary Road	TR-243	370.13	Widening	2nd
Tertiary Road	TR-244	113.55	Widening	2nd
Tertiary Road	TR-245	105.84	Widening	2nd
Tertiary Road	TR-246	70.04	Widening	2nd
Tertiary Road	TR-247	99.26	Widening	2nd
Tertiary Road	TR-248	107.59	Widening	2nd
Tertiary Road	TR-249	14.73	Widening	2nd
Tertiary Road	TR-253	0.63	Widening	2nd
Tertiary Road	TR-255	0.24	Widening	2nd
Tertiary Road	TR-258	0.41	Widening	2nd
Tertiary Road	TR-259	441.43	Widening	2nd
Tertiary Road	TR-260	40.01	Widening	2nd
Tertiary Road	TR-263	203.14	Widening	2nd
Tertiary Road	TR-264	88.26	Widening	2nd
Tertiary Road	TR-265	71.69	Widening	2nd
Tertiary Road	TR-266	40.56	Widening	2nd
Tertiary Road	TR-267	68.89	Widening	2nd
Tertiary Road	TR-268	337.89	Widening	2nd
Tertiary Road	TR-270	304.86	Widening	2nd
Tertiary Road	TR-271	221.75	Widening	2nd
Tertiary Road	TR-272	258.51	Widening	2nd
Tertiary Road	TR-273	43.44	Widening	2nd
Tertiary Road	TR-274	176.34	Widening	2nd
Tertiary Road	TR-275	533.69	Widening	2nd
Tertiary Road	TR-279	84.77	Widening	2nd
Tertiary Road	TR-284	42.45	Widening	2nd
Tertiary Road	TR-287	1.74	Widening	2nd
Tertiary Road	TR-299	31.93	Widening	2nd
Tertiary Road	TR-301	0.29	Widening	2nd
Tertiary Road	TR-748	14.73	Widening	3rd
Tertiary Road	TR-817	355.26	New	3rd
Tertiary Road	TR-818	374.48	New	3rd
Tertiary Road	TR-819	163.20	New	3rd
Tertiary Road	TR-820	494.62	New	3rd
Tertiary Road	TR-822	626.70	New	3rd
Tertiary Road	TR-823	85.60	New	3rd
Tertiary Road	TR-858	420.54	New	3rd
Tertiary Road	TR-859	249.27	New	3rd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-860	113.79	New	3rd
Tertiary Road	TR-861	188.44	New	3rd
Tertiary Road	TR-862	372.50	New	3rd

- "TR" for tertiary road, "SR" for secondary road, and "PR" for primary road.

15.8.2.4 Drainage Development Plan

The proposed drainage facilities will be 22.95 km, served as 0.79 km primary drain, 2.25 km secondary drain and 19.89 km tertiary drain in first Ward Action Plan. Table 15.29 shows the detail.


Table 15.29: Drainage Development Plan Proposals for ward 06

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
PD-2	Primary Drain	788.88	4.50-5.50	2.00-3.00	New Drain	1st
SD-1	Secondary Drain	1151.51	3.50-4.50	1.25-3.00	New Drain	1st
SD-3	Secondary Drain	569.99	3.50-4.50	1.25-3.00	New Drain	1st
SD-6	Secondary Drain	543.99	3.50-4.50	1.25-3.00	New Drain	1st
TD-8	Tertiary Drain	279.07	2.5-3.5	0.64-1.25	New Drain	2nd
TD-10	Tertiary Drain	125.21	2.5-3.5	0.64-1.25	New Drain	2nd
TD-12	Tertiary Drain	10.30	2.5-3.5	0.64-1.25	New Drain	2nd
TD-17	Tertiary Drain	4.16	2.5-3.5	0.64-1.25	New Drain	2nd
TD-50	Tertiary Drain	1921.08	2.5-3.5	0.64-1.25	New Drain	2nd
TD-51	Tertiary Drain	1037.05	2.5-3.5	0.64-1.25	New Drain	2nd
TD-54	Tertiary Drain	302.52	2.5-3.5	0.64-1.25	New Drain	2nd
TD-55	Tertiary Drain	150.92	2.5-3.5	0.64-1.25	New Drain	2nd
TD-56	Tertiary Drain	300.11	2.5-3.5	0.64-1.25	New Drain	2nd
TD-57	Tertiary Drain	325.36	2.5-3.5	0.64-1.25	New Drain	2nd
TD-58	Tertiary Drain	166.89	2.5-3.5	0.64-1.25	New Drain	2nd
TD-59	Tertiary Drain	42.06	2.5-3.5	0.64-1.25	New Drain	2nd
TD-60	Tertiary Drain	60.08	2.5-3.5	0.64-1.25	New Drain	2nd
TD-61	Tertiary Drain	272.29	2.5-3.5	0.64-1.25	New Drain	2nd
TD-62	Tertiary Drain	488.54	2.5-3.5	0.64-1.25	New Drain	2nd
TD-63	Tertiary Drain	80.90	2.5-3.5	0.64-1.25	New Drain	2nd
TD-64	Tertiary Drain	168.86	2.5-3.5	0.64-1.25	New Drain	2nd
TD-65	Tertiary Drain	894.48	2.5-3.5	0.64-1.25	New Drain	2nd
TD-66	Tertiary Drain	469.67	2.5-3.5	0.64-1.25	New Drain	2nd
TD-67	Tertiary Drain	701.79	2.5-3.5	0.64-1.25	New Drain	2nd
TD-68	Tertiary Drain	280.29	2.5-3.5	0.64-1.25	New Drain	2nd
TD-69	Tertiary Drain	85.30	2.5-3.5	0.64-1.25	New Drain	2nd
TD-70	Tertiary Drain	735.37	2.5-3.5	0.64-1.25	New Drain	2nd
TD-71	Tertiary Drain	12.88	2.5-3.5	0.64-1.25	New Drain	2nd
TD-73	Tertiary Drain	125.25	2.5-3.5	0.64-1.25	New Drain	2nd
TD-74	Tertiary Drain	62.20	2.5-3.5	0.64-1.25	New Drain	2nd
TD-75	Tertiary Drain	76.57	2.5-3.5	0.64-1.25	New Drain	2nd
TD-76	Tertiary Drain	125.25	2.5-3.5	0.64-1.25	New Drain	2nd
TD-77	Tertiary Drain	200.55	2.5-3.5	0.64-1.25	New Drain	2nd
TD-78	Tertiary Drain	80.10	2.5-3.5	0.64-1.25	New Drain	2nd
TD-79	Tertiary Drain	17.13	2.5-3.5	0.64-1.25	New Drain	2nd
TD-80	Tertiary Drain	47.10	2.5-3.5	0.64-1.25	New Drain	2nd
TD-81	Tertiary Drain	22.53	2.5-3.5	0.64-1.25	New Drain	2nd
TD-82	Tertiary Drain	94.47	2.5-3.5	0.64-1.25	New Drain	2nd
TD-83	Tertiary Drain	76.85	2.5-3.5	0.64-1.25	New Drain	2nd
TD-84	Tertiary Drain	128.12	2.5-3.5	0.64-1.25	New Drain	2nd
TD-86	Tertiary Drain	9.20	2.5-3.5	0.64-1.25	New Drain	2nd
TD-96	Tertiary Drain	570.94	2.5-3.5	0.64-1.25	New Drain	2nd
TD-97	Tertiary Drain	51.50	2.5-3.5	0.64-1.25	New Drain	2nd
TD-98	Tertiary Drain	294.18	2.5-3.5	0.64-1.25	New Drain	2nd
TD-99	Tertiary Drain	47.58	2.5-3.5	0.64-1.25	New Drain	2nd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-100	Tertiary Drain	29.21	2.5-3.5	0.64-1.25	New Drain	2nd
TD-104	Tertiary Drain	48.06	2.5-3.5	0.64-1.25	New Drain	2nd
TD-105	Tertiary Drain	50.58	2.5-3.5	0.64-1.25	New Drain	2nd
TD-112	Tertiary Drain	2.72	2.5-3.5	0.64-1.25	New Drain	2nd
TD-115	Tertiary Drain	262.57	2.5-3.5	0.64-1.25	New Drain	2nd
TD-118	Tertiary Drain	108.72	2.5-3.5	0.64-1.25	New Drain	2nd
TD-119	Tertiary Drain	33.79	2.5-3.5	0.64-1.25	New Drain	2nd
TD-120	Tertiary Drain	138.51	2.5-3.5	0.64-1.25	New Drain	2nd
TD-121	Tertiary Drain	68.37	2.5-3.5	0.64-1.25	New Drain	2nd
TD-122	Tertiary Drain	15.11	2.5-3.5	0.64-1.25	New Drain	2nd
TD-123	Tertiary Drain	155.13	2.5-3.5	0.64-1.25	New Drain	2nd
TD-126	Tertiary Drain	176.75	2.5-3.5	0.64-1.25	New Drain	2nd
TD-127	Tertiary Drain	148.29	2.5-3.5	0.64-1.25	New Drain	2nd
TD-128	Tertiary Drain	46.97	2.5-3.5	0.64-1.25	New Drain	2nd
TD-129	Tertiary Drain	156.30	2.5-3.5	0.64-1.25	New Drain	2nd
TD-145	Tertiary Drain	4.47	2.5-3.5	0.64-1.25	New Drain	2nd
TD-149	Tertiary Drain	117.73	2.5-3.5	0.64-1.25	New Drain	2nd
TD-153	Tertiary Drain	84.71	2.5-3.5	0.64-1.25	New Drain	2nd
TD-161	Tertiary Drain	260.89	2.5-3.5	0.64-1.25	New Drain	2nd
TD-201	Tertiary Drain	8.42	2.5-3.5	0.64-1.25	New Drain	2nd
TD-202	Tertiary Drain	370.13	2.5-3.5	0.64-1.25	New Drain	2nd
TD-203	Tertiary Drain	113.55	2.5-3.5	0.64-1.25	New Drain	2nd
TD-204	Tertiary Drain	105.84	2.5-3.5	0.64-1.25	New Drain	2nd
TD-205	Tertiary Drain	70.04	2.5-3.5	0.64-1.25	New Drain	2nd
TD-206	Tertiary Drain	99.26	2.5-3.5	0.64-1.25	New Drain	2nd
TD-207	Tertiary Drain	107.59	2.5-3.5	0.64-1.25	New Drain	2nd
TD-208	Tertiary Drain	14.73	2.5-3.5	0.64-1.25	New Drain	2nd
TD-212	Tertiary Drain	0.63	2.5-3.5	0.64-1.25	New Drain	2nd
TD-214	Tertiary Drain	0.24	2.5-3.5	0.64-1.25	New Drain	2nd
TD-217	Tertiary Drain	0.41	2.5-3.5	0.64-1.25	New Drain	2nd
TD-218	Tertiary Drain	441.43	2.5-3.5	0.64-1.25	New Drain	2nd
TD-219	Tertiary Drain	40.01	2.5-3.5	0.64-1.25	New Drain	2nd
TD-222	Tertiary Drain	203.14	2.5-3.5	0.64-1.25	New Drain	2nd
TD-223	Tertiary Drain	88.26	2.5-3.5	0.64-1.25	New Drain	2nd
TD-224	Tertiary Drain	71.69	2.5-3.5	0.64-1.25	New Drain	2nd
TD-225	Tertiary Drain	68.89	2.5-3.5	0.64-1.25	New Drain	2nd
TD-226	Tertiary Drain	337.89	2.5-3.5	0.64-1.25	New Drain	3rd
TD-228	Tertiary Drain	304.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-229	Tertiary Drain	221.75	2.5-3.5	0.64-1.25	New Drain	3rd
TD-230	Tertiary Drain	258.51	2.5-3.5	0.64-1.25	New Drain	3rd
TD-231	Tertiary Drain	176.34	2.5-3.5	0.64-1.25	New Drain	3rd
TD-232	Tertiary Drain	533.69	2.5-3.5	0.64-1.25	New Drain	3rd
TD-236	Tertiary Drain	84.77	2.5-3.5	0.64-1.25	New Drain	3rd
TD-240	Tertiary Drain	42.45	2.5-3.5	0.64-1.25	New Drain	3rd
TD-242	Tertiary Drain	1.74	2.5-3.5	0.64-1.25	New Drain	3rd
TD-254	Tertiary Drain	31.93	2.5-3.5	0.64-1.25	New Drain	3rd
TD-256	Tertiary Drain	0.29	2.5-3.5	0.64-1.25	New Drain	3rd
TD-655	Tertiary Drain	355.26	2.5-3.5	0.64-1.25	New Drain	3rd
TD-656	Tertiary Drain	374.48	2.5-3.5	0.64-1.25	New Drain	3rd
TD-657	Tertiary Drain	163.20	2.5-3.5	0.64-1.25	New Drain	3rd
TD-658	Tertiary Drain	494.62	2.5-3.5	0.64-1.25	New Drain	3rd
TD-659	Tertiary Drain	626.70	2.5-3.5	0.64-1.25	New Drain	3rd
TD-660	Tertiary Drain	85.60	2.5-3.5	0.64-1.25	New Drain	3rd
TD-694	Tertiary Drain	420.54	2.5-3.5	0.64-1.25	New Drain	3rd
TD-695	Tertiary Drain	249.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-696	Tertiary Drain	113.79	2.5-3.5	0.64-1.25	New Drain	3rd
TD-697	Tertiary Drain	188.44	2.5-3.5	0.64-1.25	New Drain	3rd
TD-725	Tertiary Drain	169.83	2.5-3.5	0.64-1.25	New Drain	3rd

Map 15.17 represents proposed Road and Drainage Network Map of Ward 6.

Map 15.17: Proposed Road & Drainage Network of ward no.6



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Bridge
- Culvert
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall

0 55110 220 330 440 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT
SCPL Sheltech Consultants (Pvt.) Ltd.
1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.8.2.5 Urban Services

a. Solid Waste Management

The consultant proposes solid waste transfer stations at ward no. 06. It is recommended that home collection system is introduced in the ward by creation of local CBOs. Table 1.30 shows the detail.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the Torkey River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement. One Water Treatment Plant covering 3.91 acres land has been proposed for this purpose.

c. Sanitation


The Paurashava must try to promote hygienic sanitation for the whole Paurashavsa to ensure better public health.

Table 15.30: Urban Services Development Proposals for ward 06

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	1.96
Commercial Activity	Kitchen Market	1	1.42
Community Facility	Graveyard	1	1.32
Education & Research	High School	1	2.17
Health Facility	Clinic	1	1.36
Open Space	Park	1	0.96
	Playground	1	1.44
Transportation Facilities	Bus Stand	1	0.92
Urban Settlement	Resettelement Zone	1	6.67
Utility Service	Waste Transfer Station	1	0.58
	Electricity Line	As per existing program of PDB	-
	Water Treatment Plant	1	3.91

Map 15.18 represents proposed urban services for ward 6**.**

Map 15.18: Development Proposal of ward no.6



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

0 60 120 240 360 480 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.9 Ward Action Plan for Ward No. 07

15.9.1 Demography

Ward no.7 is located on the West-Southern of the town. Population projection shows that 5976 people would be in the ward in the year 2031. The density of population will be 11 persons per acre. Table 15.31 shows the details.

Table 15.31: Population Statistics of Ward No. 07

Item	Year			
	2016	2021	2026	2031
Area (acre)	535.98	535.98	535.98	535.98
Population	5066	5311	5634	5976
Density of Population (acre)	9	10	11	11

15.9.2 Ward Action Plan Proposals

1.9.2.1 Review of Existing Land Use

Out of total 535.98 acres of land about 63.77% is used as agricultural use. The next use is residential use, more than 109 acres of land are used in this purpose. Waterbody occupies about 10.19% land of the ward. More than 2% is used as circulation network.


15.9.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.32 shows the amount of land existing and proposed uses in Ward no. 7. **Map 15.19** shows proposed land use of Ward 07

Table 15.32: Comparative Existing Land Use and Proposed Land Use of Ward No. 07

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agriculture	341.8	63.77	1	Administrative	6.52	1.22
2	Circulation Network	11.62	2.17	2	Agriculture	233.68	43.60
3	Commercial Activities	5.46	1.02	3	Circulation Network	49.21	9.18
4	Community Facilities	1.92	0.36	4	Commercial	5.42	1.01
5	Education & Research	2.46	0.46	5	Community Facilities	2.63	0.49
6	Government Office	4.85	0.90	6	Educational Facilities	9.36	1.75
7	Health facilities	1.64	0.31	7	Health Facilities	1.50	0.28
8	Industrial	0.02	0.00	8	Industrial Facilities	0.02	0.00
9	NGO office	1.07	0.20		Mixed Use	8.49	1.58
10	Open space	0.51	0.10	9	Open Space	9.69	1.81
11	Residential area	109.99	20.52	10	Rural Settlement	16.82	3.14
12	Water Body	54.64	10.19	11	Transportation & Communication	0.75	0.14
				12	Urban Settlement	5.40	1.01
				13	Urban Deffered	134.38	25.07
				14	Utility Service	0.38	0.07
				15	Waterbody	51.73	9.65
	Total	**535.98**	**100**		**Total**	**535.98**	**100**

Map 15.19: Landuse Plan of ward no.7



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 65 130 260 390 520 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.9.2.3 Proposed Road Infrastructure Development

Total 24.03 km road development proposal have been proposed in ward action plan for ward no. 07. Total length of tertiary road will be 19.85 km and width of these roads will be 20ft for this ward. Total length of secondary road will be 2.47 km and width of these roads will be 40ft for this ward. There is 1.71 km primary road proposal. Detail scenario of road network development proposal was given in table 15.33.

Table 15.33: Road Network Proposal at Ward no. 07

Type	Proposed Road ID	Length in m	Remark	Phase
Primary Road	PR-1	1710.04	Widening	1st
Secondary Road	SR-6	859.24	Widening	1st
Secondary Road	SR-7	744.17	Widening	1st
Secondary Road	SR-13	866.22	Widening	1st
Tertiary Road	TR-139	373.59	Widening	1st
Tertiary Road	TR-146	3.97	Widening	1st
Tertiary Road	TR-168	610.70	Widening	1st
Tertiary Road	TR-171	583.32	Widening	2nd
Tertiary Road	TR-172	188.36	Widening	2nd
Tertiary Road	TR-173	156.54	Widening	2nd
Tertiary Road	TR-174	95.98	Widening	2nd
Tertiary Road	TR-175	68.89	Widening	2nd
Tertiary Road	TR-176	91.46	Widening	2nd
Tertiary Road	TR-177	153.65	Widening	2nd
Tertiary Road	TR-178	150.99	Widening	2nd
Tertiary Road	TR-179	37.64	Widening	2nd
Tertiary Road	TR-181	23.57	Widening	2nd
Tertiary Road	TR-184	81.74	Widening	2nd
Tertiary Road	TR-185	141.78	Widening	2nd
Tertiary Road	TR-230	27.39	Widening	2nd
Tertiary Road	TR-251	74.34	Widening	2nd
Tertiary Road	TR-254	136.94	Widening	2nd
Tertiary Road	TR-256	139.02	Widening	2nd
Tertiary Road	TR-257	49.49	Widening	2nd
Tertiary Road	TR-261	40.07	Widening	2nd
Tertiary Road	TR-269	181.63	Widening	2nd
Tertiary Road	TR-277	1.16	Widening	2nd
Tertiary Road	TR-280	91.81	Widening	2nd
Tertiary Road	TR-281	387.86	Widening	2nd
Tertiary Road	TR-282	63.35	Widening	2nd
Tertiary Road	TR-283	408.93	Widening	2nd
Tertiary Road	TR-285	242.60	Widening	2nd
Tertiary Road	TR-291	34.39	Widening	2nd
Tertiary Road	TR-292	360.64	Widening	2nd
Tertiary Road	TR-293	28.56	Widening	2nd
Tertiary Road	TR-294	42.89	Widening	2nd
Tertiary Road	TR-295	38.58	Widening	2nd
Tertiary Road	TR-296	39.61	Widening	2nd
Tertiary Road	TR-297	35.24	Widening	2nd
Tertiary Road	TR-298	27.23	Widening	2nd
Tertiary Road	TR-299	621.35	Widening	2nd
Tertiary Road	TR-302	47.56	Widening	2nd
Tertiary Road	TR-303	36.95	Widening	2nd
Tertiary Road	TR-304	35.84	Widening	2nd
Tertiary Road	TR-305	55.89	Widening	2nd
Tertiary Road	TR-306	29.27	Widening	2nd
Tertiary Road	TR-307	42.81	Widening	2nd
Tertiary Road	TR-308	65.03	Widening	2nd
Tertiary Road	TR-309	50.91	Widening	2nd
Tertiary Road	TR-310	385.44	Widening	2nd
Tertiary Road	TR-311	37.07	Widening	2nd
Tertiary Road	TR-312	127.01	Widening	2nd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-313	197.04	Widening	3rd
Tertiary Road	TR-314	30.22	Widening	3rd
Tertiary Road	TR-315	30.17	Widening	3rd
Tertiary Road	TR-316	54.17	Widening	3rd
Tertiary Road	TR-317	112.22	Widening	3rd
Tertiary Road	TR-318	20.02	Widening	3rd
Tertiary Road	TR-319	18.79	Widening	3rd
Tertiary Road	TR-320	35.39	Widening	3rd
Tertiary Road	TR-321	256.43	Widening	3rd
Tertiary Road	TR-322	81.83	Widening	3rd
Tertiary Road	TR-323	85.07	Widening	3rd
Tertiary Road	TR-324	156.07	Widening	3rd
Tertiary Road	TR-325	81.93	Widening	3rd
Tertiary Road	TR-326	36.98	Widening	3rd
Tertiary Road	TR-327	65.68	Widening	3rd
Tertiary Road	TR-328	36.35	Widening	3rd
Tertiary Road	TR-329	45.00	Widening	3rd
Tertiary Road	TR-330	1018.52	Widening	3rd
Tertiary Road	TR-333	239.25	Widening	3rd
Tertiary Road	TR-334	33.74	Widening	3rd
Tertiary Road	TR-335	97.79	Widening	3rd
Tertiary Road	TR-336	60.14	Widening	3rd
Tertiary Road	TR-337	76.46	Widening	3rd
Tertiary Road	TR-338	66.40	Widening	3rd
Tertiary Road	TR-339	84.74	Widening	3rd
Tertiary Road	TR-340	502.60	Widening	3rd
Tertiary Road	TR-535	207.92	Widening	3rd
Tertiary Road	TR-539	60.84	Widening	3rd
Tertiary Road	TR-540	1.82	Widening	3rd
Tertiary Road	TR-542	3.27	Widening	3rd
Tertiary Road	TR-544	5.76	Widening	3rd
Tertiary Road	TR-547	5.71	Widening	3rd
Tertiary Road	TR-549	40.14	Widening	3rd
Tertiary Road	TR-552	39.04	Widening	3rd
Tertiary Road	TR-553	607.46	Widening	3rd
Tertiary Road	TR-554	462.42	Widening	3rd
Tertiary Road	TR-555	248.96	Widening	3rd
Tertiary Road	TR-556	616.10	Widening	3rd
Tertiary Road	TR-587	63.39	Widening	3rd
Tertiary Road	TR-588	144.81	Widening	3rd
Tertiary Road	TR-589	285.07	Widening	3rd
Tertiary Road	TR-590	63.95	Widening	3rd
Tertiary Road	TR-591	79.60	Widening	3rd
Tertiary Road	TR-592	35.87	Widening	3rd
Tertiary Road	TR-593	32.95	Widening	3rd
Tertiary Road	TR-594	216.67	Widening	3rd
Tertiary Road	TR-595	23.28	Widening	3rd
Tertiary Road	TR-596	33.60	Widening	3rd
Tertiary Road	TR-597	39.75	Widening	3rd
Tertiary Road	TR-600	461.57	Widening	3rd
Tertiary Road	TR-603	196.66	Widening	3rd
Tertiary Road	TR-604	193.52	Widening	3rd
Tertiary Road	TR-605	48.29	Widening	3rd
Tertiary Road	TR-609	3.21	Widening	3rd
Tertiary Road	TR-614	69.84	Widening	3rd
Tertiary Road	TR-744	24.20	Widening	3rd
Tertiary Road	TR-745	232.12	Widening	3rd
Tertiary Road	TR-746	200.92	Widening	3rd
Tertiary Road	TR-821	593.28	New	3rd
Tertiary Road	TR-823	321.37	New	3rd
Tertiary Road	TR-824	263.38	New	3rd
Tertiary Road	TR-825	136.47	New	3rd
Tertiary Road	TR-834	328.79	New	3rd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-835	153.84	New	3rd
Tertiary Road	TR-836	762.99	New	3rd
Tertiary Road	TR-853	284.19	New	3rd
Tertiary Road	TR-854	488.43	New	3rd
Tertiary Road	TR-856	1166.27	New	3rd
Tertiary Road	TR-861	289.58	New	3rd
Tertiary Road	TR-883	41.21	Widening	3rd

- "TR" for tertiary road, "SR" for secondary road, and "PR" for primary road.

15.9.2.4 Drainage Development Plan

There are both manmade and natural drainage facilities at ward no. 07. Existing drainage is mostly depending on natural drainage facilities. The proposed drainage facilities will be developed based on this natural channel and served as primary drain for the ward and will be connected with secondary drain and tertiary drain. Table 15.34 shows the detail.

Table 15.34: Drainage Development Plan Proposals for ward 07

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
PD-5	Primary Drain	516.03	4.50-5.50	2.00-3.00	New Drain	1st
SD-3	Secondary Drain	859.24	3.50-4.50	1.25-3.00	New Drain	1st
SD-4	Secondary Drain	408.93	3.50-4.50	1.25-3.00	New Drain	1st
SD-6	Secondary Drain	1003.49	3.50-4.50	1.25-3.00	New Drain	1st
SD-8	Secondary Drain	866.22	3.50-4.50	1.25-3.00	New Drain	1st
SD-14	Secondary Drain	832.82	3.50-4.50	1.25-3.00	New Drain	2nd
SD-16	Secondary Drain	669.63	3.50-4.50	1.25-3.00	New Drain	2nd
SD-21	Secondary Drain	177.81	3.50-4.50	1.25-3.00	New Drain	2nd
TD-110	Tertiary Drain	373.59	2.5-3.5	0.64-1.25	New Drain	2nd
TD-116	Tertiary Drain	3.97	2.5-3.5	0.64-1.25	New Drain	2nd
TD-135	Tertiary Drain	610.70	2.5-3.5	0.64-1.25	New Drain	2nd
TD-138	Tertiary Drain	583.32	2.5-3.5	0.64-1.25	New Drain	2nd
TD-139	Tertiary Drain	188.36	2.5-3.5	0.64-1.25	New Drain	2nd
TD-140	Tertiary Drain	156.54	2.5-3.5	0.64-1.25	New Drain	2nd
TD-141	Tertiary Drain	95.98	2.5-3.5	0.64-1.25	New Drain	2nd
TD-143	Tertiary Drain	91.46	2.5-3.5	0.64-1.25	New Drain	2nd
TD-144	Tertiary Drain	153.65	2.5-3.5	0.64-1.25	New Drain	2nd
TD-145	Tertiary Drain	153.41	2.5-3.5	0.64-1.25	New Drain	2nd
TD-146	Tertiary Drain	37.64	2.5-3.5	0.64-1.25	New Drain	2nd
TD-147	Tertiary Drain	23.57	2.5-3.5	0.64-1.25	New Drain	2nd
TD-150	Tertiary Drain	81.74	2.5-3.5	0.64-1.25	New Drain	2nd
TD-151	Tertiary Drain	141.78	2.5-3.5	0.64-1.25	New Drain	2nd
TD-188	Tertiary Drain	37.23	2.5-3.5	0.64-1.25	New Drain	2nd
TD-191	Tertiary Drain	27.39	2.5-3.5	0.64-1.25	New Drain	2nd
TD-210	Tertiary Drain	74.34	2.5-3.5	0.64-1.25	New Drain	2nd
TD-213	Tertiary Drain	136.94	2.5-3.5	0.64-1.25	New Drain	2nd
TD-215	Tertiary Drain	139.02	2.5-3.5	0.64-1.25	New Drain	2nd
TD-216	Tertiary Drain	49.49	2.5-3.5	0.64-1.25	New Drain	2nd
TD-220	Tertiary Drain	40.07	2.5-3.5	0.64-1.25	New Drain	2nd
TD-227	Tertiary Drain	181.63	2.5-3.5	0.64-1.25	New Drain	3rd
TD-234	Tertiary Drain	1.16	2.5-3.5	0.64-1.25	New Drain	3rd
TD-237	Tertiary Drain	91.81	2.5-3.5	0.64-1.25	New Drain	3rd
TD-238	Tertiary Drain	387.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-247	Tertiary Drain	360.64	2.5-3.5	0.64-1.25	New Drain	3rd
TD-248	Tertiary Drain	28.56	2.5-3.5	0.64-1.25	New Drain	3rd
TD-254	Tertiary Drain	621.35	2.5-3.5	0.64-1.25	New Drain	3rd
TD-257	Tertiary Drain	47.56	2.5-3.5	0.64-1.25	New Drain	3rd
TD-259	Tertiary Drain	55.89	2.5-3.5	0.64-1.25	New Drain	3rd
TD-260	Tertiary Drain	29.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-263	Tertiary Drain	519.41	2.5-3.5	0.64-1.25	New Drain	3rd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-264	Tertiary Drain	197.04	2.5-3.5	0.64-1.25	New Drain	3rd
TD-265	Tertiary Drain	30.22	2.5-3.5	0.64-1.25	New Drain	3rd
TD-267	Tertiary Drain	112.22	2.5-3.5	0.64-1.25	New Drain	3rd
TD-268	Tertiary Drain	20.02	2.5-3.5	0.64-1.25	New Drain	3rd
TD-269	Tertiary Drain	256.43	2.5-3.5	0.64-1.25	New Drain	3rd
TD-270	Tertiary Drain	81.83	2.5-3.5	0.64-1.25	New Drain	3rd
TD-271	Tertiary Drain	85.07	2.5-3.5	0.64-1.25	New Drain	3rd
TD-275	Tertiary Drain	1018.52	2.5-3.5	0.64-1.25	New Drain	3rd
TD-278	Tertiary Drain	239.25	2.5-3.5	0.64-1.25	New Drain	3rd
TD-279	Tertiary Drain	97.79	2.5-3.5	0.64-1.25	New Drain	3rd
TD-280	Tertiary Drain	60.14	2.5-3.5	0.64-1.25	New Drain	3rd
TD-281	Tertiary Drain	76.46	2.5-3.5	0.64-1.25	New Drain	3rd
TD-282	Tertiary Drain	66.40	2.5-3.5	0.64-1.25	New Drain	3rd
TD-283	Tertiary Drain	84.74	2.5-3.5	0.64-1.25	New Drain	3rd
TD-284	Tertiary Drain	502.60	2.5-3.5	0.64-1.25	New Drain	3rd
TD-433	Tertiary Drain	207.92	2.5-3.5	0.64-1.25	New Drain	3rd
TD-437	Tertiary Drain	1.82	2.5-3.5	0.64-1.25	New Drain	3rd
TD-439	Tertiary Drain	3.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-440	Tertiary Drain	5.76	2.5-3.5	0.64-1.25	New Drain	3rd
TD-443	Tertiary Drain	5.71	2.5-3.5	0.64-1.25	New Drain	3rd
TD-447	Tertiary Drain	607.46	2.5-3.5	0.64-1.25	New Drain	3rd
TD-448	Tertiary Drain	462.42	2.5-3.5	0.64-1.25	New Drain	3rd
TD-449	Tertiary Drain	248.96	2.5-3.5	0.64-1.25	New Drain	3rd
TD-450	Tertiary Drain	616.10	2.5-3.5	0.64-1.25	New Drain	3rd
TD-475	Tertiary Drain	144.81	2.5-3.5	0.64-1.25	New Drain	3rd
TD-476	Tertiary Drain	285.07	2.5-3.5	0.64-1.25	New Drain	3rd
TD-478	Tertiary Drain	79.60	2.5-3.5	0.64-1.25	New Drain	3rd
TD-479	Tertiary Drain	216.67	2.5-3.5	0.64-1.25	New Drain	3rd
TD-481	Tertiary Drain	461.57	2.5-3.5	0.64-1.25	New Drain	3rd
TD-484	Tertiary Drain	196.66	2.5-3.5	0.64-1.25	New Drain	3rd
TD-485	Tertiary Drain	193.52	2.5-3.5	0.64-1.25	New Drain	3rd
TD-486	Tertiary Drain	48.29	2.5-3.5	0.64-1.25	New Drain	3rd
TD-489	Tertiary Drain	3.21	2.5-3.5	0.64-1.25	New Drain	3rd
TD-585	Tertiary Drain	24.20	2.5-3.5	0.64-1.25	New Drain	3rd
TD-586	Tertiary Drain	232.12	2.5-3.5	0.64-1.25	New Drain	3rd
TD-587	Tertiary Drain	200.92	2.5-3.5	0.64-1.25	New Drain	3rd
TD-660	Tertiary Drain	321.37	2.5-3.5	0.64-1.25	New Drain	3rd
TD-661	Tertiary Drain	263.38	2.5-3.5	0.64-1.25	New Drain	3rd
TD-662	Tertiary Drain	136.47	2.5-3.5	0.64-1.25	New Drain	3rd
TD-671	Tertiary Drain	328.79	2.5-3.5	0.64-1.25	New Drain	3rd
TD-672	Tertiary Drain	153.84	2.5-3.5	0.64-1.25	New Drain	3rd
TD-689	Tertiary Drain	284.19	2.5-3.5	0.64-1.25	New Drain	3rd
TD-690	Tertiary Drain	488.43	2.5-3.5	0.64-1.25	New Drain	3rd
TD-692	Tertiary Drain	1166.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-697	Tertiary Drain	289.58	2.5-3.5	0.64-1.25	New Drain	3rd
TD-726	Tertiary Drain	963.82	2.5-3.5	0.64-1.25	New Drain	3rd

Besides, it will be necessary to re-excavate the khals that serve as primary drains flowing of Water through them. **Map 15.20** represents proposed Road and Drainage Network for Ward 7.

15.9.2.5 Urban Services

a. Solid Waste Management

The consultant proposes solid waste transfer stations in some suitable locations for the management of solid waste. It is recommended that home collection system is introduced in the ward by creation of local CBOs. This will cause organized collection of waste and prevent indiscriminate littering.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the Torkey River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement.

c. Sanitation


The Paurashava must try to promote hygienic sanitation for the whole Paurashava to ensure better public health.

Table 15.35: Urban Services Development Proposals for ward 07

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	1.57
Commercial Activity	Kutcha Bazar	1	0.36
	Super Market	1	1.92
Community Facility	Community Center	1	0.98
Education & Research	Girls College	1	4.47
	Primary School	1	1.88
Open Space	Park	2	5.03
	Playground	1	3.76
Utility Service	Electricity Line	As per existing program of PDB	-
	Waste Transfer Station	2	0.38

Map 15.21 represents proposed urban services for ward 7.

Map 15.21: Development Proposal of ward no.7



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

0 65 130 260 390 520 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.10 Ward Action Plan for Ward No. 08

15.10.1 Demography

Ward No. 8 is located on the East-Southern of the town. It has the moderate density of population. The estimated population for the year 2031 will be 5541 with a density of 10 persons per acre. Table 15.36 shows the detail.

Table 15.36: Population Statistics of Ward No. 08

Item	Year			
	2016	2021	2026	2031
Area (acre)	528.58	528.58	528.58	528.58
Population	4697	4924	5223	5541
Density of Population (acre)	9	9	10	10

15.10.2 Ward Action Plan Proposals

15.10.2.1 Review of Existing Land Use

Out of total 528.58 acre of land of this ward more than 374.12 acre of land i.e. 70.78% is used as agricultural land. The next use is residential; 90.54 acres are used as this purpose. It occupies almost 17.13% of total land. Waterbody occupies about 9.44% land. More than 1.65% is used as circulation network. Only 0.19% of land is used as Commercial activities.


15.10.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.37 shows the amount of land existing and proposed uses in Ward no. 8. **Map 15.22** shows proposed land use of Ward 08

Table 15.37: Comparative Scenario of Existing and Proposed Land Use of Ward No. 08

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agriculture	374.12	70.78	1	Administrative	1.64	0.31
2	Circulation Network	8.74	1.65	2	Agriculture	338.14	63.97
3	Commercial Activities	1.03	0.19	3	Circulation Network	33.66	6.37
4	Community Facilities	1.22	0.23	4	Commercial	1.75	0.33
5	Education & Research	1.68	0.32	5	Community Facilities	1.10	0.21
6	Government Office		0.00	6	Educational Facilities	4.15	0.79
7	Health facilities	0.34	0.06	7	Health Facilities	4.51	0.85
8	Industrial	0.15	0.03	8	Industrial Facilities	0.12	0.02
9	Open space	0.85	0.16	9	Open Space	3.15	0.60
10	Residential area	90.54	17.13	10	Urban Settlement	96.71	18.30
11	Water Body	49.91	9.44	11	Utility Service	0.39	0.07
				12	Waterbody	43.26	8.18
	Total	**528.58**	**100**		**Total**	**528.58**	**100**

Map 15.22: Landuse Plan of ward no.8



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 50 100 200 300 400 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.10.2.3 Proposed Road Infrastructure Development

Total 19.46 km road development proposal have been proposed for this ward. Total length of tertiary road will be 17.67 km and width of these roads will be 20 ft. Total length of secondary road will be 1.79 km and width of these roads will be 40 to 60 ft for this ward. Detail scenario of road network development proposal was given in table 15.38.

Table 15.38: Road Network Proposal at Ward no.08 of Gauranadi Paurashava

Type	Proposed Road ID	Length in m	Remark	Phase
Secondary Road	SR-7	582.30	Widening	1st
Secondary Road	SR-13	92.18	Widening	1st
Secondary Road	SR-16	212.13	Widening	1st
Secondary Road	SR-18	5.23	New	1st
Secondary Road	SR-22	898.01	Widening	1st
Tertiary Road	TR-541	54.29	Widening	1st
Tertiary Road	TR-543	17.95	Widening	1st
Tertiary Road	TR-546	305.67	Widening	2nd
Tertiary Road	TR-548	234.91	Widening	2nd
Tertiary Road	TR-558	198.04	Widening	2nd
Tertiary Road	TR-564	55.45	Widening	2nd
Tertiary Road	TR-565	452.63	Widening	2nd
Tertiary Road	TR-566	254.50	Widening	2nd
Tertiary Road	TR-567	42.67	Widening	2nd
Tertiary Road	TR-568	51.86	Widening	2nd
Tertiary Road	TR-571	0.32	Widening	2nd
Tertiary Road	TR-574	29.39	Widening	2nd
Tertiary Road	TR-575	78.98	Widening	2nd
Tertiary Road	TR-576	50.29	Widening	2nd
Tertiary Road	TR-577	25.34	Widening	2nd
Tertiary Road	TR-578	849.60	Widening	2nd
Tertiary Road	TR-579	35.57	Widening	2nd
Tertiary Road	TR-580	35.92	Widening	2nd
Tertiary Road	TR-581	35.52	Widening	2nd
Tertiary Road	TR-582	278.46	Widening	2nd
Tertiary Road	TR-583	459.11	Widening	2nd
Tertiary Road	TR-584	47.14	Widening	2nd
Tertiary Road	TR-585	263.14	Widening	2nd
Tertiary Road	TR-586	34.05	Widening	2nd
Tertiary Road	TR-606	28.25	Widening	2nd
Tertiary Road	TR-607	65.13	Widening	2nd
Tertiary Road	TR-611	701.03	Widening	2nd
Tertiary Road	TR-615	1.34	Widening	2nd
Tertiary Road	TR-617	557.13	Widening	2nd
Tertiary Road	TR-618	230.34	Widening	2nd
Tertiary Road	TR-619	290.93	Widening	2nd
Tertiary Road	TR-620	37.92	Widening	2nd
Tertiary Road	TR-621	318.76	Widening	2nd
Tertiary Road	TR-622	161.23	Widening	2nd
Tertiary Road	TR-623	60.76	Widening	2nd
Tertiary Road	TR-624	45.04	Widening	2nd
Tertiary Road	TR-625	29.52	Widening	3rd
Tertiary Road	TR-626	426.11	Widening	3rd
Tertiary Road	TR-627	862.12	Widening	3rd
Tertiary Road	TR-631	432.64	Widening	3rd
Tertiary Road	TR-632	49.55	Widening	3rd
Tertiary Road	TR-633	662.54	Widening	3rd
Tertiary Road	TR-634	43.19	Widening	3rd
Tertiary Road	TR-635	573.68	Widening	3rd
Tertiary Road	TR-636	31.98	Widening	3rd
Tertiary Road	TR-637	469.36	Widening	3rd
Tertiary Road	TR-638	119.73	Widening	3rd
Tertiary Road	TR-639	43.17	Widening	3rd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-640	48.01	Widening	3rd
Tertiary Road	TR-641	191.96	Widening	3rd
Tertiary Road	TR-642	215.86	Widening	3rd
Tertiary Road	TR-643	191.76	Widening	3rd
Tertiary Road	TR-644	77.27	Widening	3rd
Tertiary Road	TR-645	214.31	Widening	3rd
Tertiary Road	TR-649	70.47	Widening	3rd
Tertiary Road	TR-678	113.09	Widening	3rd
Tertiary Road	TR-680	478.53	Widening	3rd
Tertiary Road	TR-682	198.92	Widening	3rd
Tertiary Road	TR-685	4.60	Widening	3rd
Tertiary Road	TR-689	25.17	Widening	3rd
Tertiary Road	TR-693	46.25	Widening	3rd
Tertiary Road	TR-703	216.15	Widening	3rd
Tertiary Road	TR-704	47.81	Widening	3rd
Tertiary Road	TR-725	12.62	Widening	3rd
Tertiary Road	TR-732	275.01	Widening	3rd
Tertiary Road	TR-733	0.01	Widening	3rd
Tertiary Road	TR-734	413.19	Widening	3rd
Tertiary Road	TR-735	159.27	Widening	3rd
Tertiary Road	TR-736	85.85	Widening	3rd
Tertiary Road	TR-763	270.77	Widening	3rd
Tertiary Road	TR-827	471.19	New	3rd
Tertiary Road	TR-828	1192.89	New	3rd
Tertiary Road	TR-829	246.89	New	1st
Tertiary Road	TR-830	505.58	New	1st
Tertiary Road	TR-831	193.87	New	1st
Tertiary Road	TR-837	317.76	New	1st
Tertiary Road	TR-838	140.83	Widening	1st
Tertiary Road	TR-839	37.17	Widening	1st
Tertiary Road	TR-840	43.24	Widening	1st
Tertiary Road	TR-841	16.87	Widening	2nd
Tertiary Road	TR-842	64.64	Widening	2nd
Tertiary Road	TR-843	79.67	Widening	2nd
Tertiary Road	TR-844	192.05	Widening	2nd
Tertiary Road	TR-845	358.54	Widening	2nd
Tertiary Road	TR-878	213.92	Widening	2nd
Tertiary Road	TR-879	76.13	Widening	2nd
Tertiary Road	TR-880	29.69	Widening	2nd

- "TR" for tertiary road, and "SR" for secondary road.

15.10.2.4 Drainage Development Plan

There are both natural and manmade drainage facilities at ward no. 08 of Gauranadi Paurashava. Existing drainage is mostly depending on natural drainage facilities. The proposed drainage facilities will be developed based on this natural channel. Table 15.39 shows the detail.

Table 15.39: Drainage Development Plan Proposals for ward 08

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
PD-7	Primary Drain	429.07	4.50-5.50	2.00-3.00	New Drain	1st
SD-8	Secondary Drain	92.18	3.50-4.50	1.25-3.00	New Drain	1st
SD-11	Secondary Drain	212.13	3.50-4.50	1.25-3.00	New Drain	2nd
SD-14	Secondary Drain	1503.92	3.50-4.50	1.25-3.00	New Drain	2nd
TD-188	Tertiary Drain	1051.25	2.5-3.5	0.64-1.25	New Drain	2nd
TD-438	Tertiary Drain	54.29	2.5-3.5	0.64-1.25	New Drain	3rd
TD-442	Tertiary Drain	305.67	2.5-3.5	0.64-1.25	New Drain	3rd
TD-444	Tertiary Drain	234.91	2.5-3.5	0.64-1.25	New Drain	3rd
TD-452	Tertiary Drain	198.04	2.5-3.5	0.64-1.25	New Drain	3rd
TD-457	Tertiary Drain	452.63	2.5-3.5	0.64-1.25	New Drain	3rd
TD-458	Tertiary Drain	254.50	2.5-3.5	0.64-1.25	New Drain	3rd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-459	Tertiary Drain	51.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-462	Tertiary Drain	0.32	2.5-3.5	0.64-1.25	New Drain	3rd
TD-465	Tertiary Drain	29.39	2.5-3.5	0.64-1.25	New Drain	3rd
TD-466	Tertiary Drain	78.98	2.5-3.5	0.64-1.25	New Drain	3rd
TD-467	Tertiary Drain	50.29	2.5-3.5	0.64-1.25	New Drain	3rd
TD-468	Tertiary Drain	849.60	2.5-3.5	0.64-1.25	New Drain	3rd
TD-470	Tertiary Drain	278.46	2.5-3.5	0.64-1.25	New Drain	3rd
TD-471	Tertiary Drain	459.11	2.5-3.5	0.64-1.25	New Drain	3rd
TD-472	Tertiary Drain	47.14	2.5-3.5	0.64-1.25	New Drain	3rd
TD-473	Tertiary Drain	263.14	2.5-3.5	0.64-1.25	New Drain	3rd
TD-487	Tertiary Drain	65.13	2.5-3.5	0.64-1.25	New Drain	3rd
TD-493	Tertiary Drain	1.34	2.5-3.5	0.64-1.25	New Drain	3rd
TD-494	Tertiary Drain	230.34	2.5-3.5	0.64-1.25	New Drain	3rd
TD-495	Tertiary Drain	290.93	2.5-3.5	0.64-1.25	New Drain	3rd
TD-496	Tertiary Drain	318.76	2.5-3.5	0.64-1.25	New Drain	3rd
TD-497	Tertiary Drain	161.23	2.5-3.5	0.64-1.25	New Drain	3rd
TD-499	Tertiary Drain	45.04	2.5-3.5	0.64-1.25	New Drain	3rd
TD-500	Tertiary Drain	862.12	2.5-3.5	0.64-1.25	New Drain	3rd
TD-504	Tertiary Drain	432.64	2.5-3.5	0.64-1.25	New Drain	3rd
TD-505	Tertiary Drain	662.54	2.5-3.5	0.64-1.25	New Drain	3rd
TD-507	Tertiary Drain	469.36	2.5-3.5	0.64-1.25	New Drain	3rd
TD-508	Tertiary Drain	119.73	2.5-3.5	0.64-1.25	New Drain	3rd
TD-509	Tertiary Drain	191.96	2.5-3.5	0.64-1.25	New Drain	3rd
TD-510	Tertiary Drain	215.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-511	Tertiary Drain	191.76	2.5-3.5	0.64-1.25	New Drain	3rd
TD-512	Tertiary Drain	77.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-513	Tertiary Drain	214.31	2.5-3.5	0.64-1.25	New Drain	3rd
TD-532	Tertiary Drain	113.09	2.5-3.5	0.64-1.25	New Drain	3rd
TD-534	Tertiary Drain	478.53	2.5-3.5	0.64-1.25	New Drain	3rd
TD-536	Tertiary Drain	198.92	2.5-3.5	0.64-1.25	New Drain	3rd
TD-539	Tertiary Drain	4.60	2.5-3.5	0.64-1.25	New Drain	3rd
TD-543	Tertiary Drain	25.17	2.5-3.5	0.64-1.25	New Drain	3rd
TD-551	Tertiary Drain	216.15	2.5-3.5	0.64-1.25	New Drain	3rd
TD-552	Tertiary Drain	47.81	2.5-3.5	0.64-1.25	New Drain	3rd
TD-568	Tertiary Drain	12.62	2.5-3.5	0.64-1.25	New Drain	3rd
TD-574	Tertiary Drain	275.01	2.5-3.5	0.64-1.25	New Drain	3rd
TD-575	Tertiary Drain	0.01	2.5-3.5	0.64-1.25	New Drain	3rd
TD-576	Tertiary Drain	413.19	2.5-3.5	0.64-1.25	New Drain	3rd
TD-577	Tertiary Drain	159.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-578	Tertiary Drain	85.85	2.5-3.5	0.64-1.25	New Drain	3rd
TD-603	Tertiary Drain	270.77	2.5-3.5	0.64-1.25	New Drain	3rd
TD-664	Tertiary Drain	471.19	2.5-3.5	0.64-1.25	New Drain	3rd
TD-665	Tertiary Drain	1192.89	2.5-3.5	0.64-1.25	New Drain	3rd
TD-666	Tertiary Drain	246.89	2.5-3.5	0.64-1.25	New Drain	3rd
TD-667	Tertiary Drain	505.58	2.5-3.5	0.64-1.25	New Drain	3rd
TD-668	Tertiary Drain	193.87	2.5-3.5	0.64-1.25	New Drain	3rd
TD-673	Tertiary Drain	317.76	2.5-3.5	0.64-1.25	New Drain	3rd
TD-674	Tertiary Drain	140.83	2.5-3.5	0.64-1.25	New Drain	3rd
TD-675	Tertiary Drain	37.17	2.5-3.5	0.64-1.25	New Drain	3rd
TD-676	Tertiary Drain	43.24	2.5-3.5	0.64-1.25	New Drain	3rd
TD-677	Tertiary Drain	16.87	2.5-3.5	0.64-1.25	New Drain	3rd
TD-678	Tertiary Drain	64.64	2.5-3.5	0.64-1.25	New Drain	3rd
TD-679	Tertiary Drain	79.67	2.5-3.5	0.64-1.25	New Drain	3rd
TD-680	Tertiary Drain	192.05	2.5-3.5	0.64-1.25	New Drain	3rd
TD-681	Tertiary Drain	358.54	2.5-3.5	0.64-1.25	New Drain	3rd
TD-706	Tertiary Drain	5.23	2.5-3.5	0.64-1.25	New Drain	3rd
TD-716	Tertiary Drain	213.92	2.5-3.5	0.64-1.25	New Drain	3rd
TD-717	Tertiary Drain	76.13	2.5-3.5	0.64-1.25	New Drain	3rd
TD-718	Tertiary Drain	29.69	2.5-3.5	0.64-1.25	New Drain	3rd
TD-732	Tertiary Drain	1.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-733	Tertiary Drain	212.17	2.5-3.5	0.64-1.25	New Drain	3rd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-734	Tertiary Drain	30.09	2.5-3.5	0.64-1.25	New Drain	3rd
TD-735	Tertiary Drain	88.41	2.5-3.5	0.64-1.25	New Drain	3rd
TD-736	Tertiary Drain	152.70	2.5-3.5	0.64-1.25	New Drain	3rd
TD-737	Tertiary Drain	268.81	2.5-3.5	0.64-1.25	New Drain	3rd

Besides, it will be necessary to re-excavate the khals that serve as primary drains. The consultants have identified existing whole of the khals need to be re-excavated to allow smooth flow of water through them.

Map 15.23 represents proposed Road and Drainage Map of ward 8.

15.10.2.5 Urban Services

a. Solid Waste Management

Solid waste management is a major urban service. As density of population increases the volume of solid waste also increases proportionately. However, the income level is also a major factor influencing the volume of solid waste. Population and the volume of waste in the Paurashava are yet to be large enough to become a problem for the city. But the present management system is not satisfactory and it might to lead to problem in future. The consultant proposes solid waste transfer stations in a suitable location. It is recommended that home collection system is introduced in the ward by creation of local CBOs. This will cause organized collection of waste and prevent indiscriminate littering.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the Torkey River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement.

c. Sanitation


The Paurashava must try to promote hygienic sanitation for the whole Paurashava to ensure better public health.

Table 15.40: Urban Service Development Proposals for ward 08

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	1.64
Commercial Activity	Kitchen Market	1	1.07
Education & Research	High School	1	2.77
Health Facility	Hospital	1	4.26
Open Space	Park	1	2.46
Urban Settlement	Low Income Housing	1	10.92
Utility Service	Electricity Line	As per existing program of PDB	-
	Waste Transfer Station	1	0.39

Map 15.24 represents proposed urban services for ward 8 .

Map 15.23: Proposed Road & Drainage Network of ward no.8



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Bridge
- Culvert
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall

0 50 100 200 300 400 Meters


Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

Map 15.24: Development Proposal of ward no.8



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

0 50 100 200 300 400 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.11 Ward Action Plan for Ward No. 09

15.11.1 Demography

Ward No. 9 is located on the Southern part of the town. It is the large ward with low density of 6 persons per acre with population of 4694 persons.

Table 15.41: Population Statistics of Ward No. 09

Item	Year			
	2016	2021	2026	2031
Area (acre)	764.03	764.03	764.03	764.03
Population	3979	4171	4425	4694
Density of Population (acre)	5	5	6	6

15.11.2 Ward Action Plan Proposals

15.11.2.1 Review of Existing Land Use

Out of total about 764.03 acre of land of this ward almost 620.53 acre of land i.e. 81.22% of the total land is under agricultural use. Residential use occupies 9.62% land of the ward. 1.37% land is for circulation network, 0.14% is for community services, 7.17% land is for waterbodies in this ward.


15.11.2.2 Proposed Land Use Zoning

The category wise proposals are presented here. Table 15.42 shows the amount of land existing and proposed uses in Ward no. 9. **Map 15.25** shows proposed land use of Ward 09.

Table 15.42: Comparative Scenario of Existing and Proposed Land Use of Ward no. 09

Sl. No.	Landuse (Existing)	Area (Acre)	%	Sl. No.	Landuse (Proposed)	Area (Acre)	%
1	Agriculture	620.53	81.22	1	Administrative	1.27	0.17
2	Circulation Network	10.47	1.37	2	Agriculture	406.91	53.26
3	Commercial Activities	1.19	0.16	3	Circulation Network	64.86	8.49
4	Community Facilities	1.1	0.14	4	Commercial Activities	5.00	0.65
5	Education & Research	1.48	0.19	5	Community Facilities	5.27	0.69
6	Government Office	0.39	0.05	6	Educational Facilities	4.47	0.59
7	Industrial	0.09	0.01	7	Health Facilities	4.08	0.53
8	Open space	0.54	0.07	8	Industrial Facilities	0.08	0.01
9	Residential area	73.49	9.62	9	Open Space	6.66	0.87
10	Water Body	54.75	7.17	10	Mixed use	10.78	1.41
				11	Recreational Facilities	5.35	0.70
				12	Residential Area	7.39	0.97
				13	Transportation & Communication	79.84	10.45
				14	Urban Deferred	108.83	14.24
				15	Utility Service	5.61	0.73
				16	Waterbody	47.61	6.23
	Total	**764.03**	**100**		**Total**	**764.03**	**100**

Map 15.25: Landuse Plan of ward no.9



Legend

- Paurashava Boundary
- Mouza Boundary
- Ward Boundary

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Waterbody
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service

0 80 160 320 480 640 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com

In Association with

15.11.2.3 Proposed Road Infrastructure Development

Total 27.35 km road development proposal have been proposed for Ward no. 09 of Gauranadi Paurashava. Total length of tertiary road will be 19.60 km and width of these roads will be 20 ft. Total length of secondary road will be 4.99 km and width of these roads will be 40 to 60 ft for this ward. Total length of primary road will be 2.76 km and width of these roads will be 100 ft. Detail scenario of road network development proposal was given in Table 15.43. **Map 15.26** represents proposed Road network for ward 9.

Table 15.43: Road Network Proposal at Ward no. 09

Type	Proposed Road ID	Length in m	Remark	Phase
Primary Road	PR-1	2092.13	Widening	1st
Primary Road	PR-2	667.52	Widening	1st
Secondary Road	SR-13	712.57	Widening	1st
Secondary Road	SR-15	1664.35	Widening	2nd
Secondary Road	SR-16	1227.77	Widening	2nd
Secondary Road	SR-18	36.51	New	2nd
Secondary Road	SR-19	424.59	New	2nd
Secondary Road	SR-21	927.49	Widening	2nd
Tertiary Road	TR-341	684.00	Widening	2nd
Tertiary Road	TR-342	497.15	Widening	2nd
Tertiary Road	TR-343	490.29	Widening	2nd
Tertiary Road	TR-344	195.74	Widening	2nd
Tertiary Road	TR-345	506.43	Widening	2nd
Tertiary Road	TR-346	54.90	Widening	2nd
Tertiary Road	TR-347	19.09	Widening	2nd
Tertiary Road	TR-348	21.67	Widening	2nd
Tertiary Road	TR-349	276.11	Widening	2nd
Tertiary Road	TR-598	388.88	Widening	2nd
Tertiary Road	TR-599	194.67	Widening	2nd
Tertiary Road	TR-602	336.59	Widening	2nd
Tertiary Road	TR-608	13.63	Widening	2nd
Tertiary Road	TR-616	42.70	Widening	2nd
Tertiary Road	TR-621	0.96	Widening	2nd
Tertiary Road	TR-646	40.57	Widening	2nd
Tertiary Road	TR-647	279.81	Widening	3rd
Tertiary Road	TR-648	426.02	Widening	3rd
Tertiary Road	TR-650	24.44	Widening	3rd
Tertiary Road	TR-651	31.80	Widening	3rd
Tertiary Road	TR-652	14.76	Widening	3rd
Tertiary Road	TR-653	131.20	Widening	3rd
Tertiary Road	TR-654	71.61	Widening	3rd
Tertiary Road	TR-655	41.65	Widening	3rd
Tertiary Road	TR-656	25.43	Widening	3rd
Tertiary Road	TR-657	28.01	Widening	3rd
Tertiary Road	TR-658	40.53	Widening	3rd
Tertiary Road	TR-659	23.60	Widening	3rd
Tertiary Road	TR-660	59.64	Widening	3rd
Tertiary Road	TR-661	368.17	Widening	3rd
Tertiary Road	TR-662	389.05	Widening	3rd
Tertiary Road	TR-663	90.24	Widening	3rd
Tertiary Road	TR-664	23.81	Widening	3rd
Tertiary Road	TR-665	26.93	Widening	3rd
Tertiary Road	TR-666	45.01	Widening	3rd
Tertiary Road	TR-667	32.76	Widening	3rd
Tertiary Road	TR-668	92.06	Widening	3rd
Tertiary Road	TR-669	450.70	Widening	3rd
Tertiary Road	TR-670	43.96	Widening	3rd
Tertiary Road	TR-671	36.47	Widening	3rd
Tertiary Road	TR-672	328.44	Widening	3rd
Tertiary Road	TR-673	505.61	Widening	3rd
Tertiary Road	TR-674	455.72	Widening	3rd

Type	Proposed Road ID	Length in m	Remark	Phase
Tertiary Road	TR-675	35.18	Widening	2nd
Tertiary Road	TR-676	30.27	Widening	2nd
Tertiary Road	TR-677	57.04	Widening	2nd
Tertiary Road	TR-679	2.27	Widening	2nd
Tertiary Road	TR-684	85.53	Widening	2nd
Tertiary Road	TR-687	48.70	Widening	2nd
Tertiary Road	TR-688	214.78	Widening	3rd
Tertiary Road	TR-689	149.69	Widening	3rd
Tertiary Road	TR-690	13.88	Widening	3rd
Tertiary Road	TR-691	75.57	Widening	3rd
Tertiary Road	TR-692	297.68	Widening	3rd
Tertiary Road	TR-695	4.04	Widening	3rd
Tertiary Road	TR-696	87.30	Widening	3rd
Tertiary Road	TR-697	46.60	Widening	3rd
Tertiary Road	TR-698	32.15	Widening	3rd
Tertiary Road	TR-699	1065.61	Widening	3rd
Tertiary Road	TR-700	21.61	Widening	3rd
Tertiary Road	TR-701	32.19	Widening	3rd
Tertiary Road	TR-702	42.36	Widening	3rd
Tertiary Road	TR-705	292.73	Widening	3rd
Tertiary Road	TR-706	64.41	Widening	3rd
Tertiary Road	TR-707	922.48	Widening	3rd
Tertiary Road	TR-720	320.86	Widening	3rd
Tertiary Road	TR-721	28.05	Widening	3rd
Tertiary Road	TR-722	890.42	Widening	3rd
Tertiary Road	TR-747	289.48	Widening	3rd
Tertiary Road	TR-826	206.35	Widening	3rd
Tertiary Road	TR-846	791.96	New	3rd
Tertiary Road	TR-847	319.87	New	3rd
Tertiary Road	TR-848	231.18	New	3rd
Tertiary Road	TR-849	623.30	New	3rd
Tertiary Road	TR-850	431.39	New	3rd
Tertiary Road	TR-851	228.27	New	3rd
Tertiary Road	TR-852	1281.12	New	2nd
Tertiary Road	TR-853	778.21	New	2nd
Tertiary Road	TR-866	332.70	New	2nd
Tertiary Road	TR-867	281.17	New	2nd
Tertiary Road	TR-868	276.36	New	2nd
Tertiary Road	TR-869	593.23	New	2nd
Tertiary Road	TR-870	220.03	New	3rd
Tertiary Road	TR-875	4.57	Widening	3rd

- "TR" for tertiary road, "SR" for secondary road, and "PR" for primary road.

15.11.2.4 Drainage Development Plan

There are both natural and manmade drainage facilities at ward no. 09 of Gauranadi Paurashava. Existing drainage is mostly depending on natural drainage facilities. The proposed drainage facilities will be developed based on this natural channel. Table 15.44 shows the detail.

Table 15.44: Drainage Development Plan Proposals for ward 09


Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
SD-5	Secondary Drain	479.95	3.50-4.50	1.25-3.00	New Drain	1st
SD-8	Secondary Drain	712.57	3.50-4.50	1.25-3.00	New Drain	1st
SD-9	Secondary Drain	426.02	3.50-4.50	1.25-3.00	New Drain	1st
SD-11	Secondary Drain	882.98	3.50-4.50	1.25-3.00	New Drain	2nd
SD-15	Secondary Drain	927.49	3.50-4.50	1.25-3.00	New Drain	2nd
SD-16	Secondary Drain	2092.13	3.50-4.50	1.25-3.00	New Drain	2nd
SD-17	Secondary Drain	1656.15	3.50-4.50	1.25-3.00	New Drain	2nd
TD-285	Tertiary Drain	670.07	2.5-3.5	0.64-1.25	New Drain	3rd

Proposed Drain ID	Proposed Hierarchy	Length in (m)	Width in (ft)	Depth in (m)	Remark	Phasing
TD-286	Tertiary Drain	490.29	2.5-3.5	0.64-1.25	New Drain	3rd
TD-287	Tertiary Drain	195.74	2.5-3.5	0.64-1.25	New Drain	3rd
TD-288	Tertiary Drain	506.43	2.5-3.5	0.64-1.25	New Drain	3rd
TD-289	Tertiary Drain	54.90	2.5-3.5	0.64-1.25	New Drain	3rd
TD-290	Tertiary Drain	276.11	2.5-3.5	0.64-1.25	New Drain	3rd
TD-480	Tertiary Drain	583.55	2.5-3.5	0.64-1.25	New Drain	3rd
TD-483	Tertiary Drain	336.59	2.5-3.5	0.64-1.25	New Drain	3rd
TD-488	Tertiary Drain	13.63	2.5-3.5	0.64-1.25	New Drain	3rd
TD-496	Tertiary Drain	0.96	2.5-3.5	0.64-1.25	New Drain	3rd
TD-514	Tertiary Drain	279.81	2.5-3.5	0.64-1.25	New Drain	3rd
TD-515	Tertiary Drain	131.20	2.5-3.5	0.64-1.25	New Drain	3rd
TD-516	Tertiary Drain	71.61	2.5-3.5	0.64-1.25	New Drain	3rd
TD-519	Tertiary Drain	368.17	2.5-3.5	0.64-1.25	New Drain	3rd
TD-520	Tertiary Drain	389.05	2.5-3.5	0.64-1.25	New Drain	3rd
TD-521	Tertiary Drain	90.24	2.5-3.5	0.64-1.25	New Drain	3rd
TD-522	Tertiary Drain	45.01	2.5-3.5	0.64-1.25	New Drain	3rd
TD-523	Tertiary Drain	92.06	2.5-3.5	0.64-1.25	New Drain	3rd
TD-524	Tertiary Drain	450.70	2.5-3.5	0.64-1.25	New Drain	3rd
TD-527	Tertiary Drain	328.44	2.5-3.5	0.64-1.25	New Drain	3rd
TD-528	Tertiary Drain	505.61	2.5-3.5	0.64-1.25	New Drain	3rd
TD-529	Tertiary Drain	455.72	2.5-3.5	0.64-1.25	New Drain	3rd
TD-531	Tertiary Drain	57.04	2.5-3.5	0.64-1.25	New Drain	3rd
TD-533	Tertiary Drain	2.27	2.5-3.5	0.64-1.25	New Drain	3rd
TD-538	Tertiary Drain	85.53	2.5-3.5	0.64-1.25	New Drain	3rd
TD-541	Tertiary Drain	48.70	2.5-3.5	0.64-1.25	New Drain	3rd
TD-542	Tertiary Drain	214.78	2.5-3.5	0.64-1.25	New Drain	3rd
TD-543	Tertiary Drain	149.69	2.5-3.5	0.64-1.25	New Drain	3rd
TD-544	Tertiary Drain	297.68	2.5-3.5	0.64-1.25	New Drain	3rd
TD-547	Tertiary Drain	4.04	2.5-3.5	0.64-1.25	New Drain	3rd
TD-548	Tertiary Drain	87.30	2.5-3.5	0.64-1.25	New Drain	3rd
TD-550	Tertiary Drain	1065.61	2.5-3.5	0.64-1.25	New Drain	3rd
TD-553	Tertiary Drain	292.73	2.5-3.5	0.64-1.25	New Drain	3rd
TD-555	Tertiary Drain	922.48	2.5-3.5	0.64-1.25	New Drain	3rd
TD-565	Tertiary Drain	320.86	2.5-3.5	0.64-1.25	New Drain	3rd
TD-566	Tertiary Drain	890.42	2.5-3.5	0.64-1.25	New Drain	3rd
TD-588	Tertiary Drain	289.48	2.5-3.5	0.64-1.25	New Drain	3rd
TD-663	Tertiary Drain	206.35	2.5-3.5	0.64-1.25	New Drain	3rd
TD-682	Tertiary Drain	791.96	2.5-3.5	0.64-1.25	New Drain	3rd
TD-683	Tertiary Drain	319.87	2.5-3.5	0.64-1.25	New Drain	3rd
TD-684	Tertiary Drain	231.18	2.5-3.5	0.64-1.25	New Drain	3rd
TD-685	Tertiary Drain	623.30	2.5-3.5	0.64-1.25	New Drain	3rd
TD-686	Tertiary Drain	431.39	2.5-3.5	0.64-1.25	New Drain	3rd
TD-687	Tertiary Drain	566.38	2.5-3.5	0.64-1.25	New Drain	3rd
TD-688	Tertiary Drain	1281.12	2.5-3.5	0.64-1.25	New Drain	3rd
TD-689	Tertiary Drain	778.21	2.5-3.5	0.64-1.25	New Drain	3rd
TD-701	Tertiary Drain	332.70	2.5-3.5	0.64-1.25	New Drain	3rd
TD-702	Tertiary Drain	281.17	2.5-3.5	0.64-1.25	New Drain	3rd
TD-703	Tertiary Drain	276.36	2.5-3.5	0.64-1.25	New Drain	3rd
TD-704	Tertiary Drain	593.23	2.5-3.5	0.64-1.25	New Drain	3rd
TD-705	Tertiary Drain	220.03	2.5-3.5	0.64-1.25	New Drain	3rd
TD-706	Tertiary Drain	36.51	2.5-3.5	0.64-1.25	New Drain	3rd
TD-707	Tertiary Drain	424.59	2.5-3.5	0.64-1.25	New Drain	3rd
TD-713	Tertiary Drain	4.57	2.5-3.5	0.64-1.25	New Drain	3rd
TD-727	Tertiary Drain	8.20	2.5-3.5	0.64-1.25	New Drain	3rd

Besides, it will be necessary to re-excavate the khals that serve as primary drains. The consultants have identified existing whole of the khals need to be re-excavated to allow smooth flow of water through them.

Map 15.26 represents proposed Road and Drainage network for ward 9.

Map 15.26: Proposed Road & Drainage Network of ward no.9



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Bridge
- Culvert
- Primary Road
- Secondary Road
- Tertiary Road
- Waterbody
- Primary Drain
- Secondary Drain
- Tertiary Drain
- Outfall

0 80 160 320 480 640 Meter

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT
SCPL Sheltech Consultants (Pvt.) Ltd.
1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.11.2.5 Urban Services

a. Solid Waste Management

Solid waste management is a major urban service. As density of population increases the volume of solid waste also increases proportionately. However, the income level is also a major factor influencing the volume of solid waste. Population and the volume of waste in the Paurashava are yet to be large enough to become a problem for the city. But the present management system is not satisfactory and it might to lead to problem in future. The consultant proposes solid waste transfer stations in a suitable location. It is recommended that home collection system is introduced in the ward by creation of local CBOs. This will cause organized collection of waste and prevent indiscriminate littering.

b. Water Supply

It is proposed to install a network based water supply system by exploring fresh water from the Torkey River for the entire Paurashava. And water supply lines in this ward will be established along all categories of roads as per the growth of the settlement.

c. Sanitation


The Paurashava must try to promote hygienic sanitation for the whole Paurashava to ensure better public health.

Table 15.45: Urban Service Development Proposals for ward 09

Landuse	Item	No.	Area (acre)
Administrative	Ward Center	1	0.93
Commercial Activity	Neighborhood Market	1	1.23
	Shopping Complex	1	2.79
Community Facility	Graveyard	1	4.39
Education & Research	Girlss School	1	3.07
Health Facility	Clinic	1	4.08
Open Space	Park	2	6.34
	Playground	1	4.03
Recreational Facilities	Stadium	1	5.35
Transportation Facilities	Bus Terminal	1	5.22
	Tempo Stand	1	2.17
Urban Settlement	Housing Area	1	33.93
Utility Service	Dumping Site	1	5.43
	Electricity Line	As per existing program of PDB	-
	Waste Transfer Station	1	0.18

Map 15.27 represents proposed urban services for ward 9.

Map 15.27: Development Proposal of ward no.9



Legend

- Paurashava Boundary
- Ward Boundary
- Mouza Boundary
- Low Income Housing
- Madrasha
- Mosque
- Government Office
- Post Office
- Resettelement Zone
- Auditorium/Community Center
- Bus Terminal/Stand
- College
- Dumping Station
- Electric-Sub-Station
- Fuel Station
- Graveyard
- Hospital / Clinic
- Inustry
- Market
- Overhead Tank
- Park
- Playground
- Rickshaw Stand
- School /Primary School
- Secondary School
- Shamshan Ghat
- Stadium
- Tempo Stand
- Truck Terminal/Stand
- Ward Center
- Waste Transfer Station
- Water Treatment Plant

Land Use Type

- Administrative
- Agriculture
- Circulation Network
- Commercial Activity
- Community Facility
- Deferred Area
- Education & Research
- Health Facility
- Industrial
- Mixed Use
- Open Space
- Recreational Facilities
- Rural Settelement
- Transportation Facilities
- Urban Settlement
- Utility Service
- Waterbody

0 80 160 320 480 640 Meters

Local Government Engineering Department (LGED)
Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development and Cooperatives Local Government Division

CONSULTANT

SCPL Sheltech Consultants (Pvt.) Ltd.

1/E/2, Paribagh (Mazar Road), Shahbagh, Dhaka - 1000
scpl.mail@gmail.com
In Association with

15.12: Implementation Guidelines

The Master Plan of Gauranadi Paurashava will be an effective tool for planned urban development, if it is implemented properly with legal enforcement. The different components of the Master Plan have varied implications if they are not implemented in an integrated manner. There is no separate laws related directly to the implementation of Master Plan of the Paurashavas in the country other than the Paurashava Ordinance/Act 2009 and some relevant national policies and laws as discussed in chapter 5 under the Structure Plan.

However, the legal provisions that have been made in the Paurashava Ordinance/Act 2009 can effectively be applied in the implementation of the Master Plan of Gauranadi Pouashava for the time being along with other relevant national policies and laws that have also implications at Paurashava level, such as Wetland Conservation Act 2000 and BNBC 1993. Other national policies, guidelines and laws relevant to population, agriculture, environment, tourism, building materials, building construction etc. have implications for the implementation of various components including the Ward Action Plan of the Master Plan of Gauranadi Paurashava.

Therefore, until specific laws and guidelines are made by the government for the Paurashavas in Bangladesh for the implementation of Master Plans, the existing laws, policies and guidelines should be strictly followed so that the goal and objectives of these plans are achieved. Effective application of the various existing policies and laws require prudent exercise of professional knowledge and expertise, which is lacking in the existing human resources of the Paurashavas in Bangladesh. In particular, the Paurashavas require professional urban/town planner(s) in the set up of their manpower. In this context, there is an urgent need for the creation of a planning division/section in the existing set up of the Paurashava Organogram.

15.12.1 Proposals for Mitigation of Identified Issues

The critical issues of planning and development identified in the Structure Plan have been addressed through the preparation of Urban Area Plan and Ward Action Plan. The proposals made in these plans resolve the issues addressed in the Structure Plan.

15.12.2 Comparative Advantage of Master Plan

The Paurashavas in Bangladesh do not have any practicing plans at present in regard to organized development of land use or infrastructure. This situation has been continuing over a long period of time in the past promoting spontaneous land and infrastructure development. As a result, there are examples of unplanned development creating discomfort to the people living in almost all Paurashavas in the country. The implementation of the currently prepared Master Plan of the Paurashava will remove those obstacles by applying the principles, guidelines and proposals of various components of its Master Plan. The Ward Action Plan prepared following the Urban Area Plan will solve the most pressing needs of the town in infrastructure development.

15.13 Conclusion

The Paurashavas in Bangladesh for the first time in its history are having their detailed Master Plans prepared scientifically using modern tools and techniques. These Master Plans will be effective tools for planned development of most of the urban centers in Bangladesh. The planned township development will also ensure required services for the rural areas of the country. This in turn will make a positive impact on economic growth, social progress and environmental sustainability. Gauranadi Paurashava must avail this opportunity for its progress in the future by implementing its newly prepared Master Plan.

Annexure

Team Composition of Master Plan Preparation

A.1 Personnel of the Project Management Office (UTIDP, LGED)

Sl No.	Name	Position
1	Md. Moslah Uddin	Project Director
2	Md. Manzurul Islam	Deputy Project Director
3	Syed Shahriar Amin	Urban Planner
4	Ziaul Hoque	Urban Planner
5		Urban Planner

A.2 Personnel of the Consultancy Firm Sheltech Consultants (Pvt.) Ltd.

A. Key Personnel:

Sl No.	Name	Position
1	Sultana Dilruba Aziz	Team Leader
2	Afsana M Kamal	Deputy Team Leader
3	Rukhsana Parveen	Urban Planner
4	Dr. Md. Altaf Hossain	Urban Planner
5	A.K.M. Mahfuzul Kabir	Demographer/Statistician
6	Dr. Santi Ranjan Hawlader	Urban Development Economist
7	Lipika Khan	Transport Planning Expert
8	Mohammed Iqbal Hossain	Municipal Engineer
9	Mohammad Ferozuddin	Architect Planner
10	Mohammad Quadiruzzaman	Environmental Analyst
11	Tripal Kumar Sen	GIS Specialist
12	Md. Hefzul Bari	Legal Expert

B. Supporting Stuff:

Sl No.	Name	Position
1	Mohammad Helal	Office Manager
2	M.A. Quayum	Computer Operator
3	Md. Jhangir Hossain	Computer Operator
4	Raihanul Islam	CAD Operator
5	Zakaria Ahmed	CAD Operator
6	ANM Shafiqul Alam	Surveyor
7	Aolad Hossain	Surveyor

Gournadi

রেজিষ্টার্ড নং ডি এ-১

বাংলাদেশ গেজেট

অতিরিক্ত সংখ্যা

কর্তৃপক্ষ কর্তৃক প্রকাশিত

বুধবার, অক্টোবর ২, ১৯৯৬

গণপ্রজাতন্ত্রী বাংলাদেশ সরকার

স্থানীয় সরকার, পল্লী উন্নয়ন ও সমবায় মন্ত্রণালয়

স্থানীয় সরকার বিভাগ

(পৌর-৩ শাখা)

প্রজ্ঞাপন

তারিখ, ১৬ই আশ্বিন ১৪০৩/১লা অক্টোবর ১৯৯৬

এস, আর, ও নং ১৭০-আইন/৯৬—Paurashava Ordinance, 1977 (XXVI of 1977) এর section 3(1) এ প্রদত্ত ক্ষমতাবলে সরকার বরিশাল জেলার গৌরনদী থানাধীন নিম্ন তফসিলে বর্ণিত পল্লী এলাকাসমূহকে এতদ্বারা শহর এলাকা ঘোষণা করিল।

তফসিল

ক্রমিক নং	ইউনিয়নের নাম	মৌজার নাম	জে, এল, নং	দাগ নং
১	২	৩	৪	৫
(১)	বার্থী	সুন্দরদী	৬৩	১—২৫৭৮
		টরকিরচর	৬২	১—৩৯৭
		লাখেরাজ কসবা	৬৬	১—৩৭৩
(২)	চাঁদশী	গোবর্ধন	৭৪	১—৩৭০
		বড় কসবা	৬৯	১—১৪৩৪
		বানিয়াজুরী	৭৫	১—৬১১
		চর গাঁদাতলী	৭২	১—৩৫৪

(১১০৫১)

মূল্য: টাকা ১.০০

১	২	৩	৪	৫
		দক্ষিণ পালরদি	৭১	১—৬৬৩
		উত্তর পালরদি	৭০	১—৫৩৩
		উত্তর বিজয়পুর	৭৩	১—৫০৯
(৩)	মাহিলারা	কাসেমাবাদ	১৪১	১—১৮১১
		সাওড়া	১৩৩	১—৪০১
		তিনাগার	১৩৯	১—৪৪৩
		দক্ষিণ বিজয়পুর	১৩৪	১—৫৬১
		গেরাকুল	১৪০	১—৫২৮
		আশোকাঠী	১৩৮	১—৫৬৬
(৪)	নলচিড়া	দিয়াশুর	১৫২	১—৫৫৩

রাষ্ট্রপতির আদেশক্রমে

মোহাম্মদ হোসেন সেরনিয়াবাত
উপ-সচিব (পৌর)।

মোঃ মিজানুর রহমান, উপ-নিয়ন্ত্রক, বাংলাদেশ সরকারী মুদ্রণালয়, ঢাকা কর্তৃক মুদ্রিত
মোঃ আতোয়ার রহমান, উপ-নিয়ন্ত্রক, বাংলাদেশ ফরমস্ ও প্রকাশনী অফিস,
তেজগাঁও, ঢাকা কর্তৃক প্রকাশিত।

Annex- C: Land use Permission

a. Urban Residential Land Use

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table C.1: Land Use Permitted

Permitted Urban Residential Uses
Artisan's Shop
Assisted Living or Elderly Home
Confectionery Shop
Barber Shop
Child Daycare \ Preschool
Cleaning \ Laundry Shop
Communication Service Facilities
Communication Tower Within Permitted Height
Condominium or Apartment
Cottage
Cyber Café
Daycare Center (Commercial or Nonprofit)
Drug Store or Pharmacy
Employee Housing (Guards \ Drivers) \ Ancillary Use
General Store
Grocery Store
High School
Household Appliance and Furniture Repair Service (No Outside Storage)
Housing For Seasonal Firm Labor
Landscape and Horticultural Services
Mosque, Place Of Worship
Newspaper Stand
Nursery School
Orphanage
Eidgah
Photocopying and Duplicating Services (No Outside Storage)
Pipelines and Utility Lines
Playing Field
Primary School
Private Garages (Ancillary Use)
Project Identification Signs
Property Management Signs
Public Transport Facility
Satellite Dish Antenna
Shelter (Passers By)
Shoe Repair or Shoeshine Shop (Small)
CBO Office
Special Dwelling
Temporary Tent
Temporary tent for Permitted Function
Newspaper Stand
Specialized School: Dance, Art, Music, Physically Challenged & Others
Transmission Lines
Urban-Nature Reserve
Utility Lines
Woodlot
Children's Park (Must Have Parking)
ATM Booth
Water Pump \ Reservoir
Monument (Neighborhood Scale)
Bill Payment Booth
Boarding and Rooming House
Dormitory
Memorial Structure (Ancillary)
Neighborhood Center* *(Where Neighborhood Center exists)*
Permitted
Community Center
Doctor \ Dentist Chamber
Cultural Exhibits and Libraries
Fast Food Establishment \ Food Kiosk
Flowers, Nursery Stock and Florist Supplies
Fitness Centre
Gaming Clubs
Departmental Stores
Retail Shops \ Facilities

Source: Compiled by the Consultants

*Permission of Neighborhood Center Facilities in absence of formal neighborhood should be subject to Landuse Permit Committee

Land Use Conditionally Permitted

The following uses may be permitted or disallowed in this zone after review and approval by the authority/committee following appropriate procedure while the application meets the criteria mentioned in the requirement.

Table C.2: Land Use Conditionally Permitted

Conditionally Permitted Urban Residential Uses
Addiction Treatment Center
Amusement and Recreation (Indoors)
Funeral Services
Art Gallery, Art Studio \ Workshop
Automobile Driving Academy
Beauty and Body Service
Billiard Parlor \ Pool Hall
Book or Stationery Store or Newsstand
Building Maintenance \ Cleaning Services, No Outside Storage
Bus Passenger Shelter
Graveyard \ Cemetery
Coffee Shop \ Tea Stall
Correctional Institution
Courier Service
Crematorium
Plantation (Except Narcotic Plant)
Furniture & Variety Stores
Emergency Shelter
Energy Installation
Garages
Garden Center or Retail Nursery
Fire Brigade Station
Police Station
Temporary Rescue Shed
Guest House
Slaughter House
Static Transformer Stations
Tourist Home or Resort
Market (Bazar)
Optical Goods Sales
Outdoor Café
Outdoor Fruit and Vegetable Markets
Community Hall
Neighborhood Co-Operative Office
Overhead Water Storage Tanks
Row House
Paints and Varnishes Store
Parking Lot
Patio Homes
Photofinishing Laboratory
Post Office
Postal Facilities
Sports and Recreation Club
Tennis Club
Flood Management Structure
Telephone Sub Station
Electrical Sub Station

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

b. General Industry
Land use Permitted

General Industry land use category approve only Green and Orange-A category industry mentioned in *The Environmental Conservation Rule, 1997*.The following uses in the tables are proposed to be applicable for this zone only.

Table C.3: Land Use Permitted

Permitted General Industrial Activities
Confectionery Shop
Bank & Financial Institution
Bicycle Assembly, Parts and Accessories
Blacksmith
Bus Passenger Shelter
Communication Tower Within Permitted Height
Freight Transport Facility
Police Box \ Barrack
Fire \ Rescue Station
Grocery Store
Household Appliance and Furniture Repair Service

Permitted General Industrial Activities
Machine Sheds
Meat and Poultry (Packing & Processing)
Mosque, Place Of Worship
Newspaper Stand
Photocopying and Duplicating Services
Pipelines and Utility Lines
Printing, Publishing and Distributing
Public Transport Facility
Restaurant
Retail Shops \ Facilities
Salvage Processing
Salvage Yards
Satellite Dish Antenna
Sawmill, Chipping and Pallet Mill
Shelter (Passers By)
Television, Radio or Electronics Repair (No Outside Storage)
Transmission Lines
Truck Stop & Washing or Freight Terminal
Utility Lines
Wood Products
Woodlot
ATM Booth
Water Pump \ Reservoir
Effluent Treatment Plant
Social Forestry

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or denied in this zone after review and approval by the authority/committee following appropriate procedure.

Table C.4: Land Use Conditionally Permitted

Conditionally Permitted General Industrial Land Uses
Amusement and Recreation (Indoors)
Appliance Store
Plantation (Except Narcotic Plant)
Cyber Café
Daycare Center (Commercial or Nonprofit)
Doctor \ Dentist Chamber
Electrical and Electronic Equipment and Instruments Sales
Employee Housing
Energy Installation
Fast Food Establishment \ Food Kiosk
Garages
Grain & Feed Mills
Incineration Facility
Super Store
Lithographic or Print Shop
Motor Vehicle Fuelling Station \ Gas Station
Motorcycle Sales Outlet
Outdoor Fruit and Vegetable Markets
Outside Bulk Storage
Overhead Water Storage Tanks
Painting and Wallpaper Sales
Paints and Varnishes
Parking Lot
Parking Lot (Commercial)
Private Garages
Retail Shops Ancillary To Studio \ Workshop
Jute Mill

Source: Compiled by the Consultants

Restricted Uses

All other uses; except the permitted and conditionally permitted uses.

c. Commercial Zone

Land Use Permitted

Commercial zone is mainly intended for supporting the office and business works. There are several functions that are permitted in this zone.

Table C.5: Land Use Permitted

Permitted Commercial Activity
Accounting, Auditing or Bookkeeping Services
Billboards, Advertisements & Advertising Structure
Agri-Business
Agricultural Sales and Services
Ambulance Service
Antique Shop
Appliance Store

Permitted Commercial Activity
Auction Market
Auditorium, Coliseum, Meeting Halls, and Conference Facilities, Convention
Auto Leasing or Rental Office
Auto Paint Shop
Auto Parts and Accessory Sales (Indoors)
Auto Repair Shop (With Garage)
Automobile Wash
Automobile Sales
Confectionery Shop
Bakery or Confectionery Retail
Bank & Financial Institution
Bar (Licensed)
Barber Shop
Beauty and Body Service
Bicycle Shop
Billiard Parlor \ Pool Hall
Book or Stationery Store or Newsstand
Building Material Sales or Storage (Indoors)
Bulk Mail and Packaging
Bus Passenger Shelter
Cinema Hall
Communication Service Facilities
Communication Tower Within Permitted Height
Computer Maintenance and Repair
Computer Sales & Services
Conference Center
Construction Company
Courier Service
Cyber Café
Daycare Center (Commercial or Nonprofit)
Department Stores, Furniture & Variety Stores
Doctor \ Dentist Chamber
Drug Store or Pharmacy
Electrical and Electronic Equipment and Instruments Sales
Fast Food Establishment \ Food Kiosk
Freight Handling, Storage & Distribution
Freight Transport Facility
Freight Yard
General Store
Grocery Store
Guest House

Permitted Commercial Activity
Hotel or Motel
Inter-City Bus Terminal
Jewelry and Silverware Sales
Junk \ Salvage Yard
Super Store
Market (Bazar)
Mosque, Place Of Worship
Motorcycle Sales Outlet
Multi-Storey Car Park
Newspaper Stand
Outdoor Fruit and Vegetable Markets
Outdoor Recreation, Commercial
Parking Lot (Commercial)
Pet Store
Photocopying and Duplicating Services
Photofinishing Laboratory & Studio
Pipelines and Utility Lines
Post Office
Preserved Fruits and Vegetables Facility \ Cold Storage
Printing, Publishing and Distributing
Project Identification Signs
Property Management Signs
Public Transport Facility
Refrigerator or Large Appliance Repair
Resort
Restaurant
Retail Shops \ Facilities
Salvage Processing
Salvage Yards
Satellite Dish Antenna
Sawmill, Chipping and Pallet Mill
Shelter (Passers By)
Shopping Mall \ Plaza
Slaughter House
Software Development
Sporting Goods and Toys Sales
Taxi Stand
Telephone Exchanges
Television, Radio or Electronics Repair (No Outside Storage)
Theater (Indoor)
Transmission Lines
Utility Lines
Vehicle Sales & Service, Leasing or Rental

Permitted Commercial Activity
Veterinarian Clinics, Animal Hospitals, Kennels and Boarding Facilities
Warehousing
Wood Products
Woodlot
ATM Booth
Water Pump \ Reservoir
Agro-Based Industry (Rice Mill, Saw Mill, Cold Storage)
Social Forestry

Source: Compiled by the Consultants

Land Use Conditionally Permitted

Some functions are permitted with some condition in this zone.

Table C.6: Land Use Conditionally Permitted

Conditionally permitted commercial activities
Amusement and Recreation (Indoors)
Bicycle Assembly, Parts and Accessories
Broadcast Studio \ Recording Studio (No Audience)
Coffee Shop \ Tea Stall
Concert Hall, Stage Shows
Construction, Survey, Soil Testing Firms
Trade Shows
Craft Workshop
Plantation (Except Narcotic Plant)
Energy Installation
Firm Equipment Sales & Service
Agricultural Chemicals, Pesticides or Fertilizers Shop
Fitness Centre
Flowers, Nursery Stock and Florist Supplies
Forest Products Sales
Fuel and Ice Dealers
Garages
Garden Center or Retail Nursery
Police Box \ Barrack
Fire \ Rescue Station
Grain & Feed Mills
Household Appliance and Furniture Repair Service

Conditionally permitted commercial activities
Incineration Facility
Indoor Amusement Centers, Game Arcades
Indoor Theatre
Lithographic or Print Shop
Motor Vehicle Fuelling Station \ Gas Station
Musical Instrument Sales or Repair
Optical Goods Sales
Painting and Wallpaper Sales
Paints and Varnishes
Parking Lot
Patio Homes
Postal Facilities
Poultry
Private Garages
Professional Office
Retail Shops Ancillary To Studio \ Workshop
Stone \ Cut Stone Products Sales

Source: Compiled by the Consultants

Restricted Uses

All other uses except;, the permitted and conditionally permitted uses.

d. Rural Settlement

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table C.7: Land Use Permitted

Permitted Rural Settlement
Agricultural Dwellings
Animal Husbandry
Animal Shelter
Graveyard \ Cemetery
Child Daycare \ Preschool
Primary School
Communication Tower Within Permitted Height
Cottage
Crematorium
Dairy Firming
General Store
Grocery Store
Handloom (Cottage Industry)

Permitted Rural Settlement
Housing For Seasonal Firm Labor
Mosque, Place Of Worship
Newspaper Stand
Nursery School
orphanage
Outdoor Religious Events (Eidgah)
Playing Field
Satellite Dish Antenna
NGO \ CBO Facilities
Special Dwelling (E.G. Dorm For Physically Challenged Etc.)
Temporary Shed \ Tent
Specialized School: Dance, Art, Music, Physically Challenged & Others
Static Electrical Sub Stations
Transmission Lines
Utility Lines
Woodlot
Plantation (Except Narcotic Plant)
Social Forestry
Memorial Structure

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or disallowed in this zone after review and approval by the authority/committee following appropriate procedure while the application meets the criteria mentioned in the requirement.

Table No. C.8: Land Use Conditionally Permitted

Conditionally permitted uses under Rural Settlement
Artisan's Shop (Potter, Blacksmith, and Goldsmith Etc.)
Research organization (Agriculture \ Fisheries)
Energy Installation
Fish Hatchery
Garden Center or Retail Nursery
Emergency Shelter
Sports and Recreation Club, Firing Range: Indoor

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

e. Mixed use zone

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table C.9: Land Use Permitted

Permitted uses in Mixed Use Zone
Accounting, Auditing or Bookkeeping Services
Addiction Treatment Center
Billboards, Advertisements & Advertising Structure
Agricultural Sales and Services
Antique Store
Appliance Store
Art Gallery, Art Studio \ Workshop
Artisan's Shop
Assisted Living or Elderly Home
Auditorium, Coliseum, Meeting Halls, and Conference Facilities, Convention
Auto Leasing or Rental Office
Automobile Wash
Automobile Driving Academy
Confectionery Shop
Bakery or Confectionery Retail
Bank & Financial Institution
Barber Shop
Bicycle Shop
Billiard Parlor \ Pool Hall
Blacksmith
Boarding and Rooming House
Book or Stationery Store or Newsstand
Bus Passenger Shelter
Child Daycare \ Preschool
Cleaning \ Laundry Shop
Commercial Recreational Buildings
Communication Service Facilities
Communication Tower Within Permitted Height
Community Center
Condominium or Apartment

Permitted uses in Mixed Use Zone
Correctional Institution
Courier Service
Cyber Café
Daycare Center (Commercial or Nonprofit)
Doctor \ Dentist Chamber
Employee Housing
Fabric Store
Fast Food Establishment \ Food Kiosk
Funeral Services
General Store
Grocery Store
Guest House
Hospital
Jewelry and Silverware Sales
Landscape and Horticultural Services
Mosque, Place Of Worship
Newspaper Stand
Nursery School
Photocopying and Duplicating Services
Pipelines and Utility Lines
Primary School
Project Identification Signs
Property Management Signs
Public Transport Facility
Resort
Satellite Dish Antenna
Shelter (Passers By)
Shoe Repair or Shoeshine Shop (Small)
Slaughter House
Social organization
Software Development
Special Dwelling
Toys and Hobby Goods Processing and Supplies
Training Centre
Transmission Lines
Utility Lines
Vehicle Sales & Service, Leasing or Rental
Warehousing
Woodlot
Children's Park
ATM Booth
Water Pump \ Reservoir
Social Forestry
Dormitory
Rickshaw \ Auto Rickshaw Stand

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or disallowed in this zone after review and approval by the authority/committee.

Table C.10: Land Use Conditionally Permitted

Conditionally permitted uses in Mixed Use Zone
Agricultural Chemicals, Pesticides or Fertilizers Shop
Amusement and Recreation (Indoors)
Beauty and Body Service
Broadcast Studio \ Recording Studio (No Audience)
Building Maintenance \ Cleaning Services, No Outside Storage
Building Material Sales or Storage (Indoors)
Graveyard \ Cemetery
Coffee Shop \ Tea Stall
Computer Maintenance and Repair
Computer Sales & Services
Concert Hall, Stage Shows
Conference Center
Construction Company
Construction, Survey, Soil Testing Firms
Cottage
Counseling Services
Craft Workshop
Crematorium
Plantation (Except Narcotic Plant)
Cultural Exhibits and Libraries
Department Stores, Furniture & Variety Stores
Drug Store or Pharmacy
Energy Installation
Fitness Centre
Flowers, Nursery Stock and Florist Supplies
Freight Handling, Storage & Distribution
Freight Transport Facility
Gaming Clubs
Garages
Garden Center or Retail Nursery
Commercial Office
Project Office
Government Office
Hotel or Motel

Conditionally permitted uses in Mixed Use Zone
Household Appliance and Furniture Repair Service
Indoor Amusement Centers, Game Arcades
Indoor Theatre
Lithographic or Print Shop
Market (Bazar)
Health Office, Dental Laboratory, Clinic or Lab
Musical Instrument Sales or Repair
Optical Goods Sales
Outdoor Café
Outdoor Fruit and Vegetable Markets
Painting and Wallpaper Sales
Paints and Varnishes
Patio Homes
Photofinishing Laboratory & Studio
Poultry
Printing, Publishing and Distributing
Psychiatric Hospital
Retail Shops Ancillary To Studio \ Workshop
Radio \ Television or T&T Station With Transmitter Tower
Refrigerator or Large Appliance Repair
Restaurant
Retail Shops \ Facilities
Sporting Goods and Toys Sales
Sports and Recreation Club, Firing Range: Indoor
Telephone Exchanges
Television, Radio or Electronics Repair (No Outside Storage)

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

f. Education and Research Area

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table C.11: Land Use Permitted

Permitted uses under Education & Research Zone
Addiction Treatment Center
Billboards, Advertisements & Advertising Structure
Art Gallery, Art Studio \ Workshop
Automobile Driving Academy
Confectionery Shop
Bus Passenger Shelter
Child Daycare \ Preschool
College, University, Technical Institute
Communication Service Facilities
Communication Tower Within Permitted Height
Conference Center
Correctional Institution
Cultural Exhibits and Libraries
Cyber Café
Freight Transport Facility
General Store
Grocery Store
High School
Hospital
Lithographic or Print Shop
Mosque, Place Of Worship
Multi-Storey Car Park
Newspaper Stand
Nursery School
Outdoor Religious Events
Photocopying and Duplicating Services
Post Office
Primary School
Professional Office
Project Identification Signs
Property Management Signs
Public Transport Facility
Satellite Dish Antenna
School (Retarded)
Scientific Research Establishment
Shelter (Passers By)
Specialized School: Dance, Art, Music & Others
Training Centre
Transmission Lines
Utility Lines
Vocational, Business, Secretarial School
Woodlot
ATM Booth
Water Pump \ Reservoir
Social Forestry
Dormitory
Veterinary School \ College and Hospital

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or denied in this zone after review and approval by the authority/committee.

Table C.12: Land Use Conditionally Permitted

Conditionally permitted uses under Education and Research Zone
Auditorium, Coliseum, Meeting Halls, and Conference Facilities, Convention
Bank & Financial Institution
Barber Shop
Boarding and Rooming House
Book or Stationery Store or Newsstand
Coffee Shop \ Tea Stall
Counseling Services
Courier Service
Plantation (Except Narcotic Plant)
Daycare Center (Commercial or Nonprofit)
Doctor \ Dentist Chamber
Drug Store or Pharmacy
Fast Food Establishment \ Food Kiosk
Flowers, Nursery Stock and Florist Supplies
Gallery \ Museum
Garages
Indoor Theatre
orphanage
Outdoor Café
Parking Lot
Pipelines and Utility Lines
Postal Facilities
Psychiatric Hospital

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

g. Government Office

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table C.13: Land Use Permitted

Permitted uses under Government Office Zone
Accounting, Auditing or Bookkeeping Services
Billboards, Advertisements & Advertising Structure
Confectionery Shop
Bus Passenger Shelter
Civic Administration
Communication Service Facilities
Communication Tower Within Permitted Height
Construction, Survey, Soil Testing Firms
Cultural Exhibits and Libraries
Cyber Café
Emergency Shelter
Freight Transport Facility
General Store
Project Office
Government Office
Grocery Store
Guest House
Multi-Storey Car Park
Newspaper Stand
Outdoor Religious Events
Photocopying and Duplicating Services
Post Office
Professional Office
Public Transport Facility
Satellite Dish Antenna
Scientific Research Establishment
Shelter (Passers By)
Training Centre
Transmission Lines
Utility Lines
Woodlot
ATM Booth
Water Pump \ Reservoir
Social Forestry

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or denied in this zone after review and approval by the authority/committee.

Table C.14: Land Use Conditionally Permitted

Conditionally permitted uses under Government office
Amusement and Recreation (Indoors)
Auditorium, Coliseum, Meeting Halls, and Conference Facilities, Convention
Bank & Financial Institution
Boarding and Rooming House
Book or Stationery Store or Newsstand
Coffee Shop \ Tea Stall
Conference Center
Courier Service
Plantation (Except Narcotic Plant)
Daycare Center (Commercial or Nonprofit)
Detention Facilities
Doctor \ Dentist Chamber
Energy Installation
Fast Food Establishment \ Food Kiosk
Flowers, Nursery Stock and Florist Supplies
Freight Handling, Storage & Distribution
Freight Yard
Gallery \ Museum
Garages
Police Box \ Barrack
Fire \ Rescue Station
Lithographic or Print Shop
Mosque, Place Of Worship
Outdoor Café
Parking Lot
Parking Lot (Commercial)
Pipelines and Utility Lines
Postal Facilities

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

h. Agricultural Zone

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table C.15: Land Use Permitted

Permitted uses under Agricultural Zone
Food Grain Cultivation
Vegetable Cultivation
Cash Crop Cultivation
Horticulture
Arboriculture
Dairy Firming
Deep Tube Well
Shallow Tube Well
Irrigation Facilities (Irrigation Canal, Culvert, Flood Wall etc)
Temporary Structure (Agricultural)
Animal Shelter
Duckery
Aquatic Recreation Facility (Without Structure)
Tree Plantation (Except Narcotic Plant)
Aquaculture
Static Transformer Stations
Transmission Lines
Utility Lines
Woodlot
Social Forestry

Source: Compiled by the Consultants

Land Use Conditionally Permitted

Table A18: Land Use Conditionally Permitted

Conditionally permitted uses under Agricultural Zone
Graveyard \ Cemetery
Communication Tower Within Permitted Height
Crematorium
Fish Hatchery
Garden Center or Retail Nursery
Poultry

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

j. Open Space

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table C.16: Land Use Permitted

Permitted uses under Open Space
Botanical Garden & Arboretum
Bus Passenger Shelter
Caravan Park \ Camping Ground
Carnivals and Fairs
Circus
Plantation (Except Narcotic Plant)
Landscape and Horticultural Services
Open Theater
Park and Recreation Facilities (General)
Pipelines and Utility Lines
Playing Field
Special Function Tent
Tennis Club
Transmission Lines
Urban-Nature Reserve
Utility Lines
Woodlot
Zoo
Roadside Parking
Social Forestry
Memorial Structure

Source: Compiled by the Consultants

Landuse Conditionally Permitted

Table C.17: Land Use Conditionally Permitted

Conditionally permitted uses under open space
Communication Tower Within Permitted Height
Trade Shows
Fitness Centre
Flowers, Nursery Stock and Florist Supplies
Golf Course
Motorized Recreation
Outdoor Recreation Facilities
Outdoor Recreation, Commercial
Outdoor Sports and Recreation
Park Maintenance Facility
Retreat Center
Sports and Recreation Club, Firing Range: Indoor

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted.

k. Water Body

Retaining water is the main purpose of this type of Landuse.

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table C.18: Land Use Permitted

Permitted uses under Water Body
Aquatic Recreation Facility (Without Structure)
Fishing Club
Utility Lines
Water Parks
Memorial Structure

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or denied in this zone after review and approval by the authority/committee.

Table C.19: Land Use Conditionally Permitted

Conditionally permitted uses under water body
Plantation (Except Narcotic Plant)
Marina \ Boating Facility
Motorized Recreation

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted.

গৌরনদী পৌরসভার মহাপরিকল্পণার উপর চূড়ান্ত মতবিনিময় সভার কার্যবিবরণী

তারিখ: ১৩/১২/২০১৩
স্থান: গৌরনদী পৌরসভা
সময়: বিকাল ৩:০০ ঘটিকায়

স্থানীয় সরকার প্রকৌশল অধিদপ্তর, গৌরনদী পৌরসভা ও পরামর্শক প্রতিষ্ঠানের যৌথ উদ্যোগে গৌরনদী পৌরসভার মহাপরিকল্পণার উপর মাননীয় মেয়র জনাব মোঃ হারিছুর রহমান এর সভাপতিত্বে চূড়ান্ত মতবিনিময় সভা অনুষ্ঠিত হয়। উক্ত মতবিনিময় সভায় পৌরসভার কাউন্সিলরবৃন্দ সহ স্থানীয় গণ্যমান্য ব্যক্তিবর্গ, বিভিন্ন সরকারি-বেসরকারি অধিদপ্তরের কর্মকর্তাবৃন্দ, স্থানীয় সরকার প্রকৌশল অধিদপ্তরের প্রতিনিধি এবং মহাপরিকল্পণা প্রণয়ন প্রকল্পে নিযুক্ত পরামর্শকবৃন্দ উপস্থিত হয়ে আলোচনায় অংশগ্রহন করেন।

সভার শুরুতে মাননীয় মেয়র মহোদয় জনাব মোঃ হারিছুর রহমান উপস্থিত সকলকে শুভেচ্ছা জানিয়ে আনুষ্ঠানিকভাবে সভার কার্যক্রম শুরু করেন এবং স্বাগত বক্তব্যে উল্লেখ করেন যে, আগামী (২০) বিশ বছরের জন্য এই মহাপরিকল্পণা। উক্ত পরিকল্পণায় উপস্থিত সকলকে সুচিন্তিত মতামত প্রদানের জন্য আহ্বান করেন যাতে করে পরিকল্পণাটি আরও গঠণমূলক ও বাস্তব সম্মত হয়।

পরামর্শক প্রতিষ্ঠানের পক্ষ থেকে ডঃ নুরুল ইসলাম নাজেম, উপস্থিত সকলকে স্বাগত জানিয়ে মহাপরিকল্পণার উপর Power Point Presentation এর মাধ্যমে তার বক্তব্য তুলে ধরেন। তিনি কার্যক্রমসমূহ, উন্নয়নের সম্ভাবনাসমূহ ধাপে ধাপে বর্ণনা করেন। এরপর মহাপরিকল্পণার কোথায় কিভাবে প্রস্তাবনা সমূহ ওয়ার্ড ভিত্তিক দেওয়া হয়েছে সেসব বিষদ আলোচনা করেন। তিনি আরও উল্লেখ করেন যে, সকলের মতামতের ভিত্তিতে যে প্রস্তাবসমূহ দেওয়া হয়েছিল তা নিম্নরূপ:

Proposed Facility	Area (acre)	Ward No.	Mouza Name	Plot No.
Resettlement Zone	6.67	6	Gobardhan	13, 15-28, 54, 56-58, 65, 391
Low Income Housing	10.91	8	Diasur	405, 413-38, 442, 546, 551
Housing Area	33.93	9	Harisana(Kasemabad)	885-86, 888-91, 893-94, 897-08, 910-923, 925-26, 956, 958-62, 979,1660-67, 1669-88, 1694-99, 1702-03
Katcha Bazar	0.36	7	Dakshin Bijoypur	534
Super Market	1.92	7	Asokati	180-81,191,193-96,198,204,564
Shopping Complex	2.79	9	Harisana(Kasemabad)	679-87,689-90,694-95
Slaughter House	1.84	2	Bara Kasba	149, 157, 159,165, 234, 236-37
Wholesale Market	4.44	1	Sundardi	2123
Neighborhood Market	1.23	9	Harisana(Kasemabad)	572,574,591-92,984
Pauro Market	0.42	5	Char Gadhatali	252-55,257,275,312
Retailsale Market	3.42		Lakherajkasba	228-41,243,277-78
Industrial zone	12.87	3	Baniasuri	266-67,270-75,329-46,348-51,353-56,387
Toll Center	0.31	3	Baniasuri	213,247,280-81
Stadium	5.35	9	Harisana(Kasemabad)	843-44,846-52,856-59,987
Linear Park	1.95	2	Bara Kasba	265,268-69,277,357-58,360,366,375,378
Round About	0.07	6	Uttar Bijaypur	346,370,405-07

মোঃ হারিছুর রহমান
মেয়র
গৌরনদী পৌরসভা, বরিশাল।

Proposed Facility	Area (acre)	Ward No.	Mouza Name	Plot No.
Shishu Park	2.49	4,5	Dakshin Palardi & Tikhasar	160,174-89,662, 50,427,429
Hospital	4.26	8	Diasur	127-30,132,135-39,142
Community Center	0.98	7	Asokati	40-42,68-70
Pauro Library	0.14	5	Char Gadhatali	134,156
Proposed Gausia Madrasa Graveyard	0.56	1	Sundardi	38,51-52
Girls College	4.48	7	Dakshin Bijoypur	251,253-54,256,265-69,289-95,308-10
Girls School	3.07	9	Harisana(Kasemabad)	770-71,896-97,1645,1648-51,1654-58,1661-62
Vocational Training Center cum Cyclone Shelter	2.45	2	Bara Kasba	1244-46,1248-54,1305-07,1317
Bus Stand	0.60	6	Uttar Bijaypur	451
Bus Terminal	5.22	9	Harisana(Kasemabad)	1488-96,1787-92,1795
Rickshaw stand	0.40	1	Sundardi	30-31,52,54-55
Fuel station	1.21	4	Dakshin Palardi	163-66,169-70
Truck Terminal	0.81	2	Tarkir Char	101-03
Truck Stand	1.63	3	Baniasuri	268-71,275-76,283
Overhead Tank	1.54	3	Baniasuri	597,600-01,603-04,606-07
Water Treatment Plant	3.91	6	Gobardhan	122-23,126-27,195-03
Waste Disposal Site	5.43	9	Harisana(Kasemabad)	1783-87,1792-95,1799-01

সমাপনী বক্তব্যে মেয়র মহোদয় পরামর্শক প্রতিষ্ঠানের পরিকল্পণাবিদগণকে এবং স্থানীয় সরকার প্রকৌশল অধিদপ্তরকে পৌরসভার মহাপরিকল্পণা প্রনয়নের জন্য পুনরায় ধন্যবাদ জ্ঞাপন করেন এবং সম্ভাব্য সকল দিকনির্দেশনাগুলি সন্নিবেশিত করে যথাশীঘ্র সম্ভব চূড়ান্ত মহাপরিকল্পণা প্রণয়ন করার জন্য অনুরোধ করেন। সভায় আর কোন আলোচনা না থাকায় সকলকে ধন্যবাদ জানিয়ে পৌরসভার স্বপ্ন বাস্তবায়নের আশা ব্যক্ত করে সভার কার্যক্রম সমাপ্তি ঘোষণা করেন।

(জনাব মোঃ হাবিছুর রহমান)
মেয়র
গৌরনদী পৌরসভা

মোঃ হাবিছুর রহমান
মেয়র
গৌরনদী পৌরসভা, বরিশাল।

স্থানীয় সরকার প্রকৌশল অধিদপ্তর, ঢাকা-১২০৭
উপজেলা শহর অবকাঠামো উন্নয়ন প্রকল্প, প্যাকেজ-১১

গৌরনদী পৌরসভার মহাপরিকল্পনার উপর চূড়ান্ত মতবিনিময় সভা
গৌরনদী পৌরসভা।
স্থান: গৌরনদী পৌরসভা। তারিখ: ১৩ ডিসেম্বর, ২০১৩ খ্রিঃ; বিকাল ৩:০০ ঘটিকা

অংশগ্রহনকারীর তালিকা

ক্রমিক নং	নাম	প্রতিষ্ঠান ও পদবী	ফোন নম্বর	স্বাক্ষর
১	মো: তাজিরুল মেহেদী	সহকারী প্রকৌশলী গৌরনদী	01821260689	
২	[illegible]	[illegible]	[illegible]	
৩	সরদার আবুবক্কর	সহকারী প্রকৌশলী গৌরনদী পৌরসভা	01736681273	
৪	[illegible]	[illegible]	01732727983	১৩/১২/১৩
৫	[illegible]	[illegible]	[illegible]	১৩/১২/১৩
৬	[illegible]	স্বাস্থ্য সহকারী গৌরনদী পৌরসভা	01934-329693	১৩/১২/১৩
৭	[illegible]	[illegible]	01814-851395	১৩/১২/১৩
৮	[illegible]	[illegible]	01715-245228	১৩/১২/১৩
৯	[illegible]	[illegible]	01727058884	13.12.13.
১০	[illegible]	[illegible]	01912943161	১৩/১২/১৩
১১	মো: [illegible]	সহঃ প্রকৌঃ সার্ভেয়ার গৌরনদী পৌরসভা	01718217632	১৩/১২/১৩

ক্রমিক নং	নাম	প্রতিষ্ঠান ও পদবী	ফোন নম্বর	স্বাক্ষর
১২	মোঃ গিয়াস উদ্দীন মন্ডকার	পৌরনদী পৌরসভা পানি সরবরাহ শাখা -বিলক্লার্ক	০১৭৪৫৫৭ ০১৭৪৫৫৭১৬৪৪	
১৩	মো: জাকির হোসাইন	পৌরনদী পৌরসভা সহ: কর আদায়কারী	০১৭৩৩১০৭৩৪৩	
১৪	মোছাঃ তাহমিনা ইসলাম	পৌরনদী পৌরসভা পানি সরবরাহ শাখা পাম্প চালক	০১৩১৭৩৫৭৭৩০	
১৫	মো: সাহাবুল শেখ	কর সহকারী	০১৭২২৩২৯৯৭	
১৬	মোছা: রুমা আক্তার মিলন	পৌরনদী পৌরসভা সহ: হিসাবরক্ষক	০১৭২৯৭১৬২১৭	
১৭	মোঃ মেহেদী হাসান	পৌরনদী পৌরসভা লাইসেন্স শাখা	০১৭২৭৪২৩৫৩৭	
১৮	আনোয়ারা ভেরানিমাবাত	ধর্ম,প্রতিবন্ধী ও সমাজসেবা প্রতিনিধি কাউন্সিলর	০১৭২১৭৯০৯৫৩	
১৯	মিরিন আক্তার	কর আদায় পৌরনদী পৌরসভা	০১৭৭৩০৯৯৭৯	
২০	আয়মিন ইসলাম	কর আদায় পৌরনদী পৌরসভা	০১৯৫৭৭৫৪৪৩৩	আয়মিন
২১	আয়মিন খানম	কর আদায়কারী পৌরনদী পৌরসভা	০১৭২৪৩৯৭০৭	
২২	মিনারা বেগম	কর আদায় পৌরনদী পৌরসভা	০১৯৩৭৪৪৯৭১	
২৩	আফরোজা সাবরীন তানিয়া	কিশোরী সুপারভাইজার পৌরনদী পৌরসভা	০১৮৫৪৬৫২০	
২৪	মোঃ আল-আমিন	বিদ্যুৎ সহকারী পৌরনদী পৌরসভা	০১৯৫১০৫৪৫৫০	
২৫	মোঃ বশির শেখ	ড্রাইভার	০১৭৮৫৩৭৫৮৩৮	

ক্রমিক নং	নাম	প্রতিষ্ঠান ও পদবী	ফোন নম্বর	স্বাক্ষর
২৬	[illegible]	[illegible]	01716[illegible]	[illegible]
২৭	[illegible]	[illegible]	01[illegible]	[illegible]
২৮	[illegible]	[illegible]	01722[illegible]	[illegible]
২৯	[illegible]	[illegible]	01556570369	[illegible]
৩০	[illegible]	[illegible]	01721[illegible]26-39	[illegible]
৩১	[illegible]	[illegible]	01[illegible]580116	[illegible]
৩২	[illegible]	[illegible]	01684[illegible]	Rofik
৩৩	[illegible]	[illegible]	01918222630	[illegible]
৩৪	[illegible]	[illegible]	01926[illegible]	[illegible]
৩৫	[illegible]	[illegible]	01761640792	[illegible]
৩৬	[illegible]	[illegible]	01753625097	[illegible]
৩৭	[illegible]	[illegible]	01732[illegible]	[illegible]
৩৮	[illegible]	[illegible]	01[illegible]	[illegible]
৩৯	[illegible]	[illegible]	01754[illegible]	[illegible]

ক্রমিক নং	নাম	প্রতিষ্ঠান ও পদবী	ফোন নম্বর	স্বাক্ষর
৪০	মো: ফিরোজ সরদার	ড্রাইভার	01919 805803	ফিরোজ
৪১	কুর দিয়া বেগম	পাম্প পুরুষী	01721598588	কুর দিয়া
৪২	মো: সাগর	পাম্প পুরুষী	01731399767	সাগর
৪৩	মো: আরিফুল ইসলাম	কৃষি কাজ	01765072981	আরিফুল
৪৪	মো: সেরদৌস	কৃষি কাজ	01754489 3৪৪	সেরদৌস
৪৫	মো: খোকন হোসেন - মুন্সিগঞ্জ	ফার্মাসিস্ট - ২নং গেইট	01726311212	খোকন
৪৬				
৪৭				
৪৮				
৪৯				
৫০				
৫১				
৫২				

Table E1: Proposed Road Inventory

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Secondary Road	SR-1	Allah Er Dan Mosque Road	Widening	10.00	40	771.11	Ward No. 03	1st Phase
Secondary Road	SR-1	Allah Er Dan Mosque Road	Widening	10.00	40	602.09	Ward No. 04	1st Phase
Secondary Road	SR-2	Access Road	Widening	8.00	60	1921.08	Ward No. 06	1st Phase
Secondary Road	SR-3	Access Road	Widening	8.00	40	746.43	Ward No. 03	1st Phase
Secondary Road	SR-3	Access Road	Widening	8.00	40	1825.93	Ward No. 06	1st Phase
Secondary Road	SR-4	Access Road	Widening	8.00	40	1151.51	Ward No. 06	1st Phase
Secondary Road	SR-5	Access Road	Widening	8.00	60	741.02	Ward No. 04	1st Phase
Secondary Road	SR-5	Access Road	Widening	8.00	60	260.89	Ward No. 06	1st Phase
Secondary Road	SR-6	Access Road	Widening	10.00	40	859.24	Ward No. 07	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	1710.04	Ward No. 07	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	710.33	Ward No. 03	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	123.07	Ward No. 03	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	123.07	Ward No. 02	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	375.61	Ward No. 02	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	1130.37	Ward No. 04	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	2092.13	Ward No. 09	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	543.99	Ward No. 06	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	1565.18	Ward No. 01	1st Phase
Primary Road	PR-2	Proposed Bypass	Widening	8.00	100	667.52	Ward No. 09	1st Phase
Primary Road	PR-2	Proposed Bypass	Widening	8.00	100	157.07	Ward No. 06	1st Phase
Primary Road	PR-2	Proposed Bypass	Widening	8.00	100	28.87	Ward No. 01	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	19.10	Ward No. 03	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	19.10	Ward No. 02	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	16.30	Ward No. 03	1st Phase
Primary Road	PR-1	Dhaka-Barisal Highway	Widening	8.00	100	16.30	Ward No. 02	1st Phase
Tertiary Road	TR-3	Access Road	Widening	4.00	20	4.24	Ward No. 03	2nd Phase
Tertiary Road	TR-3	Access Road	Widening	4.00	20	4.24	Ward No. 02	2nd Phase
Tertiary Road	TR-4	Bir Muktijoddha porimal Mondol road	Widening	10.00	20	26.63	Ward No. 03	2nd Phase
Tertiary Road	TR-5	Bir Muktizuddha Syed Abul Hossain Ro	Widening	16.00	20	98.97	Ward No. 03	2nd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-6	Char Bridge Road	Widening	10.00	20	3.40	Ward No. 03	2nd Phase
Tertiary Road	TR-8	Char Bridge Road	Widening	10.00	20	279.07	Ward No. 06	2nd Phase
Tertiary Road	TR-9	Delukanto Road	Widening	4.00	20	110.27	Ward No. 03	2nd Phase
Tertiary Road	TR-10	Dhaka-Barisal Highway	Widening	20.00	20	125.21	Ward No. 06	2nd Phase
Tertiary Road	TR-12	Dhaka-Barisal Highway	Widening	20.00	20	10.30	Ward No. 06	2nd Phase
Tertiary Road	TR-13	Dhaka-Barisal Highway	Widening	20.00	20	159.87	Ward No. 03	2nd Phase
Tertiary Road	TR-14	Dhaka-Barisal Highway	Widening	20.00	20	33.94	Ward No. 03	2nd Phase
Tertiary Road	TR-15	Dhaka-Barisal Highway	Widening	20.00	20	293.33	Ward No. 03	2nd Phase
Tertiary Road	TR-17	Gaurnadi Sharikol GCC Road	Widening	12.00	20	4.16	Ward No. 06	2nd Phase
Tertiary Road	TR-18	Gaurnadi Sharikol GCC Road	Widening	12.00	20	449.99	Ward No. 03	2nd Phase
Tertiary Road	TR-20	Gobordhon Boro Bari Sarak	Widening	8.00	20	2.39	Ward No. 04	2nd Phase
Tertiary Road	TR-21	Golam Malek Road	Widening	10.00	20	333.30	Ward No. 03	2nd Phase
Tertiary Road	TR-22	Golam Malek Road	Widening	10.00	20	61.29	Ward No. 03	2nd Phase
Tertiary Road	TR-23	High School Road	Widening	10.00	20	46.54	Ward No. 03	2nd Phase
Tertiary Road	TR-24	Nabinagar Road	Widening	8.00	20	59.59	Ward No. 03	2nd Phase
Tertiary Road	TR-26	Sadar Road	Widening	12.00	20	83.65	Ward No. 04	2nd Phase
Tertiary Road	TR-27	Shahid Abdur Rob Serniabat Road	Widening	12.00	20	384.35	Ward No. 04	2nd Phase
Tertiary Road	TR-28	Shahid Abdur Rob Serniabat Road	Widening	12.00	20	418.06	Ward No. 04	2nd Phase
Tertiary Road	TR-30	Shahid Abdur Rob Serniabat Road	Widening	12.00	20	19.72	Ward No. 06	2nd Phase
Tertiary Road	TR-31	Taslima Akter Memorial Road	Widening	10.00	20	22.58	Ward No. 03	2nd Phase
Tertiary Road	TR-32	Turki Bondor Road	Widening	8.00	20	117.42	Ward No. 03	2nd Phase
Tertiary Road	TR-34	Turki Bondor Road	Widening	6.00	20	256.92	Ward No. 04	2nd Phase
Tertiary Road	TR-35	Turki Bondor Road	Widening	6.00	20	648.40	Ward No. 04	2nd Phase
Tertiary Road	TR-36	Turki Bondor Road	Widening	6.00	20	57.23	Ward No. 03	2nd Phase
Tertiary Road	TR-38	Turki Bondor Road	Widening	10.00	20	3.27	Ward No. 04	2nd Phase
Tertiary Road	TR-39	Turki Bondor Road	Widening	6.00	20	50.90	Ward No. 04	2nd Phase
Tertiary Road	TR-40	Turki Bondor Road	Widening	8.00	20	337.53	Ward No. 04	2nd Phase
Tertiary Road	TR-41	Turki Bondor Road	Widening	6.00	20	35.10	Ward No. 04	2nd Phase
Tertiary Road	TR-42	Turki Bondor	Widening	6.00	20	52.43	Ward	2nd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
		Road					No. 04	Phase
Tertiary Road	TR-43	Turki Bondor Road	Widening	6.00	20	386.87	Ward No. 04	2nd Phase
Tertiary Road	TR-44	Turki Bondor Road	Widening	6.00	20	115.69	Ward No. 04	2nd Phase
Tertiary Road	TR-45	Turki Bondor Road	Widening	6.00	20	35.45	Ward No. 04	2nd Phase
Tertiary Road	TR-46	Turki Bondor Road	Widening	6.00	20	271.93	Ward No. 04	2nd Phase
Tertiary Road	TR-47	Turki Bondor Road	Widening	6.00	20	62.38	Ward No. 04	2nd Phase
Tertiary Road	TR-48	Turki Bondor Road	Widening	6.00	20	36.91	Ward No. 04	2nd Phase
Tertiary Road	TR-49	Turki Bondor Road	Widening	6.00	20	23.08	Ward No. 04	2nd Phase
Tertiary Road	TR-50	Turki Bondor Road	Widening	10.00	20	29.72	Ward No. 04	2nd Phase
Tertiary Road	TR-51	Turki Bondor Road	Widening	3.00	20	25.64	Ward No. 04	2nd Phase
Tertiary Road	TR-52	Turki Bondor Road	Widening	6.00	20	29.19	Ward No. 04	2nd Phase
Tertiary Road	TR-53	Turki Bondor Road	Widening	6.00	20	126.06	Ward No. 03	2nd Phase
Tertiary Road	TR-53	Turki Bondor Road	Widening	6.00	20	461.99	Ward No. 02	2nd Phase
Tertiary Road	TR-53	Turki Bondor Road	Widening	6.00	20	598.88	Ward No. 04	2nd Phase
Tertiary Road	TR-54	Turki Bondor Road	Widening	6.00	20	66.16	Ward No. 03	2nd Phase
Tertiary Road	TR-55	Turki Bondor Road	Widening	6.00	20	0.00	Ward No. 03	2nd Phase
Tertiary Road	TR-55	Turki Bondor Road	Widening	6.00	20	0.00	Ward No. 04	2nd Phase
Tertiary Road	TR-56	Turki Bondor Road	Widening	5.00	20	20.06	Ward No. 04	2nd Phase
Tertiary Road	TR-57	Upazila Road	Widening	12.00	20	476.56	Ward No. 02	2nd Phase
Tertiary Road	TR-57	Upazila Road	Widening	12.00	20	152.28	Ward No. 04	2nd Phase
Tertiary Road	TR-58	Access Road	Widening	8.00	20	35.48	Ward No. 04	2nd Phase
Tertiary Road	TR-59	Access Road	Widening	6.00	20	19.93	Ward No. 02	2nd Phase
Tertiary Road	TR-60	Access Road	Widening	8.00	20	15.01	Ward No. 04	2nd Phase
Tertiary Road	TR-61	Access Road	Widening	8.00	20	75.87	Ward No. 02	2nd Phase
Tertiary Road	TR-62	Access Road	Widening	8.00	20	16.96	Ward No. 04	2nd Phase
Tertiary Road	TR-63	Access Road	Widening	8.00	20	40.99	Ward No. 02	2nd Phase
Tertiary Road	TR-64	Access Road	Widening	8.00	20	16.68	Ward No. 04	2nd Phase
Tertiary Road	TR-65	Access Road	Widening	8.00	20	348.69	Ward No. 02	2nd Phase
Tertiary Road	TR-65	Access Road	Widening	8.00	20	166.01	Ward No. 04	2nd Phase
Tertiary Road	TR-66	Access Road	Widening	8.00	20	34.53	Ward No. 04	2nd Phase
Tertiary Road	TR-67	Access Road	Widening	8.00	20	31.07	Ward No. 04	2nd Phase
Tertiary Road	TR-68	Access Road	Widening	8.00	20	48.83	Ward No. 03	2nd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-69	Access Road	Widening	8.00	20	2.59	Ward No. 03	2nd Phase
Tertiary Road	TR-70	Access Road	Widening	8.00	20	119.35	Ward No. 06	2nd Phase
Tertiary Road	TR-71	Access Road	Widening	8.00	20	169.28	Ward No. 03	2nd Phase
Tertiary Road	TR-72	Access Road	Widening	6.00	20	302.52	Ward No. 06	2nd Phase
Tertiary Road	TR-73	Access Road	Widening	6.00	20	150.92	Ward No. 06	2nd Phase
Tertiary Road	TR-74	Access Road	Widening	6.00	20	300.11	Ward No. 06	2nd Phase
Tertiary Road	TR-75	Access Road	Widening	8.00	20	325.36	Ward No. 06	2nd Phase
Tertiary Road	TR-76	Access Road	Widening	8.00	20	166.89	Ward No. 06	2nd Phase
Tertiary Road	TR-77	Access Road	Widening	8.00	20	42.06	Ward No. 06	2nd Phase
Tertiary Road	TR-78	Access Road	Widening	8.00	20	60.08	Ward No. 06	2nd Phase
Tertiary Road	TR-79	Access Road	Widening	6.00	20	272.29	Ward No. 06	2nd Phase
Tertiary Road	TR-80	Access Road	Widening	8.00	20	29.89	Ward No. 06	2nd Phase
Tertiary Road	TR-81	Access Road	Widening	8.00	20	488.54	Ward No. 06	2nd Phase
Tertiary Road	TR-82	Access Road	Widening	8.00	20	80.90	Ward No. 06	2nd Phase
Tertiary Road	TR-83	Access Road	Widening	6.00	20	10.16	Ward No. 06	2nd Phase
Tertiary Road	TR-84	Access Road	Widening	8.00	20	168.86	Ward No. 06	2nd Phase
Tertiary Road	TR-85	Access Road	Widening	8.00	20	42.53	Ward No. 06	2nd Phase
Tertiary Road	TR-86	Access Road	Widening	8.00	20	894.48	Ward No. 06	2nd Phase
Tertiary Road	TR-87	Access Road	Widening	6.00	20	469.67	Ward No. 06	2nd Phase
Tertiary Road	TR-88	Access Road	Widening	6.00	20	256.23	Ward No. 06	2nd Phase
Tertiary Road	TR-89	Access Road	Widening	6.00	20	280.29	Ward No. 06	2nd Phase
Tertiary Road	TR-90	Access Road	Widening	8.00	20	85.30	Ward No. 06	2nd Phase
Tertiary Road	TR-91	Access Road	Widening	6.00	20	735.37	Ward No. 06	2nd Phase
Tertiary Road	TR-92	Access Road	Widening	6.00	20	12.88	Ward No. 06	2nd Phase
Tertiary Road	TR-93	Access Road	Widening	8.00	20	25.82	Ward No. 06	2nd Phase
Tertiary Road	TR-94	Access Road	Widening	8.00	20	67.51	Ward No. 06	2nd Phase
Tertiary Road	TR-95	Access Road	Widening	6.00	20	125.25	Ward No. 06	2nd Phase
Tertiary Road	TR-96	Access Road	Widening	8.00	20	62.20	Ward No. 06	2nd Phase
Tertiary Road	TR-97	Access Road	Widening	8.00	20	76.57	Ward No. 06	2nd Phase
Tertiary Road	TR-98	Access Road	Widening	8.00	20	125.25	Ward No. 06	2nd Phase
Tertiary Road	TR-99	Access Road	Widening	8.00	20	200.55	Ward No. 06	2nd Phase
Tertiary Road	TR-100	Access Road	Widening	8.00	20	80.10	Ward	2nd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 06	Phase
Tertiary Road	TR-101	Access Road	Widening	8.00	20	17.13	Ward No. 06	2nd Phase
Tertiary Road	TR-102	Access Road	Widening	6.00	20	47.10	Ward No. 06	2nd Phase
Tertiary Road	TR-103	Access Road	Widening	6.00	20	22.53	Ward No. 06	2nd Phase
Tertiary Road	TR-104	Access Road	Widening	6.00	20	94.47	Ward No. 06	2nd Phase
Tertiary Road	TR-105	Access Road	Widening	6.00	20	615.38	Ward No. 06	2nd Phase
Tertiary Road	TR-106	Access Road	Widening	6.00	20	76.85	Ward No. 06	2nd Phase
Tertiary Road	TR-107	Access Road	Widening	6.00	20	128.12	Ward No. 06	2nd Phase
Tertiary Road	TR-108	Access Road	Widening	10.00	20	287.69	Ward No. 04	2nd Phase
Tertiary Road	TR-109	Access Road	Widening	10.00	20	9.20	Ward No. 06	2nd Phase
Tertiary Road	TR-110	Access Road	Widening	8.00	20	25.17	Ward No. 04	2nd Phase
Tertiary Road	TR-111	Access Road	Widening	8.00	20	287.18	Ward No. 04	2nd Phase
Tertiary Road	TR-112	Access Road	Widening	8.00	20	24.87	Ward No. 04	2nd Phase
Tertiary Road	TR-113	Access Road	Widening	10.00	20	1042.63	Ward No. 04	2nd Phase
Tertiary Road	TR-115	Access Road	Widening	10.00	20	75.95	Ward No. 05	2nd Phase
Tertiary Road	TR-116	Access Road	Widening	8.00	20	12.97	Ward No. 04	2nd Phase
Tertiary Road	TR-117	Access Road	Widening	8.00	20	13.36	Ward No. 04	2nd Phase
Tertiary Road	TR-118	Access Road	Widening	8.00	20	97.90	Ward No. 04	2nd Phase
Tertiary Road	TR-119	Access Road	Widening	8.00	20	159.13	Ward No. 04	2nd Phase
Tertiary Road	TR-121	Access Road	Widening	8.00	20	33.24	Ward No. 04	2nd Phase
Tertiary Road	TR-122	Access Road	Widening	8.00	20	45.98	Ward No. 06	2nd Phase
Tertiary Road	TR-123	Access Road	Widening	8.00	20	79.10	Ward No. 06	2nd Phase
Tertiary Road	TR-124	Access Road	Widening	8.00	20	51.50	Ward No. 06	2nd Phase
Tertiary Road	TR-125	Access Road	Widening	6.00	20	294.18	Ward No. 06	2nd Phase
Tertiary Road	TR-126	Access Road	Widening	4.00	20	47.58	Ward No. 06	2nd Phase
Tertiary Road	TR-127	Access Road	Widening	8.00	20	29.21	Ward No. 06	2nd Phase
Tertiary Road	TR-128	Access Road	Widening	8.00	20	82.67	Ward No. 04	2nd Phase
Tertiary Road	TR-131	Access Road	Widening	6.00	20	48.06	Ward No. 06	2nd Phase
Tertiary Road	TR-132	Access Road	Widening	8.00	20	50.58	Ward No. 06	2nd Phase
Tertiary Road	TR-133	Access Road	Widening	6.00	20	203.15	Ward No. 05	2nd Phase
Tertiary Road	TR-134	Access Road	Widening	6.00	20	216.83	Ward No. 05	2nd Phase
Tertiary Road	TR-135	Access Road	Widening	6.00	20	144.05	Ward No. 05	2nd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-136	Access Road	Widening	8.00	20	732.85	Ward No. 05	2nd Phase
Tertiary Road	TR-137	Access Road	Widening	6.00	20	48.53	Ward No. 05	2nd Phase
Tertiary Road	TR-138	Access Road	Widening	6.00	20	43.25	Ward No. 05	2nd Phase
Tertiary Road	TR-139	Access Road	Widening	6.00	20	373.59	Ward No. 07	2nd Phase
Tertiary Road	TR-141	Access Road	Widening	8.00	20	2.72	Ward No. 06	2nd Phase
Tertiary Road	TR-143	Access Road	Widening	6.00	20	608.54	Ward No. 05	2nd Phase
Tertiary Road	TR-144	Access Road	Widening	6.00	20	15.49	Ward No. 05	2nd Phase
Tertiary Road	TR-145	Access Road	Widening	6.00	20	262.57	Ward No. 06	2nd Phase
Tertiary Road	TR-146	Access Road	Widening	6.00	20	3.97	Ward No. 07	2nd Phase
Tertiary Road	TR-148	Access Road	Widening	8.00	20	108.72	Ward No. 06	2nd Phase
Tertiary Road	TR-149	Access Road	Widening	6.00	20	33.79	Ward No. 06	2nd Phase
Tertiary Road	TR-150	Access Road	Widening	6.00	20	138.51	Ward No. 06	2nd Phase
Tertiary Road	TR-151	Access Road	Widening	6.00	20	68.37	Ward No. 06	2nd Phase
Tertiary Road	TR-152	Access Road	Widening	6.00	20	15.11	Ward No. 06	2nd Phase
Tertiary Road	TR-153	Access Road	Widening	6.00	20	155.13	Ward No. 06	2nd Phase
Tertiary Road	TR-154	Access Road	Widening	6.00	20	20.90	Ward No. 06	2nd Phase
Tertiary Road	TR-155	Access Road	Widening	6.00	20	51.56	Ward No. 06	2nd Phase
Tertiary Road	TR-156	Access Road	Widening	6.00	20	176.75	Ward No. 06	2nd Phase
Tertiary Road	TR-157	Access Road	Widening	6.00	20	148.29	Ward No. 06	2nd Phase
Tertiary Road	TR-158	Access Road	Widening	8.00	20	38.44	Ward No. 06	2nd Phase
Tertiary Road	TR-159	Access Road	Widening	8.00	20	46.97	Ward No. 06	2nd Phase
Tertiary Road	TR-160	Access Road	Widening	8.00	20	156.30	Ward No. 06	2nd Phase
Tertiary Road	TR-161	Access Road	Widening	8.00	20	32.16	Ward No. 06	2nd Phase
Tertiary Road	TR-162	Access Road	Widening	8.00	20	39.89	Ward No. 06	2nd Phase
Tertiary Road	TR-163	Access Road	Widening	4.00	20	506.11	Ward No. 05	2nd Phase
Tertiary Road	TR-164	Access Road	Widening	8.00	20	95.22	Ward No. 05	2nd Phase
Tertiary Road	TR-165	Access Road	Widening	6.00	20	68.03	Ward No. 05	2nd Phase
Tertiary Road	TR-166	Access Road	Widening	6.00	20	17.46	Ward No. 05	2nd Phase
Tertiary Road	TR-167	Access Road	Widening	6.00	20	26.33	Ward No. 05	2nd Phase
Tertiary Road	TR-168	Access Road	Widening	6.00	20	610.70	Ward No. 07	2nd Phase
Tertiary Road	TR-169	Access Road	Widening	8.00	20	329.25	Ward No. 05	2nd Phase
Tertiary Road	TR-170	Access Road	Widening	8.00	20	66.52	Ward	2nd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 05	Phase
Tertiary Road	TR-171	Access Road	Widening	8.00	20	583.32	Ward No. 07	2nd Phase
Tertiary Road	TR-172	Access Road	Widening	6.00	20	188.36	Ward No. 07	2nd Phase
Tertiary Road	TR-173	Access Road	Widening	6.00	20	156.54	Ward No. 07	2nd Phase
Tertiary Road	TR-174	Access Road	Widening	6.00	20	95.98	Ward No. 07	2nd Phase
Tertiary Road	TR-175	Access Road	Widening	10.00	20	68.89	Ward No. 07	2nd Phase
Tertiary Road	TR-176	Access Road	Widening	8.00	20	91.46	Ward No. 07	2nd Phase
Tertiary Road	TR-177	Access Road	Widening	8.00	20	153.65	Ward No. 07	2nd Phase
Tertiary Road	TR-178	Access Road	Widening	8.00	20	150.99	Ward No. 07	2nd Phase
Tertiary Road	TR-179	Access Road	Widening	8.00	20	37.64	Ward No. 07	2nd Phase
Tertiary Road	TR-180	Access Road	Widening	8.00	20	28.48	Ward No. 06	2nd Phase
Tertiary Road	TR-181	Access Road	Widening	8.00	20	23.57	Ward No. 07	2nd Phase
Tertiary Road	TR-183	Access Road	Widening	6.00	20	117.73	Ward No. 06	2nd Phase
Tertiary Road	TR-184	Access Road	Widening	7.00	20	81.74	Ward No. 07	2nd Phase
Tertiary Road	TR-185	Access Road	Widening	8.00	20	141.78	Ward No. 07	2nd Phase
Tertiary Road	TR-187	Access Road	Widening	8.00	20	84.71	Ward No. 06	2nd Phase
Tertiary Road	TR-188	Access Road	Widening	6.00	20	50.24	Ward No. 04	2nd Phase
Tertiary Road	TR-189	Access Road	Widening	8.00	20	86.54	Ward No. 04	2nd Phase
Tertiary Road	TR-190	Access Road	Widening	4.00	20	73.66	Ward No. 04	2nd Phase
Tertiary Road	TR-191	Access Road	Widening	6.00	20	63.81	Ward No. 04	2nd Phase
Tertiary Road	TR-192	Access Road	Widening	8.00	20	66.79	Ward No. 04	2nd Phase
Tertiary Road	TR-193	Access Road	Widening	8.00	20	36.99	Ward No. 04	2nd Phase
Tertiary Road	TR-194	Access Road	Widening	6.00	20	181.88	Ward No. 05	2nd Phase
Tertiary Road	TR-195	Access Road	Widening	8.00	20	174.65	Ward No. 04	2nd Phase
Tertiary Road	TR-196	Access Road	Widening	4.00	20	366.97	Ward No. 05	2nd Phase
Tertiary Road	TR-197	Access Road	Widening	8.00	20	176.12	Ward No. 05	2nd Phase
Tertiary Road	TR-198	Access Road	Widening	8.00	20	61.52	Ward No. 05	2nd Phase
Tertiary Road	TR-199	Access Road	Widening	8.00	20	17.27	Ward No. 04	2nd Phase
Tertiary Road	TR-200	Access Road	Widening	8.00	20	1.42	Ward No. 05	2nd Phase
Tertiary Road	TR-201	Access Road	Widening	6.00	20	165.55	Ward No. 04	2nd Phase
Tertiary Road	TR-202	Access Road	Widening	6.00	20	99.06	Ward No. 04	2nd Phase
Tertiary Road	TR-203	Access Road	Widening	8.00	20	29.69	Ward No. 04	2nd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-204	Access Road	Widening	8.00	20	27.80	Ward No. 04	2nd Phase
Tertiary Road	TR-205	Access Road	Widening	8.00	20	20.10	Ward No. 04	2nd Phase
Tertiary Road	TR-206	Access Road	Widening	8.00	20	55.33	Ward No. 04	2nd Phase
Tertiary Road	TR-207	Access Road	Widening	8.00	20	50.96	Ward No. 04	2nd Phase
Tertiary Road	TR-208	Access Road	Widening	16.00	20	150.86	Ward No. 05	2nd Phase
Tertiary Road	TR-209	Access Road	Widening	6.00	20	129.42	Ward No. 05	2nd Phase
Tertiary Road	TR-210	Access Road	Widening	6.00	20	96.49	Ward No. 05	2nd Phase
Tertiary Road	TR-211	Access Road	Widening	10.00	20	43.24	Ward No. 05	2nd Phase
Tertiary Road	TR-212	Access Road	Widening	10.00	20	243.41	Ward No. 05	2nd Phase
Tertiary Road	TR-213	Access Road	Widening	8.00	20	36.98	Ward No. 05	2nd Phase
Tertiary Road	TR-214	Access Road	Widening	8.00	20	34.93	Ward No. 05	2nd Phase
Tertiary Road	TR-215	Access Road	Widening	6.00	20	92.92	Ward No. 05	2nd Phase
Tertiary Road	TR-216	Access Road	Widening	6.00	20	17.36	Ward No. 05	2nd Phase
Tertiary Road	TR-217	Access Road	Widening	6.00	20	109.69	Ward No. 05	2nd Phase
Tertiary Road	TR-218	Access Road	Widening	6.00	20	924.85	Ward No. 05	2nd Phase
Tertiary Road	TR-219	Access Road	Widening	6.00	20	36.42	Ward No. 05	2nd Phase
Tertiary Road	TR-220	Access Road	Widening	6.00	20	22.98	Ward No. 05	2nd Phase
Tertiary Road	TR-221	Access Road	Widening	6.00	20	29.46	Ward No. 05	2nd Phase
Tertiary Road	TR-222	Access Road	Widening	6.00	20	329.53	Ward No. 05	2nd Phase
Tertiary Road	TR-223	Access Road	Widening	6.00	20	168.83	Ward No. 05	2nd Phase
Tertiary Road	TR-224	Access Road	Widening	6.00	20	134.64	Ward No. 05	2nd Phase
Tertiary Road	TR-225	Access Road	Widening	6.00	20	45.51	Ward No. 05	2nd Phase
Tertiary Road	TR-226	Access Road	Widening	8.00	20	85.45	Ward No. 05	2nd Phase
Tertiary Road	TR-227	Access Road	Widening	8.00	20	246.39	Ward No. 05	2nd Phase
Tertiary Road	TR-228	Access Road	Widening	8.00	20	27.46	Ward No. 05	2nd Phase
Tertiary Road	TR-229	Access Road	Widening	6.00	20	94.41	Ward No. 05	2nd Phase
Tertiary Road	TR-230	Access Road	Widening	6.00	20	27.39	Ward No. 07	2nd Phase
Tertiary Road	TR-232	Access Road	Widening	8.00	20	645.13	Ward No. 05	2nd Phase
Tertiary Road	TR-233	Access Road	Widening	6.00	20	112.19	Ward No. 05	2nd Phase
Tertiary Road	TR-234	Access Road	Widening	8.00	20	127.78	Ward No. 05	2nd Phase
Tertiary Road	TR-235	Access Road	Widening	6.00	20	30.08	Ward No. 05	2nd Phase
Tertiary Road	TR-236	Access Road	Widening	8.00	20	428.06	Ward	2nd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 05	Phase
Tertiary Road	TR-237	Access Road	Widening	8.00	20	42.35	Ward No. 05	2nd Phase
Tertiary Road	TR-238	Access Road	Widening	6.00	20	51.88	Ward No. 05	2nd Phase
Tertiary Road	TR-239	Access Road	Widening	6.00	20	90.59	Ward No. 05	2nd Phase
Tertiary Road	TR-240	Access Road	Widening	16.00	20	62.76	Ward No. 05	2nd Phase
Tertiary Road	TR-241	Access Road	Widening	8.00	20	111.53	Ward No. 05	2nd Phase
Tertiary Road	TR-242	Access Road	Widening	6.00	20	8.42	Ward No. 06	2nd Phase
Tertiary Road	TR-243	Access Road	Widening	6.00	20	370.13	Ward No. 06	2nd Phase
Tertiary Road	TR-244	Access Road	Widening	8.00	20	113.55	Ward No. 06	2nd Phase
Tertiary Road	TR-245	Access Road	Widening	8.00	20	105.84	Ward No. 06	2nd Phase
Tertiary Road	TR-246	Access Road	Widening	6.00	20	70.04	Ward No. 06	2nd Phase
Tertiary Road	TR-247	Access Road	Widening	10.00	20	99.26	Ward No. 06	2nd Phase
Tertiary Road	TR-248	Access Road	Widening	6.00	20	107.59	Ward No. 06	2nd Phase
Tertiary Road	TR-249	Access Road	Widening	8.00	20	14.73	Ward No. 06	2nd Phase
Secondary Road	SR-6	Access Road	Widening	10.00	40	569.99	Ward No. 06	2nd Phase
Tertiary Road	TR-251	Access Road	Widening	8.00	20	74.34	Ward No. 07	2nd Phase
Tertiary Road	TR-253	Access Road	Widening	6.00	20	0.63	Ward No. 06	2nd Phase
Tertiary Road	TR-254	Access Road	Widening	8.00	20	136.94	Ward No. 07	2nd Phase
Tertiary Road	TR-255	Access Road	Widening	8.00	20	0.24	Ward No. 06	2nd Phase
Tertiary Road	TR-256	Access Road	Widening	8.00	20	139.02	Ward No. 07	2nd Phase
Tertiary Road	TR-257	Access Road	Widening	8.00	20	49.49	Ward No. 07	2nd Phase
Tertiary Road	TR-258	Access Road	Widening	12.00	20	0.41	Ward No. 06	2nd Phase
Tertiary Road	TR-259	Access Road	Widening	6.00	20	441.43	Ward No. 06	2nd Phase
Tertiary Road	TR-260	Access Road	Widening	6.00	20	40.01	Ward No. 06	2nd Phase
Tertiary Road	TR-261	Access Road	Widening	8.00	20	40.07	Ward No. 07	2nd Phase
Tertiary Road	TR-263	Access Road	Widening	10.00	20	203.14	Ward No. 06	2nd Phase
Tertiary Road	TR-264	Access Road	Widening	8.00	20	88.26	Ward No. 06	2nd Phase
Tertiary Road	TR-265	Access Road	Widening	6.00	20	71.69	Ward No. 06	2nd Phase
Tertiary Road	TR-266	Access Road	Widening	6.00	20	40.56	Ward No. 06	2nd Phase
Tertiary Road	TR-267	Access Road	Widening	8.00	20	68.89	Ward No. 06	2nd Phase
Tertiary Road	TR-268	Access Road	Widening	6.00	20	337.89	Ward No. 06	2nd Phase
Tertiary Road	TR-269	Access Road	Widening	6.00	20	181.63	Ward No. 07	2nd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-270	Access Road	Widening	6.00	20	304.86	Ward No. 06	2nd Phase
Tertiary Road	TR-271	Access Road	Widening	8.00	20	221.75	Ward No. 06	2nd Phase
Tertiary Road	TR-272	Access Road	Widening	8.00	20	258.51	Ward No. 06	2nd Phase
Tertiary Road	TR-273	Access Road	Widening	10.00	20	43.44	Ward No. 06	2nd Phase
Tertiary Road	TR-274	Access Road	Widening	6.00	20	176.34	Ward No. 06	2nd Phase
Tertiary Road	TR-275	Access Road	Widening	8.00	20	533.69	Ward No. 06	2nd Phase
Tertiary Road	TR-277	Access Road	Widening	6.00	20	1.16	Ward No. 07	2nd Phase
Tertiary Road	TR-279	Access Road	Widening	8.00	20	84.77	Ward No. 06	2nd Phase
Tertiary Road	TR-280	Access Road	Widening	8.00	20	91.81	Ward No. 07	2nd Phase
Tertiary Road	TR-281	Access Road	Widening	6.00	20	387.86	Ward No. 07	2nd Phase
Tertiary Road	TR-282	Access Road	Widening	8.00	20	63.35	Ward No. 07	2nd Phase
Tertiary Road	TR-283	Access Road	Widening	6.00	20	408.93	Ward No. 07	2nd Phase
Tertiary Road	TR-284	Access Road	Widening	8.00	20	42.45	Ward No. 06	2nd Phase
Tertiary Road	TR-285	Access Road	Widening	8.00	20	242.60	Ward No. 07	2nd Phase
Tertiary Road	TR-287	Access Road	Widening	6.00	20	1.74	Ward No. 06	2nd Phase
Tertiary Road	TR-288	Access Road	Widening	8.00	20	59.48	Ward No. 05	2nd Phase
Tertiary Road	TR-289	Access Road	Widening	8.00	20	43.24	Ward No. 05	2nd Phase
Tertiary Road	TR-290	Access Road	Widening	6.00	20	31.71	Ward No. 05	2nd Phase
Tertiary Road	TR-291	Access Road	Widening	8.00	20	34.39	Ward No. 07	2nd Phase
Tertiary Road	TR-292	Access Road	Widening	8.00	20	360.64	Ward No. 07	2nd Phase
Tertiary Road	TR-293	Access Road	Widening	8.00	20	28.56	Ward No. 07	2nd Phase
Tertiary Road	TR-294	Access Road	Widening	6.00	20	42.89	Ward No. 07	2nd Phase
Tertiary Road	TR-295	Access Road	Widening	6.00	20	38.58	Ward No. 07	2nd Phase
Tertiary Road	TR-296	Access Road	Widening	8.00	20	39.61	Ward No. 07	2nd Phase
Tertiary Road	TR-297	Access Road	Widening	8.00	20	35.24	Ward No. 07	2nd Phase
Tertiary Road	TR-298	Access Road	Widening	8.00	20	27.23	Ward No. 07	2nd Phase
Tertiary Road	TR-299	Access Road	Widening	8.00	20	621.35	Ward No. 07	2nd Phase
Tertiary Road	TR-299	Access Road	Widening	8.00	20	31.93	Ward No. 06	2nd Phase
Tertiary Road	TR-301	Access Road	Widening	8.00	20	0.29	Ward No. 06	2nd Phase
Tertiary Road	TR-302	Access Road	Widening	8.00	20	47.56	Ward No. 07	2nd Phase
Tertiary Road	TR-303	Access Road	Widening	6.00	20	36.95	Ward No. 07	2nd Phase
Tertiary Road	TR-304	Access Road	Widening	8.00	20	35.84	Ward	2nd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 07	Phase
Tertiary Road	TR-305	Access Road	Widening	8.00	20	55.89	Ward No. 07	2nd Phase
Tertiary Road	TR-306	Access Road	Widening	8.00	20	29.27	Ward No. 07	2nd Phase
Tertiary Road	TR-307	Access Road	Widening	8.00	20	42.81	Ward No. 07	2nd Phase
Tertiary Road	TR-308	Access Road	Widening	8.00	20	65.03	Ward No. 07	2nd Phase
Tertiary Road	TR-309	Access Road	Widening	8.00	20	50.91	Ward No. 07	2nd Phase
Tertiary Road	TR-310	Access Road	Widening	8.00	20	385.44	Ward No. 07	2nd Phase
Tertiary Road	TR-311	Access Road	Widening	8.00	20	37.07	Ward No. 07	2nd Phase
Tertiary Road	TR-312	Access Road	Widening	8.00	20	127.01	Ward No. 07	2nd Phase
Tertiary Road	TR-313	Access Road	Widening	8.00	20	197.04	Ward No. 07	2nd Phase
Tertiary Road	TR-314	Access Road	Widening	8.00	20	30.22	Ward No. 07	2nd Phase
Tertiary Road	TR-315	Access Road	Widening	6.00	20	30.17	Ward No. 07	2nd Phase
Secondary Road	SR-7	Access Road	Widening	6.00	40	744.17	Ward No. 07	2nd Phase
Secondary Road	SR-7	Access Road	Widening	6.00	40	582.30	Ward No. 08	2nd Phase
Secondary Road	SR-7	Access Road	Widening	6.00	40	763.57	Ward No. 05	2nd Phase
Secondary Road	SR-8	Access Road	Widening	12.00	40	1573.61	Ward No. 03	2nd Phase
Secondary Road	SR-8	Access Road	Widening	12.00	40	692.61	Ward No. 01	2nd Phase
Secondary Road	SR-9	Access Road	Widening	8.00	40	986.12	Ward No. 01	2nd Phase
Secondary Road	SR-10	Access Road	Widening	8.00	40	735.67	Ward No. 01	2nd Phase
Secondary Road	SR-11	Access Road	Widening	8.00	40	831.83	Ward No. 03	2nd Phase
Secondary Road	SR-12	Access Road	Widening	8.00	60	1177.09	Ward No. 01	2nd Phase
Secondary Road	SR-13	Access Road	Widening	6.00	40	866.22	Ward No. 07	2nd Phase
Secondary Road	SR-13	Access Road	Widening	6.00	40	92.18	Ward No. 08	2nd Phase
Secondary Road	SR-13	Access Road	Widening	6.00	40	712.57	Ward No. 09	2nd Phase
Secondary Road	SR-13	Access Road	Widening	6.00	40	38.15	Ward No. 05	2nd Phase
Secondary Road	SR-14	Access Road	Widening	6.00	40	703.70	Ward No. 05	2nd Phase
Secondary Road	SR-15	Access Road	Widening	6.00	40	1664.35	Ward No. 09	2nd Phase
Secondary Road	SR-16	Access Road	Widening	4.00	60	212.13	Ward No. 08	2nd Phase
Secondary Road	SR-16	Access Road	Widening	4.00	60	1227.77	Ward No. 09	2nd Phase
Secondary Road	SR-17		New	0.00	60	243.57	Ward No. 02	2nd Phase
Secondary Road	SR-17		New	0.00	60	825.34	Ward No. 04	2nd Phase
Secondary Road	SR-18		New	0.00	40	5.23	Ward No. 08	2nd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Secondary Road	SR-18		New	0.00	40	36.51	Ward No. 09	2nd Phase
Secondary Road	SR-19		New	0.00	40	424.59	Ward No. 09	2nd Phase
Tertiary Road	TR-871	Access Road	Widening	6.00	20	66.23	Ward No. 02	2nd Phase
Tertiary Road	TR-872	Access Road	Widening	6.00	20	8.38	Ward No. 02	2nd Phase
Tertiary Road	TR-873	Access Road	Widening	6.00	20	129.64	Ward No. 02	2nd Phase
Tertiary Road	TR-874	Access Road	Widening	6.00	20	105.50	Ward No. 02	2nd Phase
Secondary Road	SR-20	Access Road	Widening	6.00	60	1384.41	Ward No. 02	2nd Phase
Tertiary Road	TR-875	Access Road	Widening	6.00	20	4.57	Ward No. 09	2nd Phase
Secondary Road	SR-21	Access Road	Widening	6.00	40	927.49	Ward No. 09	2nd Phase
Tertiary Road	TR-876	Access Road	Widening	8.00	20	27.03	Ward No. 03	2nd Phase
Tertiary Road	TR-877	Access Road	Widening	10.00	20	7.63	Ward No. 04	2nd Phase
Tertiary Road	TR-878	Access Road	Widening	12.00	20	213.92	Ward No. 08	2nd Phase
Tertiary Road	TR-879	Access Road	Widening	12.00	20	76.13	Ward No. 08	2nd Phase
Tertiary Road	TR-880	Access Road	Widening	12.00	20	29.69	Ward No. 08	2nd Phase
Secondary Road	SR-22	Access Road	Widening	12.00	60	898.01	Ward No. 08	2nd Phase
Secondary Road	SR-22	Access Road	Widening	12.00	60	827.05	Ward No. 05	2nd Phase
Secondary Road	SR-23	Access Road	Widening	10.00	60	521.49	Ward No. 02	2nd Phase
Secondary Road	SR-23	Access Road	Widening	10.00	60	199.81	Ward No. 04	2nd Phase
Tertiary Road	TR-881	Access Road	Widening	6.00	20	3.38	Ward No. 05	2nd Phase
Tertiary Road	TR-882	Access Road	Widening	6.00	20	517.43	Ward No. 05	2nd Phase
Tertiary Road	TR-883	Access Road	Widening	6.00	20	41.21	Ward No. 07	2nd Phase
Tertiary Road	TR-884	Dhaka-Barisal Highway	Widening	20.00	20	103.75	Ward No. 03	2nd Phase
Tertiary Road	TR-885	Dhaka-Barisal Highway	Widening	20.00	20	343.09	Ward No. 03	2nd Phase
Tertiary Road	TR-886	Dhaka-Barisal Highway	Widening	20.00	20	203.39	Ward No. 03	2nd Phase
Tertiary Road	TR-887	Dhaka-Barisal Highway	Widening	20.00	20	209.25	Ward No. 03	2nd Phase
Tertiary Road	TR-761	Access Road	Widening	4.00	20	19.10	Ward No. 03	2nd Phase
Tertiary Road	TR-761	Access Road	Widening	4.00	20	19.10	Ward No. 02	2nd Phase
Tertiary Road	TR-767	Access Road	Widening	4.00	20	16.30	Ward No. 03	2nd Phase
Tertiary Road	TR-767	Access Road	Widening	4.00	20	16.30	Ward No. 02	2nd Phase
Tertiary Road	TR-316	Access Road	Widening	6.00	20	54.17	Ward No. 07	3rd Phase
Tertiary Road	TR-317	Access Road	Widening	6.00	20	112.22	Ward No. 07	3rd Phase
Tertiary Road	TR-318	Access Road	Widening	6.00	20	20.02	Ward	3rd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 07	Phase
Tertiary Road	TR-319	Access Road	Widening	8.00	20	18.79	Ward No. 07	3rd Phase
Tertiary Road	TR-320	Access Road	Widening	8.00	20	35.39	Ward No. 07	3rd Phase
Tertiary Road	TR-321	Access Road	Widening	6.00	20	256.43	Ward No. 07	3rd Phase
Tertiary Road	TR-322	Access Road	Widening	8.00	20	81.83	Ward No. 07	3rd Phase
Tertiary Road	TR-323	Access Road	Widening	6.00	20	85.07	Ward No. 07	3rd Phase
Tertiary Road	TR-324	Access Road	Widening	8.00	20	156.07	Ward No. 07	3rd Phase
Tertiary Road	TR-325	Access Road	Widening	6.00	20	81.93	Ward No. 07	3rd Phase
Tertiary Road	TR-326	Access Road	Widening	8.00	20	36.98	Ward No. 07	3rd Phase
Tertiary Road	TR-327	Access Road	Widening	8.00	20	65.68	Ward No. 07	3rd Phase
Tertiary Road	TR-328	Access Road	Widening	6.00	20	36.35	Ward No. 07	3rd Phase
Tertiary Road	TR-329	Access Road	Widening	6.00	20	45.00	Ward No. 07	3rd Phase
Tertiary Road	TR-330	Access Road	Widening	6.00	20	1018.52	Ward No. 07	3rd Phase
Tertiary Road	TR-332	Access Road	Widening	6.00	20	8.49	Ward No. 05	3rd Phase
Tertiary Road	TR-333	Access Road	Widening	6.00	20	239.25	Ward No. 07	3rd Phase
Tertiary Road	TR-334	Access Road	Widening	6.00	20	33.74	Ward No. 07	3rd Phase
Tertiary Road	TR-335	Access Road	Widening	6.00	20	97.79	Ward No. 07	3rd Phase
Tertiary Road	TR-336	Access Road	Widening	6.00	20	60.14	Ward No. 07	3rd Phase
Tertiary Road	TR-337	Access Road	Widening	10.00	20	76.46	Ward No. 07	3rd Phase
Tertiary Road	TR-338	Access Road	Widening	16.00	20	66.40	Ward No. 07	3rd Phase
Tertiary Road	TR-339	Access Road	Widening	8.00	20	84.74	Ward No. 07	3rd Phase
Tertiary Road	TR-340	Access Road	Widening	6.00	20	502.60	Ward No. 07	3rd Phase
Tertiary Road	TR-341	Access Road	Widening	6.00	20	684.00	Ward No. 09	3rd Phase
Tertiary Road	TR-342	Access Road	Widening	6.00	20	497.15	Ward No. 09	3rd Phase
Tertiary Road	TR-343	Access Road	Widening	8.00	20	490.29	Ward No. 09	3rd Phase
Tertiary Road	TR-344	Access Road	Widening	8.00	20	195.74	Ward No. 09	3rd Phase
Tertiary Road	TR-345	Access Road	Widening	6.00	20	506.43	Ward No. 09	3rd Phase
Tertiary Road	TR-346	Access Road	Widening	8.00	20	54.90	Ward No. 09	3rd Phase
Tertiary Road	TR-347	Access Road	Widening	8.00	20	19.09	Ward No. 09	3rd Phase
Tertiary Road	TR-348	Access Road	Widening	8.00	20	21.67	Ward No. 09	3rd Phase
Tertiary Road	TR-349	Access Road	Widening	8.00	20	276.11	Ward No. 09	3rd Phase
Tertiary Road	TR-350	Access Road	Widening	8.00	20	70.20	Ward No. 01	3rd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-351	Access Road	Widening	8.00	20	101.61	Ward No. 01	3rd Phase
Tertiary Road	TR-352	Access Road	Widening	10.00	20	61.28	Ward No. 01	3rd Phase
Tertiary Road	TR-353	Access Road	Widening	10.00	20	215.53	Ward No. 01	3rd Phase
Tertiary Road	TR-354	Access Road	Widening	6.00	20	37.90	Ward No. 01	3rd Phase
Tertiary Road	TR-355	Access Road	Widening	6.00	20	274.71	Ward No. 01	3rd Phase
Tertiary Road	TR-356	Access Road	Widening	8.00	20	36.41	Ward No. 01	3rd Phase
Tertiary Road	TR-357	Access Road	Widening	8.00	20	34.13	Ward No. 01	3rd Phase
Tertiary Road	TR-358	Access Road	Widening	8.00	20	37.74	Ward No. 01	3rd Phase
Tertiary Road	TR-359	Access Road	Widening	6.00	20	39.01	Ward No. 01	3rd Phase
Tertiary Road	TR-360	Access Road	Widening	8.00	20	209.43	Ward No. 01	3rd Phase
Tertiary Road	TR-361	Access Road	Widening	8.00	20	125.44	Ward No. 01	3rd Phase
Tertiary Road	TR-362	Access Road	Widening	8.00	20	47.53	Ward No. 01	3rd Phase
Tertiary Road	TR-363	Access Road	Widening	8.00	20	38.78	Ward No. 01	3rd Phase
Tertiary Road	TR-364	Access Road	Widening	6.00	20	201.67	Ward No. 01	3rd Phase
Tertiary Road	TR-365	Access Road	Widening	6.00	20	71.37	Ward No. 01	3rd Phase
Tertiary Road	TR-366	Access Road	Widening	6.00	20	68.56	Ward No. 01	3rd Phase
Tertiary Road	TR-367	Access Road	Widening	10.00	20	913.56	Ward No. 01	3rd Phase
Tertiary Road	TR-368	Access Road	Widening	10.00	20	58.23	Ward No. 01	3rd Phase
Tertiary Road	TR-369	Access Road	Widening	8.00	20	91.03	Ward No. 01	3rd Phase
Tertiary Road	TR-370	Access Road	Widening	6.00	20	174.03	Ward No. 01	3rd Phase
Tertiary Road	TR-371	Access Road	Widening	8.00	20	611.49	Ward No. 01	3rd Phase
Tertiary Road	TR-372	Access Road	Widening	6.00	20	42.11	Ward No. 01	3rd Phase
Tertiary Road	TR-373	Access Road	Widening	6.00	20	126.18	Ward No. 02	3rd Phase
Tertiary Road	TR-374	Access Road	Widening	6.00	20	300.36	Ward No. 02	3rd Phase
Tertiary Road	TR-378	Access Road	Widening	8.00	20	30.65	Ward No. 01	3rd Phase
Tertiary Road	TR-379	Access Road	Widening	8.00	20	27.20	Ward No. 01	3rd Phase
Tertiary Road	TR-380	Access Road	Widening	6.00	20	315.59	Ward No. 01	3rd Phase
Tertiary Road	TR-381	Access Road	Widening	8.00	20	90.27	Ward No. 01	3rd Phase
Tertiary Road	TR-382	Access Road	Widening	8.00	20	97.66	Ward No. 01	3rd Phase
Tertiary Road	TR-383	Access Road	Widening	6.00	20	239.52	Ward No. 01	3rd Phase
Tertiary Road	TR-384	Access Road	Widening	6.00	20	57.37	Ward No. 01	3rd Phase
Tertiary Road	TR-385	Access Road	Widening	8.00	20	81.91	Ward	3rd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 01	Phase
Tertiary Road	TR-386	Access Road	Widening	6.00	20	81.29	Ward No. 01	3rd Phase
Tertiary Road	TR-387	Access Road	Widening	8.00	20	69.58	Ward No. 01	3rd Phase
Tertiary Road	TR-388	Access Road	Widening	6.00	20	91.49	Ward No. 01	3rd Phase
Tertiary Road	TR-389	Access Road	Widening	6.00	20	151.52	Ward No. 01	3rd Phase
Tertiary Road	TR-390	Access Road	Widening	6.00	20	37.89	Ward No. 01	3rd Phase
Tertiary Road	TR-391	Access Road	Widening	6.00	20	49.28	Ward No. 01	3rd Phase
Tertiary Road	TR-392	Access Road	Widening	8.00	20	40.86	Ward No. 01	3rd Phase
Tertiary Road	TR-393	Access Road	Widening	6.00	20	460.19	Ward No. 01	3rd Phase
Tertiary Road	TR-394	Access Road	Widening	8.00	20	23.34	Ward No. 01	3rd Phase
Tertiary Road	TR-395	Access Road	Widening	8.00	20	699.97	Ward No. 01	3rd Phase
Tertiary Road	TR-396	Access Road	Widening	8.00	20	278.76	Ward No. 01	3rd Phase
Tertiary Road	TR-397	Access Road	Widening	8.00	20	74.50	Ward No. 01	3rd Phase
Tertiary Road	TR-398	Access Road	Widening	8.00	20	209.87	Ward No. 01	3rd Phase
Tertiary Road	TR-399	Access Road	Widening	6.00	20	14.98	Ward No. 03	3rd Phase
Tertiary Road	TR-400	Access Road	Widening	6.00	20	291.92	Ward No. 03	3rd Phase
Tertiary Road	TR-401	Access Road	Widening	8.00	20	73.75	Ward No. 03	3rd Phase
Tertiary Road	TR-402	Access Road	Widening	6.00	20	70.79	Ward No. 03	3rd Phase
Tertiary Road	TR-403	Access Road	Widening	8.00	20	78.42	Ward No. 03	3rd Phase
Tertiary Road	TR-404	Access Road	Widening	8.00	20	209.51	Ward No. 03	3rd Phase
Tertiary Road	TR-405	Access Road	Widening	8.00	20	97.64	Ward No. 03	3rd Phase
Tertiary Road	TR-406	Access Road	Widening	6.00	20	105.85	Ward No. 03	3rd Phase
Tertiary Road	TR-407	Access Road	Widening	10.00	20	220.11	Ward No. 03	3rd Phase
Tertiary Road	TR-408	Access Road	Widening	8.00	20	66.56	Ward No. 03	3rd Phase
Tertiary Road	TR-410	Access Road	Widening	8.00	20	283.13	Ward No. 02	3rd Phase
Tertiary Road	TR-411	Access Road	Widening	8.00	20	118.86	Ward No. 01	3rd Phase
Tertiary Road	TR-412	Access Road	Widening	8.00	20	308.83	Ward No. 01	3rd Phase
Tertiary Road	TR-413	Access Road	Widening	7.00	20	123.93	Ward No. 01	3rd Phase
Tertiary Road	TR-414	Access Road	Widening	8.00	20	55.80	Ward No. 01	3rd Phase
Tertiary Road	TR-415	Access Road	Widening	6.00	20	127.38	Ward No. 01	3rd Phase
Tertiary Road	TR-416	Access Road	Widening	8.00	20	25.35	Ward No. 03	3rd Phase
Tertiary Road	TR-418	Access Road	Widening	6.00	20	77.32	Ward No. 01	3rd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-419	Access Road	Widening	6.00	20	107.78	Ward No. 01	3rd Phase
Tertiary Road	TR-420	Access Road	Widening	6.00	20	43.91	Ward No. 01	3rd Phase
Tertiary Road	TR-421	Access Road	Widening	6.00	20	917.50	Ward No. 01	3rd Phase
Tertiary Road	TR-422	Access Road	Widening	6.00	20	27.65	Ward No. 01	3rd Phase
Tertiary Road	TR-423	Access Road	Widening	6.00	20	942.13	Ward No. 01	3rd Phase
Tertiary Road	TR-424	Access Road	Widening	8.00	20	26.24	Ward No. 01	3rd Phase
Tertiary Road	TR-425	Access Road	Widening	6.00	20	251.58	Ward No. 01	3rd Phase
Tertiary Road	TR-426	Access Road	Widening	8.00	20	178.40	Ward No. 01	3rd Phase
Tertiary Road	TR-427	Access Road	Widening	6.00	20	123.80	Ward No. 03	3rd Phase
Tertiary Road	TR-428	Access Road	Widening	6.00	20	28.79	Ward No. 03	3rd Phase
Tertiary Road	TR-429	Access Road	Widening	6.00	20	277.06	Ward No. 03	3rd Phase
Tertiary Road	TR-430	Access Road	Widening	8.00	20	94.86	Ward No. 03	3rd Phase
Tertiary Road	TR-431	Access Road	Widening	6.00	20	319.50	Ward No. 03	3rd Phase
Tertiary Road	TR-431	Access Road	Widening	6.00	20	246.77	Ward No. 01	3rd Phase
Tertiary Road	TR-432	Access Road	Widening	12.00	20	972.58	Ward No. 02	3rd Phase
Tertiary Road	TR-433	Access Road	Widening	8.00	20	174.65	Ward No. 02	3rd Phase
Tertiary Road	TR-434	Access Road	Widening	8.00	20	23.68	Ward No. 02	3rd Phase
Tertiary Road	TR-435	Access Road	Widening	6.00	20	191.58	Ward No. 01	3rd Phase
Tertiary Road	TR-436	Access Road	Widening	8.00	20	38.46	Ward No. 01	3rd Phase
Tertiary Road	TR-437	Access Road	Widening	8.00	20	154.99	Ward No. 01	3rd Phase
Tertiary Road	TR-438	Access Road	Widening	8.00	20	181.55	Ward No. 01	3rd Phase
Tertiary Road	TR-439	Access Road	Widening	8.00	20	24.70	Ward No. 01	3rd Phase
Tertiary Road	TR-440	Access Road	Widening	10.00	20	75.36	Ward No. 01	3rd Phase
Tertiary Road	TR-441	Access Road	Widening	6.00	20	269.61	Ward No. 02	3rd Phase
Tertiary Road	TR-443	Access Road	Widening	8.00	20	70.82	Ward No. 01	3rd Phase
Tertiary Road	TR-444	Access Road	Widening	6.00	20	121.16	Ward No. 01	3rd Phase
Tertiary Road	TR-445	Access Road	Widening	6.00	20	86.10	Ward No. 02	3rd Phase
Tertiary Road	TR-447	Access Road	Widening	6.00	20	62.41	Ward No. 01	3rd Phase
Tertiary Road	TR-448	Access Road	Widening	6.00	20	126.62	Ward No. 02	3rd Phase
Tertiary Road	TR-449	Access Road	Widening	10.00	20	44.85	Ward No. 02	3rd Phase
Tertiary Road	TR-450	Access Road	Widening	6.00	20	152.98	Ward No. 01	3rd Phase
Tertiary Road	TR-451	Access Road	Widening	8.00	20	30.85	Ward	3rd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 01	Phase
Tertiary Road	TR-454	Access Road	Widening	10.00	20	686.97	Ward No. 04	3rd Phase
Tertiary Road	TR-455	Access Road	Widening	6.00	20	52.95	Ward No. 01	3rd Phase
Tertiary Road	TR-456	Access Road	Widening	10.00	20	72.31	Ward No. 01	3rd Phase
Tertiary Road	TR-457	Access Road	Widening	6.00	20	208.83	Ward No. 01	3rd Phase
Tertiary Road	TR-458	Access Road	Widening	8.00	20	171.33	Ward No. 01	3rd Phase
Tertiary Road	TR-459	Access Road	Widening	8.00	20	166.22	Ward No. 01	3rd Phase
Tertiary Road	TR-460	Access Road	Widening	6.00	20	25.54	Ward No. 01	3rd Phase
Tertiary Road	TR-461	Access Road	Widening	6.00	20	36.60	Ward No. 01	3rd Phase
Tertiary Road	TR-462	Access Road	Widening	8.00	20	1.05	Ward No. 02	3rd Phase
Tertiary Road	TR-464	Access Road	Widening	8.00	20	65.28	Ward No. 01	3rd Phase
Tertiary Road	TR-465	Access Road	Widening	6.00	20	25.30	Ward No. 01	3rd Phase
Tertiary Road	TR-466	Access Road	Widening	6.00	20	199.49	Ward No. 01	3rd Phase
Tertiary Road	TR-467	Access Road	Widening	6.00	20	24.32	Ward No. 01	3rd Phase
Tertiary Road	TR-468	Access Road	Widening	10.00	20	34.10	Ward No. 01	3rd Phase
Tertiary Road	TR-469	Access Road	Widening	6.00	20	12.17	Ward No. 01	3rd Phase
Tertiary Road	TR-470	Access Road	Widening	8.00	20	181.41	Ward No. 01	3rd Phase
Tertiary Road	TR-471	Access Road	Widening	6.00	20	163.52	Ward No. 03	3rd Phase
Tertiary Road	TR-472	Access Road	Widening	10.00	20	712.59	Ward No. 03	3rd Phase
Tertiary Road	TR-473	Access Road	Widening	10.00	20	42.86	Ward No. 03	3rd Phase
Tertiary Road	TR-474	Access Road	Widening	8.00	20	669.92	Ward No. 03	3rd Phase
Tertiary Road	TR-475	Access Road	Widening	8.00	20	44.40	Ward No. 03	3rd Phase
Tertiary Road	TR-476	Access Road	Widening	8.00	20	33.04	Ward No. 03	3rd Phase
Tertiary Road	TR-477	Access Road	Widening	8.00	20	215.26	Ward No. 03	3rd Phase
Tertiary Road	TR-478	Access Road	Widening	8.00	20	50.57	Ward No. 02	3rd Phase
Tertiary Road	TR-479	Access Road	Widening	8.00	20	165.23	Ward No. 03	3rd Phase
Tertiary Road	TR-481	Access Road	Widening	6.00	20	9.29	Ward No. 02	3rd Phase
Tertiary Road	TR-482	Access Road	Widening	6.00	20	73.53	Ward No. 03	3rd Phase
Tertiary Road	TR-483	Access Road	Widening	8.00	20	0.09	Ward No. 03	3rd Phase
Tertiary Road	TR-484	Access Road	Widening	10.00	20	670.24	Ward No. 02	3rd Phase
Tertiary Road	TR-485	Access Road	Widening	8.00	20	71.56	Ward No. 02	3rd Phase
Tertiary Road	TR-486	Access Road	Widening	6.00	20	0.01	Ward No. 03	3rd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-487	Access Road	Widening	10.00	20	85.17	Ward No. 02	3rd Phase
Tertiary Road	TR-488	Access Road	Widening	10.00	20	624.55	Ward No. 02	3rd Phase
Tertiary Road	TR-489	Access Road	Widening	6.00	20	31.80	Ward No. 03	3rd Phase
Tertiary Road	TR-490	Access Road	Widening	6.00	20	208.90	Ward No. 03	3rd Phase
Tertiary Road	TR-490	Access Road	Widening	6.00	20	192.79	Ward No. 02	3rd Phase
Tertiary Road	TR-491	Access Road	Widening	8.00	20	834.28	Ward No. 02	3rd Phase
Tertiary Road	TR-492	Access Road	Widening	8.00	20	70.93	Ward No. 03	3rd Phase
Tertiary Road	TR-493	Access Road	Widening	8.00	20	275.65	Ward No. 03	3rd Phase
Tertiary Road	TR-494	Access Road	Widening	8.00	20	22.52	Ward No. 02	3rd Phase
Tertiary Road	TR-495	Access Road	Widening	6.00	20	298.19	Ward No. 02	3rd Phase
Tertiary Road	TR-496	Access Road	Widening	8.00	20	49.48	Ward No. 02	3rd Phase
Tertiary Road	TR-497	Access Road	Widening	8.00	20	71.22	Ward No. 03	3rd Phase
Tertiary Road	TR-498	Access Road	Widening	6.00	20	176.23	Ward No. 03	3rd Phase
Tertiary Road	TR-499	Access Road	Widening	6.00	20	43.20	Ward No. 03	3rd Phase
Tertiary Road	TR-500	Access Road	Widening	6.00	20	539.57	Ward No. 03	3rd Phase
Tertiary Road	TR-502	Access Road	Widening	8.00	20	0.05	Ward No. 02	3rd Phase
Tertiary Road	TR-503	Access Road	Widening	8.00	20	213.69	Ward No. 03	3rd Phase
Tertiary Road	TR-504	Access Road	Widening	8.00	20	29.42	Ward No. 03	3rd Phase
Tertiary Road	TR-505	Access Road	Widening	8.00	20	24.30	Ward No. 03	3rd Phase
Tertiary Road	TR-506	Access Road	Widening	8.00	20	261.50	Ward No. 02	3rd Phase
Tertiary Road	TR-507	Access Road	Widening	6.00	20	35.34	Ward No. 02	3rd Phase
Tertiary Road	TR-508	Access Road	Widening	6.00	20	62.68	Ward No. 02	3rd Phase
Tertiary Road	TR-509	Access Road	Widening	6.00	20	33.37	Ward No. 02	3rd Phase
Tertiary Road	TR-510	Access Road	Widening	6.00	20	52.25	Ward No. 02	3rd Phase
Tertiary Road	TR-511	Access Road	Widening	8.00	20	67.33	Ward No. 02	3rd Phase
Tertiary Road	TR-512	Access Road	Widening	6.00	20	423.82	Ward No. 02	3rd Phase
Tertiary Road	TR-513	Access Road	Widening	8.00	20	59.88	Ward No. 04	3rd Phase
Tertiary Road	TR-514	Access Road	Widening	8.00	20	1.83	Ward No. 02	3rd Phase
Tertiary Road	TR-515	Access Road	Widening	8.00	20	1.09	Ward No. 02	3rd Phase
Tertiary Road	TR-515	Access Road	Widening	8.00	20	143.71	Ward No. 04	3rd Phase
Tertiary Road	TR-516	Access Road	Widening	6.00	20	165.91	Ward No. 04	3rd Phase
Tertiary Road	TR-517	Access Road	Widening	6.00	20	141.48	Ward	3rd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 04	Phase
Tertiary Road	TR-518	Access Road	Widening	6.00	20	35.90	Ward No. 04	3rd Phase
Tertiary Road	TR-519	Access Road	Widening	8.00	20	93.57	Ward No. 02	3rd Phase
Tertiary Road	TR-520	Access Road	Widening	6.00	20	680.79	Ward No. 02	3rd Phase
Tertiary Road	TR-521	Access Road	Widening	6.00	20	47.01	Ward No. 02	3rd Phase
Tertiary Road	TR-524	Access Road	Widening	6.00	20	69.25	Ward No. 02	3rd Phase
Tertiary Road	TR-526	Access Road	Widening	8.00	20	4.39	Ward No. 04	3rd Phase
Tertiary Road	TR-527	Access Road	Widening	8.00	20	35.50	Ward No. 02	3rd Phase
Tertiary Road	TR-528	Access Road	Widening	8.00	20	61.85	Ward No. 05	3rd Phase
Tertiary Road	TR-529	Access Road	Widening	8.00	20	58.12	Ward No. 05	3rd Phase
Tertiary Road	TR-530	Access Road	Widening	6.00	20	17.81	Ward No. 05	3rd Phase
Tertiary Road	TR-531	Access Road	Widening	8.00	20	53.64	Ward No. 05	3rd Phase
Tertiary Road	TR-532	Access Road	Widening	6.00	20	52.59	Ward No. 05	3rd Phase
Tertiary Road	TR-535	Access Road	Widening	6.00	20	207.92	Ward No. 07	3rd Phase
Tertiary Road	TR-538	Access Road	Widening	6.00	20	266.84	Ward No. 05	3rd Phase
Tertiary Road	TR-539	Access Road	Widening	8.00	20	60.84	Ward No. 07	3rd Phase
Tertiary Road	TR-540	Access Road	Widening	8.00	20	1.82	Ward No. 07	3rd Phase
Tertiary Road	TR-541	Access Road	Widening	6.00	20	54.29	Ward No. 08	3rd Phase
Tertiary Road	TR-542	Access Road	Widening	10.00	20	3.27	Ward No. 07	3rd Phase
Tertiary Road	TR-543	Access Road	Widening	6.00	20	17.95	Ward No. 08	3rd Phase
Tertiary Road	TR-544	Access Road	Widening	6.00	20	5.76	Ward No. 07	3rd Phase
Tertiary Road	TR-546	Access Road	Widening	8.00	20	305.67	Ward No. 08	3rd Phase
Tertiary Road	TR-547	Access Road	Widening	8.00	20	5.71	Ward No. 07	3rd Phase
Tertiary Road	TR-548	Access Road	Widening	8.00	20	234.91	Ward No. 08	3rd Phase
Tertiary Road	TR-549	Access Road	Widening	6.00	20	40.14	Ward No. 07	3rd Phase
Tertiary Road	TR-551	Access Road	Widening	6.00	20	0.96	Ward No. 05	3rd Phase
Tertiary Road	TR-552	Access Road	Widening	6.00	20	39.04	Ward No. 07	3rd Phase
Tertiary Road	TR-553	Access Road	Widening	6.00	20	607.46	Ward No. 07	3rd Phase
Tertiary Road	TR-554	Access Road	Widening	6.00	20	462.42	Ward No. 07	3rd Phase
Tertiary Road	TR-555	Access Road	Widening	8.00	20	248.96	Ward No. 07	3rd Phase
Tertiary Road	TR-556	Access Road	Widening	8.00	20	616.10	Ward No. 07	3rd Phase
Tertiary Road	TR-557	Access Road	Widening	6.00	20	79.38	Ward No. 05	3rd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-558	Access Road	Widening	8.00	20	198.04	Ward No. 08	3rd Phase
Tertiary Road	TR-560	Access Road	Widening	8.00	20	135.64	Ward No. 05	3rd Phase
Tertiary Road	TR-561	Access Road	Widening	6.00	20	384.86	Ward No. 05	3rd Phase
Tertiary Road	TR-562	Access Road	Widening	6.00	20	37.88	Ward No. 05	3rd Phase
Tertiary Road	TR-563	Access Road	Widening	6.00	20	46.96	Ward No. 05	3rd Phase
Tertiary Road	TR-564	Access Road	Widening	8.00	20	55.45	Ward No. 08	3rd Phase
Tertiary Road	TR-565	Access Road	Widening	6.00	20	452.63	Ward No. 08	3rd Phase
Tertiary Road	TR-566	Access Road	Widening	8.00	20	254.50	Ward No. 08	3rd Phase
Tertiary Road	TR-567	Access Road	Widening	8.00	20	42.67	Ward No. 08	3rd Phase
Tertiary Road	TR-568	Access Road	Widening	8.00	20	51.86	Ward No. 08	3rd Phase
Tertiary Road	TR-569	Access Road	Widening	8.00	20	188.03	Ward No. 05	3rd Phase
Tertiary Road	TR-570	Access Road	Widening	8.00	20	76.78	Ward No. 05	3rd Phase
Tertiary Road	TR-571	Access Road	Widening	8.00	20	0.32	Ward No. 08	3rd Phase
Tertiary Road	TR-573	Access Road	Widening	8.00	20	158.48	Ward No. 05	3rd Phase
Tertiary Road	TR-574	Access Road	Widening	6.00	20	29.39	Ward No. 08	3rd Phase
Tertiary Road	TR-575	Access Road	Widening	6.00	20	78.98	Ward No. 08	3rd Phase
Tertiary Road	TR-576	Access Road	Widening	6.00	20	50.29	Ward No. 08	3rd Phase
Tertiary Road	TR-577	Access Road	Widening	8.00	20	25.34	Ward No. 08	3rd Phase
Tertiary Road	TR-578	Access Road	Widening	8.00	20	849.60	Ward No. 08	3rd Phase
Tertiary Road	TR-579	Access Road	Widening	6.00	20	35.57	Ward No. 08	3rd Phase
Tertiary Road	TR-580	Access Road	Widening	8.00	20	35.92	Ward No. 08	3rd Phase
Tertiary Road	TR-581	Access Road	Widening	8.00	20	35.52	Ward No. 08	3rd Phase
Tertiary Road	TR-582	Access Road	Widening	8.00	20	278.46	Ward No. 08	3rd Phase
Tertiary Road	TR-583	Access Road	Widening	8.00	20	459.11	Ward No. 08	3rd Phase
Tertiary Road	TR-584	Access Road	Widening	8.00	20	47.14	Ward No. 08	3rd Phase
Tertiary Road	TR-585	Access Road	Widening	8.00	20	263.14	Ward No. 08	3rd Phase
Tertiary Road	TR-586	Access Road	Widening	8.00	20	34.05	Ward No. 08	3rd Phase
Tertiary Road	TR-587	Access Road	Widening	8.00	20	63.39	Ward No. 07	3rd Phase
Tertiary Road	TR-588	Access Road	Widening	6.00	20	144.81	Ward No. 07	3rd Phase
Tertiary Road	TR-589	Access Road	Widening	8.00	20	285.07	Ward No. 07	3rd Phase
Tertiary Road	TR-590	Access Road	Widening	6.00	20	63.95	Ward No. 07	3rd Phase
Tertiary Road	TR-591	Access Road	Widening	6.00	20	79.60	Ward	3rd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 07	Phase
Tertiary Road	TR-592	Access Road	Widening	6.00	20	35.87	Ward No. 07	3rd Phase
Tertiary Road	TR-593	Access Road	Widening	6.00	20	32.95	Ward No. 07	3rd Phase
Tertiary Road	TR-594	Access Road	Widening	8.00	20	216.67	Ward No. 07	3rd Phase
Tertiary Road	TR-595	Access Road	Widening	6.00	20	23.28	Ward No. 07	3rd Phase
Tertiary Road	TR-596	Access Road	Widening	8.00	20	33.60	Ward No. 07	3rd Phase
Tertiary Road	TR-597	Access Road	Widening	6.00	20	39.75	Ward No. 07	3rd Phase
Tertiary Road	TR-598	Access Road	Widening	8.00	20	388.88	Ward No. 09	3rd Phase
Tertiary Road	TR-599	Access Road	Widening	6.00	20	194.67	Ward No. 09	3rd Phase
Tertiary Road	TR-600	Access Road	Widening	6.00	20	461.57	Ward No. 07	3rd Phase
Tertiary Road	TR-602	Access Road	Widening	10.00	20	336.59	Ward No. 09	3rd Phase
Tertiary Road	TR-603	Access Road	Widening	8.00	20	196.66	Ward No. 07	3rd Phase
Tertiary Road	TR-604	Access Road	Widening	6.00	20	193.52	Ward No. 07	3rd Phase
Tertiary Road	TR-605	Access Road	Widening	6.00	20	48.29	Ward No. 07	3rd Phase
Tertiary Road	TR-606	Access Road	Widening	6.00	20	28.25	Ward No. 08	3rd Phase
Tertiary Road	TR-607	Access Road	Widening	10.00	20	65.13	Ward No. 08	3rd Phase
Tertiary Road	TR-608	Access Road	Widening	6.00	20	13.63	Ward No. 09	3rd Phase
Tertiary Road	TR-609	Access Road	Widening	10.00	20	3.21	Ward No. 07	3rd Phase
Tertiary Road	TR-611	Access Road	Widening	8.00	20	701.03	Ward No. 08	3rd Phase
Tertiary Road	TR-613	Access Road	Widening	8.00	20	82.46	Ward No. 05	3rd Phase
Tertiary Road	TR-614	Access Road	Widening	8.00	20	69.84	Ward No. 07	3rd Phase
Tertiary Road	TR-615	Access Road	Widening	8.00	20	1.34	Ward No. 08	3rd Phase
Tertiary Road	TR-616	Access Road	Widening	6.00	20	42.70	Ward No. 09	3rd Phase
Tertiary Road	TR-617	Access Road	Widening	8.00	20	557.13	Ward No. 08	3rd Phase
Tertiary Road	TR-618	Access Road	Widening	6.00	20	230.34	Ward No. 08	3rd Phase
Tertiary Road	TR-619	Access Road	Widening	8.00	20	290.93	Ward No. 08	3rd Phase
Tertiary Road	TR-620	Access Road	Widening	8.00	20	37.92	Ward No. 08	3rd Phase
Tertiary Road	TR-621	Access Road	Widening	8.00	20	318.76	Ward No. 08	3rd Phase
Tertiary Road	TR-621	Access Road	Widening	8.00	20	0.96	Ward No. 09	3rd Phase
Tertiary Road	TR-622	Access Road	Widening	8.00	20	161.23	Ward No. 08	3rd Phase
Tertiary Road	TR-623	Access Road	Widening	8.00	20	60.76	Ward No. 08	3rd Phase
Tertiary Road	TR-624	Access Road	Widening	8.00	20	45.04	Ward No. 08	3rd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-625	Access Road	Widening	10.00	20	29.52	Ward No. 08	3rd Phase
Tertiary Road	TR-626	Access Road	Widening	10.00	20	426.11	Ward No. 08	3rd Phase
Tertiary Road	TR-627	Access Road	Widening	8.00	20	862.12	Ward No. 08	3rd Phase
Tertiary Road	TR-627	Access Road	Widening	8.00	20	98.62	Ward No. 05	3rd Phase
Tertiary Road	TR-630	Access Road	Widening	8.00	20	57.21	Ward No. 05	3rd Phase
Tertiary Road	TR-631	Access Road	Widening	8.00	20	432.64	Ward No. 08	3rd Phase
Tertiary Road	TR-632	Access Road	Widening	8.00	20	49.55	Ward No. 08	3rd Phase
Tertiary Road	TR-633	Access Road	Widening	6.00	20	662.54	Ward No. 08	3rd Phase
Tertiary Road	TR-634	Access Road	Widening	8.00	20	43.19	Ward No. 08	3rd Phase
Tertiary Road	TR-635	Access Road	Widening	8.00	20	573.68	Ward No. 08	3rd Phase
Tertiary Road	TR-636	Access Road	Widening	6.00	20	31.98	Ward No. 08	3rd Phase
Tertiary Road	TR-637	Access Road	Widening	8.00	20	469.36	Ward No. 08	3rd Phase
Tertiary Road	TR-638	Access Road	Widening	6.00	20	119.73	Ward No. 08	3rd Phase
Tertiary Road	TR-639	Access Road	Widening	8.00	20	43.17	Ward No. 08	3rd Phase
Tertiary Road	TR-640	Access Road	Widening	8.00	20	48.01	Ward No. 08	3rd Phase
Tertiary Road	TR-641	Access Road	Widening	8.00	20	191.96	Ward No. 08	3rd Phase
Tertiary Road	TR-642	Access Road	Widening	8.00	20	215.86	Ward No. 08	3rd Phase
Tertiary Road	TR-643	Access Road	Widening	6.00	20	191.76	Ward No. 08	3rd Phase
Tertiary Road	TR-644	Access Road	Widening	8.00	20	77.27	Ward No. 08	3rd Phase
Tertiary Road	TR-645	Access Road	Widening	6.00	20	214.31	Ward No. 08	3rd Phase
Tertiary Road	TR-646	Access Road	Widening	8.00	20	40.57	Ward No. 09	3rd Phase
Tertiary Road	TR-647	Access Road	Widening	8.00	20	279.81	Ward No. 09	3rd Phase
Tertiary Road	TR-648	Access Road	Widening	8.00	20	426.02	Ward No. 09	3rd Phase
Tertiary Road	TR-649	Access Road	Widening	6.00	20	70.47	Ward No. 08	3rd Phase
Tertiary Road	TR-650	Access Road	Widening	10.00	20	24.44	Ward No. 09	3rd Phase
Tertiary Road	TR-651	Access Road	Widening	8.00	20	31.80	Ward No. 09	3rd Phase
Tertiary Road	TR-652	Access Road	Widening	6.00	20	14.76	Ward No. 09	3rd Phase
Tertiary Road	TR-653	Access Road	Widening	8.00	20	131.20	Ward No. 09	3rd Phase
Tertiary Road	TR-654	Access Road	Widening	6.00	20	71.61	Ward No. 09	3rd Phase
Tertiary Road	TR-655	Access Road	Widening	8.00	20	41.65	Ward No. 09	3rd Phase
Tertiary Road	TR-656	Access Road	Widening	6.00	20	25.43	Ward No. 09	3rd Phase
Tertiary Road	TR-657	Access Road	Widening	8.00	20	28.01	Ward	3rd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 09	Phase
Tertiary Road	TR-658	Access Road	Widening	6.00	20	40.53	Ward No. 09	3rd Phase
Tertiary Road	TR-659	Access Road	Widening	8.00	20	23.60	Ward No. 09	3rd Phase
Tertiary Road	TR-660	Access Road	Widening	8.00	20	59.64	Ward No. 09	3rd Phase
Tertiary Road	TR-661	Access Road	Widening	6.00	20	368.17	Ward No. 09	3rd Phase
Tertiary Road	TR-662	Access Road	Widening	8.00	20	389.05	Ward No. 09	3rd Phase
Tertiary Road	TR-663	Access Road	Widening	6.00	20	90.24	Ward No. 09	3rd Phase
Tertiary Road	TR-664	Access Road	Widening	8.00	20	23.81	Ward No. 09	3rd Phase
Tertiary Road	TR-665	Access Road	Widening	6.00	20	26.93	Ward No. 09	3rd Phase
Tertiary Road	TR-666	Access Road	Widening	6.00	20	45.01	Ward No. 09	3rd Phase
Tertiary Road	TR-667	Access Road	Widening	6.00	20	32.76	Ward No. 09	3rd Phase
Tertiary Road	TR-668	Access Road	Widening	6.00	20	92.06	Ward No. 09	3rd Phase
Tertiary Road	TR-669	Access Road	Widening	6.00	20	450.70	Ward No. 09	3rd Phase
Tertiary Road	TR-670	Access Road	Widening	8.00	20	43.96	Ward No. 09	3rd Phase
Tertiary Road	TR-671	Access Road	Widening	8.00	20	36.47	Ward No. 09	3rd Phase
Tertiary Road	TR-672	Access Road	Widening	6.00	20	328.44	Ward No. 09	3rd Phase
Tertiary Road	TR-673	Access Road	Widening	6.00	20	505.61	Ward No. 09	3rd Phase
Tertiary Road	TR-674	Access Road	Widening	6.00	20	455.72	Ward No. 09	3rd Phase
Tertiary Road	TR-675	Access Road	Widening	6.00	20	35.18	Ward No. 09	3rd Phase
Tertiary Road	TR-676	Access Road	Widening	6.00	20	30.27	Ward No. 09	3rd Phase
Tertiary Road	TR-677	Access Road	Widening	6.00	20	57.04	Ward No. 09	3rd Phase
Tertiary Road	TR-678	Access Road	Widening	6.00	20	113.09	Ward No. 08	3rd Phase
Tertiary Road	TR-679	Access Road	Widening	8.00	20	2.27	Ward No. 09	3rd Phase
Tertiary Road	TR-680	Access Road	Widening	6.00	20	478.53	Ward No. 08	3rd Phase
Tertiary Road	TR-682	Access Road	Widening	6.00	20	198.92	Ward No. 08	3rd Phase
Tertiary Road	TR-684	Access Road	Widening	8.00	20	85.53	Ward No. 09	3rd Phase
Tertiary Road	TR-685	Access Road	Widening	8.00	20	4.60	Ward No. 08	3rd Phase
Tertiary Road	TR-687	Access Road	Widening	8.00	20	48.70	Ward No. 09	3rd Phase
Tertiary Road	TR-688	Access Road	Widening	6.00	20	214.78	Ward No. 09	3rd Phase
Tertiary Road	TR-689	Access Road	Widening	6.00	20	25.17	Ward No. 08	3rd Phase
Tertiary Road	TR-689	Access Road	Widening	6.00	20	149.69	Ward No. 09	3rd Phase
Tertiary Road	TR-690	Access Road	Widening	8.00	20	13.88	Ward No. 09	3rd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-691	Access Road	Widening	8.00	20	75.57	Ward No. 09	3rd Phase
Tertiary Road	TR-692	Access Road	Widening	8.00	20	297.68	Ward No. 09	3rd Phase
Tertiary Road	TR-693	Access Road	Widening	8.00	20	46.25	Ward No. 08	3rd Phase
Tertiary Road	TR-695	Access Road	Widening	6.00	20	4.04	Ward No. 09	3rd Phase
Tertiary Road	TR-696	Access Road	Widening	6.00	20	87.30	Ward No. 09	3rd Phase
Tertiary Road	TR-697	Access Road	Widening	8.00	20	46.60	Ward No. 09	3rd Phase
Tertiary Road	TR-698	Access Road	Widening	8.00	20	32.15	Ward No. 09	3rd Phase
Tertiary Road	TR-699	Access Road	Widening	8.00	20	1065.61	Ward No. 09	3rd Phase
Tertiary Road	TR-700	Access Road	Widening	8.00	20	21.61	Ward No. 09	3rd Phase
Tertiary Road	TR-701	Access Road	Widening	6.00	20	32.19	Ward No. 09	3rd Phase
Tertiary Road	TR-702	Access Road	Widening	6.00	20	42.36	Ward No. 09	3rd Phase
Tertiary Road	TR-703	Access Road	Widening	6.00	20	216.15	Ward No. 08	3rd Phase
Tertiary Road	TR-704	Access Road	Widening	6.00	20	47.81	Ward No. 08	3rd Phase
Tertiary Road	TR-705	Access Road	Widening	8.00	20	292.73	Ward No. 09	3rd Phase
Tertiary Road	TR-706	Access Road	Widening	8.00	20	64.41	Ward No. 09	3rd Phase
Tertiary Road	TR-707	Access Road	Widening	6.00	20	922.48	Ward No. 09	3rd Phase
Tertiary Road	TR-708	Access Road	Widening	8.00	20	17.02	Ward No. 02	3rd Phase
Tertiary Road	TR-709	Access Road	Widening	6.00	20	34.32	Ward No. 01	3rd Phase
Tertiary Road	TR-710	Access Road	Widening	6.00	20	46.52	Ward No. 01	3rd Phase
Tertiary Road	TR-711	Access Road	Widening	6.00	20	37.04	Ward No. 04	3rd Phase
Tertiary Road	TR-712	Access Road	Widening	8.00	20	170.61	Ward No. 04	3rd Phase
Tertiary Road	TR-714	Access Road	Widening	7.00	20	99.19	Ward No. 05	3rd Phase
Tertiary Road	TR-715	Access Road	Widening	8.00	20	95.28	Ward No. 03	3rd Phase
Tertiary Road	TR-716	Access Road	Widening	8.00	20	9.08	Ward No. 05	3rd Phase
Tertiary Road	TR-717	Access Road	Widening	8.00	20	53.94	Ward No. 05	3rd Phase
Tertiary Road	TR-718	Access Road	Widening	8.00	20	16.82	Ward No. 05	3rd Phase
Tertiary Road	TR-719	Access Road	Widening	10.00	20	82.52	Ward No. 05	3rd Phase
Tertiary Road	TR-720	Access Road	Widening	8.00	20	320.86	Ward No. 09	3rd Phase
Tertiary Road	TR-721	Access Road	Widening	6.00	20	28.05	Ward No. 09	3rd Phase
Tertiary Road	TR-722	Access Road	Widening	12.00	20	890.42	Ward No. 09	3rd Phase
Tertiary Road	TR-724	Access Road	Widening	6.00	20	1060.34	Ward No. 05	3rd Phase
Tertiary Road	TR-725	Access Road	Widening	6.00	20	12.62	Ward	3rd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 08	Phase
Tertiary Road	TR-726	Access Road	Widening	8.00	20	36.16	Ward No. 03	3rd Phase
Tertiary Road	TR-727	Access Road	Widening	6.00	20	260.98	Ward No. 01	3rd Phase
Tertiary Road	TR-728	Access Road	Widening	6.00	20	97.77	Ward No. 01	3rd Phase
Tertiary Road	TR-729	Access Road	Widening	8.00	20	125.86	Ward No. 01	3rd Phase
Tertiary Road	TR-730	Access Road	Widening	8.00	20	473.30	Ward No. 02	3rd Phase
Tertiary Road	TR-732	Access Road	Widening	4.00	20	275.01	Ward No. 08	3rd Phase
Tertiary Road	TR-733	Access Road	Widening	10.00	20	0.01	Ward No. 08	3rd Phase
Tertiary Road	TR-734	Access Road	Widening	6.00	20	413.19	Ward No. 08	3rd Phase
Tertiary Road	TR-735	Access Road	Widening	6.00	20	159.27	Ward No. 08	3rd Phase
Tertiary Road	TR-736	Access Road	Widening	6.00	20	85.85	Ward No. 08	3rd Phase
Tertiary Road	TR-737	Access Road	Widening	8.00	20	38.30	Ward No. 05	3rd Phase
Tertiary Road	TR-738	Access Road	Widening	8.00	20	52.49	Ward No. 05	3rd Phase
Tertiary Road	TR-739	Access Road	Widening	8.00	20	49.92	Ward No. 05	3rd Phase
Tertiary Road	TR-740	Access Road	Widening	8.00	20	115.82	Ward No. 04	3rd Phase
Tertiary Road	TR-742	Access Road	Widening	10.00	20	139.53	Ward No. 05	3rd Phase
Tertiary Road	TR-743	Access Road	Widening	10.00	20	44.97	Ward No. 05	3rd Phase
Tertiary Road	TR-744	Access Road	Widening	10.00	20	24.20	Ward No. 07	3rd Phase
Tertiary Road	TR-745	Access Road	Widening	10.00	20	232.12	Ward No. 07	3rd Phase
Tertiary Road	TR-746	Access Road	Widening	10.00	20	200.92	Ward No. 07	3rd Phase
Tertiary Road	TR-747	Access Road	Widening	6.00	20	289.48	Ward No. 09	3rd Phase
Tertiary Road	TR-748	Access Road	Widening	6.00	20	14.73	Ward No. 06	3rd Phase
Tertiary Road	TR-749	Access Road	Widening	10.00	20	535.33	Ward No. 02	3rd Phase
Tertiary Road	TR-750	Access Road	Widening	10.00	20	14.41	Ward No. 01	3rd Phase
Tertiary Road	TR-751	Access Road	Widening	6.00	20	279.30	Ward No. 01	3rd Phase
Tertiary Road	TR-752	Access Road	Widening	8.00	20	33.34	Ward No. 01	3rd Phase
Tertiary Road	TR-753	Access Road	Widening	8.00	20	9.98	Ward No. 01	3rd Phase
Tertiary Road	TR-754	Access Road	Widening	8.00	20	69.63	Ward No. 01	3rd Phase
Tertiary Road	TR-755	Access Road	Widening	8.00	20	32.70	Ward No. 01	3rd Phase
Tertiary Road	TR-756	Access Road	Widening	6.00	20	29.09	Ward No. 01	3rd Phase
Tertiary Road	TR-757	Access Road	Widening	8.00	20	17.80	Ward No. 01	3rd Phase
Tertiary Road	TR-758	Access Road	Widening	5.00	20	42.12	Ward No. 05	3rd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-759	Access Road	Widening	6.00	20	68.98	Ward No. 01	3rd Phase
Tertiary Road	TR-760	Access Road	Widening	4.00	20	40.63	Ward No. 01	3rd Phase
Tertiary Road	TR-763	Access Road	Widening	8.00	20	270.77	Ward No. 08	3rd Phase
Tertiary Road	TR-794		New	0.00	20	499.50	Ward No. 01	3rd Phase
Tertiary Road	TR-795		New	0.00	20	387.78	Ward No. 01	3rd Phase
Tertiary Road	TR-796	Access Road	Widening	8.00	20	97.72	Ward No. 01	3rd Phase
Tertiary Road	TR-797	Access Road	Widening	8.00	20	361.28	Ward No. 01	3rd Phase
Tertiary Road	TR-798	Access Road	Widening	8.00	20	201.30	Ward No. 01	3rd Phase
Tertiary Road	TR-799	Access Road	Widening	8.00	20	293.63	Ward No. 01	3rd Phase
Tertiary Road	TR-800		New	0.00	20	235.72	Ward No. 01	3rd Phase
Tertiary Road	TR-801		New	0.00	20	517.97	Ward No. 01	3rd Phase
Tertiary Road	TR-802		New	0.00	20	460.98	Ward No. 01	3rd Phase
Tertiary Road	TR-803		New	0.00	20	159.94	Ward No. 01	3rd Phase
Tertiary Road	TR-804		New	0.00	20	186.25	Ward No. 02	3rd Phase
Tertiary Road	TR-804		New	0.00	20	97.08	Ward No. 01	3rd Phase
Tertiary Road	TR-805		New	0.00	20	324.26	Ward No. 01	3rd Phase
Tertiary Road	TR-806		New	0.00	20	574.45	Ward No. 03	3rd Phase
Tertiary Road	TR-807	Dhaka-Barisal Highway	Widening	20.00	20	280.71	Ward No. 03	3rd Phase
Tertiary Road	TR-808	Dhaka-Barisal Highway	Widening	20.00	20	119.08	Ward No. 03	3rd Phase
Tertiary Road	TR-809	Dhaka-Barisal Highway	Widening	20.00	20	6.39	Ward No. 03	3rd Phase
Tertiary Road	TR-810	Dhaka-Barisal Highway	Widening	20.00	20	146.00	Ward No. 03	3rd Phase
Tertiary Road	TR-811	Dhaka-Barisal Highway	Widening	20.00	20	243.74	Ward No. 03	3rd Phase
Tertiary Road	TR-812		New	0.00	20	332.68	Ward No. 04	3rd Phase
Tertiary Road	TR-813		New	0.00	20	164.64	Ward No. 02	3rd Phase
Tertiary Road	TR-814		New	0.00	20	146.47	Ward No. 02	3rd Phase
Tertiary Road	TR-814		New	0.00	20	410.04	Ward No. 04	3rd Phase
Tertiary Road	TR-815		New	0.00	20	254.03	Ward No. 04	3rd Phase
Tertiary Road	TR-816		New	0.00	20	188.06	Ward No. 04	3rd Phase
Tertiary Road	TR-817		New	0.00	20	355.26	Ward No. 06	3rd Phase
Tertiary Road	TR-818		New	0.00	20	374.48	Ward No. 06	3rd Phase
Tertiary Road	TR-819		New	0.00	20	163.20	Ward No. 06	3rd Phase
Tertiary Road	TR-820		New	0.00	20	494.62	Ward	3rd

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
							No. 06	Phase
Tertiary Road	TR-821		New	0.00	20	593.28	Ward No. 07	3rd Phase
Tertiary Road	TR-822		New	0.00	20	626.70	Ward No. 06	3rd Phase
Tertiary Road	TR-823		New	0.00	20	321.37	Ward No. 07	3rd Phase
Tertiary Road	TR-823		New	0.00	20	85.60	Ward No. 06	3rd Phase
Tertiary Road	TR-824		New	0.00	20	263.38	Ward No. 07	3rd Phase
Tertiary Road	TR-825		New	0.00	20	136.47	Ward No. 07	3rd Phase
Tertiary Road	TR-826	Access Road	Widening	6.00	20	206.35	Ward No. 09	3rd Phase
Tertiary Road	TR-827		New	0.00	20	471.19	Ward No. 08	3rd Phase
Tertiary Road	TR-828		New	0.00	20	1192.89	Ward No. 08	3rd Phase
Tertiary Road	TR-829		New	0.00	20	246.89	Ward No. 08	3rd Phase
Tertiary Road	TR-829		New	0.00	20	69.41	Ward No. 05	3rd Phase
Tertiary Road	TR-830		New	0.00	20	505.58	Ward No. 08	3rd Phase
Tertiary Road	TR-831		New	0.00	20	193.87	Ward No. 08	3rd Phase
Tertiary Road	TR-832		New	0.00	20	104.13	Ward No. 05	3rd Phase
Tertiary Road	TR-833		New	0.00	20	654.49	Ward No. 05	3rd Phase
Tertiary Road	TR-834		New	0.00	20	328.79	Ward No. 07	3rd Phase
Tertiary Road	TR-835		New	0.00	20	153.84	Ward No. 07	3rd Phase
Tertiary Road	TR-836		New	0.00	20	762.99	Ward No. 07	3rd Phase
Tertiary Road	TR-837		New	0.00	20	317.76	Ward No. 08	3rd Phase
Tertiary Road	TR-838	Access Road	Widening	6.00	20	140.83	Ward No. 08	3rd Phase
Tertiary Road	TR-839	Access Road	Widening	6.00	20	37.17	Ward No. 08	3rd Phase
Tertiary Road	TR-840	Access Road	Widening	6.00	20	43.24	Ward No. 08	3rd Phase
Tertiary Road	TR-841	Access Road	Widening	6.00	20	16.87	Ward No. 08	3rd Phase
Tertiary Road	TR-842	Access Road	Widening	6.00	20	64.64	Ward No. 08	3rd Phase
Tertiary Road	TR-843	Access Road	Widening	6.00	20	79.67	Ward No. 08	3rd Phase
Tertiary Road	TR-844	Access Road	Widening	6.00	20	192.05	Ward No. 08	3rd Phase
Tertiary Road	TR-845	Access Road	Widening	6.00	20	358.54	Ward No. 08	3rd Phase
Tertiary Road	TR-846		New	0.00	20	791.96	Ward No. 09	3rd Phase
Tertiary Road	TR-847		New	0.00	20	319.87	Ward No. 09	3rd Phase
Tertiary Road	TR-848		New	0.00	20	231.18	Ward No. 09	3rd Phase
Tertiary Road	TR-849		New	0.00	20	623.30	Ward No. 09	3rd Phase

Proposed Hierarchy	Proposed Road ID	Road Name	Proposed Type	Existing width (ft)	Proposed width (ft)	Length (m)	Ward No.	Phasing
Tertiary Road	TR-850		New	0.00	20	431.39	Ward No. 09	3rd Phase
Tertiary Road	TR-851		New	0.00	20	228.27	Ward No. 09	3rd Phase
Tertiary Road	TR-852		New	0.00	20	1281.12	Ward No. 09	3rd Phase
Tertiary Road	TR-853		New	0.00	20	284.19	Ward No. 07	3rd Phase
Tertiary Road	TR-853		New	0.00	20	778.21	Ward No. 09	3rd Phase
Tertiary Road	TR-854		New	0.00	20	488.43	Ward No. 07	3rd Phase
Tertiary Road	TR-855		New	0.00	20	81.51	Ward No. 04	3rd Phase
Tertiary Road	TR-856		New	0.00	20	1166.27	Ward No. 07	3rd Phase
Tertiary Road	TR-856		New	0.00	20	43.11	Ward No. 05	3rd Phase
Tertiary Road	TR-857		New	0.00	20	326.50	Ward No. 05	3rd Phase
Tertiary Road	TR-858		New	0.00	20	420.54	Ward No. 06	3rd Phase
Tertiary Road	TR-859		New	0.00	20	249.27	Ward No. 06	3rd Phase
Tertiary Road	TR-860		New	0.00	20	113.79	Ward No. 06	3rd Phase
Tertiary Road	TR-861		New	0.00	20	289.58	Ward No. 07	3rd Phase
Tertiary Road	TR-861		New	0.00	20	188.44	Ward No. 06	3rd Phase
Tertiary Road	TR-862		New	0.00	20	212.82	Ward No. 03	3rd Phase
Tertiary Road	TR-862		New	0.00	20	544.14	Ward No. 04	3rd Phase
Tertiary Road	TR-862		New	0.00	20	372.50	Ward No. 06	3rd Phase
Tertiary Road	TR-863		New	0.00	20	292.63	Ward No. 04	3rd Phase
Tertiary Road	TR-864		New	0.00	20	531.27	Ward No. 02	3rd Phase
Tertiary Road	TR-864		New	0.00	20	393.66	Ward No. 04	3rd Phase
Tertiary Road	TR-865		New	0.00	20	406.69	Ward No. 04	3rd Phase
Tertiary Road	TR-866		New	0.00	20	332.70	Ward No. 09	3rd Phase
Tertiary Road	TR-867		New	0.00	20	281.17	Ward No. 09	3rd Phase
Tertiary Road	TR-868		New	0.00	20	276.36	Ward No. 09	3rd Phase
Tertiary Road	TR-869		New	0.00	20	593.23	Ward No. 09	3rd Phase
Tertiary Road	TR-870		New	0.00	20	220.03	Ward No. 09	3rd Phase

Table F1: Proposed Drain Inventory

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
SD-1	Secondary Drain	New Drain	3.50-4.50	1151.51	1.25-3.00	Ward No. 06	1st Phase
SD-2	Secondary Drain	New Drain	3.50-4.50	847.51	1.25-3.00	Ward No. 05	1st Phase
SD-3	Secondary Drain	New Drain	3.50-4.50	859.24	1.25-3.00	Ward No. 07	1st Phase
SD-3	Secondary Drain	New Drain	3.50-4.50	569.99	1.25-3.00	Ward No. 06	1st Phase
SD-4	Secondary Drain	New Drain	3.50-4.50	408.93	1.25-3.00	Ward No. 07	1st Phase
SD-5	Secondary Drain	New Drain	3.50-4.50	479.95	1.25-3.00	Ward No. 09	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	1003.49	1.25-3.00	Ward No. 07	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	1383.25	1.25-3.00	Ward No. 03	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	123.07	1.25-3.00	Ward No. 03	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	123.07	1.25-3.00	Ward No. 02	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	1088.99	1.25-3.00	Ward No. 02	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	1130.37	1.25-3.00	Ward No. 04	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	543.99	1.25-3.00	Ward No. 06	1st Phase
SD-7	Secondary Drain	New Drain	3.50-4.50	489.19	1.25-3.00	Ward No. 02	1st Phase
SD-8	Secondary Drain	New Drain	3.50-4.50	866.22	1.25-3.00	Ward No. 07	1st Phase
SD-8	Secondary Drain	New Drain	3.50-4.50	92.18	1.25-3.00	Ward No. 08	1st Phase
SD-8	Secondary Drain	New Drain	3.50-4.50	712.57	1.25-3.00	Ward No. 09	1st Phase
SD-8	Secondary Drain	New Drain	3.50-4.50	38.15	1.25-3.00	Ward No. 05	1st Phase
SD-9	Secondary Drain	New Drain	3.50-4.50	426.02	1.25-3.00	Ward No. 09	1st Phase
SD-10	Secondary Drain	New Drain	3.50-4.50	260.98	1.25-3.00	Ward No. 01	1st Phase
PD-1	Primary Drain	New Drain	4.50-5.50	521.49	2.00-3.00	Ward No. 02	1st Phase
PD-1	Primary Drain	New Drain	4.50-5.50	199.81	2.00-3.00	Ward No. 04	1st Phase
PD-2	Primary Drain	New Drain	4.50-5.50	788.88	2.00-3.00	Ward No. 06	1st Phase
PD-3	Primary Drain	New Drain	4.50-5.50	26.46	2.00-3.00	Ward No. 03	1st Phase
PD-3	Primary Drain	New Drain	4.50-5.50	1565.18	2.00-3.00	Ward No. 01	1st Phase
PD-4	Primary Drain	New Drain	4.50-5.50	1.36	2.00-3.00	Ward No. 05	1st Phase
SD-22	Secondary Drain	New Drain	3.50-4.50	461.99	1.25-3.00	Ward No. 02	1st Phase
SD-22	Secondary Drain	New Drain	3.50-4.50	123.36	1.25-3.00	Ward No. 04	1st Phase
PD-5	Primary Drain	New Drain	4.50-5.50	516.03	2.00-3.00	Ward No. 07	1st Phase
PD-5	Primary Drain	New Drain	4.50-5.50	33.66	2.00-3.00	Ward No. 05	1st Phase
PD-6	Primary Drain	New Drain	4.50-5.50	234.38	2.00-3.00	Ward No. 05	1st Phase
PD-7	Primary Drain	New Drain	4.50-5.50	429.07	2.00-3.00	Ward No. 08	1st Phase
PD-7	Primary Drain	New Drain	4.50-5.50	512.50	2.00-3.00	Ward No. 05	1st Phase
SD-23	Secondary Drain	New Drain	3.50-4.50	0.62	1.25-3.00	Ward No. 05	1st Phase
SD-24	Secondary Drain	New Drain	3.50-4.50	276.74	1.25-3.00	Ward No. 05	1st Phase
SD-25	Secondary Drain	New Drain	3.50-4.50	365.22	1.25-3.00	Ward No. 05	1st Phase
SD-26	Secondary Drain	New Drain	3.50-4.50	34.45	1.25-3.00	Ward No. 05	1st Phase
SD-27	Secondary Drain	New Drain	3.50-4.50	1229.46	1.25-3.00	Ward No. 03	1st Phase
SD-27	Secondary Drain	New Drain	3.50-4.50	602.09	1.25-3.00	Ward No. 04	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	19.10	1.25-3.00	Ward No. 03	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	19.10	1.25-3.00	Ward No. 02	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	16.30	1.25-3.00	Ward No. 03	1st Phase
SD-6	Secondary Drain	New Drain	3.50-4.50	16.30	1.25-3.00	Ward No. 02	1st Phase
TD-3	Tertiary Drain	New Drain	2.5-3.5	4.24	0.64-1.25	Ward No. 03	2nd Phase
TD-3	Tertiary Drain	New Drain	2.5-3.5	4.24	0.64-1.25	Ward No. 02	2nd Phase
TD-4	Tertiary Drain	New Drain	2.5-3.5	26.63	0.64-1.25	Ward No. 03	2nd Phase
TD-5	Tertiary Drain	New Drain	2.5-3.5	98.97	0.64-1.25	Ward No. 03	2nd Phase
TD-6	Tertiary Drain	New Drain	2.5-3.5	3.40	0.64-1.25	Ward No. 03	2nd Phase
TD-8	Tertiary Drain	New Drain	2.5-3.5	279.07	0.64-1.25	Ward No. 06	2nd Phase
TD-9	Tertiary Drain	New Drain	2.5-3.5	110.27	0.64-1.25	Ward No. 03	2nd Phase
TD-10	Tertiary Drain	New Drain	2.5-3.5	125.21	0.64-1.25	Ward No. 06	2nd Phase
TD-12	Tertiary Drain	New Drain	2.5-3.5	10.30	0.64-1.25	Ward No. 06	2nd Phase
TD-13	Tertiary Drain	New Drain	2.5-3.5	159.87	0.64-1.25	Ward No. 03	2nd Phase
TD-14	Tertiary Drain	New Drain	2.5-3.5	33.94	0.64-1.25	Ward No. 03	2nd Phase
TD-15	Tertiary Drain	New Drain	2.5-3.5	293.33	0.64-1.25	Ward No. 03	2nd Phase
TD-17	Tertiary Drain	New Drain	2.5-3.5	4.16	0.64-1.25	Ward No. 06	2nd Phase
TD-18	Tertiary Drain	New Drain	2.5-3.5	576.05	0.64-1.25	Ward No. 03	2nd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-18	Tertiary Drain	New Drain	2.5-3.5	475.51	0.64-1.25	Ward No. 04	2nd Phase
TD-20	Tertiary Drain	New Drain	2.5-3.5	2.39	0.64-1.25	Ward No. 04	2nd Phase
TD-21	Tertiary Drain	New Drain	2.5-3.5	333.30	0.64-1.25	Ward No. 03	2nd Phase
TD-22	Tertiary Drain	New Drain	2.5-3.5	61.29	0.64-1.25	Ward No. 03	2nd Phase
TD-23	Tertiary Drain	New Drain	2.5-3.5	46.54	0.64-1.25	Ward No. 03	2nd Phase
TD-24	Tertiary Drain	New Drain	2.5-3.5	59.59	0.64-1.25	Ward No. 03	2nd Phase
TD-26	Tertiary Drain	New Drain	2.5-3.5	83.65	0.64-1.25	Ward No. 04	2nd Phase
TD-27	Tertiary Drain	New Drain	2.5-3.5	384.35	0.64-1.25	Ward No. 04	2nd Phase
TD-28	Tertiary Drain	New Drain	2.5-3.5	418.06	0.64-1.25	Ward No. 04	2nd Phase
TD-30	Tertiary Drain	New Drain	2.5-3.5	117.42	0.64-1.25	Ward No. 03	2nd Phase
TD-32	Tertiary Drain	New Drain	2.5-3.5	256.92	0.64-1.25	Ward No. 04	2nd Phase
TD-33	Tertiary Drain	New Drain	2.5-3.5	648.40	0.64-1.25	Ward No. 04	2nd Phase
TD-34	Tertiary Drain	New Drain	2.5-3.5	57.23	0.64-1.25	Ward No. 03	2nd Phase
TD-36	Tertiary Drain	New Drain	2.5-3.5	3.27	0.64-1.25	Ward No. 04	2nd Phase
TD-37	Tertiary Drain	New Drain	2.5-3.5	337.53	0.64-1.25	Ward No. 04	2nd Phase
TD-38	Tertiary Drain	New Drain	2.5-3.5	386.87	0.64-1.25	Ward No. 04	2nd Phase
TD-39	Tertiary Drain	New Drain	2.5-3.5	115.69	0.64-1.25	Ward No. 04	2nd Phase
TD-40	Tertiary Drain	New Drain	2.5-3.5	271.93	0.64-1.25	Ward No. 04	2nd Phase
TD-42	Tertiary Drain	New Drain	2.5-3.5	66.16	0.64-1.25	Ward No. 03	2nd Phase
TD-43	Tertiary Drain	New Drain	2.5-3.5	0.00	0.64-1.25	Ward No. 03	2nd Phase
TD-43	Tertiary Drain	New Drain	2.5-3.5	0.00	0.64-1.25	Ward No. 04	2nd Phase
TD-44	Tertiary Drain	New Drain	2.5-3.5	20.06	0.64-1.25	Ward No. 04	2nd Phase
TD-45	Tertiary Drain	New Drain	2.5-3.5	476.56	0.64-1.25	Ward No. 02	2nd Phase
TD-45	Tertiary Drain	New Drain	2.5-3.5	152.28	0.64-1.25	Ward No. 04	2nd Phase
TD-48	Tertiary Drain	New Drain	2.5-3.5	348.69	0.64-1.25	Ward No. 02	2nd Phase
TD-48	Tertiary Drain	New Drain	2.5-3.5	166.01	0.64-1.25	Ward No. 04	2nd Phase
TD-50	Tertiary Drain	New Drain	2.5-3.5	1921.08	0.64-1.25	Ward No. 06	2nd Phase
TD-51	Tertiary Drain	New Drain	2.5-3.5	1037.05	0.64-1.25	Ward No. 06	2nd Phase
TD-52	Tertiary Drain	New Drain	2.5-3.5	48.83	0.64-1.25	Ward No. 03	2nd Phase
TD-53	Tertiary Drain	New Drain	2.5-3.5	2.59	0.64-1.25	Ward No. 03	2nd Phase
TD-54	Tertiary Drain	New Drain	2.5-3.5	302.52	0.64-1.25	Ward No. 06	2nd Phase
TD-55	Tertiary Drain	New Drain	2.5-3.5	150.92	0.64-1.25	Ward No. 06	2nd Phase
TD-56	Tertiary Drain	New Drain	2.5-3.5	300.11	0.64-1.25	Ward No. 06	2nd Phase
TD-57	Tertiary Drain	New Drain	2.5-3.5	325.36	0.64-1.25	Ward No. 06	2nd Phase
TD-58	Tertiary Drain	New Drain	2.5-3.5	166.89	0.64-1.25	Ward No. 06	2nd Phase
TD-59	Tertiary Drain	New Drain	2.5-3.5	42.06	0.64-1.25	Ward No. 06	2nd Phase
TD-60	Tertiary Drain	New Drain	2.5-3.5	60.08	0.64-1.25	Ward No. 06	2nd Phase
TD-61	Tertiary Drain	New Drain	2.5-3.5	272.29	0.64-1.25	Ward No. 06	2nd Phase
TD-62	Tertiary Drain	New Drain	2.5-3.5	488.54	0.64-1.25	Ward No. 06	2nd Phase
TD-63	Tertiary Drain	New Drain	2.5-3.5	80.90	0.64-1.25	Ward No. 06	2nd Phase
TD-64	Tertiary Drain	New Drain	2.5-3.5	168.86	0.64-1.25	Ward No. 06	2nd Phase
TD-65	Tertiary Drain	New Drain	2.5-3.5	894.48	0.64-1.25	Ward No. 06	2nd Phase
TD-66	Tertiary Drain	New Drain	2.5-3.5	469.67	0.64-1.25	Ward No. 06	2nd Phase
TD-67	Tertiary Drain	New Drain	2.5-3.5	701.79	0.64-1.25	Ward No. 06	2nd Phase
TD-68	Tertiary Drain	New Drain	2.5-3.5	280.29	0.64-1.25	Ward No. 06	2nd Phase
TD-69	Tertiary Drain	New Drain	2.5-3.5	85.30	0.64-1.25	Ward No. 06	2nd Phase
TD-70	Tertiary Drain	New Drain	2.5-3.5	735.37	0.64-1.25	Ward No. 06	2nd Phase
TD-71	Tertiary Drain	New Drain	2.5-3.5	12.88	0.64-1.25	Ward No. 06	2nd Phase
TD-73	Tertiary Drain	New Drain	2.5-3.5	125.25	0.64-1.25	Ward No. 06	2nd Phase
TD-74	Tertiary Drain	New Drain	2.5-3.5	62.20	0.64-1.25	Ward No. 06	2nd Phase
TD-75	Tertiary Drain	New Drain	2.5-3.5	76.57	0.64-1.25	Ward No. 06	2nd Phase
TD-76	Tertiary Drain	New Drain	2.5-3.5	125.25	0.64-1.25	Ward No. 06	2nd Phase
TD-77	Tertiary Drain	New Drain	2.5-3.5	200.55	0.64-1.25	Ward No. 06	2nd Phase
TD-78	Tertiary Drain	New Drain	2.5-3.5	80.10	0.64-1.25	Ward No. 06	2nd Phase
TD-79	Tertiary Drain	New Drain	2.5-3.5	17.13	0.64-1.25	Ward No. 06	2nd Phase
TD-80	Tertiary Drain	New Drain	2.5-3.5	47.10	0.64-1.25	Ward No. 06	2nd Phase
TD-81	Tertiary Drain	New Drain	2.5-3.5	22.53	0.64-1.25	Ward No. 06	2nd Phase
TD-82	Tertiary Drain	New Drain	2.5-3.5	94.47	0.64-1.25	Ward No. 06	2nd Phase
TD-83	Tertiary Drain	New Drain	2.5-3.5	76.85	0.64-1.25	Ward No. 06	2nd Phase
TD-84	Tertiary Drain	New Drain	2.5-3.5	128.12	0.64-1.25	Ward No. 06	2nd Phase
TD-85	Tertiary Drain	New Drain	2.5-3.5	275.00	0.64-1.25	Ward No. 04	2nd Phase
TD-86	Tertiary Drain	New Drain	2.5-3.5	9.20	0.64-1.25	Ward No. 06	2nd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-87	Tertiary Drain	New Drain	2.5-3.5	287.18	0.64-1.25	Ward No. 04	2nd Phase
TD-88	Tertiary Drain	New Drain	2.5-3.5	1042.63	0.64-1.25	Ward No. 04	2nd Phase
TD-90	Tertiary Drain	New Drain	2.5-3.5	75.95	0.64-1.25	Ward No. 05	2nd Phase
TD-91	Tertiary Drain	New Drain	2.5-3.5	97.90	0.64-1.25	Ward No. 04	2nd Phase
TD-92	Tertiary Drain	New Drain	2.5-3.5	159.13	0.64-1.25	Ward No. 04	2nd Phase
TD-94	Tertiary Drain	New Drain	2.5-3.5	33.24	0.64-1.25	Ward No. 04	2nd Phase
TD-96	Tertiary Drain	New Drain	2.5-3.5	382.10	0.64-1.25	Ward No. 03	2nd Phase
TD-96	Tertiary Drain	New Drain	2.5-3.5	544.15	0.64-1.25	Ward No. 04	2nd Phase
TD-96	Tertiary Drain	New Drain	2.5-3.5	570.94	0.64-1.25	Ward No. 06	2nd Phase
TD-97	Tertiary Drain	New Drain	2.5-3.5	51.50	0.64-1.25	Ward No. 06	2nd Phase
TD-98	Tertiary Drain	New Drain	2.5-3.5	294.18	0.64-1.25	Ward No. 06	2nd Phase
TD-99	Tertiary Drain	New Drain	2.5-3.5	47.58	0.64-1.25	Ward No. 06	2nd Phase
TD-100	Tertiary Drain	New Drain	2.5-3.5	29.21	0.64-1.25	Ward No. 06	2nd Phase
TD-101	Tertiary Drain	New Drain	2.5-3.5	82.67	0.64-1.25	Ward No. 04	2nd Phase
TD-104	Tertiary Drain	New Drain	2.5-3.5	48.06	0.64-1.25	Ward No. 06	2nd Phase
TD-105	Tertiary Drain	New Drain	2.5-3.5	50.58	0.64-1.25	Ward No. 06	2nd Phase
TD-106	Tertiary Drain	New Drain	2.5-3.5	203.15	0.64-1.25	Ward No. 05	2nd Phase
TD-107	Tertiary Drain	New Drain	2.5-3.5	216.83	0.64-1.25	Ward No. 05	2nd Phase
TD-108	Tertiary Drain	New Drain	2.5-3.5	144.05	0.64-1.25	Ward No. 05	2nd Phase
TD-109	Tertiary Drain	New Drain	2.5-3.5	732.85	0.64-1.25	Ward No. 05	2nd Phase
TD-110	Tertiary Drain	New Drain	2.5-3.5	373.59	0.64-1.25	Ward No. 07	2nd Phase
TD-112	Tertiary Drain	New Drain	2.5-3.5	2.72	0.64-1.25	Ward No. 06	2nd Phase
TD-115	Tertiary Drain	New Drain	2.5-3.5	262.57	0.64-1.25	Ward No. 06	2nd Phase
TD-116	Tertiary Drain	New Drain	2.5-3.5	3.97	0.64-1.25	Ward No. 07	2nd Phase
TD-118	Tertiary Drain	New Drain	2.5-3.5	108.72	0.64-1.25	Ward No. 06	2nd Phase
TD-119	Tertiary Drain	New Drain	2.5-3.5	33.79	0.64-1.25	Ward No. 06	2nd Phase
TD-120	Tertiary Drain	New Drain	2.5-3.5	138.51	0.64-1.25	Ward No. 06	2nd Phase
TD-121	Tertiary Drain	New Drain	2.5-3.5	68.37	0.64-1.25	Ward No. 06	2nd Phase
TD-122	Tertiary Drain	New Drain	2.5-3.5	15.11	0.64-1.25	Ward No. 06	2nd Phase
TD-123	Tertiary Drain	New Drain	2.5-3.5	155.13	0.64-1.25	Ward No. 06	2nd Phase
TD-126	Tertiary Drain	New Drain	2.5-3.5	176.75	0.64-1.25	Ward No. 06	2nd Phase
TD-127	Tertiary Drain	New Drain	2.5-3.5	148.29	0.64-1.25	Ward No. 06	2nd Phase
TD-128	Tertiary Drain	New Drain	2.5-3.5	46.97	0.64-1.25	Ward No. 06	2nd Phase
TD-129	Tertiary Drain	New Drain	2.5-3.5	156.30	0.64-1.25	Ward No. 06	2nd Phase
TD-132	Tertiary Drain	New Drain	2.5-3.5	506.11	0.64-1.25	Ward No. 05	2nd Phase
TD-133	Tertiary Drain	New Drain	2.5-3.5	95.22	0.64-1.25	Ward No. 05	2nd Phase
TD-134	Tertiary Drain	New Drain	2.5-3.5	68.03	0.64-1.25	Ward No. 05	2nd Phase
TD-135	Tertiary Drain	New Drain	2.5-3.5	610.70	0.64-1.25	Ward No. 07	2nd Phase
TD-136	Tertiary Drain	New Drain	2.5-3.5	329.25	0.64-1.25	Ward No. 05	2nd Phase
TD-137	Tertiary Drain	New Drain	2.5-3.5	66.52	0.64-1.25	Ward No. 05	2nd Phase
TD-138	Tertiary Drain	New Drain	2.5-3.5	583.32	0.64-1.25	Ward No. 07	2nd Phase
TD-139	Tertiary Drain	New Drain	2.5-3.5	188.36	0.64-1.25	Ward No. 07	2nd Phase
TD-140	Tertiary Drain	New Drain	2.5-3.5	156.54	0.64-1.25	Ward No. 07	2nd Phase
TD-141	Tertiary Drain	New Drain	2.5-3.5	95.98	0.64-1.25	Ward No. 07	2nd Phase
TD-143	Tertiary Drain	New Drain	2.5-3.5	91.46	0.64-1.25	Ward No. 07	2nd Phase
TD-144	Tertiary Drain	New Drain	2.5-3.5	153.65	0.64-1.25	Ward No. 07	2nd Phase
TD-145	Tertiary Drain	New Drain	2.5-3.5	153.41	0.64-1.25	Ward No. 07	2nd Phase
TD-145	Tertiary Drain	New Drain	2.5-3.5	4.47	0.64-1.25	Ward No. 06	2nd Phase
TD-146	Tertiary Drain	New Drain	2.5-3.5	37.64	0.64-1.25	Ward No. 07	2nd Phase
TD-147	Tertiary Drain	New Drain	2.5-3.5	23.57	0.64-1.25	Ward No. 07	2nd Phase
TD-149	Tertiary Drain	New Drain	2.5-3.5	117.73	0.64-1.25	Ward No. 06	2nd Phase
TD-150	Tertiary Drain	New Drain	2.5-3.5	81.74	0.64-1.25	Ward No. 07	2nd Phase
TD-151	Tertiary Drain	New Drain	2.5-3.5	141.78	0.64-1.25	Ward No. 07	2nd Phase
TD-153	Tertiary Drain	New Drain	2.5-3.5	84.71	0.64-1.25	Ward No. 06	2nd Phase
TD-154	Tertiary Drain	New Drain	2.5-3.5	50.24	0.64-1.25	Ward No. 04	2nd Phase
TD-155	Tertiary Drain	New Drain	2.5-3.5	86.54	0.64-1.25	Ward No. 04	2nd Phase
TD-156	Tertiary Drain	New Drain	2.5-3.5	73.66	0.64-1.25	Ward No. 04	2nd Phase
TD-157	Tertiary Drain	New Drain	2.5-3.5	63.81	0.64-1.25	Ward No. 04	2nd Phase
TD-158	Tertiary Drain	New Drain	2.5-3.5	66.79	0.64-1.25	Ward No. 04	2nd Phase
TD-159	Tertiary Drain	New Drain	2.5-3.5	36.99	0.64-1.25	Ward No. 04	2nd Phase
TD-160	Tertiary Drain	New Drain	2.5-3.5	181.88	0.64-1.25	Ward No. 05	2nd Phase
TD-161	Tertiary Drain	New Drain	2.5-3.5	243.57	0.64-1.25	Ward No. 02	2nd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-161	Tertiary Drain	New Drain	2.5-3.5	1741.01	0.64-1.25	Ward No. 04	2nd Phase
TD-161	Tertiary Drain	New Drain	2.5-3.5	260.89	0.64-1.25	Ward No. 06	2nd Phase
TD-162	Tertiary Drain	New Drain	2.5-3.5	366.97	0.64-1.25	Ward No. 05	2nd Phase
TD-163	Tertiary Drain	New Drain	2.5-3.5	176.12	0.64-1.25	Ward No. 05	2nd Phase
TD-164	Tertiary Drain	New Drain	2.5-3.5	61.52	0.64-1.25	Ward No. 05	2nd Phase
TD-165	Tertiary Drain	New Drain	2.5-3.5	17.27	0.64-1.25	Ward No. 04	2nd Phase
TD-166	Tertiary Drain	New Drain	2.5-3.5	1.42	0.64-1.25	Ward No. 05	2nd Phase
TD-167	Tertiary Drain	New Drain	2.5-3.5	165.55	0.64-1.25	Ward No. 04	2nd Phase
TD-168	Tertiary Drain	New Drain	2.5-3.5	99.06	0.64-1.25	Ward No. 04	2nd Phase
TD-169	Tertiary Drain	New Drain	2.5-3.5	29.69	0.64-1.25	Ward No. 04	2nd Phase
TD-170	Tertiary Drain	New Drain	2.5-3.5	27.80	0.64-1.25	Ward No. 04	2nd Phase
TD-171	Tertiary Drain	New Drain	2.5-3.5	20.10	0.64-1.25	Ward No. 04	2nd Phase
TD-172	Tertiary Drain	New Drain	2.5-3.5	55.33	0.64-1.25	Ward No. 04	2nd Phase
TD-173	Tertiary Drain	New Drain	2.5-3.5	50.96	0.64-1.25	Ward No. 04	2nd Phase
TD-174	Tertiary Drain	New Drain	2.5-3.5	129.42	0.64-1.25	Ward No. 05	2nd Phase
TD-175	Tertiary Drain	New Drain	2.5-3.5	96.49	0.64-1.25	Ward No. 05	2nd Phase
TD-177	Tertiary Drain	New Drain	2.5-3.5	243.41	0.64-1.25	Ward No. 05	2nd Phase
TD-180	Tertiary Drain	New Drain	2.5-3.5	92.92	0.64-1.25	Ward No. 05	2nd Phase
TD-181	Tertiary Drain	New Drain	2.5-3.5	109.69	0.64-1.25	Ward No. 05	2nd Phase
TD-182	Tertiary Drain	New Drain	2.5-3.5	924.85	0.64-1.25	Ward No. 05	2nd Phase
TD-184	Tertiary Drain	New Drain	2.5-3.5	329.53	0.64-1.25	Ward No. 05	2nd Phase
TD-185	Tertiary Drain	New Drain	2.5-3.5	168.83	0.64-1.25	Ward No. 05	2nd Phase
TD-186	Tertiary Drain	New Drain	2.5-3.5	134.64	0.64-1.25	Ward No. 05	2nd Phase
TD-187	Tertiary Drain	New Drain	2.5-3.5	45.51	0.64-1.25	Ward No. 05	2nd Phase
TD-188	Tertiary Drain	New Drain	2.5-3.5	37.23	0.64-1.25	Ward No. 07	2nd Phase
TD-188	Tertiary Drain	New Drain	2.5-3.5	1051.25	0.64-1.25	Ward No. 08	2nd Phase
TD-188	Tertiary Drain	New Drain	2.5-3.5	912.50	0.64-1.25	Ward No. 05	2nd Phase
TD-189	Tertiary Drain	New Drain	2.5-3.5	246.39	0.64-1.25	Ward No. 05	2nd Phase
TD-190	Tertiary Drain	New Drain	2.5-3.5	94.41	0.64-1.25	Ward No. 05	2nd Phase
TD-191	Tertiary Drain	New Drain	2.5-3.5	27.39	0.64-1.25	Ward No. 07	2nd Phase
TD-193	Tertiary Drain	New Drain	2.5-3.5	645.13	0.64-1.25	Ward No. 05	2nd Phase
TD-194	Tertiary Drain	New Drain	2.5-3.5	112.19	0.64-1.25	Ward No. 05	2nd Phase
TD-195	Tertiary Drain	New Drain	2.5-3.5	127.78	0.64-1.25	Ward No. 05	2nd Phase
TD-196	Tertiary Drain	New Drain	2.5-3.5	428.06	0.64-1.25	Ward No. 05	2nd Phase
TD-197	Tertiary Drain	New Drain	2.5-3.5	42.35	0.64-1.25	Ward No. 05	2nd Phase
TD-198	Tertiary Drain	New Drain	2.5-3.5	879.37	0.64-1.25	Ward No. 05	2nd Phase
TD-199	Tertiary Drain	New Drain	2.5-3.5	62.76	0.64-1.25	Ward No. 05	2nd Phase
TD-200	Tertiary Drain	New Drain	2.5-3.5	111.53	0.64-1.25	Ward No. 05	2nd Phase
TD-201	Tertiary Drain	New Drain	2.5-3.5	8.42	0.64-1.25	Ward No. 06	2nd Phase
TD-202	Tertiary Drain	New Drain	2.5-3.5	370.13	0.64-1.25	Ward No. 06	2nd Phase
TD-203	Tertiary Drain	New Drain	2.5-3.5	113.55	0.64-1.25	Ward No. 06	2nd Phase
TD-204	Tertiary Drain	New Drain	2.5-3.5	105.84	0.64-1.25	Ward No. 06	2nd Phase
TD-205	Tertiary Drain	New Drain	2.5-3.5	70.04	0.64-1.25	Ward No. 06	2nd Phase
TD-206	Tertiary Drain	New Drain	2.5-3.5	99.26	0.64-1.25	Ward No. 06	2nd Phase
TD-207	Tertiary Drain	New Drain	2.5-3.5	107.59	0.64-1.25	Ward No. 06	2nd Phase
TD-208	Tertiary Drain	New Drain	2.5-3.5	14.73	0.64-1.25	Ward No. 06	2nd Phase
TD-210	Tertiary Drain	New Drain	2.5-3.5	74.34	0.64-1.25	Ward No. 07	2nd Phase
TD-212	Tertiary Drain	New Drain	2.5-3.5	0.63	0.64-1.25	Ward No. 06	2nd Phase
TD-213	Tertiary Drain	New Drain	2.5-3.5	136.94	0.64-1.25	Ward No. 07	2nd Phase
TD-214	Tertiary Drain	New Drain	2.5-3.5	0.24	0.64-1.25	Ward No. 06	2nd Phase
TD-215	Tertiary Drain	New Drain	2.5-3.5	139.02	0.64-1.25	Ward No. 07	2nd Phase
TD-216	Tertiary Drain	New Drain	2.5-3.5	49.49	0.64-1.25	Ward No. 07	2nd Phase
TD-217	Tertiary Drain	New Drain	2.5-3.5	0.41	0.64-1.25	Ward No. 06	2nd Phase
TD-218	Tertiary Drain	New Drain	2.5-3.5	441.43	0.64-1.25	Ward No. 06	2nd Phase
TD-219	Tertiary Drain	New Drain	2.5-3.5	40.01	0.64-1.25	Ward No. 06	2nd Phase
TD-220	Tertiary Drain	New Drain	2.5-3.5	40.07	0.64-1.25	Ward No. 07	2nd Phase
TD-222	Tertiary Drain	New Drain	2.5-3.5	203.14	0.64-1.25	Ward No. 06	2nd Phase
TD-223	Tertiary Drain	New Drain	2.5-3.5	88.26	0.64-1.25	Ward No. 06	2nd Phase
TD-224	Tertiary Drain	New Drain	2.5-3.5	71.69	0.64-1.25	Ward No. 06	2nd Phase
TD-225	Tertiary Drain	New Drain	2.5-3.5	68.89	0.64-1.25	Ward No. 06	2nd Phase
SD-11	Secondary Drain	New Drain	3.50-4.50	212.13	1.25-3.00	Ward No. 08	2nd Phase
SD-11	Secondary Drain	New Drain	3.50-4.50	882.98	1.25-3.00	Ward No. 09	2nd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
SD-12	Secondary Drain	New Drain	3.50-4.50	1354.75	1.25-3.00	Ward No. 01	2nd Phase
SD-13	Secondary Drain	New Drain	3.50-4.50	146.47	1.25-3.00	Ward No. 02	2nd Phase
SD-13	Secondary Drain	New Drain	3.50-4.50	410.04	1.25-3.00	Ward No. 04	2nd Phase
SD-14	Secondary Drain	New Drain	3.50-4.50	832.82	1.25-3.00	Ward No. 07	2nd Phase
SD-14	Secondary Drain	New Drain	3.50-4.50	1503.92	1.25-3.00	Ward No. 08	2nd Phase
SD-15	Secondary Drain	New Drain	3.50-4.50	927.49	1.25-3.00	Ward No. 09	2nd Phase
SD-16	Secondary Drain	New Drain	3.50-4.50	669.63	1.25-3.00	Ward No. 07	2nd Phase
SD-16	Secondary Drain	New Drain	3.50-4.50	2092.13	1.25-3.00	Ward No. 09	2nd Phase
SD-17	Secondary Drain	New Drain	3.50-4.50	1656.15	1.25-3.00	Ward No. 09	2nd Phase
SD-18	Secondary Drain	New Drain	3.50-4.50	1.04	1.25-3.00	Ward No. 05	2nd Phase
SD-19	Secondary Drain	New Drain	3.50-4.50	2.56	1.25-3.00	Ward No. 05	2nd Phase
SD-20	Secondary Drain	New Drain	3.50-4.50	2.62	1.25-3.00	Ward No. 05	2nd Phase
SD-21	Secondary Drain	New Drain	3.50-4.50	177.81	1.25-3.00	Ward No. 07	2nd Phase
TD-226	Tertiary Drain	New Drain	2.5-3.5	337.89	0.64-1.25	Ward No. 06	3rd Phase
TD-227	Tertiary Drain	New Drain	2.5-3.5	181.63	0.64-1.25	Ward No. 07	3rd Phase
TD-228	Tertiary Drain	New Drain	2.5-3.5	304.86	0.64-1.25	Ward No. 06	3rd Phase
TD-229	Tertiary Drain	New Drain	2.5-3.5	221.75	0.64-1.25	Ward No. 06	3rd Phase
TD-230	Tertiary Drain	New Drain	2.5-3.5	258.51	0.64-1.25	Ward No. 06	3rd Phase
TD-231	Tertiary Drain	New Drain	2.5-3.5	176.34	0.64-1.25	Ward No. 06	3rd Phase
TD-232	Tertiary Drain	New Drain	2.5-3.5	533.69	0.64-1.25	Ward No. 06	3rd Phase
TD-234	Tertiary Drain	New Drain	2.5-3.5	1.16	0.64-1.25	Ward No. 07	3rd Phase
TD-236	Tertiary Drain	New Drain	2.5-3.5	84.77	0.64-1.25	Ward No. 06	3rd Phase
TD-237	Tertiary Drain	New Drain	2.5-3.5	91.81	0.64-1.25	Ward No. 07	3rd Phase
TD-238	Tertiary Drain	New Drain	2.5-3.5	387.86	0.64-1.25	Ward No. 07	3rd Phase
TD-240	Tertiary Drain	New Drain	2.5-3.5	42.45	0.64-1.25	Ward No. 06	3rd Phase
TD-242	Tertiary Drain	New Drain	2.5-3.5	1.74	0.64-1.25	Ward No. 06	3rd Phase
TD-243	Tertiary Drain	New Drain	2.5-3.5	59.48	0.64-1.25	Ward No. 05	3rd Phase
TD-244	Tertiary Drain	New Drain	2.5-3.5	43.24	0.64-1.25	Ward No. 05	3rd Phase
TD-247	Tertiary Drain	New Drain	2.5-3.5	360.64	0.64-1.25	Ward No. 07	3rd Phase
TD-248	Tertiary Drain	New Drain	2.5-3.5	28.56	0.64-1.25	Ward No. 07	3rd Phase
TD-254	Tertiary Drain	New Drain	2.5-3.5	621.35	0.64-1.25	Ward No. 07	3rd Phase
TD-254	Tertiary Drain	New Drain	2.5-3.5	31.93	0.64-1.25	Ward No. 06	3rd Phase
TD-256	Tertiary Drain	New Drain	2.5-3.5	0.29	0.64-1.25	Ward No. 06	3rd Phase
TD-257	Tertiary Drain	New Drain	2.5-3.5	47.56	0.64-1.25	Ward No. 07	3rd Phase
TD-259	Tertiary Drain	New Drain	2.5-3.5	55.89	0.64-1.25	Ward No. 07	3rd Phase
TD-260	Tertiary Drain	New Drain	2.5-3.5	29.27	0.64-1.25	Ward No. 07	3rd Phase
TD-263	Tertiary Drain	New Drain	2.5-3.5	519.41	0.64-1.25	Ward No. 07	3rd Phase
TD-264	Tertiary Drain	New Drain	2.5-3.5	197.04	0.64-1.25	Ward No. 07	3rd Phase
TD-265	Tertiary Drain	New Drain	2.5-3.5	30.22	0.64-1.25	Ward No. 07	3rd Phase
TD-267	Tertiary Drain	New Drain	2.5-3.5	112.22	0.64-1.25	Ward No. 07	3rd Phase
TD-268	Tertiary Drain	New Drain	2.5-3.5	20.02	0.64-1.25	Ward No. 07	3rd Phase
TD-269	Tertiary Drain	New Drain	2.5-3.5	256.43	0.64-1.25	Ward No. 07	3rd Phase
TD-270	Tertiary Drain	New Drain	2.5-3.5	81.83	0.64-1.25	Ward No. 07	3rd Phase
TD-271	Tertiary Drain	New Drain	2.5-3.5	85.07	0.64-1.25	Ward No. 07	3rd Phase
TD-275	Tertiary Drain	New Drain	2.5-3.5	1018.52	0.64-1.25	Ward No. 07	3rd Phase
TD-277	Tertiary Drain	New Drain	2.5-3.5	8.49	0.64-1.25	Ward No. 05	3rd Phase
TD-278	Tertiary Drain	New Drain	2.5-3.5	239.25	0.64-1.25	Ward No. 07	3rd Phase
TD-279	Tertiary Drain	New Drain	2.5-3.5	97.79	0.64-1.25	Ward No. 07	3rd Phase
TD-280	Tertiary Drain	New Drain	2.5-3.5	60.14	0.64-1.25	Ward No. 07	3rd Phase
TD-281	Tertiary Drain	New Drain	2.5-3.5	76.46	0.64-1.25	Ward No. 07	3rd Phase
TD-282	Tertiary Drain	New Drain	2.5-3.5	66.40	0.64-1.25	Ward No. 07	3rd Phase
TD-283	Tertiary Drain	New Drain	2.5-3.5	84.74	0.64-1.25	Ward No. 07	3rd Phase
TD-284	Tertiary Drain	New Drain	2.5-3.5	502.60	0.64-1.25	Ward No. 07	3rd Phase
TD-285	Tertiary Drain	New Drain	2.5-3.5	670.07	0.64-1.25	Ward No. 09	3rd Phase
TD-286	Tertiary Drain	New Drain	2.5-3.5	490.29	0.64-1.25	Ward No. 09	3rd Phase
TD-287	Tertiary Drain	New Drain	2.5-3.5	195.74	0.64-1.25	Ward No. 09	3rd Phase
TD-288	Tertiary Drain	New Drain	2.5-3.5	506.43	0.64-1.25	Ward No. 09	3rd Phase
TD-289	Tertiary Drain	New Drain	2.5-3.5	54.90	0.64-1.25	Ward No. 09	3rd Phase
TD-290	Tertiary Drain	New Drain	2.5-3.5	276.11	0.64-1.25	Ward No. 09	3rd Phase
TD-291	Tertiary Drain	New Drain	2.5-3.5	101.61	0.64-1.25	Ward No. 01	3rd Phase
TD-292	Tertiary Drain	New Drain	2.5-3.5	215.53	0.64-1.25	Ward No. 01	3rd Phase
TD-293	Tertiary Drain	New Drain	2.5-3.5	1546.91	0.64-1.25	Ward No. 03	3rd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-293	Tertiary Drain	New Drain	2.5-3.5	509.76	0.64-1.25	Ward No. 01	3rd Phase
TD-294	Tertiary Drain	New Drain	2.5-3.5	209.43	0.64-1.25	Ward No. 01	3rd Phase
TD-295	Tertiary Drain	New Drain	2.5-3.5	47.53	0.64-1.25	Ward No. 01	3rd Phase
TD-296	Tertiary Drain	New Drain	2.5-3.5	986.12	0.64-1.25	Ward No. 01	3rd Phase
TD-297	Tertiary Drain	New Drain	2.5-3.5	201.67	0.64-1.25	Ward No. 01	3rd Phase
TD-298	Tertiary Drain	New Drain	2.5-3.5	71.37	0.64-1.25	Ward No. 01	3rd Phase
TD-299	Tertiary Drain	New Drain	2.5-3.5	68.56	0.64-1.25	Ward No. 01	3rd Phase
TD-300	Tertiary Drain	New Drain	2.5-3.5	913.56	0.64-1.25	Ward No. 01	3rd Phase
TD-301	Tertiary Drain	New Drain	2.5-3.5	174.03	0.64-1.25	Ward No. 01	3rd Phase
TD-302	Tertiary Drain	New Drain	2.5-3.5	42.11	0.64-1.25	Ward No. 01	3rd Phase
TD-303	Tertiary Drain	New Drain	2.5-3.5	126.18	0.64-1.25	Ward No. 02	3rd Phase
TD-307	Tertiary Drain	New Drain	2.5-3.5	315.59	0.64-1.25	Ward No. 01	3rd Phase
TD-308	Tertiary Drain	New Drain	2.5-3.5	735.67	0.64-1.25	Ward No. 01	3rd Phase
TD-309	Tertiary Drain	New Drain	2.5-3.5	90.27	0.64-1.25	Ward No. 01	3rd Phase
TD-310	Tertiary Drain	New Drain	2.5-3.5	239.52	0.64-1.25	Ward No. 01	3rd Phase
TD-311	Tertiary Drain	New Drain	2.5-3.5	57.37	0.64-1.25	Ward No. 01	3rd Phase
TD-312	Tertiary Drain	New Drain	2.5-3.5	81.91	0.64-1.25	Ward No. 01	3rd Phase
TD-313	Tertiary Drain	New Drain	2.5-3.5	81.29	0.64-1.25	Ward No. 01	3rd Phase
TD-314	Tertiary Drain	New Drain	2.5-3.5	69.58	0.64-1.25	Ward No. 01	3rd Phase
TD-315	Tertiary Drain	New Drain	2.5-3.5	91.49	0.64-1.25	Ward No. 01	3rd Phase
TD-316	Tertiary Drain	New Drain	2.5-3.5	151.52	0.64-1.25	Ward No. 01	3rd Phase
TD-317	Tertiary Drain	New Drain	2.5-3.5	460.19	0.64-1.25	Ward No. 01	3rd Phase
TD-318	Tertiary Drain	New Drain	2.5-3.5	278.76	0.64-1.25	Ward No. 01	3rd Phase
TD-320	Tertiary Drain	New Drain	2.5-3.5	209.87	0.64-1.25	Ward No. 01	3rd Phase
TD-321	Tertiary Drain	New Drain	2.5-3.5	14.98	0.64-1.25	Ward No. 03	3rd Phase
TD-322	Tertiary Drain	New Drain	2.5-3.5	291.92	0.64-1.25	Ward No. 03	3rd Phase
TD-323	Tertiary Drain	New Drain	2.5-3.5	73.75	0.64-1.25	Ward No. 03	3rd Phase
TD-324	Tertiary Drain	New Drain	2.5-3.5	70.79	0.64-1.25	Ward No. 03	3rd Phase
TD-325	Tertiary Drain	New Drain	2.5-3.5	78.42	0.64-1.25	Ward No. 03	3rd Phase
TD-326	Tertiary Drain	New Drain	2.5-3.5	209.51	0.64-1.25	Ward No. 03	3rd Phase
TD-327	Tertiary Drain	New Drain	2.5-3.5	97.64	0.64-1.25	Ward No. 03	3rd Phase
TD-328	Tertiary Drain	New Drain	2.5-3.5	105.85	0.64-1.25	Ward No. 03	3rd Phase
TD-329	Tertiary Drain	New Drain	2.5-3.5	220.11	0.64-1.25	Ward No. 03	3rd Phase
TD-330	Tertiary Drain	New Drain	2.5-3.5	66.56	0.64-1.25	Ward No. 03	3rd Phase
TD-332	Tertiary Drain	New Drain	2.5-3.5	283.13	0.64-1.25	Ward No. 02	3rd Phase
TD-333	Tertiary Drain	New Drain	2.5-3.5	118.86	0.64-1.25	Ward No. 01	3rd Phase
TD-334	Tertiary Drain	New Drain	2.5-3.5	308.83	0.64-1.25	Ward No. 01	3rd Phase
TD-335	Tertiary Drain	New Drain	2.5-3.5	123.93	0.64-1.25	Ward No. 01	3rd Phase
TD-336	Tertiary Drain	New Drain	2.5-3.5	127.38	0.64-1.25	Ward No. 01	3rd Phase
TD-337	Tertiary Drain	New Drain	2.5-3.5	25.35	0.64-1.25	Ward No. 03	3rd Phase
TD-339	Tertiary Drain	New Drain	2.5-3.5	77.32	0.64-1.25	Ward No. 01	3rd Phase
TD-340	Tertiary Drain	New Drain	2.5-3.5	107.78	0.64-1.25	Ward No. 01	3rd Phase
TD-341	Tertiary Drain	New Drain	2.5-3.5	917.50	0.64-1.25	Ward No. 01	3rd Phase
TD-343	Tertiary Drain	New Drain	2.5-3.5	5.94	0.64-1.25	Ward No. 03	3rd Phase
TD-343	Tertiary Drain	New Drain	2.5-3.5	1399.69	0.64-1.25	Ward No. 01	3rd Phase
TD-344	Tertiary Drain	New Drain	2.5-3.5	26.24	0.64-1.25	Ward No. 01	3rd Phase
TD-345	Tertiary Drain	New Drain	2.5-3.5	251.58	0.64-1.25	Ward No. 01	3rd Phase
TD-346	Tertiary Drain	New Drain	2.5-3.5	178.40	0.64-1.25	Ward No. 01	3rd Phase
TD-347	Tertiary Drain	New Drain	2.5-3.5	831.83	0.64-1.25	Ward No. 03	3rd Phase
TD-348	Tertiary Drain	New Drain	2.5-3.5	123.80	0.64-1.25	Ward No. 03	3rd Phase
TD-349	Tertiary Drain	New Drain	2.5-3.5	277.06	0.64-1.25	Ward No. 03	3rd Phase
TD-350	Tertiary Drain	New Drain	2.5-3.5	94.86	0.64-1.25	Ward No. 03	3rd Phase
TD-351	Tertiary Drain	New Drain	2.5-3.5	319.50	0.64-1.25	Ward No. 03	3rd Phase
TD-351	Tertiary Drain	New Drain	2.5-3.5	246.77	0.64-1.25	Ward No. 01	3rd Phase
TD-352	Tertiary Drain	New Drain	2.5-3.5	590.84	0.64-1.25	Ward No. 02	3rd Phase
TD-353	Tertiary Drain	New Drain	2.5-3.5	174.65	0.64-1.25	Ward No. 02	3rd Phase
TD-354	Tertiary Drain	New Drain	2.5-3.5	191.58	0.64-1.25	Ward No. 01	3rd Phase
TD-355	Tertiary Drain	New Drain	2.5-3.5	38.46	0.64-1.25	Ward No. 01	3rd Phase
TD-356	Tertiary Drain	New Drain	2.5-3.5	154.99	0.64-1.25	Ward No. 01	3rd Phase
TD-357	Tertiary Drain	New Drain	2.5-3.5	1177.09	0.64-1.25	Ward No. 01	3rd Phase
TD-358	Tertiary Drain	New Drain	2.5-3.5	181.55	0.64-1.25	Ward No. 01	3rd Phase
TD-359	Tertiary Drain	New Drain	2.5-3.5	24.70	0.64-1.25	Ward No. 01	3rd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-360	Tertiary Drain	New Drain	2.5-3.5	75.36	0.64-1.25	Ward No. 01	3rd Phase
TD-362	Tertiary Drain	New Drain	2.5-3.5	175.95	0.64-1.25	Ward No. 02	3rd Phase
TD-362	Tertiary Drain	New Drain	2.5-3.5	70.82	0.64-1.25	Ward No. 01	3rd Phase
TD-363	Tertiary Drain	New Drain	2.5-3.5	121.16	0.64-1.25	Ward No. 01	3rd Phase
TD-364	Tertiary Drain	New Drain	2.5-3.5	86.10	0.64-1.25	Ward No. 02	3rd Phase
TD-366	Tertiary Drain	New Drain	2.5-3.5	62.41	0.64-1.25	Ward No. 01	3rd Phase
TD-367	Tertiary Drain	New Drain	2.5-3.5	126.62	0.64-1.25	Ward No. 02	3rd Phase
TD-368	Tertiary Drain	New Drain	2.5-3.5	152.98	0.64-1.25	Ward No. 01	3rd Phase
TD-369	Tertiary Drain	New Drain	2.5-3.5	30.85	0.64-1.25	Ward No. 01	3rd Phase
TD-372	Tertiary Drain	New Drain	2.5-3.5	686.97	0.64-1.25	Ward No. 04	3rd Phase
TD-373	Tertiary Drain	New Drain	2.5-3.5	52.95	0.64-1.25	Ward No. 01	3rd Phase
TD-374	Tertiary Drain	New Drain	2.5-3.5	72.31	0.64-1.25	Ward No. 01	3rd Phase
TD-375	Tertiary Drain	New Drain	2.5-3.5	208.83	0.64-1.25	Ward No. 01	3rd Phase
TD-376	Tertiary Drain	New Drain	2.5-3.5	171.33	0.64-1.25	Ward No. 01	3rd Phase
TD-377	Tertiary Drain	New Drain	2.5-3.5	166.22	0.64-1.25	Ward No. 01	3rd Phase
TD-378	Tertiary Drain	New Drain	2.5-3.5	25.54	0.64-1.25	Ward No. 01	3rd Phase
TD-380	Tertiary Drain	New Drain	2.5-3.5	1.05	0.64-1.25	Ward No. 02	3rd Phase
TD-382	Tertiary Drain	New Drain	2.5-3.5	65.28	0.64-1.25	Ward No. 01	3rd Phase
TD-383	Tertiary Drain	New Drain	2.5-3.5	25.30	0.64-1.25	Ward No. 01	3rd Phase
TD-384	Tertiary Drain	New Drain	2.5-3.5	199.49	0.64-1.25	Ward No. 01	3rd Phase
TD-386	Tertiary Drain	New Drain	2.5-3.5	34.10	0.64-1.25	Ward No. 01	3rd Phase
TD-387	Tertiary Drain	New Drain	2.5-3.5	12.17	0.64-1.25	Ward No. 01	3rd Phase
TD-388	Tertiary Drain	New Drain	2.5-3.5	181.41	0.64-1.25	Ward No. 01	3rd Phase
TD-389	Tertiary Drain	New Drain	2.5-3.5	163.52	0.64-1.25	Ward No. 03	3rd Phase
TD-390	Tertiary Drain	New Drain	2.5-3.5	42.86	0.64-1.25	Ward No. 03	3rd Phase
TD-391	Tertiary Drain	New Drain	2.5-3.5	669.92	0.64-1.25	Ward No. 03	3rd Phase
TD-394	Tertiary Drain	New Drain	2.5-3.5	215.26	0.64-1.25	Ward No. 03	3rd Phase
TD-395	Tertiary Drain	New Drain	2.5-3.5	50.57	0.64-1.25	Ward No. 02	3rd Phase
TD-396	Tertiary Drain	New Drain	2.5-3.5	165.23	0.64-1.25	Ward No. 03	3rd Phase
TD-398	Tertiary Drain	New Drain	2.5-3.5	9.29	0.64-1.25	Ward No. 02	3rd Phase
TD-399	Tertiary Drain	New Drain	2.5-3.5	0.09	0.64-1.25	Ward No. 03	3rd Phase
TD-400	Tertiary Drain	New Drain	2.5-3.5	0.01	0.64-1.25	Ward No. 03	3rd Phase
TD-401	Tertiary Drain	New Drain	2.5-3.5	816.14	0.64-1.25	Ward No. 02	3rd Phase
TD-402	Tertiary Drain	New Drain	2.5-3.5	208.90	0.64-1.25	Ward No. 03	3rd Phase
TD-402	Tertiary Drain	New Drain	2.5-3.5	192.79	0.64-1.25	Ward No. 02	3rd Phase
TD-403	Tertiary Drain	New Drain	2.5-3.5	834.28	0.64-1.25	Ward No. 02	3rd Phase
TD-404	Tertiary Drain	New Drain	2.5-3.5	275.65	0.64-1.25	Ward No. 03	3rd Phase
TD-406	Tertiary Drain	New Drain	2.5-3.5	298.19	0.64-1.25	Ward No. 02	3rd Phase
TD-407	Tertiary Drain	New Drain	2.5-3.5	71.22	0.64-1.25	Ward No. 03	3rd Phase
TD-408	Tertiary Drain	New Drain	2.5-3.5	176.23	0.64-1.25	Ward No. 03	3rd Phase
TD-409	Tertiary Drain	New Drain	2.5-3.5	539.57	0.64-1.25	Ward No. 03	3rd Phase
TD-411	Tertiary Drain	New Drain	2.5-3.5	0.05	0.64-1.25	Ward No. 02	3rd Phase
TD-412	Tertiary Drain	New Drain	2.5-3.5	213.69	0.64-1.25	Ward No. 03	3rd Phase
TD-413	Tertiary Drain	New Drain	2.5-3.5	261.50	0.64-1.25	Ward No. 02	3rd Phase
TD-415	Tertiary Drain	New Drain	2.5-3.5	423.82	0.64-1.25	Ward No. 02	3rd Phase
TD-416	Tertiary Drain	New Drain	2.5-3.5	59.88	0.64-1.25	Ward No. 04	3rd Phase
TD-417	Tertiary Drain	New Drain	2.5-3.5	1.83	0.64-1.25	Ward No. 02	3rd Phase
TD-418	Tertiary Drain	New Drain	2.5-3.5	1.09	0.64-1.25	Ward No. 02	3rd Phase
TD-418	Tertiary Drain	New Drain	2.5-3.5	143.71	0.64-1.25	Ward No. 04	3rd Phase
TD-419	Tertiary Drain	New Drain	2.5-3.5	165.91	0.64-1.25	Ward No. 04	3rd Phase
TD-420	Tertiary Drain	New Drain	2.5-3.5	141.48	0.64-1.25	Ward No. 04	3rd Phase
TD-421	Tertiary Drain	New Drain	2.5-3.5	93.57	0.64-1.25	Ward No. 02	3rd Phase
TD-424	Tertiary Drain	New Drain	2.5-3.5	69.25	0.64-1.25	Ward No. 02	3rd Phase
TD-426	Tertiary Drain	New Drain	2.5-3.5	4.39	0.64-1.25	Ward No. 04	3rd Phase
TD-427	Tertiary Drain	New Drain	2.5-3.5	61.85	0.64-1.25	Ward No. 05	3rd Phase
TD-428	Tertiary Drain	New Drain	2.5-3.5	58.12	0.64-1.25	Ward No. 05	3rd Phase
TD-429	Tertiary Drain	New Drain	2.5-3.5	53.64	0.64-1.25	Ward No. 05	3rd Phase
TD-430	Tertiary Drain	New Drain	2.5-3.5	52.59	0.64-1.25	Ward No. 05	3rd Phase
TD-433	Tertiary Drain	New Drain	2.5-3.5	207.92	0.64-1.25	Ward No. 07	3rd Phase
TD-436	Tertiary Drain	New Drain	2.5-3.5	236.82	0.64-1.25	Ward No. 05	3rd Phase
TD-437	Tertiary Drain	New Drain	2.5-3.5	1.82	0.64-1.25	Ward No. 07	3rd Phase
TD-438	Tertiary Drain	New Drain	2.5-3.5	54.29	0.64-1.25	Ward No. 08	3rd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-439	Tertiary Drain	New Drain	2.5-3.5	3.27	0.64-1.25	Ward No. 07	3rd Phase
TD-440	Tertiary Drain	New Drain	2.5-3.5	5.76	0.64-1.25	Ward No. 07	3rd Phase
TD-442	Tertiary Drain	New Drain	2.5-3.5	305.67	0.64-1.25	Ward No. 08	3rd Phase
TD-443	Tertiary Drain	New Drain	2.5-3.5	5.71	0.64-1.25	Ward No. 07	3rd Phase
TD-444	Tertiary Drain	New Drain	2.5-3.5	234.91	0.64-1.25	Ward No. 08	3rd Phase
TD-446	Tertiary Drain	New Drain	2.5-3.5	0.96	0.64-1.25	Ward No. 05	3rd Phase
TD-447	Tertiary Drain	New Drain	2.5-3.5	607.46	0.64-1.25	Ward No. 07	3rd Phase
TD-448	Tertiary Drain	New Drain	2.5-3.5	462.42	0.64-1.25	Ward No. 07	3rd Phase
TD-449	Tertiary Drain	New Drain	2.5-3.5	248.96	0.64-1.25	Ward No. 07	3rd Phase
TD-450	Tertiary Drain	New Drain	2.5-3.5	616.10	0.64-1.25	Ward No. 07	3rd Phase
TD-451	Tertiary Drain	New Drain	2.5-3.5	79.38	0.64-1.25	Ward No. 05	3rd Phase
TD-452	Tertiary Drain	New Drain	2.5-3.5	198.04	0.64-1.25	Ward No. 08	3rd Phase
TD-454	Tertiary Drain	New Drain	2.5-3.5	135.64	0.64-1.25	Ward No. 05	3rd Phase
TD-455	Tertiary Drain	New Drain	2.5-3.5	384.86	0.64-1.25	Ward No. 05	3rd Phase
TD-457	Tertiary Drain	New Drain	2.5-3.5	452.63	0.64-1.25	Ward No. 08	3rd Phase
TD-458	Tertiary Drain	New Drain	2.5-3.5	254.50	0.64-1.25	Ward No. 08	3rd Phase
TD-459	Tertiary Drain	New Drain	2.5-3.5	51.86	0.64-1.25	Ward No. 08	3rd Phase
TD-460	Tertiary Drain	New Drain	2.5-3.5	188.03	0.64-1.25	Ward No. 05	3rd Phase
TD-461	Tertiary Drain	New Drain	2.5-3.5	76.78	0.64-1.25	Ward No. 05	3rd Phase
TD-462	Tertiary Drain	New Drain	2.5-3.5	0.32	0.64-1.25	Ward No. 08	3rd Phase
TD-464	Tertiary Drain	New Drain	2.5-3.5	158.48	0.64-1.25	Ward No. 05	3rd Phase
TD-465	Tertiary Drain	New Drain	2.5-3.5	29.39	0.64-1.25	Ward No. 08	3rd Phase
TD-466	Tertiary Drain	New Drain	2.5-3.5	78.98	0.64-1.25	Ward No. 08	3rd Phase
TD-467	Tertiary Drain	New Drain	2.5-3.5	50.29	0.64-1.25	Ward No. 08	3rd Phase
TD-468	Tertiary Drain	New Drain	2.5-3.5	849.60	0.64-1.25	Ward No. 08	3rd Phase
TD-470	Tertiary Drain	New Drain	2.5-3.5	278.46	0.64-1.25	Ward No. 08	3rd Phase
TD-471	Tertiary Drain	New Drain	2.5-3.5	459.11	0.64-1.25	Ward No. 08	3rd Phase
TD-472	Tertiary Drain	New Drain	2.5-3.5	47.14	0.64-1.25	Ward No. 08	3rd Phase
TD-473	Tertiary Drain	New Drain	2.5-3.5	263.14	0.64-1.25	Ward No. 08	3rd Phase
TD-475	Tertiary Drain	New Drain	2.5-3.5	144.81	0.64-1.25	Ward No. 07	3rd Phase
TD-476	Tertiary Drain	New Drain	2.5-3.5	285.07	0.64-1.25	Ward No. 07	3rd Phase
TD-478	Tertiary Drain	New Drain	2.5-3.5	79.60	0.64-1.25	Ward No. 07	3rd Phase
TD-479	Tertiary Drain	New Drain	2.5-3.5	216.67	0.64-1.25	Ward No. 07	3rd Phase
TD-480	Tertiary Drain	New Drain	2.5-3.5	583.55	0.64-1.25	Ward No. 09	3rd Phase
TD-481	Tertiary Drain	New Drain	2.5-3.5	461.57	0.64-1.25	Ward No. 07	3rd Phase
TD-483	Tertiary Drain	New Drain	2.5-3.5	336.59	0.64-1.25	Ward No. 09	3rd Phase
TD-484	Tertiary Drain	New Drain	2.5-3.5	196.66	0.64-1.25	Ward No. 07	3rd Phase
TD-485	Tertiary Drain	New Drain	2.5-3.5	193.52	0.64-1.25	Ward No. 07	3rd Phase
TD-486	Tertiary Drain	New Drain	2.5-3.5	48.29	0.64-1.25	Ward No. 07	3rd Phase
TD-487	Tertiary Drain	New Drain	2.5-3.5	65.13	0.64-1.25	Ward No. 08	3rd Phase
TD-488	Tertiary Drain	New Drain	2.5-3.5	13.63	0.64-1.25	Ward No. 09	3rd Phase
TD-489	Tertiary Drain	New Drain	2.5-3.5	3.21	0.64-1.25	Ward No. 07	3rd Phase
TD-492	Tertiary Drain	New Drain	2.5-3.5	82.46	0.64-1.25	Ward No. 05	3rd Phase
TD-493	Tertiary Drain	New Drain	2.5-3.5	1.34	0.64-1.25	Ward No. 08	3rd Phase
TD-494	Tertiary Drain	New Drain	2.5-3.5	230.34	0.64-1.25	Ward No. 08	3rd Phase
TD-495	Tertiary Drain	New Drain	2.5-3.5	290.93	0.64-1.25	Ward No. 08	3rd Phase
TD-496	Tertiary Drain	New Drain	2.5-3.5	318.76	0.64-1.25	Ward No. 08	3rd Phase
TD-496	Tertiary Drain	New Drain	2.5-3.5	0.96	0.64-1.25	Ward No. 09	3rd Phase
TD-497	Tertiary Drain	New Drain	2.5-3.5	161.23	0.64-1.25	Ward No. 08	3rd Phase
TD-499	Tertiary Drain	New Drain	2.5-3.5	45.04	0.64-1.25	Ward No. 08	3rd Phase
TD-500	Tertiary Drain	New Drain	2.5-3.5	862.12	0.64-1.25	Ward No. 08	3rd Phase
TD-500	Tertiary Drain	New Drain	2.5-3.5	98.62	0.64-1.25	Ward No. 05	3rd Phase
TD-503	Tertiary Drain	New Drain	2.5-3.5	57.21	0.64-1.25	Ward No. 05	3rd Phase
TD-504	Tertiary Drain	New Drain	2.5-3.5	432.64	0.64-1.25	Ward No. 08	3rd Phase
TD-505	Tertiary Drain	New Drain	2.5-3.5	662.54	0.64-1.25	Ward No. 08	3rd Phase
TD-507	Tertiary Drain	New Drain	2.5-3.5	469.36	0.64-1.25	Ward No. 08	3rd Phase
TD-508	Tertiary Drain	New Drain	2.5-3.5	119.73	0.64-1.25	Ward No. 08	3rd Phase
TD-509	Tertiary Drain	New Drain	2.5-3.5	191.96	0.64-1.25	Ward No. 08	3rd Phase
TD-510	Tertiary Drain	New Drain	2.5-3.5	215.86	0.64-1.25	Ward No. 08	3rd Phase
TD-511	Tertiary Drain	New Drain	2.5-3.5	191.76	0.64-1.25	Ward No. 08	3rd Phase
TD-512	Tertiary Drain	New Drain	2.5-3.5	77.27	0.64-1.25	Ward No. 08	3rd Phase
TD-513	Tertiary Drain	New Drain	2.5-3.5	214.31	0.64-1.25	Ward No. 08	3rd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-514	Tertiary Drain	New Drain	2.5-3.5	279.81	0.64-1.25	Ward No. 09	3rd Phase
TD-515	Tertiary Drain	New Drain	2.5-3.5	131.20	0.64-1.25	Ward No. 09	3rd Phase
TD-516	Tertiary Drain	New Drain	2.5-3.5	71.61	0.64-1.25	Ward No. 09	3rd Phase
TD-519	Tertiary Drain	New Drain	2.5-3.5	368.17	0.64-1.25	Ward No. 09	3rd Phase
TD-520	Tertiary Drain	New Drain	2.5-3.5	389.05	0.64-1.25	Ward No. 09	3rd Phase
TD-521	Tertiary Drain	New Drain	2.5-3.5	90.24	0.64-1.25	Ward No. 09	3rd Phase
TD-522	Tertiary Drain	New Drain	2.5-3.5	45.01	0.64-1.25	Ward No. 09	3rd Phase
TD-523	Tertiary Drain	New Drain	2.5-3.5	92.06	0.64-1.25	Ward No. 09	3rd Phase
TD-524	Tertiary Drain	New Drain	2.5-3.5	450.70	0.64-1.25	Ward No. 09	3rd Phase
TD-527	Tertiary Drain	New Drain	2.5-3.5	328.44	0.64-1.25	Ward No. 09	3rd Phase
TD-528	Tertiary Drain	New Drain	2.5-3.5	505.61	0.64-1.25	Ward No. 09	3rd Phase
TD-529	Tertiary Drain	New Drain	2.5-3.5	455.72	0.64-1.25	Ward No. 09	3rd Phase
TD-531	Tertiary Drain	New Drain	2.5-3.5	57.04	0.64-1.25	Ward No. 09	3rd Phase
TD-532	Tertiary Drain	New Drain	2.5-3.5	113.09	0.64-1.25	Ward No. 08	3rd Phase
TD-533	Tertiary Drain	New Drain	2.5-3.5	2.27	0.64-1.25	Ward No. 09	3rd Phase
TD-534	Tertiary Drain	New Drain	2.5-3.5	478.53	0.64-1.25	Ward No. 08	3rd Phase
TD-536	Tertiary Drain	New Drain	2.5-3.5	198.92	0.64-1.25	Ward No. 08	3rd Phase
TD-538	Tertiary Drain	New Drain	2.5-3.5	85.53	0.64-1.25	Ward No. 09	3rd Phase
TD-539	Tertiary Drain	New Drain	2.5-3.5	4.60	0.64-1.25	Ward No. 08	3rd Phase
TD-541	Tertiary Drain	New Drain	2.5-3.5	48.70	0.64-1.25	Ward No. 09	3rd Phase
TD-542	Tertiary Drain	New Drain	2.5-3.5	214.78	0.64-1.25	Ward No. 09	3rd Phase
TD-543	Tertiary Drain	New Drain	2.5-3.5	25.17	0.64-1.25	Ward No. 08	3rd Phase
TD-543	Tertiary Drain	New Drain	2.5-3.5	149.69	0.64-1.25	Ward No. 09	3rd Phase
TD-544	Tertiary Drain	New Drain	2.5-3.5	297.68	0.64-1.25	Ward No. 09	3rd Phase
TD-547	Tertiary Drain	New Drain	2.5-3.5	4.04	0.64-1.25	Ward No. 09	3rd Phase
TD-548	Tertiary Drain	New Drain	2.5-3.5	87.30	0.64-1.25	Ward No. 09	3rd Phase
TD-550	Tertiary Drain	New Drain	2.5-3.5	1065.61	0.64-1.25	Ward No. 09	3rd Phase
TD-551	Tertiary Drain	New Drain	2.5-3.5	216.15	0.64-1.25	Ward No. 08	3rd Phase
TD-552	Tertiary Drain	New Drain	2.5-3.5	47.81	0.64-1.25	Ward No. 08	3rd Phase
TD-553	Tertiary Drain	New Drain	2.5-3.5	292.73	0.64-1.25	Ward No. 09	3rd Phase
TD-555	Tertiary Drain	New Drain	2.5-3.5	922.48	0.64-1.25	Ward No. 09	3rd Phase
TD-556	Tertiary Drain	New Drain	2.5-3.5	34.32	0.64-1.25	Ward No. 01	3rd Phase
TD-558	Tertiary Drain	New Drain	2.5-3.5	37.04	0.64-1.25	Ward No. 04	3rd Phase
TD-559	Tertiary Drain	New Drain	2.5-3.5	170.61	0.64-1.25	Ward No. 04	3rd Phase
TD-561	Tertiary Drain	New Drain	2.5-3.5	99.19	0.64-1.25	Ward No. 05	3rd Phase
TD-562	Tertiary Drain	New Drain	2.5-3.5	9.08	0.64-1.25	Ward No. 05	3rd Phase
TD-563	Tertiary Drain	New Drain	2.5-3.5	53.94	0.64-1.25	Ward No. 05	3rd Phase
TD-564	Tertiary Drain	New Drain	2.5-3.5	82.52	0.64-1.25	Ward No. 05	3rd Phase
TD-565	Tertiary Drain	New Drain	2.5-3.5	320.86	0.64-1.25	Ward No. 09	3rd Phase
TD-566	Tertiary Drain	New Drain	2.5-3.5	890.42	0.64-1.25	Ward No. 09	3rd Phase
TD-568	Tertiary Drain	New Drain	2.5-3.5	12.62	0.64-1.25	Ward No. 08	3rd Phase
TD-569	Tertiary Drain	New Drain	2.5-3.5	36.16	0.64-1.25	Ward No. 03	3rd Phase
TD-570	Tertiary Drain	New Drain	2.5-3.5	97.77	0.64-1.25	Ward No. 01	3rd Phase
TD-571	Tertiary Drain	New Drain	2.5-3.5	125.86	0.64-1.25	Ward No. 01	3rd Phase
TD-572	Tertiary Drain	New Drain	2.5-3.5	473.30	0.64-1.25	Ward No. 02	3rd Phase
TD-574	Tertiary Drain	New Drain	2.5-3.5	275.01	0.64-1.25	Ward No. 08	3rd Phase
TD-575	Tertiary Drain	New Drain	2.5-3.5	0.01	0.64-1.25	Ward No. 08	3rd Phase
TD-576	Tertiary Drain	New Drain	2.5-3.5	413.19	0.64-1.25	Ward No. 08	3rd Phase
TD-577	Tertiary Drain	New Drain	2.5-3.5	159.27	0.64-1.25	Ward No. 08	3rd Phase
TD-578	Tertiary Drain	New Drain	2.5-3.5	85.85	0.64-1.25	Ward No. 08	3rd Phase
TD-580	Tertiary Drain	New Drain	2.5-3.5	49.92	0.64-1.25	Ward No. 05	3rd Phase
TD-581	Tertiary Drain	New Drain	2.5-3.5	115.82	0.64-1.25	Ward No. 04	3rd Phase
TD-583	Tertiary Drain	New Drain	2.5-3.5	108.95	0.64-1.25	Ward No. 05	3rd Phase
TD-584	Tertiary Drain	New Drain	2.5-3.5	44.97	0.64-1.25	Ward No. 05	3rd Phase
TD-585	Tertiary Drain	New Drain	2.5-3.5	24.20	0.64-1.25	Ward No. 07	3rd Phase
TD-586	Tertiary Drain	New Drain	2.5-3.5	232.12	0.64-1.25	Ward No. 07	3rd Phase
TD-587	Tertiary Drain	New Drain	2.5-3.5	200.92	0.64-1.25	Ward No. 07	3rd Phase
TD-588	Tertiary Drain	New Drain	2.5-3.5	289.48	0.64-1.25	Ward No. 09	3rd Phase
TD-590	Tertiary Drain	New Drain	2.5-3.5	535.33	0.64-1.25	Ward No. 02	3rd Phase
TD-592	Tertiary Drain	New Drain	2.5-3.5	279.30	0.64-1.25	Ward No. 01	3rd Phase
TD-593	Tertiary Drain	New Drain	2.5-3.5	9.98	0.64-1.25	Ward No. 01	3rd Phase
TD-594	Tertiary Drain	New Drain	2.5-3.5	69.63	0.64-1.25	Ward No. 01	3rd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-598	Tertiary Drain	New Drain	2.5-3.5	42.12	0.64-1.25	Ward No. 05	3rd Phase
TD-599	Tertiary Drain	New Drain	2.5-3.5	68.98	0.64-1.25	Ward No. 01	3rd Phase
TD-600	Tertiary Drain	New Drain	2.5-3.5	40.63	0.64-1.25	Ward No. 01	3rd Phase
TD-603	Tertiary Drain	New Drain	2.5-3.5	270.77	0.64-1.25	Ward No. 08	3rd Phase
TD-634	Tertiary Drain	New Drain	2.5-3.5	499.50	0.64-1.25	Ward No. 01	3rd Phase
TD-635	Tertiary Drain	New Drain	2.5-3.5	387.78	0.64-1.25	Ward No. 01	3rd Phase
TD-636	Tertiary Drain	New Drain	2.5-3.5	97.72	0.64-1.25	Ward No. 01	3rd Phase
TD-637	Tertiary Drain	New Drain	2.5-3.5	361.28	0.64-1.25	Ward No. 01	3rd Phase
TD-638	Tertiary Drain	New Drain	2.5-3.5	201.30	0.64-1.25	Ward No. 01	3rd Phase
TD-639	Tertiary Drain	New Drain	2.5-3.5	293.63	0.64-1.25	Ward No. 01	3rd Phase
TD-640	Tertiary Drain	New Drain	2.5-3.5	235.72	0.64-1.25	Ward No. 01	3rd Phase
TD-641	Tertiary Drain	New Drain	2.5-3.5	517.97	0.64-1.25	Ward No. 01	3rd Phase
TD-642	Tertiary Drain	New Drain	2.5-3.5	159.94	0.64-1.25	Ward No. 01	3rd Phase
TD-643	Tertiary Drain	New Drain	2.5-3.5	186.25	0.64-1.25	Ward No. 02	3rd Phase
TD-643	Tertiary Drain	New Drain	2.5-3.5	97.08	0.64-1.25	Ward No. 01	3rd Phase
TD-644	Tertiary Drain	New Drain	2.5-3.5	324.26	0.64-1.25	Ward No. 01	3rd Phase
TD-645	Tertiary Drain	New Drain	2.5-3.5	842.94	0.64-1.25	Ward No. 03	3rd Phase
TD-646	Tertiary Drain	New Drain	2.5-3.5	280.71	0.64-1.25	Ward No. 03	3rd Phase
TD-647	Tertiary Drain	New Drain	2.5-3.5	119.08	0.64-1.25	Ward No. 03	3rd Phase
TD-648	Tertiary Drain	New Drain	2.5-3.5	6.39	0.64-1.25	Ward No. 03	3rd Phase
TD-649	Tertiary Drain	New Drain	2.5-3.5	146.00	0.64-1.25	Ward No. 03	3rd Phase
TD-650	Tertiary Drain	New Drain	2.5-3.5	243.74	0.64-1.25	Ward No. 03	3rd Phase
TD-651	Tertiary Drain	New Drain	2.5-3.5	332.68	0.64-1.25	Ward No. 04	3rd Phase
TD-652	Tertiary Drain	New Drain	2.5-3.5	164.64	0.64-1.25	Ward No. 02	3rd Phase
TD-653	Tertiary Drain	New Drain	2.5-3.5	254.03	0.64-1.25	Ward No. 04	3rd Phase
TD-654	Tertiary Drain	New Drain	2.5-3.5	188.06	0.64-1.25	Ward No. 04	3rd Phase
TD-655	Tertiary Drain	New Drain	2.5-3.5	355.26	0.64-1.25	Ward No. 06	3rd Phase
TD-656	Tertiary Drain	New Drain	2.5-3.5	374.48	0.64-1.25	Ward No. 06	3rd Phase
TD-657	Tertiary Drain	New Drain	2.5-3.5	163.20	0.64-1.25	Ward No. 06	3rd Phase
TD-658	Tertiary Drain	New Drain	2.5-3.5	494.62	0.64-1.25	Ward No. 06	3rd Phase
TD-659	Tertiary Drain	New Drain	2.5-3.5	626.70	0.64-1.25	Ward No. 06	3rd Phase
TD-660	Tertiary Drain	New Drain	2.5-3.5	321.37	0.64-1.25	Ward No. 07	3rd Phase
TD-660	Tertiary Drain	New Drain	2.5-3.5	85.60	0.64-1.25	Ward No. 06	3rd Phase
TD-661	Tertiary Drain	New Drain	2.5-3.5	263.38	0.64-1.25	Ward No. 07	3rd Phase
TD-662	Tertiary Drain	New Drain	2.5-3.5	136.47	0.64-1.25	Ward No. 07	3rd Phase
TD-663	Tertiary Drain	New Drain	2.5-3.5	206.35	0.64-1.25	Ward No. 09	3rd Phase
TD-664	Tertiary Drain	New Drain	2.5-3.5	471.19	0.64-1.25	Ward No. 08	3rd Phase
TD-665	Tertiary Drain	New Drain	2.5-3.5	1192.89	0.64-1.25	Ward No. 08	3rd Phase
TD-666	Tertiary Drain	New Drain	2.5-3.5	246.89	0.64-1.25	Ward No. 08	3rd Phase
TD-666	Tertiary Drain	New Drain	2.5-3.5	69.41	0.64-1.25	Ward No. 05	3rd Phase
TD-667	Tertiary Drain	New Drain	2.5-3.5	505.58	0.64-1.25	Ward No. 08	3rd Phase
TD-668	Tertiary Drain	New Drain	2.5-3.5	193.87	0.64-1.25	Ward No. 08	3rd Phase
TD-669	Tertiary Drain	New Drain	2.5-3.5	104.13	0.64-1.25	Ward No. 05	3rd Phase
TD-670	Tertiary Drain	New Drain	2.5-3.5	654.49	0.64-1.25	Ward No. 05	3rd Phase
TD-671	Tertiary Drain	New Drain	2.5-3.5	328.79	0.64-1.25	Ward No. 07	3rd Phase
TD-672	Tertiary Drain	New Drain	2.5-3.5	153.84	0.64-1.25	Ward No. 07	3rd Phase
TD-673	Tertiary Drain	New Drain	2.5-3.5	317.76	0.64-1.25	Ward No. 08	3rd Phase
TD-674	Tertiary Drain	New Drain	2.5-3.5	140.83	0.64-1.25	Ward No. 08	3rd Phase
TD-675	Tertiary Drain	New Drain	2.5-3.5	37.17	0.64-1.25	Ward No. 08	3rd Phase
TD-676	Tertiary Drain	New Drain	2.5-3.5	43.24	0.64-1.25	Ward No. 08	3rd Phase
TD-677	Tertiary Drain	New Drain	2.5-3.5	16.87	0.64-1.25	Ward No. 08	3rd Phase
TD-678	Tertiary Drain	New Drain	2.5-3.5	64.64	0.64-1.25	Ward No. 08	3rd Phase
TD-679	Tertiary Drain	New Drain	2.5-3.5	79.67	0.64-1.25	Ward No. 08	3rd Phase
TD-680	Tertiary Drain	New Drain	2.5-3.5	192.05	0.64-1.25	Ward No. 08	3rd Phase
TD-681	Tertiary Drain	New Drain	2.5-3.5	358.54	0.64-1.25	Ward No. 08	3rd Phase
TD-682	Tertiary Drain	New Drain	2.5-3.5	791.96	0.64-1.25	Ward No. 09	3rd Phase
TD-683	Tertiary Drain	New Drain	2.5-3.5	319.87	0.64-1.25	Ward No. 09	3rd Phase
TD-684	Tertiary Drain	New Drain	2.5-3.5	231.18	0.64-1.25	Ward No. 09	3rd Phase
TD-685	Tertiary Drain	New Drain	2.5-3.5	623.30	0.64-1.25	Ward No. 09	3rd Phase
TD-686	Tertiary Drain	New Drain	2.5-3.5	431.39	0.64-1.25	Ward No. 09	3rd Phase
TD-687	Tertiary Drain	New Drain	2.5-3.5	566.38	0.64-1.25	Ward No. 09	3rd Phase
TD-688	Tertiary Drain	New Drain	2.5-3.5	1281.12	0.64-1.25	Ward No. 09	3rd Phase

Proposed Drain ID	Proposed Hierarchy	Proposed Type	Proposed Width (ft)	Proposed Length(m)	Proposed Depth(m)	Ward No	Phasing
TD-689	Tertiary Drain	New Drain	2.5-3.5	284.19	0.64-1.25	Ward No. 07	3rd Phase
TD-689	Tertiary Drain	New Drain	2.5-3.5	778.21	0.64-1.25	Ward No. 09	3rd Phase
TD-690	Tertiary Drain	New Drain	2.5-3.5	488.43	0.64-1.25	Ward No. 07	3rd Phase
TD-691	Tertiary Drain	New Drain	2.5-3.5	81.51	0.64-1.25	Ward No. 04	3rd Phase
TD-692	Tertiary Drain	New Drain	2.5-3.5	1166.27	0.64-1.25	Ward No. 07	3rd Phase
TD-692	Tertiary Drain	New Drain	2.5-3.5	43.11	0.64-1.25	Ward No. 05	3rd Phase
TD-693	Tertiary Drain	New Drain	2.5-3.5	326.50	0.64-1.25	Ward No. 05	3rd Phase
TD-694	Tertiary Drain	New Drain	2.5-3.5	420.54	0.64-1.25	Ward No. 06	3rd Phase
TD-695	Tertiary Drain	New Drain	2.5-3.5	249.27	0.64-1.25	Ward No. 06	3rd Phase
TD-696	Tertiary Drain	New Drain	2.5-3.5	113.79	0.64-1.25	Ward No. 06	3rd Phase
TD-697	Tertiary Drain	New Drain	2.5-3.5	289.58	0.64-1.25	Ward No. 07	3rd Phase
TD-697	Tertiary Drain	New Drain	2.5-3.5	188.44	0.64-1.25	Ward No. 06	3rd Phase
TD-698	Tertiary Drain	New Drain	2.5-3.5	292.63	0.64-1.25	Ward No. 04	3rd Phase
TD-699	Tertiary Drain	New Drain	2.5-3.5	531.27	0.64-1.25	Ward No. 02	3rd Phase
TD-699	Tertiary Drain	New Drain	2.5-3.5	393.66	0.64-1.25	Ward No. 04	3rd Phase
TD-700	Tertiary Drain	New Drain	2.5-3.5	406.69	0.64-1.25	Ward No. 04	3rd Phase
TD-701	Tertiary Drain	New Drain	2.5-3.5	332.70	0.64-1.25	Ward No. 09	3rd Phase
TD-702	Tertiary Drain	New Drain	2.5-3.5	281.17	0.64-1.25	Ward No. 09	3rd Phase
TD-703	Tertiary Drain	New Drain	2.5-3.5	276.36	0.64-1.25	Ward No. 09	3rd Phase
TD-704	Tertiary Drain	New Drain	2.5-3.5	593.23	0.64-1.25	Ward No. 09	3rd Phase
TD-705	Tertiary Drain	New Drain	2.5-3.5	220.03	0.64-1.25	Ward No. 09	3rd Phase
TD-706	Tertiary Drain	New Drain	2.5-3.5	5.23	0.64-1.25	Ward No. 08	3rd Phase
TD-706	Tertiary Drain	New Drain	2.5-3.5	36.51	0.64-1.25	Ward No. 09	3rd Phase
TD-707	Tertiary Drain	New Drain	2.5-3.5	424.59	0.64-1.25	Ward No. 09	3rd Phase
TD-708	Tertiary Drain	New Drain	2.5-3.5	66.23	0.64-1.25	Ward No. 02	3rd Phase
TD-709	Tertiary Drain	New Drain	2.5-3.5	8.38	0.64-1.25	Ward No. 02	3rd Phase
TD-710	Tertiary Drain	New Drain	2.5-3.5	129.64	0.64-1.25	Ward No. 02	3rd Phase
TD-711	Tertiary Drain	New Drain	2.5-3.5	105.50	0.64-1.25	Ward No. 02	3rd Phase
TD-712	Tertiary Drain	New Drain	2.5-3.5	1384.41	0.64-1.25	Ward No. 02	3rd Phase
TD-713	Tertiary Drain	New Drain	2.5-3.5	4.57	0.64-1.25	Ward No. 09	3rd Phase
TD-714	Tertiary Drain	New Drain	2.5-3.5	27.03	0.64-1.25	Ward No. 03	3rd Phase
TD-715	Tertiary Drain	New Drain	2.5-3.5	7.63	0.64-1.25	Ward No. 04	3rd Phase
TD-716	Tertiary Drain	New Drain	2.5-3.5	213.92	0.64-1.25	Ward No. 08	3rd Phase
TD-716	Tertiary Drain	New Drain	2.5-3.5	236.49	0.64-1.25	Ward No. 05	3rd Phase
TD-717	Tertiary Drain	New Drain	2.5-3.5	76.13	0.64-1.25	Ward No. 08	3rd Phase
TD-718	Tertiary Drain	New Drain	2.5-3.5	29.69	0.64-1.25	Ward No. 08	3rd Phase
TD-719	Tertiary Drain	New Drain	2.5-3.5	3.38	0.64-1.25	Ward No. 05	3rd Phase
TD-720	Tertiary Drain	New Drain	2.5-3.5	517.43	0.64-1.25	Ward No. 05	3rd Phase
TD-721	Tertiary Drain	New Drain	2.5-3.5	103.75	0.64-1.25	Ward No. 03	3rd Phase
TD-722	Tertiary Drain	New Drain	2.5-3.5	343.09	0.64-1.25	Ward No. 03	3rd Phase
TD-723	Tertiary Drain	New Drain	2.5-3.5	203.39	0.64-1.25	Ward No. 03	3rd Phase
TD-724	Tertiary Drain	New Drain	2.5-3.5	209.25	0.64-1.25	Ward No. 03	3rd Phase
TD-725	Tertiary Drain	New Drain	2.5-3.5	169.83	0.64-1.25	Ward No. 06	3rd Phase
TD-726	Tertiary Drain	New Drain	2.5-3.5	963.82	0.64-1.25	Ward No. 07	3rd Phase
TD-727	Tertiary Drain	New Drain	2.5-3.5	8.20	0.64-1.25	Ward No. 09	3rd Phase
TD-728	Tertiary Drain	New Drain	2.5-3.5	20.05	0.64-1.25	Ward No. 01	3rd Phase
TD-729	Tertiary Drain	New Drain	2.5-3.5	186.76	0.64-1.25	Ward No. 01	3rd Phase
TD-730	Tertiary Drain	New Drain	2.5-3.5	0.66	0.64-1.25	Ward No. 01	3rd Phase
TD-731	Tertiary Drain	New Drain	2.5-3.5	335.65	0.64-1.25	Ward No. 01	3rd Phase
TD-732	Tertiary Drain	New Drain	2.5-3.5	1.86	0.64-1.25	Ward No. 08	3rd Phase
TD-733	Tertiary Drain	New Drain	2.5-3.5	212.17	0.64-1.25	Ward No. 08	3rd Phase
TD-734	Tertiary Drain	New Drain	2.5-3.5	30.09	0.64-1.25	Ward No. 08	3rd Phase
TD-735	Tertiary Drain	New Drain	2.5-3.5	88.41	0.64-1.25	Ward No. 08	3rd Phase
TD-736	Tertiary Drain	New Drain	2.5-3.5	152.70	0.64-1.25	Ward No. 08	3rd Phase
TD-737	Tertiary Drain	New Drain	2.5-3.5	268.81	0.64-1.25	Ward No. 08	3rd Phase
TD-601	Tertiary Drain	New Drain	2.5-3.5	19.10	0.64-1.25	Ward No. 03	3rd Phase
TD-601	Tertiary Drain	New Drain	2.5-3.5	19.10	0.64-1.25	Ward No. 02	3rd Phase
TD-607	Tertiary Drain	New Drain	2.5-3.5	16.30	0.64-1.25	Ward No. 03	3rd Phase
TD-607	Tertiary Drain	New Drain	2.5-3.5	16.30	0.64-1.25	Ward No. 02	3rd Phase

Table G1: Planning Schedule of Waterbodies in Gauranadi Paurashava

Land Use	Mouza	Plot No	Area
Waterbody	Asokati	1-2,7-8,12-14,22,24,29,32,36-37,40,43-44,50,53-55,60-62,82-85, 95-97,99-100,102,120,123-25,127-29,133-34,140,142,144-54, 157, 159,161-65,172-75,178-79,184-85,189,191,196,200,208-09, 215,218,227-30,232-34,236-37,242-46,251,255,271-78,281-83, 298-02,304-06,327-28,338,352,370,378-79,399,404,416-18,442, 445-47, 450-51,454-59,461,463-66,468,472-81,483,488,495-97, 500,507-08, 510-11,519-20,523-24,528,530-31,535-37,540,543, 546,548-49, 554-57,561,99999	452.58
	Baniasuri	29-33,35-40,42,46,51,54-55,58,71,73-74,76-77,79,87,99-01,110-13,124-30,132-33,139,144-45,147-48,151-52,156,158-60,163-65,167-70,173-77,182-83,187-90,192-93,197,200,204-06,219,226-27,230,233-35,238-40,259-61,279,305,307-13,317-18,320-21,327-28,330,352,357-59,365-67,373,376-78,382,386,390-94,396,399-400,403-05,407-08,410,412,414,417,423,425-32,435,452,456-57,460-61,463-64,466,468-72,490-92,497-01,505,510-17,523,535-36,545-46,556,558,562,564-75,579-80,582,22222	
	Bara Kasba	1,14-15,20-22,24-27,37,40-41,46-49,53,64,68-69,73-75,78,80-81,84-85,90,106,117,120-21,124-25,128-29,131-32,134-41,146,151-54,159-61,167-68,170-78,180-81,194-200,202,208-09,211,213-23,227,229,234-37,239-42,244-54,256,261,263-66,268-77,280-81,283-86,288,291-94,296,301-02,304,306,308,309,311-14,317,326-27,329-30,332,334-36,338-39,341-42,344-48,356-66,374-82,385-87,807,810-14,847-49,882-83,909-12,914-17,920,971-75,996,1004-005,1090-92,1101,1122-24,1126-28,1328-38,1340-44,1389-90,1416-18,1427,1430-31,1434,99999	
	Char Gadhatali	1-5,7-10,13,16-20,22-23,25,29-32,73-77,92-94,103-05,129-135,154-60,164-65,167-71,174-83,188-90,210-11,252-57,281-83,315-17,325-28,330-35,338-40,350-54	
	Dakshin Bijoypur	2-5,7,16,54,56-58,63,65-66,68-69,72-75,81-83,90-97,106-12,121-26,157-59,161-62,178,231,248-50,274-92,300-301,321-29,369-71,393-94,401-05,420-23,430-35,449-50,461-63,470-72,479-82,501-07,509-16,518-20,526-28,538-44,560,99999	
	Dakshin Palardi	12-14,17-18,21-22,24-26,34-35,65-71,84-89,98-02,115-19,121,127-28,141-44,149-60,170,210-12,216-23,257-61,280-84,293-98,307-20,340-44,347-56,360-64,368-72,380-87,396-99,407,415-16,427-32,465-66,491,493,629,654-55,661,669	
	Diasur	11-17,20-24,27,30-32,36,40,42-43,47-49,64-69,77-78,101,103-06,108,111-12,116-23,150-51,154,161-63,169-70,176-77,247-53,264-71,279-81,313-16,361-73,378-83,469-71,486-90,501-05,513-15,531-33,540,542-43,548,99999	
	Gerakul	1-4,6-7,14-15,18-21,30-33,36-38,58-64,88-91,93-98,101-02,110,118,121-22,139-41,160-161,169-74,177-79,185-89,211-16,218-22,242-44,246-55,266-69,274-76,278-84,286-88,300-03,312-16,318-25,327-30,332-37,339-40,346-48,350-57,369-81, 385-88,394-99,401-06,408-10,432-40,524,526-28	
	Gobardhan	13,22,29-31,36-37,43-48,50-51,53,58,65,67-69,108-09,114-17,120,130,136-38,207-08,221-23,260-61,277-	

		81,298,302,307-09,324-26,328-29,334-39,368-71,375-77,379-81,383-84,22222	
	Harisana (Kasemabad)	12,22-23,53,55,58,61,67-68,98,100-01,183-84,219-23,225,227,240,242,246,248,253-56,258-62,278,283-84,286-87,290,297,304,307,319-21,325-30,361-65,448,450-53,458-65,470-71,487-88,504-06,538-41,572-84,593-99,601-04,607-10,622,624-38,663-71,700-03,730-31,743,754-57,799-07,809-17,822-24,853-55,941,976,980,986-87,996-1226-28,1249-60,1311-15,1342-46,1431-33,1481,1484,1486-87,1527-29,1531,1596-03,1630-35,1644-47,1722-23,1730-35,1738-45,1765-67,1780-82,1797,1800,1807,9836	
	Lakherajkasba	4,10-11,17-19,33-34,42-44,52-56,60-61,63-64,66,68,71,73,78-79,81-82,84,98-100,124-30,135,138-41,146-51,159-60,184-91,199-200,202-12,221-24,257-59,280-85,287-89,305-07,319-21,338-41,347-48,357-60,362-63,367,99999	
	Saora	1-2,6,11,19,23,26-30,34-38,40-41,46,55-57,62-65,67,70-72,76,81-86,88,95,97-98,100,105-06,109-11,126-28,140-46,148,170-74,178-86,199-02,207-11,228-29,231-33,236-45,260,262-63,278-86,288-96,320-23,330-32,341-46,350-52,382,384-87,389-90,395-97,399	
	Sundardi	1-3,5,7,9,11,14-15,29-30,32-34,69-73,153-54,157-61,179-83,195-99,212-15,228,231,234-35,286,289,293-94,304-07,320,341,343,349,361,368-69,375-76,430,432-34,441-42,451-55,510-14,535-36,547-50,561-64,599-01,626-35,664-68,713-17,737-50,1501-07,1526-30,1552-64,1598-04,1617-23,1654-57,1672-81,1687-88,1697-1700,1720 - 29,1762-73,1802-03,1853-60,1899-01,2016-17,2031-37,2100-02,2110,2123,2340,2344,2346,99999	
	Tarkir Char	6-11,15-16,26-27,31-34,38-41,63-64,68-75,110-29,133,135-36	
	Tikhasar	1-9,13-14,16-31,41-43,45-46,50,52,54-55,57,71,73-76,85,87,96-98,101-02,117,121,123,126,128-31,185,187,198-200,253-55,280-85,291-92,295-01,306-10,395-97,400-02,411-16,420-21,429-31,436,438,440-41,99999	