



Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development & Cooperatives
Local Government Division

SINGRA PAURASHAVA
MASTER PLAN: 2011-2031

MARCH, 2015

Technical Assistance: Local Government Engineering Department (LGED)



Government of the People's Republic of Bangladesh
Ministry of Local Government, Rural Development & Cooperatives
Local Government Division

SINGRA PAURASHAVA MASTER PLAN: 2011-2031

STRUCTURE PLAN

URBAN AREA PLAN:

- Landuse Plan
- Transportation & Traffic Management Plan
- Drainage & Environmental Management Plan

WARD ACTION PLAN

March, 2015



SINGRA PAURASHAVA
SINGRA, NATORE

SINGRA PAURASHAVA MASTER PLAN: 2011-2031

Published by:

SINGRA PAURASHAVA

**Supported by Upazila Towns Infrastructure Development Project (UTIDP) of
Local Government Engineering Department (LGED) under
Local Government Division**

Consultant:

AQUA Consultants & Associates Ltd.

AQUA Tower (Level- 14 & 15), 43, Mohakhali C/A, Dhaka-1212

Printed By:

Copyright: Singra Paurashava

Local Government Division (LGD),

Ministry of Local Government, Rural Development and Cooperatives.

First Edition: March, 2015

Price: BDT 1500.00

USD 20.00

Preface

Bangladesh has been experiencing rapid urbanization in the last four decades where level of urbanization has reached from 7.6% to nearly 29% between 1970 and 2011. Multidimensional complex factors like; socio-economic, political, demographic and climatic are responsible for this higher growth of spatial transformation. The fast urbanization is putting pressure on the small towns' limited land, urban services and environment along with countries big cities. Whereas urbanization is also considered as an opportunity and an integral part of the development process. Proper development plans and guidelines with necessary legislative measures and appropriate institutional arrangement can help to achieve sustainable urban as well as rural development.

However, presently, the Paurashavas has the legal mandate to take initiatives of formulating development plans, providing infrastructure and other services and creating opportunities for people to initiate developments with sustainable and harmonic approach. In this regards, Singra had initiated steps to frame its' Master Plan (Physical Development Plan) by taking technical assistance from the Local Government Engineering Department (LGED). LGED under the Local Government Division of the Ministry of Local Government, Rural Development and Cooperatives initiated a project titled 'Upazila Towns Infrastructure Development Project (UTIDP)' providing all sorts of technical assistances to prepare long term physical development plan titled 'Master Plan' for Singra Paurashava.

Master Plan of Singra Paurashava has been prepared following the pre-requisite of the Local Government (Paurashava) Act, 2009. To prepare the Master Plan, LGED engaged consulting firm named AQUA Consultants & Associates Ltd. and set up a Project Management Office (PMO) deploying a Project Director, Deputy Project Director, experienced Urban Planners as Individual Consultant and support staffs. Regular monitoring, evaluation and feedback from PMO had also accelerate the pace and quality of the master plan preparation tasks. During formulation of the Master Plan, the Paurashava authority along with the project & the Consultant ensure people's opinion, observation and expectation in various ways: conducting sharing meetings, Public Hearing etc. At the end of the formulation process, the Paurashava completed all procedures necessary for its approval as per the related clauses and sub-clauses of the Local Government (Paurashava) Act, 2009. Paurashava Authority has submitted this Plan to the Local Government Division of the Ministry of Local Government, Rural Development and Cooperatives for final approval and gazette notification.

This Master Plan comprises of three tier of plan in a hierarchical order, these are: Structure Plan for 20 years, Urban Area Plan for 10 years and Ward Action Plan for 5 years. Urban Area Plan also comprises of three components namely; Land use plan, Traffic & Transportation Management plan and Drainage & Environmental Management Plan. This Master plan will serve as guidelines for the future infrastructure development of Singra Paurashava together with land use control and effective management of service facilities.

The Paurashava Authority acknowledges the full support and all out cooperation from the consultant team, the Project Management office of UTIDP, LGED, Local Government Division of the Local Government, Rural Development and Cooperatives Ministry, public representatives, other stakeholders and civil society with deepest gratitude for accomplishing this remarkable assignment.

Cooperation and participation from national to local authorities, all government institutions, private entities and people of Singra Paurashava will be necessary to implement this Master Plan successfully and make this Paurashava developed and livable. I hope Singra Paurashava will be a model Paurashava in Bangladesh through building itself green and sustainable by successful implementation of this Master Plan.

(Shamim Al Razi Md. Shihanur Rahman)
Mayor
Singra Paurahsava.

Executive Summary

The Master Plan Report of Singra Paurashava has been prepared and submitted by the consultant AQUA-SCPL-RCC consortium for the partial fulfillment of the requirements stated in the Terms of Reference (ToR) for Upazila Towns Infrastructure Development Project (UTIDP; package- 9) being implemented by Local Government Engineering Department (LGED) under the Ministry of Local Government Rural Development and Co-operatives (LGRD&C), Government of the People's Republic of Bangladesh. The Master Plan Report is the fourth of the series of the reports to be submitted as per the ToR of the project "Upazila Town Infrastructure Development Project-Preparation of Singra Paurashava Master Plan (Structure Plan, Urban Area Plan and Ward Action Plan)".

Prior to starting the MasterPlan report the consultant undertook field visit and organized a meeting with the stakeholders to understand the growth pattern, problems and prospects in future developing aspects of the project area. Existing Paurashava boundary covering an area of 2703.74 acres or 10.94 sq. km. was delineated as planning area for preparation of Master Plan with due emphasis on local and regional development agenda for next 20 years.

The pattern of settlements in the Paurashava reflects that the Paurashava still possesses predominantly the rural characteristics. No planned residential area exists in the Paurashava. Structures are established without any planning standard and in haphazard manner. Population density of the Paurashava area is found 3034/ sq. km in the year 2011. The Growth Rate of Singra Paurashava is estimated to be 3.92 %. The projected population found for the year 2031 is 71617 which are 2.15 times higher than the present population (33192) of Singra Paurashava. The gross density of the area will be 26 ppa (person per acre). People in this Paurashava mostly belong to middle and higher income groups. Only a small number of people belong to higher income group. According to BBS 2001, Agricultural is the main economic activity of the majority of the people of this Paurashava. The percentage of the people in this occupation is 42.46%. The next highest occupation class observed is the small business and others service. Other major occupations are day laborers, expatriate wage earners, and public and private services. Present socio-economic condition of Singra Paurashava is not very enthusiastic.

The project area is located in the bank of Atrai and Goura River; This Paurashava has been intersected in east-west direction by Natore-Bogra Road and urban development has taken place mainly along this highway. The Paurashava as well as the Upazila is connected within the region by Road Networks. The project area is one of the important centers of economic activities within the eastern region. It has long cultural and trading relation with Gurudaspur, Bagatipara, Natore and Bogra. The average elevation of the land of the Paurashava area is 10.76 mPWD. Mean elevation of different wards of Singra Paurashava is very close to the mean value for the entire Paurashava except the areas in Ward Nos.8 and 9. Most of the area of the Paurashava area lies under normal flood level. For Singra Paurashava mean spot height for Agricultural Land is found to be 10.45 mPWD where as the mean spot height found for roads/Circulation network is about 12.39 mPWD and mean spot height found for residential is about 11.99 mPWD. Parts of Ward Nos. 1, 5 and 8 are found to be at relatively higher elevation. Comparing to overall land level and Ward No. 8 is higher than any other portion of this Paurashava. This area is the hub of commercial activities. The physical feature survey reveals that there are in total 9897 structures exist in the Paurashava of which residential structures are the highest (89.31%) and commercial structures are second

highest (6.83%). Maximum structures of the Paurashava (64.94%) is katcha while semi pucca structures are 27.44% and pucca structures are only 7.62% of the total structures of the Paurashava. In total the Paurashava has 43 small bridges/ culverts and 62.77 km of roads. The Paurashava has 219 ponds and 239 ditches as well. Among 33.06 km of total Road network 39.71km is Pucca and 18.86 km is Katcha. In this Paurashava there is 4.19km semi-Pucca Road. In Singra Paurashava in total 4.20 km of pucca drain exists and wards no 2 there is no drain.

The project area is predominantly agricultural in character. Land use survey reveals that agriculture is the most dominant land use category of the Singra Paurashava which comprises 65.40% of the total land area of the Paurashava. The land under agriculture purpose use is mostly double cropped area, which are low-lying depressions and remain under water during the monsoon flood. Paurashava Commercial, educational and mixed use lands are very much negligible in percentage. Core areas (Ward Nos. 4, 5 and 8) of the town along this highway and its close vicinity developed with diversified land use without any proper planning guidelines causing many difficulties such as, traffic congestion, drainage problems and environmental degradations etc. for the town. Existence of Atrai & Goura River and quite a good number of canals in and around the Paurashava created opportunities for cultured fisheries in the Paurashava area. Good transportation linkage within the region and other parts of the country and potential for agriculture and fishery has created abundant scope for establishment of agro-based industries with adequate forward and backward linkages in the Paurashava.

The structure plan (Part-A) area consist of different zones (Core Area, Fringe Area, Peripheral Area, New Urban Area, Agriculture, Water body and Major Circulation) and it covers 2703.74 acres of land in entire Paurashava. Agricultural area (1065.01 acres) is the highest percentage of land (39.39%) followed by Peripheral Area (15.35%), Fringe Area (13.52%) and Water body (12.85%). The core area covers only 175.2 acres of land and the percentage is 6.42.

Urban Area Plan is the mid level plan that covers the existing Paurashava. It lays down the land use zoning plan and infrastructure development proposals at the town level. Land use planning is an important part of Master Plan ensuring that land is used efficiently for the benefit of economy, society and environment of Singra Paurashava. Urban Area Plan is the first phase illustration of the Structure Plan intended to be implemented over a time span of 10 years that includes 1st phase (1st-5th year) and 2nd phase (6th-10th year) of development programs.

The components of Urban Area Plan include Land Use Plan, Transportation and Traffic Management Plan, Drainage and Environmental Management Plan, Proposals for Urban Services. The future housing area estimates on a recommended planning standard of 100/150 persons per acre. With this standard, the maximum land required to accommodate total projected population (71617) in the year 2031 will be 716.17 acres. Total commercial land in 2031 has been fixed at 20.07 acres, Education 103.84 acres, open space 153.98 acres and transport 9.87 acres. But in the time of land use proposal of Singra Paurashava it is not possible to maintain the all standard due to insufficient land. In land use proposal 462.89 acres of land is for Urban Residential Zone where 295.04 acres is for rural settlement. The commercial lands have been proposed 33.18 acres, Education & Research Zone 68.44 acres, Open Space 94.23 acres, Transportation Facilities 6.23 acres, Community Facilities 20.59 acres and Health Services 14.34 acres.

The Transportation and Traffic Management Plan covers the scope of improvement of the existing network and system and plan proposals for new development. The proposals on improvement and new development are made for the project area up to 2031. The existing circulation network of Singra Paurashava is 62.77 km and the proposed circulation network is 205.54 acres includes existing. The primary roads (Natore-Bogra) have been proposed 100ft (ROW) and minimum width of road 20ft (ROW) in entire Paurashava. The main intention of transport plan is to ensured proper functional linkage within other regional centres. One truck terminal, eleven tempo stand and three Rickshaw stand and two Ghats are proposed to cover the whole area. It is also focused on parking facilities and built passenger shed.

The purpose of the Drainage Plan is to make an assessment of the present drainage facilities and to improve future development. This Plan shall be a planning tool and shall be used as a guideline for Singra Paurashava that shall be responsible for the approval of drainage improvements. Natural canal in Singra Paurashava is acting as a critical role in entire Paurashava. The natural drainage network is composed with 466 water bodies in Singra Paurashava out of which 219 are ponds and 239 are ditches and 04 khals. Total area devoted to water bodies in Singra Paurashava is around 345.23 acres. Present man made drain is about 4.20km and all this drains is pucca. The proposed drain of Singra Paurashava is about 26.74km where 3.31 km is primary drain, 8.91km is secondary drain and 14.52km is Tertiary drain. This will designated up to 2031.

Singra Paurashava is lacking for sewerage system and people are used to dispose household sewer to the surface drains and or surface water bodies. This Paurashava does not possess good solid waste management system. Only there are three vehicle and 6 vans for solid waste disposal although those are not properly functioning. There was no designated dumping area in Singra Paurashava. In proposed plan 7.66 acres of land is reserved for dumping ground and it is located in ward no 12. Total 02 waste transfer stations have been proposed in core area.

In Part-C of the report contains Ward Action Plan of each individual Ward and this Development Proposals will be implemented within 1st to 5th year of planning period.

The Ward Action Plans (Part-C) are prepared under the framework of Structure Plan and Urban Area Plan. The Ward Action Plans contain details of development proposals at Ward level including the problems and opportunities existing therein and also include the proposals made in the upper level plan that is in the Urban Area Plan. The Ward Action Plans have been formulated for execution within a period of 5 years.

Finally, The Paurashava is self sufficient neither in preparation of plan nor in implementation of plan proposals; is dependence on central government for technical and financial assistance huge. This dependence might hinder the overall plan making and implementation process. Besides, plan implementation would require the Paurashava to have a good coordination among various stakeholders and with the line ministry (LGRD&C) in place. Therefore a right kind of Institutional arrangement, and implementation framework would be required for successful implementation of the plan proposals and its future updating. However, the current project regarding Preparation of Master Plan for Singra Paurashava under "UTIDP" emphasizes on having proper guidelines and planning standards by the Paurashava for ensuring sustainable and planned development of the Paurashava.

**Preparation of Master Plan for Paurashavas under
Upazila Towns Infrastructure Development Project (UTIDP)**

TABLE OF CONTENTS

Preface	
Executive Summary	i-iii
Table of Contents.....	i-vi
List of Tables.....	vii-viii
List of Maps.....	ix
List of Figures.....	x
List of Abbreviations, Acronyms And Local Terms	xi
 Part A: Structure Plan	
Chapter 1: Introduction.....	1
1.1 General	1
1.2 Philosophy of the Preparation of Master Plan	4
1.3 Objectives of the Master Plan	4
1.4 Approach and Methodology	4
1.5 Scope of Work.....	5
1.6 Organization of the Master Plan Report.....	7
Chapter 2: Introduction to Structure Plan	8
2.1 Background of the Paurashava.....	8
2.2 Vision of the Structure Plan	9
2.3 Objectives of the Structure Plan	11
2.4 Concepts, Content and Format of the Structure Plan.....	11
2.5 Duration and Amendment of the Structure Plan	12
2.6 Structure Plan Area.....	12
Chapter 3: Existing Development Status of Singra Paurashava	13
3.1 Social Development	13
3.2 Economic Development	13
3.2.1 Economic Activities	13
3.2.2 Existing Employment Pattern.....	15
3.3 Population	15
3.4 Physical Infrastructure Development	17
3.5 Utility Services.....	18
3.6 Environmental Issues.....	19
3.7 Institutional Capacity.....	20
3.8 Urban Growth Area	21
3.9 Catchments Area	21
3.10 Land Use and Urban Services	22
3.11 Paurashava Functional Linkage with the Regional and National Network	22
3.12 Role of Agencies for Different Sectoral Activities	25
Chapter 4: Critical Issues for Planning	27
4.1 Socio-Economic and Demographic Issues	27
4.2 Transportation and Communication.....	27
4.3 Urban Utilities.....	30
4.4 Drainage and Environment	30

4.5 Related Other Issues	30
4.6 Disaster Issues.....	30
4.7 Land Use Control	30
4.8 Laws and Regulations.....	31
4.9 Existing Problems and Weaknesses in the Development	32
Chapter 5: Reviews of Policies, Laws and Regulations	34
5.1 Introduction	34
5.2 Review of Relevant National Policies	34
5.2.1 Directives of the Local Government (Paurashava) Act, 2009 for Preparing the Master Plan.....	34
5.2.2 National Land Use Policy 2001.....	35
5.2.3 National Housing Policy, 1993.....	35
5.2.4 Population Policy 2004	36
5.2.5 Transportation Policy 2004	36
5.2.6 National Environment Policy 1992.....	36
5.2.7 Industrial Policy 2005.....	38
5.2.8 National Tourism Policy 1992 and 2010	39
5.2.9 Agriculture Policy 1999.....	39
5.2.10 Urban Forest Policy 1994	40
5.2.11 National Plan for Disaster Management, 2008-15.....	41
5.2.12 National Plan of Action for Person's with Disabilities (PWDs) as well as Autism, 1995	41
5.2.13 Review of Relevant Laws and Regulations	42
5.2.13.1 The Act (36 of 2000) for Conservation of Play field, Open space, Park and Natural Water Reservoir in Mega City, Divisional Town, District Town and Paurashavas of Bangladesh.....	42
5.2.13.2 Bangladesh National Building Code (BNBC) 1993.....	42
5.2.13.3 The Building Construction Act 1952.....	42
5.3 Applicability of the Acts, Regulations and Policies in the Paurashava Master Plan	43
Chapter 6: Projection of Future Growth by 2031	47
6.1 Projection of Population	47
6.2 Identification of Future Economic Opportunities	49
6.3 Projection of Land use	51
Chapter 7: Landuse Zoning Policies and Development Strategies	52
7.1 Zone of Structure Plan Area	52
7.1.1 Core Area.....	54
7.1.2 Fringe Area	54
7.1.3 Peripheral Area	55
7.1.4 New Urban Area	56
7.1.5 Agriculture.....	56
7.1.6 Water body/Retention Area	57
7.1.7 Major Circulation Network.....	57
7.2 Strategies for optimum use of Urban Land Resources.....	57
7.2.1 Optimum use of Urban Land Resources	57
7.2.2 Plans for New Area Development.....	58
7.2.3 Areas for Conservation and Protection.....	59
7.3 Policies for Development	59
7.3.1 Policies for Socio-economic Sector	59
7.3.2 Physical Infrastructure Sector.....	63
7.3.3 Environmental Issues	64
Chapter 8: Implementation Issues.....	66
8.1 Institutional Capacity Building of the Paurashava.....	66
8.1.1 Staffing and Training.....	67

8.1.2 Lack of Automation	67
8.1.3 Town Planning Capacity	67
8.1.3.1 Institutional Framework	67
8.1.3.2 Lack of Paurashava Town Planning Capacity	69
8.1.4 Legal Aspects	69
8.1.5 Good Governance in Legal Provisions	69
8.1.6 Financial Issues	70
8.1.7 Monitoring, Evaluation and Updating	70
8.1.8 Periodic Review and Updating	71
8.2 Resource Mobilization	71
8.3 Concluding Remarks	71

Part B: Urban Area Plan

Chapter 9: Urban Area Plan 73

9.1 Goals and Objectives of Urban Area Plan	73
9.2 Methodology and Approach to Planning	73
9.2.1 Delineation of Planning Areas	74
9.2.2 Content and Form of Urban Area Plan	75

Chapter 10: Landuse Plan 76

10.1 Existing and Projected land use	76
10.1.1 Existing Land Use	76
10.1.2 Land Requirement Estimation	78
10.2 Land Use Proposals	83
10.2.1 Designation of Future Land Use	84
10.2.2 Land Use Zoning	84
10.2.2.1 Types of Land Use Zoning	84
10.2.2.2 Classification of Land Use Zoning	85
10.2.3 Land Use Permission	100
10.3 Plan Implementation Strategies	101
10.3.1 Land Development Regulations to implement the Land Use Plan	101
10.3.2 Implementation, Monitoring and Evaluation of the Land Use Plan	103

Chapter 11: Traffic and Transportation Management Plan 105

11.1 Introduction	105
11.1.1 General	105
11.1.2 Approach and Methodology	105
11.2 Existing Conditions of Transportation Facilities	106
11.2.1 Roadway Characteristics and Functional Classification	106
11.2.2 Mode of Transport	107
11.2.3 Intensity of Traffic Volume	107
11.2.4 Level of Service: Degree of Traffic Congestion and Delay	108
11.2.5 Facilities for Pedestrians	111
11.2.6 Analysis of Existing Deficiencies	111
11.2.6.1 Roadway Capacity Deficiencies	111
11.2.6.2 Operational, Safety, Signal and other Deficiencies	114
11.2.7 Condition of other mode of transport (Rail/Water/Air)	114
11.3 Future Projections	114
11.3.1 Travel Demand Forecasting for Next 20 Years	115
11.3.2 Transportation Network Considered	116
11.3.3 Future Traffic Volume and Level of Service	116
11.4 Transportation Development plan	117
11.4.1 Plans for Road Network Development	117
11.4.1.1 Road Network Plan	118
11.4.1.2 Proposal for improvement of the existing road networks	119

11.4.1.3 List of Proposed new roads.....	123
11.4.2 Plan for Transportation Facilities	124
11.4.2.1 Transportation Facilities Plan.....	124
11.4.2.2 Parking and Terminal Facilities.....	125
11.4.2.3 Development of Facilities for Pedestrians, Bicycles and Rickshaws	126
11.4.2.4 Other Transportation Facilities	126
11.4.3 Waterway Development/Improvement Options	127
11.4.4 Railway Development Option	127
11.5 Transportation System Management Strategy (TSM)	127
11.5.1 Strategies for Facility Operations.....	127
11.5.2 Strategies for Traffic Flow and Safety	129
11.5.3 Strategies for Traffic Management	130
11.6 Plan Implementation Strategies	131
11.6.1 Regulations to implement the Transportation Plan.....	131
11.6.2 Implementation, Monitoring, Evaluation and Coordination of the Plan	132
Chapter 12: Drainage and Environmental Management Plan	133
12.1 Introduction	133
12.1.1 Goals and Objectives.....	133
12.1.2 Methodology and Approach to Planning.....	133
12.2 Existing Drainage Network.....	142
12.2.1 Introduction	142
12.2.2 Existing Drainage System/Network	142
12.2.3 Analysis on land level (Topography).....	145
12.2.4 Analysis of peak runoff and identification of drainage outfalls.....	149
12.3 Plans for Drainage Management and Flood Control	150
12.3.1 Plan for Drain Network Development	150
12.3.1.1 Drain Network Plan	150
12.3.1.2 Proposal for Improvement of the Existing Drainage Networks	151
12.3.1.3 List of Proposed New Drains.....	151
12.3.1.4 Proposed Drainage Structure.....	154
12.4 Plan Implementation Strategies	156
12.4.1 Regulations to implement the Drainage and Flood Plan	156
12.4.2 Implementation, Monitoring, Evaluation & Coordination of the Plan	159
12.5 Introduction	161
12.5.1 Goals and Objectives.....	161
12.5.2 Methodology and Approach to Planning.....	161
12.6 Existing Environmental Condition	161
12.6.1 Introduction	161
12.6.2 Geo-morphology	162
12.6.3 Solid Waste and Garbage disposal	165
12.6.4 Waste Management System.....	165
12.6.5 Pollutions	165
12.6.5.1 Water.....	165
12.6.5.2 Air	165
12.6.5.3 Sound	166
12.6.5.4 Arsenic	166
12.6.6 Natural Calamities and Localized Hazards.....	166
12.6.6.1 Cyclone	166
12.6.6.2 River Erosion.....	167
12.6.6.3 Flood	167
12.6.6.4 Earth Quake	167
12.6.6.5 Water Logging	167
12.6.6.6 Fire Hazard.....	168
12.7 Plans for Environmental Management and Pollution Control	168
12.7.1 Proposals for Environmental Issues	168
12.7.1.1 Solid waste management Plan.....	168

12.7.1.2 Plan for Protecting Open Space, Wet-Land and Relevant Features	169
12.7.1.3 Proposals for Pollution Control	172
12.7.1.3.1 Industrial	172
12.7.1.3.2 Air/Water/Land/Sound	173
12.7.1.3.3 Other Pollution	175
12.7.2 Natural Calamities and Hazard Mitigation Proposals	175
12.7.2.1 Plan for Addressing Natural Calamities (Structural and non structural measures)	175
12.7.2.2 Plan for Addressing Hazards	177
12.8 Plan Implementation Strategies	179
12.8.1 Regulations to Implement the Environmental Management Plan	179
12.8.2 Implementation, Monitoring, Evaluation and Coordination of the Plan	180
Chapter 13: Plan for Urban Services.....	182
13.1 Water Supply.....	182
13.2 Solid Waste Management	184
13.3 Sanitation	184
13.4 Electricity and Gas	184
13.5 Telecommunication	184
 Part C: Ward Action Plan	
Chapter 14: Ward Action Plan.....	186
14.1 Introduction	186
14.1.1 Background.....	186
14.1.2 Content and Form of Ward Action Plan	186
14.1.3 Linkage with Structure and Urban Area Plan	186
14.1.4 Approach & Methodology	186
14.2 Derivation of the Ward Action Plan	187
14.2.1 Revisiting Structure Plan and Urban Area Plan.....	187
14.2.2 Prioritization	187
14.2.3 Ward Wise Action Plan for Next Five Years	188
14.3 Demographic Conditions of Ward-01	190
14.4 Critical Issues and Opportunities of the Ward	190
14.5 Ward Action Plan Proposals	191
14.5.1 Riview of Existing Land Use	191
14.5.2 Proposed Land Use Zoning	191
14.5.3 Road Network Development Plan.....	194
14.5.4 Drainage Development Plan	194
14.5.5 Urban Services Development Plan of ward no-01	195
14.6 Demographic Conditions of Ward-02.....	197
14.7 Critical Issues and Opportunities of the Ward	197
14.8 Ward Action Plan Proposals	198
14.8.1 Riview of Existing Land Use	198
14.8.2 Proposed Land Use Zoning	198
14.8.3 Road Network Development Plan.....	201
14.8.4 Urban Services Development Plan of ward no-02.....	202
14.9 Demographic Conditions of Ward-03.....	204
14.10 Critical Issues and Opportunities of the Ward	204
14.11 Ward Action Plan Proposals	205
14.11.1 Riview of Existing Land Use	205
14.11.2 Proposed Land Use Zoning	205
14.11.3 Road Network Development Plan	208
14.11.4 Drainage Development Plan	208
14.11.5 Urban Services Development Plan of ward no-03	209

14.12 Demographic Conditions of Ward-04.....	211
14.13 Critical Issues and Opportunities of the Ward	211
14.14 Ward Action Plan Proposals	212
14.14.1 Riview of Existing Land Use	212
14.14.2 Proposed Land Use Zoning	212
14.14.3 Road Network Development Plan	215
14.14.4 Drainage Development Plan	216
14.14.5 Urban Services Development Plan of ward no-04	216
14.15 Demographic Conditions of Ward-05.....	219
14.16 Critical Issues and Opportunities of the Ward	219
14.17 Ward Action Plan Proposals	220
14.17.1 Riview of Existing Land Use	220
14.17.2 Proposed Land Use Zoning	220
14.17.3 Road Network Development Plan	223
14.17.4 Drainage Development Plan	223
14.17.5 Urban Services Development Plan of ward no-05	224
14.18 Demographic Conditions of Ward-06.....	226
14.19 Critical Issues and Opportunities of the Ward	226
14.20 Ward Action Plan Proposals	227
14.20.1 Riview of Existing Land Use	227
14.20.2 Proposed Land Use Zoning	227
14.20.3 Road Network Development Plan	230
14.20.4 Drainage Development Plan	230
14.20.5 Urban Services Development Plan of ward no-06	231
14.21 Demographic Conditions of Ward-07.....	233
14.22 Critical Issues and Opportunities of the Ward	233
14.23 Ward Action Plan Proposals	234
14.23.1 Riview of Existing Land Use	234
14.23.2 Proposed Land Use Zoning	234
14.23.3 Road Network Development Plan	237
14.23.4 Drainage Development Plan	237
14.23.5 Urban Services Development Plan of ward no-07	238
14.24 Demographic Conditions of Ward-08.....	240
14.25 Critical Issues and Opportunities of the Ward	240
14.26 Ward Action Plan Proposals	241
14.26.1 Riview of Existing Land Use	241
14.26.2 Proposed Land Use Zoning	241
14.26.3 Road Network Development Plan	244
14.26.4 Drainage Development Plan	244
14.26.5 Urban Services Development Plan of ward no-08	245
14.27 Demographic Conditions of Ward-09.....	247
14.28 Critical Issues and Opportunities of the Ward	247
14.29 Ward Action Plan Proposals	248
14.29.1 Riview of Existing Land Use	248
14.29.2 Proposed Land Use Zoning	249
14.29.3 Road Network Development Plan	251
14.29.4 Drainage Development Plan	251
14.29.5 Urban Services Development Plan of ward no-09	252
14.30 Demographic Conditions of Ward-10.....	255
14.31 Critical Issues and Opportunities of the Ward	255
14.32 Ward Action Plan Proposals	256
14.32.1 Riview of Existing Land Use	256
14.32.2 Proposed Land Use Zoning	257
14.32.3 Road Network Development Plan	259

14.32.4 Urban Services Development Plan of ward no-10	259
14.33 Demographic Conditions of Ward-11	261
14.34 Critical Issues and Opportunities of the Ward	261
14.35 Ward Action Plan Proposals	262
14.35.1 Riview of Existing Land Use	262
14.35.2 Proposed Land Use Zoning	263
14.35.3 Road Network Development Plan	265
14.35.4 Urban Services Development Plan of ward no-11	265
14.36 Demographic Conditions of Ward-12.....	267
14.37 Critical Issues and Opportunities of the Ward	267
14.38 Ward Action Plan Proposals	268
14.38.1 Riview of Existing Land Use	268
14.38.2 Proposed Land Use Zoning	269
14.38.3 Road Network Development Plan	271
14.38.4 Urban Services Development Plan of ward no-12	271
14.39 Implementation Guidelines	273
14.39.1 Tasks of Paurashava Authority.....	273
14.39.2 Institutional Strengthening	273
14.39.3 Role of Municipal Authority	273
14.39.4 Publicity and Circulation of the Plans and Documents	273
14.40 Concluding Remarks.....	273

Annexure

Annexure-A:Land Use Permission

Annexure-B: Road Network Proposal of Singra Paurashava

Annexure-C: Proposed Drain Inventory and Schedule of Major Facilities

Annexure-D: Planning Schedule of Waterbody of Singra Paurashava

Annexure-E: Resolution of Final Consultation Meeting

Annexure-F: Gazette of Singra Paurashava

Appendix

Appendix-1: Structure Plan Map of Singra Paurashava

Appendix-2: Land Use Plan Map of Singra Paurashava

Appendix-3: Transportation and Traffic Management Plan

Appendix-4: Drainage and Environmental Management Plan

List of Tables

Table 3-1:	Population Distribution in Singra Paurashava	15
Table 5-1:	Important provisions of different Acts, Policies and Rules having relevance with the preparation of Paurashava Master Plan	44
Table 6-1:	Population Projection with Density for Singra Paurashava Up to 2031	48
Table 6-2:	Population Projection with Density for Singra Paurashava Up to 2031	48
Table 6-3:	Population Projection with Density for Singra Paurashava Up to 2031	49
Table 6-4:	Existing Working Force for Singra Paurashava.....	50
Table 7-1:	Structure Plan Policy Zoning.....	52
Table 7-2:	Policy for optimum use of urban land resources.....	58
Table 7-3:	Policy for new area development.....	58
Table 7-4:	Area for conservation and protection.....	59
Table 7-5:	Policy for Population Sector	60
Table 7-6:	Policy for Economic Development and Employment Generation	61
Table 7-7:	Housing and Slum Improvement	61
Table 7-8:	Social Amenities and Community Facilities.....	62
Table 7-9:	Policy for Transport Sector.....	63
Table 7-10:	Policy for Utility Services.....	64
Table 7-11:	Policy for Natural Resources	65
Table 9-1:	List of Mouza Maps of Singra Paurashava	74
Table 10-1:	Existing Land use Classification of Singra Paurashava	76
Table 10-2:	Planning Standard Considered for Land Uses	78
Table 10-3:	Estimation of Housing Land Requirement.....	79
Table 10-4:	Estimation of Land Requirement for Commerce and Shopping	80
Table 10-5:	Estimation of Land Requirement for Industries.....	80
Table 10-6:	Estimation of Land Requirement for Education Facilities.....	80
Table 10-7:	Estimation of Land Requirement for Health Facilities	81
Table 10-8:	Estimation of Land Requirement for Administration	81
Table 10-9:	Estimation of Land Requirement for Community Facilities.....	82
Table 10-10:	Estimation of Land Requirement for Open Space/Recreational Facilities.....	82
Table 10-11:	Estimation of Land Requirement for Utilities.....	83
Table 10-12:	Estimation of Land Requirement for Transport and Communication.....	83
Table 10-13:	Proposed Land Use Categories for Urban Area Plan of Singra Paurashava	85
Table 10-14:	New Development Proposal for Low Income People & Old People Rehabilitation.....	87
Table 10-15:	New Development Proposal for Industrial Area	88
Table 10-16:	New Development Proposal for Commercial Facilities.....	90
Table 10-17:	New Land Proposal for Education and Research.....	91
Table 10-18:	New Land Proposal for Open Space	93
Table 10-19:	New Transportation Facilities.....	96
Table 10-20:	New Land Use Proposal for Utility Services	97
Table 10-21:	New Land Use Proposal for Health Services.....	98
Table 10-22:	New Land Use Proposal for Community Facility.....	100
Table 11-1:	Sample Size and Location Number According to Surveys	106
Table 11-2:	Road status in Singra Paurashava	107
Table 11-3:	Roadway Level-Of-Service (LOS) Ratings of Wikipedia	109
Table 11-4:	Existing Level of Service (LOS) of major roads of Singra Paurashava.....	109
Table 11-5:	O-D matrix of surveyed trips of Singra Paurashava	110
Table 11-6:	Trip Purpose according to Mode Use of Singra Paurashava.....	110
Table 11-7:	Width of some Major Roads in Singra Paurashava	112
Table 11-8:	Geometric Road Standard of Roads Proposed by LGED	115
Table 11-9:	Projection of Target Year Traffic Volume.....	116
Table 11-10:	Level of Service of Different Major Roads and their Relative Proposals	117
Table 11-11:	Proposals of Roads Standard in the Project Area.....	117
Table 11-12:	Summery of Road Widening Proposal in Singra Paurashava	120
Table 11-13:	Road Improvement Proposal in Singra Paurashava	120
Table 11-14:	List of Proposed Roads in Singra Paurashava	123
Table 11-15:	List of Proposed Roads in Singra Paurashava	124
Table 11-16:	List of Proposed Roundabout in Singra Paurashava	126
Table 11-17:	Traffic Control Facilities in Singra Paurashava.....	127

Table 12-1: Storage Coefficients for flat land	135
Table 12-2: Modified Rational Method Runoff Coefficients	136
Table 12-3: List of Existing Natural Canals/Khals& River of Singra Paurashava	142
Table 12-4: Ward-Wise drainage Network of Singra Paurashava	143
Table 12-5: Location, start and end of some drains in Singra Paurashava	143
Table 12-6: List of Existing Drains in Singra Paurashava	144
Table 12-7: Summary of Spot Level Data of Singra Paurashava	145
Table 12-8: Characteristics of Land Levels of Singra Paurashava	146
Table 12-9: Land Use Category with Spot Heights (mPWD) in Singra Paurashava	146
Table 12-10: Common Run – off coefficients for Different Types of Area	149
Table 12-11: List of Drains for Proposed Improvement	151
Table 12-12: Proposal of New Drains	152
Table 12-13: List of Construction Criteria and Locations	157
Table 14-2: Proposal of Roads for Ward-01	194
Table 14-3: Proposal of Drain for Ward-01	194
Table 14-4: Proposal for Other Facilities of Ward-01	195
Table 14-6: Proposal of Roads for Ward-02	201
Table 14-7: Proposal of Drain for Ward-02	201
Table 14-8: Proposal for Other Facilities of Ward-02	202
Table 14-10: Proposal of Roads for Ward-03	208
Table 14-11: Proposal of Drain for Ward-03	208
Table 14-12: Proposal for Other Facilities of Ward-03	209
Table 14-14: Proposal of Roads for Ward-04	215
Table 14-15: Proposal of Drains for Ward-04	216
Table 14-16: Proposal for Other Facilities of Ward-04	216
Table 14-18: Proposal of Roads for Ward-05	223
Table 14-19: Proposal of Drain for Ward-05	223
Table 14-20: Proposal for Other Facilities of Ward-05	224
Table 14-22: Proposal of Roads for Ward-06	230
Table 14-23: Proposal of Drain for Ward-06	230
Table 14-24: Proposal for Other Facilities of Ward-06	231
Table 14-26: Proposal of Roads for Ward-07	237
Table 14-27: Proposal of Drain for Ward-07	237
Table 14-28: Proposal for Other Facilities of Ward-07	238
Table 14-30: Proposal of Roads for Ward-08	244
Table 14-31: Proposal of Drain for Ward-08	244
Table 14-32: Proposal for Other Facilities of Ward-08	245
Table 14-34: Proposal of Roads for Ward-09	251
Table 14-35: Proposal of Drain for Ward-09	251
Table 14-36: Proposal for Other Facilities of Ward-09	252
Table 14-38: Proposal of Roads for Ward-10	259
Table 14-39: Proposal for Other Facilities of Ward-10	259
Table 14-41: Proposal of Roads for Ward-11	265
Table 14-42: Proposal for Other Facilities of Ward-11	265
Table 14-44: Proposal of Roads for Ward-12	271
Table 14-45: Proposal for Other Facilities of Ward-12	271

List of Maps

Map 1-1:	SingraPaurashava within Bangladesh	3
Map 2-1:	Location Map of Singra Paurashava within Natore District	10
Map 3-1:	Communication Network of Natore Region showing Connectivity with Singra Paurashava ..	24
Map 4-1:	Existing Road Network Map ofSingraPaurashava	29
Map 7-1:	Structure Plan Zone of SingraPaurashava	53
Map 10-1:	Existing Land Use Map of SingraPaurashava	77
Map 10-2:	Land use Proposal for SingraPaurashava	89
Map 11-1:	Width of some Major Roads in Singra Paurashava	113
Map 11-2:	Proposed Road map of SingraPaurashava	122
Map 12-1:	Contour Map of Singra Paurashava	147
Map 12-2:	Surface Analysis (IDW Method) of Singra Paurashava	148
Map 12-3:	Drainage Plan Map of Singra Paurashava	155
Map 12-4:	A Brief of Solid Waste Management Proposal of Singra Paurashava	170
Map 12-5:	Location of Existing and Proposed Open Spaces of Singra Paurashava	171
Map 13-1:	Proposed Water Supply Network Map of Singra Paurashava	183
Map 13-2:	Proposed Urban Services of Singra Paurashava	185
Map 14-1:	Ward Action Plan of Singra Paurashava	189
Map 14-2:	The Proposed Land Use Zoning Map of Ward-01	193
Map 14-3:	The Proposed Urban Services and Drainage Network Facilities Map of Ward-01	196
Map 14-4:	The Proposed Land Use Zoning Map of Ward-02	200
Map 14-5:	The Proposed Urban Services and Drainage Network Facilities Map of Ward-02	203
Map 14-6:	The Proposed Land Use Zoning Map of Ward-03	207
Map 14-7:	The Proposed Urban Services and Drainage Network Facilities Map of Ward-03	210
Map 14-8:	The Proposed Land Use Zoning Map of Ward-04	214
Map 14-9:	The ProposedUrban Services and Drainage Network Facilities Map of Ward-04	218
Map 14-10:	The Proposed Land Use Zoning Map of Ward-05	222
Map 14-11:	The ProposedUrban Services and Drainage Network Facilities Map of Ward-05	225
Map 14-12:	The Proposed Land Use Zoning Map of Ward-06	229
Map 14-13:	The ProposedUrban Services and Drainage Network Facilities Map of Ward-06	232
Map 14-14:	The Proposed Land Use Zoning Map of Ward-07	236
Map 14-15:	The ProposedUrban Services and Drainage Network Facilities Map of Ward-07	239
Map 14-16:	The Proposed Land Use Zoning Map of Ward-08	243
Map 14-17:	The Proposed Urban Services and Drainage Network Facilities Map of Ward-08	246
Map 14-18:	The Proposed Land Use Zoning Map of Ward-09	250
Map 14-19:	The Proposed Urban Services and Drainage Network Facilities Map of Ward-09	254
Map 14-20:	The Proposed Land Use Zoning Map of Ward-10	258
Map 14-21:	The Proposed Urban Services and Drainage Network Facilities Map of Ward-10	260
Map 14-22:	The Proposed Land Use Zoning Map of Ward-11	264
Map 14-23:	The Proposed Urban Services and Drainage Network Facilities Map of Ward-11	266
Map 14-24:	The Proposed Land Use Zoning Map of Ward-12	270
Map 14-25:	The Proposed Urban Services and Drainage Network Facilities Map of Ward-12	272

List of Figures

Fig 3-1:	Percentage Distribution of Population at SingraPaurashava, 6 Years or Above by Education Level	16
Fig 3-2:	Percentage Distribution of the Household by Monthly Income and Expenditure at Singra Paurashava	17
Fig 3-3:	Future Growth Direction of SingraPaurashava	21
Fig 7-1:	Total Core Area of Singra Paurashava	54
Fig 7-2:	Fringe Area beside Core Area	55
Fig 7-3:	Peripheral Area in South East Corner of SingraPaurashava	55
Fig 7-4:	New Urban Area beside Paurashava Office, and Core Area	56
Fig 7-5:	Agriculture Land spread all over of the Paurashava	56
Fig 8-1:	Scope of Work for Planning Division	68
Fig 11-1:	Flow Chart of the Methodology	106
Fig 11-2:	Bus stand morrIntersection Flow Diagram	108
Fig 11-3:	Primery Road Width 100ft ROW	118
Fig 11-4:	Secondary Road Width 40ft ROW	118
Fig 11-5:	Secondary Road Width 30ft ROW	119
Fig 11-6:	Local/Access Road Width 20ft ROW	119
Fig 12-1:	A sketch showing plot and block drain	137
Fig 12-2:	Bridge and culvert	138
Fig 12-3:	A schematic view of Drainage sluice, pipe sluice and siphon on embankment which relieve drainage congestion	138
Fig 12-4:	Typical Earthen drain	139
Fig 12-5:	A Typical Secondary Drain	139
Fig 12-6:	A Typical Tertiary Drain	140
Fig 12-7:	A Typical Quaternary Drain	141
Fig 12-8:	Temperature characteristics of last 10 years in Singra Paurashava	162
Fig 12-9:	Normal Maximum and Minimum Temperature Characteristics across the year in SingraPaurashava	163
Fig 12-10:	Average Rainfall Characteristics across the year in SingraPaurashava	163
Fig 12-11:	Rainfall Characteristics for last 10 years in Singra Paurashava	164
Fig 12-12:	Humidity characteristics of last 10 years in SingraPaurashava	164
Fig 12-13:	Overview of the Solid Waste Management Plan	168
Fig 14-1:	Flow Chart of Methodology	187

Acronyms

BM	Bench Mark
BTM	Bangladesh Transverse Mercator
CBD	Central Business District
CNG	Compressed Natural Gas
CS	Cadastral survey
DGPS	Differential Global Positioning System
DLRS	Directorate of Land Records and Survey
DPA	Demarcation of Planning Area
DPHE	Department of Public Health and Engineering
GCP	Ground Control Point
GIS	Geographic Information System
GPS	Global positioning system
K.P.H	kilometers Per Hour
K.M.	Kilometer
LGED	Local Government Engineering Department
MSL	Mean Sea Level
O-D	Origin and destination Survey
PCU	Passenger Car Unit
PWD	Public Works Department
RHD	Roads and Highway Department
RTK-GPS	Real Time Kinematics Global Positioning System
SOB	Survey of Bangladesh
TCP	Temporary Control Points
TIC	Tentative points)
TS	Total Station
UTIDP	Upazila Towns Infrastructure Development Project

LOCAL WORDS

Khal	Canal
Tempo	Human hauler
Bazar	Trade Center
Hat	Weekly an occasional Market
Paurashava	Municipality

Chapter 1: Introduction

1.1 General

Urbanization in Bangladesh is moving at a rapid pace. Between 1961 to 1981, the average urban growth rate was 8%. The present average growth rate is about 4.5%. According to the population census of 2001, the share of urban population was about 23.29% and at present it is approximately 25%. By the year 2015, the share of urban population will be about 37% of the national population. The importance of urban development is emphasized in terms of its role in the national economy. More than 60% of the national GDP is derived from the non-agricultural sectors that are mainly based in urban areas. Again, the most foreign exchange earning sectors, like, garment and knitwear enterprises are agglomerated in urban areas. These sectors earn over 70% of the foreign exchange. Remittance is also a major sector of foreign exchange earnings and a large share of the remittance goes into the purchase of urban land. Surplus remittance is invested in business and manufacturing located in urban areas. These phenomena indicate the increasing role of urban areas being played in the national economy. The expansion of urban economy leads to the growth of urban population and concomitant haphazard urban spatial growth without planning. The rapid urbanization is marked by the creation of Paurashavas, whose number at present stands at 318. Paurashavas are created not only to provide urban services to their citizens, but also to create a livable environment through development of planned and environmentally sound living space.

The present infrastructure provisions in the Paurashavas are in a precarious state. Drains are mostly clogged that cannot drain out water during heavy rains and natural drainage systems have either been filled up or occupied by land grabbers creating water logging during monsoon. Traffic in Paurashavas is increasing day by day with the increase in population and demand. But the sub-standard road network cannot keep pace with the growing demand for movement. As a result, congestion becomes a common problem. Road networks are not developed in planned and systematic way leaving room for traffic congestion that increases economic loss to the people due to travel delay. The land use development in the Paurashavas is unorganized and unplanned, which is a major source of environmental deterioration. Building Construction Rules are not effectively enforced in the Paurashavas mainly for want of a well formulated Master Plan and qualified planning professional.

Under the above circumstances, it is high time to think about solving the problems of the Paurashavas that might otherwise be emerged critically in the future. To overcome all likely problems to come in future, the Paurashavas should go for planned development through preparation and implementation of a Master Plan. The Master Plan can be prepared exercising the power conferred to them by the Paurashava Ordinance 2009. The Upazila Town Infrastructure Development Project (UTIDP) aims to prepare Master Plan for 223 Upazila level Paurashavas and Kuakata Tourism center under 12 packages for a period of next 20 years. The project has provisions for separate plans for land use control, drainage and environment, traffic and transportation management and improvement. The project also aims to prepare a Ward Action Plan (WAP) to ensure systematic execution of future infrastructure development projects. There is

also aim to prepare proposals to enhance Paurashava revenue so that it becomes more capable to meet its own capital needs.

Of the total 223 Paurashavas Singra is one of 20 Paurashavas within Natore Region under Package 09. The location of Singra within Bangladesh is shown in **Map 1-1**.

Map 1-1: SingraPaurashava within Bangladesh

Thus the Master Plan of SingraPaurashava suggests for the development of urban infrastructure, such as new roads and bridges/culverts, drainage facilities, street lights, markets, bus stands, solid waste management, sanitation, water supply, community facilities and other such infrastructure in order to equip the Paurashava to face future challenges of urbanization and economic regeneration. The Master Plan will initially focus on growth and development, social integration and environmental improvement following principles of sustainable development.

1.2 Philosophy of the Preparation of Master Plan

The philosophy behind preparation of Master Plan of the Upazila level Paurashava lies in the very motive of providing community welfare through a process of spatial organization, socio-economic rejuvenation, environmental improvement and provision of amenities to the present and future generations. The Master Plan aims for rational use of scarce land resources for concentrated development at urban scale following the principles of sustainable development.

1.3 Objectives of the Master Plan

As per the Terms of Reference (TOR), the objectives of the preparation of Master Plan of SingraPaurashava are to:

- a) Find out development issues and potentials of the SingraPaurashava and make a 20-year development vision for the Paurashava and prepare a Master Plan in line with the vision for the development;
- b) Plan for the people of SingraPaurashava to develop and update provisions for better transport and communication network, housing, roads, markets, bus terminals, sanitation, water supply, drainage, solid waste management, electricity, education, leisure and such other infrastructure facilities for meeting the social and community needs of the poor and the disadvantaged groups for better quality of life;
- c) Prepare a multi-sector short and long term investment plan through participatory process for better living standards by identifying area based priority-drainage master plan, transportation and traffic management plan, other need specific plan as per requirement in accordance with the principle of sustainability;
- d) Provide controls for private sector development, with clarity and security in regard to future development;
- e) Provide guideline for development considering the opportunity and constrains of future development of the Upazila Town; and
- f) Prepare a 20-year Master Plan to be used as a tool to ensure and promote growth of the SingraPaurashava in line with the guiding principles of the Master Plan and control any unplanned growth by any private and public organization.

1.4 Approach and Methodology

The UTIDP Project is aimed for substantial development of infrastructure and services for the Paurashava with optimum provision of opportunities for Paurashava dwellers and making scope for extending services to surrounding areas.

The current project is preparing a Master plan of the Paurashava, where the existing condition and different problems are identified, studied and analyzed and the probable solutions are to be sought

to ameliorate the same. The study moves through a process of data collection-analysis and fixation of objectives for planning. The approach is based on field survey for data collection and collection of information from secondary sources. The data is presented through maps, text and tabular form. Then the survey report and maps are prepared and submitted. Analysis of collected data is carried out to identify the nature and extent of problems prevailing in the Paurashava in order to fix the objectives of the actions to be undertaken in the form of planning and the interim report prepared and submitted. Through the process, involvement of the stakeholders has been ensured to make the planning as much sustainable as possible. For this purpose, continuous formal and informal discussions and meetings have been carried out throughout the project period using participatory approach. The discussions serve two purposes, first, a sense of belongingness develops within the minds of the stakeholders, particularly among the citizens, about the master plan to be prepared, and secondly, identification of problems and finding their solutions become easier with the participation of stakeholders, as the local stakeholders are more knowledgeable about local problems and possible solutions of those problems.

After doing all these jobs thoroughly the Master Plan had been done based on a prepared planning standard for Paurashava level town and formulating future strategies for the corresponding area. Again after final consultation with the stakeholders on the prepared plan the Final Master Plan has to be completed.

1.5 Scope of Work

The scope of work under this consultancy services covers all aspects related to the preparation of Master Plan, which includes Land Use Plan, Transportation and Traffic Management Plan, Drainage and Environmental Management Plan and Ward Action Plan for the proposed Paurashava. In order to prepare these plans, the activities contain but not limited to the following:

1. Visits have been made to the Paurashava at different stages of work of the preparation of Master Plan of SingraPaurashava.
2. Feasibility for preparation of Master Plan has been submitted to the office of the PD, UTIDP.
3. An Inception Seminar has been organized at the Paurashava level to inform the Paurashava about the scope and Terms of Reference for the preparation of Master Plan. A thorough investigation has been made based on potential scope and opportunities available in the Paurashava to develop a 20 year development vision to link up the ideas and view of the Paurashava people.
4. Determination of the study area and planning area has been done based on existing condition, demand of the Paurashava and potential scope for future development. A detailed survey has been conducted on the existing conditions of socio-economic, demographic, transportation and traffic, physical features, topographic, and land use of the Paurashava area following the approved format and data have been collected from primary and secondary sources. Analysis of such data and information has been carried out to find out the possible area of intervention to forecast future population of the Paurashava (15-20 years), vis-a-vis assess their requirement for different services, such as physical infrastructure facilities, employment generation, housing, right of way and land requirement for the existing and proposed roads, drains, playgrounds, recreation centers

and other environmental and social infrastructure. The following major tasks have been accomplished:

- a. Identification and investigation of the existing natural and man-made drains, natural river system, the extent and frequency of floods, area of planning intervention have been done. Other works include study of the contour and topographic maps produced by the relevant agencies and review of any previous drainage Master Plan available for the Paurashava.
- b. A comprehensive (storm water) Drainage Master Plan for a plan period of 20 years has been prepared considering all relevant issues including discharge calculation, catchments areas, design of main and secondary drains along with their sizes, types and gradients and retention areas with preliminary cost estimates for the proposed drainage system.
- c. Recommendations have been made on planning, institutional and legal mechanisms to ensure provision of adequate land for the establishment of proper rights of way for (storm water) drainage system in the Paurashava.
- d. Collection and assessment of the essential data relating to existing transport Land Use Plan, relevant regional and national highway development plans, accident statistics, number and type of vehicles registered for each Paurashava have been made.
- e. Assessment has been made on the requirements of critical data and data have been collected through reconnaissance and traffic surveys, which should estimate present traffic volume, forecast the future traffic growth, identification of travel patterns, areas of traffic conflicts and their underlying causes.
- f. Study has been conducted on the viability of different solutions for traffic management and development of a practical short term traffic management plan has been accomplished, including one way systems, restricted access for large vehicles, improved signal system, traffic islands, roundabouts, pedestrian crossings, deceleration lanes for turning traffic, suitable turning radius, parking policies and separation of pedestrians and rickshaws etc.
- g. Assessment has been done on the non-pedestrian traffic movements that are dominated by cycle rickshaw. Special recommendations should be made as to how best to utilize this form of transport without causing unnecessary delays to other vehicles. Proposals should also consider pedestrians and their safety, with special attention for the children.
- h. Assessment has been made on the current land use with regard to road transportation, bus & truck stations, railway stations etc, and recommendations to be provided on actions to optimize this land use.
- i. Preparation of a Road Network Plan based on topographic and base Map prepared under the Project. Recommendation has been made on the road development standards, which serve as a guide for the long and short term implementation of road. Also Traffic and Transportation Management Plan and traffic enforcement measure have been suggested.

- j. Preparation of the Master Plan with all suitable intervention, supported by appropriate strategic policy, outline framework, institutional arrangement and possible source of fund for effective implementation of the plan.
- k. Preparation of a plan has been set out proposed Master Plan at 3-levels namely Structural Plan, Urban Area Plan and Ward Action Plan.
- l. At the first level, policies and strategies have been worked out for the preparation of a Structure Plan for each Paurashava under the package. The Master Plan has been prepared consisting of Structural Plan, Land Use Plan, Transportation and Traffic Management Plan, Drainage and Environmental Management Plan and Ward Action Plan.
- m. A total list of primary and secondary roads, drains and other social infrastructures for each Paurashava for a plan period of next 20 years has been made. Examining and classifying according to the existing condition, long, medium and short term plans have been proposed and estimated cost for improvement of drain and road alignment and other infrastructures have been prepared.
- n. In line with the proposed Master Plan, a Ward Action Plan has been proposed with list of priority schemes for the development of roads, drains, traffic management and other social infrastructures for implementation during the first five years of plan period.
- o. With the help of concerned Paurashava, at least 2 public consultation meetings or seminars have been organized, one for discussion on Interim Report and the other on Final Report on the proposed Master Plan. Beneficiary's point of view has been integrated in the plan with utmost careful consideration.
- p. Preparation and submission of Master Plan and Report with required standards as per the TOR.

1.6 Organization of the Master Plan Report

The Master Plan Report is organized in three major parts with an introduction at the beginning. The three major parts contain various components of work under the UTIDP of LGED. The three major parts of the Master Plan of SingraPaurashava are as follows:

INTRODUCTION: It describes the ToR of the UTIDP, philosophy and objectives of the Master Plan, methodology and scope of the work and organization of the Master Plan Report.

PART – A: The Structure Plan sets the conceptual framework and strategies for planned development of the Paurashava based on its potentials for next 20 years up to 2031.

PART – B: Urban Area Plan includes i) Land Use Plan; ii) Transportation and Traffic Management Plan; iii) Drainage and Environmental Management Plan; and iv) Proposals for Urban Services.

PART – C: Ward Action Plan presents ward wise detailed proposals for implementation within first five years of the Master Plan period of 20 years.

Chapter 2: Introduction to Structure Plan

The Master Plan Report is the fourth of the series of the reports to be submitted as per the ToR of the project “Upazila Town Infrastructure Development Project - Preparation of SingraPaurashava Master Plan (Structure Plan, Urban Area Plan and Ward Action Plan)”. Part A of this report describes the Structure Plan of SingraPaurashava and Chapter -2 describes the conceptual issues related to the preparation of Structure Plan for SingraPaurashava.

2.1 Background of the Paurashava

As per the Local Government (Paurashava) Act 2009, the Paurashavas in Bangladesh are categorized mainly into A, B, and C classes based mainly on annual income of the Paurashava. There is also a separate category called “Special Class”, basically for industrial and commercial hubs of Narayanganj and Tongi within the Dhaka Metropolitan Development Area (DMDA).

Singra is a A-category Paurashava with an area of 10.94 sq. km (2703.74 acre) that was established in 1999 with 12 wards following the Paurashava Ordinance 1977. It is bounded on the north by Nandigram Upazila of Natore district and Raninagar Upazila of Naogaon district, on the east by Tarash Upazila of Sirajganj district and Sherpur Upazila of Sirajganj district, on the south by Gurudspur Upazila, and on the west by Atrai Upazila of Naogaon district. The location of Singra within Natore district is shown in **Map 2-1**.

Singra Paurashava is the urban center in the Singra Upazila. Not much known about origin of the name of the Paurashava. The Upazila occupies an area of 528.46 sq. km. It is located between 24°24' and 24°41' north latitudes and between 89°03' and 89°20' east longitudes. Natore region is characterized by high and low lands.

Singra is located within the flood plain of Atrai River. The Atrai and Gurnai rivers are of hydrographical importance of the area, which are more or less moribund. During the rainy season, these moribund rivers act as excellent drainage channels draining of a large volume of water and have a strong current.

Singra falls within the undulated Barind Land. The level of undulation ranges from 1 to 5 meters. Ward 8 covering Singra mouza are found as the most elevated area of the Paurashava. The town center of the Paurashava is comparatively elevated and not subject to annual flooding. Flooding in the area usually occurs due to the over flow of the River Atrai, the Gurnai. In recent years, the severe flooding was occurred in 1988 and 1998. Duration of the flooding was more than 2 months and flood level was 1 to 3 meters above the surface. The extensive peripheral areas of Paurashava jurisdiction are comparatively low and are flooded each year during the monsoon. There exist a small number of unsanitary pools, kharis (canal), ditches and filth within the Paurashava. These depressions serve as catchments basin and help in reducing the flood intensity and also mitigate the flood damages during and after heavy rainfall in the monsoon period. Most of the buildings within the town are constructed in normal height but the houses outside the urban areas are mostly constructed on the elevated land of 3 and 4 meters above natural ground level to keep them free from annual flooding.

2.2 Vision of the Structure Plan

The vision of the plan is the creation of an urban livable environment, where people irrespective of their socio-economic, demographic and religious identities can live and enjoy today within affordable means without sacrificing interests of tomorrow. The implementation of Master Plan of the Paurashava will translate this vision into reality.

Map 2-1: Location Map of Singra Paurashava within Natore District

2.3 Objectives of the Structure Plan

To guide long term growth within the Structure Plan Area by means of demarcation of the future growth areas and indication of potential locations of major development areas includes: a) indication of important physical infrastructure; and b) setting out policy recommendations for future development. According to the Terms of Reference, the objectives of SingraPaurashava Structure Plan are:

- Description of the Paurashava's administrative, economic, social, physical environmental growth, functional linkage and hierarchy in the national and regional context; catchments area; population; land use and urban services; agencies responsible for different sectoral activities, etc.
- Identification of urban growth area based on analysis of patterns and trends of development, and projection of population, land use and economic activities for next 20 years.
- Identification and description of physical and environmental problems of SingraPaurashava.
- Discussion of relevant policies to analyze and find out potential scopes for the use in the present exercise and also find out constraints and weakness of the existing policy to suggest appropriate measures for the development and management of SingraPaurashava.
- To provide land use development strategies.
- To provide strategies and policies for sectoral as well as socio-economic, infrastructural and environmental issues of development.
- To discuss about implementation issues including institutional capacity building and strengthening of Paurashava, resource mobilization etc.

2.4 Concepts, Content and Format of the Structure Plan

Concept

Structure Plan is a kind of guide plan, or framework plan, or an indicative plan that is presented with maps and explanatory texts in a broader planning perspective than other components of Master Plan. Structure Plan indicates the broad magnitudes and directions of urban growth, including infrastructure networks, the placement of major facilities such as hospitals and upazila complex. A Structure Plan is not intended to specify detailed lot by lot land use or local road configurations and development proposals. Rather it identifies the areas where growth and change are such that more detailed local and action plans are needed. Structure Plan does not require excessive effort in gathering data and it is flexible and dynamic and can be changed to accommodate demanded changes. The present Structure Plan is an overall long term strategic plan for the Paurashava Shahar (Town), Singra.

Structure Plan is the 1st component of the Master Plan package. The other two lower level components are Urban Area Plan and Ward Action Plan. Structure Plan lays down the framework of the future plan including strategy and the sectoral policies. The Urban Area Plan and the Ward Action Plan detail out development proposals under the framework of Structure Plan. The extended area was selected in consultation with the Paurashava for possible extension of the Paurashava. But no development proposals are suggested for the extended part as existing Paurashava area is enough to accommodate population and services during Structure Plan period, that is, up to the year 2031.

Content and Format of the Structure Plan

The Structure Plan is an indicative plan that gives a brief on the future development of an area with policy guidelines. It is a long-term plan with flexibility in the sense that it sets down a broad framework for future development, but not the details. The format of a Structure Plan comprises written document and indicative major development locations presented in maps and diagrams as parts of the report. The written text analyses the issues that are not possible to be presented as diagrams, drawings and maps. Therefore, the written document is as important as the physical plan and diagrams and should be read in conjunction with each other.

2.5 Duration and Amendment of the Structure Plan

The Structure Plan is to remain valid for a period of 20 years from the time of its approval that is up to the year 2031. Structure Plan can contain two Urban Area Plan for the time period of 10 years each and four Ward Action Plan for the time period of 5 years each.

2.6 Structure Plan Area

The total area of Singra Structure Plan is 2703.74 acres (10.94 sq km) that include total area of SingraPaurashava, and there is no extended area in the structure plan of SingraPaurashava. All the 12 wards of the Paurashava are covered by Structure Plan area.

Chapter 3: Existing Development Status of SingraPaurashava

This chapter of the report makes a review of the various issues related to existing growth trend of the Paurashava and unveils its problems. The existing scenario in development status concerning socio-economic, physical infrastructure and environment are presented in the following paragraphs.

3.1 Social Development

Development is a dynamic issue. Measurement of social development essentially requires time series data. Consultant collected recent data of the project area by means of sample survey (5% of total households) with no reference to previous situation. Population census reports are the only sources of information for Paurashava level data, but they cover only a selected number of issues that are not sufficient to make a qualitative judgment of social improvement. It makes a review of social development based on available population census data of 2001 and 2011 and presents the current situation using the sample socio-economic survey data. This social review indicates positive social development in SingraPaurashava. As per household survey, present average household size of the Paurashava is 4. This indicates the success of family planning programme at SingraPaurashava though the national average (4.8). Success is also achieved in education sector. Literacy rate was raised to 56.82% in 2011 from 47.9% in 2001 and only 39.2% in 1991 according to BBS data. The employment situation is also slightly improved in this Paurashava.

3.2 Economic Development

Economic activity is the lifeblood of any urban centre. The higher is the economic activity, the higher will be the level of employment and consequent physical growth. So, before going for a development plan, it is necessary to assess the current level, constraint and prospects of economic activities of the Paurashava.

The principal criterion to judge the economy of an urban centre is to learn about its main sources of employment. Besides, the number of productive enterprises and tertiary level activities are also the indicators of the pattern and level of economic activities in any area. Although 65.40 % of the Paurashava area is under agriculture only 42.46% are farmers and about 25.77% is engaged in business according to BBS, 2001. So a fair portion of people is engaged in agriculture for their livelihood. About 0.75% are engaged in public and private sector services. About 2.39% are labourers and small income earner professionals. And rest 31.39% is not engaged in formal earning activities. So, the economic picture of the Paurashava has a potentiality.

3.2.1 Economic Activities

Economic activity is the lifeblood of any urban centre. The higher is the economic activity, the higher will be the level of employment and consequent physical growth. So, before going for a development plan, it is necessary to assess the current level, constraint and prospects of economic activities of the Paurashava.

The principal criterion to judge the economy of an urban centre is to learn about its main sources of employment. Besides, the number of productive enterprises and tertiary level activities are also the indicators of the pattern and level of economic activities in any area. Existing 65.40 % of the Paurashava area is under agriculture where 42.46% (BBS-2001) are farmers in the project area. So a fair portion of people is engaged in agriculture for their livelihood. About 0.75% are engaged in public and private sector services. About 23.98% are involved with business activities. And rest 31.39% is not engaged in formal earning activities.

Industry

Except some small scale processing units, there is virtually no manufacturing, as such, in the Paurashava. The town actually has no strong industrial base. There are a number of rice processing units and saw mills in the town that may grow in the future, and should choose suitable locations in the Master Plan.

Commerce

The commercial activities in the Paurashava are dominated by retail small business. The Singra bazar located at in 5 & 8 of the Paurashava. The retailers mostly collect their goods from this bazar, which is also the largest wholesale market.

Services

In Singra Paurashava, total output of the service sector consists of the public administration and defense; storage and communication; financial intermediations; education; renting and business activities; health, community, social work; and social and personal services activities. According to BBS 2001, 2.05% households found depend directly on services, as the main source of income. And according to socio-economic survey about 5.45% household are engaged in private service. Nationally the share of the services sector to GDP growth is 53.4% in FY 2010 which was 52.6% in FY 2009 and 50.0% in FY 2008 (State of the Bangladesh Economy in FY 2010-11, P-65).

Agriculture

According to BBS 2001 reveals that about 42.46 percent of the income earners in the Paurashava are engaged in farming occupation. Besides about 23.98% are small business living in the Paurashava (BBS, 2001). The farmers and farm laborers work in farm lands, both, within and outside the Paurashava. It is evident from land use survey of the Paurashava that about 65.40% of the Paurashava lands are still under agriculture.

Agro-based

As the Paurashava is mostly rural in nature at present, with effective agricultural extension services, the agricultural output can be increased many times to serve the agro-based industries in future. In this backdrop, the major challenge is to strike a balance between urbanization and maintenance of rural nature of the project area.

Informal Sector Economic Activities

Informal sector study was not a part of ToR, so the consultant did not conduct any formal study on the informal sector. It can be considered that the informal sector characteristics at upazila level Paurashava are same all over Bangladesh. It is more prominent, where the concentration of

people takes place. Informal sector is a part and parcel of urban economy in developing countries. They have small capital and are usually self-employed. In Singra, the concentration of informal businesses is found around the bazar area, transport terminal and stoppage areas and also near the Upazila Complex.

3.2.2 Existing Employment Pattern

Out of the employed male population, More than 23.98 percent is engaged in business. Since secondary sector employment is seriously lacking in the town, people move to self-employment like small business. Trading has not been found feasible as employment in the town, mainly, because of lower level of affordability of the people powered by remittance they receive from abroad regularly. About .6 percent of the working force is unemployed. The scenario is unlikely to change unless there is any major investment in the industrial sector that can pool a large number of workers and render the local economy more vibrant services.

According to BBS 2001, 2.05% are employed in government/autonomous organizations. It is unlikely that public sector jobs will show any major improvement in future. But with the increase in business, and industry there is possibility that private sector jobs will show further increase.

Small business is an important source of income in this region. About 23.98% of the Paurashava households get involves in this sector.

3.3 Population

According to BBS 2011, the total population of SingraPaurashava was 16569 and the density of population was 797 persons/ sq.km with an annual growth rate of 2.36. At Present, Ward 03 is the most densely populated area. The density per sq.km is 1445 in this Ward, followed by 1289 in Ward no. 01 and 917 for Ward no. 04.

Table 3-1: Population Distribution in Singra Paurashava

WARD NO	Area (in sq. km)	Population 2001 (BBS)	Density (persons/ sq.km)	Population 2011	Density (persons/sq.km)
WARD-1	0.57	2316	4056	2952	5170
WARD-2	1.83	2299	1257	2705	1479
WARD-3	0.92	2223	2406	2932	3174
WARD-4	1.21	3241	2679	4734	3914
WARD-5	0.21	1807	8499	1909	8979
WARD-6	2.11	2443	1157	2414	1143
WARD-7	0.78	2554	3279	2742	3520
WARD-8	0.50	3259	6512	4730	9451
WARD-9	1.12	2453	2200	3343	2998
WARD-10	0.26	-	-	1248	4751
WARD-11	0.70	-	-	2041	2917
WARD-12	0.73	-	-	1442	1984
Total	10.94	22595	2252	33192	3034

Sex Ratio

The average sex ratio (males per 100 females) for the project area is 100: 105, slight lower than the national average (100:106).

Again, percentage of elderly (65+) male population is much higher than the percentage of elderly female population. In the total population, however, the male population outnumbers the female population. These are some interesting information that can be observed from sample household survey at SingraPaurashava.

Marital Status

The percentage of married and unmarried population is almost equally distributed. A negligible percentage of population is widow or widower. There is no respond of divorce, which is a good social aspect for the Paurashava.

Religious Status

Religious composition of population has various implications for area planning and overall welfare of the population. Almost 89.68 percent people of the study area belong to the Muslim community followed by only 10.29 percent Hindu.

Education

The following Table shows the Level of Education of respondents in Singra Paurashava. From the Table7.8 it is seen that about 16.35%respondents have education level of class I-V, 14.74% have education level of class VI-X,20.83% have education level SSC, 8.01% of have education level of HSC,8.65% of have education level of BSS. About 29.49% people are illiterate in Singra Paurashava. According to the Census report 2001, literacy rates in Singra Paurashava were 52.90% for males and 42.60% for females. However, from the socio-economic survey it is found that the literacy rate in Singra Paurashava is about 70.51% which is much higher than previous record. This indicates that over the last decade the literacy rate has increased to a great extent.




Fig 3-1:Percentage Distribution of Population at SingraPaurashava, 6 Years or Above by Education Level

Monthly Income and Expenditure of the Household

According to socio economic survey,It reveals that only 0.32% households have income level below 3001TK; 5.45% households have income level between 3001 to 5000 TK; 43.91% households have income level between 5001 to 7000TK; 24.36% households have expenditure level between 7001 to 10000 TK and only 25.96% households have income more than 10000TK. From the table it appears that the most of the people in this Paurashava are of middle income group. Income and expenditure level is given in **Fig 3-2**.




Fig 3-2:Percentage Distribution of the Household by Monthly Income and Expenditure at Singra Paurashava

It reveals that 0.3%households have expenditure level below 3001TK; 17% households have expenditure level between 3001 to 5000 TK; 44.2% households have expenditure level between 5001 to 7000TK; 17.3%households have expenditure level between 7001 to 10000 TK and 21.2%households have expenditure more than 10000TK.

Migration pattern

In this Paurashava there is no significant migration scenario. Only 6household out of total sample have been found migrated in this Paurashava. And they migrated in this Paurashava due to river bank erosion.

3.4 Physical Infrastructure Development

Buildings and Structures

SingraPaurashava has mainly grown following the major transport networks. Buildings and structures developed are based on road network system of the Paurashava. The highest percentage of structures is katcha (64.94%), followed by the semi- pucca structures 27.44%, and the rest 7.62% structures are pucca. It is revealed from the survey that 66.98 percent residential structure of the area is katcha, 27.60% is semi-pucca and 5.42%is pucca. Ward-no. 08 (12.55%) have the highest percentage of pucca houses and the lowest concentration (2.15%) of residential structures are found in Ward No. 12.

In SingraPaurashava it is found that, in case of Pucca structures, about 97.91% structures are single storied. Ward no. 08 have some two-storied and three-storied structures. On the other hand, for commercial structures, most of the structures are pucca and semi-pucca and are distributed over only a few wards. There are only 676 structures that are used for commercial activity.

In this Paurashava it is found that about 0.25% structures (25) are used for Governmental institution. It can be noticed that these governmental offices are located in wards in 1, 4, 5, 6 and 8. Paurashavas education, health, recreation, commercial and automobile facilities are mainly located in the Ward nos. 04, 05 and 01.

Transport and Communication

The three four roads coming from four different directions meet together at the bus stand morr and pass through the town. The roads coming from different places are; Singra-Natore, Singra to Natore, Singra to Kalon and Singra- Tajpur road. Total length of roads in the Paurashava is 62.77 km; Length of katcha road is 18.86 km, semi-pucca 4.19 km and pucca road 39.71 km within the Paurashava area. In this Paurashava there are some LGED roads. Singra-Gurudaspur roads, TNT road etc are main roads in this Paurashava which is owned and maintained by LGED. The Paurashava has one formal bus terminal, but it has one bus stand and one informal Nasimon stand. Land beside Natore-Bograroad and roadsides are being used for parking. Natore-Bogra road is the only RHD road in singra Paurashava.

Within the Paurashava there exits no rail way network but have a provision of waterway network.

3.5 Utility Services

The following paragraphs present the existing condition of utility services in the Paurashava.

Electricity

In SingraPaurashava there is electricity connection. The survey finding shows that there are 464 electric poles within the Paurashava area. In SingraPaurashava there is an electric substation. Map 3.11 shows the location of electric poles in SingraPaurashava. In ward no 8 there is the highest number of electric pole and in ward no 12 there is the lowest number of electric pole in SingraPaurashava. The people of the Paurashava complained that they face severe problem of load shedding.

Water Supply

In SingraPaurashava, there are mainly two ways of water supply facilities. These are tube-well and piped water supply. In this Paurashava the main source of water supply is tube-well. About 88.02% people use tube-well for their water source. This piped water supply(1.45%) covers Upazila Parishad, Government quarter, market area and households along the main road only. The piped water supply covers only a small portion in the ward 8.

Telecommunication

As a Paurashava, telephone network exists in SingraPaurashava. According to survey, the Paurashava accommodates 11 telephone poles. It has been found that that in ward no 7 there is highest number of telephone pole.

Solid Waste Management

According to the Paurashava authority, in this Paurashava there are 10 permanent dustbins and there are 17 temporary dustbin for solid waste dumping, which are located in different place. The Paurashava does not collect waste from household. About 15-17 tones of solid wastes generate daily in Singra Paurashava.

Gas Supply

The Paurashava has no gas supply facility at present.

Drains

It has been found that the entire drains of Singra Paurashava are Pucca. The field survey indicates that there is moderate amount of drainage in Singra Paurashava. In this Paurashava, there is 4.20 km drain and the no. of drain is 40.

3.6 Environmental Issues

Surface water of ponds, canals and rivers at Singra is observed to be fresh and free from salinity. Water Development Board has taken a project to protect the Paurashava from river erosion by constructing embankment. With the development of a planned drainage system some environmental problem will be minimized.

Paurashava authority has taken initiative to reduce surface water pollution. At present, 60.40% (BBS-2001) inhabitants of the Paurashava use sanitary latrine.

From the overall survey findings, it has been revealed that the inhabitants of the Paurashava do not face any severe environmental problem. The problems that exist here can be mitigated through proper planning of the Paurashava.

The urban environment of Singra Paurashava includes both built and natural environment. Urbanization has increased some hazards on natural environment. Where the built environment overburdens the natural environment urban development cannot be sustainable. The urbanization is vital for country's economic growth. Urban centers concentrate services, infrastructure, labor, knowledge, entrepreneurship and markets. Cities and towns are key generators of economic activities. The urban economies are critically important in national economic growth and of development goal. Urbanization is unavoidable. So in every phase of planning processes, all these environmental issues shall be evaluated and proper measure shall be taken to minimize the adverse environmental impacts on land pollution, water and air quality, biodiversity resources and marine resources by energy usage, transport network, waste management, slum improvement, disaster etc. The town of Singra is no different from other towns of Bangladesh, but as disasters are concerned it is moderately vulnerable to at least one disaster and it is flood. Some areas of the Paurashava are subject to water logging. Some part of ward 5 & 8 and Singra Bazaar area experience little drainage problem. Singra Paurashava is not normally affected by flood from the adjacent rivers. But the Paurashava is almost regularly affected by the storm water during monsoon period due to the inability of the existing drainage system to cope up with the situation. The existing drains cannot discharge the huge volume of storm water efficiently to the defined out falls. Because of prevailing such situation, local flooding occurs in many places of the Paurashava.

3.7 Institutional Capacity

The implementation of the Master Plan will require strengthening of the capacity of the Paurashava Authority. Although the capacity building is going in different ways by the government, the institutional capacity building for implementing the Master Plan of the Paurashava has not yet been seriously considered. This will be an important task for the government to restructure the organogram and include the required technical staff with appropriate job description for addressing the issues of implementing the Master Plan.

Existing Manpower

According to Paurashava manual, there should have been 130 officials and staff engaged in a “A” class Paurashava to manage the engineering, administrative, health, family planning, and conservancy works within the Paurashava area. In the organogram, Mayor is the head of the institution. Chief Executive Officer coordinates the three major divisions. These divisions are Engineering (headed by executive engineer), Administrative (headed by Secretary), and Conservancy, Health and Family Planning (headed by Health Officer). In this organogram, both full time and contractual officials are included.

Existing manpower scenario of SingraPaurashava is not so good. There is acute shortage of manpower in each section of the Paurashava. The important posts lying vacant are the Posts of Executive Engineer, Chief Executive Officer and the Town Planner; though in the “A” class Paurashava there is no options for the post of Town planner. Though a standard ‘A’ class Paurashava comprises of 68 personnel in Engineering Department, but SingraPaurashava has not sufficient personnel in Engineering Department.

Paurashava Town Planning and Implementation Capacity of Master Plan

At present, the Paurashava has no town planning department or any appropriate manpower, especially Town planner to prepare or implement town plan. The existing capacity of the Paurashava is seriously inadequate to implement the Paurashava Master Plan. The Paurashava must strengthen its capacity to implement its Master Plan, when it is completed by employing requisite manpower.

Conservancy and Health Services

Conservancy service of SingraPaurashava is also very poor. Paurashava has no fixed waste dumping land. The waste collection and dumping is operated in traditional way. Conservancy department of the Paurashava is not established yet. Staffs are recruited on contract basis to convey the work of conservancy service. There is no community based organization (CBO) for introducing house to house waste collection system in the Paurashava.

There is an Upazila Health Complex and clinic exists in the Paurashava area. People are supposed to go Singra Upazila Health Complex for treatment.

Logistic Support/Equipment

According to the Paurashava manual, a “A” class Paurashava should get logistic support/equipment to continue the work properly. This includes one jeep, one road roller (5-7 ton), two trucks/tractors, two motor cycles, three bicycles (according to the needs of the Paurashava), one mixture machine, one type writer machine, one photocopier machine and one duplicating

machine. SingraPaurashavagot almost all of these logistic supports from the government, except the jeep and truck/tractor. Additionally, they have one Computer and printer for official support.

3.8 Urban Growth Area

In the project area, urban development is taking place along both sides of the Natore-Bogra road from west to east. Development pressure is high at the surrounding areas of bus stand morr. This road is experiencing rapid change with development of residential settings.

The future growth potential of SingraPaurashava is high. Recent trend in population increase indicates that high population density will not be a big problem in this Paurashava. However, it is obvious, and more likely that the growth of this Paurashava will follow natural increase and a little migration in population.

Analyzing the existing structure of the Paurashava and other growth factors it is expected that the future growth direction will occur in south-east direction, along Singra-Natore Road. Several factors will lead such future growth direction.

In the south-east direction, along the main road the area have More urban characteristics with More urban facilities compared to north-south part of the Paurashava, Middle part is More developed and have More urban and civic facilities compared to other part. In the Middle part of the Paurashava there exists Upazila Headquarter; and other urban areas, which is much More developed that the existing Paurashava.

The main road which passes the Paurashava meets important urban areas like Natore and Natore in west-east direction. West-east part of the Paurashava is not much likely to physical expansion.




Fig 3-3:Future Growth Direction of SingraPaurashava

3.9 Catchments Area

It is widely recognized that there is a strong interdependence of social, economic and environmental development between rural and urban areas. The cities and towns play an

important role in rural development as markets for their goods and products, and also as the sites for food processing and other agricultural related activities, and as source of non-farm income, especially from wage labour. On the other hand, urban areas rely on rural areas for food production, labour, and raw materials for manufacturing and markets for their products. This linkage is stronger in small town like the Paurashavas, primarily due to their proximity to the surrounding rural hinterland. People of the catchment areas can access public service offices and hospitals in the towns with less difficulty than offices in cities, while schools and other facilities serve a large number of the catchment area population, contributing significantly to rural development.

The adjacent Singra and Tanore Upazilas have some influence over Singra Paurashava. The favorable location has benefits Singra in two ways: it allows people to come to Singra to purchase goods and services, and it allows Singra businesses, including wholesale businesses, to deliver goods and services to places outside the town. The Singra Upazila HQ's provides govt. services for neighboring communities of the entire Upazila including the Paurashava area. The entire Upazila for given services by the Paurashava are the catchment area of Singra Paurashava.

Transport and communication connectivity is an important factor for economic development of an area. Though Singra is located at the far corner of Natore and north corner of Bangladesh, it has a good road communication network with Natore and nearby Upazila towns. The regional transportation network is shown in **Map 3-1**.

3.10 Land Use and Urban Services

The general land uses of the project area are shown in Table 11.1 in Chapter 11. In the land use pattern of the Paurashava, 17 types of land uses are found. It is clearly evident from the table that agricultural land use (almost 65.40%) dominates the Paurashava area, followed by residential (16.62%), water bodies (More than 13.14%), road network and transport and communication (only 0.05%), and government services and educational land use occupy same percentage of land (More than 0.25%). Singra Paurashava has experienced major development along the river Atrai.

Settlements are found particularly in the areas of higher elevation following linear pattern along side the roads and More specifically around the central bazar. The trend of settlement growth is greater in areas close to the main road. The core part of the Paurashava is the most built up part of the planning area. Apart from core area, in most of the other areas, residential developments have taken place as dispersed settlements on high lands. Dispersed settlements make provision of services difficult.

3.11 Paurashava Functional Linkage with the Regional and National Network

Any development initiative at the local level must relate to the national level plans in order to achieve cohesion and integrity with overall development of the country to attain the national development objectives.

The present system of national level planning hardly links the local level plans. The present system of allocation of resources in national development budget is a top down approach, which is highly influenced by political objectives. As a result, urban sector is not yet considered a priority sector and due to resource constraint, many problems of the Paurashavas remain unresolved. Therefore,

it is important to establish a linkage between the local plans and the national development plan so that aspirations of the people can be realized. National development plans are prepared considering the overall needs and aspirations of the country with respect to different sectors of development.

This necessitates for a bottom up approach of development planning and the budget allocation should be made according to the choice of the local governments who are accountable to the Paurashava people directly. Budget should be allocated according to the priority list of the projects prepared by the Paurashava that is supposed to reflect the needs of the Paurashava people as the list can be prepared by the counselors and the Mayor who are directly elected by the people.

The aim of the Structure Plan is to prepare a development plan for SingraPaurashava with full participation of its stakeholders. In the process of planning, a large number of development projects have been identified in different sectors. Implementation of development projects will improve infrastructure and services and will create an environment for utilization of local resources. This will attract more investment in the locality to generate new employment. New employment will generate income for the poor people and shall improve the poverty situation, which is the main objective of PRSP. New jobs will also be created during implementation of various development projects of the Paurashava prepared under the master plan. New and improved road infrastructure will increase mobility vis-a-vis economic activities of the Paurashava that will help to address the problems of unemployment.

The current program of Paurashava Planning helps to address urban poverty through adequate steps taken up to accelerate urban infrastructure development based on the SingraPaurashava plan. The new developments will induce new investments in trade and industry and lead to generation of more employment in the service, construction, transport and informal sectors. This will directly assist in reducing poverty. It will help absorb additional work force of rural areas as a result of natural growth of population. Agricultural sector has limitations in absorbing labor force.

Map 3-1: Communication Network of Natore Region showing Connectivity with Singra Paurashava

3.12 Role of Agencies for Different Sectoral Activities

The successful implementation of Structure Plan depends upon the efficiency of the stakeholders and the degree of integration and coordination among them. Structure Plan of a town involves a complex affair having numerous stakeholders influencing the decision making process of development.

Care has been taken for all programmes and projects to be developed in a sound manner technically, socially, environmentally and institutionally with full participation of local communities. Due care has been taken so that there have no significant adverse internal or external environmental impacts. Sustainable urban development based on a continuous dialogue between the actors involved in urban development is needed to improve the urban environment. It is expected that after the completion and implementation of the Master Plan and as well as the mentioned projects and programmes of other organizations in Singra, this small town will develop with its full potential.

Development Schemes Implemented by the GOs

The recent infrastructure development schemes implemented by the Government includes roads, road lights etc.

Singra is an agriculture-based urban area and Upazila Agriculture Office has a significant influence on its agricultural sector. Central Government use subsidy for the betterment of the farmers. Local office distributes fertilizer to the poor farmers with 20 kg per head through the Paurashava. Some times, the agriculture office distributes 10 kg per head to balance between demand and allocation of fertilizer. Besides, agriculture office also arranges training workshops for the farmers on modern techniques of cultivation that increase production.

Upazila Fisheries and Livestock Office distribute fish fry and fertilizers for fish and vaccination of poultry and other livestock to the people free of cost. They also arrange training session to train the people. Upazila Parisad some times takes initiatives for afforestation and distribution of saplings.

Upazila Health Complex only implements a few activities like vaccination, training on child and mother health etc.

Electrification of Singra is operated by Polli Biddutayan Board (Rural Electrification Board- REB) that has a Master Plan to avail 100% electrify in the whole Upazila including the Paurashava area. The Master Plan explains the basis of electrification to the residents and the commercial establishments on a priority.

DPHE recently conducted a survey in 14 villages among the 22 villages to know the arsenic contamination level of Singra. It covers Paurashava and its surrounding areas. The authority has prepared water supply network for SingraPaurashava, but failed to implement it.

Local Government and Engineering Department (LGED) has upcoming project of construction of road, culverts and box culverts within the Paurashava.

Development Schemes Implemented by the NGOs

There is no mentionable infrastructure development project undertaken by the NGO's in the Paurashava. Several NGOs are working in Singra to develop socio-economic condition and to alleviate poverty of the local people providing infrastructure service and other facilities. Operationally important NGOs are Asroy, Human Right Organization, Bangladesh Warrior's Sanshad, BRAC and Social Work Centre.

Development Schemes Implemented by Private Sector

There are a few development works that have been implemented by private sector. Some commercial activities and private schools have been developed by private initiative.

Chapter 4: Critical Issues for Planning

Deficiency in infrastructure and services is one of the major critical problems of the Paurashavas in Bangladesh, and Singra is no exception. The reasons for such deficiency may vary, but are mostly linked with the institutional capacity and resource potential of the Paurashavas. The institutional capacity of each similar category Paurashava in terms of manpower and other logistics at present can be same across the country, but their efficiency and performance in practice may vary for a variety of reasons.

Chapter 4 describes the critical issues for planning based on the existing conditions in respect of Socio-Economic and Demographic issues, Transport and Communication, Urban Utilities, Drainage and Environment, related other issues namely disaster, land use control, law and regulation etc. The weaknesses in the present development processes are also taken into consideration to identify the critical issues for planning at SingraPaurashava.

4.1 Socio-Economic and Demographic Issues

Most of the Paurashavas in Bangladesh are basically urban centers with direct links to rural areas. There are significant differences in the standard of socio-economic well being and demographic characteristics of these small towns with large cities in the country. Most of these Paurashava towns have small population, not enough to sustain economic growth to render services and facilities for quality of life needed in an urban environment. As a result, qualities in socio-cultural and demographic matters suffer from inadequacies in their requirements of facilities and services of various kinds. Since SingraPaurashava has all such problems and shortcomings, in the preparation of various components of the Master Plan, this aspect of reality in development has to be addressed for sustainable solutions.

4.2 Transportation and Communication

Transportation and communication network plays very important role in the growth pattern of both urban and rural settlements and their socio-economic and environmental development. Houses and other establishments always prefer road side lands to have easy access to different places and functions. The transportation and communication network at SingraPaurashava is not yet planned and developed to serve a town. The Paurashava has a very low traffic volume to sustain high cost of development in this sector, particularly in areas of low population density and scattered settlements. However, without planning a transport network for the Paurashava area as a whole, a standard transport network and an efficient traffic management system for the future cannot be ensured. The nature of problems and deficiencies are identified below.

a. Unplanned and Narrow Road

Roads in the town are being developed without using any planning standard and network plan. As a result, narrow roads with tortuous pattern are common. Narrow roads and poor maintenance of roads are major problems for traffic movement in some parts of the Paurashava. New houses and other structures are cropping up along these sub-standard narrow roads. This is likely to poise traffic movement problems in the future, when development becomes more intense and density of

population increases. The existing narrow roads require widening and improvements of pavement. Some road segments within the Paurashava are built in an unplanned manner. These segments will require improvement as per future traffic volume and required space for turning lane in the intersections.

b. Traffic Congestion

A very level of vehicular traffic in the streets of the town at present does not pose a threat for congestion in the near future. However, occasional congestions are found to arise from non-motorized traffic at selected locations, where public assembly is profound, especially Singra Bazar Chowrasta intersection. At present such congestions happen due to poor designing of the intersections. The slow moving rickshaws, on street parking and on street loading-unloading of goods are found to be the major sources of traffic congestion.

Manually operated rickshaw is a cozy and cheap traffic mode that can take passengers to their door steps. It is, therefore, a very popular mode that requires special planning attention in the design of transportation network and individual roads. Walking and cycling is encouraged in contemporary town planning practices to create healthy environment for all. Pedestrian safety should be an important element in the design of roads and other related infrastructure. These aspects require special attention in the Master Plan of SingraPaurashava.

Reason for Congestion

- Lack of management is the prime reason for traffic congestion. There is a common tendency among the rickshaw pullers to disobey rules. They roam about the busy areas in search of passengers and park rickshaws at critical points leading to congestion.
- There is no proper and adequate space for parking auto-rickshaws and tempos. They are parked on the road. On road waiting for trips by these vehicles is also a source of congestion.
- Local buses often take passengers from wherever they find. In the same way, they disembark passengers according to their desires. These practices hamper smooth traffic movement.

c. Bus, Truck, and Tempo Terminal/Stand

Singra has one formal bus terminal but no truck terminals. It has few bus stoppages along the main road. For the planned development of township in the future, these facilities are to be provided at suitable locations.

Map 4-1: Existing Road Network Map of Singra Paurashava

4.3 Urban Utilities

A key issue related to the sustainable development of planning area providing a minimum quality and standard of living, pertains to the availability of and accessibility to basic infrastructure facilities, viz. water, power, sewerage, drainage and solid waste management. The present state of infrastructure problems in the Paurashava may become a cause of crisis. At present, state of telecommunications and power scenario in SingraPaurashava is not so good. There is no water and gas supply system in this Paurashava. Thus critical need of advance action and arrangement is required for adequate provision of physical infrastructure.

4.4 Drainage and Environment

Majority of the population at SingraPaurashava is deprived of drainage facility. Uncollected waste is washed out into the roadside drains and natural canals. Blockage of drains by solid waste reduces the carrying capacity of drains and natural canals and become a source of pollution. Paurashava has very limited resources to clean the drains. It has been observed that in some areas, domestic sewage conveys directly to the water channels. Water logging is a problem at some parts of SingraPaurashava, causing water logging for 5-7 days each time a heavy rainfall occurs between June and November every year.

The sources of surface water pollution are domestic waste, unhealthy sanitation and extensive use of fertilizer in the agriculture. Condition of solid waste management at SingraPaurashava is very poor. There are 10 permanent and 17 temporary dustbins found in this Paurashava. One truck and two push carts are used to collect solid waste. Hospital waste is dumped to their own dustbin. Garbage of kitchen markets is dumped to nearby dustbins. The present conditions demand substantial improvement to ensure desirable environment.

4.5 Related Other Issues

SingraPaurashava is located under Natore District. The SingraPaurashava is important in the national context for some reasons. It is well connected by road via Natore Divisional headquarter. The Atrai Rivers are of hydrographical importance of the area. Many agricultural Products produced in this area are exported throughout the country.

4.6 Disaster Issues

Singra is not located in highly disaster prone area except flood. Floods sometimes overflow from the river and it creates severe problem in locality. So, embankment cum road is suitable to protect this area.

4.7 Land Use Control

A Land Use Plan of the town was prepared in 1987 by Urban Development Directorate (UDD), but it was never brought into practice due to lack of regulatory measure for implementation. Instead, discretionary decisions are used in case of land use decisions. The Land Use Plan at that time was prepared for the Upazila Headquarters by UDD, but remained under the administrative control of the Ministry of LGRD & C. So conflict and lack of legal basis in implementation prevailed. In the present context of socio-economic demand and land use dynamics in the country, development of

a Paurashava without a Master Plan cannot be imagined. The preparation of Master Plan is mandatory as per Local Government (Paurashava) Act 2009.

4.8 Laws and Regulations

Absence of adequate planning and development control is a problem in all urban areas of Bangladesh and Singra is no exception. A number of legislative measures are there to help the administration of urban area, urban development and management. But all of these planning laws cannot be readily enforced and many of them are not adequate in regulating planned development. Due to lack of proper implementation and enforcement, many important laws are mostly not applied by the urban local governments. As a result, weakness in the implementation of planned development in the Paurashava remains to be a critical problem and has to be addressed.

A substantial portion of national resource is invested in building construction in both public and private sectors. In order to ensure optimum return of this investment and to achieve satisfactory performance of the buildings in terms of safety, serviceability, health, sanitation and general welfare of the people, building construction needs to be controlled and regulated. Legislative measure for such control has been provided in the Building Construction Act, 1952 and from time to time, regulations have been promulgated by the government under the Section 18 of this Act. As per law, it is mandatory to get any structure approved from appropriate authority before construction. Permission for building construction in the Paurashava is administered by this authority within its jurisdiction. However, as elsewhere in the country, noncompliance to these rules is also observed here.

a. Weak Local Government

Though Paurashava is a democratically elected urban local government, its authority is limited to work as a local government. In most cases, prior government permission is required before taking any legal action against unscrupulous acts. Section- 66, Section-69 (1) and (2), Section- 72 (4), Section-32 (2) of the Local Government (Paurashava) Act, 2009 are few examples. This is one of the reasons that there has been a little progress in decentralization of governance at local level in Bangladesh.

b. Lack of Fund

Local bodies in this country are in constant shortage of funds as is the case in Singra. The sources of the Paurashavas income are generally taxes, rates, fees and charges levied by it, and rents and profits accruing from individuals and institutions. The government grants, profits from investments, receipts accruing from the trusts placed with it, loans raised by it and proceeds from other services are the other sources of income for the Paurashava.

The lack of efficient manpower, poor assessment system, and weak legal enforcement for practicing an efficient revenue generation and collection system are the main reasons for the current weakness in the financial management. It is widely accepted that there are also corrupt practices in our public institutions in delivering services, which require to be addressed through institutional and legal reforms.

c. Public Participation in Plan Making Process

The planning and development Acts of earlier times had contained a little scope for the authorities concerned to seek public opinion on their city/town plans prepared before they are sent to the government for final approval. Not having any scope for public participation is against the democratic norms of an elected urban local government like the Paurashava Authority. The authority must involve people by law in the planning and development process, and hear their views, needs and grievances to mitigate problems. This vital aspect should be incorporated in a stronger manner in the law through revision.

d. Coordination of Activities of Public Sector Development Agencies

There are a large number of public sector development agencies working in the town and surrounding areas, but there is lack of coordination among activities of these development agencies. Absence of coordination results wastage of resources and often brings misery to the people. This is commonly evident in our urban development works, for example, as one agency digs the streets for telecommunication network and repairs the streets, another agency starts digging for sewerage ducts. Effective coordination by law in this case is necessary for an integrated approach in development saving time and resources. There should be legal provisions for such coordination by the Paurashava Authority to ensure accountability of the agencies working for their respective jobs in the Paurashava area.

e. New Rules for Practicing Planning Standards

At present, there is no standard for infrastructure, services and facilities provided by the public sector. There is need to formulate standard rules for services and facilities and get incorporated in the Local Government (Paurashava) Act, 2009 to secure public interests. A standard has been set in the UTIDP for future land use proposals in the Master Plan of the Paurashava.

f. Betterment fee

Due to failure of execution of the powers of charging betterment fee, all the benefits of land value enhancement due to Paurashava development of infrastructure go to the adjacent landowners or the persons having interest therein. A proper execution of betterment fees will help increase in revenue earning of the Paurashava.

g. Penalty for Violation of Plan Provisions

The penalty for violation of plan provisions provided in the Paurashava Ordinance (Section 49) is only Tk. 5000/- and for delay Tk.50/day, if violation continues further after notification. This is an extremely low rate of penalty, which should be revised for a substantial increase to prevent any violation effectively. The penalty provision should be more stringent to ensure enforcement of plan provisions.

4.9 Existing Problems and Weaknesses in the Development

The two major problems that currently exist in Singra Paurashava include the following:

- a) The Paurashava town has a weak economic and revenue base that does not support improvement in the socio-economic well being of the people. The Paurashava authority for lack of resources, fails to make required investments in the development of physical infrastructure to improve the quality of life of the people living in the town.
- b) The Paurashava has also no definite plan for the development of various physical infrastructures in a planned manner. With lack of resources, it also lacks in professionally skilled manpower to carry out development in a planned way.

Thus for making this Paurashava a viable urban center, attention should be paid toward cost-effective development of all of its required infrastructure in phases, with the help of professionally skilled manpower and utilizing the newly prepared Master Plan as an important tool for all sorts of development.

Chapter 5: Reviews of Policies, Laws and Regulations

5.1 Introduction

The urban planning and land use regulations are essential for municipal development. They impact on land market favorably or unfavorably and result in social benefits and costs depending on their nature and the specific contexts in which they are applied. Policies, regulations and processes that facilitate availability of land and its uses for planned development at affordable costs need to be continued and those lead to contrary results need to be eliminated or modified.

5.2 Review of Relevant National Policies

The various existing policies, regulations and laws of the country have direct and indirect effects on the preparation and implementation of Master Plans of the Paurashavas in the country. These are briefly reviewed in this chapter to examine their adherence with the Master Plans of the Paurashavas.

5.2.1 Directives of the Local Government (Paurashava) Act, 2009 for Preparing the Master Plan

The Paurashava Ordinances at different times since 1960's till the present time have iterated that a Paurashava as it gets established must prepare its Master Plan for planned development of the municipal town. So far, three ordinances have been made in the year 1967, 1977 and 2008, all suggesting for planned development. The Paurashava Ordinance 2008 was later modified and enacted as Local Government (Paurashava) Act, 2009 in the national Parliament on 6, October, 2009.

The 2009 Act made provision for having the Master Plan prepared by a Paurashava within five years of its inception. The Master Plan of a Paurashava town is aimed for ensuring planned development, and should include the following:

- Survey of history, detailed statistical information, public service activities and other mentioned subjects of the Paurashava;
- Development, extension and upgradation of any area within the Paurashava; and
- Control and regulation of development of any land, any building construction and renovation within the Paurashava.

Actions Suggested in the Act to Prepare Master Plan

The Local Government (Paurashava) Act, 2009 suggests for having qualified Town Planner in its Organogram of Manpower to undertake the job of preparing the Master Plan of the Paurashava. Until such qualified Town Planner is not available in the Paurashava, the Paurashava may require a competent national government authority to prepare such plan for the Paurashava. The Act also makes it contingent to form a Town Planning Committee within the capacity of its manpower to execute the Master Plan of the Paurashava Town.

SingraPaurashava has no Town Planner and Town Planning Committee at the moment. This makes the Paurashava dependent on having the Master Plan currently being prepared by LGED.

5.2.2 National Land Use Policy 2001

To safeguard the use of its land resources, particularly the valuable agricultural land of the country, the government in 2001 declared the National Land Use Policy. The policy proposed for the preparation of national land use plan, which is very much relevant to the current plan of the Paurashava.

The land use plan is to be based on the criteria of land productivity, land capability and land suitability, use and requirement of land by agriculture, forestry, industrialization, urbanization and housing. Following are the key issues of the national land use plan:

- Execution of coordinated land conservation programs aimed at prevention of desertification and weathering of land, conservation of land fertility, development and conservation of land.
- Prevention of destroying the landscape by earth cutting, excavation and removal of land.
- Formulation and effective execution of Land Use Plan in order to ensure planned use of land.
- Payment of compensation to those who will be affected by land weathering and land acquisition by the government.
- Monitoring, survey and research on desertification, land reclamation, prevention of weathering of land, conservation and development of land and watershed areas.

The policy emphasizes on the planned and the best use of land, and stressed on the most intensive use of this scarce resources of the country. The policy aims to introduce 'land use zoning' based on particular characteristics of land, prevent unplanned expansion of residential areas and control of indiscriminate growth of industrial and commercial activities. In absence of execution, the situation in land use and land management is severely being deteriorated.

5.2.3 National Housing Policy, 1993

The Government of Bangladesh formulated the first ever housing policy of the country in 1993. The priority of the government is to create affordable housing, which might be possible through controlling unplanned and haphazard housing area development. The policy is committed to encourage private developers in land and infrastructure development, and house construction. The policy also made commitment to provide government assistance on participatory housing infrastructure development involving the community, NGOs, CBOs, private developers and social welfare organizations.

The policy declares that in housing activities, the government will continue to remain as a facilitator in housing sector. The government intends to provide housing only to the poor and the rootless classes of the society. The policy makes commitments to encourage private organizations, NGOs and CBOs in housing development, income generation and environmental improvement under local planning. The preparation of Master Plan of the Paurashavas is, therefore, a step forward to address the various development issues including housing for mass people at local level.

5.2.4 Population Policy 2004

Prepared in 2004, the Population Policy of Bangladesh responds to the critical need to deal with the complex national population problem in a holistic way. It aims to build national consensus and synergy among institutions: public, private, civil society and NGOs about the problem.

The objectives of the National Population Policy are to improve the living standard of the people through making a desirable balance between population and development. The Policy proposals can broadly be divided into four sectors, human resources development, decentralization of population activities, participation of NGOs and private sector in population planning. The population policy aims to create a large skilled workforce, emphasizing on education and training strategies.

The policy calls for decentralization of population activities and ensure people's participation through decentralization of services and devolution of power to the local levels. The policy aims to prepare Action Plan through participation of local elites, opinion makers, representatives of poorer section of the society along with the local level government officials. With a view to give a holistic approach, the population policy calls for making the NGOs and private sector as important partners in population activities at various levels.

5.2.5 Transportation Policy 2004

Prepared in 2004, following are the policy objectives of Transport Policy:

- To provide a safe and dependable transport service for all.
- Removal of unnecessary control and formulation of laws and regulations conducive to providing services.
- Fare control and reduction of transport cost of goods for export.
- Determining the roles of the Government sector and the private sector.
- To maintain an economic and environmental balance.
- To ensure maximum utilization of Government funds.
- Expansion of the role of transport in the ever increasing economic activities.
- Growth of traffic commensurate with economic development.
- Introduction of an integrated transport system and provision of alternate transport systems.

The aim is to encourage greater private sector participation with national ownership of road and rail infrastructure. Lease of infrastructure may be allowed on long term basis. The Government is interested to establish a user role within its transport planning process. The Government intends to make arrangements to realize the cost of transport operation and road maintenance from road users through new fiscal policies and protect public interests. The Government will regulate tariffs for passenger and goods both in road and rail transport.

5.2.6 National Environment Policy 1992

Government declared an environmental policy in 1992 with a view to safeguard the national environment. The main objectives of the policy are:

- To promote natural balance and overall development by means of conservation and development of environment.
- To save the country from natural disaster.
- To identify and control all sources of pollution and degradation.
- To ensure environment friendly development in all sectors.
- To ensure sustainable, long term and environment friendly use of all national resources.
- To get involved with all international initiatives on environmental issues.

The comprehensive environmental policy covers as many as 15 sectors of development namely, agriculture, industry, health and health promotion, energy, water resources, flood control and irrigation, land, forest, wild life and biodiversity, fish and animal resources, food, coastal and maritime environment, transport and communication, housing and urbanization, population, education and public awareness, science, technology and research, legal framework, institutional structure. The consultant highlights only those sectors that have relevance to urban development and planning.

Industrial Sector

The following environmental measures are important:

- Potential polluting industries must incorporate control measures in its set up.
- All industries must conduct EIA and take pollution control measures.
- All industries in residential areas to be gradually shifted and new locations to be identified for planned industrial development.
- The industries producing pollutants should have their own system of pollution monitoring.
- Recycling of waste in order to reduce the volume of waste.
- Safeguard health of industrial workers.

Health Sector

The following environmental issues are important:

- Supply of safe drinking water in the Paurashava area and introduction of low cost healthy sanitation system.
- Control of pollution in all kinds of water bodies by municipal, industrial and toxic materials.
- Ban on carrying waste during day time and in open garbage trucks.
- Steps to be taken to protect public health and environment from all activities harmful for human health.
- Inclusion of environment in the academic syllabi.

Energy Sector

The following are some relevant policies:

- Large scale for introduction of improved cooker and wide dissemination of the technology to conserve energy and save environment.
- Promotion of biogas, solar energy, mini hydro electric unit and wind mill as sources of energy.

- Take up measures to reduce the amount of harmful elements in fuel including, sulfur in diesel and lead in petrol.
- Care has to be taken so that use and transformation of primary and commercial energy does not create any adverse impact on the environmental balance.
- Appropriate measures have to be taken during extraction and distribution of different natural resources like, oil, gas coal, peat so that they do not create any adverse impact on air, water, land, hydrological balance and the eco-system.
- Care has to be taken during giving fitness certificate to vehicles that emit black smoke. Mobile courts will have to be arranged to enforce the relevant legal provisions.

Transport and Communication Sector

The important aspects are:

- Care to be taken to make the road infrastructure development congenial to environment and the development of roads does not impede drainage of water.
- Appropriate measure to be taken so that the passengers and the transport do not endanger public health by indiscriminate throwing of solid waste and defecation.
- The rail, road and water transport must adopt measures to control emission of excessive black smoke.
- Creation of public awareness about the effect of pollution of river water.
- Control on water pollution to be ensured in inland river ports and dockyards.
- Encourage railway rolling stocks that generate less pollution.
- Forestation on both sides of railways and roads.

Population Sector

The important aspects are:

- Conduct study on the impact of population growth on environment and take appropriate measures to mitigate the problems of population growth.
- Prepare manpower utilization plan to make planned and effective use of human resources congenial to environment.
- Emphasize participation of women in environment conservation.
- Appropriate measures are needed to safeguard health of the poor and save them from the adverse effects of environmental degradation.

5.2.7 Industrial Policy 2005

The key aspects of the Industrial Policy 2005 are to:

- set up planned industries considering the real domestic demand, prospect of exporting goods abroad, and discouraging unplanned industries in the light of the past experience.
- accept private initiatives as the main driving force of economic development and uphold the government's facilitating role in creating a favourable atmosphere for private investments.
- take necessary initiatives to establish industries on state initiative in those sectors that are considered very important and essential, where private entrepreneurs are not forthcoming.

- cater to the needs of consumer satisfaction of the local products; measures to be undertaken to: produce quality products, diversify goods, and provide support for enhancing productivity using appropriate and advanced technology.
- provide inspiration for the speedy expansion of cottage industries and SMEs, and for further investment in these sectors so that new employment opportunities are generated, unemployment reduced and poverty alleviation programs made available.
- prioritize the expansion and development of agro-based and agricultural processing industries, and assist in the expansion of poultry, dairy and goat-sheep industry as agricultural industries.
- provide women entrepreneurs with all necessary assistance in establishing industries in various sectors.
- provide all necessary assistance for producing environment-friendly product with the objective to creating a pollution-free environment in the industrial sector.
- Enrich the industrial sector with the proper utilization of various natural and mineral resources.

5.2.8 National Tourism Policy 1992 and 2010

Recognizing the contribution of tourism to the socio-economic development of the country, the government framed the National Tourism Policy in 1992. The government in a gazette notification in May 2010 declared that the government may declare any potential site as a tourist area and if declared so, any development within the area will require formal permission from the government. The attractions of tourism can be varied, and the major policy thrusts for the sector are:

- To create interest in tourism among the people
- To preserve, protect, develop and maintain tourism resources
- To take steps for poverty-alleviation through creating employment
- To build a positive image of the area concerned
- To identify sectors for private capital investment
- To arrange entertainment and recreation
- To strengthen solidarity and integrity among the peoples

5.2.9 Agriculture Policy 1999

Agriculture Policy of Bangladesh was framed in 1999. A new policy is currently under preparation. The following are the important considerations in the 1999 Agriculture Policy.

The major issues dealt within the policy are, seed, fertilizer, irrigation, pest management, agricultural research, extension services, marketing of agro-products, land use, education and training, environment and agriculture, women and agriculture, coordination of various agencies engaged in agricultural development. Most of these issues are not relevant to the current Master Plan. The only relevant issue is the land use. So, review has been carried out on the land use only.

The Policy stresses on all possible steps to ensure optimum use of land. Its use has to be compatible with the overall goals of socio-economic services and utility provisions. The policy targeted to take the following steps to ensure planned utilization of land:

- Land zoning programme will be taken up by the Soil Resources Development Institute (SRDI) on a priority basis. Integrated approach of SRDI will be further strengthened for this purpose.
- To ensure maximum utilization of land, bottom up planning through people's participation will be started from the mouza or village level.
- Measures can be taken to stop fertile agricultural land being used for non-agricultural purposes, such as private construction, house building, brickfield, etc.
- Acquisition of land in excess of requirement for non-agricultural purposes will be discouraged.

About one percent of agricultural lands are being converted into non-agricultural use every year. In a country of constantly growing population, withdrawal of land from agriculture will affect food production. So it is necessary to safeguard farm land from conversion. But this vital issue has been partially addressed in the policy. It states only about fertile land and not agricultural in general.

Government has not framed any effective mechanism to discourage acquisition of land in excess of requirement for non-agricultural purpose. To protect agricultural land, immediate steps are necessary to delineate agricultural lands. This issue has not been covered in the policy. It has been found that large areas of agricultural lands are unnecessarily being included within Paurashava. Sometimes, it is about 70% of the total Paurashava area.

5.2.10 Urban Forest Policy 1994

Representing an amendment of the forest policy of 1979, current national forest policy was enacted in 1994 and officially announced on 31st May 1995. The policy was formulated to initiate a 20-year Forestry Master Plan (FMP). The plan provides a framework for optimizing the forestry sector's ability to stabilize environmental conditions and assist economic and social development. Three imperatives were identified: sustainability, efficiency and people's participation. Important objectives are:

- To afforest about 20% of the total area of the country by initiating various a forestation programmes in forest lands, fallow lands, lands not useful for agriculture, hinter lands and other possible areas to meet the basic needs of the present and future generations and to ensure greater contribution of the forestry sector to economic development;
- To enrich biodiversity in the existing degraded forests by conserving the remaining natural habitats of birds and animals.
- To strengthen agriculture by extending assistance to those sectors related with forest development, especially by conserving land and water resources
- To provide for and implement a forestation programmes on both public and private lands.

The policy statements which are most relevant to local participatory forestry are as follows:

- tree growing by communities, local groups or individual families on roadsides, windbreaks, canal/river banks and other public or marginal lands will be promoted through NGOs and relevant state agencies;
- Buffer zones attached to protected areas may be allocated for tree farming and agro-forestry on a long term lease basis;

- The State will provide technical assistance and financial support to promote all forms of homestead forestry;
- Cottage and small scale labor intensive industries, which contribute to the local economy and process wood and other forest based raw materials, will be promoted;
- The traditional rights of people living within and adjacent to designated forest areas will be maintained and their forest-related cultural values and religious beliefs will be respected.

5.2.11 National Plan for Disaster Management, 2008-15

National Plan for Disaster Management 2008-2015 is an outcome of the national and international commitments of the Government of Bangladesh (GoB) for addressing the disaster risks comprehensively. The plan is developed to reduce the vulnerability of the poor to the effects of natural, environmental and human induced hazards to a manageable and acceptable humanitarian level. The objectives of this Plan are to:

- Align the strategic direction of disaster management programs with national priorities and international commitments.
- Articulate the vision and goals for disaster management
- Outline the strategic direction and priorities to guide the design and implementation of disaster management policies and programs.
- Create a cohesive and well-coordinated programming framework incorporating government, non-government and private sector.
- Ensure that disaster management has a comprehensive and all-hazards focus comprising disaster risk reduction and emergency response.
- Illustrate to other ministries, NGOs, civil society and the private sector how their work can contribute to the achievements of the strategic goals and government vision on disaster management.

A holistic approach for disaster management has been emphasized to work together with all the stakeholders and build strategic, scientific and implementation partnerships with all the relevant government departments and agencies, other key non-government players including NGOs, academic and technical institutions, the private sector and the donors. The role of Government is mainly to ensure risk reduction and comprehensive disaster management.

5.2.12 National Plan of Action for Person's with Disabilities (PWDs) as well as Autism, 1995

In line with the Government policy the Department of Social Services under the Ministry of Social Welfare has an enthusiastic vision & mission to address the social issues relating to Person's with Disabilities (PWDs) as well as Autism. The National policy for the persons with disability, 1995 calls for social protection and ensured the rights of the vulnerable groups. In the recent time, dynamic and sustainable steps have been taken for the PWDs. The steps are:

- To establish separate ticket counters in railway station, bus terminals, river ports, steamer terminal, airport and airways office to facilitate easy availability of tickets for the PWDs.
- To maintain reserve seats in the bus, train and water transports for PWDs.

- To fill up 10 percent reserved quota for employment in government jobs by orphans and PWDs.
- To construct a ramp in all the government offices to facilitate easy movement of the PWDs.
- To withdraw the existing restrictions regarding appointment of PWDs in the Govt. class I & class II jobs, and arrange micro-credit for PWDs by all the Nationalized Commercial Banks (NCBs).

5.2.13 Review of Relevant Laws and Regulations

5.2.13.1 The Act (36 of 2000) for Conservation of Play field, Open space, Park and Natural Water Reservoir in Mega City, Divisional Town, District Town and Paurashavas of Bangladesh

According to the section 5 of the Act, any land having such use as play field, park and natural reservoir can not be changed or can not be used for any other purpose(s). However, in absence of Paurashava Master Plan, the Act can not be properly applied. This emphasizes upon having Master Plan for each Paurashava.

In the existing provision of the Act, any person violating the Act may be liable to punishment up to 5 years of imprisonment or Tk. 50,000 fine or both. The Act makes a provision for appeal, however, and any land owner having any land with above mentioned use may apply to the appropriate authority to have permission to change the use. The authority shall convey the results of appeal within 60 days of the appeal.

5.2.13.2 Bangladesh National Building Code (BNBC) 1993

The Bangladesh National Building Code (BNBC) 1993 was formulated in 1993, but given legal status in 2008. The purpose of Bangladesh National Building Code (BNBC) is to establish minimum standards for design, construction, quality of materials, use and occupancy, location and maintenance of all buildings in order to safeguard within achievable limits, life, limb, health, property and public welfare. It aims to ensure public safety, health, and general welfare in so far as they are affected by the construction, alteration, repair, removal, demolition, use or occupancy or buildings, structures of premises, through structural strength, stability, means of egress, safety from fire and other hazards, sanitation, light and ventilation. The BNBC suggests for conservation and restoration of historic buildings.

5.2.13.3 The Building Construction Act 1952

This Act was prepared in 1952 to prevent haphazard construction of buildings and excavation of tanks that are likely to interfere with the planning of certain areas in Bangladesh. The Act is usually exercised in areas under the urban local governments. The Act sets some conditions regarding construction of buildings in urban areas, where the Act will be in execution.

Preparation of Master Plan

The Act calls for preparation of a Master Plan of the urban area concerned before approval of building plan. The Master Plan shall show the future land use of the area through land use zoning. The buildings will be approved according to the land use provisions of the zoning plan. Having a Master Plan prepared, a Paurashava has the scope of exercising the following provisions/actions:

Building Construction Rules

The Act in its Section 18 keeps provision for preparation of Building Construction (BC) rules to ensure healthy and environment friendly building development. The last BC Rules were prepared in 1996. However, due to special characteristics of building development in Dhaka city a separate set of BC Rules was prepared for Dhaka City in 2008 under the same Act.

Power to Removal of Construction (Section 3B)

The Act gives special power to plan approval authority to remove any building that did not follow the specified rules of the Act or take action against any building owner who constructs building violating the rules after approval of the building plan.

Restriction on Cutting of Hills (Section 3C)

The Act forbids cutting of any hill without prior permission of appropriate authority.

Removal of Unauthorized Building (Section 7)

The Act empowers the authority to remove any building that has been built violating the BC rules. On failure to do so, the authority itself shall dismantle it and the entire cost shall be recovered from the owner as public demand.

Appeal

The Act, however, keeps provision for appeal, if the owner finds himself aggrieved due to any action by the authority.

Observation on the Building Construction Act

For appropriate execution of the Act, there is necessity of having Master Plan for a Paurashava. At the moment, there is serious lack of monitoring of disobedience of rules by the builders. Once the Master Plan is made for a Paurashava Town, the Paurashava Authority will be able to follow the rules properly.

5.3 Applicability of the Acts, Regulations and Policies in the Paurashava Master Plan

The key aspects of the policies presented in this Chapter have both direct and indirect relationships with the preparation of Master Plan of Paurashava Town in general, and SingraPaurashava in particular. The Local Government (Paurashava) Act,2009, the Building Construction Act 1952, the BNBC, the Conservation Act 2000, Agriculture Policy etc. have serious stakes in the execution of Paurashava Master Plan. The other policies also have relevance in the preparation of Master Plan for an Urban Centre. As a result, the relevant aspects of the Acts, rules, and policies are mentioned in this chapter and are taken into consideration in the preparation of the Master Plan for the Paurashava. The key aspects that are most relevant with the preparation of Paurashava Master Plan are shown in **Table 5.1**.

Table 5-1: Important provisions of different Acts, Policies and Rules having relevance with the preparation of Paurashava Master Plan

Act/Ordinance, Policies, Rules	Relevance with Paurashava Master Plan
Local Government (Paurashava) Act, 2009	Makes provision for having a Master Plan of the Paurashava Town. Provides legal basis for the preparation and implementation of Paurashava Master Plan. Suggests on the content and structure, and other relevant issues, such as provision for qualified Town Planner in the Paurashava staff.
National Land Use Policy 2001	Formulation and effective execution of Land Use Plan in order to ensure planned use of land. Suggests for afforestation, conservation and development of land maintaining landscape.
National Housing Policy, 1993	To create affordable housing through controlling unplanned and haphazard housing area development. To encourage private developers in land and infrastructure development, and house construction. Participatory housing infrastructure development involving the community, NGOs, CBOs, private developers and social welfare organizations.
Population Policy 2004	To improve the living standard of the people through a desirable balance between population and development. The proposals are divided into four sectors - human resources development, decentralization of population activities, participation of NGOs and private sector. The policy aims to create a large skilled workforce providing education and training.
Transportation Policy 2004	To provide a safe and dependable transport service for all. Removal of unnecessary control and formulation of laws and regulations conducive to providing services, determining the role of public and private sectors, maintaining an economic and environmental balance, maximum utilization of Government funds and introduction of an integrated transport system and provision of alternate transport systems.
National Environment Policy 1992	To promote natural balance and overall development by means of conservation and development of environment, save an area from natural disaster, identify and control all sources of pollution and degradation, ensure environment friendly development in all sectors, ensure sustainable, long term and environment friendly use of all national resources, and get involved with international initiatives on environmental issues.
Industrial Policy 2005	To set up planned industries considering the real domestic and export demand discouraging unplanned industries, provide necessary assistance for producing environment-friendly products with the objective of creating a pollution-free environment, and enrich the industrial sector with the proper utilization of various natural and mineral resources. To prioritize the expansion and development of agro-based and agricultural processing industries, and assist in the expansion of poultry, dairy and goat-sheep industry as agricultural industries; and provide women entrepreneurs with all necessary assistance in establishing such industries.
National Tourism Policy 1992 and 2010	To create interest in tourism among the people, preserve, protect, develop and maintain tourism resources, take steps for poverty-alleviation through creating employment, build a positive image of the area concerned, arrange entertainment and recreation, identify sectors for private capital investment, and strengthen solidarity and integrity among the peoples.

Act/Ordinance, Policies, Rules	Relevance with Paurashava Master Plan
Agriculture Policy 1999	To strengthen land zoning program, ensure maximum utilization of land through bottom up planning and people's participation, stop fertile agricultural land being used for non-agricultural purposes, and discourage acquisition of land in excess of requirement for non-agricultural purposes.
Urban Forest Policy 1994	To afforest about 20% of the total area of the country by initiating various afforestation programs in forest lands, fallow lands, lands not useful for agriculture, hinter lands and other possible areas to meet the basic needs of the present and future generations and to ensure greater contribution of the forestry sector to economic development; enrich biodiversity in the existing degraded forests by conserving the remaining natural habitats of birds and animals; To strengthen agriculture by extending assistance to those sectors related with forest development, especially by conserving land and water resources; and implement afforestation programs on both public and private lands.
National Plan for Disaster Management, 2008-15	To align the strategic direction of disaster management programs with national priorities and international commitments, articulate the vision and goals for disaster management, outline the strategic directions and priorities to guide the design and implementation of disaster management policies and programs, create a cohesive and well-coordinated programming framework incorporating government, non-government and private sector, and ensure that disaster management has a comprehensive and all-hazards focus comprising disaster risk reduction and emergency response.
National Plan of Action for Person's With Disabilities (PWDs) as well as Autism, 1995	To establish separate ticket counters in railway station, bus terminals, river ports, steamer terminal, airport and airways office to facilitate easy availability of tickets for the PWDs, fill up 10 percent reserved quota for employment in government jobs by orphans and PWDs, construct a ramp in all the government offices to facilitate easy movement of the PWDs, and withdraw the existing restrictions regarding appointment of PWDs in the Government Class I & class II jobs.
The Act (36 of 2000) for Conservation of Play field, Open space, Park and Natural Water Reservoir in Mega City, Divisional Town, District Town and Paurashavas of Bangladesh	To protect the existing use of land such use as play field, park and natural reservoir, and ensure punishment for conversion of such lands by any person/authority without proper permission from the appropriate authority..
Bangladesh National Building Code (BNBC) 1993	To establish minimum standards for design, construction, quality of materials, use and occupancy, location and maintenance of all buildings in order to safeguard within achievable limits, life, limb, health, property and public welfare. It aims to insure public safety, health, and general welfare in so far as they are affected by the construction, alteration, repair, removal, demolition, use or occupancy or buildings, structures of premises, through structural strength, stability, means of egress, safety from fire and other hazards, sanitation, light and ventilation. The BNBC also suggests for conservation and restoration of historic buildings.

Act/Ordinance, Policies, Rules	Relevance with Paurashava Master Plan
The Building Construction Act 1952	The Act calls for preparation of a Master Plan of the urban area concerned before approval of building plan. The Master Plan shall show the future land use of the area through land use zoning. The buildings will be approved according to the land use provisions of the zoning plan. To ensure healthy and environment-friendly building development. To empower special power to remove any building that did not follow the specified rules of the Act. To take action against any building owner who constructs building violating the rules after approval of the building plan. To forbid cutting of any hill without prior permission of appropriate authority. To keep provision for appeal, if the owner finds himself aggrieved due to any action by the authority.

Chapter 6: Projection of Future Growth by 2031

The future growth projection is helpful to draw mechanisms for improving and guiding long-term development strategies, identifying existing problems and future demand and making possible suggestions, to formulate viable projects for urban development and increase management capabilities of the concerned authority.

6.1 Projection of Population

It is a difficult task to collect detailed information of population for a recently declared Paurashava in Bangladesh. Perhaps no single factor is more important for planning than the size and composition of a region's population and the way it changes in the future. Estimation of future population for a specific period of a particular area is one of the most difficult tasks in the planning process. For Bangladesh, population projection is a very difficult task as the required data are not available for the particular area of a Paurashava and same is the case for Singra.

The population figures collected from secondary sources, especially for the Paurashava were very much ambiguous. So for the final projection, several discussions were made with experts and BBS officials. Following the annual growth rate for the study area available from the 2001 Population Census, the projection up to the year 2031 with five years interval has been made.

The data found from several sources is arranged in different formats according to their requirement and analysis. So, comparison of data between different sources is very difficult. As a result, projection with various sources of information on population shows variable results in the calculation. Migration information is not available in population census by BBS as it only considers the natural growth rate. But actual population projection requires both natural growth rate and migration rate. For this unavailability of migration rate, population projection becomes very difficult.

By the formula population in any requisite year can be projected using the following equation which is also known as Geometric Progression Method of the following formula.

$$P_n = P_o (1 + R/100)^n \text{-----(i)}$$

As projections are based on the assumption that the past trends will continue to operate in the future, population of current year (according to BBS, 2011) have been taken to estimate the future population. The existing population of SingraPaurashava is 33192 in 2011 within an area of 2703.74 acres. According to 2001 Population Census, the population was 22595. With an annual growth rate of 3.92%, the forecasted population of SingraPaurashava will be-

$$\begin{aligned} P_n &= P_o (1 + R/100)^n \\ P_n &= 22595 (1 + 3.92/100)^{20} \\ P_n &= 71617 \end{aligned}$$

The existing population of SingraPaurashava is 33192 in 2011 within an area of 2703.74 acres. According to 2001 Population Census, the population was 22595. With an annual growth rate of 3.92%, the forecasted population of SingraPaurashava will be 71617 in the year 2031. The gross density of the area will be 26ppa (person per acre). Due to the maximum concentration of

residence in Ward no. 08, the density of population will also be higher (83ppa) in this area. **Table 6-1** shows ward wise population distribution of SingraPaurashava based on growth rate.

Table 6-1: Population Projection with Density for Singra Paurashava Up to 2031

Ward	Area (Acre)	Pop'01	PPA	Pop'11	PPA	Pop'16	PPA	Pop'21	PPA	Pop'26	PPA	Pop'31	PPA
1	141.09	2316	16	2952	21	3578	25	4336	31	5255	37	6369	45
2	451.82	2299	5	2705	6	3278	7	3973	9	4816	11	5836	13
3	228.27	2223	10	2932	13	3554	16	4307	19	5220	23	6326	28
4	298.89	3241	11	4734	16	5738	19	6954	23	8428	28	10214	34
5	52.54	1807	34	1909	36	2314	44	2804	53	3399	65	4119	78
6	521.98	2443	5	2414	5	2926	6	3546	7	4298	8	5209	10
7	192.47	2554	13	2742	14	3323	17	4028	21	4882	25	5916	31
8	123.67	3259	26	4730	38	5733	46	6948	56	8421	68	10206	83
9	275.57	2453	9	3343	12	4052	15	4911	18	5951	22	7213	26
10	64.91	-	-	1248	19	1513	23	1833	28	2222	34	2693	41
11	172.90	-	-	2041	12	2474	14	2998	17	3634	21	4404	25
12	179.63	-	-	1442	8	1748	10	2118	12	2567	14	3111	17
Total	2703.74	22,595	8	33192	12	40228	15	48756	18	59091	22	71617	26

Source: BBS, 2011. Estimation by the Consultant

Note: Annual Medium Growth rate for Population projection has been considered as 3.92%.

Table 6-2 shows the ward wise population growth of SingraPaurashava up to 2031 at a High population growth rate consider as 4.42%.

Table 6-2: Population Projection with Density for Singra Paurashava Up to 2031

Ward	Area (Acre)	Pop'01	PPA	Pop'11	PPA	Pop'16	PPA	Pop'21	PPA	Pop'26	PPA	Pop'31	PPA
1	141.09	2316	16	2952	21	3665	26	4549	32	5648	40	7011	50
2	451.82	2299	5	2705	6	3358	7	4169	9	5175	11	6425	14
3	228.27	2223	10	2932	13	3640	16	4519	20	5609	25	6964	31
4	298.89	3241	11	4734	16	5877	20	7296	24	9057	30	11244	38
5	52.54	1807	34	1909	36	2370	45	2942	56	3652	70	4534	86
6	521.98	2443	5	2414	5	2997	6	3720	7	4618	9	5733	11
7	192.47	2554	13	2742	14	3404	18	4226	22	5246	27	6512	34
8	123.67	3259	26	4730	38	5872	47	7290	59	9049	73	11234	91
9	275.57	2453	9	3343	12	4150	15	5152	19	6396	23	7940	29
10	64.91	-	-	1248	19	1549	24	1923	30	2388	37	2964	46
11	172.90	-	-	2041	12	2534	15	3145	18	3905	23	4847	28
12	179.63	-	-	1442	8	1790	10	2222	12	2759	15	3425	19
Total	2703.74	22595	8	33192	12	41205	15	51153	19	63502	23	78833	29

Source: BBS, 2011. Estimation by the Consultant

Note: High Growth rate for Population projection has been considered as 4.42%.

Table 6-3 shows the ward wise population growth of SingraPaurashava up to 2031 at a low annual population growth rate consider as 3.42%.

Table 6-3: Population Projection with Density for Singra Paurashava Up to 2031

Ward	Area (Acre)	Pop'01	PPA	Pop'11	PPA	Pop'16	PPA	Pop'21	PPA	Pop'26	PPA	Pop'31	PPA
1	141.09	2316	16	2952	21	3493	25	4132	29	4889	35	5784	41
2	451.82	2299	5	2705	6	3200	7	3786	8	4480	10	5300	12
3	228.27	2223	10	2932	13	3469	15	4104	18	4855	21	5745	25
4	298.89	3241	11	4734	16	5601	19	6626	22	7840	26	9275	31
5	52.54	1807	34	1909	36	2259	43	2672	51	3161	60	3740	71
6	521.98	2443	5	2414	5	2856	5	3379	6	3998	8	4730	9
7	192.47	2554	13	2742	14	3244	17	3838	20	4541	24	5372	28
8	123.67	3259	26	4730	38	5596	45	6621	54	7833	63	9267	75
9	275.57	2453	9	3343	12	3955	14	4679	17	5536	20	6550	24
10	64.91	-	-	1248	19	1477	23	1747	27	2067	32	2445	38
11	172.90	-	-	2041	12	2415	14	2857	17	3380	20	3999	23
12	179.63	-	-	1442	8	1706	9	2018	11	2388	13	2825	16
Total	2703.74	22595	8	33192	12	39270	15	46460	17	54967	20	65032	24

Source: BBS, 2011. Estimation by the Consultant

Note: Low Growth rate for Population projection has been considered as 3.42%.

With an annual growth rate of 4.42% (assuming higher growth rate), the forecasted population of SingraPaurashava will be 78833 in the year 2031. The gross density of the area will be 29ppa (person per acre). Due to the maximum concentration of residence in Ward no. 08, the density of population will also be higher (91ppa) in this zone.

Again, with low growth rate of 3.42%, the forecasted population of SingraPaurashava will be 65032 in the year 2031. The gross density of the area will be 24ppa (person per acre). Due to the maximum concentration of residence in Ward no. 08, the density of population will also be higher (75ppa) in this zone.

6.2 Identification of Future Economic Opportunities

The contribution of the small towns to the economic development of their hinterlands depends largely on the urban development in these urban centers. Depending on transport, communication and storage facilities, this Paurashava can play a vital role in linking rural farmers to the urban market. For instance, development of road network between this small town and its rural hinterlands may greatly benefit rural farmers as it enables them to transfer their agro produces to bigger markets. The industrial development in the Paurashava will have significant impact on the demand for raw materials that are required for the industrial production. All sorts of production materials, like brick, wood, bamboo etc. are produced in the countryside, serving as supply centers for urban demand. To support urban industries and related activities, it requires adequate infrastructure, such as urban rural transfer routes, communication and information structures. Investments in these projects result in enhanced productivity in both urban and rural areas.

Table 6-4 shows the work force of SingraPaurashava. From the BBS- 2001, it is revealed that the among the economically active age group of population, 36.45% are found engaged directly in Employment activities while 63.55% are found not engaged in employment activities. Not working population found about 31.39%, where as looking for work found 1.47% and 30.69% of population found engaged in house hold work. The major occupations found are farming, fishing, business and trading, services in government, non-government and private organizations, day-laboring in agriculture. From the Household Survey it is revealed that the Agricultural (farming) activities are

the dominant occupation class in the town. The percentage of the people engaged in this occupation is in a major portion. The next highest occupation class found is the small business and private service. Most of the households' earning members often adopt a secondary occupation which indicates that under-employment is very much prevalent in the project area.

In the project area, most of the economically active population whose age is 10 years and above are involving in agriculture (farming), small business and transport sector.

Table 6-4: Existing Working Force for Singra Paurashava

Total	Not Working	Looking for Work	House hold Work	Agriculture	Industry	Water, Electric & Gas	Construction	Transport	Hotels & Restaurant	Business	Service	Others
17675	5549	259	5425	2735	89	10	154	211	28	1545	132	1538
%	31.39	1.47	30.69	15.47	0.50	0.06	0.87	1.19	0.16	8.74	0.75	8.70
Total	63.55%			36.45%								

Source: Community Series (Zila: Natore), Bangladesh Population Census-2001

However, it is extremely difficult to make any precise projection about future economy of this small urban center. Considering the present level of economic activities, no major change is anticipated in the local economy in the near future.

The town has good prospects to local economic upliftment provided appropriate government policies and initiatives are taken. People have money, but they will have to convert it into capital. The following suggestions may be considered.

First, training on entrepreneurship may be arranged for prospective young and educated entrepreneurs to encourage them to invest in manufacturing, in particular.

Second, local entrepreneurs may go for consumer goods production targeting local market.

Third, prospective investors may also explore possibilities of investment in agriculture sector for local as well as export market, particularly, in fisheries, poultry and horticulture.

As stated earlier agriculture is an important source of income mainly in Natore region. Remittance is the main source of income of 40 percent of the household of SingraPaurashava (BBS, 2001 and household survey). They mainly invested on land, which is considered the safest investment, as the land value never falls. Without investment in basic industries, it is unlikely that the local economy will experience a major boost in the near future. Both government and private initiatives will bring prospective up gradation of the economy through proper policy for utilization of the remitted money inflow. It is the high time to create some special incentive packages for their investment make a rewarding role in the economy of the country.

6.3 Projection of Land use

Projected land use is a critical component to a comprehensive plan. The forecast determines the amount of land needed to accommodate future growth, and includes the land required for residential, commercial and industrial uses. In some instances, a community may have enough vacant lands within its boundary to accommodate its forecasted population increases and land use demands. In other instances, there may be a need to consider land outside a community's boundaries to accommodate this increase. According to land use projection it reveals that there is land required for residential purpose in the year 2031. The Consultants estimates about 716.17 acres of land for residential uses with a net residential density of 100 people per acre. Including existing commercial activities, the total commercial land in 2031 has been fixed at 89.28 acres. Again need of educational land for projected population will be 103.84 acres and 19.11 acres of land for community facilities. A huge land (153.98 acres) will require for open space and recreational facilities covering play field, park, Neighbourhood Park and stadium. The projection and demand on land requirements as per the planning standard approved by the PMO office of UTIDP project are discussed details in Chapter-10 and Section 10.1.2.

Chapter 7: Landuse Zoning Policies and Development Strategies

This chapter sets land use policies and development strategies for planning area. It classifies the Structure Plan area into categories and also includes strategies for optimum use of urban land resources, plans for new area development and areas for conservation and protection.

7.1 Zone of Structure Plan Area

To guide long term growth within the Structure Plan Area by means of demarcation of the future growth areas and indication of potential locations of major development zones are broadly classified into seven categories. **Table 7-1** shows the Structure Plan area zones, its area and percentage coverage. Details of the description of structure planning zones are given in the following paragraphs. **Map 7-1** and **Appendix-1** shows the structure plan of SingraPaurashava.

Table 7-1: Structure Plan Policy Zoning

Zoning	Description of the Zone	Area (acre)	%
Core Area	This area is also known as built-up area. This is defined as the area which has the highest concentration of services; it also has the highest population concentration and density. It will absorb most population growth during the Land use Plan (2011-2031) period.	175.2	6.42
Fringe Area	This zone is developing areas which will take further decades to reach the population densities of the urban core area. Low initial densities in these areas do not justify supply of a full range of services as they will initially be underused. However, it is essential that planning and reservation of rights of way, at least for primary networks, be undertaken soon to enable provision when justified by increased density levels and allowed by resources.	365.65	13.52
Peripheral Area	This is the zone where a slow trend of urbanization is continuing in unplanned manner. The area identified in the Structure Plan as the likely choice for new urban development beyond the core area. Ideally, it might be reasonable to provide primary infrastructure networks in this area to foster development and encouraged to enable a more rapid urbanization in a planned way.	415.15	15.35
New Urban Area	This zone will be the required additional area for future planned urban development as per population projection. New facilities and services like road, drains, footpath, waste transfer station and other civic services will be provided. This area is proposed to grow within 2031.	129.69	4.80
Agriculture	Agricultural land (also <i>agricultural area</i>) denotes the land suitable for agricultural production, both crops and livestock. It is one of the main resources in agriculture. The land under annual crops, such as cereals, other crops, potatoes, vegetables, and melons; also includes land left temporarily fallow; land under permanent crops (e.g., fruit plantations); areas for natural grasses and grazing of livestock.	1065.01	39.39
Water body	Water body containing an area equals to or more than 0.25 acres excluding those of khal, irrigation canal and river will be treated as this category.	345.8	12.85
Major Circulation	Major circulation contains major road network and railways linkage with regional and national settings.	206.78	7.67
Total		2703.74	100.00

Map 7-1: Structure Plan Zone of SingraPaurashava

7.1.1 Core Area

Total 175.2 acres of land, which covers 6.42% of Structure Plan area, is declared as Core Area (**Map 7-1** and **Fig 7-1**). It is located within Ward nos. 4, 5, and 8. It includes the highest concentration of services area for an example, schools, post office, police box, Clinic in Singra Bazar area etc. and it has the highest potentiality of development. Because the town developed based on the Singra Bazar, which is located at the centre of the Paurashava, there are differences in levels of provision, particularly between the formally developed and planned areas and the majority of unplanned areas. Levels of provision should be maintained in the planned areas. Since these areas are forecasted to show density increase and increased demand and therefore will require regular upgrading. The main thrust to improve services should be in the unplanned zones, particularly where the deficiencies already are great and quality of life will sharply decline when the services also have to cater for the additional population.




Fig 7-1: Total Core Area of Singra Paurashava

7.1.2 Fringe Area

A total of 365.65 acres of land covering only 13.52% of Structure Plan area is declared as Fringe Area (**Map 7-1** and **Fig 7-2**). Maximum fringe area of proposed structure plan is located North West corner of Core area. It covers large portion area of Ward nos. 1, 6 and 9. This area mainly proposed, where a slow trend of urbanization is continuing in unplanned manner. The area is identified in the Structure Plan as the likely choice for new urban development beyond the core area. Ideally, it might be reasonable to provide primary infrastructure networks in this area to foster development encouraging a more rapid urbanization in a planned way.




Fig 7-2: Fringe Area beside Core Area

7.1.3 Peripheral Area

A total of 415.15 acres of area, which covers 15.35 % of Structure Plan area, is declared as Urban Peripheral Area (**Map 7-1** and **Fig 7-3**). Maximum peripheral area is in Ward nos. 02, 07, 10, 11 and 12 of the Paurashava. This zone is developing areas that will take a longer time to reach the population densities of the urban core area. Low initial densities in these areas do not justify supply of a full range of services as they will initially be underused. However, it is essential that planning and reservation of rights of way, at least for primary networks, be undertaken soon to enable provision when justified by increased density levels and allowed by resources.




Fig 7-3: Peripheral Area in South East Corner of Singra Paurashava

7.1.4 New Urban Area

Total 129.69 acres of land covering 4.80% of Structure Plan area is declared as New Urban Area (**Map 7-1** and **Fig 7-4**). New urban area mainly located within Ward nos. 1, and 9. All these wards has partially involved with new urban area. It is assumed that town will be developed based on established as trade center which is mostly depends on successfully custom ghat and establish trading relation with others. So most of the new urban lands in Ward nos. 1 and 9 will be meet the demand of future development trend for this for this reason. A large portion of Land in Ward 1 will be used to future planned urban development as per population projection.




Fig 7-4: New Urban Area beside Paurashava Office, and Core Area

7.1.5 Agriculture

Total 1065.01 acres of land covering 39.39 % of Structure Plan area is declared as Agriculture Area (**Map 7-1** and **Fig 7-5**). Agriculture Area is quite spread all over the Paurashava.




Fig 7-5: Agriculture Land spread all over of the Paurashava

7.1.6 Water body/Retention Area

Total 345.8 acres area, which covers 12.85 % of Structure Plan area, is declared as water body (**Map 7-1**). It includes pond, ditch and all the canals and river within the Paurashava. More detail information is provided in drainage and environmental plan.

7.1.7 Major Circulation Network

It contains major road network with Natore and other neighbor urban center and also included the major road way network required for maintaining existing internal communication. Total 206.78 acres of land including proposed road which covers 7.67% of total structure plan area. **Map 7-1** shows major circulation network.

7.2 Strategies for optimum use of Urban Land Resources

7.2.1 Optimum use of Urban Land Resources

With a limited land mass, Bangladesh is the most densely populated country in the world. The land area of the country remains static amid continuously increasing population. Such a situation calls for strict regulation to utilize its scarce land resources for non-agricultural purposes. Increase in urban population means more demand for houses, roads, schools, hospitals, factories, bazars, shops, business centres, offices, other service facilities etc. Providing all these facilities require land and that is at the cost of valuable agricultural land, as the country has hardly any fallow land to accommodate all these land uses. SingraPaurashava is surrounded by valuable fertile agricultural land. Any urban expansion will cost net deduction of agricultural land that will consequently affect local food and cash crop production. Practice of thriftiness on land utilization is, therefore, essentially needed in plans and development proposals. Such practice should start through adoption of conservative and rational standards of space use and their proper application in planning, designing and development. **Table 7-2** shows the optimum use of urban land resources.

Table 7-2: Policy for optimum use of urban land resources

Policy	Justification	Means of Implementation	Implementing Agency
Policy UA/1: Optimization of Available Land Resources Growth within the established urban area is not compact in Singra. There are still large amount of land lying vacant amid all categories of land uses within the Paurashava area and beyond. Infilling of these lands should be promoted and encouraged to optimize use of land.	Keeping large land areas vacant within the existing built up area, extension of physical boundary of the town is not logical. Such a tendency might cause valuable agricultural land out of use. There is a need to economize the use of land, which is a scarce resource against an expanding population in the country.	<i>Control:</i> Imposition of tax on the land remaining vacant for a long time can be tried to discourage speculation on the land use practices. Measures should be adopted to minimize the use of land by public sector agencies. Policies to discourage large scale land acquisition for development by the public sector can be tried. <i>Promotion:</i> The public sector should develop infrastructure facilities and services in deprived areas to enable the land owners for development.	- SingraPaurashava; -Ministry of Land
<u>Policy UA/2: Utilisation of Khas Land for Urban Development</u>	Khas lands are public land that should be made best use for community purpose. Instead of evicting people from their own land for implementing development proposals, khas land should be used as much as possible.	Taking over of khas land by Paurashava that falls under different development proposals under the current development plan. Paurashava can later on hand over the land to the concerned authority that will implement the particular development proposals.	-SingraPaurashava -Ministry of Land -DC, Natore

7.2.2 Plans for New Area Development

Table 7.3 shows policy to develop new urban area. It includes justification of new area development, means of implementation and agencies for implementation.

Table 7-3: Policy for new area development

Policy	Justification	Means of Implementation	Implementing Agency
Policy Ua/3: Initiatives For New Urban Area Development	New areas with their growing stage offer excellent opportunity for organized development with little or no compensation cost for eviction and less hindrances in motivation of the local residents in favor of organized development,	Participatory approach to new urban area development is to be supported by innovative ideas of spatial development. Long motivational activities will have to be carried out for this purpose. Public sector with technical and financial support of the private sector and cooperation from service giving agencies will make the task easier.	- SingraPaurashava - DPHE - Private sector

7.2.3 Areas for Conservation and Protection

To ensure livable environment in the planning area, different areas are conserved in various forms, namely agricultural land, low land, pond and natural drainage, green belt, historic and heritage areas, etc. Details are given in **Table 7.4**.

Table 7-4: Area for conservation and protection

Type of Land	Means of Implementation	Implementing Agency
Loss of Productive Agricultural Land: The Master Plan area has a vast agricultural land in the northern side of this project. After implementation of the project, environment of agriculture will be converted into non-productive urban and semi-urban area.	The EIA Guidelines of DOE emphasized on the avoidance of productive agricultural land for any development project. Therefore, it will be wise to consider more economical use of land to avoid fertile lands. The town expansion and land acquisition should be based on the growth rate of population. According to population projection for the year 2031, the present residential land use area will grow with increasing density. So a large share of agricultural land can be spared at least for the time being.	- SingraPaurashava - DOE
Low Land, Pond and Drainage Path: A total of 171 ponds with an area equal to or more than 0.25 acres within the Paurashava are declared as retention area. In no way permission for filling up of these ponds should be given. Paurashava should acquire these ponds at suitable time to use them for retention and emergency use.	This area is declared as water body in the Master Plan. As per the guideline of Wetland Conservation Act 2000, this area will be conserved as water body. According to population projection for the year 2031, the present residential land use area can be developed with increasing density up to this year. So a large share of water body can be spared.	- SingraPaurashava - Water Development Board
Green Belt: The Bank of the Atrai river is declared as green belt. This area will be used for afforestation and recreational purposes for conservation of environment and creation of opportunity for tourism development in this town.	This area is declared as green belt in the Master Plan.	- SingraPaurashava

7.3 Policies for Development

This section of the chapter sets forth strategies and policies for various components of the Master Plan on sectoral basis.

7.3.1 Policies for Socio-economic Sector

Population

Controlling population should be given utmost importance nationally, as because of the uninterrupted population growth, the country's economic problems are being accentuated, pressing on its resources. It makes poverty reduction difficult, which is the key to overall national

development. It is, therefore, necessary to enhance population control drive. The people at the grassroots can play an effective role in this regard. An efficient, well trained and well paid grassroots level work force can help profoundly in achieving the targets of population control policy of the government. Side by side, promotion of education can be very effective in the creation of awareness about small family size. The Paurashava may undertake relevant measures in line with national objectives to strengthen its own position in population planning.

Strategy

Raise the level of education among mass people and emphasize more on grassroots level family planning workers' services with effective delivery of birth control services.

Table 7-5: Policy for Population Sector

Policy	Executing Agency
<u>Popu/1:</u> Declaring population as one of the most critical sectors of national development Justification: Per capita national growth is being eaten up by constantly growing population. By controlling population, national benefits earned from economic growth can be shared in a better way, raising the level of living standard of the people.	-Ministry of Planning -Ministry of Health and Family Planning
<u>Popu/2:</u> Putting more efforts and resources in raising the level of education. Justification: Education would not only create awareness among the masses about the benefits of small family size, it will also help secure better job with higher pay that would reduce poverty.	
<u>Popu/3:</u> Creation of well paid and well trained grassroots level family planning workers for motivational work. Justification: Grassroots level workers can give door to door motivational services and distribute birth control materials in a better way. To get good services they must be efficient and well paid.	-Ministry of Planning -Ministry of Health and Family Planning

Economic Development and Employment Generation

Economic development of any place is associated with generation of employment. The generation of employment depends on the rate of investment in various sectors of an economy. An urban economy of any town starts building up with investment in the basic sector that leads to the building up of the non-basic sector. Investment in basic sector is not very bright in Singra as it is a very small town with a very small size of population. However, the Paurashava must ensure that any foreseeable opportunity in economic development is given due attention for its own growth and economic benefits.

Strategy:

- Creating basic sector investment climate and leading the local economy forward through promotion of Small and Medium Enterprises (SME).

Table 7-6: Policy for Economic Development and Employment Generation

Policy	Executing Agency
<u>Econ/1:</u> Provision of bank loans on easy terms to attract prospective investors in the Justification: Easy loans would encourage and attract prospective investors for investment in small scale industries.	-Ministry of Industries -Ministry of Commerce
<u>Popu/2:</u> Taking of measures to channelize remittance to value adding productive sectors. Justification: Larger amount of remittance is being diverted to land purchase, which is considered as the safest investment. This huge capital may be diverted to productive sectors to help create more employment.	
<u>Popu/3:</u> Arranging entrepreneurship training programmes for prospective investors. Justification: There are many potential investors who are ignorant of the ways and means of investment and operation of an enterprise. The training can help them get educated in these lines.	-Ministry of Industries -Ministry of Commerce

Housing

As the town has low level of population, housing is yet to become a problem here. Housing policy and programmes are provided and executed by the national government. There is no local office of the National Housing Authority to execute housing programmes at Upazila level. As a local government, Paurashava can facilitate housing area development by means of providing road infrastructure, drainage, water supply, etc in designated housing zones. The consultant supports the prevailing national housing policy and advocates its execution at all levels, which at the moment is highly lacking.

No slums are observed in this small town, the way they are exposed in large cities. So no slum and squatter related problems are there in the town. This provides a better scope for planned housing development in the Paurashava.

Strategy:

- Upholding the role of Paurashava, as a facilitator to provide all necessary infrastructure and services to enable housing by people in general. As a least cost approach, involvement of the land owners can be encouraged in housing area development on a public-private partnership basis.

Table 7-7: Housing and Slum Improvement

Policy	Executing Agency
<u>Policy House/1:</u> Provision of necessary services and facilities to promote housing at private sector.	- National Housing Authority

Policy	Executing Agency
Justification: It is more difficult to provide housing on public sector initiatives, as it involves funding and land acquisition that takes a long time. By providing infrastructure and services, general people can be encouraged to build their own houses.	- Ministry of LGRD - SingraPaurashava
Policy House/2: Housing zone land owners can be involved in a participatory development approach, where Paurashava will provide infrastructure and the cost will be shared by land owners.	- National Housing Authority - Ministry of LGRD - SingraPaurashava

Social Amenities and Community Facilities

Social amenities and community facilities include, education facilities, health facilities, open space recreation facilities like, park and playground, amusement park and community centre. For comfortable and healthy urban living, these facilities are the fundamentals. Since these are social services, they must be provided by the public sector agencies as public good. For education and health facilities, the national governments have policies and there are separate ministries and their agencies to execute the policies through programmes and projects. There are also Upazila level offices of the concerned agencies to take care of the execution of national education and health policies and programmes. For providing amenities like, park and playground and community centre, the responsibility lies with the Paurashava.

For park and playground, the Paurashava may secure local khas land. The open space recreation is difficult to provide as population expands and land price goes higher. Once time is lost, vacant lands are also lost. Amid soaring land price and absence of vacant land, it becomes extremely difficult to provide open space recreation. So, it is better to secure vacant lands for open space before density of population increases and land becomes scarce and pricier. For community center, intensive use of land should be made by making multiple use of the same space, for example, providing community center, ward councilor's office, clinic or any other use in the same building.

Strategy:

- Exploring khas /public land within the Paurashava and using the unused/vacant land for providing amenities, before density of population increases and land becomes scarce and dearer.

Table 7-8: Social Amenities and Community Facilities

Policy	Executing Agency
Policy-Amenity/1: Procurement of khas and other public land for park, playfield, community centre.	-Ministry of Land -DC Office, Natore
Justification: Since above facilities are non-revenue earning, they should be procured at least cost.	- Ministry of LGRD - SingraPaurashava
Policy-Amenity/2: Land should be procured for open space facilities as quickly as possible, because when land value will be higher, cost of providing the facilities will also be very higher. Besides, with the growth of population, vacant land will disappear gradually, so no land will be available at strategic locations for providing open space facilities.	-Ministry of Land -DC Office, Natore - Ministry of LGRD&C - SingraPaurashava

7.3.2 Physical Infrastructure Sector

Transport

By far, transport is the most important means to revitalize an urban center. Intra and inter urban transportation facilities create economies of scale for prospective investors and enables easy and comfortable mobility of the residents. Easy and cheaper transportation of raw materials and finished goods create good investment climate for manufacturing enterprises that lead to development of the service sector firms. New employment generates and the non-basic sector expands leading to thriving urban center. To create transportation facilities, quality inter-Upazila and inter-District road network will have to be created that makes movement faster and easy. With good transport infrastructure, economic development may become attractive. Besides, quality of local roads will have to be upgraded to encourage people live in the town. Once population starts increasing, it will expand local consumer market and will attract new investments in consumer goods production.

Strategy:

- Creation of efficient inter-city and intra-town communication for easy transportation of goods and passengers.

Table 7-9: Policy for Transport Sector

Policy	Executing Agency
<u>Policy-Transport/1:</u> Development of efficient inter-city road network with standard road. Justification: Increased inter-city mobility will increase business transactions and generate investment and employment.	- Roads & Highways Department (RHD)
<u>Policy-Transport/2:</u> Promotion of efficient road transport facilities between urban centers. Justification: Not only that communication is needed between urban centers, but to attract investment, emphasis must be laid on quality of roads built.	
<u>Policy-Transport/3:</u> Development of local road network through participatory approach. Justification: Development of roads will involve huge cost. Participatory development will enable cost sharing, which will reduce cost of road construction substantially.	- SingraPaurashava - Local Government Engineering Department (LGED)

Utility Services

Utility services are the most essential parts of urban life. To make an urban center livable, there must be adequate provision for utility services. Utility services include water supply, solid waste management, power supply, sanitation and drainage. Except power supply, the rest are the responsibilities of the Paurashava.

Strategy:

- Attainment of self reliance in revenue collection and adoption of participatory approach to service provision to ensure better services and facilities to the people.

Table 7-10: Policy for Utility Services

Policy	Executing Agency
<u>Policy-Utility/1:</u> Exploration of alternative sources of water to ensure sustainable supply. Justification: Amid constant rise of urban population, it is time to explore alternative sources of water like, rain water harvesting and surface water supply.	- LGED - SingraPaurashava
<u>Policy-Utility/2:</u> Involvement of beneficiaries in solid waste management. Justification: Involvement of beneficiaries in solid waste management will make the operation more effective and reduce financial responsibility of the	
<u>Policy-Utility/3:</u> Exploring re-use and recycling of waste materials to extract resources. Justification: Re-use and recycling of waste materials will produce resources and reduce cost of waste management.	- SingraPaurashava - NGOs and CBOs
<u>Policy-Utility/4:</u> Publicity on the benefits of hygienic sanitation to motivate people and enable people to have easy access to sanitary materials. Justification: Motivation will encourage people to adopt healthy sanitation and reduce	
<u>Policy-Utility/5:</u> Protection of natural drainage system and preparation of hierarchical drainage network. Justification: Natural drainage systems are being grabbed and filled up, which increases the risk of water logging. Well planned hierarchical drainage network helps smooth drainage of storm and waste water.	- LGED - SingraPaurashava

7.3.3 Environmental Issues

From environmental point of view SingraPaurashava is not yet badly affected. There are some issues that must be taken care of. The issue of sanitation has already been dealt within the utility services section. Except cyclone, there is no natural hazard. There is no mentionable air, water or soil pollution in the Paurashava from any mentionable sources at present.

Natural Resources

The Paurashava is not endowed with many natural resources that can be conserved. Among the meager natural resources that are available, 487 numbers of ponds and natural drainage canals can be mentioned. Out of the total ponds 171 with an area equal to or more than 0.25 acres and the natural khals need to be protected and conserved to ensure sustainability in drainage and water supply of the Paurashava.

Strategy:

- All khas land and canals should be vested with Paurashava for use in community interest.

Table 7-11: Policy for Natural Resources

Policy	Executing Agency
<u>Policy-Nature /1:</u> All khas lands within the Paurashava must be assessed and handed over to the Paurashava for use in community interest. Justification: This will prevent misuse of khas lands by political & powerful local people.	- Ministry of Land - SingraPaurashava
<u>Policy-Nature /2:</u> All natural canals within the Paurashava must be vested with the Paurashava for maintenance and proper use as drainage canal. Justification: This will help prevent unauthorized occupation & filling of natural drainage.	

Chapter 8: Implementation Issues

This chapter deals with the issues of implementation of the Master Plan. Here, recommendations have been made about capacity building and resource mobilization for the implementation of the plan.

8.1 Institutional Capacity Building of the Paurashava

In the present context of spatial and legal jurisdiction of the Paurashava for planned development of its area, some recommendations are made here. Also, observing the financial and Institutional strength of individual stakeholders in relation to their liabilities and identifying their shortages and absence of any perfect coordinating body, some suggestions have been made as remedial measures as a whole.

- All urban local governments including Upazila level Paurashavas must be given More independence and autonomy to perform their responsibilities. At the same time, their accountability to the government and people regarding their performance has to be ensured. For this purpose the legal framework of the urban local governments has to be reviewed and updated. The legal provisions have to be consolidated and simplified and make them compatible to changing circumstances. Opportunities must be created in the Act allowing scope for privatization of service providing activities.
- To avoid duplication of development functions, there should be clear line of separation between central government and the urban local government.
- A double entry cash accounting system has to be introduced to modernize the accounting system. For this purpose, massive training programme has to be arranged for the relevant municipal staff.
- To improve revenue collection, the urban local governments should be given more power and responsibilities. Measures should be taken for strengthening the Paurashava administration for municipal development.
- Section-50 of the Local Government (Paurashava) Act,2009needs to be revised and more power should be given to the Executive Officer for appointment of employees.

It can not virtually function effectively as a Paurashava under such a stringent financial condition. To function, effectively, it must raise its revenue earning. But it is reported that the Paurashava can not collect all its holding tax from the citizens. Holding tax is the most important source of its own revenue earning. It must take care to ensure 100% recovery of holding tax. The Paurashava can not function effectively depending upon government grant only. The existing manpower position of the Engineering, Development control and Accounts should be substantially raised to handle future volume of work. Moreover, additional staff especially for the implementation of Master Plan will soon be required.

The present plan package imposes a large number of development projects on SingraPaurashava for implementation. Paurashava will not only be the custodian of the plan, it will also directly implement much of the development projects. Besides, it will also be responsible for monitoring and implementation of the development projects by other urban development and service giving agencies. This situation calls for strengthening of the existing capability of Paurashava.

8.1.1 Staffing and Training

As a traditional system of the Paurashava, first class and second class are appointed by the Ministry of Local Government and other staffs are appointed by Paurashava. In SingraPaurashava, the revenue income is too low. That's why it is not capable to pay the salary of all the officials and staffs. The salary is recovered from the government grant and BMDF allocation. This is the main reason for under staffing of the Paurashava.

There is no proper arrangement for staff training. As a result, the staffs are mostly unskilled. They can not deliver proper service to the citizens. Besides, most of them are not qualified enough to render proper services.

8.1.2 Lack of Automation

Most works in the Paurashava are done manually. Such practice delays works and deprives the citizens from services. This is also a source of mal-practice and corruption. Modern office and working equipment should be installed. Use of modern technology will increase efficiency in planning and record keeping, finally expedite decision making process.

8.1.3 Town Planning Capacity

8.1.3.1 Institutional Framework

To rearrange the institutional framework for the Paurashavas recently the government has made a committee to reform the organogram of all the Paurashavas of Bangladesh. According to the clause no. 72-78 (Paurashava Officer & staff, provident fund etc) of Paurashava Act, 2009 and on the basis of the type and category of works, the committee suggested appropriate section/units/divisions within the Paurashava framework. Planning unit or division will be necessary to set sequentially as the authority can perform it's mandatory responsibility 'town development and control' well and serve the inhabitants presently as well as in the future. The planning unit/division may have some sections that are as follows:

Planning unit/Division:	a) IT Section
	b) Planning Section
	c) Beautification and recreation Section

According to the division and it's relevant sections, what so ever appropriate with the necessity and capacity over time, it is recommended to set up necessary manpower for each category of Paurashava. Possible scope of proposed planning unit/division is given bellow:




Fig 8-1:Scope of Work for Planning Division

8.1.3.2 Lack of Paurashava Town Planning Capacity

At present, the Paurashava has no town planning department or any appropriate manpower to prepare and implement the Master Plan. For proper implementation of the Master Plan for each Paurashava under UTIDP, establishment of a separate planning unit is indispensable. The Paurashava must strengthen its capacity to implement its Master Plan when it will be completed. It will otherwise be in trouble for implementation, monitoring and updating the Master Plan.

Singra is a 'A' class Paurashava. For the 'A' class Paurashava Government approved an organogram/ manpower requirement. If we compare the existing manpower with the approved organogram we find that there is a huge gap between the two. Many positions have been vacant since the inception of Paurashava. Out of total 130 numbers of allocated positions only 47 numbers are filled up. However, strengthening of the Town Planning Unit is a pre-requisite for successful implementation of the Structure Plan. Following organogram of the Town Planning Unit is proposed for staffing capacity building of this Unit.

8.1.4 Legal Aspects

The drive to establish strong urban local governance in the Paurashava is yet to be legalized. The governance programs at present are operated project wise based on the formulated policies of the implementing agencies of the national government. The Laws that the country inherited are mostly prepared during the colonial rule to serve its own interests. Even after independence from the British, the issue of good governance was not infused into the new Acts formulated.

8.1.5 Good Governance in Legal Provisions

There is hardly any Act where the elements of good governance are clearly visible. The consultant has identified some Acts, where some elements of good governance can be traced.

The Paurashava/Municipal Act/Ordinances prepared at different times since 1960's have iterated for the preparation of Master Plan by the Paurashava/Municipality for its planned development. So far urban local government Ordinances/Acts made in 1967, 1977, 2008 and 2009, all suggested for planned development. The Local Government (Paurashava) Act, 2009 has made the provision of having a Master Plan prepared by a Paurashava within five years of its inception. The function of the Paurashava also includes that it ensures planned development following the rules of the Ordinance. But there is no provision for public participation in the Paurashava Ordinance 2009. In all these legal documents, people's role has been ignored which is the violation of the norms of good governance. The constitution of the Peoples' republic of Bangladesh clearly spells out that the Government should work to minimize the gap between urban and rural areas. A planned Paurashava development in that pursuit can provide necessary services to improve quality of life in both urban and rural areas within the Upazila.

8.1.6 Financial Issues

Governance in SingraPaurashava

Financial governance refers to transparency and accountability of financial matters. All financial matters must be transparent to all. People must know about the policies and programs of the Paurashava, how much revenue is collected each year and the amount of expenditure made on annual development. They must also be answerable to the people on how the public money is being spent and accounts being maintained.

The Ministry of LGRD and Cooperative has undertaken a number of projects in respect of establishing governance in upgrading Paurashava accounts system, like, UGIIP, STIFPP. Computer and accessories are supplied under these projects for automation of the accounts system. Besides, trainings are also offered to the Paurashava accounts staff for enabling introduction of automation in accounts system. But all these services have not yet reached SingraPaurashava.

Revenue Management

The Paurashava still follows a traditional management system in tax collection and revenue management though a scheme of computerized automotive financial system has already been introduced in this Paurashava. Assessment section is responsible to assess the tax of the Paurashava and tax collection, and license and bazar section are responsible to collect the tax of the Paurashava. The public is mainly informed about tax collection during the presentation of annual budget. They may, however, get information from the councilor or Paurashava accounts office.

Paurashava's Financial Capacity and Plan Execution

The main focus of Paurashava financial governance is to establish automation in entire financial management. This includes computerization of accounts system, holding tax management, and billing of different service charges. Software for above functions have been supplied and installed in the Paurashavas covered by financial automotive projects. The projects also provided training to the relevant staffs for functioning of the systems. With the implementation of these projects people can now instantly know about the status of their tax payment, bill payment, and licensing. This has not only made the functions of the Paurashava easy, but also has freed the citizens for paying bribe, and experiencing hassle. The size of annual budgets of the Paurashavas indicates the poor financial status of the Paurashavas. With low income, SingraPaurashava will have to depend substantially on the government funding for implementing the development projects. But the government has limitations of its resources. In such a situation, if the Paurashava can not raise its own revenue adequately, it will not be able to execute much of the development projects under the Master Plan.

8.1.7 Monitoring, Evaluation and Updating

Monitoring and evaluation is a very important part of plan implementation. Monitoring helps check if the plan is being implemented properly. It also measures the level of implementation of the plan. If the plan implementation is not on track, corrective measures can be taken to put execution on the track. After expiry of any plan, evaluation is made about the errors and omissions. Such evaluation helps take corrective measures in the next plan. Such monitoring and evaluation must

be carried out from within the Paurashava. But SingraPaurashava is not equipped with qualified manpower to make such evaluation. Monitoring and evaluation of a plan is essentially, the responsibility of qualified and experienced planners. As there is no planner in the Paurashava, monitoring of plan implementation will be seriously affected. However, plan evaluation can be accomplished by means of out sourcing as and when it is required.

8.1.8 Periodic Review and Updating

The plan package needs to be updated regularly to make it respond to the spatial changes over time. But such updating would require relevant technical professionals and requisite fund that are highly lacking in SingraPaurashava. As there is no planner or planning section in the Paurashava, review and updating of the Master Plan will require service of senior level planners that Paurashava might not be able to provide. This service will have to be procured by out sourcing and the Paurashava is not even capable to accomplish this financially either. This will create problem when the plans or its components gets obsolete or need to be changed. Another problem would arise when the duration of plans ends. It is necessary that the entire plan document (including all planning and land use proposals) should be reviewed every 4th year of the plan period and will come into execution from the 5th year. The aim of the review will be to analyze the status of implementation of plan provisions, the changing physical growth pattern, infrastructure development, and the trend of public and private physical development including growth direction.

A new set of plans will have to be prepared replacing the old ones. This problem, however, can be overcome by undertaking another planning project by LGED. So, for regular updating and changes, and plan implementation monitoring, the Paurashava should immediately set up a planning section with a number of planners and other staff. The section will not only look after planning, but will also be responsible for development control, estate management, and project preparation. Since the planners would be qualified and skilled in computer operation, they can also help achieving automation of the Paurashava functions.

8.2 Resource Mobilization

Resource mobilization will be one of the most challenging tasks in implementing the current plan package. Though the development proposals are said to be executed by a large number of development agencies, but it is beyond doubt that the heaviest burdens will have to be shouldered by the Paurashava. As a local government agency, it suffers from resource constraint due to low level of urbanization and investment by both public and private sectors. The land value will maintain perpetually low growth rate in the town. Therefore, prospect of mobilization of substantial resource from sale of serviced land is extremely meager. For the same reason, revenue earning from betterment fee, planning permission and other sources may also remain low. Paurashava is heavily dependent on the government for executing its development projects as it is unable to collect sufficient revenue from its tax and non-tax sources. Therefore, it is clear that execution of development projects under the current plan will depend heavily on the government response to supply adequate fund. This situation calls for increasing revenue earning by generating new revenue sources.

8.3 Concluding Remarks

From the past experience, it has been observed that plans are prepared for organized development, but development control has been subject to negligence. In most cases, execution

has been piece-meal. It is unfortunate that town planning has not yet become a part of our urban development culture. Individuals develop lands and construct buildings with a little respect for planned development, and the concerned authority is also unable to exercise full control on development. Some strict measures are necessary to make stakeholders follow up plans and development rules. Awareness is to be built among the people to follow the Master Plan provisions and plan. Government agencies must be compelled to follow plans. Existing laws in this regard must be updated incorporating provisions of plan execution.

Chapter 9: Urban Area Plan

This is the first chapter of Part- B that starts with Urban Area Plan. Urban Area Plan is the mid level plan that covers the existing Paurashava. It lays down the land use zoning plan and infrastructure development proposals at the town level. Land use planning is an important part of Master Plan ensuring that land is used efficiently for the benefit of economy, society and environment of SingraPaurashava. This planning means the scientific, aesthetic, and orderly disposition of land, resources, facilities and services with a view to securing the physical, economic and social well-being of urban communities.

9.1 Goals and Objectives of Urban Area Plan

Urban Area Plan is the first phase illustration of the Structure Plan intended to be implemented over a time span of 10 years that includes 1st phase (1st-5th year) and 2nd phase (6th-10th year) of development programs. The Urban Area Plan has been prepared within the policy framework of the Structure Plan and aims to attain the overall project objectives. So there is a hierarchical relationship between the two. In fact, Urban Area Plan is the first phase detailed illustration of the policies and strategies of the structure plan.

The preparation of Master Plan for SingraPaurashava is aimed towards its future development, and covers the areas that are likely to become urban in future. The Urban Area Plan is aimed to:

- determine the present and future functional structure of the town, including its land uses; and
- provide infrastructure proposals for improving and guiding development of future urban area.

9.2 Methodology and Approach to Planning

The base map supporting for land use survey was obtained from the physical feature survey that contained all categories of physical features within the planning area (Chapter 3 of Survey Report). During physical feature survey, all structures and the functions of principal buildings were picked up and depicted on the map. The physical features were superimposed on a mouza map and printed for land use survey on the map. The map was carried to the field by investigators for detailed plot to plot land use survey (Chapter 4 of Survey Report). The field investigators carrying the map visited each and every plot and the structures therein and noted their uses in writing and marking them on the map with colour pencil. They also verified the land uses and put during the physical feature survey. Back in the office, the common land uses of plots were delineated in the map as per land use format given in the ToR. The delineated zones were then digitized and a new land use map was prepared for the entire planning area. After land use demarcation, field checking was done to correct possible errors.

Urban Land Use Plan is aimed to guide the physical development of Singra town including its economic and social activities. This plan adheres to the policy directives spelled out in the Structure Plan. The current Urban Area Plan is akin to the traditional Master Plan approach prevalent in the country that designates plot-to-plot use of land apart from infrastructure development proposals. Thus it will also serve as a development control mechanism/instrument.

The Urban Area Plan is, therefore, more rigid than Structure Plan. Making a land use plan on a cadastral map makes the Urban Area Plan more rigid. Once the plan on a cadastral map is drawn and accepted by the government and formalized, it gains a formal status and thus becomes a binding for all concerned.

The objectives of the Urban Area Plan have been attained through: ,

- orderly location of various urban land uses;
- location of appropriate transportation and drainage network; and
- orderly location of services and facilities.

9.2.1 ,Delineation of Planning Areas

For delineation of Master Plan area, it is necessary to identify the possible future urban growth locations. The objective of project area demarcation is to determine the boundary of the area and mark it on the map as well as in the field. Logic behind the delineation of the Planning area of SingraPaurashava for the year 2031 has been done on the basis of the gazette notification of the Paurashava and after the reconnaissance survey within the area, the discussions with all groups of stakeholders, analyzing the present trend of developmental growth of the town. Cooperation of the Paurashava was more important in delineating the Paurashava area in the cadastral map and the future planning area boundary (Detail was given in Chapter 2, Section 2.4 of Survey Report). As conversant with local conditions and the future trend of development, valuable advices were received from the Pura Mayor, engineers and other staffs. **Table 9-1** presents the detail about the mouzas, within the 9 wards of the Paurashava.

Table 9-1: List of Mouza Maps of Singra Paurashava

SI No	Paurashava	Mouza Name	J.L No	Sheet No	Mouza Type	Source
1.	Singra	Aow Kuri	343	0	RS	DLRS
2.	Singra	Balua Basua	341	0	RS	DLRS
3.	Singra	Baluvora	373	0	RS	DLRS
4.	Singra	Boro Has Pukuria	279	0	RS	DLRS
5.	Singra	Boro Maguri	346	0	RS	DLRS
6.	Singra	Boro Maguri	346	0	RS	DLRS
7.	Singra	Boro Sawail	387	1	RS	DLRS
8.	Singra	Bosta	348	0	RS	DLRS
9.	Singra	Chak Gopal	337	0	RS	DLRS
10.	Singra	Chak Singra	344	0	RS	DLRS
11.	Singra	Choto Has Pukuria	278	0	RS	DLRS
12.	Singra	Dakhin Domdoma	276	0	RS	DLRS
13.	Singra	Falia	259	0	RS	DLRS
14.	Singra	Hat Singra	339	0	RS	DLRS
15.	Singra	Kata Pukuria	338	0	RS	DLRS
16.	Singra	Katua Bari	370	0	RS	DLRS
17.	Singra	Niagain	333	1	RS	DLRS
18.	Singra	Niagain	333	2	RS	DLRS
19.	Singra	Niagain	333	3	RS	DLRS
20.	Singra	Par Sawail	369	1	RS	DLRS
21.	Singra	Par Singra	340	0	RS	DLRS
22.	Singra	Patkol	372	0	RS	DLRS

SI No	Paurashava	Mouza Name	J.L No	Sheet No	Mouza Type	Source
23.	Singra	Poran Hati	334	0	RS	DLRS
24.	Singra	Porbo Masinda	335	0	RS	DLRS
25.	Singra	Singra	342	0	RS	DLRS
26.	Singra	Sohag Bari	371	0	RS	DLRS
27.	Singra	Sola Kuri	345	0	RS	DLRS
28.	Singra	Uttar Domdoma	336	0	RS	DLRS

Source: DLRS, 2010

9.2.2 Content and Form of Urban Area Plan

The Urban Area Plan is presented in both map and textual format. The plan map is presented in 1:1980 or 1 inch to 165 feet scale, superimposed on latest cadastral/revenue map having plot boundaries within mouzas. The plan is accompanied by an explanatory report supported by necessary figures, maps and data. The report explains the various plan proposals and other components of the plan. At present, the Urban Area Plan covers the total area of Structure Plan area of 2703.74 acres with a present population of 33192 of SingraPaurashava.

The Urban Area Plan of the Master Plan of SingraPaurashava contains several components. These are:

- i) Land Use Plan;
- ii) Transportation and Traffic Management Plan;
- iii) Drainage and Environmental Management Plan and
- iv) Proposals for Urban Services.

Chapter 10: Landuse Plan

The Land Use Plan is the main part of the Urban Area Plan and is planned for the period of first 10 years. The proposals in the Land Use Plan will be implemented through the 1st and 2nd phase development programs of the Master Plan. The 1st phase development projects are identified as priority projects and are listed in the Ward Action Plan for implementation within the first five years of the Master Plan.

10.1 Existing and Projected land use

This section describes the analysis of existing and proposed land uses and at the same time mentions estimation on the requirement of land for different land uses. It also lays down the land use zoning plan and infrastructure development proposals at the town level.

10.1.1 Existing Land Use

Map 10-1 illustrates how the land uses are distributed at present in the Paurashava area. The information helps the preparation of Master Plan providing background information for selection of areas of different land uses.

In the land use pattern of the Paurashava, 16 types of land uses are found. It is clearly evident from the table that agricultural land use (almost 65.40%) dominates the Paurashava area, followed by residential (16.62%), water bodies (More than 13.14%), circulation network and transport and communication (only 0.20%), and government services and educational land use occupy same percentage of land (More than 0.45%).

Table 10-1: Existing Land use Classification of Singra Paurashava

Sl.No.	Land Use Category	Area in Acres	%
1.	Agriculture	1768.11	65.40
2.	Circulation Network	51.73	1.91
3.	Commercial	22.19	0.82
4.	Community Services	5.46	0.20
5.	Education and Research	12.18	0.45
6.	Governmental Services	6.43	0.24
7.	Industrial	15.41	0.57
8.	Miscellaneous	2.00	0.07
9.	Mixed Use	3.29	0.12
10.	Non-Government Services	0.46	0.02
11.	Recreational Facilities	0.29	0.01
12.	Residential	449.25	16.62
13.	Service Activity	1.87	0.07
14.	Transport and Communication	1.40	0.05
15.	Urban Green Space	8.50	0.31
16.	Water body	355.18	13.14
17.	Forest	0.00	0.00
18.	Restricted Area	0.00	0.00
Total		2703.74	100.00

Source: Land Use Survey, 2008

Map 10-1: Existing Land Use Map of SingraPaurashava

Singra Paurashava has followed its major development along the Natore-Bogra road. The main population is engaged with the farming.

10.1.2 Land Requirement Estimation

The main basis of future land requirement will be the population size of the Paurashava and area will be covered by each utility service. The existing services have to be considered in the forecasts. Land requirements for different types of utility services have been analyzed following the standard developed jointly by the team leaders of all packages and urban planners from Project Management Office (PMO) of the UTIDP. The category wise land allocations are provided below.

Table 10-2: Planning Standard Considered for Land Uses

Types of Land Uses	Recommended Standard Provision
	(unit)
General residential	100 – 150 persons/1 acre
Real Estate – Public/Private	200 population/ 1 acre
Roads	
Paurashava primary roads	150 – 100 feet
Paurashava secondary roads	100 – 60 feet
Paurashava local roads	40 - 20 feet
Education	
Nursery	0.5 acre/10,000 population
Primary School/ kindergarten	2.00 acres/5000 population
Secondary/High School	5.00 acres /20,000 population
College	10.00 acres/20,000 population
Vocational Training Centre	5 - 10 acres / Upazilla
Other	5.00 acres / 20,000 population
Open Space	
Play field/ground	3.00 acres/20,000 population
Park	1.00 acre /1000 population
Neighborhood park	1.00 acre /1000 population
Stadium/sports complex	5 – 10 acres/Upazila HQ
Cinema/ Theatre	1.0 acre /20,000 population
Health	
Upazila health complex/ hospital	10 -20 acres/Upazila HQ
health centre/Maternity clinic	1.00 acre/ 5,000 population
Community Facilities	
Mosque/Church/Temple	0.5 acre /20,000 population
Eidgah/	1.0 acre/20,000 population
Graveyard	1.00 acre /20,000 population
Community centre	1.00 acre /20,000 population
Police Station	3 – 5 acres/Upazila HQ
Police Box/outpost	0.5 acre/ per box
Fire Station	1.00 acre/ 20,000 population
Post office	0.5 acre /20,000 population
Commerce and Shopping	
Wholesale market	1.0 acres/ 10000 population
Retail sale market	1.0 acres/ 1000 population
Corner shops	0.25 acre/per corner shop
neighborhood market	1.00 acre/per neighborhood market
Super Market	1.50 – 2.50 acres/per super market

Types of Land Uses	Recommended Standard Provision
	(unit)
Utilities	
*Solid waste transfer station	Minimum 20 decimal per ward
* Solid waste disposal site	Minimum 5 Acre per Paurashava
Electric sub-station	1.00 acre/20,000 population
Telephone exchange	0.5 acre/20,000 population
Fuel Station	0.5 acre/20,000 population
Industry	
small scale	1.50 acres /1000 population
cottage/agro-based	1.00 acres /1000 population
Transportation	
Bus terminal	1.0 acre /20,000 population
Truck terminal	0.50 acre /20,000 population
Launch/steamer terminal	1.00 acre /20,000 population
Railway station	4.00 acre / per Station
Baby taxi/tempo stand	0.25 acre /one baby taxi/tempo stand
Rickshaw/van stand	0.25 acre /Rickshaw/van stand
Passenger Shed	0.25 acre /Passenger Shed
Administration	
Upazila complex	15.00 acres
Paurashava office	3 – 5 acres
Jail/Sub-Jail	10 acres/Upazila HQ
Agri-extension Farm	10 acres/Upazila HQ
Urban Deferred	10 percent of the total built up area
Reserve	-

Source: UTIDP Planning Standard, LGED

Housing

Housing is the most significant segment of urban development scenario. The future housing area need to be based on a recommended planning standard of 100/150 persons per acre. With this standard, the estimation shows, the maximum land required to accommodate total projected population (71617) in the year 2031 will be 716.17 acres. Existing residential land of SingraPaurashava is 449.246 acres and net residential density is 159persons per acre. The consultant, extend the existing housing land (716.17 acres) for the population of the Paurashava in 2031 (net density will be about 150 persons per acre). **Table 10-3** shows the detail.

Table 10-3: Estimation of Housing Land Requirement

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
General Housing	150 persons/acre	477.45	449.246	Required land to accommodate the future population
	100 persons/acre	716.17		

Source: Estimation by the Consultants

Commerce and Shopping

Market facilities are usually provided privately on commercial basis depending on the trend of sale of goods. So it is not possible to fix a standard or project actual area for these services. The

standard for commercial use can only be applied if ever these facilities are provided by the Paurashava. However, for the sake of current planning, we can earmark land as per standard at appropriate location, where commercial facilities may be developed privately or publicly. The total commercial land in 2031 has been estimated at 89.28acres. **Table 10-4** shows the detail.

Table 10-4: Estimation of Land Requirement for Commerce and Shopping

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Wholesale market	1.00 acre/ 10000 population	7.162	10.91	NR
Neighborhood/Local market	1.00 acre/per neighborhood Market	9	0.00	9.00
Retail Sale Market	1.0 acres/ 1000 population	71.62	3.50	68.12
Super Market	1.50 – 2.50 acres/per super	1.50	0	1.5
Total:		89.28	14.41	74.87

Source: Estimation by the Consultants

Industry

According to approved planning standard, the total land for industries is estimated to be 143.23 acres with 71.62 acres for small scale industries and 71.62 acres for Heavy industries. **Table 10-5** shows the details.

Table 10-5: Estimation of Land Requirement for Industries

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Small scale	1.50 acres /1000 population	71.62	15.42	56.22
Heavy Industries	1.00 acres /1000 population	71.62	0.00	71.62
Total:		143.23	15.42	127.83

Source: Estimation by the Consultants

Education

Estimation of land according to standard indicates that there will be a land requirement of 103.84 acres to accommodate educational facilities by the year 2031. Existing land uses under various education facilities of SingraPaurashava is 11.96. There will be need of additional 91.88 acres of land for education facilities. Details are shown in **Table 10-6**.

Table 10-6: Estimation of Land Requirement for Education Facilities

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Nursery	0.5 acre/10,000 population	3.58	0.47	3.11
Primary School/ kindergarten	2.00 acres/5000 population	28.65	2.01	26.64

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Secondary/High School	5.00 acres/ 20,000 population	17.90	3.86	14.04
College	10.00 acres/20,000 population	35.81	3.62	32.19
Vocational Training Centre	5 – 10 acres / Upazila	5	0	5.00
Madrasa	-	-	1.64	-
Other	5.00 acres/ 20,000 population	17.90	2.00	15.90
Total:		103.84	11.96	91.88

Source: Estimation by the Consultants

Health

There already exists an upazila health complex in Singra Upazila. As SingraPaurashava is under the Singra Upazila there should be no provision of another complex. In future, as the population and density increases, demand for local health facilities other than Health Complex will increase which currently use only 0.72 acre. So the Paurashava requires additional 13.66 acres of land for the Health center/Maternity clinics in future. Table 10-7 shows the detail.

Table 10-7: Estimation of Land Requirement for Health Facilities

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Upazila health complex/ hospital	10 -20 acres/Upazila HQ	10	0.72	9.28
Health center/ Maternity clinic	1.00 acre/ 5,000 population	14.32	0.66	13.66
Total:		24.32	1.38	22.94

Source: Estimation by the Consultants

Administration

Estimation of land according to standard indicates that there will be a land requirement of 8 acres to accommodate administrative facilities by the year 2031. If we deduct 2.25 acres of existing land under various administrative facilities, additional 5.75 acres of land for these facilities will be required. Table 10-8 shows the details.

Table 10-8: Estimation of Land Requirement for Administration

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Upazila complex	15.00 acres	0	0	0
Paurashava office	3 – 5 acres	3	1.45	1.55
Others	10 acres/Upazila HQ	5	.8	4.20
Total:		8	2.25	5.75

Source: Estimation by the Consultants

Community Facilities

For various community facilities, the total land requirement has been fixed at 19.11 acres. About 1.79 acres have been earmarked for mosque, 1.79 acres for eidgah, 3.58 for Paurashava provided graveyard. No additional land is required for mosque, church and graveyard. A total of 3.00 acres have been reserved for police station, 3.58 acres of land is required for fire station and 1.79 acres for post office. **Table 10-9** shows the details.

Table 10-9: Estimation of Land Requirement for Community Facilities

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Mosque/Church/Temple	.5 acre /20,000 population	1.79	3.6	NR
Eidgah	1.0 acre/20,000 population	1.79	0.99	0.80
Graveyard	1.0 acre/20,000 population	3.58	4.34	0.76
Community center	1.00 acre /20,000 population	3.58	0.32	3.26
Police Station	3 – 5 acres/Upazila HQ	3.00	0.27	2.73
Fire Station	3 – 5 acres/Upazila HQ	3.58	0.00	3.58
Post office	0.5 acre /20,000 population	1.79	0.00	1.79
Total:		9.52	19.11	9.59

Source: Estimation by the Consultants

Open Space/Recreational Facilities

Field survey shows no public park or play field in the town, except play grounds in the premises of educational institutions. The total land required for various open space recreation facilities recommended by consultants stands at 153.98 acres. The facilities include, play field/ground, parks of various categories and stadium/sport complex. **Table 10-10** shows the detail.

Table 10-10: Estimation of Land Requirement for Open Space/Recreational Facilities

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Play field/Urban Green Space	3.00 acres/20,000 population	10.74	0.00	10.74
Park	1.0 acre /1000 population	71.62	0.00	71.62
Neighborhood park	1.00 acre /1000 population	71.62	0.00	71.62
Stadium/sports complex	5 - 10 acres/Upazila HQ	0.00	0.00	0.00
Total:		153.98	0.00	153.98

Source: Estimation by the Consultants

Utilities

A number of utility establishments are required in a town to run services properly. The consultant, according to approved standard, has earmarked 3.58 acres for water supply installations, like, pump stations and other establishments related to water supply; and 3.58 acres have been fixed for gas related facilities. The total land requirement for utilities is 19.93 acres. **Table 10-11** shows the details.

Table 10-11: Estimation of Land Requirement for Utilities

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Water supply	1.00 acre /20,000 population	3.58	0.00	3.58
Gas	1.00 acre /20,000 population	3.58	0.00	3.58
Solid waste disposal site	5.00 acre /Paurashava	5.00	0.00	5.00
Waste transfer station	0.2/Ward	2.4	0.00	0.25
Electric sub-station	1.00 acre /20,000 population	3.58	0.18	3.40
Telephone exchange	1.00 acre/20,000 population	1.79	0.08	1.71
Total		19.93	0.26	17.52

Source: Estimation by the Consultants

Transport and Communication

Estimation of land according to standard indicates that there will be a land requirement of 9.87 acres to accommodate transport and communication facilities by the year 2031. If we deduct the already available 1.09 acres of existing land uses under various facilities, an additional 8.78 acres of land is required for this category of land use. **Table 10-12** shows the details.

Table 10-12: Estimation of Land Requirement for Transport and Communication

Use/Facility	Recommended Standard	Land in Acre		
		Estimation	Existing Land	Addl. Requirement
Bus terminal	1.00 acre /20,000 population	3.58	1.09	2.49
Truck terminal	0.50 acre /20,000 population	1.79	0.00	1.79
Launch/steamer terminal	1.00 acre /20,000 population	0.00	0.00	NR
Railway station	4.00 acre / per Station	0.00	0.00	NR
Baby taxi/tempo stand	0.25 acre /one baby taxi/tempo stand	1.50	0.00	1.50
Rickshaw/van stand	0.25 acre /Rickshaw/van stand	1.50	0.00	NR
Passenger shed	0.25 acre /Passenger shed	1.50	0.00	1.50
Total:		9.87	1.09	8.78

Source: Estimation by the Consultants

10.2 Land Use Proposals

Bangladesh is the most densely populated country in the world. The land area of the country remains static amid continuously increasing population. Such a situation calls for strict regulation to utilize its scarce land resources for non-agricultural purposes. Increase in urban population means more demand for houses, roads, schools, hospitals, factories, bazars, shops, business centers, offices and other service facilities. Providing all these facilities require land and that is at the cost of valuable agricultural land, as the country has hardly any fallow land to accommodate all these land uses. SingraPaurashava is surrounded by valuable fertile agricultural land. Any urban

expansion will cost net deduction of agricultural land that will consequently affect local food and cash crop production. A conservative and rational standard of space use and their proper application in planning, designing and development is, therefore, followed in the land use proposals.

10.2.1 Designation of Future Land Use

Designation of the future land uses in the Land use Plan is an important task of planning as it will ensure the compliance with the Structure Plan guidelines and provide the details of land use pattern along with transport and drainage network and utility lines. The existing uses and new proposals of land uses for future development have been identified and designated on the map for compliance by law. The land use categories with quantity of land required are based on the sectoral needs for now and in future. The implementation of the plan will require cooperation and collaboration of relevant authorities and agencies, and the Paurashava being the custodian of the Plan will safeguard the status of the Plan.

10.2.2 Land Use Zoning

Development control is an essential part of urban planning. For development control certain procedures have to be followed for approval of designs of various categories of structures, establishments and land uses. The first condition is to secure land use permit according to approved zoning plan followed by approval of the design of proposed building/structure.

10.2.2.1 Types of Land Use Zoning

In land use zoning, the entire area of a town is divided into suitable land use zones to create congenial and livable environment and thereby enhance land value. In Bangladesh such land use zoning is incorporated as a part of the master plan / land use plan/urban area plan. Before submitting building plans for approval an applicant must secure land use permit from the Paurashava. For land use permit, an applicant's prospective use of structure must be compatible with the approved land use zone of the site. Land use zoning limits activities that can or cannot function on a land parcel by establishing a range of development options. Land use zoning is a legal instrument by application of which a Paurashava can control.

- i) The height of building/structure,
- ii) The area of a land parcel that must be left vacant, and
- iii) The use of a buildings and land.

Zoning can be of three types, area zoning, density zoning and height zoning.

Area Zoning

By area zoning an area is divided into zones suitable for that particular area. The main objectives of such zoning are done mainly from environmental point of view that accrues other social benefits.

Density Zoning

The aim of the density zoning is to limit the size of population in any particular area by means of density control. The size of population has bearing on the capacity of designed utility facilities and

amenities and traffic volume and crowding, especially in the residential areas. Such zoning is done to ensure a healthy and enjoyable community living.

Height Zoning

Height zoning restrict the height of buildings structures in any particular area. This zoning is aimed to promote the proper and sound development of areas. Height zoning is of particular importance in airport areas to ensue take off and landing of aircrafts. Considering the existing level of development and development prospects, the consultant recommends to follow the area zoning only. Zoning is only a part of development control regulations. A prospective developer in a Paurashava has to comply with other rules and regulations, like, Building Construction Rules, 1996 under Building Construction Act 1952, Bangladesh National Building Code 1993 and other conditions of construction method, building safety and associated issues.

10.2.2.2 Classification of Land Use Zoning

After a detailed consultation between the Paurashava personnel and the consultants of the project, the land use classification for the Paurashava Master Plan is finalized **Table 10-13. Map 10-2 and Appendix-2** shows the Land Use Plan of SingraPaurashava.

Table 10-13: Proposed Land Use Categories for Urban Area Plan of Singra Paurashava

Sl. #	Land Use Category	Remarks	Area (acre)	%
1.	Urban Residential Zone	Urban Residential area is a land use in which housing predominates. These include single family housing, multi-family residential, or mobile homes. Zoning for residential use may permit some services or work opportunities or may totally exclude business and industry. It may permit high density land use.	462.89	17.12
2.	Rural Settlement	Rural settlement includes the low dense residential area which is scattered and rural in nature. It may permit only low density uses. Aiming to control the growth in this zone, less service and facilities will be provided.	295.04	10.88
3.	Commercial Zone	The land used for commercial activities is considered as commercial land use. These activities include the buying and selling of goods and services in retail businesses, wholesale buying and selling, financial establishments, and wide variety of services that are broadly classified as "business". Even though these commercial activities use only a small amount of land, they are extremely important to a community's economy. Commercial land includes established markets and areas earmarked for markets.	33.18	1.22
4.	Mixed Use Zone	Mixed land use refers to the area without a dominant land use (Residential, commercial, industrial etc.).	8.95	0.33
5.	General Industrial Zone	Green and Orange A categories as per The Environment Conservation Rules, 1997	16.19	0.60
6.	Heavy Industrial Zone	Other toxic and pollutions Industries (Orange B and Red categories as per The Environment Conservation Rules, 1997)	29.94	1.11
7.	Government Office	All Government Offices except large scale service based offices as Civil Surgeon Office, DC Office, Police Box, Police Fari, Police Station, LGED Office, Paurashava Office, Settlement Office, Union Parishad Office, Upazila Headquarter, BADC Office, Fisheries Office, Ansar/VDP Office, Agriculture Office, Zila Parishad Office, Post Office, Telephone Exchange Office and Other Government Offices.	5.79	0.21

Sl. #	Land Use Category	Remarks	Area (acre)	%
8.	Education & Research Zone	All kinds of educational institutes like Primary/ secondary/other Schools/ Colleges etc are mentioned to calculate the land use for education and research purpose.	68.44	2.50
9.	Agricultural Zone	Agricultural land denotes the land suitable for agricultural production, both crops and livestock. It is one of the main resources in agriculture. It includes productive land (single, double and triple cropped), seed bed, fisheries, poultry farm, dairy farm, nursery, horticulture etc.	1064.47	39.33
10.	Water body	Equal or More than 0.25 acre and justification by the consultant and wet land will merge with water body	345.23	12.73
11.	Open Space	Playground, Botanical Garden, Stadium, Zoo etc. (Facilities without or with minimum building structure)	94.23	3.44
12.	Recreational Facilities	Facilities other than those mentioned to Open Space and indoor based facilities with designated building structure i.e. Cinema Hall, Theater Hall etc.	0.23	0.01
13.	Circulation Network	Road and Rail communication	205.54	7.60
14.	Transportation Facilities	Under transport and communication land use both transport and communication services are considered. This category includes airport, bus terminal/ stand, ferry ghat, filling station, garage, launch terminal, post office, passenger shed, telephone exchange, ticket counter, transport office etc.	6.23	0.23
15.	Utility Services	Utility services include Overhead Tank ,Power Office/Control Room, Public Toilet, Sewerage Office, Waste Disposal ,Fire Service, Water Pump House, Water Reservoir, Water Treatment Plant etc.	10.54	0.39
16.	Health Services	This land will be used to provide health facility.	14.34	0.50
17.	Community Facilities	All community facilities including funeral places and other religious uses	20.59	0.76
18.	Historical and Heritage Site	The entire mentionable historical and heritage site.	0.00	0.00
19.	Restricted Area	A Restricted Area is an area where no one but certain people can enter. Here the areas which are not accessible for the general public except some high ranked personnel are considered as restricted area.	0.00	0.00
20.	Overlay Zone	If the consultant justify any area that should not be defined as other given definitions but the facility(s) may not be avoidable, they may use this category	Not applicable	
21.	Urban Deferred	Optional depending on the Paurashava and the Consultant's judgment	18.91	0.96
22.	Forest	Designated Forest Area	Not applicable	
23.	Beach	Sea Beach	Not applicable	
24.	Miscellaneous	Any other categories which are not related to above 23 categories.	2.14	0.08
Total:			2703.74	100

According to the proposed land use zoning categories shown in table 10.13, the amount of land for each land use category was calculated.

In the sections below, the general definition of the use and description of associated permitted and conditionally permitted uses under each land use zone have been provided. The uses that are not listed here in any of the categories shall be treated as Miscellaneous Use for the corresponding land use category and shall not be permitted unless unanimously decided otherwise by the appropriate authority. In such situations, the use shall get permission in the category of New Use.

The following is a short description of recommended land use zones. Land use plan of SingraPaurashava is given in **Map 10-2** and **Appendix-2**.

Urban Residential Area

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present Master Plan. In total, this zone covers 462.89 acres of land (Net density 146p/acre) delineated up to the year 2031, considering standard provided by LGED. Table A.1, Annexure- A shows the permitted use of urban residential area and conditional permission will be given to a number of other land uses as specified in Table A.2, Annexure- A.

Table 10-14: New Development Proposal for Low Income People & Old People Rehabilitation

ID	Use	Location	Ward No.	Area (acre)	Mouza Schedule	
					Mouza	Plot No.(RS)
LPP	Low Income Housing Project	Beside of Natore-Bograroad	03	3.00	Dakhin Domdoma_276_00	Partial 171-173,176,178,179
OHR	Old Home Rehabilitation	Beside of Natore-Bogra	03	3.00	Bosta_348_00	Partial 36-40

Rural Settlement

Most of the Paurashava has some rural characteristics. So in Urban Area Land use category for UTIDP Master Plan the residential settlements within the agricultural belt are categorized as rural settlements. These settlements have usually temporary type of structures. SingraPaurashava is mostly rural in character. About 65.40% existing land use is in agriculture practice and most of the settlement situated surrounding or within this agricultural land. So in a manner to develop control of SingraPaurashava some portion of land declare as rural settlement. This settlement occupies 295.04 acres of land, which comprises More than 10% of the total land. The areas of rural settlement have some restrictions for non-agricultural development. Table A7, Annexure-A shows the permitted land use of rural settlement and Table A8, Annexure-A conditionally permitted use in this zone.

General Industry

General Industrial Zone (**Table 10-14**) is intended to provide locations, where manufacturing and processing industries can be set up and function without creating hazards to surrounding land uses. There is scope to establish Green and Orange-A category industry as per mentioned in The Environmental Conservation Rule, 1997. As a small urban center, it is unlikely that any major industrial development will take place here in the near future. This zone has an area of 46.13 acres (1.71%) designated up to 2031. Though as per the planning standard provided by PMO office SingraPaurashava require 143.23 industrial lands (**Table 10-5**).

Table 10-15: New Development Proposal for Industrial Area

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Industrial Area	46.31	6	Niagain_333_01	1534(p), 1535-1538, 1541-1543, 1548-1555, 1840, 1844-1848, 1853, 1615-1627, 1628(p), 1629(p), 1746	Land acquisition and developed basic infrastructure	Establish Industry	Ensure full functioning of industrial area

Map 10-2: Land use Proposal for SingraPaurashava

Again, since there is no industrial agglomeration within the town, the industrial zone will be meant for new industries. In this zone, a complex line of industrial and supporting non-industrial land uses will be permitted as per Table A.3, Annexure- A and conditional permission will be given to a number of other land uses as specified in Table A.4 and Annexure- A. **Table 10-13** shows new land use proposals for this type of activity in SingraPaurashava. This land will be provided in the general industrial area.

Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails and wholesale can be set up and function without creating hazards to surrounding land uses. This zone has an area of 33.18acres (1.22%) designated up to 2031 and zone will allow commercial uses as listed in Table A.5, Annexure- A, and conditional uses as listed in Table A.6, Annexure- A.

Table 10-16: New Development Proposal for Commercial Facilities

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Neighbourhood Market	1.65	1	Kata Pukuria_38_00	Partial 214-216	Land acquisition and establishment	Maintaining and improve facilities	
Neighborhood Market	0.85	2	Uttar Domdoma_336_00	Partial 417-422	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood Market	0.89	3	Dakhin Domdoma_276_00	Partial-15-18,23-24	Land acquisition and establishment	Maintaining and improve facilities	
Neighborhood Market	0.70	6	Patkol_372_00	Partial- 57-63	Land acquisition and establishment	Maintaining and improve facilities	
Neighborhood Market	2.53	6	Baluvora_373_00	Partial-92,93	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood market	0.45	8	Singra_342_00	Partial-199,203,204,208	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood Market	1.00	9	Chak Singra_344_00	Partial-158,161,231,233	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood Market	0.99	9	Chak Singra_344_00	Partial 158,161,231-233	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood Market	1.27	9	Sohag Bari_371_00	Partial-88-97	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood Market	0.12	10	Par Sawail_369_01	Partial- 151,152	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood Market	0.54	10	Katua Bari_370_00	Partial-138-143	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood Market	1.52	11	Boro Sawail_387_01	Partial-231,232,234-238	Land acquisition and establishment	Maintaining and improve facilities	
Neighbourhood Market	1.44	11	Boro Sawail_387_01	Partial-308-310,316-319,, 187-190	Land acquisition and establishment	Maintaining and improve facilities	

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Neighbourhood Market	1.65	1	Kata Pukuria_338_00	Partial 214-216	Land acquisition and establishment	Maintaining and improve facilities	
Total	13.95						

Mixed Use Area/Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. In a small town like Singra, as the trend shows, an exclusive commercial land use is unlikely to function. This land use will allow flexibility of development, instead of restricting development. Total area for mixed uses has been put to 8.95 acres, including both, existing and proposed land uses. This zone will allow residential structures together with commercial uses as listed in Table A.11, Annexure-A, and conditional uses as listed in Table A.12, Annexure-A. Table 10.13 presents the proposed land uses and their phase-wise development proposals.

Governmental Services

Administrative zone covers all kinds of government and non-government offices in the town. The total area under this use has been estimated as it has now.

Education and Research Area

Institutional zone refers to mainly education, health and other social service facilities as listed in Table A.13, **Annexure-A**, and conditional uses as listed in Table A.14, **Annexure-A**. The total area under this use has been determined as 68.44 acres although the standard suggests about 103.84 acres of land. Detail new land proposal for education and research is shown in **Table 10-16**. Some standard of LGED is not considered here due to insufficient land in built up area. Total seven primary schools, one secondary school, one vocational training institute and one college will be established in this land.

Table 10-17: New Land Proposal for Education and Research

Type of Facilities	Ward No.	Mouza Name	Plot No.	Area in Acre	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Primary School	6	Poran Hati_334_00	2(P)	0.20	Land acquisition and establish	Continue the development	
	3	Dakhin Domdoma_276_00	114,115,116(p)	4.57		Land acquisition and establishing	Continue the development
	08	Singra_342_00	Partial-400-403,437-442,188-190	5.61		Land acquisition and	Continue the development

Type of Facilities	Ward No.	Mouza Name	Plot No.	Area in Acre	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
						establishment	
	11	Boro Sawail_387_01	238,242,245,246,250(p),247(p),251	2.45		Land acquisition and establishment	Continue the development
High School	2	Uttar Domdoma_336_00	149(p),304(P),307(P)	1.2	Land acquisition and establish	Continue the development	
	3	Falia_259_00	130(p),175(p),9999(p)	1.00	Land acquisition and establish	Continue the development	
	10	Par Sawail_369_01	Partial 152,153,154,156,157,158,159,160,161,162,163	2.64	Land acquisition and establish	Continue the development	
Nursery	7	Niagain_333_02	1325(p),3007(p),1326(p),1327(p),	0.49		Land acquisition and establishment	Continue the development
	8	Singra_342_00	348,379(p),378(p)	0.34	Land acquisition and establish	Continue the development	
	10	Par Sawail_369_01	68(p),69(p),101(p)	0.50		Land acquisition and establishment	Continue the development
	9	Chak Singra_344_00	Partial-238-247	2.09		Land acquisition and establishment	Continue the development
	4	Sola Kuri_345_00	118-122,126(p),127(p)	0.27	Land acquisition and establish	Continue the development	
	1	Kata Pukuria_338_00	285(p)	0.50		Land acquisition and establishment	Continue the development
Polytechnique College	1	Kata Pukuria_338_00	133,137,243-245,303(p),304	5.66		Land acquisition and establishment	Continue the development
College	06	Baluvora_373_00	Partial 115,184,185,186,187,188,190,191,208,209,210,404	6.32	Land acquisition and establish	Continue the development	
Vocational Training Institute	06	Baluvora_373_00	Partial 115,178,179,180,184	4.47	Land acquisition and establish	Continue the development	
Madrasa	9	Sola	Partial-305-307	1.92	Land	Continue the	

Type of Facilities	Ward No.	Mouza Name	Plot No.	Area in Acre	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
		Kuri_345_00			acquisition and establish		development
Total				40.23			

Agriculture Area/ Agricultural Zone

The Paurashava has a vast area of agricultural land that demands formation of a separate zone of, agriculture. Agriculture zone is primarily meant for agriculture; land uses related to it and land uses that support it. Detail of land use is presented in Table A.17, Annexure- A and conditional uses as listed in Table A.18, Annexure- A. The total area under this use has been estimated as 1063.60acres that include existing and proposed land uses.

Water Body

The plan suggests preserving most of these water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or More than 0.25 acres will be preserved as the water retention ponds. There will be permitted uses in this zone as stated in Table A.23, Annexure- A and some other uses may conditionally be permitted as stated in Table-A.24, Annexure- A. Annexure-D shows the planning schedule of Water Body Area in SingraPaurashava.

Open Space/Recreational Facilities

This zone has been provided to meet the active and passive recreational needs of the people and at the same time, conserve the natural resources. The total area estimated for this zone stands at 94.23 acres. But Some standard of LGED is not considered here due to insufficient land in built up area.The details of permitted and conditional permits have been presented in Table A.19 Annexure- A, and conditional uses as listed in Table-A.20, Annexure- A. **Table 10-17** shows the detail of new land proposal for open space proposal in SingraPaurashava. There are eight playgrounds, one stadium, one central park and ten local parks will be established in this proposed open space.

Table 10-18: New Land Proposal for Open Space

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Playground	3.69	3	Dakhin Domdoma_276_00	50(p),51(p),107-110(p)		Land acquisition and establishment	Maintaining the playground and improve facilities
	1.87	7	Niagain_333_02	1391(p),1392-1393(p),1397(p)		Land acquisition and establishment	Maintaining the playground and improve facilities

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
	1.65	2	Uttar Domdoma_336_00	407,408,409(p),410(p)		Land acquisition and establishment	Maintaining the playground and improve facilities
	1.42	10	Par Sawail_369_01	139-142(p),132(p)		Land acquisition and establishment	Maintaining the playground and improve facilities
	2.58	12	Patkol_372_00	336-338(p)		Land acquisition and establishment	Maintaining the playground and improve facilities.
	7.16	06	Baluvora_373_00	Partial-195-203,236-245	Land acquisition and establishment	Continue the development	
	4.88	06	Boro Sawail_387_01	Partial 48,49,50,51,56,57,71,72,73,74,75,76,77,81,82,83,84,85,86,87,88,89,90,91,92,476	Land acquisition and establishment	Continue the development	
	4.76	09	Chak Singra_344_00	Partial 180,181,182,183,204,208,209,210,211,212,213,214,216,217,218,219,220,221,222,223,224,225,226,227,228,244,246,251	Land acquisition and establishment	Continue the development	
Stadium	6.45	9	Sola Kuri_345_00	40-47(p),50-52(p)	Land acquisition and establishment	Continue the development	
Central Park	2.72	8	Singra_342_00	151(p),165-167(p),	Land acquisition and establishment	Continue the development	
Neighborhood Park	2.75	6	Baluvora_373_00	20-22(p)		Land acquisition and establishment	Maintaining and improve facilities.
	3.3	9	Sola Kuri_345_00	Partial 242,261,264,265,268,274		Land acquisition and establishment	Maintaining and improve facilities

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
							ies.
	1.61	3	Uttar Domdoma_336_00	Partial 1003,1005,1013		Land acquisition and establishment	Main taining and improve facilities.
	11.20	5	Poran Hati_334_00	Partial 1-8,21-36	Land acquisition and establishment	Continue the development	
	7.27	1	Porbo Masinda_335_00	Partial 1-6,14-17	Land acquisition and establishment	Continue the development	
	1.65	7	Niagain_333_02	1399,1400,1334(P),1336(p)	Land acquisition and establishment	Continue the development	
	5.43	02	Uttar Domdoma_336_00	Partial 283,284,285,286,358,359,362,365,366,367,368,369,370,371,372,373,374,375,376,377,378,379,380,381,382,383,1042	Land acquisition and establishment	Continue the development	
	8.25	06	Baluvora_373_00	Partial 185,187,188,190,191,192,193,194,204,205,206,207,208,209,210,404	Land acquisition and establishment	Continue the development	
	2.10	10	Par Sawail_369_01	Partial 67,68,98,101,103,104,105,106,107,108,109,110,118,149,150,154,155,156	Land acquisition and establishment	Continue the development	
	6.46	11	Boro Sawail_387_01 & Katua Bari_370_00	Partial Boro Sawail 253,254,255,256,257,258,259,260,261,262,263,264,265,266,267,268,269,270,273,274,275 Katua Bari 258,260,261,277,279,280,281,282,283,284,285,286,287,288,289,293	Land acquisition and establishment	Continue the development	
Total	87.2						

Circulation Network

The road network is mainly considered as circulation network. National highway, pucca/ semi-pucca/ katcha road, footpath, flyover, over- bridge, underpass, bridge, culvert, railway, railway bridge all are include in circulation network. Total 205.54 acre land which covers 7.47% of total planning area of SingraPaurashava. At present 51.72 acres of land uses for circulation network in this Paurashava.

Transportation Facilities

Transportation facilities incorporate transport and communication services. For an example airport, bus terminal/ stand, ferry ghat, filling station, and garage, launch terminal, post office, passenger shed, telephone exchange, ticket counter, transport office etc. Total 6.23 acres land (0.23% of total area) will be used for this purpose. But some standard of LGED is not considered here due to insufficient land in built up area. **Table 10-18** shows the new transportation facilities for SingraPaurashava.

Table 10-19: New Transportation Facilities

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Truck Terminal	0.69	12	Niagain_333_01	Partial 1562,1563,1564	Land acquisition and establishment	Maintaining and improve facilities	
Tempo Stand	0.25	7	Niagain_333_02	Partial 1502,1504,1505,1395	Land acquisition and establishment	Maintaining and improve facilities	
	0.48	8	,Singra_342_00	Partial-190-191,197-199	Land acquisition and establishment	Maintaining and improve facilities	
	0.18	4	,Singra_342_00	Partial-140-151	Land acquisition and establishment	Maintaining and improve facilities	
	0.25	3	,Falia_259_00	Partial-131,133	Land acquisition and establishment	Maintaining and improve facilities	
	0.25	4	,Balua Basua_341_00	Partial-24	Land acquisition and establishment	Maintaining and improve facilities	
	0.25	9	Sola Kuri_345_00	Partial-378-380,384		Land acquisition and establishment	Maintaining and improve facilities
	0.75	02	Uttar Domdoma_336_00	Partial 336,337,338,339,340		Land acquisition and establishment	Maintaining and improve facilities
	0.25	03	Falia_259_00	Partial 125,126,130		Land acquisition and establishment	Maintaining and improve facilities
	0.66	10	Par Sawail_369_01	Partial 110,111,114,115,127,145,146,147,148,149		Land acquisition and establishment	Maintaining and improve facilities

					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyo nd 10 th year
	0.38	11	Katua Bari_370_00	Partial 243,253,254,255, 256,257,299		Land acquisitio n and establish ment	Maintaini ng and improve facilities
Rickshaw / Van Stand	0.25	9	Sola Kuri_345_00	Partial- 224,225,231,232		Land acquisitio n and establish ment	Maintaini ng and improve facilities
	0.33	4	Singra_342_00	Partial-135,151	Land acquisition and establishment	Maintaining and improve facilities	
	0.25	1	Chak Gopal_337_00	Partial-61,67,70	Land acquisition and establishment	Maintaining and improve facilities	
Ghat	0.02	1	Porbo Masinda_335_0 0	Partial-33	Land acquisition and establishment	Maintaining and improve facilities	
	0.02	1	Porbo Masinda_335_0 0	Partial-23,25	Land acquisition and establishment	Maintaining and improve facilities	
Total	5.26						

Utility Services

It incorporated all utilities and service facilities except the health service. For an example water treatment plant, water reservoir, water pump house, public toilet, fire service, waste disposal, sewerage office, power office or control room and over head tank. In survey stage this type land use was define as service activity. Total 10.54 acres land which covers 0.39% total area of SingraPaurashava. Total 02 waste transfer stations, one waste dumping station will be newly established to fulfill the desired need of SingraPaurashava.

Table 10-20: New Land Use Proposal for Utility Services

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyon d 10 th year
Water Pump House	1.00	6	Patkol_372_00	Partial- 263,266,281		Land acquisition and establish ment	Mainta ining and improv e faciliti es
	1.00	6	Baluvora_373_00	Partial-115	Land acquisition and establishment	Maintaining and improve facilities	
Waste Transfer Station	0.16	8	Singra_342_00	Partial-385	Land acquisition and	Maintaining and improve facilities	

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Water Pump House	1.00	6	Patkol_372_00	Partial-263,266,281		Land acquisition and establishment	Maintaining and improve facilities
	1.00	6	Baluvora_373_00	Partial-115	Land acquisition and establishment	Maintaining and improve facilities	
	0.13	5	Sundarpur_113_03	Partial-1	Land acquisition and establishment	Maintaining and improve facilities	
Waste Dumping Area	7.49	12	Niagain_333_01	1715,1718,1720,1721,1722,1724,1726,1727,8,9,1730,1734,1741,1748	Land acquisition and establishment	Maintaining and improve facilities	
Total	9.78						

Health Services

This land will be used to provide health facility. Total 14.34acre land 0.50% of total land will be used for this purpose. Along with this community based health facilities ill be provided at ward center. Ward center is given in mixed use category in land use plan proposal.

Table 10-21: New Land Use Proposal for Health Services

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Clinic	0.11	4	Singra_342_00	Partial-140,151		Land acquisition and establishment	Maintaining and improve facilities
	0.62	1	Kata Pukuria_338_00	Partial-73,74,86		Land acquisition and establishment	Maintaining and improve facilities
	0.62	04	Kata Pukuria_338_00	P-267	Land acquisition and establishment	Maintaining and improve facilities	
	1.74	06	Poran Hati_334_00	Partial41,43,58	Land acquisition and establishment	Maintaining and improve facilities	
	1.18	07	Niagain_333_02	Partial1398,1411,1414,1446,1447,1448,1451,1452,1453,145	Land acquisition and establishment	Maintaining and improve facilities	

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
				4	t		
	2.04	08	Singra_342_00	Partial168,172,173,174,175,176,177,393,394,395,396,397,398,401	Land acquisition and establishment	Maintaining and improve facilities	
	0.3	04	Boro Maguri_346_00 & Bosta_348_00	Partial Boro Maguri 8,9,10,11 Bosta 51,52		Land acquisition and establishment	Maintaining and improve facilities
	1.00	10	Katua Bari_370_00	Partial-132,136,139,137,142,143		Land acquisition and establishment	Maintaining and improve facilities
	1.00	10	Patkol_372_00	Partial-261,285,286,287,289		Land acquisition and establishment	Maintaining and improve facilities
	0.25	3	Uttar Domdoma_336_00	Partial-775	Land acquisition and establishment	Maintaining and improve facilities	
	0.78	11	Kata Pukuria_338_00	Partial-306,307,309,246	Land acquisition and establishment	Maintaining and improve facilities	
	1.00	6	Uttar Domdoma_336_00	Partial-430-433	Land acquisition and establishment	Maintaining and improve facilities	
	1.00	12	Patkol_372_00	Partial-394,399		Land acquisition and establishment	Maintaining and improve facilities
Total	11.64						

Community Facilities

Community services include community centre, club house, religious centres, other community services etc. In additionally all funeral places and other religious uses incorporated in this category. A Ward Center for each ward is also proposed in this plan where ward councillors office will be situated. A digital center will also be present in every ward center. Total 20.59 acres land which covers 0.82% of total planning area will be used for this purpose.

Table 10-22: New Land Use Proposal for Community Facility

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
Community Centre	1.00	9	Sola Kuri_345_00	Partial-366,374,380		Land acquisition and establishment	Maintaining and improve facilities
	0.55	4	Kata Pukuria_338_00	Partial-267	Land acquisition and establishment	Maintaining and improve facilities	
Fire Service	1.00	3	Dakhin Domdoma_276_00	Partial-161-163,150	Land acquisition and establishment	Maintaining and improve facilities	
Post Office	0.11	5	Hat Singra_339_00	Partial-110,111	Land acquisition and establishment	Maintaining and improve facilities	
Total	2.66						

Restricted Area

A Restricted Area is an area where no one but certain people can enter. Here the areas which are not accessible for the general public except some high ranked personnel are considered as restricted area. Only 0.18 acres (0.01%) of land which exist in present have been reserved in this plan for SingraPaurashava.

Urban Deferred

The Urban Deferred refers to lands lying outside of the urban growth boundary and identified as Urban Reserve. The total area under this use has been proposed as 18.91 (0.96%) acres that include existing and proposed land uses. The following are permitted Uses within the Urban Reserve (UR) Zone:

- Agriculture, Livestock based
- Agriculture, Vegetation based (mushroom farms shall not be permitted)
- Existing facilities up to the date of gazette notification of the Master Plan. Condition is that, no further extension will be permitted.

10.2.3 Land Use Permission

One of the major purposes of land use zoning is to restrict an area for a particular use meant for the zone. This is intended to maintain a disciplined land use distribution and development. But there are many uses other than the use meant for the zone that are considered for permit in the zone. Sometimes such applications are accommodated to support or assist the area, with conditions imposed in giving land use permit, sometimes strict restrictions are maintained by refusal of applications. Detailed lists of permissible and conditionally permissible uses have been provided in Annexure-A according to land use categories. The list has been developed with ideas borrowed from the recommendations made by the consultants under the recently completed DAP Project of RAJUK. It is required that permit procedures mentioned in Annexure-A are officially

adopted through incorporation in the Building Construction Rules under Section 18 of the Building Construction Act 1952.

10.3 Plan Implementation Strategies

This section deals with the issues of implementation of land use plan. Discussion is made on development regulation and recommendation on implementation, monitoring and evaluation of urban land use plan.

10.3.1 Land Development Regulations to implement the Land Use Plan

Urban planning regulations are necessary for the smooth functioning of land use plan. The land use regulations impact on planned development and result in social benefits and costs depending on their nature and the specific contexts in which they are applied. Careful reforms of these regulations can result in a lower cost for urban development and for housing. An additional benefit could be in terms of a More functional spatial organization of the town. Regulations and processes that facilitate land availability and uses for planned development at affordable costs need to be continued. Regulatory and process reforms can lead to:

- more compact towns, containment of urban sprawl, more efficient urban forms,
- less costly urban infrastructure,
- more market-friendly development of urban land;
- more intensely used central areas, better efficiency of public transportation systems and decrease in trip length and transportation costs;
- less violations in zoning, sub-division and building regulations, and reduction in non-conforming and non-compatible uses and slums;
- reduction in difference between what is allowed under regulations and what is financially feasible due to land use reforms leading to reduced opportunities for corruption;
- generally lower land prices in city/town but higher prices in some prime commercial and business districts driven by market forces;
- average urban population densities likely to stay constant as more efficient land use consumption.

The following measures of Land Development Regulations should strictly be followed for the proper implementation of the Land use Plan.

a. Restriction on Use of Land Contrary to the Master Plan

No person shall use any land for any purpose other than that laid down in the land use zoning of the Master Plan approved by the Government. All future developments and constructions, both public and private within the area of Structure Plan shall be in conformity with the Master Plan approved by the Government. No compensation shall be payable to any person owing to demolition of any construction developed in violation of the Master Plan provisions.

b. Building Permission and Construction Approval

Development control mechanism will be one of the major plan implementation instruments to be carried out through the Building Construction Rules under Section 17 of the EBBC Act 1952 and the land use provisions of the Master Plan.

c. Building Permission in Proposed Development Areas

The Master Plan proposes a number of development projects. Many of the lands under these development projects are under private ownership. No development in these lands by their owners will be allowed. They will remain in the present form till they are taken over by the respective authority for development or the development project is abandoned.

d. Parking in Commercial and Mixed Use Areas

For parking, BC Rules, 1996 has specific provisions for housing and commercial areas. But no provision has been suggested for mixed use areas. According to the rules for commercial area, 23 sq.m areas, has to be reserved for every 200 sq.m of commercial space. The consultant suggests that for mixed areas, BC Rules, 1996 meant for commercial area should also be applied to the mixed areas under the current plan.

f. Rules for Realization of Betterment Fee

The Ordinance enables Paurashava to charge betterment fees on land owners or any other person having interest in it for an increase in land value due to execution of any development scheme by the Authority. The Authority should develop appropriate procedures in this regard and get them approved to start charging betterment fee. Due to failure of execution of the powers of charging betterment fee, all benefits of land value enhancement due to Paurashava development projects goes to the land owner at the cost of the community. So it is not irrational for the road developer to demand a share of the benefit accruing to the land owner following road development.

g. Planning Rules for Real Estate Companies

With the increase in population, there will be further rise of land based real estate activities. But there is no provision in the Paurashava Ordinance to control the activities of real estate companies. It is needed that infrastructure and services provided in the housing plans of the real estate projects be standardized to secure interest of the buyers. Strict vigilance is needed against any fraudulent practices that might affect public interest.

However, any control imposed on the housing companies must be imbued with a positive approach, so that it does not affect the housing promotion activities of the private sector. The intention would be to allow them function under certain control that would secure public interest and at the same time will not discourage private investment in housing. The infrastructure, services and facilities provided in a housing project must be standardized. Road width and the land allocated for community facilities must be adequate to meet requirements of the future inhabitants. The infrastructure provided therein must follow minimum standard as some day these housing estates would become parts of the future town and the infrastructure provided therein would be used by a wide range of population of the town.

To control apartment development, the national rules under Building Construction Act 1952 will be applied. The rules for land based real estate projects exist for Dhaka only. In anticipation of expansion of real estate projects, there is an urgent need to prepare a set of rules for small towns. The real estate companies seeking approval for their housing project layout plan must fulfill certain conditions as set in the rules. The set of rules is clearly described in the Private Residential Land Development Rule-2004.

h. Minimum Road Width

Building Construction Rules, 1996, should be amended in the following way by incorporating the minimum road width standard.

To ease future traffic movement, it is necessary to keep provision for wider roads in the present plan. It is an uphill task to widen roads after development has taken place along the road. So it is wiser to reserve wider right of way for new roads now. Building Construction Rules, 1996 has determined the minimum road width as 12 ft. or 3.65 meter for roads in general and approximately 10 ft. for private roads. The consultants feel that this standard is not enough in view of future increase in population density and traffic. For safeguarding and easing future traffic movement the consultants have set the minimum width for any road for common use as 20 ft. or 6 meter and 16 ft. or 4.77 meter for private roads. However, in the built up areas, where development has already blocked the scope for developing such wide roads, the consultant recommends the minimum road width provisions of BC Rules, 1996. The new road width provision will be applicable in new areas. In the areas, where there already exist roads of less than 20 ft., the land owners on either side of the road will equally share the space needed to increase the road width to 20 ft. The land owners must leave the space vacant for taking it over by the Paurashava for widening of the road at some later date. No proposal for construction should be permitted on the vacant space reserved for road widening though the land will remain under its current ownership till it is taken over by the authority. In the light of the above recommendations, necessary amendment will have to be brought in the BC Rules, 1996 applicable to the secondary and small towns only.

i. Low Land, Pond and Drainage Path

No low land that retains water for certain period of the year can be filled up and no obstruction to natural or man made drainage system shall be allowed. Prior permission of SingraPaurashava will be required for filling up of any low lands. The Paurashava shall accord such permission based on prevailing laws. All ponds should not be allowed to be filled up as they are a good source of urban water supply as well as serve as open space. As per the Wetland Conservation Act 2000, the use of these water bodies can not be changed without prior permission of the authority.

j. Security Areas - Cantonment, BDR, Police Stations

BDR, Police, etc. areas have to be safe guarded from any possible incompatible development.

k. Radio, Television, Water Treatment and Pump Station and Power Station Sites

The key point installations including radio, television, water treatment and pump station and power station sites will have to be safeguarded from any possible undesirable development around these areas that can endanger their security. No building except vegetation should be allowed within 183 meters around the transmission towers.

10.3.2 Implementation, Monitoring and Evaluation of the Land Use Plan

Monitoring and evaluation is a very important part of plan implementation. Monitoring helps check if the plan is being implemented properly. It also measures the level of implementation of the plan. If the plan implementation is not on track, corrective measures can be taken to put the execution on track. After expiry of any plan, evaluation is made about the errors and omissions. Such

evaluation helps take corrective measures in the next plan. Such monitoring and evaluation must be carried out from within the Paurashava. But SingraPaurashava is not equipped with qualified manpower to make such evaluation. Monitoring and evaluation of a plan is essentially, the responsibility of qualified and experienced planners. As there is no planner in the Paurashava, its monitoring of plan implementation will be seriously affected. However, plan evaluation can be accomplished by means of out sourcing.

Updating of Plans

The plan package needs to be updated regularly to make it respond to the spatial changes over time. But such updating would require relevant technical professional and fund that are highly lacking in SingraPaurashava. There is no planner or planning department in the Paurashava. Updating would require service of senior level planners that Paurashava would not be able to provide. This service will have to be procured by out sourcing and the Paurashava is not even capable to accomplish this financially either. This will create problem when the plans or its components gets obsolete or need to be changed. Another problem would arise when the duration of plans ends. A new set of plans would have to be prepared replacing the old ones. This problem, however, can be overcome by undertaking another planning project by LGED. So, for regular updating and changes and plan implementation monitoring, the Paurashava should immediately move for setting up a planning department with planner(s) and other staff. The department will not only look after planning, but will also be responsible for development control, estate management and project preparation. Since the planners would be qualified and skilled in computer operation, they can also help achieving automation of the Paurashava functions.

Chapter 11: Traffic and Transportation Management Plan

11.1 Introduction

11.1.1 General

The transportation system directs the urban development pattern. The performance of transportation system largely influences the economy and social progress of an area. It provides mobility to people, goods and services to their destination. It has linkages with other sectors of development and for a sustainable development of any area, its traffic and transportation system should be adequately addressed. The current chapter of the report is about Transportation and Traffic Management Plan covering the scope of improvement of the existing network and system and plan proposals for new development. The proposals on improvement and new development are made for the project area up to 2031. The report also provides the purpose and the role of Transportation and Traffic Management Plan and its relation with Structure Plan and Land Use Plan.

11.1.2 Approach and Methodology

Transport study provides special attention to urban transportation planning as it greatly influences the location decisions and travel behavior of people, goods and services. Transportation is critical for the efficiency of towns contributing to their productivity and economic growth. A good network of roads & other transportation mode coupled with an efficient transport management system makes a substantial contribution to the "working efficiency" of cities and towns and enables them to become catalysts for social and economic development. On the other hand, the impact of a poorly designed urban transport system is manifested in terms of traffic congestion, delays, accidents, high energy consumption, high pollution of the environment and inequitable access to services. A well-planned transportation system results in orderly urban growth, greater use of urban public transport, lower vehicular pollution, and shorter auto trips.

Standard methodology was followed for traffic study in the project area. An introduction meeting was held at Paurashava and the Paurashava authority recommended Wednesday as local Hat day and others as regular day to conduct transport survey. With reference to their observations, survey time was set from 6:00 AM to 12:00 PM for those two days when traffic movements were frequent.

In order to identify the major causes of the congestion and the nature of the problem on transportation networks, a number of tasks were undertaken. Those tasks included traffic volume counting at the directions, speed and delay studies, Origin-Destination (O-D) survey at major traffic generating intersections and consultation with the stakeholders regarding the generated problems. The volume and movement pattern of people and goods within the planning area were collected through a series of volume and O-D surveys.

In addition to collect information on volume and pattern of traffic movement by traffic survey, the Consultant accommodates certain important questions regarding people's attitude and preferences.

The volume counts were conducted at four points in a node. For this, Manual counting method was followed to conduct the traffic volume survey and data was recorded in prescribed formats (**Table 11-1**).

Table 11-1: Sample Size and Location Number According to Surveys

Types of Survey	Sample Size/Locations
Volume count	1 nodes
O-D survey	100 Samples at three location
Journey Speed/Delay	Natore - Bogra Road and link connecting Ward 4 , 5 and 8

Details methodology of the work is shown in a flow chart (**Fig 11-1**) below.




Fig 11-1: Flow Chart of the Methodology

11.2 Existing Conditions of Transportation Facilities

11.2.1 Roadway Characteristics and Functional Classification

The planning area covers 10.94 sq. km. (2703.74 acres) and road length is 62.77 km. There are only one important road intersections named bus stand morr providing linkages with other secondary roads. SingraPaurashava does have direct transport communications with the Dhaka by bus. The areas towards the Natore-Bograroad are predominantly rural with little commercial

development along the road. The road network and hierarchy within the Paurashava boundary is poorly established.

The roads of the Paurashava belong to number of agencies. Local Government Engineering Department (LGED) responsible for construction and maintenance of Upazila and Union roads and SingraPaurashava responsible for construction and maintenance of roads within the Paurashavaarea. Existing transportation system is dominated by road network catering to the passenger service and freight transport (**Table 11-2**).

Table 11-2: Road status in Singra Paurashava

Type	Length		Area	
	KM	%	Acres	%
Pucca	39.71	63.26	13.15	25.30
Semi-pucca	4.19	6.68	36.35	69.92
Katcha	18.86	30.05	2.48	4.77
Total	62.77	100.00	51.98	100.00

Source: Transportation Survey of SingraPaurashava by AQUA, 2010.

The road network provides access to various places within the study area and connects various parts of the country following bus routes. Major trips of vehicles are generated from, within the Paurashava, Bazar Morr, Natore Road, Gurudaspur Road and Singra-Natore Road. Existing transportation system is dominated by road network catering to the passenger service and freight transport.

The major routes which connect SingraPaurashava are:

- Singra to Natore
- Singra to Bogra
- Singra to Kalom
- Singra to Gurudaspur Road

Apart from major roads, a large number of local roads having width varying from 10 ft. to 20ft width, provide access to individual houses and establishments and connect them to major roads.

11.2.2 Mode of Transport

Road is the only mode of transport in the Paurashava. The road is using for efficient movement and multi-dimensional purposes. As a result, transportation survey includes only the road transportation and the outcome of the survey is presented in the following paragraphs.

11.2.3 Intensity of Traffic Volume

To analyze the existing traffic situation, one location has been identified where the volume count survey were conducted for 18 hour basis. To find out total discharging traffic volumes both in peak hour and off peak hour traffic survey has been analyzed. The Traffic Volume survey was conducted on the following Singra Bazar Morr that is very important considering the locational importance as these locations do not only cover the inter-Upazila traffic but also provide accurate

view of the local traffic. The following figure shows details of the traffic node. Motorized traffic flow occurs in west-east direction according to diagram, especially only for bus service. The west (Natore) and east (Natore) links can be characterized by two funnel connected face to face in the node. A general overview of the traffic flow has been given in the following **Fig 10-2**. It is found that traffic movement in general occur mainly bus stand morr. A significant number of vehicle trips are also attracted towards north-south corner of the node.



Fig 11-2: Bus stand morrIntersection Flow Diagram

11.2.4 Level of Service: Degree of Traffic Congestion and Delay

Level of Service (also called Quality of Service or Service Quality) refers to the speed, convenience, comfort and security of transportation facilities and services as experienced by users. Level-Of-Service (LOS) ratings, typically from A (best) to F (worst), are widely used in transport Planning to evaluate problems and potential solutions. Because they are easy to understand, Level-Of-Service rating often influences transport planning decisions. Such ratings systems can be used identify problems, establish Performance Indicators and targets, evaluate potential solutions, compare locations, and track trends.

Traffic generation centers at SingraPaurashava are very limited. The central bazar is the main Traffic generation center. Besides, different governmental offices, shopping centers, educational institutions etc. are also generate traffic.

Traffic generation centers are mostly Bus Stoppage, Bazar, and Police box, Different Educational Institutions, Different Markets, Katcha Bazars, Land Office and Different Govt. Offices. Traffic generation centers are mostly Bus Stand, Different Educational Institutions, Different Markets,

Katcha Bazars, Land Office and Different Govt. Offices. The bazaar areas are the most congested areas in SingraPaurashava.

The transportation services are also very limited in SingraPaurashava. Wikipedia rates the Roadway Level-of-Service (LOS) by using speed survey data (**Table 11-3**).

Table 11-3: Roadway Level-Of-Service (LOS) Ratings of Wikipedia

LOS	Description	Speed (mph)
A	Traffic flows at or above the posted speed limit and all motorists have complete mobility between lanes.	Over 60
B	Slightly congested, with some impingement of maneuverability. Two motorists might be forced to drive side by side, limiting lane changes.	57-60
C	Ability to pass or change lanes is not assured. Most experienced drivers are comfortable, and posted speed is maintained, but roads are close to capacity. This is often the target LOS for urban highways.	54-57
D	Typical of an urban highway during commuting hours. Speeds are somewhat reduced, motorists are hemmed in by other cars and trucks.	46-54
E	Flow becomes irregular and speed varies rapidly, but rarely reaches the posted limit. On highways this is consistent with a road over its designed capacity.	30-46
F	Flow is forced; every vehicle moves in lockstep with the vehicle in front of it, with frequent drops in speed to nearly zero mph. A road for which the travel time cannot be predicted.	Under 30

[N.B. This table summarizes roadway Level of Service (LOS) rating. These only account for motor vehicle traffic speeds and congestion delay. Other impacts and modes are often ignored.]

The LOS for different roads of SingraPaurashava is demonstrated here on the basis of Wikipedia ratings (**Table: 11-4**).

Table 11-4: Existing Level of Service (LOS) of major roads of Singra Paurashava

Sl. #	Name of Roads	Speed (mph)							LOS
		Truck	Bus	Car/ Microbus	Auto Rickshaw	Motorcycle	Other (Nosimon)	Average	
1	Singra -Natore	25.00	30.00	48.50	22.30	52.84	20.00	33.1	E
2	Singra -Bogra	25.00	32.00	45.20	23.25	55.25	22.20	33.8	E
3	Singra -Kalon	-	-	35.25	20.50	50.00	20.25	21.0	F
4	Singra -Tajpur	-	-	30.50	18.50	40.00	20.12	18.2	F

Source: Traffic and Transportation Survey Data of SingraPaurashava by AQUA, 2011

The Origin-Destination (O-D) survey is important in describing transportation. This survey is conducted to collect information on travel and transportation generated between zones of a study area. Due to the proper design, this study will identify the passenger movements where and when trips originated and end, the socio-economic characteristic of the trip market, the purpose of travel and the mode of travel. **Table 11-5** describe about Paurashavas O-D trips.

Table 11-5: O-D matrix of surveyed trips of Singra Paurashava

		W1	W2	W3	W4	W5	W6	W7	W8	W9	OP (Natore)	OP (Natore)	OP (Kalom)	OP (Tajpur)	Total
Origin	W1	2	3	2	2	8	4	3	5	2	1	1	1	1	35
	W2	2	3	3	3	5	4	2	6	1	1	2	3	2	37
	W3	4	2	2	3	4	3	3	2	2	2	1	0	1	29
	W4	2	3	5	9	4	2	2	5	1	0	2	0	0	35
	W5	1	2	5	4	4	3	2	6	2	0	0	0	1	30
	W6	1	2	4	5	3	3	2	4	1	1	1	1	0	28
	W7	1	2	4	3	3	2	2	4	2	1	0	1	1	26
	W8	1	2	2	3	4	2	1	3	2	2	1	0	0	23
	W9	1	1	3	3	3	2	2	2	2	1	1	0	1	22
	OP (Natore)	1	0	2	1	0	1	2	1	0	0	3	1	1	13
	OP (Natore)	1	2	2	0	2	2	2	3	3	2	0	1	1	21
	OP (Kalom)	2	1	0	2	0	1	0	4	1	1	1	0	0	13
	OP (Tajpur)	1	2	1	2	0	1	0	1	2	2	1	0	0	13
	Total	20	25	35	40	40	30	23	46	21	14	14	8	9	325

*W= Ward, IP=Inside Paurashava, O=Outside Paurashava

Source: Traffic and Transportation Survey Data of SingraPaurashava by AQUA, 2010

Table 11-5 reveals that both are internal and external trips. It is found that ward 4, 5 and 8 Singra bazar attracts more trips. Apart from this, ward 2, 7, and 9 also place for trip destination. It is also noted that this road also used for external trips, for instances a significant number of trips produce and go for Natore.

Table 11-6 shows the relationship between mode use and trip purpose where it is found that trips is mainly used for work purpose. Rickshaws are used for all types of trips especially for work trips.

Table 11-6: Trip Purpose according to Mode Use of Singra Paurashava

Vehicle	Work/Personal Business	School/College/University	Shopping	Social/Recreation/Sports	Home	Others	Total
Truck	2	0	1	0	1	0	4
Bus	8	5	1	2	2	1	19
Car/pickup/jeep	2	2	1	2	1	1	9
Auto-rickshaw/Tempo	5	5	2	2	2	0	16
Motorcycle	4	3	2	1	1	1	12
Rickshaw	4	5	3	2	2	1	17
Bi-cycle	4	2	2	1	2	1	12
Votvoti	2	1	0	0	1	1	5
Van	2	2	0	1	1	0	6
Total	33	25	12	11	13	6	100

Source: Traffic and Transportation Survey Data of SingraPaurashava by AQUA, 2010

11.2.5 Facilities for Pedestrians

Most of the public generally considers pedestrian facilities to be limited to sidewalks; however, they encompass a much broader scope of services and facilities. Pedestrian facilities include, but are not limited to, traffic control devices, curb ramps, grade separations (overpasses and underpasses), crosswalks, and design features intended to encourage pedestrian travel (such as traffic calming devices including speed bumps or center refuge islands). In general, these facilities parallel the roadway system and provided as part of the public right-of-way. Pedestrian facilities or “pedestrian lanes” provide people with space to travel within the public right-of way that separated from roadway vehicles. It improves mobility for pedestrians and provides access and an alternative means of travel to and from home, work, parks, schools, shopping areas, and transit stops. It also provides places for children to walk, run, skate, bike, and play, where no walkways are provided, or where walkways are in poor repair or have missing sections. It is obligatory to mention here that, at present there is no pedestrian facilities available at SingraPaurashava.

11.2.6 Analysis of Existing Deficiencies

Like any other town, Singra has also transportation deficiencies, which are identified from two different sources. Firstly, by reconnaissance survey of the town, field observation interview of passenger and operator and secondly, by means of household sample survey.

11.2.6.1 Roadway Capacity Deficiencies

Primary Road (Regional Road)

The Natore to Natore Road is known as primary road as per SingraPaurashava, length is 4.09 km and average 7.20 meter. Road standard (ROW) recommended is 100 feet to 150 feet, proves that the ROW of the existing primary road in the Paurashava is lower than the standard (ROW) recommended. Moreover, in hat day and non-hat day, highest volume of traffic flows on the primary road and it is about 668 to 1176 PCU/hours.

Secondary Road:

There are three major secondary roads are in the Paurashava named Singra-Kalon road, length is 3.23 km and average width 2.66 meter, Singra-Gurudasapur road, length is 2.91 km and average width 3.7 meter and Singra-Tajpur union road, length is 1.54 km and average width 3.01 meter.

Road standard (ROW) recommended is 60 feet to 100 feet, proves that the ROW of the existing secondary roads in the Paurashava is lower than the standard (ROW) recommended. Moreover, in hat day and non-hat day, highest volume of traffic flows on those secondary roads is about 485 PCU/hour.

Tertiary Road:

In the Paurashava, two major tertiary roads have been identified and they are Singra-Karanpari Road, length is 0.80 km and average width 4.53 meter. Balua bausu jame mosque Road, length is 0.52 km and average width 4.05 meter.

Road standard (ROW) recommended for tertiary road is 20 feet to 40 feet, proves that the ROW of existing tertiary roads in the Paurashava is lower than the standard (ROW) recommended.

Moreover, in hat day and non-hat day, highest volume of traffic flows on those tertiary roads is about 150 PCU/hour.

Access road:

Road standard (ROW) recommended may be imposed on access road and it is 20 feet to 40 feet. In the Paurashava, all access roads are less than 12 feet and most of them are using as footway. Non-motorized vehicles named Van sometimes use those walkways.

Narrow Road Width ,

Narrow widths of roads and poor maintenance have marked by most respondents as major road problems in the town. From the survey, it has found that there are various problems in connection with transport such as problem of narrow road, and damaged during rainy season etc. This will cause traffic on the street will rise and will create serious traffic congestion on the narrow streets. The project area is served by 62.77 kilometers of roads. When asked about the problem of roads, they pointed to narrow width of roads, flooding of roads during monsoon, poor condition of roads due to lack of maintenance, traffic congestion at particular points of the town.

When asked about the problem of roads, most households respondents answered affirmative (Household survey, 2010). Indicating to major road problems, they pointed to narrow road; broken roads due to poor maintenance, flooding of roads during monsoon, and traffic congestion.

The following **Table 11.7** shows the details about the road width deficiencies of SingraPaurashava.

Table 11-7: Width of some Major Roads in Singra Paurashava

Road Type	Name	Type	Length (Km)	Width (m)
Primary Road	Natore-Bogra Road	Pucca	4.69	7.28
Secondary Road	Singra-Kalom Road	Pucca	3.44	3.34
	Singra-Gurudaspur Road	Pucca	2.91	3.69
	Upazilla Parisad Road	Pucca	0.87	4.57
	TNT Office Road	Pucca	2.52	3.96
	Sigra-Tajpur Union Road	Pucca	1.54	3.01
Tertiary Road	Singra-Karanpari Road	Pucca	0.80	4.53
	Balua bausu jame mosque Road	Pucca	0.52	4.05

Source: Transportation Survey of SingraPaurashava by AQUA, 2010

The above table clearly define that the Paurashava has severe deficiencies regarding road width. It has been very unfortunate that not a single road (including primary road) has not near to the standard width mark. It has been found that very narrow road width (less than 8 feet roads) which only provides free movement of a rickshaw is 46.89 percent of the total roadway. Narrow roads are defined as those road having 8-12 feet width where two rickshaws can pass comfortably (44.92%).

Map 11-1: Width of some Major Roads in Singra Paurashava

Traffic Conflict

Traffic conflict is common and frequent in towns where there is admixture of transport vehicles – slow and fast – in the streets. Areas of conflict occur at point where the intensity of traffic movement is high. The consultant studied the traffic movement in all over the town and identified one main point where the traffic conflict is highest, which is Bus stand Morr Intersection. At this point the slow moving vehicles, like, rickshaw, Nasimon and vans come in conflict with motor vehicles, creating traffic congestion. As the slow mobbing vehicles are higher, the conflict is usually frequent.

The identified reasons for traffic conflict are improper intersection design, parking of vehicles on the street, waiting of operators on the roads looking for possible passengers, absence of traffic signal, disobedience of traffic rules etc.

11.2.6.2 Operational, Safety, Signal and other Deficiencies

Traffic management system is absent in the Paurashava. No operational system yet being imposed on traffic movement.

Due to the minimum PCU/hr. both in hat and non-hat day, availability of non-motorized vehicles and absent of available built-up area, road safety exists naturally in the Paurashava.

Traffic signaling system is totally absent in the Paurashava. Generally, traffic signaling system will not be needed up to the limit of the planning period. On some specific point of primary and secondary roads, traffic signaling will be needed.

11.2.7 Condition of other mode of transport (Rail/Water/Air)

Within the Paurashava there exists no rail way network.

There is no air transport facility in Singra, for air travelling the people of Singra depending upon the Capital City Dhaka.

11.3 Future Projections

Road design standards are prescribed in the section 21 of the Public Roads Act, 2004. The regulations of the sections are:

1. The Government may declare design standards for roads by publication in the Official Gazette.
2. The road design standards shall set out design requirements for roadways and road-related areas including structures located on roadways or road-related areas.
3. A road authority shall comply with the road standards when carrying out works on a roadway, road-related area or when installing, modifying or maintaining a structure on a roadway or road-related area.
4. Despite sub-section (3), a road authority is not required to comply with the road standards if:
 - a. The road authority is carrying out maintenance and, in the view of the road authority; it would not be practicable to comply with the road design standards.

- b. The Government has, in writing, exempted the road authority from complying with the road design standards in relation to the works or structure.
- c. The Government may revoke or amend road design standards in the same manner as a declaration.

The Urban Area Plan for Dhaka City has recommended road standards with the consideration of traffic volumes, which were not undertaken in conjunction with the Dhaka Integrated Transport Study (DITS). A wide range of standards was suggested for various classes of roads, ranging from 4 meters to 24 meters, as mentioned below. The required right of way (ROW) is also indicated:

- Main Road,,24.0,meter, (78 ft) ROW
- Arterial Road,,14.5,meter,(47.5 ft) ROW
- Collector Road,,13.0,meter,(42.6 ft) ROW
- Access Road,,9.0,meter,(29.5 ft) ROW
- Access Road,,6.0,meter,(19.7 ft) ROW
- Non-motorized Road,4.0,meter,(13.4 ft) ROW
- Footpath,,2.5,meter,(8.2 ft) ROW

In order to promote development of all roads in a systematic manner, new road standards were recommended for both built up areas, as well as for less built-up areas. These will replace the old standards, which were included in the Dhaka Metropolitan Development Plan (DMDP). The standards, when adopted will facilitate earmarking the right of way (ROW) for all major roads. The details of these standards used in this plan are indicated in **Table 11-8** below.

Table 11-8: Geometric Road Standard of Roads Proposed by LGED

Types of Road	Recommended width
Paurashava Primary Roads	150-100 feet
Paurashava Secondary Roads	100-60 feet
Local Roads	40-20 feet

Source: UTIDP Planning Standard, LGED

11.3.1 Travel Demand Forecasting for Next 20 Years

Existing road network is quite enough for accommodating present volume of traffic. The study area is rural in nature. Most of the roads are katcha and needs to be constructed as pucca. Katcha roads become clayey in the rainy season and bring immense sufferings for the users. As a result, social, cultural and economic activities are disrupted significantly at that time. A very limited uses of small boats are found for transportation of goods within the short distance particularly on hat day. Due to the absence of effective alternatives, passengers and goods movement of the study area is largely dependent on road transportation. This dependency will be calculated according to the increase of accessibility, consideration of the missing links, volume of traffic movement, bulk density of the area and economic importance of the area. Growth direction is also a considerable component for the demand analysis of the road.

11.3.2 Transportation Network Considered

The growth of transport networks obviously affects the social and economic activities that an area can support; yet the dynamics of how such growth occurs is one of the least understood areas in transport, geography, and planning. Transport network changes are treated exclusively as the result of top-down decision-making. Changes to the transport network are rather the result of numerous small decisions (and some large ones) by property owners, firms, developers, towns, cities, counties, and MPOs in response to market conditions and policy initiatives. Understanding how markets and policies translate into facilities on the ground is essential for scientific understanding and improving forecasting, planning, policymaking, and evaluation.

11.3.3 Future Traffic Volume and Level of Service

Traffic volume, as indicated by traffic counts at various locations on the roadway network; which reflect current travel patterns and how well the network is serving the travel demand.

When planning ahead to address the needs of our transportation network, it is important to project the level of traffic that we can anticipate during our planning period and beyond. Population growth plays a key role in determining the needs of a transportation system. Generally, an increase in population results in an increase in the use of transportation facilities; which in most cases means more vehicles on the roadways.

The future traffic volume of SingraPaurashava is forecasted by adopting extrapolation method. An extrapolation factor indicating the growth trends, which is derived from earlier and present year traffic volume is introduced in this method. The future traffic volume is forecasted at one intersection, which is bus stand morr intersection, is the most important intersection of the SingraPaurashava. The intensity of traffic movement observed in these intersections is high and traffic conflict is prevalent at these points. The forecasted traffic volume of two major intersections of SingraPaurashava is presented in **Table11-9**.

Table 11-9: Projection of Target Year Traffic Volume

Name of Intersection	Duration	Year			
		2011	2016	2021	2031
Traffic Volume at Bus stand morr Intersection	09:00-10:00	220	267	323	392
	10:00-11:00	286	347	420	509
	17:00-18:00	272	330	400	484
	16.00-17.00	185	224	272	329

Source: Transportation Survey of SingraPaurashava by AQUA, 2010

For this reason, future population growth is often a good indicator of future increases in traffic volumes.

The Level of Service (LOS) represents the minimum acceptable performance standards on a particular roadway facility indicated in **Table 11-10**. The Paurashava authority should have adopted the policy LOS for their road system. The key factors in the policy of Level of Service (LOS) consider the following:

- The individual characteristics of the community, its goals, objectives and needs

- The ability to provide the facilities that are determined necessary to maintain the policy level of service for current and future traffic volumes
- The ability to fund the facilities that are determined necessary to maintain the policy level of service for current and future traffic volumes

Table 11-10: Level of Service of Different Major Roads and their Relative Proposals

Sl. #	Road Name	Average Speed of Vehicle	Road Width (m)	Level of Service	Remarks
1	Singra –Natore Road	33.1	7.28	E	Need road widening
2	Singra -Natore Road	33.8	7.28	E	Need road widening
3	Singra –Kalon Road	21.0	3.34	F	Need road widening
4	Singra -Tajpur road	18.2	3.01	F	Need road widening

Source: Transportation Survey of SingraPaurashava by AQUA, 2010

11.4 Transportation Development plan

11.4.1 Plans for Road Network Development

The standards are meant for use by UTIDP, LGED and other planning and development agencies. The standards have been adopted by the consultants to draw up the transportation development plan. Following are the suggested planning standards (Table 11-11) for road network development. These road hierarchies are proposed based on the functional linkage of the road of Singra Paurashava.

Table 11-11: Proposals of Roads Standard in the Project Area

	Widening
Paurashava primary roads	ROW 100 ft
Paurashava secondary roads	ROW 40-60ft
Access Road/ Local Road	ROW 20ft

Source: Upazila Towns Infrastructure Development Project and Proposed by Consulting Firm.

Neighborhood and Local Road

The right of way (RoW) of all neighborhoods (mahallah) roads may be in between 20 ft. to 30 ft. depending on their functions.

Standard Road Design

All urban roads should have flexible pavements. The road intersection should be designed to allow easy movement of vehicles. At bridge, the road design should provide for an adequate sight distance and a smooth riding.

Functions of Roads

Each category of road has its particular functions to perform. Access road carries traffic from buildings to the collector road and collector road carries traffic to the major road and vice versa. In reality, however, it is almost impossible to maintain this hierarchical use of roads except in an entirely planned area. However, functions will not be dependent on the road width, rather on the location of the road, surrounding land use and the link it is providing or the volume of traffic it

iscarrying. Thus a 40 feet wide secondary road can become a major road due to its strategiclocation and the purpose it is serving.

11.4.1.1 Road Network Plan

Planning standard is a fundamental tool for formulation of any planning perspective including transport plan. The suggested planning standards of road width for UTIDP are illustrated in **Table-11-8**. The standards are meant for use by UTIDP, LGED and other planning and development agencies. The standards have been adopted by the consultants to draw up the current series of plans. An integrated road network plan has been prepared commensurating the planning standards and considering the convenient movement of all vehicular and pedestrian traffic. Three types of road, such as Paurashava Primary Road, Paurashava Secondary Road and Local Road are proposed designating a unique ID No. to each road for the purpose of identifying them in map. The road network plan along with transportation management plan is presented in **Map 11-2** below.

Paurashava Primary Road

Natore-Bogra Highway Road is proposed as Primary road. Total length of primaryroad is 4.5 km with 100 ft RoW. Figure 11.3 shows the layout design of primary road with 100ft RoW.




Fig 11-3: Primery Road Width 100ft ROW

Paurashava Secondary Road

Total secondary road is 33.64 km with 30-50 ft RoW of which 21.15 km road will widen and rest 12.49 km road will be newly constructed in on different phases to fulfill the future needs of the Paurashava. Figure 11.4 and 11-5 shows the layout design of primary road with 40 ft & 30 ft RoW.




Fig 11-4: Secondary Road Width 40ft ROW




Fig 11-5: Secondary Road Width 30ft ROW

Access Road/ Local Road

Total Local road is 58.04 km with 20 ft RoW. Of which total 38.59 km road will widening existing road and 19.45 km road will newly construct to fulfill the future need of the Paurashava. Figure 11.6 shows the layout design of primary road with 20 ft RoW.




Fig 11-6: Local/Access Road Width 20ft ROW

11.4.1.2 Proposal for improvement of the existing road networks

Traffic management measures may be adopted to increase traffic capacity and safety. The improvement could be done by removing the deficiencies in the existing core road network by widening and /or strengthening of selected stretches / corridors in a phased manner and improvement of road geometrics and safety provisions. **Table 11-12** shows the summary of road widening proposal.

Table 11-12: Summary of Road Widening Proposal in Singra Paurashava

Road Width (in ft)	Length (in meter)	Length (in km)	Percentage	Road Type
20	58037.27	58.04	60.33	Access/Local Road
30	12541.67	12.54	13.04	Secondary Road
40	12897.06	12.90	13.41	Secondary Road
50	8203.73	8.20	8.53	Primary Road
100	4520.64	4.52	4.70	Primary Road
Total	96200.376	96.20	100.00	

Table 11-13 shows the detailed scenario of road widening proposal of Singra Paurashava along with width of the existing roads.

Table 11-13: Road Improvement Proposal in Singra Paurashava

Road ID			Length (in M)	Type of Road	Phase-wise development		
	PW ¹ (Ex.) In meter	RoW ² (Pr.) In ft			First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
WR-1	7.28	100	4520.637	Primary Road	First Phase	Development will continue	
WR-105	4.537	30	807.258	Secondary Road		Second Phase	Development will continue
WR-107	3.396	30	736.007	Secondary Road		Second Phase	Development will continue
WR-12	3.215	20	568.825	Local/Access Road	Third Phase		
WR-127	3.963	50	870.703	Secondary Road	First Phase	Development will continue	
WR-13	3.25	20	2008.607	Local/Access Road	Third Phase		
WR-171	3.049	30	702.033	Secondary Road		Second Phase	Development will continue
WR-18	3.699	40	2912.197	Secondary Road	First Phase	Development will continue	
WR-2	3.34	50	3238.444	Secondary Road	First Phase	Development will continue	
WR-246	3.963	40	870.033	Secondary Road	First Phase	Development will continue	
WR-313	3.963	50	2519.714	Secondary Road	First Phase	Development will continue	
WR-332	3.132	20	1121.400	Local/Access Road	Third Phase		
WR-346	3.963	40	1541.957	Secondary Road	First Phase		Development will continue
WR-352	3.299	20	1361.006	Local/Access Road	Third Phase		
WR-355	3.1	20	2593.923	Local/Access Road	Third Phase		
WR-56	4.07	30	1032.974	Secondary Road		Second Phase	Development will continue

Road ID	PW ¹ (Ex.) In meter	RoW ² (Pr.) In ft	Length (in M)	Type of Road	Phase-wise development		
					First Phase (1 st to 5 th yr)	Second Phase (6 th to 10 th yr)	Beyond 10 th year
WR-69	2.696	20	825.147	Local/Access Road	Third Phase		
WR-9	3.699	40	586.832	Secondary Road	First Phase	Development will continue	
WR-99	4.059	30	521.497	Secondary Road		Second Phase	Development will continue

**** Road length $\geq$ 500 meter incorporated here. Detail was given in Appendix and Ward ActionPlan.**

1. PW (Ex.) : Paved Width of Existing Road
2. RoW (Pr.): Rights of Way of Proposed Road

Source: Upazila Towns Infrastructure Development Project and Proposed by Consulting Firm

Map 11-2: Proposed Road map of SingraPaurashava

11.4.1.3 List of Proposed new roads

The Urban Area Plan provides brief description of any proposed transport improvements. The transport content of this plan has been developed around the framework of the Structure Plan. The specific transport proposals set out in the Urban Area Plan for public consideration include new road schemes and improvements, traffic management measures, the co-ordination of public transport services, the control of car and lorry parking and the improvement of cyclist and pedestrian safety. The proposals put forward for discussion to the mass people of the Paurashava. The Paurashava authority also advises about road development should not be duplicated in the public examination of Urban Area Plan and Ward Action Plans. Local Authority roads, which are not strategic, are not included in the Ward Action Plan and both the need for the road and the line of the route are matters for the Urban Area Plan to consider. A list proposed of new roads have been made after studying the existing road network, travel demand pattern, potential for future urban growth and conducting public consultation meeting with Paurashava officials, councilors, local people and other stakeholders which is presented in **Table 11-14**.

Table 11-14: List of Proposed Roads in Singra Paurashava

Road ID	RoW in Ft	Road Type	Length in M	Phase
NR-12	20	Local/Access Road	321.073	Second Phase
NR-13	20	Local/Access Road	628.291	Second Phase
NR-15	20	Local/Access Road	322.982	Second Phase
NR-17	50	Secondary Road	1328.265	Second Phase
NR-18	30	Secondary Road	313.090	Third Phase
NR-19	30	Secondary Road	745.460	Third Phase
NR-2	20	Local/Access Road	306.861	Second Phase
NR-20	20	Local/Access Road	304.472	Second Phase
NR-21	40	Secondary Road	1000.014	Second Phase
NR-26	40	Secondary Road	1364.682	Second Phase
NR-28	20	Local/Access Road	543.790	Second Phase
NR-29	20	Local/Access Road	431.410	Second Phase
NR-3	20	Local/Access Road	872.234	Second Phase
NR-33	40	Secondary Road	827.692	Second Phase
NR-39	40	Secondary Road	1202.412	Second Phase
NR-4	30	Secondary Road	431.942	Second Phase
NR-58	20	Local/Access Road	370.946	Third Phase
NR-68	20	Local/Access Road	420.018	Second Phase
NR-69	40	Secondary Road	568.506	Second Phase
NR-70	20	Local/Access Road	330.398	Second Phase
NR-75	30	Secondary Road	508.771	Third Phase
NR-78	30	Secondary Road	549.515	First Phase
NR-83	20	Local/Access Road	304.498	Third Phase
NR-84	20	Local/Access Road	614.897	Third Phase
NR-85	50	Secondary Road	4388.157	Second Phase
NR-87	20	Local/Access Road	377.778	Third Phase
NR-88	20	Local/Access Road	363.876	Third Phase
NR-89	20	Local/Access Road	806.719	Third Phase
NR-90	20	Local/Access Road	737.858	Third Phase
NR-91	20	Local/Access Road	508.854	Third Phase
NR-93	20	Local/Access Road	365.269	Third Phase
NR-95	20	Local/Access Road	887.028	Third Phase
NR-96	20	Local/Access Road	1018.971	Third Phase
NR-97	20	Local/Access Road	535.811	Third Phase
NR-99	40	Secondary Road	555.936	First Phase

*** Road length $\geq$ 300 meter incorporated here. Detail was given in Appendix*

11.4.2 Plan for Transportation Facilities

11.4.2.1 Transportation Facilities Plan

Bus Terminal

There is a designated bus terminal in this Paurashava. So, there is no need to propose the new bus terminal rather than it is good to enlarge the existing terminal.

Truck Terminal

The SingraPaurashava is the route to carry the goods. Besides, there is much importance of trucks for the Paurashava/Upazila. Therefore, a truck terminal is proposed to the extreme south-west corner of the Paurashava beside Singra-Natore main road.

Tempo/Rickshaw Stand

Tempo and Rickshaw is now a major and cheap commuter in small towns that play important role in commuter transportation. There is no formal tempo stand in the Paurashava.

Table 11-15: List of Proposed Roads in Singra Paurashava

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.
Truck Terminal	0.66	12	,Niagain_333_01	Partial 1562,1563,1564
Tempo Stand	0.25	7	Niagain_333_02	Partial 1502,1504,1505,1395
	0.44	8	,Singra_342_00	Partial- 190-191,197-199
	0.18	4	,Singra_342_00	Partial-140-151
	0.25	3	,Falia_259_00	Partial-131,133
	0.25	4	,Balua Basua_341_00	Partial-24
	0.25	9	Sola Kuri_345_00	Partial-378-380,384
	0.75	02	Uttar Domdoma_336_00	Partial 336,337,338,339,340
	0.25	03	Falia_259_00	Partial 125,126,130
	0.66	10	Par Sawail_369_01	Partial 110,111,114,115,127,145,146,147,148,149
	0.38	11	Katua Bari_370_00	Partial 243,253,254,255,256,257,299
Rickshaw/ Van Stand	0.25	9	Sola Kuri_345_00	Partial-224,225,231,232
	0.33	4	Singra_342_00	Partial-135,151
	0.25	1	Chak Gopal_337_00	Partial-61,67,70

Type of Facilities	Area in Acre	Ward No.	Mouza Name	Plot No.
Ghat	0.02	1	Porbo Masinda_335_00	Partial-33
	0.02	1	Porbo Masinda_335_00	Partial-23,25
Total	5.03			

11.4.2.2 Parking and Terminal Facilities

There is no parking facilities provided in SingraPaurashava. People are habituated for parking beside the roads. This parking practice occupied considerable spaces and reduces the effective road width. Particularly in bazaar area where a number of markets exist the parking problem become acute during weekly hat days. If it is possible to integrate parking area for tempo, rickshaw, van, etc. near to Bazar area the congestion problem will be solved.

In order to mitigate the traffic congestion and traffic conflict at the Bazar area one parking area is proposed at the north side of SingraPaurashava (**Map11-2**). On-street parking shall be prohibited on all roads within the Bazar area except at places where it is specifically permitted for parking.

Adequate terminal facilities will be provided at the bus and truck terminal for the convenience and comfort of the commuters.

The bus terminal should have to accommodate the following services:

- Ticket Counter
- Passenger-shed
- Workshop
- Cleaning and washing facility
- Loading and unloading place
- Bus parking space
- Toilet facility
- Waiting room
- Canteen

Proposed facilities accommodate in the truck terminal complex:

- Workshop
- Cleaning and washing
- Loading and unloading place
- Truck parking space
- Toilet facility
- Canteen

11.4.2.3 Development of Facilities for Pedestrians, Bicycles and Rickshaws

Footpath may refer to sidewalk, which runs along vehicular roads. It is a separate lane exclusively designed for the purpose of pedestrian movement. The footpath is quite safe and free from any accident. Unfortunately, there is no footpath besides any road of SingraPaurashava.


The transportation system within residential neighborhoods should favor pedestrian movement and discourage vehicular through traffic in both new and existing neighborhoods. A pedestrian system that utilizes neighborhood streets and paths to link the residents with the commercial and school functions serving the area will be encouraged.

The provision of separate bicycle or rickshaw lane is not a requisite for a low level of non-motorized traffic movement pattern, which is prevalent in any Upazila level small town like SingraPaurashava.

11.4.2.4 Other Transportation Facilities

Roundabout,

A roundabout is a type of circular intersection. It can handle much higher volumes of turning traffic. Their safety benefits result primarily from the control they exercise on approach speeds, and this makes them ideal for junctions at the entrance to towns and villages. They are also one of the safest ways of handling the transition between dual carriageways and single carriageways.



The presence of mixed traffic, including NMVs and pedestrians, means that roundabouts must be designed primarily for speed control. The proposed list of roundabout in SingraPaurashava is as follows:

Table 11-16: List of Proposed Roundabout in Singra Paurashava

ID	Ward No.	Location
1	08	Bus Stand Morr

Traffic Signs and Signals,

Traffic signs and signals are required in order to provide for the safe and orderly movement of motorized and non-motorized traffic and pedestrians. These provide information about routes, directions, destinations and points of interest. They also provide information on regulations, which apply to specific locations or at specific times, and warn of hazards, which may not be evident.

When a traffic sign is correctly used, the majority of motorists will comply with the posted regulation or warning, and drive in a safe and orderly manner. In order to minimize the rate of traffic conflict the following signs and signals should be provided at the key location considering the prevailing traffic situation and traffic management option.

Table 11-17: Traffic Control Facilities in Singra Paurashava

Traffic Control System sub-division		Present	Remarks
Traffic Signs (Traffic signs are devices placed along, beside, or above a highway, roadway, pathway, or other route to guide, warn, and regulate the flow of traffic, including motor vehicles, bicycles, pedestrians and other travellers.)	Regulatory	None	Should be Installed
	Warning	None	Should be Installed
	Marker	None	Should be Installed
	Guide & Informational	None	Should be Installed
	Others	None	Should be Installed
Traffic Signals (Traffic signals are electrically operated traffic control devices which alternately direct traffic to stop and to proceed.)		None	Should be Installed
Traffic Police control Hour (Under this system, a person or a group of persons according to law by local/national authorities facilitate the movement of traffic and to prevent and/or report any breach of road traffic regulations on roadway.)		None	Should be Installed

Source: Transportation Survey of Singra Paurashava by AQUA, 2010

11.4.3 Waterway Development/Improvement Options

There is a potential scope of waterway network within the vicinity of the Singra Paurashava and there is proposed two ghats from higher authority. Thus, waterway development option is not applicable at Singra Paurashava.

11.4.4 Railway Development Option

There is no existing railway line in the vicinity of the Singra Paurashava and there is no proposal for its establishment from higher authority. Thus, railway development option is not applicable at Singra Paurashava.

11.5 Transportation System Management Strategy (TSM)

Traffic Management for Singra Paurashava is not just to consideration of vehicle movement rather considering the suitability to walk comfortably, to ride bicycle, distance consideration, easy access to market, parking facilities, etc. Traffic management context for a local Town can be reconsidered as the following Figure:

11.5.1 Strategies for Facility Operations

□ Creation of major linkage

As the town grows and the traffic intensifies on the streets, an efficient network of roads has to be built based on major North-South link. This would ensure direct connection between different curial nodes of the network and help reduce both travel length and time. This is a nonstop process and will be closely in interaction with the spatial development policies for the Town.

□ Lane-based traffic management

Determining number of lanes on every street and their individual capacity and routing the traffic management and any future expansion on that capacity assessment. Lanes can be designated for different modes. Use of every segment of the road has to be pre-designed and clearly defined e.g. movement, parking, pedestrian crossing etc.

❑ **Promote use of FFT (Fuel Free Transport) and discourage FDT (Fuel Dependent Transport)**

Use of fossil fuel and harmful emissions are a major environmental issue all over the world. That's where FFT can play a vital role. Modes like walking, bicycling are in general called 'green transport' for their environmental friendliness. Promotion of these means of mobility can eliminate long-term negative impacts of fuel-based vehicles and enhance health and safety of the inhabitants.

❑ **Promote Plantation on the Walking way besides of the Roads**

Embankment cum Roads and other major roads have been proposed for promoting plantation with street furniture.

❑ **Providing Properly Designed Pedestrian Ways**

SingraPaurashava has no provisions of pedestrian ways, which is one of the major crucial problems for the Town in Transport sector. All necessary facilities should be provided for the pedestrians. A designed pedestrian ways must be integrated closely with other transportation elements so that walking becomes a recognized mode and becomes a pleasure and a place for brief social gatherings for the Paurashava dwellers.

❑ **Road space allocation:**

Road space should be allocated among different mode and use based on the hierarchy of the road and its adjacent land-use. This is essential for safety and effectiveness of the road.

❑ **Development & availability of Public Transport (PT)**

This should form the major share of the motorized vehicle. PT has to be available within comfortable walking distance from any part of the Paurashava. Maintenance of an efficient public transport provides a cheap and accessible solution for mass movement.

❑ **Preserve and utilize natural network (adjacent River/ Khals) as Transport Corridors**

Establishing the network of Khals and River as vital corridors of transportation, especially for goods movement would create a viable alternative to road transport and also help preserve this traditional mode. Water transport is usually cheap and as goods delivery generally has a lead time, waterways can play crucial role in this sector. It can also serve recreational purposes for the city dwellers.

❑ **Minimizing Transfer Times**

The present deficiencies in the inter-modal integration of the transport system are economically unsustainable in the long run. The current systems are time consuming to travel by more than one mode for the Town of SingraPaurashava.

❑ **Integrating the Management of Land Use and Transportation in SingraPaurashava**

The growth of the Town still concentrated to the core part of the area adjacent to the bazaar area which is just North Portion of the Municipality. To bring out a proper traffic and transport design core part of the town have to manage with high consideration and the semi core and fringe area should have to design for future projection basis.

11.5.2 Strategies for Traffic Flow and Safety

The following strategies have been identified for Traffic flow and safety

❑ **Avoid dispersed and scattered development patterns**

Dispersed and scattered type of development promotes 'sprawl' and increases for travel. It raises the need for more and more transport corridors inducing ever greater traffic.

❑ **Consider traffic impact of land use and occupancy of structure while giving building construction and land use permit**

Kind of use for the any structure has to be clearly defined. 'Transportation Clearance' should be given considering the structure size and proposed use and has to be a compulsory criterion for receiving building permit.

❑ **Effective road network design has to consider for the mixed land-use areas that provide both places to live and work**

Mixed land use provides the commercial base for supporting viable public transit. For providing effective road network design the study has been proposed the road cross section according to the road categories.

❑ **Widening the existing Roads**

All existing Roads have to be widening according to the Land use Importance.

❑ **Provide parallel service roads along the National Highway and Ensure less Use of this Highway from Local Purposes**

Direct connection of over access roads, cattle using, haphazard way passenger/ vehicle over-crossing, adjacent tea shops/vegetable markets etc should be avoided. For this purpose service roads have been proposed for the High way to save from over connection of local roads and other high way related services.

❑ **Separate lane for NMT**

Provisions of Separate lane for NMT will help to avoid traffic jam and conflicts.

❑ **Pedestrian First**

All the roads of the Paurashava necessary facilities should be provided for the pedestrians. A designed pedestrian ways must be integrated closely with other transportation elements so that walking becomes a recognized mode and becomes a pleasure and a place for brief social gatherings for the city dwellers.

❑ **Parking Provision**

Auto Rickshaw, Rickshaw stoppage will be provided on the suitable place for the present need and also for growing future demand. Set up Rickshaw or Auto Rickshaw stops on street corners and other suitable locations.

11.5.3 Strategies for Traffic Management

The following strategies have been identified for Traffic Management

❑ **Formulate a Local Area Traffic Management Unit (LATMU)**

Designing, modeling and at last managing traffic and Transport is not an easy task. It needs important decisions of policy makers from both Public and Administrative representatives. For the Upazila Towns Mayor is the principle for taking any decisions whereas traffic and Transport related decisions require a Coordination Board where high official's opinion is very much important. For this purpose a small Town Transport Planning and management unit is require to manage traffic and transport situations.

❑ **Integrating the Management of Land Use and Transportation in SingraPaurashava**

As transport is basically a function of land use, any proposed development should be examined with respect to the traffic impact it has on the locality. Kind of use for the any structure has to be clearly defined. 'Transportation Clearance' should be given considering the structure size and proposed use and has to be a compulsory criterion for receiving building permit.

The growth of the Town still concentrated to the core part of the area adjacent to the bazaar area which is just North Portion of the Municipality. To bring out a proper traffic and transport design core part of the town have to manage with high consideration and the semi core and fringe area should have to design for future projection basis. Mixed land-use creates vibrant, lively neighborhoods/communities and reduces the need for longer distance travel and commuting. Short distances travel also encourages use of sustainable alternatives like walking and bicycling. Mixed land use provides the commercial base for supporting viable public transit. This would also imply restricting development of new strictly single-use zones (like residential, commercial etc.)

Dispersed and scattered type of development promotes 'sprawl' and increases for travel. It raises the need for more and more transport corridors inducing ever greater traffic. Therefore, avoiding and discouraging this kind of development by various policy measures would help reduce creating new trips.

❑ **Developing an Integrated Transportation System**

As there is no transport studies have conducted before for the Upazila Towns, no serious effort has been made for the functional integration of different modes of transport. However, it is well known that without effective integration of transportation systems, economic benefit, convenience and comfort from transportation services cannot be derived.

❑ **Avoid dispersed and scattered development patterns**

Dispersed and scattered type of development promotes 'sprawl' and increases for travel. It raises the need for more and more transport corridors inducing ever greater traffic. Therefore, avoiding

and discouraging this kind of development by various policy measures would help reduce creating new trips.

❑ **Need for Integration between Modes**

The main challenge in the area is to identify and link together the most appropriate modes for any journey. Unfortunately the existing modes (BUS -Try Auto Rickshaw -NMT) are acting independently of each other. As a result the passengers suffer due to the lack of inter-connection and scheduling and freight traffic faces delays and increased costs particularly when it is carried by waterways from outstations for destinations inside of the Paurashava. There is an urgent need for integration between modes for economic reasons and for convenience and comfort of the passengers. Traffic management is the It encompasses traffic engineering, but also includes policy making, planning and consultation processes and that's why a traffic management unit has to be launched. One traffic management unit will launch which will be under the UpazilaParishad and must be merged with the Paurashava for regulation, organization, guidance and control of all kinds of stationary and moving road users, and vehicles, including pedestrians, cyclists, motorcyclists, truck and cars, respecting the needs of abutting land uses.

❑ **Aspects of Access Control**

Maximum use should be made of the existing infrastructure before new roads are contemplated. In moving towards areas of vehicle restrictions and the management of demand a number of measures will be necessary in order to reduce congestion and pollution in the core part of the Town.

❑ **Minimizing Transfer Times**

The present deficiencies in the inter-modal integration of the transport system are economically unsustainable in the long run. The current systems are time consuming to travel by more than one mode for the Town of SingraPaurashava.

11.6 Plan Implementation Strategies

11.6.1 Regulations to Implement the Transportation Plan

There is no specific policy provided for the local urban traffic and transport management for the small town of Bangladesh though there exists National Land Transport policy for Bangladesh. For this purposes to implement the transport plan national land transport policy can be followed. Again a traffic transport management authority must have to provide merge with Paurashava urban planning sector to manage transport related development and implementation.

The roles of the municipality will be largely unchanged. Their functions will still be to provide essential services for the population including in the transport sector – public transport, traffic management signal systems, parking control and management and street lighting. The development of transport systems and infrastructure within the municipalities will be in accordance with the Structure Plan that will be provided under the Master Plan.

❑ **Effective co-ordination in transport**

Better coordination to be established between the UpazilaParishad and Departments under its control; & regulations will be formulated to achieve the goal of creating better working links

between the Government and the public and private sectors. A committee has to develop to monitor the entire development project of the Paurashava to analysis about transport sector violation.

Government to promote clearer objectives and responsibilities for each sector in order to create more integrated working relationships.

❑ **Promoting the role of the transport users**

The Government will examine how best the interests of users can be represented within the existing national government and local authority system; The Government will establish a user role within its transport planning process.

❑ **Transport users should pay for the costs of services**

The Government makes arrangements to realize cost of transport operation and road maintenance from road users through new fiscal policies; to protect public interest, the Government will regulate tariffs for passenger and goods both in road and rail transport.

❑ **Subsidies for transport services**

The government should allow subsidy to the transport sector only on consideration of public interest.

11.6.2 Implementation, Monitoring, Evaluation and Coordination of the Plan

In Urban area planning the most significant role will be played by Paurashava planning department. The Planning department will carry out the entire work of project initiation and plan formulation. These works are complicated and time consuming, and require multidisciplinary professionals. But there is no provision of planning department in SingraPaurashava. It is not possibly by the existing Paurashava personnel to undertake UAP programme after discharging all its regular office functions. This would necessitate strengthening of the institutional capacity of the traffic and transport Planning Section. Under the reorganized organogram of the Planning department, a Planning department can be created to deal with all affairs of area planning for the 'A' category Paurashava.

Under the current government policy regarding public sector agencies, it is unlikely that a major reshuffling can be achieved in improvement of existing manpower position of the Planning Section. As a result a large part of the planning process may have to be done through private consultancy.

According to the Local Government (Paurashava) Act, 2009, Paurashava will, in the prescribed manner, prepare and execute a Road Maintenance and Development Program. A Paurashava also maintain the measures on Street lighting, street watering, traffic control, and public vehicles. They will maintain such public streets and other means of public communication as may be necessary for the comfort and convenience of the inhabitants of the municipality and of the visitors thereto.

Chapter 12: Drainage and Environmental Management Plan

A. Drainage Plan

12.1 Introduction

The purpose of the Drainage Plan is to make an assessment of the present drainage facilities and the scope for future development within 2703.74 acres study area of the SingraPaurashava that consists of partially developed commercial, residential area and infrastructure. The purpose of the survey was to gather information available and use them at the time of the preparation of the drainage Plan that shall act as a guiding document for designing of drains in future. This Drainage Plan shall be a planning tool and shall be used as a guideline for SingraPaurashava that shall be responsible for the approval of drainage improvements. In the past, the term drainage included only the hydrologic and hydraulic aspects for discharge of storm runoff. Perhaps the most pressing challenge that now a days we face include the management of our water resources and flood hazard, maintain a continuous supply of water for industrial, agricultural, transportation, recreation, and potable water for present and future generations. The Drainage Plan aspects shall also include the flood and water resources management and pollution abatement. The Drainage Plan will propose improvements necessary to the major drainage systems to accommodate storm runoff of the SingraPaurashava. This planning process will consider both structural and nonstructural techniques to reduce the effect of the storm runoff which may be summarized as follows:

- Improvements to major drainage outfalls
- Improvement of the drainage network
- Management of available water resources
- Conservation of existing natural drainage channels

12.1.1 Goals and Objectives

Following are the overall objectives of the drainage plan of SingraPaurashava:

- To allow smooth drainage of storm water and the waste water of the town.
- To develop a comprehensive drainage network with area coverage and capacity.
- To prevent encroachment to natural drainage system.
- To create awareness about disposing of solid waste in the drainage system.

12.1.2 Methodology and Approach to Planning

Preparation of the Drainage Plan involves (I) analyzing the existing conditions related to drainage facilities and the flood management (II) identifying major drainage outfalls and on the basis of the outfalls splitting the total drainage area into a number of drainage zones (III) defining all pertinent design criteria and (IV) defining drainage facility requirements and sizing.

The drains are designed to collect excess rainfall that comes as surface runoff from urban area, convey the runoff and finally discharge them to outfalls. The design of drains involves hydrological computations of rainfall intensity, its frequency of occurrence, duration etc., and the total runoff of a

particular catchment area. The US Soil Conservation Service (SCS) method shall be used as an alternative of the Modified Rational Method for larger catchment areas.

In Modified Rational Method, the overall watershed is divided into zones that contribute to hydraulically significant points of concentration. The boundary of the zones is established based upon local topographic boundaries such as streets, existing drainage systems, etc., using good engineering practice.

Method Used

Storm and used water: The drains are designed to collect excess rainfall that comes as surface runoff from urban area, convey the runoff and finally discharge them to outfalls. The design of drains involves hydrological computations of rainfall intensity, its frequency of occurrence, duration etc., and the total run off of a particular area. The modified rational method shall be used for calculation of peak runoff for a definite frequency and duration from particular drainage basin. One limitation of this method is that it cannot be used for catchment area greater than 320 acres. The Natural Resources Conservation Service (NRCS) method formerly the US Soil Conservation Service (SCS) method shall be used.

In Modified Rational Method, the overall watershed is divided into zones that contribute to hydraulically significant points of concentration. The boundary of the zones is established based upon local topographic boundaries such as streets, existing drainage systems, etc., using good engineering practice. The design flow rate by Modified Rational Formula is –

$$Q = C_s C_r I A$$

Where:

Q,=,Design runoff flow rate (cfs)
I,=,Rainfall intensity (in/hr)
Cs,=,Storage coefficient
Cr,=,Runoff coefficient
A,=,Drainage area (acres)

Rainfall Intensity (I): The rainfall intensity is the average rainfall rate for a particular drainage basin or sub-basin. The intensity is selected on the basis of the design rainfall duration and return period. The return period is established by design standards as a design parameter. Rainfall intensity with 5 years return period is generally employed for design of primary drains and canal improvement. Rainfall intensity with 3 years return period is employed for design of secondary drains. The design duration is equal to the time of concentration for the drainage area under consideration. Time of concentration is a critical parameter both for the Modified Rational Equation and SCS method. Time of concentration is generally defined as the longest runoff travel time for contributing flow to reach the outlet or design point, or other point of interest. It is frequently calculated along the longest flow path physically.

Estimating the time of concentration involves identification of an appropriate flow path or paths and estimating runoff travel times along the flow paths. Where post-development conditions include significant pervious surfaces, the time of concentration for just impervious portions of the basin may be required to calculate and compare peak flow response for the basin as a whole against that of the more rapidly-draining impervious surfaces alone. The Time of Concentration composed of the Initial Time of Concentration, sometimes referred to as the Inlet Time or Time of Entry and

the Travel Time. Initial Time of Concentration is that time required for runoff to travel from the most remote point in the drainage area to the first point of concentration. This can be determined using the Ki pitch equation. The Initial Time of Concentration must be five minutes or longer. In instances where Initial Times of Concentration are estimated to be shorter than five minutes, five minutes shall be applied.

The second part of the Time of Concentration is the Travel Time that takes the flow to travel along the drain. Channel flow occurs in channels carrying integrated flows, pipes (flowing partially full), and streams. Where storage is not significant, Travel Times can be estimated by applying Manning's Equation, and using estimates of channel characteristics and appropriate roughness values for pipe, channel, or stream features as tabulated in **Table-12-1**.

Table 12-1: Storage Coefficients for flat land

Characteristicsofsurface	StorageCoefficient		
	Slope <1: 1000	Slope <1: 500	Slope <1: 500
Residential urban	0.70	0.80	0.90
Commercial	0.80	0.90	1.00
Industrial	0.70	0.80	0.90
Residential Rural nature	0.60	0.70	0.80
Agricultural	0.50	0.60	0.70
Forest/woodland	0.30	0.40	0.50
Aquatic land	0.30	0.40	0.50
Pavedarea/road	0.80	0.90	1.00

Source: Countywide Comprehensive Plan (Master Drainage Plan) Exhibit-VIII

$$V = [1.49/n] [R^{2/3}] [S^{1/2}]$$

Where

V,=,Velocity of flow, feet/second

N,=,Manning's roughness coefficient for channel flow

S,=,Slope, feet/foot

R,=,Hydraulic radius, feet

And

$$T t = V / (60L)$$

Where

T t,=,Travel time, minutes

V,=,Velocity, feet/second

L,=,Length, feet

Storage Coefficient (Cs): Due to very flat topography of Bangladesh, the runoff is significantly slow. The rainfall after evaporation and infiltration accumulates first in the depressions, until these have been reached their capacity and then runoff. To take these effects a storage coefficient is used. The value of the storage coefficient is based on average ground slope and the nature of the ground surface. Some of the storage coefficients are listed in **Table-12-2**.

Table 12-2: Modified Rational Method Runoff Coefficients

Landusedesignation	RunoffCoefficient Cr
Residential rural	0.30
Residential semi urban	0.40
Residential urban	0.50~0.60
Apartment professional	0.70
Neighborhood Commercial	0.85
Community Commercial	0.85
Industrial	0.70~0.75
Slumarea	0.50~0.55
Agricultural exclusive	0.25
Forest and watershed	0.20~0.25
Public facilities	0.3~0.60
Forest/ woodland	0.25
Pavedarea/road	0.99

Source: Countywide Comprehensive Plan (Master Drainage Plan) Exhibit-VIII

Catchment Area:

The size and shape of the catchment or sub-catchment for each drain shall be determined by plan metering topographic maps and by field survey. In determining the total runoff of a catchment area the following assumptions to be made:

- The peak rate of runoff at any point is a direct function of the average rainfall for the time of concentration to that point.
- The recurrence interval of the peak discharge is same as the recurrence interval of the average rainfall intensity.
- The Time of Concentration is the time required for the runoff to become established and flow from the most distant point of the drainage area to the point of discharge.

Projection

In implementing various infrastructures for development, drainage is generally given less priority and is normally considered to be the last or final steps for development. Such scenario is particularly true for Bangladesh; although different types of drainage infrastructures are among others by far the heaviest impact on physical infrastructure network. As a result, physical environment, health, hygiene and standard of living suffer seriously. In development projects, Government, Semi-government and Public sector allocated funds are mostly spent on buildings, roads and other more visible infrastructures and drainage comes as the last item of development. By the time, drainage development begins to start, there appears shortage of fund, consequently as a matter of policy-do little or do-nothing situation appears and as eyewash very little is done for drainage development. In case of urban development, if drainage is not given priority, sufferings of the inhabitants will continuously increase with the passage of time.

Drainage development for urbanization should start with drains. Drains can be classified as Plot drains, Block drains, Tertiary drains, Secondary drains and Primary drains. Other natural drainage

infrastructure is lowland, outfall areas, khals and rivers. Man-made drains are Plot, Block, Tertiary, Secondary and Primary drains and others are natural drainage infrastructures. In planning for drainage network, care will be given on road network in terms of conflict of drainage and waterways with roads. In the following and subsequent sections major element, their principle, purpose and function of drainage infrastructures are discussed and presented in lower to higher order which will be considered as a method for drainage plan.

Plot Drains

Plot drains are provided around a building on a plot. In most cases, the drain is made of bricks and is rectangular in shape that can carry storm water generated in the plot and from the building. Plot drain is connected to the Block or Mohallah drain.




Fig 12-1: A sketch showing plot and block drain

Block Drain

Block drain is provided at the outside of a block that accommodates several buildings of the block. The block drains are made of bricks like plot drains but bigger in size so that it can serve the storm water generated within the block and the buildings and open areas within the block. Sometimes the block drain may serve few neighboring blocks or Mohallahs. Block drains carry storm water coming from the plot drains. Shape of the block drain is also rectangular, bigger than plot drains and its bottom is lower than plot drain. Sketch of the plot drain also shows the block or Mohallah drain under plot drain.

Other Drainage Related Infrastructures

In order to facilitate or mitigate drainage issues some infrastructures are provided or used, these are namely

- i. Bridges, culverts, box culverts
- ii. Drainage sluices, pipe sluices, siphons
- iii. Flood protection embankments and flood walls
- iv. Sluice gates, Regulators, Navigation lock
- v. Flood protection and drainage structures.

i. Bridges, Culverts and Box Culverts

These structures are provided at places wherever roads cross the drainage network system. Such structures are built on the roads to free passage of drainage water and sometimes to provide

navigation/ boat passages. Consequently the conflict between drainage and road networks is mitigated. Figures below show bridge and culverts in such system.




Fig 12-2: Bridge and culvert

ii. Drainage sluices, pipe sluices and siphons

Drainage sluices, pipe sluices and siphons are provided on the embankments. Embankments protect the area from floods coming from outside rivers and make the project area flood free. However storm water from rainfall-runoff within the area causes localized flood, drainage congestion




Fig 12-3: A schematic view of Drainage sluice, pipe sluice and siphon on embankment which relieve drainage congestion.

and submergence. A sketch below shows a few of such structures.

A schematic view of Drainage sluice, pipe sluice and siphon on embankment which relieve drainage congestion.

Primary Drain

Primary drains are also called main drains. Primary drains cover larger storm drainage area than tertiary and secondary drains. Sometimes primary drain bears local name. In ascending order its position is third. Its cross-section is larger than other types; carrying capacity is high and is constructed of brick, cement concrete and sometimes reinforced concrete. Primary drains may be of earthen structure provided sufficient land is available and land value is low. Contributing drainage water comes from tertiary and secondary drains. Primary drains discharge its drainage water to outfall, natural khal, river or large lowland area / Beels.




Fig 12-4: Typical Earthen drain

Secondary Drain

Secondary drains collect discharge from tertiary drains. One secondary drain may receive drainage discharges from several tertiary drains in its course. Size and capacity of secondary drain is much bigger than tertiary drains; its catchment area is much bigger than tertiary drain. Like tertiary drain, it may run parallel to bigger roads. Secondary drains may run along and through the middle of its storm water contributing area.




Fig 12-5: A Typical Secondary Drain

Tertiary Drain

Tertiary drain carry run-off or storm water received from the above mentioned plot drains and block or Mohallah drains. Their catchment area or storm water contributing area is bigger than Mohallah drains. In most Paurashava areas it is difficult to find such naming or classifications. However, such classifications can be seen in references. Tertiary drains generally are the under jurisdiction of Paurashava. Those drains or drainage networks are constructed and maintained directly by the Paurashava.




Fig 12-6: A Typical Tertiary Drain

Reservoirs

Large tanks, ponds, Dighis, lakes, etc. serve as immediate detention areas for storm water. Those structures are man-made and also natural; may be privately owned or government-owned or khas land. These structures function as drainage relief and source of water for emergency use, fisheries, duckeries, environment and nature preservation. For every mouza such reservoir is available. Physical feature survey maps and field survey maps (tank, pond and reservoir) show the existence of reservoirs and database shows their dimensions. Those structures should not be disturbed or removed by physical interventions by fillings or other means rather should be properly maintained and preserved.

Quaternary Drain

Quaternary Drains had to be introduced in this particular project due to the complexity of the existing system. These drains are the smallest parts of a large drainage system. It takes the discharge of a small area to a tertiary drain. These are the smallest drains considering the depth and width.




Fig 12-7: A Typical Quaternary Drain

Other kinds of drainage infrastructure are lowland, outfall areas, khals and rivers. Man made drains are Plot, Block, Tertiary, Secondary and Primary drains and others are natural drainage infrastructures. In planning for drainage network, care should be given for road network in terms of conflict of drainage and waterways with roads. In the following and subsequent sections major element, their principle, purpose and function are discussed and presented in lower to higher order.

Drainage Khals and Waterways

Khals and waterways are natural channels and act as drainage elements. In every mouza more or less such natural channel, khals and waterways carry the excess storm water to the connecting river lying further in the down stream. Sometimes old and silted-up khals are re-excavated to improve drainage efficiency. Most of the natural khals carry the local storm water particularly runoff from the Mouza / Mouzas those it passes through. Khals are narrow and deep in cross-sections; on the other hand waterways are shallow and wider. Physical feature survey maps, field survey maps (river, khal / drainage) show the drainage khals and waterways and their database shows the dimensions.

12.2 Existing Drainage Network

12.2.1 Introduction

For the preparation of Drainage Plan, survey started through field reconnaissance and review of available document related to the study area. The SingraPaurashava and its adjacent area have been visited several times to identify the sources of flooding, existing drainage pattern, flood flow pattern and geographical position of the study area. Field trips have also been carried out to identify the infrastructures, rivers, canals, beels, ponds etc., those required to be surveyed for preparation of maps. It is investigated whether any Drainage Plan has been prepared by any other agency.

12.2.2 Existing Drainage System/Network

The drainage system of the SingraPaurashava has been surveyed and classified into three categories: (i) unlined natural canals and khals acting as primary drains, (ii) beels playing important role in acting as retention ponds and (iii) brick masonry secondary and tertiary drains and earthen shallow secondary drains. The natural primary drains of the SingraPaurashava have emerged as a natural process following the natural slope of the ground, for the flow of storm runoff without human intervention.

Natural Drainage System:

The natural drainage network is composed with 466 water bodies in SingraPaurashava out of which 219 are ponds and 239 are ditches and 04 khals. Total area devoted to water bodies in SingraPaurashava is around 198.73 acres. It can also be seen that the ward 6 possess highest area for water bodies. In this ward there are 13 ponds and 40 ditches but river portion is bigger than any other ward.

There are natural drainage systems along roadside and the linkage between natural and man-made drainage system in somewhere. The existing four khals and two river are covered the entire Paurashava of natural drainage system and act as primary drain.

Table 12-3: List of Existing Natural Canals/Khals& River of Singra Paurashava

SI	Kha	Name	Area(acres)	Length(m)	Mouza
1		Charpatka	3.94	764.042	Boro Sawail_387_01
2		Domdoma Khal	22.20	3450.05	Uttar Domdoma_336_00
3			8.00	485.49	Dakhin Domdoma_276_00
4			7.50	330.67	Singra_342_00
Total			41.64	5030.252	
1.		Atrai	158.137	7445.31	Partial-Uttar Domdoma_336_00, Porbo Masinda_335_00, Singra_342_00,, Hat Singra_339_00, Baluvora_373_00, Par Singra_340_00, Chak Singra_344_00, Sola Kuri_345_00, Katua Bari_370_00,, Niagain_333_02
2.		Gurnai	37.59	3005.99	Partial- Niagain_333_01, Baluvora_373_00, Patkol_372_00, Boro Sawail_387_01

Source: Physical Feature Survey, 2010.

There are linkages between natural and man-made drainage system. But how much effective and active the linkage is with the poorly maintained man-made drains is a question. Almost half of the depth of the man-made drain is filled with solid garbage's; as a result, the channel is not properly functioning.

Man-made Drains

The following table shows the ward-wise drainage coverage and type on the basis of construction pattern in SingraPaurashava. From the table it is seen there exists Pucca and Katcha drains in SingraPaurashava. The table also indicates that there is limited amount of drainage in SingraPaurashava. In this Paurashava there is 5.62 km drain. Uncovered drains are mostly in existence with poor condition. Detail statistics of existing man-made drainage network is shown in the **Table-12-4**.

Table 12-4: Ward-Wise drainage Network of Singra Paurashava

Ward No	Length(km)		
	Pucca		Status
	Area(Acres)	%	
1	0.54	12.79	Uncovered
2	0.00	0.00	Uncovered
3	0.80	18.98	Uncovered
4	0.39	9.36	Uncovered
5	0.67	15.86	Uncovered
6	0.22	5.12	Uncovered
7	0.25	6.00	Uncovered
8	1.13	26.90	Uncovered
9	0.21	5.00	Uncovered
10	0.00	0.00	Uncovered
11	0.00	0.00	Uncovered
12	0.00	0.00	Uncovered
Total	4.20	100.00	Uncovered

Source: Drainage and Environmental Survey in SingraPaurashava, 2010

In Singra there are no mentionable long drains with designated outfall. Only the following five drains can be considered as large drain compared to other drains (**Table 12-5**).

Table 12-5: Location, start and end of some drains in Singra Paurashava

SI No	Location	Type	Ward No	Length (m)	Width (m)	Start	End (Outfall)
1	Along Natore-Bogra Road	Pucca	4	372.46	0.4	Along Natore-BograRoad	Pond
2	Along Upazilla Parisad Road	Pucca	8	406.67	0.5	HamidialslamiaJame Mosque	River

3	TNT Office Road	Pucca	3	281.21	0.4	Pilot School & College	Khal
4	TNT Office Road	Pucca	1	124.73	0.6	TNT Office Road	Pond

Source: Drainage and Environmental Survey in Singra Paurashava, 2010

The drains so far constructed in Singra Paurashava are listed in Table-12-6 below. These drains are constructed by the Paurashava and the DPHE. The DPHE after construction handed over its drains to Paurashava for maintenance. Within the Paurashava total 4.20 km brick drains so far constructed.

Table 12-6: List of Existing Drains in Singra Paurashava

SI No.	Type	Length(m)	Width
ID-1	Tertiary Drain (Brick Drain)	0.099	0.20
ID-2	Tertiary Drain (Brick Drain)	0.111	0.20
ID-3	Tertiary Drain (Brick Drain)	0.169	0.40
ID-4	Tertiary Drain (Brick Drain)	0.013	0.20
ID-5	Tertiary Drain (Brick Drain)	0.023	0.20
ID-6	Tertiary Drain (Brick Drain)	0.064	0.40
ID-7	Tertiary Drain (Brick Drain)	0.090	0.40
ID-8	Tertiary Drain (Brick Drain)	0.035	0.40
ID-9	Tertiary Drain (Brick Drain)	0.024	0.20
ID-10	Tertiary Drain (Brick Drain)	0.057	0.20
ID-11	Tertiary Drain (Brick Drain)	0.046	0.20
ID-12	Tertiary Drain (Brick Drain)	0.060	0.20
ID-13	Tertiary Drain (Brick Drain)	0.159	0.50
ID-14	Tertiary Drain (Brick Drain)	0.407	0.50
ID-15	Tertiary Drain (Brick Drain)	0.021	0.20
ID-16	Tertiary Drain (Brick Drain)	0.089	0.50
ID-17	Tertiary Drain (Brick Drain)	0.068	0.50
ID-18	Tertiary Drain (Brick Drain)	0.054	0.50
ID-19	Tertiary Drain (Brick Drain)	0.158	0.60
ID-20	Tertiary Drain (Brick Drain)	0.125	0.60
ID-21	Tertiary Drain (Brick Drain)	0.043	0.40
ID-22	Tertiary Drain (Brick Drain)	0.115	0.20
ID-23	Tertiary Drain (Brick Drain)	0.139	0.20
ID-24	Tertiary Drain (Brick Drain)	0.080	0.30
ID-25	Tertiary Drain (Brick Drain)	0.128	0.20
ID-26	Tertiary Drain (Brick Drain)	0.372	0.40
ID-27	Tertiary Drain (Brick Drain)	0.037	0.20
ID-28	Tertiary Drain (Brick Drain)	0.281	0.40
ID-29	Tertiary Drain (Brick Drain)	0.158	0.20
ID-30	Tertiary Drain (Brick Drain)	0.053	0.20
ID-31	Tertiary Drain (Brick Drain)	0.063	0.20
ID-32	Tertiary Drain (Brick Drain)	0.205	0.40
ID-33	Tertiary Drain (Brick Drain)	0.112	0.20
ID-34	Tertiary Drain (Brick Drain)	0.040	0.40

SI No.	Type	Length(m)	Width
ID-35	Tertiary Drain (Brick Drain)	0.063	0.20
ID-36	Tertiary Drain (Brick Drain)	0.129	0.50
ID-37	Tertiary Drain (Brick Drain)	0.053	0.40
ID-38	Tertiary Drain (Brick Drain)	0.052	0.40
ID-39	Tertiary Drain (Brick Drain)	0.103	0.20
ID-40	Tertiary Drain (Brick Drain)	0.103	0.20
ID-1	Tertiary Drain (Brick Drain)	0.099	0.20
ID-2	Tertiary Drain (Brick Drain)	0.111	0.20
ID-3	Tertiary Drain (Brick Drain)	0.169	0.40
ID-4	Tertiary Drain (Brick Drain)	0.013	0.20
ID-5	Tertiary Drain (Brick Drain)	0.023	0.20
ID-6	Tertiary Drain (Brick Drain)	0.064	0.40
ID-7	Tertiary Drain (Brick Drain)	0.090	0.40
ID-8	Tertiary Drain (Brick Drain)	0.035	0.40
ID-9	Tertiary Drain (Brick Drain)	0.024	0.20
ID-10	Tertiary Drain (Brick Drain)	0.057	0.20
ID-11	Tertiary Drain (Brick Drain)	0.046	0.20
ID-12	Tertiary Drain (Brick Drain)	0.060	0.20
ID-13	Tertiary Drain (Brick Drain)	0.159	0.50
ID-14	Tertiary Drain (Brick Drain)	0.407	0.50
ID-15	Tertiary Drain (Brick Drain)	0.021	0.20
ID-16	Tertiary Drain (Brick Drain)	0.089	0.50

Source: Drainage and Environmental Survey in Singra Paurashava, 2010

12.2.3 Analysis on land level (Topography)

Land Levels/Spot Levels

The Total Station (TS) based surveys were conducted for measuring the spot levels/land levels of the project area (Northing, Easting, Elevation or RL). Later on these spot levels were used for generating the contour of the project area. In general the spot levels on the land were taken approximately at 35 meter intervals.

Maximum level of SingraPaurashava is 18.01m located at ward no 8 and lowest point is recorded as 5.12m located at ward no 6. Average elevation of Singra Paurashava area is derived as 10.76m.

Details statistical summary of land levels survey are shown in **Table 12-7** and **Table 12-8** below.

Table 12-7: Summary of Spot Level Data of Singra Paurashava

Total Spot Level Points	8171
Highest Elevation	18.01m
Lowest Elevation	5.12m
Mean	10.76m
Standard Deviation	1.69

Source: Topographic Survey in SingraPaurashava, 2010

Table 12-8: Characteristics of Land Levels of Singra Paurashava

Ward No	Land Level Characteristics
Ward no 01	High
Ward no 02	Low
Ward no 03	Medium
Ward no 04	Medium
Ward no 05	High
Ward no 06	Low
Ward no 07	Medium
Ward no 08	High
Ward no 09	Medium
Ward no 10	Medium
Ward no 11	Low
Ward no 12	Medium

Source: Derived from Topographic Survey Data of SingraPaurashava, 2010

General Contour Descriptions

SingraPaurashava is situated in a medium land area. More interpretation can be derived from a Surface Analysis. In the following there are two maps. The first **Map 12-1** shows the contour description and **Map 12-2** surface analysis of SingraPaurashava. From Surface Analysis, it can be found that the middle part of the Paurashava is comparatively higher than other areas. The middle part comprises of parts of ward 1,5 and 8. From the surface analysis map it is found that ward 6 and 11 is much lower compared to other wards. From the surface analysis map we deduce the following table.

Table 12-9: Land Use Category with Spot Heights (mPWD) in Singra Paurashava

Land use	Max	Min	Mean
Agriculture	18.006	6.137	10.445
Circulation Network	15.622	6.470	12.393
Commercial Activity	14.488	11.322	13.316
Community Service	14.296	7.860	12.585
Education and Research	14.071	7.788	12.078
Governmental Services	13.598	11.701	12.869
Industrial/Processing & Manufacturing	14.327	10.928	12.733
Miscellaneous	13.567	12.312	13.120
Mixed Use	14.613	13.577	13.968
Residential	14.825	5.869	11.997
Service Activity	10.635	10.635	10.635
Transport and Communication	14.420	12.429	13.248
Urban Green Space	13.643	10.863	12.503
Waterbody	16.268	5.122	10.875

Source: Topographic Survey in SingraPaurashava, 2010

Map 12-1: Contour Map of Singra Paurashava

Map 12-2: Surface Analysis (IDW Method) of Singra Paurashava

12.2.4 Analysis of peak runoff and identification of drainage outfalls

The size and shape of the catchments or sub-catchments for each drain shall be determined by planimeter from topographic maps and by field survey. In determining the total runoff of a catchment area the following assumptions to be made:

- The peak rate of runoff at any point is a direct function of the average rainfall intensity for the Time of Concentration to that point.
- The recurrence interval of the peak discharge is same as the recurrence interval of the average rainfall intensity.
- The Time of Concentration is the time required for the runoff to become established and flow from the most distant point of the drainage area to the point of discharge.

Regarding runoff discharge it has been observed that there are 8 numbers of khals passing through the SingraPaurashava. Those are the only natural drainage channels which receives part of the runoff volume from part of the town.

It has been observed from the drainage network survey that 4.20 km brick masonry drains have been constructed by the Paurashava and the DPHE during last few years. Some of the drains are working properly but most of them are temporarily connected to ditches or discharging to paddy field. These drains have been constructed in an unplanned way and without considering proper outfalls. The drains are constructed as piece meal, no proper size and gradient has been maintained. As a result, with the expansion of township some of them already have to abandon. The common run-off coefficients of different types of areas are listed in **Table 12-10** below.

Table 12-10: Common Run – off coefficients for Different Types of Area

Type of Drainage Area		Run-off Coefficient: C
Business	Downtown areas	0.70 – 0.95
	Neighborhood area	0.50 – 0.70
Residential	Single – family areas	0.30 – 0.50
	Multi – units, detached	0.40 – 0.60
	Multi – units, attached	0.60 – 0.75
	Suburban	0.25 – 0.40
	Apartment dwelling areas	0.50 – 0.70
Industrial	Light areas	0.50 – 0.80
	Heavy areas	0.60 – 0.90
	Parks, cemeteries, playgrounds	0.10 – 0.35
	Rail road yard areas	0.20 – 0.40
	Unimproved areas	0.10 – 0.30
	Streets; Driveways and roofs	0.10 – 0.95
Lawns	Sandy soil, flat, 2%	0.05 – 0.10
	Sandy soil, avg, 2 – 7%	0.10 – 0.15
	Sandy soil, steep, 7%	0.15 – 0.20
	Heavy soil, flat, 2%	0.13 – 0.17
	Heavy soil, avg, 2 – 7%	0.18 – 0.22
	Heavy soil, steep, 7%	0.25 – 0.35

Source: Handbook of Hydrology, by - David R. Maidment

12.3 Plans for Drainage Management and Flood Control

12.3.1 Plan for Drain Network Development

Sustainable drainage network system, an alternative to conventional drainage is introduced to mimic natural drainage, with the aim of reducing flooding and improving the quality of water draining from urban surfaces (runoff). A comprehensive drainage network is developed leaving the existing beels and khals to remain their natural form. To solve the overall drainage problem of the SingraPaurashava a Drainage Plan has to prepare as integral part of Paurashava Master Plan. During preparation of land use plan special emphasis to be given to retain the existing water bodies. Special attention to be given to protect the khash lands of khals and beel from illegal encroachment and no circumstances it shall be allowed to change their nature. As part of the Drainage Plan the Paurashava to be divided into several drainage zones. Runoff from each drainage zones shall reach to the primary drains. The existing tertiary drains those will match with the proposed network will be rehabilitated, those not have to abandon.

12.3.1.1 Drain Network Plan

The activity for the relevant authority will be assisted by the preparation of the drainage master plan for the Paurashava which details the necessary corridors, plot sizes and generalized locations for:

- Primary canal / khal (new and improved).
- Secondary and tertiary canal / khal (new and improved).
- Storage ponds.
- Silt traps.
- River embankment.

Initially, the Paurashava will encourage implementation of the first phase recommendation of the drainage master plan. A brief summary of the proposals to be undertaken in Phase-1 is given below. Reference should be made to the Map for identification of the drainage areas referred in the text.

Phase-1 (Storm water drainage)

- Local improvements and the removal of obstacles from existing canals in drainage areas .
Works to include:
 - Redesign of hydraulically inefficient bends, entrances and exists.
 - Rising and / or widening of bridges and culverts to give unobstructed flows.
 - Returning the channels to a uniform cross-section by removal of encroaching properties and structures.
 - Raising crossings over roadside channels to adjacent properties above the flood level of the waterway.

Phase-2 (Rain water and household drainage)

- Construction of surface drain linked with the residences, may be covered or uncovered.
- Provide linkages with secondary and tertiary drains.
- Out-fall of such drains may be nearby canals and low-lands.
- For discharging of rainwater from commercial areas, covered surface drain may be constructed and they will be linked with the secondary and tertiary canals.

12.3.1.2 Proposal for Improvement of the Existing Drainage Networks

There is 4.20 km existing main khals in Singra Paurashava. This total 04 khals will be served as primary drain. Based on this primary drain drainage network system of Singra Paurashava will be established. Total 3.31 km primary drain, 8.91 km secondary drain and 14.52 km tertiary drain proposed in drainage development plan. Map 12.3 shows the drainage network Plan of Singra Paurashava. Table 12.11 shows the summary of proposed drainage facilities at Singra Paurashava. And Map 12.3 shows the drainage network proposal for Singra Paurashava. In addition, the Atrai flowing through the northern border of Singra Paurashava will serve as the main out fall and main natural drainage network.

The details of improvement of identified existing drains are shown in **Table 12-11**.

Table 12-11: List of Drains for Proposed Improvement

Type of Drain	Length in Km	%
Primary Drain	3.31	12.38
Secondary Drain	8.91	33.32
Tertiary Drain	14.52	54.30
Total	26.74	100.00

Source: Drainage and Environmental Survey in Singra Paurashava, 2010

Drainage corridors: If a drainage network has to be installed, the drainage originating throughout the Paurashava would be carried by means of surface drains and culverts. These should be accommodated within road reserves.

General location required: For sewerage treatment plant, large plot will be needed, preferably on outskirts of the Paurashava. For sewerage pumping station, small plots throughout the Paurashava will be needed and a system should be introduced.

Maintaining of land slope: Important component of the drainage network is land slope, which was not maintained during the construction of existing drains. The slope of the Paurashava is found towards east and southeast. Slope of all drains should maintain this direction.

12.3.1.3 List of Proposed New Drains

For effective functioning of existing drainage network, some new drains have been proposed in the project area which is listed in **Table 12-12**. The list has been prepared based on analysis of topographic map, existing drainage network, field visits and consultation with the Paurashava officials and local people. So the detail drainage master plan should get prior consideration while implementing this plan.

The proposed drains along with existing drains and other drainage infrastructures are shown in **Map 12-3**.

Table 12-12: Proposal of New Drains

ID	Type	Length(m)	Top Width(m)	Bottom Width(m)	Design Depth(m)	Outfall	WARD	Remarks
PD-1	Primary Drain	372.469	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
PD-1	Primary Drain	992.623	0.80	0.40	1.2	River	Ward No. 04	Covered Drain
PD-1	Primary Drain	473.438	0.80	0.40	1.2	River	Ward No. 03	Covered Drain
PD-2	Primary Drain	354.829	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
PD-2	Primary Drain	2.889	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
PD-3	Primary Drain	384.355	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
PD-3	Primary Drain	2.908	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
PD-3	Primary Drain	727.756	0.80	0.40	1.2	River	Ward No. 04	Covered Drain
SD-10	Secondary Drain	70.704	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
SD-10	Secondary Drain	367.053	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
SD-11	Secondary Drain	212.989	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
SD-12	Secondary Drain	381.596	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
SD-12	Secondary Drain	5.562	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
SD-13	Secondary Drain	286.697	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
SD-13	Secondary Drain	126.879	0.80	0.40	1.2	River	Ward No. 05	Covered Drain
SD-13	Secondary Drain	374.274	0.80	0.40	1.2	River	Ward No. 04	Covered Drain
SD-14	Secondary Drain	711.120	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
SD-14	Secondary Drain	455.921	0.80	0.40	1.2	River	Ward No. 03	Covered Drain
SD-14	Secondary Drain	180.158	0.80	0.40	1.2	River	Ward No. 02	Covered Drain
SD-2	Secondary Drain	303.611	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
SD-2	Secondary Drain	118.509	0.80	0.40	1.2	River	Ward No. 05	Covered Drain
SD-3	Secondary Drain	23.073	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
SD-3	Secondary Drain	13.121	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
SD-4	Secondary Drain	167.457	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
SD-5	Secondary Drain	376.428	0.80	0.40	1.2	Khal	Ward No. 05	Covered Drain
SD-5	Secondary Drain	444.514	0.80	0.40	1.2	Khal	Ward No. 04	Covered Drain
SD-5	Secondary Drain	5.942	0.80	0.40	1.2	Khal	Ward No. 01	Covered Drain
SD-50	Tertiary Drain	689.579	0.80	0.40	1.2	River	Ward No. 04	Covered Drain
SD-6	Secondary Drain	318.038	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
SD-6	Secondary Drain	323.500	0.80	0.40	1.2	River	Ward No. 05	Covered Drain
SD-6	Secondary Drain	218.561	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
SD-7	Secondary Drain	44.644	0.80	0.40	1.2	Khal	Ward No. 04	Covered Drain
SD-7	Secondary Drain	1251.62	0.80	0.40	1.2	Khal	Ward No. 03	Covered Drain
SD-7	Secondary Drain	5.397	0.80	0.40	1.2	Khal	Ward No. 02	Covered Drain
SD-8	Secondary Drain	325.164	0.80	0.40	1.2	River	Ward No. 04	Covered Drain
SD-8	Secondary Drain	670.061	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
SD-9	Secondary Drain	1098.62	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
SD-9	Secondary Drain	36.323	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
SD-9	Tertiary Drain	364.269	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
TD-1	Tertiary Drain	352.038	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
TD-1	Tertiary Drain	10.298	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-10	Tertiary Drain	242.934	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-10	Tertiary Drain	2.729	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-11	Tertiary Drain	188.304	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-11	Tertiary Drain	5.929	0.80	0.40	1.2	River	Ward No. 06	Covered Drain

ID	Type	Length(m)	Top Width(m)	Bottom Width(m)	Design Depth(m)	Outfall	WARD	Remarks
TD-12	Tertiary Drain	56.923	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
TD-13	Tertiary Drain	353.544	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
TD-14	Tertiary Drain	157.706	0.80	0.40	1.2	River	Ward No. 05	Covered Drain
TD-15	Tertiary Drain	81.249	0.80	0.40	1.2	River	Ward No. 05	Covered Drain
TD-16	Tertiary Drain	166.965	0.80	0.40	1.2	River	Ward No. 05	Covered Drain
TD-18	Tertiary Drain	121.197	0.80	0.40	1.2	River	Ward No. 04	Covered Drain
TD-19	Tertiary Drain	206.604	0.80	0.40	1.2	Khal	Ward No. 04	Covered Drain
TD-19	Tertiary Drain	1.390	0.80	0.40	1.2	Khal	Ward No. 01	Covered Drain
TD-2	Tertiary Drain	493.626	0.80	0.40	1.2	River	Ward No. 08	Covered Drain
TD-2	Tertiary Drain	16.326	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-20	Tertiary Drain	256.700	0.80	0.40	1.2	River	Ward No. 03	Covered Drain
TD-21	Tertiary Drain	325.841	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-21	Tertiary Drain	44.396	0.80	0.40	1.2	River	Ward No. 03	Covered Drain
TD-22	Tertiary Drain	389.427	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-22	Tertiary Drain	36.598	0.80	0.40	1.2	River	Ward No. 03	Covered Drain
TD-23	Tertiary Drain	226.417	0.80	0.40	1.2	River	Ward No. 04	Covered Drain
TD-24	Tertiary Drain	267.666	0.80	0.40	1.2	River	Ward No. 04	Covered Drain
TD-24	Tertiary Drain	56.915	0.80	0.40	1.2	River	Ward No. 03	Covered Drain
TD-25	Tertiary Drain	243.186	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-25	Tertiary Drain	50.153	0.80	0.40	1.2	River	Ward No. 03	Covered Drain
TD-26	Tertiary Drain	230.239	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-27	Tertiary Drain	83.013	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-28	Tertiary Drain	142.013	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-29	Tertiary Drain	174.745	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-3	Tertiary Drain	313.159	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-3	Tertiary Drain	0.506	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-31	Tertiary Drain	270.539	0.80	0.40	1.2	Khal	Ward No. 03	Covered Drain
TD-32	Tertiary Drain	330.352	0.80	0.40	1.2	Khal	Ward No. 03	Covered Drain
TD-33	Tertiary Drain	205.428	0.80	0.40	1.2	River	Ward No. 03	Covered Drain
TD-34	Tertiary Drain	291.719	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-35	Tertiary Drain	74.625	0.80	0.40	1.2	River	Ward No. 01	Covered Drain
TD-36	Tertiary Drain	413.080	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-36	Tertiary Drain	395.581	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-37	Tertiary Drain	299.487	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-38	Tertiary Drain	251.678	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-4	Tertiary Drain	80.533	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-40	Tertiary Drain	456.260	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-41	Tertiary Drain	225.046	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-42	Tertiary Drain	224.865	0.80	0.40	1.2	River	Ward No. 07	Covered Drain
TD-43	Tertiary Drain	367.916	0.80	0.40	1.2	River	Ward No. 07	Covered Drain
TD-44	Tertiary Drain	179.656	0.80	0.40	1.2	River	Ward No. 07	Covered Drain
TD-45	Tertiary Drain	119.192	0.80	0.40	1.2	River	Ward No. 07	Covered Drain
TD-46	Tertiary Drain	332.816	0.80	0.40	1.2	River	Ward No. 07	Covered Drain
TD-47	Tertiary Drain	278.329	0.80	0.40	1.2	River	Ward No. 07	Covered Drain
TD-48	Tertiary Drain	1025.69	0.80	0.40	1.2	River	Ward No. 02	Covered Drain

ID	Type	Length(m)	Top Width(m)	Bottom Width(m)	Design Depth(m)	Outfall	WARD	Remarks
TD-49	Tertiary Drain	739.638	0.80	0.40	1.2	River	Ward No. 02	Covered Drain
TD-5	Tertiary Drain	282.082	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-5	Tertiary Drain	1.427	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-6	Tertiary Drain	448.751	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-6	Tertiary Drain	5.131	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-7	Tertiary Drain	383.041	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-7	Tertiary Drain	5.324	0.80	0.40	1.2	River	Ward No. 06	Covered Drain
TD-8	Tertiary Drain	274.419	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-9	Tertiary Drain	202.557	0.80	0.40	1.2	River	Ward No. 09	Covered Drain
TD-9	Tertiary Drain	4.165	0.80	0.40	1.2	River	Ward No. 06	Covered Drain

Source: Drainage and Environmental Management Plan of Singra Paurashava

12.3.1.4 Proposed Drainage Structure

Drainage structures includesculvert, bridge, box culvert etc. In the Drainage and Environmental Management plan,five new bridges have been proposed in the area. The width and length of this bridge is 3.77m and 56.59m.

Map 12-3: Drainage Plan Map of Singra Paurashava

12.4 Plan Implementation Strategies

SingraPaurashava is affected frequently by rainfall run-off due to inability of the existing secondary and tertiary drains to drain out the run-off efficiently. There are inadequate no of secondary and tertiary drains in SingraPaurashava. Presently due to lack of adequate no of secondary and tertiary drains, most of the areas of the Paurashava are subjected to water logging during the intensive rainfall in the monsoon period. The existing secondary and tertiary drains may be improved and its different component needs to link with an overall integrated system. The existing borrow pit along the highway, secondary and tertiary drains are observed to suffer from continued negligence in respect of maintenance, clearing, removal of blocking etc.

The existing borrow pit/ drains will be incorporated into the proposed system to the extent to achieve available drainage system for the Paurashava. The drainage management plan of the Paurashava has been prepared for the peak monsoon period when the drainage system stands critical and drainage problem develops due to blocking, inadequate section of the khals and obstruction in the drainage path. Therefore, adequate numbers of new secondary and tertiary drains have to be constructed, following a systemic drainage network.

12.4.1 Regulations to implement the Drainage and Flood Plan

In preparing drainage management plan, the flowing design approach has been presented in this report. In the design approach, the Consultants have considered the practical aspects of desired results, cost efficiency, durability including ease of construction and maintenance. Visible social improvements for the urban population are considered to be the most important and mitigation of the annual flooding damage is considered to be the greatest tangible benefit. Reduction of diseases, infant Mortality and increase of life span are considered to be the greatest intangible benefits.

In line with these considerations, the following broad approach has been adopted in preparing the drainage management plan for SingraPaurashava.

Channel Improvement

Canal and channel improvement means the improvement and re-excavation of existing open channels. The existing all Khals need excavation and removal of all illegal structure along the path.

Land Acquisition

New land acquisition has to be kept to as absolute minimum due to the high cost and time required for acquisition. New land acquisition is negligible as most of the proposed drains passes through land owned by Paurashava or Khas land.

Storing and Detention Ponds

Existing borrow pits, ponds, low pockets within the urban areas and agricultural low lands within the fringe area, all ac as retention ponds and all these serve to delay the peak floods during heavy storms. The retention areas also recharge the aquifer water level. In the absence of internal storage areas within the Paurashava area, the existing ponds (≥ 0.25 acre) , proposed retention area, low pockets etc. continue to serve as reservoir in the coming years and the Paurashava should endeavor to remain these low lands in the future.

Drainage System Capacity

The drainage systems (tertiary and secondary drain) has been designed to handle the average runoff for 1.1 year recurrence interval for tertiary drain and 2 years recurrence interval for secondary drain from peak storms without overflowing considering the estimated development level as up to the year 2031. This means that fully built-up areas will be designed for the present situation, while areas, which are not fully built-up, will have excess capacity to handle rainfall of greater intensity during the developing period.

Drainage Channel Sections

The drainage system has been designed to handle the average annual run-off from peak storms with 100mm freeboard for tertiary drain and 150mm freeboard for secondary drain overtopping.

Three standard open channel sections are proposed to be used for the works, as shown in the following table. The rectangular pucca Type-1 drain is suitable for collection of run-off from medium size catchments areas and is proposed to be used for tertiary roadside drains and secondary drains in congested areas. Type-1 drain may be constructed from brick or reinforced concrete, as most appropriate and economical one.

The trapezoidal section of drain Type-2 and 3 are suitable for collection of run-off from medium and large catchments areas, and are to be used for secondary and primary drains in unconstructed areas. Drain Type- 2 is proposed to be pucca drain using nominal reinforced concrete with cement plaster surface to improve its flow characteristics and durability, add to reduce the long term costs of cleaning and maintenance. Drain Type-1 is also proposed to be a pucca drain using brick work lining, but may initially be constructed as an earthen (Katcha) drain suitable for future upgrading depending on the availability of land, flow requirements and cost. The bottoms of drains Type-2 and 3 are to be redesigned with a transverse slope of 1:8 (V: H) to keep the flow velocity as high as possible during the dry season.

Construction criteria and locations to be used are shown in the following **Table 12-13**.

Table 12-13: List of Construction Criteria and Locations

Sl. #	Type of Drain	Construction Criteria	Locations to be Used
1.	Type- 1	Lined, Brick work	Tertiary and secondary improvement on the existing drains
2.	Type- 2	Lined, Brick	Secondary and primary drains
3.	Type- 3	Lined, Katcha Drain	Primary katcha drains

Trash Rack and Sumps

Trash racks and sumps are normally used to prevent debris (silt/ solid wastes) from entering into the drainage systems where major problems could occur as a result of debris accumulation. Trash racks and sumps are considered appropriate for the Paurashava situation. In the drainage management plan, locations for trash racks and sumps along the major road network will identify during preparation of final plan.

Preventive Maintenance Program

For the proper functioning of the drainage system, it is essential to have an appropriate maintenance program. The program must include inspection, enforcement, cleaning and repair. The frequency of inspection and cleaning will be dependent on the season of the year with more frequent inspection and cleaning at the start of the rainy season and on the importance of the drain. The maintenance programs are:

a) Inspection

- Open pucca drains - monthly in general; weekly in market areas
- Covered pucca drains - monthly with drains opened in February
- Kutcha drains - monthly
- All drains - following first heavy rainfall in year

b) Cleaning

- Open pucca drains - as required
- Covered pucca drains - in February when opened
- Kutcha drains and culverts - January to February prior to rains
- All drains - as revealed by inspection

The inspections will also show where repairs are required and where encroachment into the drain and deliberate blocking of the drain is taking place. Appropriate action to enforce the regulations must be initiated immediately. The cleaning of permanently closed pucca drains and small culverts is difficult and time consuming. New drains should have removable covers to facilitate cleaning.

Responsibility of development and construction of khal/drains rests with Engineering Department. Whereas, the responsibility of cleaning and conservancy of drains falls under the conservancy section under health department. Operation and maintenance of drains of the Paurashava involve the set vices in the following areas.

- Conservancy (Cleaning of drains)
- Mosquito killing
- Solid waste management
- Structural maintenance of drains

It is essential that the Paurashava should develop a routine preventive maintenance program for the drainage system. The structural improvements to be taken up under the project will provide a sustainable benefit. A failure to develop the capacity and methods related to preventative maintenance program will entirely eliminate the benefits of the program in the long run.

Though the needs and methods must ultimately be identified by the personnel responsible for the maintenance, it is suggested that the following guidelines should be followed for initial development of the staffing and equipment for a preventive maintenance program:

- drain should be cleaned once per month, but not less frequently than once per three months;
- task objective for 1 cleaner/sweeper should be 50m of primary / secondary drains, per day;
- supervisors should be provided at the rate of 1 Jamader for each 10 sweepers, and 1 sanitary inspector for each 4 Jamaders;

- adequate equipment should be provided for efficient operations of cleaning crews, including wheel barrows and miscellaneous hand tools for each drain cleaner, 3 ton dump truck for waste transport and disposal.

Based on this, standard drain cleaning crews consisting of 51 cleaners, 5 Jamaders and 2 sanitary inspectors will be adequate to carry out the routine preventive maintenance operation required to keep the system in good operating condition.

12.4.2 Implementation, Monitoring, Evaluation & Coordination of the Plan

In some specific area of SingraPaurashava, there are some scattered low-lying areas which are subjected to water-logging during and after heavy rainfall in a year between July and August normally for 30-40 days. The depth of stagnant water varies between 0.25 m to 0.35m and usually lasts for 4.00 to 6.00 hours. The water—logging situation is likely to further aggravate in the years to come with increasing urbanization. The primary causes of this water-logging are as follows:

- Lack of cleaning and maintenance of the khals/drains
- Unplanned and under designed existing drainage system
- Obstruction and encroachments in the khals/ drains
- Lack of construction and integration of tertiary, secondary drains and primary khals
- Due to non-existence of drains in different places.

In order to address the above mentioned problem the following proposals have been made in the drainage master plan:

- The proposed drainage system for SingraPaurashava has been planned with a view to discharges most, of the storm run-off in the Baniazal Khal and Binuzal Khals by gravity flow and no pumping is necessary.
- Under the provision of proposed drainage master plan, major khals constitute the storm water run-off delivery system and have been defined as the primary khals. Timely undertaking of the drainage master plan including study is considered a timely venture to know the drainage issues within SingraPaurashava and to formulate and investment project to reduce sufferings of the Paurashava residents.
- The proposed drainage management plan is justified technically, economically and socially. The priority program is recommended for implementation considering the present serious drainage problems faced by the Paurashava residents. The project after implementation will mitigate the major drainage problems in the core and semi-core area where the density of population varies from high to medium.
- The proposed drainage master plan is likely to be co-coordinated with other utility providing organizations to avoid over-lapping and duplication. As such, very close co-ordination with DPHE, BWDB and other utility organizations should be maintained during the project implementation so that, disruption does not take place in utility services.
- It is recommended that cost of the first phase of the project priority program is funded as grant financing to Paurashava by ADB because the Paurashava is not in a position to implement this project from their own resources.
- The revenue collection of SingraPaurashava is moderate. The SingraPaurashava authority' is unable to make assessment of tax timely. SingraPaurashava shall have to improve significantly in revenue collection and the efficient financial management so that

the SingraPaurashava can properly maintain the drainage system including the control of environmental sanitation.

- Financial sustainability is possible by increasing revenue collection efficiency with activities like more arrear collection & re-assessment of taxes in regular intervals. Re-assessment in every 5 years is recommended. Re-assessment process should commence sufficiently in advance so that appeal process could be completed prior to the effective date. Distress warrants against big-defaulters both in terms of amount due and years overdue may be executed in order to achieve good Governance & financial sustainability.

B. Environmental Management Plan

12.5 Introduction

Improvement of the environmental system has been identified as one of the highest priority needs of the Paurashava authority as well as the resident. This is an essential part for the future development of the urban areas. The main objectives of the environmental study are to assess the existing environmental condition in the SingraPaurashava and to identify the future requirements of the control over environmentally critical and vulnerable areas and living things.

12.5.1 Goals and Objectives

Following are the overall objectives of environmental management plan:

- To create a sustainable living environment.
- To create awareness among citizens about livable environment.

12.5.2 Methodology and Approach to Planning

The environmental management plan consists of the Supplementary Living Environment Survey, the Comprehensive Ecological Survey and the Water Quality Survey. The Supplementary Living Environment includes water supply, land pollution, sewerage and sanitation, solid waste management, and resettlement of population due to construction of canals and primary drains. The Comprehensive Ecological Survey aims at facilitating comprehensive environmental assessment by subsequent urbanization and implementation of the drainage on the ecological elements of fauna and flora, agricultural and aqua cultural resources etc. The Water Quality Survey is the sampling and analysis of surface water from rivers, natural canals, ponds etc., and from ground water. These are required to be done to ensure necessary urban environment enhancement measures. Moreover, an overall evaluation of environmental condition due to urbanization with flood management and drainage is required in order to justify the necessity of the Drainage Plan. In planning process special attention required to reduce the insect breeding areas, and preserve and management of natural drainage area.

12.6 Existing Environmental Condition

12.6.1 Introduction

The urban environment of the SingraPaurashava includes both build and natural environment. Build environment includes waste management, water, air quality, energy usage, transport network, slum improvement, and disaster mitigation. The urbanization where the build environment overburdens the natural environment cannot be sustainable. But urbanization is vital for countries economic growth. Urban centers concentrate services, infrastructure, labor, knowledge, entrepreneurship and markets.

So in every phase of planning processes all these environmental issues will be evaluated and proper measure will be taken to minimize the adverse environmental impacts on land pollution, water and air quality, biodiversity resources and marine resources by energy usage, transport network, waste management, slum improvement, disaster mitigation etc.

12.6.2 Geo-morphology


Geological condition

It is known from the agricultural officer of Singra Upazila that there are several types of soils in this area. According to agricultural office at Singra there is 2/3 of the soil is loomy soil. Besides, doash and sandy soil are also found there.

Morphological condition

Temperature


Temperature is a measurement of the average kinetic energy of the molecules in an object or system and can be measured with a thermometer or a calorimeter. It is a means of determining the internal energy contained within the system. The following figure shows the temperature characteristics of last 10 years in SingraPaurashava. From the figure it is seen that maximum temperature has an increasing trend over the years.



Source: Based on Data from Bangladesh Meteorological Department, Dhaka, 2009

Fig 12-8: Temperature characteristics of last 10 years in Singra Paurashava

The following figure shows the Normal Maximum and Minimum Temperature Characteristics across the year in SingraPaurashava. From the figure it is seen that there exist maximum temperature in the month of April. It is also observed that in the mid-year (from April to October) the temperature is higher compared to other section of the year.




Source: Based on Data from Bangladesh Meteorological Department, Dhaka, 2009

Fig 12-9: Normal Maximum and Minimum Temperature Characteristics across the year in SingraPaurashava

Rainfall


Rainfall is the amount of precipitation of any type, primarily liquid. It is usually the amount that is measured by a rain gauge. The following figure shows the Average Rainfall Characteristics across the year in SingraPaurashava. From the figure it is seen that the highest rainfall occurs mainly in the month of June, July and August.



Source: Based on Data from Bangladesh Meteorological Department, Dhaka, 2009

Fig 12-10: Average Rainfall Characteristics across the year in SingraPaurashava

The following figure shows the rainfall characteristics of last 10 years in SingraPaurashava. From the figure it is seen that maximum rainfall has an increasing trend over the years and it becomes highest in the year 2007.




Source: Based on Data from Bangladesh Meteorological Department, Dhaka, 2009

Fig 12-11: Rainfall Characteristics for last 10 years in Singra Paurashava

Humidity

The following figure shows the humidity characteristics of last 10 years in SingraPaurashava. From the figure it is seen that there is no much change in humidity in Singra over the years.



Source: Based on Data from Bangladesh Meteorological Department, Dhaka, 2009

Fig 12-12: Humidity characteristics of last 10 years in SingraPaurashava

12.6.3 Solid Waste and Garbage disposal

The solid waste and garbage disposal of SingraPaurashava includes house hold waste, industrial waste, kitchen market waste, clinic/hospital waste, latrine waste, brickfield waste and fertilizer/chemical related waste.

The production of solid waste in SingraPaurashava per person per day is around 250gm and the total Paurashava production is 8.29 ton/day. The household waste is thrown by the people to roadside drains or open spaces adjacent to their houses. The garbage from kitchen market and untreated hospital waste from UHC disposed to open space by the side of the road, drain or ditch and polluting living environment which is a great threat to human health.

12.6.4 Waste Management System

Singra Paurashava is lacking for sewerage system and people are used to dispose household sewer to the surface drains and or surface water bodies. This Paurashava does not possess good solid waste management system. Only there are three vehicle and 6 vans for solid waste disposal although those are not properly functioning. There are 7 sweepers for solid waste collection. In Singra Paurashava, there are 10 permanent and 17 temporary dustbins located which are designated site for solid waste dumping. The Paurashava does collect waste from bazaar and from dustbin. Only roadside waste are collected and these wastes are thrown generally at various holes and borrow pits. When generally holes and borrow pits created due to earthwork for road construction then these holes and borrow pits are used for the solid waste dumping. Inadequate maintenance of human, domestic and market wastes, open and poor drainage system, water logging etc. create serious environmental degradation within the Paurashava area.

12.6.5 Pollutions

12.6.5.1 Water

Water pollution is the presence of pollutants, particles or contaminants in water beyond the level which is desirable for drinking. Saltwater encroachment associated with over drafting of aquifers or natural leaching deposits are natural sources of groundwater pollution. Most concern over groundwater contamination has centered on pollution associated with human activities. Human groundwater contamination can be related to waste disposal (private sewage disposal systems, land disposal of solid waste, municipal wastewater, wastewater impoundments, land spreading of sludge, brine disposal from the petroleum industry, mine wastes, deep-well disposal of liquid wastes, animal feedlot wastes, and radioactive wastes).

In SingraPaurashava there is no significant level of ground water pollution. Here both groundwater and surface water are free from significant pollutant. One of the main reasons behind this is the absence of industrial effluents in this area and the presence of Atrai River. Besides the generation of solid waste and municipal waste water is not a huge amount. It can be mentioned that several years ago a very little amount of arsenic was identified in ground water although which falls under acceptable level.

12.6.5.2 Air

Air pollution is the introduction of chemicals, particulate matter, or biological materials that cause harm or discomfort to humans or other living organisms, or damages the natural environment into

the atmosphere. An air pollutant is known as a substance in the air that can cause harm to humans and the environment. Pollutants can be in the form of solid particles, liquid droplets, or gases. In addition, they may be natural or manufactured. Sources for air pollution include stationary sources such as smoke stacks of power plants, manufacturing facilities and waste incinerators, as well as furnaces and other types of fuel-burning heating devices, mobile sources such as motor vehicles and other sources such as chemicals, dust and fumes from agricultural and industrial processing.

In SingraPaurashava, some sorts of pollutant are found to be exposed in the air causing air pollution. For instance, emissions from vehicle exhausts of old and poorly maintained buses and trucks, loading, unloading, and carrying of sand and soil without any dust preventive measures are found within the Paurashava. However, the amount of pollution is insignificant and within acceptable level. It can be mentioned that within this Paurashava area there is nobrickfield, which is the vital source of air pollution. According to the Paurashavaauthority, there are 20 Rice mills, 10 flour mills and about 5 ice factory. On the other hand there are 3 oil mills.

12.6.5.3 Sound

Sound pollution is a type of energy pollution in which distracting, irritating, or damaging sounds are freely audible. It is displeasing human, animal or machine-created sound that disrupts the activity or balance of human or animal life. The source of most outdoor sound pollution is mainly construction and transportation systems, including motor vehicle noise, aircraft noise and rail noise. Indoor and outdoor sound pollution sources include car alarms, emergency service sirens, mechanical equipment, fireworks, compressed air horns, grounds keeping equipment, barking dogs, appliances, lighting hum, audio entertainment systems, electric megaphones, and loud people. In SingraPaurashava, the source of sound pollution is found to be little. In this Paurashava there is a little incident of much construction work. The movement of motorized vehicle is also less. So sound pollution in this Paurashava is not significant and disturbing.

12.6.5.4 Arsenic

In Singra Paurashava there is no significant level of ground water pollution. Here both groundwater and surface water are free from significant pollutant. One of the main reasons behind this is the absence of industrial effluents in this area and the presence of Atrai River in this Upazila. Natore Districts are partially belong to Geologic District of Residual Deposits Aquifers located within above Geo-district are safe from Arsenic contamination. According to Bangladesh Geological Survey (2000) in Singra Paurashava there exist $>0.05\text{mg/L}$ which is very much low. It can be mentioned that several years ago a very little amount of arsenic was identified in ground water although which falls under acceptable level. According to DPHE, in Singra several years ago some tube-wells were identified as contaminated with arsenic but at present these tube-wells are removed. So in this Paurashava arsenic contamination is not significant.

12.6.6 Natural Calamities and Localized Hazards

12.6.6.1 Cyclone

In Singra Cyclone is not a regular phenomenon. In fact till now no record is found regarding the occurrence of Cyclone passing through this Paurashava.

12.6.6.2 River Erosion

Being one of the major floodplain areas of the country Singra Town annually experiences riverbank erosion hazard due to sudden and rapid channel shifting. Consequently, valuable cultivable land is lost; also village settlements, markets and towns are destroyed.

In Singra the local channels of the mighty Atrai River have episodically and capriciously wandered across the landscape, eroding their banks, destroying everything in their paths and accreting land elsewhere.

It can be mentioned that the SingraPaurashava, being situated apart from the Atrai River, till not destroyed by the River bank erosion. But if the River bank of the Atrai River continues to erode then within a few years the River will reach at SingraPaurashava destroying the properties in this Paurashava.

12.6.6.3 Flood

SingraPaurashava is normally affected by flood from the adjacent rivers because absence of embankment in the middlepart of Paurashava. So, the Paurashava is almost regularly affected by the storm water during monsoon period due to the inability of the existing drainage system to cope up with the situation. The existing drains cannot discharge the huge volume of storm water efficiently to the defined out falls. Because of prevailing such situation, local flooding occurs in many places of the Paurashava.

Flood is annual phenomenon in singra Paurashava. The people in this area have to suffer a lot due to annual flood. Sometimes the flood water reaches into their houses.

12.6.6.4 Earth Quake

Like Cyclone, Earth Quake in this area is not a regular phenomenon. Although several Earth Quake were observed in this area over the past decades but the intensity was very low and damages occurred due to Earth Quake.

12.6.6.5 Water Logging

Inundation occurs in some parts of the Paurashava due to localized storm that is affecting the drainage system of the Paurashava and creating a worse environment for the residents living in those areas.

The depth of inundation and duration varies from place to place. However, it is ranged from 0.5m to 2.5m in depth and the duration of water logging varies from 6 hrs to 20 hrs and even it lasts for several days. The reasons for water logging are as follows:

- a) Absence of planned drainage system.
- b) Absence of integrated drainage network of tertiary and secondary drains with primary drainage system.
- c) Existing drains with low discharge capacity.
- d) Indiscriminate disposal of solid waste into the drainage system that reduces the flow capacity of the whole system.
- e) Lack of proper initiative for cleaning and maintenance of existing drainage system.

It is known from the local people that the Paurashava authority did not take any substantial initiative to remove or to reduce the problem of water logging.

12.6.6.6 Fire Hazard

In this Paurashava no mentionable fire hazard occurred in the last decade.

12.7 Plans for Environmental Management and Pollution Control

12.7.1 Proposals for Environmental Issues

12.7.1.1 Solid waste management Plan

Solid waste management is not yet an environmental problem in the town because of low density of population and low consumption rate. But in future population will rise and density will increase. So, solid waste will pose a major environmental problem in future. It is better to take precautionary measures now to avoid any future hazard.

A waste disposal ground is proposed at South-East corner of Ward-12 for final dumping of solid waste in order to ensure a habitable environment and to keep the urban environment free from pollution. To solve the solid waste management problem door to door collection program should be introduced. The Paurashava authority along with NGO's and CBO's will collect wastes from the households and storage points daily. The van will move into the wards and whistle to announce its arrival. The same vehicle will cover other institutions, societies, complexes. Thus the system will cover the whole town and finally they will dump the wastes to the proposed waste disposal ground. A minimum charge will be fixed by the Paurashava authority for waste collection to the inhabitants. **Details has been given in Table 10-20 chapter 10.** The total process is exposed under **Fig 12-13.**




Fig 12-13: Overview of the Solid Waste Management Plan

12.7.1.2 Plan for Protecting Open Space, Wet-Land and Relevant Features

Parks and Recreational Places

A few play fields are the main recreational sites in the area. However, with implementation of this plan, new open space, playground, parks, lake, etc. will provide more leisure places for the people.

Details has been given in Table 10-18 chapter 10.

Enhancement Activities:

- Ensure new open space, playground, parks, increasing facilities to visit the river bank etc. to increase recreational facilities in the Paurashava area.

Map 12-4: A Brief of Solid Waste Management Proposal of Singra Paurashava

Map 12-5: Location of Existing and Proposed Open Spaces of Singra Paurashava

- Develop khal side as walking area with properly designed modern facilities to attract outside visitors also.

Responsible Organizations:Paurashava, Bangladesh Parjatan Corporation

Loss of Wetlands

Wetlands are mainly affected first by the urbanization process. Earth filling fills up the ponds, low land, khals. Waste water affects the aquatic ecosystem and makes the ponds, khals unproductive and as a result the aquatic plants, fishes and animals have to die or migrate to other places. Suitable urban facility attracts more residential development with the cost of filling of low cost wetland. There is no strict regulation on earth filling of ponds. However, Wetlands Conversation Act exists in Bangladesh, which is applicable only to natural beels and khals. Number of ponds in Singra Paurashava is reduced every year to accommodate housing and commercial structures. Wetlands play an important role as a reservoir of rain and flood water. They are also important to maintain the balance of ecosystems and for replenishing the ground water level through seepage.

Mitigation:

- Cutting of drainage outlets to the khals and ponds.
- Avoiding wetlands during road alignment fixation.
- Stopping housing estate, industries and other development works in wetlands through earth filling.
- Stopping earth filling of ponds in Paurashava area through creation of public awareness.
- Strict implementation of Wetland Conservation Act, 2000.

Responsible Organizations:Paurashava, DOE and NG

12.7.1.3 Proposals for Pollution Control

12.7.1.3.1 Industrial

Industrialization is not prominent economic sector in Singra Paurashava. With implementation of this project and establishment of Industrial Zone nearby with road, drainage, water, gas, electricity and telephone facilities will attract the promoter and NBRs to invest here and help in industrialization in the project area.

Enhancement Activities:

- Arrangement for gas pipe line in the industrial zone.
- Arrangement for water, electricity, telephone, fire-service and drainage facility in industrial zone.
- Arrangement for soft-loan for agro-industry, garments, electronics, IT etc.
- Strengthening the activities of Singra Shilpa and Banik Samity (KSBS).
- Invite the national and foreign investors to visit and invest in industrial zone.
- Initiate the local entrepreneurs through incentives for industrialization.
- The existing brick fields can continue next 10 year and after that they have to relocate outside the Paurashava boundary. The existing brick field must follow Brick manufacturing (Control) Act, 1989.
- Any new brick field cannot permit in the Paurashava area.

Responsible Organizations: Board of Investment, Banks, Singra Shilpa and Banik Samity

12.7.1.3.2 Air/Water/Land/Sound

Noise Pollution

Noise is unacceptable level of sound that creates annoyance, hampers mental and physical peace and may induce severe damage to the health. Along with the increasing degree of air and water pollution, noise pollution is also emerging as a new threat to the inhabitants of Paurashava. Motorized traffic is one of the major sources of noise pollution in urban areas. Although there are many sources of noise, which include industries, construction works and indiscriminate use of loud speakers, motorized traffic is the principal source of creating noise in urban areas. With the increase in the number of motorized vehicles in the city, the hazard of noise pollution has increased and exceeded the level of tolerance. The noisiest area in SingraPaurashava is Alampur Chowrasta intersection

Exposure to high level of noise may cause severe stress on the auditory and nervous system of the city dwellers, particularly the children. Regular exposure to loud noise damages the hearing capability and has adverse effects on health, like increasing mental stress and blood pressure and sleeplessness, resulting in poor work performance. With expansion of urban area, the noise pollution will be increased for increasing motor vehicles, market places, industries etc.

Mitigation:

- Stop using hydraulic horn in buses, trucks and other motor vehicles.
- Declare some areas like hospitals, schools, parks, etc. as silent zone.
- Strict implementation of law.
- To control abnormally high noise from saw mill the old machines should be repaired or replaced.
- Foundation of machines should be specially prepared to reduce noise.
- Special type of silencer may be attached with the machines to reduce noise.
- Welding and blacksmith workshops can be fenced with classes to protect the passersby from possible pollution effects.
- People constantly working in welding and blacksmith workshops should wear earplugs and glasses. Regular medical checkups can be carried out to identify possible health problems.

Responsible Organizations: Paurashava, BRTA, Singra Upazila Health Complex, Motor Owners Association and Labor Unions, etc.

Air Pollution

Almost all the project area has the same level of air quality. As from the standard of The Environment Conservation Rules, 1997 (ECR, 1997) the air quality of the category "Residential and rural" has the density of different air particles in the project area as follows:

- Suspended Particulate Maters (SPM) = 200 microgram per cusec meter,
- Sulphur-dioxide = 80 microgram per cusec meter,
- Carbon Monoxide = 2000 microgram per cusec meter and
- Oxides nitrogen = 80 microgram per cusec meter.

Mitigation:

- Use catalytic converter in buses, trucks, taxis and tempos.
- Use CNG instead of petrol.
- Set up 120 ft. high stack in brickfields and use filter to reduce the CO, SO₂ and NO₂ gases in atmosphere.
- Stop the operation of brick-fields which have grown near the homesteads, bazars and growth centers.
- Impose ban on movement of stone and sand carrying trucks using the tertiary and access roads.

Responsible Organizations: Paurashava, DOE, BRTA, DC office, Motor Owner and Labor Unions, etc.

Drainage Congestion

Drainage congestion may increase further with the present trend of development. Faulty design, slope problem in head and tail area, solid-waste and rubbish dumping, encroachment and unauthorized structures, siltation, lack of renovation and re-excavation are the main causes of drainage congestion. As a result discharge of new drainage network will create severe drainage problem in Paurashava area, particularly in monsoon period.

Mitigation:

- Excavation of the primary drainage networks specially the existing and the proposed khals.
- Re-excavate the water retention and detention area with link khals proposed in the master plan.
- Remove all un-authorized structures, developed on drainage structures.
- Make proper drainage network in new area considering the slope and local topographical condition.
- Strictly prohibit the people in dumping of rubbish and solid waste in drain.
- Regular cleaning and maintenance by the concerned authorities.

Responsible Organizations: Paurashava, LGED

Surface Water Pollution

The surface water quality of khals, ponds and ditches are polluted in respect of pH, turbidity and coliform bacteria with national standard. The present pollution level of these sites is found to be low except coliform bacteria. The main causes of surface water pollution are industrial wastewater, sanitary sewage, solid waste dumping. The present trend of development in the project area, the surface water pollution level may further increase for high volume of discharge of wastewater, sanitary sewerage, over spilling of pit and septic tank, industrial effluents, surface run-off of katcha bazars, indiscriminate solid and medical waste dumping.

Mitigation:

- Stop katcha, hanging and pit latrines.
- Create underground sewerage system for Paurashava area.
- Use pucca latrine with septic tank and soak well.

- Prohibit indiscriminate dumping of medical and solid waste in drainage, khals and river.
- Improve sanitation condition of slaughter house, fish market and katcha bazars.
- Prohibit the direct discharge of Paurashava waste water to any Canals, low lying areas and river.
- Establish waste water and sewerage treatment plant.

Responsible Organizations: Paurashava, LGED and DOE

Groundwater Depletion

Groundwater level of Paurashava has a considerable lowering over the last few decades. It has been calculated that in 2031 the lowering of ground water level might be 20m. Eventually fall of groundwater table is a common phenomenon in project area during dry period (Feb.-May). With expansion of urbanization and industrialization, the groundwater table may further fall if present tradition of using groundwater is continued.

Mitigation:

- Use khals water for pipeline supply to households and industries.
- Use of surface water treatment plant to purify the river water and use as drinking water.
- Introduce rainwater harvesting system and use in the project area.
- Stop land filling of ponds and water bodies (area more than 0.25 acre) to maintain the groundwater level through recharge and leaching process.

Responsible Organizations: Paurashava, DPHE, and NGOs

Groundwater Pollution

Groundwater pollution due to manganese, iron and hardness is a major problem in the project area. With expansion of urban area, more dependency on groundwater sources may increase the pollution level of sub-surface water.

Mitigation:

- Use surface water of khals for supply water system.
- Introduce rain water harvesting system.
- Reduce dependency on groundwater.
- Preserve surface water in ponds, khals, ditches and rivers for irrigation.

Responsible Organization: Paurashava, LGED, BWDB, DOE and NGOs

12.7.1.3.3 Other Pollution

Any pollution other than mentioned above is not yet identified at SingraPaurashava.

12.7.2 Natural Calamities and Hazard Mitigation Proposals

12.7.2.1 Plan for Addressing Natural Calamities (Structural and non structural measures)

Earthquake

Like Cyclone, Earth Quake in this area is not a regular phenomenon. It is low vulnerable region in Bangladesh. Unplanned and unregulated urbanization and disregard to BNBC rules in building construction aggravate the situation more. With the implementation of master plan the planned urbanization will strictly follow the actual zoning plan and following of BNBC rule will minimize the

earthquake damage. In DMDP Urban Area Plan Volume- II, (Part-3, Interim Planning Rules) development restriction considering the geological fault line areas states “Structures above 2 storey’s situated within 500 meters of a geological fault is not allowed unless built to the BNBC standards for Seismic Zone 3 (BNBC Section 6 Chapter 2.25)”. Similar measures are also suggested for SingraPaurashava.

Enhancement Activities:

- Ensure all new buildings are designed and constructed following the guideline of BNBC.
- Development of a comprehensive plan for managing post earthquake situation.
- Train community workers who would carry out the initial search and rescue efforts.
- Launch a massive public awareness campaign.

Responsible Organizations: Paurashava, Civil Surgeon, Civil Defense, Fire Service and DOE

Change in Topography

Topographically SingraPaurashava is flat and gentle sloping. The natural topography of Paurashava area has already been changed for urbanization. The present trend of development like roads, drainage, bridge/culvert, housing and industrial estates and bazars will radically change the natural topography and land use pattern of the area. The agricultural area will be converted into urban and semi-urban area. The present green scenic beauty will disappear, water bodies will be lost and general slope will be diminished for earth cutting due to rapid urbanization. The current effort of master plan will ensure sustainable development.

Mitigation:

- Careful planning to minimize the change of topography.
- Avoid water bodies during construction of roads, housing and industrial estates.
- Practice good architectural/engineering design during planning of housing estates, buildings and the intersections of main roads.
- Enhancement of plantation and gardening to increase the scenic beauty of the city.
- Preserve the natural greenery, ponds, khals and large water bodies.

Responsible Organizations: Paurashava, DOE and Forest Department

Land Use Change

With the implementation of master plan, the Peripheral-urban and agricultural land use will be controlled and conserved using landuse control mechanism.

Mitigation:

- Careful planning to reduce change of agricultural land use and rural set up.
- Conserve water bodies and productive agricultural land free from haphazard urban development.
- Economical use of land.

Responsible Organizations: Paurashava and Ministry of Agriculture& Livestock, DOE

12.7.2.2 Plan for Addressing Hazards

Traffic Congestion

Traffic congestion is space-based problem. It occurs at particular junction and or at a particular land use area. Urbanization and growth of population will increase movement of vehicles in and around the Paurashava. Number of rickshaws will also increase to meet the people's demand. Rickshaws will be the main cause of traffic congestion in SingraPaurashava in future.

Mitigation:

- Phase wise implementation of proposed road network.
- Strict implementation of traffic rules to improve traffic management.

Responsible Organization: Paurashava, LGED, RHD

Fire Hazard

In future the probability of fire may increase for more offices, institutions, markets, growth centers and industries. Electric short-circuit is mainly responsible for fire hazards in urban area. However, human error may also cause for fire sometimes. Slums and some industries like garments and plastic products are more susceptible to fire hazards. The present fire station facility is not enough to cope with future fire hazards.

Mitigation:

- Set up one new fire station at proposed location
- Collect modern fire prevention devices.
- Refrain people from using low quality electrical wire in buildings and industries.
- Ensure periodical checking of electric lines.
- Create awareness of people about fire hazards.
- Ensure fire-fighting devices in new industries, high-rise buildings and markets.
- Strict implementation of BC rule.
- Large and medium scale water bodies should be conserved for quick and huge supply of water at the time of emergency.

Responsible Organizations: Paurashava, PDB, DOE and Fire Service and Civil Defense

Loss of Habitat

The habitat for fauna and wildlife has been losing day by day in the Paurashava area. For urbanization and industrialization, agricultural land will be disappear, water bodies will be filled up, rivers and khals will be polluted and trees will be cut down for new settlement. Birds, fishes and other animals will permanently lose their habitat and food in the urban area.

Mitigation:

- Careful planning to avoid the sensitive ecosystem.
- Minimum use of land for urbanization.
- Preservation of water bodies and khals.
- Initiate people to avoid tree cutting and vegetation clearing.

Responsible Organizations: Paurashava, DoE and NGOs

Loss of Biodiversity

Continuous expansion of the urban area will enhance the urban development in this area. Urban elements like roads, infrastructure development, housing, commercial places, industrialization etc. will replace the existing green natural environment to manmade environment. Trees will be cut down, water bodies will be filled up and polluted; garden and bush will disappear for urban expansion in new area. Wild animals, birds and fishes will lose their habitats and as a result a big loss of biodiversity will happen for urban expansion in the Paurashava area.

Mitigation:

- Avoid critical ecological area and refugee sites from development works.
- Aware people for keeping some trees and bushes around the homesteads.
- Increase tree plantation in roadsides along the river and khals and homesteads.
- Preserve the lakes for aquatic birds and fishes and some bush areas as wildlife refuge sites.
- Ban on hunting of birds and wildlife.

Responsible Organizations: Paurashava, Forest Department, Fisheries Department and NGO's

Loss of Capture Fisheries

The project area is mainly high and medium high land. Khals and low lands are very limited. Therefore, open water fisheries resources are low in the project area. Only 15-20% fish demand is met by the capture fisheries. Ponds and khals support the capture fisheries in the project area. Lowering of water level in the river also there is no water in the khals in dry season is a major reason of the damage of aquatic environment.

With the continuing urbanization, the capture fisheries will be remarkably reduced for loss of habitat due to water pollution of sewerage and drainage discharge, industrial effluent, solid waste dumping, earth filling and less flushing. Area of khals, beels and other water bodies will be reduced for land development and urbanization.

Mitigation:

- Stop direct drainage outfall to river, khals and beels.
- Set up sewerage and wastewater treatment plant.
- At the early monsoon, keep open the gates of sluices and regulators during spawning period of fish.
- Excavation of khals and natural water bodies
- Strict regulation on land filling of water body.

Responsible Organizations: Paurashava, and DOE

Loss of Ponds and Culture Fisheries

With urbanization and industrialization through this project, many ponds will be lost for land filling by the owners for increasing land value due to human pressure, settlement and development accordingly loss of fishes. There is no strict regulation on earth filling of ponds in the area.

Mitigation:

- Designate all ponds in Master Plan Map and protect the large ones according to the ecological importance and public interest.
- Protect the ponds having area more than 0.25 acre as per regulatory framework of Master Plan.
- Create public awareness about the importance of ponds and its role in culture fisheries, bathing and water reservoir for surface run-off during monsoon.

Responsible Organizations: Paurashava, DOE and DC (Land)

Loss of Productive Agricultural Land

The Master plan Project has included a vast area of agricultural land in the project area. Both highlands and lowlands fall into this project. After implementation of MP project, agricultural environment will be converted into un-productive urban and semi-urban area.

Mitigation:

The DOE EIA Guidelines emphasized on the avoidance of productive agricultural land during any development project. Therefore, it will be wise to consider more economical use of land to avoid some fertile lands. The land acquisition should be based on the growth rate of population. The designated agricultural land in the master plan must conserve from any type development or land use change. Strict rules and regulation must be imposed to control the agricultural land.

Responsible Organizations: Paurashava and DOE

12.8 Plan Implementation Strategies

12.8.1 Regulations to Implement the Environmental Management Plan

Drainage and Environmental Management plan should be performed under the clauses in the Local Government (Paurashava) Act, 2009 and other national rules existed in Bangladesh.

According to the second part of section 50-71 of Local Government (Paurashava) Act, 2009:

Removal, collection and disposal of refuse

- 1) A Paurashava shall make adequate arrangements for the removal of refuse from all public streets, public latrines, urinals, drains, and all buildings and land vested in the Paurashava and for the collection and proper disposal of such refuse.
- 2) The occupiers of all other buildings and lands within the municipality shall be responsible for the removal of refuse from such buildings and lands subject to the general control and supervision of the Paurashava.
- 3) The Paurashava may cause public dust-bins or other suitable receptacles to be provided at suitable places and where such dust-bins or receptacles are provided, the Paurashava may, by public notice, require that all refuse accumulating in any premises or land shall be deposited by the owner or occupier of such premises or land in such dust-bins or receptacles.
- 4) All refuse removed and collected by the staff of the Paurashava or under their control and supervision and all refuse deposited in the dust-bins and other receptacles provided by the Paurashava shall be the property of the Paurashava."

Latrines and urinals

- 1) "A Paurashava may, and if so required by the Government shall, provide and maintain, in sufficient number and in proper situation, public latrines and urinals for the separate use of each sex, and shall cause the same to be kept in proper order, and to be properly cleaned.
- 2) The occupier of any premises to which any latrine or urinal pertains shall keep such latrine or urinal in a proper state to the satisfaction of the Paurashava and shall employ such staff for the purpose as may be necessary, or as may be specified by the Paurashava.
- 3) Where any premises are without privy or urinal accommodation, or without adequate privy or urinal accommodation, or the privy or urinal is on any ground objectionable, the Paurashava notice require the owner of such premises.

The privy or urinal disposed in the Paurashava's dustbin or disposal ground is the property of Paurashava."

12.8.2 Implementation, Monitoring, Evaluation and Coordination of the Plan

Resettlement

Resettlement is a burning question for any urban development project. For Master Plan Project land will be required for roads, markets & bazars, educational organizations, housing & industrial estates, open spaces, play grounds, parks, lakes, etc. Therefore, land acquisition is required from people in the project area. People have been living in their homesteads for many years in ancestral way and reluctant to leave their croplands and homesteads. The project authority should take proper care during land acquisition. Requisition of sensitive and conflict land area should be done in consultation with the landowners, local ward commissioners/ members/ chairmen and political persons. Without appropriate rehabilitation and compensation, no one should be evacuated from his homesteads. Slum people do not have the land right, they should be rehabilitated in new places with full compensation of housing and occupation.

Compensation

Land acquisition should be discussed with individuals affected and through participation of local people. The compensation of each affected landowner should be paid in the shortest possible time. If anyone loses his/her occupation/business/income source for land acquisition, it should be incorporated in compensation package. This would necessitate amendment of compensation rules. Persons losing their homesteads for housing project may be rehabilitated with due compensation and sanction of one plot in housing estate.

Section 12 of the Environment Conservation Act (ECA) 1995 stipulates that "no industrial unit or project shall be established or undertaken without obtaining environmental clearance from the Director General, Department of Environment, in the manner prescribed by the rules."

The Environment Conservation Rules (ECR) 1997 have been prepared under the clause (2) (f) of the section 20 of Environment Conservation Act (ECA) 1995. The requirements of EIA for new development projects came into enforcement under the ECR 1997. These are the first set of rules promulgated under the Environment Conservation Act 1995. Among other things, these rules set out the requirements for and procedures to obtain environmental clearance. This also explains the requirements for IEE/EIA according to different categories (green, orange/amber or red) of industrial and development interventions.

During the implementation of Master plan, environmental clearance procedure will be guided by the Environment Conservation Rules 1997 of the Department of Environment. Paurashava will have the authority to approve the plan as per agreed principles in the Master plan but the owner of the plot will be obliged to get clearance from the DOE before actual implementation.

For implementation of the mitigation plan emphasis has to be laid on implementing the mitigation measures. Appropriate institutional set up will be required to implement the measures. Government must allocate sufficient budget for this purpose.

Duration, Revision and Updating

The proposed environment management Plan along with a set of policy guidelines has been provided for a period of 20 years, 2011 through 2031. However, to suit in time and space, revision and updating of the environment management Plan will be necessary at a regular interval.

environment management Plan should be regularly reviewed and updated during the end of every fifth year of the five-year term. In this way, four revisions will be carried out during its twenty years lifetime.,

Chapter 13: Plan for Urban Services

This chapter describes the urban basic services development proposals for future development of the Paurashava. The proposals have been made at the town level, that is, the area under the urban area plan. The local level development proposals will be addressed in the Ward Action Plan. The development proposals deal with the basic urban services, like, water supply, drainage, sanitation, solid waste, telecommunication, electricity and gas, community facilities, education and health.

13.1 Water Supply

The Paurashava is taking step to develop its own network based water supply system. The entire water supply system of the Paurashava is based on household tube well and pond. As per the census 2001, about 88.02% household depend on tube well for their drinking water. However, many of the tube wells provide arsenic free drinking water. As a result lots of hand tube wells water is mostly used for washing purpose. Water from ponds is mainly used for washing.

Developing a network based supply system will depend on availability of fresh water aquifer. Detailed geological Investigation is required to find out fresh water aquifers. But here problem lies here to use of ground water. Safiuddin (2001) observed the serious arsenic contamination of groundwater in Bangladesh has come out recently as the biggest natural calamity in the world. The people in 59 out of 64 districts comprising 126,134 sq km of Bangladesh are suffering due to the arsenic contamination in drinking water (arsenic contamination is also found in the ground water of SingraPaurashava). So in case of water supply for SingraPaurashava, special emphasis will be given to use surface water rather than use of ground water. Paurashava should take a programme to preserve and maintain all major ponds at the Paurashava for the greater interest of the people at large. The consultant, according to approved standard, has considered about 2.0 acres for water supply installations, like, pump stations and other establishments related to water supply. Total 10.43 acres land will be used for utility services.

The town dwellers use ponds, khals and river water for their daily necessities other than drinking and cooking purpose. So it will require much less amount of water supply for the Paurashava town than city consumption. According to the estimation the total population in 2011 of SingraPaurashava is 33192 and at the end of the project i.e. in 2031 this will be around 71617. Assuming that per day per capita water consumption of 100 liters, Technical loss 20% and Industrial/Commercial demand 20%.

By considering the above assumption, the total demand of water consumption of SingraPaurashava will be 7161.7cubic meter by 2031. This consideration has been taken by avoiding excess industrial and commercial demand so that there are no mentionable industrial establishments in this Paurashava.

As an alternative to drinking water supply harvesting of rain water may be explored. The idea of rainwater harvesting is unknown to the local people. NGOs working in rain water harvesting training and motivation may be engaged for this purpose. Paurashava may take initiative to prepare a programme for popularizing rain water harvesting among the Paurashava people.

Map 13-1: Proposed Water Supply Network Map of Singra Paurashava

13.2 Solid Waste Management

There will be 2 waste transfer stations with an area of 0.28 acres for collection of solid waste located at suitable locations. A dumping site will be developed over an area of 7.67 acres for final disposal of the solid waste. The waste dumping site is located in Ward-12 at the south-east corner boundary of the Paurashava.

13.3 Sanitation

According to BBS 2001, the present sanitation system of the Paurashava is composed of a variety of types, like, hanging latrine, pit latrines of different types, water sealed latrines and septic tank based sanitary latrine.

The record of sanitation condition is also not perfectly available. However, the Paurashava authority told that about 70% Households covered Pucca sanitary latrine and there is no open latrine in this Paurashava.

Due to prohibitive expenditure one should not expect establishing network and treatment plant based sewerage system in the town by the Paurashava. So, for long the sanitary system of the Paurashava will remain on site. To promote healthy sanitation, Paurashava should promote low cost sanitary latrines in the town together with awareness building for healthy sanitation. It is proposed to set up public toilets in public gathering areas, like, existing and proposed bus stand, bazar and the main town center. This will cause to set up 01 number of public toilets in the town.

13.4 Electricity and Gas

Power Development Board (PDB) is mainly responsible for electricity supply in the Paurashava, supported by the Rural Electrification Board (REB). PDB works for power production and distribution, while REB is responsible for distribution only. Both, PDB and REB have their own plans for power supply in the town, which is executed in phases, depending on demand for power. In its infrastructure plan has shown the future power supply network of the town. The required electricity facility within the Paurashava will be provided through existing power system master plan of both REB and PDB. But the greatest problem of power supply in the entire country remains to be handicapped by the shortage of supply due to low production.

Area for gas related facilities is not proposed in the plan, because there is no scope for installation gas facilities in this Paurashava within the planning period.

13.5 Telecommunication

The town enjoys the networks of all mobile and PSTN telecommunication companies operating in the country. Besides, there also exist landlines of BTCL, the national telephone company. Due to easy and cheaper access to mobile, the demand for land lines has decreased substantially.

Map 13-2: Proposed Urban Services of Singra Paurashava

Chapter 14: Ward Action Plan

14.1 Introduction

This chapter presents Part-C of the report which contains Ward Action Plan of each individual Ward. First, the issues prevailing in different Wards have been briefly described followed by description of Development Proposals in first ward action plan (1st to 5th year of planning period) for each Ward.

14.1.1 Background

The Ward Action Plans are prepared under the framework of Structure Plan and Urban Area Plan. The Ward Action Plans contain details of development proposals at Ward level including the problems and opportunities existing therein and also include the proposals made in the upper level plan that is in the Urban Area Plan. The Ward Action Plans have been formulated for execution within a period of 5 years.

Ward Action Plan is a vital part of the current plan package as far as spatial development and development control is concerned. Absence of Ward Action Plan not only hampers undertaking of development projects by planning authority, but also leads to uncontrolled and unwanted spatial development in the private sector. Land use zoning is also provided in the Ward Action Plan to enable detailed view of proposed land use and development.

14.1.2 Content and Form of Ward Action Plan

The Ward Action Plan is detailed area plan based on the policy framework, guideline indication of Structure Plan and more detailed guideline of Urban Area Plan. The provision of Ward Action Plan is inherent in the Structure Plan with some specific purposes. The Ward Action Plan is to:

- a) Provide basic micro level infrastructure and services in the study area through systematic planning, under the framework of Structure Plan and proposals of the Urban Area Plan;
- b) Create congenial environment to promote economic activities;
- c) Improve drainage system and protect natural water channels from encroachment; and
- d) Create service centers to promote urban growth.

14.1.3 Linkage with Structure and Urban Area Plan

Ward Action Plan is the 3rd component of the Master Plan package. The other two upper level components are Structure Plan and Urban Area Plan. Structure Plan lay down the framework of the future plan including strategy and the sectorial policies. The Urban Area Plan and the Ward Action Plan detail out development proposals under the framework of Structure Plan.

14.1.4 Approach & Methodology

The methodology could be illustrated through tri-step process for the assessment of Ward Action Plan. The first step of the methodology of Ward Action Plan is to conceptualize the content and background of the plan. In the next step, the linkage with Structure Plan & Urban Area Plan is identified. The final phase of the study is to adopt ward action plan in details. The proposal and

planning, priority tasks and cost estimation are incorporated here to get a pictorial view of the Ward Action Plan.




Fig 14-1: Flow Chart of Methodology

14.2 Derivation of the Ward Action Plan

The Ward Action Plan is derived from the conceptual framework, and guidelines and strategies for development under Structure Plan and detailed proposals of Urban Area Plan. Ward Action Plan is aimed to provide detailed infrastructure plan to guide the physical development of Singra town including its all economic and social activities. This plan adheres to the policy directives spelled out in the Structure Plan.

14.2.1 Revisiting Structure Plan and Urban Area Plan

To guide long term growth of the Paurashava, potential locations of major development areas are identified and the Structure Plan Area is broadly classified into nine categories, namely Established Urban Area, Sub Urban Area, New Urban Area, Recreational Facility, Circulation Network, Restricted Area, Urban Peripheral Area, Agriculture Area and Water Retention Area. The Urban Area Plan is prepared under the framework of Structure Plan and the infrastructure identified for improvement and development are listed as proposals in the Urban Area Plan. The broad classification of lands in the Structure Plan and detailed proposals in the Urban Area Plan form the basis for Ward Action Plan.

14.2.2 Prioritization

The prioritization of project proposals in Ward wise Action Plan are made on the basis of urgency for development depending on the needs of people and the town's requirement for infrastructure development.

14.2.3 Ward Wise Action Plan for Next Five Years

The Ward Action Plan is prepared for each of the twelve Wards and is presented in order of their serial number. The Ward Action Plans are a series of detailed spatial development plans of different use and facilities. The plans comprise maps of appropriate scale supported by explanatory report. The Ward Action Plans have been formulated for execution within a period of 5 years. They do not initially cover the entire Structure Plan area. While all sub-areas will eventually require Ward Action Plan, only priority areas are to be dealt with initially. The aim of a Ward Action Plan is to prevent haphazard urban development and ensure livable environment in areas that are likely to be urbanized soon. Initially Detailed Area Plan should be covered for only those areas where action is needed immediately or where development pressure is high.

Public involvement is a key issue. To this end, the Paurashava has adopted a "Planning for Real" based approach which allows hands-on participation by all the residents of each local community. They help by identifying local issues and problems which the Plan can tackle; expressing their views on the Paurashavas policies; and suggesting how these could be improved. Ward Action Plan must be topical and relevant. The Paurashavas target is to ensure that they are reviewed on a 5 yearly cycle. A comprehensive Map of Ward Action Plan is shown in **Map 14-1**.

Map 14-1: Ward Action Plan of Singra Paurashava

Ward Action Plan for Ward-01

14.3 Demographic Conditions of Ward-01

Ward No. 01 is located at the middle part of Singra Paurashava. The area of the Ward is 141.08 acres. The Population was 2316 in 2001 and 2952 in 2011 according to BBS. Population projection shows 6369 population in 2031. The density will be 45 persons per acre in 2031.

Table 14-1: Population Statistics of Ward No. 01

Item	Year	
	2011	2031
Area (acre)	141.08	141.08
Population	2952	6369
Density of Population (acre)	21	45

Source: BBS 2001 and 2011

14.4 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 5.04 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 3.28 km road is pucca, 0.64 is semi-pucca and 1.12 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 21 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.5 Ward Action Plan Proposals

14.5.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 63.30 acres which is 2.30% of the total land. The second major land use is Residential land and occupying about 43.84 acres of the Paurashava area. Besides, there is about 22.50 acres water body, about 3.74 acres circulation network, about 0.45 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.5.2 Proposed Land Use Zoning

i) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers

72.04 acres of land delineated up to the year 2031 in Ward No. 01, considering standard provided by LGED.

ii) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 1.86 acres designated up to 2031.

iii) Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. Mixture of land uses will allow flexibility of development, instead of restricting development. This zone has an area of 1.25 acres designated up to 2031.

iv) Education & Research Zone

The total area under this use has been determined as 9.59 acres of land designated up to 2031.

v) Government Office

This zone covers all kinds of government offices in the town. The total area under this use has been proposed as 1.85 acres of land designated up to 2031.

vi) Rural Settlement

The total area under this use has been proposed as 0.06 acres which is most portion of this land use.

vii) Agricultural Zone

The Paurashava including Ward No. 01 has no agricultural land.

viii) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 22.11 acres.

ix) Health Services

Proposed plan suggests a community clinic in this ward with 0.60 acres of land of the whole ward.

x) Circulation Network

Existing and proposed roads covers a total of 18.01 acres of land of the whole ward.

xi) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 9.47 acres of land for open space.

Map 14-2: The Proposed Land Use Zoning Map of Ward-01

14.5.3 Road Network Development Plan

The existing road network of ward no.1 is 5.04 km where 3.28 km road is pucca, 0.64 is semi-pucca and 1.12 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 18.01 acres of land is allotted for ward no 01. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-01 is shown in table 14-2 and Map 14-3.

Table 14-2: Proposal of Roads for Ward-01

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Existing Width(m)	Proposed Width (ft)	Proposal Type
Secondary Road	New Road	NR-1	0.203	-	30	Pucca
Local/Access Road	New Road	NR-2	0.212	-	20	Pucca
Local/Access Road	New Road	NR-21	0.252	-	20	Pucca
Secondary Road	New Road	NR-3	0.870	-	40	Pucca
Local/Access Road	New Road	NR-33	0.279	-	20	Pucca
Local/Access Road	New Road	NR-4	0.283	-	20	Pucca
Secondary Road	New Road	NR-78	2.520	-	50	Pucca
Local/Access Road	Widening Road	WR-216	0.265	4.569	20	Pucca
Local/Access Road	Widening Road	WR-218	0.307	3.191	20	Pucca
Secondary Road	Widening Road	WR-229	1.000	3.963	40	Pucca
Local/Access Road	Widening Road	WR-234	0.452	4.569	20	Pucca
Secondary Road	Widening Road	WR-246	0.828	3.963	40	Pucca
Secondary Road	Widening Road	WR-272	0.432	3.963	30	Pucca
Local/Access Road	Widening Road	WR-279	0.550	3.963	30	Pucca
Secondary Road	Widening Road	WR-313	0.395	3.963	30	Pucca

*** Road length ≥ 200 meter incorporated here. Detail was given in Appendix*

14.5.4 Drainage Development Plan

Drain is necessary for discharge all its waste water and storm water. The plan proposes new drains for ward no. 01 which will be developed during the different phase. The natural sources of drainage are playing the critical roles in drainage plan.

Table 14-3: Proposal of Drain for Ward-01

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Secondary Drain	SD-14	711.120	River	0.80
Secondary Drain	SD-5	5.942	Khal	0.80
Secondary Drain	SD-6	318.038	River	0.80
Secondary Drain	SD-6	218.561	River	0.80

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Secondary Drain	SD-8	670.061	River	0.80
Tertiary Drain	TD-19	1.390	Khal	0.80
Tertiary Drain	TD-21	325.841	River	0.80
Tertiary Drain	TD-22	389.427	River	0.80
Tertiary Drain	TD-25	243.186	River	0.80
Tertiary Drain	TD-26	230.239	River	0.80
Tertiary Drain	TD-27	83.013	River	0.80
Tertiary Drain	TD-28	142.013	River	0.80
Tertiary Drain	TD-29	174.745	River	0.80
Tertiary Drain	TD-34	291.719	River	0.80
Tertiary Drain	TD-35	74.625	River	0.80

14.5.5 Urban Services Development Plan of ward no-01

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 01 has much more potentiality due to situated in Natore-Singra road. Poly Technical College, Eidgah, Clinic, Neighbourhood market, park, primary school, Rickshaw/Van Stand and ward centre are proposed here. The proposal for service facilities of ward no 01 is shown in table 14-4 together with mouza name and plot number.

Table 14-4: Proposal for Other Facilities of Ward-01

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-1	Ward Centre	Partial 227,234-237	1.00	Kata Pukuria_338_00
NP-6	Neighbourhood Park	Partial 1-6,14-17	7.27	Porbo Masinda_335_00
NM-1	Neighbourhood Market	Partial 214-216	1.65	Kata Pukuria_338_00
EDG	Eidgah	285	0.50	Kata Pukuria_338_00
PLC-1	Poly Technical College	133,137,243-245,303(p),304357,360,367,368,369	5.66	Kata Pukuria_338_00
CLN-3	Clinic	84	0.62	Kata Pukuria_338_00
NS-7	Nursery School	285(p)	0.50	Kata Pukuria_338_00
RS-3	Rickshaw/Van Stand	Partial-61,67,70	0.25	Chak Gopal_337_00
GH-1	Ghat	Partial-33	0.02	Porbo Masinda_335_00
GH-2	Ghat	Partial-23,25	0.02	Porbo Masinda_335_00

Map 14-3: The Proposed Urban Services and Drainage Network Facilities Map of Ward-01

Ward Action Plan for Ward-02

14.6 Demographic Conditions of Ward-02

Ward No. 02 is located at the extreme North of Singra Paurashava. The area of the Ward is 451.82 acres. The Population was 2299 in 2001 and 2705 in 2011 according to BBS. Population projection shows 5836 population in 2031. The density will be 13 persons per acre in 2031.

Table 14-5: Population Statistics of Ward No. 02

Item	Year	
	2011	2031
Area (acre)	451.82	451.82
Population	2705	5836
Density of Population (acre)	6	13

Source: BBS 2001 and 2011

14.7 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 6.02 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 3.02 km road is pucca, 0.63 is semi-pucca and 2.36 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 6 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.8 Ward Action Plan Proposals

14.8.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 358.85 acres which is 13.27% of the total land. The second major land use is Residential land and occupying about 44.48 acres of the Paurashava area. Besides, there is about 41.80 acres water body, about 4.75 acres circulation network, about 0.36 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.8.2 Proposed Land Use Zoning

ii) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers 0.01

acres of land delineated up to the year 2031 in Ward No. 02, considering standard provided by LGED.

iii) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 1.03 acres designated up to 2031.

iv) Education & Research Zone

The total area under this use has been determined as 2.52 acres of land designated up to 2031.

v) Rural Settlement

The total area under this use has been proposed as 57.45 acres which is most portion of this land use.

vi) Agricultural Zone

The Paurashava including Ward No. 02 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 325.17 acres that include existing and proposed land uses.

vii) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 41.28 acres.

viii) Health Services

Proposed plan suggests a community clinic in this ward with 0.15 acres of land of the whole ward.

ix) Circulation Network

Existing and proposed roads covers a total of 14.58 acres of land of the whole ward.

x) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 7.61 acres of land for open space.

Map 14-4: The Proposed Land Use Zoning Map of Ward-02

14.8.3 Road Network Development Plan

The existing road network of ward no.2 is 6.02 km where 3.02 km road is pucca, 0.63 is semi-pucca and 2.36 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 14.58 acres of land is allotted for ward no 02. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-02 is shown in table 14-6 and Map 14-5.

Table 14-6: Proposal of Roads for Ward-02

ID	Existing Road Type	Proposed Road Type	Length (k.m)	Proposed Width(ft)	Proposal Type
WR-289	Local/Access Road	Widening Road	0.289	20	Pucca
WR-325	Local/Access Road	Widening Road	0.434	20	Pucca
WR-328	Local/Access Road	Widening Road	0.290	20	Pucca
WR-329	Local/Access Road	Widening Road	0.206	20	Pucca
WR-330	Local/Access Road	Widening Road	0.277	20	Pucca
WR-332	Local/Access Road	Widening Road	1.121	20	Pucca
WR-334	Local/Access Road	Widening Road	0.240	20	Pucca
WR-338	Local/Access Road	Widening Road	0.251	40	Pucca
WR-346	Secondary Road	Widening Road	1.542	20	Pucca
WR-349	Local/Access Road	Widening Road	0.394	20	Pucca
NR-55	Local/Access Road	New Road	0.220	20	Pucca
NR-58	Local/Access Road	New Road	0.371	20	Pucca
NR-88	Local/Access Road	New Road	.363	20	Pucca

*** Road length ≥ 200 meter incorporated here. Detail was given in Appendix*

Table 14-7: Proposal of Drain for Ward-02

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Secondary Drain	SD-14	180.158	River	0.80
Secondary Drain	SD-7	5.397	Khal	0.80
Tertiary Drain	TD-48	1025.691	River	0.80
Secondary Drain	SD-14	180.158	River	0.80
Secondary Drain	SD-7	5.397	Khal	0.80
Tertiary Drain	TD-48	1025.691	River	0.80
Tertiary Drain	TD-49	739.638	River	0.80

14.8.4 Urban Services Development Plan of ward no-02

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 02 has less potentiality. High school, clinic, Neighborhood Market, park, playground, tempo stand and ward centre are proposed here. The proposal for service facilities of ward no 02 is shown in table 14-7 together with mouza name and plot number.

Table 14-8: Proposal for Other Facilities of Ward-02

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-2	Ward Centre	Partial 504,538-543	0.58	Uttar Domdoma_336_00
NM-2	Neighborhood Market	Partial 417-422	0.85	Uttar Domdoma_336_00
HS-1	High School	149(p),304(P),307(P)	1.2	Uttar Domdoma_336_00
PL-3	Playground	407,408,409(p),410(p)	1.65	Uttar Domdoma_336_00
CLC-2	Community Clinic	431-433(P)	0.15	Uttar Domdoma_336_00
NP-1	Neighborhood Park	Partial 283,284,366-375	5.85	Uttar Domdoma_336_00
TS-1	Tempo Stand	Partial 336-340	0.75	Uttar Domdoma_336_00

Map 14-5: The Proposed Urban Services and Drainage Network Facilities Map of Ward-02

Ward Action Plan for Ward-03

14.9 Demographic Conditions of Ward-03

Ward No. 03 is located at the North-East part of Singra Paurashava. The area of the Ward is 228.07 acres. The Population was 2223 in 2001 and 2932 in 2011 according to BBS. Population projection shows 6326 population in 2031. The density will be 28 persons per acre in 2031.

Table 14-9: Population Statistics of Ward No. 03

Item	Year	
	2011	2031
Area (acre)	228.07	228.07
Population	2932	6326
Density of Population (acre)	13	28

Source: BBS 2001 and 2011

14.10 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 5.91 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 4.74 km road is pucca, 0.20 is semi-pucca and 0.97 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 13 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.11 Ward Action Plan Proposals

14.11.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 157.93acres which is 5.84% of the total land. The second major land use is Residential land and occupying about 41.07 acres of the Paurashava area. Besides, there is about 21.92 acres water body, about 4.82 acres circulation network, about 0.55 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.11.2 Proposed Land Use Zoning

i) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers

38.56 acres of land delineated up to the year 2031 in Ward No. 03, considering standard provided by LGED.

ii) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 3.00 acres designated up to 2031.

iii) Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. Mixture of land uses will allow flexibility of development, instead of restricting development. This zone has an area of 0.12 acres designated up to 2031.

iv) Education & Research Zone

The total area under this use has been determined as 9.69 acres of land designated up to 2031.

v) Rural Settlement

The total area under this use has been proposed as 19.48 acres which is most portion of this land use.

vi) Agricultural Zone

The Paurashava including Ward No. 03 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 98.59 acres that include existing and proposed land uses.

vii) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 20.36 acres.

viii) Health Services

Proposed plan suggests a community clinic in this ward with 0.24 acres of land of the whole ward.

ix) Circulation Network

Existing and proposed roads covers a total of 24.17 acres of land of the whole ward.

x) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 5.10 acres of land for open space.

Map 14-6: The Proposed Land Use Zoning Map of Ward-03

14.11.3 Road Network Development Plan

The existing road network of ward no.3 is 5.91 km where 4.74 km road is pucca, 0.20 is semi-pucca and 0.97 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 24.17 acres of land is allotted for ward no 03. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-03 is shown in table 14-9 and Map 14-7.

Table 14-10: Proposal of Roads for Ward-03

ID	Existing Road Type	Proposed Road Type	Length (k.m)	Proposed Width (ft)	Proposal Type
WR-1	Primary Road	Widening Road	4.521	100	Pucca
WR-246	Secondary Road	Widening Road	0.870	40	Pucca
WR-274	Local/Access Road	Widening Road	0.270	20	Pucca
WR-289	Local/Access Road	Widening Road	0.289	20	Pucca
WR-290	Secondary Road	Widening Road	0.376	40	Pucca
WR-313	Secondary Road	Widening Road	2.520	50	Pucca
WR-321	Local/Access Road	Widening Road	0.464	40	Pucca
WR-326	Local/Access Road	Widening Road	0.342	20	Pucca
WR-346	Secondary Road	Widening Road	1.542	40	Pucca
NR-1	Local/Access Road	New Road	0.265	20	Pucca
NR-2	Local/Access Road	New Road	0.307	20	Pucca
NR-3	Local/Access Road	New Road	0.452	20	Pucca
NR-21	Secondary Road	New Road	1.000	40	Pucca
NR-39	Secondary Road	New Road	1.202	40	Pucca
NR-96	Local/Access Road	New Road	0.342	20	Pucca
NR-84	Local/Access Road	New Road	0.532	20	Pucca
NR-83	Local/Access Road	New Road	0.058	20	Pucca
NR-82	Local/Access Road	New Road	0.106	20	Pucca

*** Road length ≥ 200 meter incorporated here. Detail was given in Appendix*

14.11.4 Drainage Development Plan

Drain is necessary for discharge all its waste water and storm water. The plan proposes new drains for ward no. 03 which will be developed during the different phase. The natural sources of drainage are playing the critical roles in drainage plan.

Table 14-11: Proposal of Drain for Ward-03

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Primary Drain	PD-1	473.438	River	0.80
Secondary Drain	SD-14	455.921	River	0.80

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Secondary Drain	SD-7	1251.623	Khal	0.80
Tertiary Drain	TD-20	256.700	River	0.80
Tertiary Drain	TD-21	44.396	River	0.80
Tertiary Drain	TD-22	36.598	River	0.80
Tertiary Drain	TD-24	56.915	River	0.80
Tertiary Drain	TD-25	50.153	River	0.80
Tertiary Drain	TD-31	270.539	Khal	0.80
Tertiary Drain	TD-32	330.352	Khal	0.80
Tertiary Drain	TD-33	205.428	River	0.80

14.11.5 Urban Services Development Plan of ward no-03

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 03 has much more potentiality due to situated in Natore-Singra road. Maximum number of service is proposed both side of Natore-Singra road. Primary school, High school, tempo stand, Fire Service, Playground, Neighborhood Park, Clinic and Rickshaw stand are proposed here. The proposal for service facilities of ward no 03 is shown in table 14-11 together with mouza name and plot number.

Table 14-12: Proposal for Other Facilities of Ward-03

	Use	Plot No.	Area (Acres)	Mouza Name
WC-3	Ward Centre	Partial 11-14,17	1.00	Dakhin Domdoma_276_00
PS-3	Primary School	114,115,116(p)	4.57	Dakhin Domdoma_276_00
PL-1	Playground	50(p),51(p),107-110(p)(P), 1064(P), 1066(P)	3.69	Dakhin Domdoma_276_00
FS-1	Fire Service	Partial-161-163,150	1.00	Dakhin Domdoma_276_00
HS-2	High School	130(p),175(p),9999(p)1241,1057,1026,1020	1.00	Falia_259_00
NP-5	Neighbourhood Park	Partial 1003,1005,1013	1.61	Dakhin Domdoma_276_00
TS-6	Tempo Stand	Partial-131,133	0.25	Falia_259_00
COC-1	Community Clinic	Partial-775	0.25	Dakhin Domdoma_276_00
NM-3	Neighbourhood Market	Partial-15-18,23-24	0.89	Dakhin Domdoma_276_00
LPP	Low Income Housing Project	Partial 171-173,176,178,179	3.00	Dakhin Domdoma_276_00
OHR	Old Home Rehabilitation	Partial 36-40	3.00	Bosta_348_00
RS-5	Rickshaw/ Van Stand	Partial-790,791,799,800,1035	0.23	Dakhin Domdoma_276_00
RS-4	Rickshaw/ Van Stand	Partial-125,126,130	0.25	Falia_259_00

Map 14-7: The Proposed Urban Services and Drainage Network Facilities Map of Ward-03

Ward Action Plan for Ward-04

14.12 Demographic Conditions of Ward-04

Ward No. 04 is located at the extreme East of Singra Paurashava. The area of the Ward is 298.89 acres. The Population was 3241 in 2001 and 4734 in 2011 according to BBS. Population projection shows 10214 population in 2031. The density will be 34 persons per acre in 2031.

Table 14-13: Population Statistics of Ward No. 04

Item	Year	
	2011	2031
Area (acre)	298.89	298.89
Population	4734	10214
Density of Population (acre)	16	34

Source: BBS 2001 and 2011

14.13 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 6.24 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 4.65 km road is pucca, 0.41 is semi-pucca and 1.17 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 16 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.14 Ward Action Plan Proposals

14.14.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 200.57 acres which is 7.41% of the total land. The second major land use is Residential land and occupying about 57.85 acres of the Paurashava area. Besides, there is about 24.76 acres water body, about 6.02 acres circulation network, about 3.47 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.14.2 Proposed Land Use Zoning

i) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers

44.75 acres of land delineated up to the year 2031 in Ward No. 04, considering standard provided by LGED.

ii) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 1.98 acres designated up to 2031.

iii) Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. Mixture of land uses will allow flexibility of development, instead of restricting development. This zone has an area of 1.43 acres designated up to 2031.

iv) Education & Research Zone

The total area under this use has been determined as 0.97 acres of land designated up to 2031.

v) Government Office

This zone covers all kinds of government offices in the town. The total area under this use has been proposed as 1.66 acres of land designated up to 2031.

vi) Rural Settlement

The total area under this use has been proposed as 18.62 acres which is most portion of this land use.

vii) Agricultural Zone

The Paurashava including Ward No. 04 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 162.74 acres that include existing and proposed land uses.

viii) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 22.84 acres.

ix) Health Services

Proposed plan suggests a community clinic in this ward with 1.01 acres of land of the whole ward.

x) Circulation Network

Existing and proposed roads covers a total of 23.88 acres of land of the whole ward.

xi) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 1.85 acres of land for open space.

Map 14-8: The Proposed Land Use Zoning Map of Ward-04

14.14.3 Road Network Development Plan

The existing road network of ward no.4 is 6.24 km where 4.65 km road is pucca, 0.41 is semi-pucca and 1.17 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 23.88 acres of land is allotted for ward no 04. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-04 is shown in table 14-13 and Map 14-9.

Table 14-14: Proposal of Roads for Ward-04

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (ft)	Proposal Type
Primary Road	Widening Road	WR-1	4.521	100	Pucca
Secondary Road	Widening Road	WR-99	0.521	30	Pucca
Local/Access Road	Widening Road	WR-122	0.219	20	Pucca
Secondary Road	Widening Road	WR-127	0.871	50	Pucca
Secondary Road	Widening Road	WR-158	0.392	40	Pucca
Secondary Road	Widening Road	WR-171	0.702	30	Pucca
Secondary Road	Widening Road	WR-179	0.444	30	Pucca
Secondary Road	Widening Road	WR-216	0.395	30	Pucca
Secondary Road	Widening Road	WR-218	0.203	30	Pucca
Secondary Road	New Road	NR-39	1.202	40	Pucca
Local/Access Road	New Road	NR-89	0.807	20	Pucca
Local/Access Road	New Road	NR-90	0.488	20	Pucca
Local/Access Road	New Road	NR-90	0.250	20	Pucca
Local/Access Road	New Road	NR-91	0.272	20	Pucca
Local/Access Road	New Road	NR-93	0.320	20	Pucca
Local/Access Road	New Road	NR-95	0.706	20	Pucca
Local/Access Road	New Road	NR-96	0.342	20	Pucca
Local/Access Road	New Road	NR-96	0.677	20	Pucca
Local/Access Road	New Road	NR-97	0.536	20	Pucca
Local/Access Road	New Road	NR-98	0.284	20	Pucca
Local/Access Road	New Road	NR-97	.535	20	Pucca
Local/Access Road	New Road	NR-96	.677	20	Pucca
Local/Access Road	New Road	NR-95	.706	20	Pucca
Local/Access Road	New Road	NR-93	.320	20	Pucca
Secondary Road	New Road	NR-85	1.093	50	Pucca
Local/Access Road	New Road	NR-84	.833	20	Pucca

** Road length ≥ 200 meter incorporated here. Detail was given in Appendix

14.14.4 Drainage Development Plan

Drain is necessary for discharge all its waste water and storm water. The plan proposes new drains for ward no. 04 which will be developed during the different phase. The natural sources of drainage are playing the critical roles in drainage plan.

Table 14-15: Proposal of Drains for Ward-04

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Primary Drain	PD-1	992.623	River	0.80
Primary Drain	PD-3	727.756	River	0.80
Secondary Drain	SD-13	374.274	River	0.80
Secondary Drain	SD-5	444.514	Khal	0.80
Tertiary Drain	SD-50	689.579	River	0.80
Secondary Drain	SD-7	44.644	Khal	0.80
Secondary Drain	SD-8	325.164	River	0.80
Tertiary Drain	TD-18	121.197	River	0.80
Tertiary Drain	TD-19	206.604	Khal	0.80
Tertiary Drain	TD-23	226.417	River	0.80
Tertiary Drain	TD-24	267.666	River	0.80

14.14.5 Urban Services Development Plan of ward no-04

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 04 has much more potentiality due to situated in Natore-Singra road. Maximum number of service is proposed both side of Natore-Singra road. Clinic, Nursery School, Tempo Stand, Rickshaw stand and ward centre are proposed here. The proposal for service facilities of ward no 04 is shown in table 14-15 together with mouza name and plot number.

Table 14-16: Proposal for Other Facilities of Ward-04

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-4	Ward Centre	Partial 4,5,395	1.00	Sola Kuri_345_00
CLN-1	Clinic	Partial-325	0.62	Boro Maguri_346_00 & Bosta_348_00
CLN-5	Clinic	Partial-395	0.11	Singra_342_00
CLN-6	Clinic	P-267	0.62	Kata Pukuria_338_00
TS-5	Tempo Stand	Partial-140-151	0.18	Balua Basua_341_00
NS-6	Nursery School	118-122,126(p),127(p)	0.27	Sola Kuri_345_00
RS-2	Rickshaw/ Van Stand	Partial-135,151	0.33	Singra_342_00

ID	Use	Plot No.	Area (Acres)	Mouza Name
TS-4	Tempo Stand	Partial-140-151	0.22	Singra_342_00
PAS-1	Passenger Shed	Partial-151	0.04	Singra_342_00

Map 14-9: The Proposed Urban Services and Drainage Network Facilities Map of Ward-04

Ward Action Plan for Ward-05

14.15 Demographic Conditions of Ward-05

Ward No. 05 is located at the middle part of Singra Paurashava. The area of the Ward is 52.53 acres. The Population was 1807 in 2001 and 1909 in 2011 according to BBS. Population projection shows 4119 population in 2031. The density will be 78 persons per acre in 2031.

Table 14-17: Population Statistics of Ward No. 05

Item	Year	
	2011	2031
Area (acre)	52.53	52.53
Population	1909	4119
Density of Population (acre)	36	78

Source: BBS 2001 and 2011

14.16 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 2.80 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 2.02 km road is pucca, 0.77 is semi-pucca and 0.04 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 36 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.17 Ward Action Plan Proposals

14.17.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 15.81 acres which is 0.58% of the total land. The second major land use is Residential land and occupying about 14.47 acres of the Paurashava area. Besides, there is about 8.39 acres water body, about 2.50 acres circulation network, about 7.05 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.17.2 Proposed Land Use Zoning

i) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers

12.66 acres of land delineated up to the year 2031 in Ward No. 05, considering standard provided by LGED.

ii) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 4.24 acres designated up to 2031.

iii) Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. Mixture of land uses will allow flexibility of development, instead of restricting development. This zone has an area of 0.95 acres designated up to 2031.

iv) Education & Research Zone

The total area under this use has been determined as 1.15 acres of land designated up to 2031.

v) Government Office

This zone covers all kinds of government offices in the town. The total area under this use has been proposed as 0.44 acres of land designated up to 2031.

vi) Rural Settlement

The total area under this use has been proposed as 4.21 acres which is most portion of this land use.

vii) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 7.95 acres.

viii) Health Services

Proposed plan suggests a community clinic in this ward with 0.09 acres of land of the whole ward.

ix) Circulation Network

Existing and proposed roads covers a total of 7.56 acres of land of the whole ward.

x) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 11.92 acres of land for open space.

Map 14-10: The Proposed Land Use Zoning Map of Ward-05

14.17.3 Road Network Development Plan

The existing road network of ward no.5 is 2.80 km where 2.02 km road is pucca, 0.77 is semi-pucca and 0.04 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 7.56 acres of land is allotted for ward no 05. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-05 is shown in table 14-17 and Map 14-11.

Table 14-18: Proposal of Roads for Ward-05

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (ft)	Proposal Type
Secondary Road	Widening Road	WR-127	0.871	50	Pucca
Secondary Road	Widening Road	WR-190	0.286	40	Pucca
Local/Access Road	Widening Road	WR-223	0.218	20	Pucca
Local/Access Road	Widening Road	WR-224	0.213	20	Pucca
Local/Access Road	Widening Road	WR-229	0.212	20	Pucca
Local/Access Road	Widening Road	WR-234	0.252	20	Pucca
Secondary Road	Widening Road	WR-313	2.520	50	Pucca
Local/Access Road	New Road	NR-20	0.304	20	Pucca
Secondary Road	New Road	NR-33	0.828	40	Pucca
Local/Access Road	New Road	NR-79	0.233	20	Pucca

*** Road length $\geq$ 200 meter incorporated here. Detail was given in Appendix*

14.17.4 Drainage Development Plan

Drain is necessary for discharge all its waste water and storm water. The plan proposes new drains for ward no. 05 which will be developed during the different phase. The natural sources of drainage are playing the critical roles in drainage plan.

Table 14-19: Proposal of Drain for Ward-05

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Secondary Drain	SD-13	126.879	River	0.80
Secondary Drain	SD-2	118.509	River	0.80
Secondary Drain	SD-5	376.428	Khal	0.80
Secondary Drain	SD-6	323.500	River	0.80
Tertiary Drain	TD-14	157.706	River	0.80
Tertiary Drain	TD-15	81.249	River	0.80
Tertiary Drain	TD-16	166.965	River	0.80

14.17.5 Urban Services Development Plan of ward no-05

The urban services is the pre condition of any potential development. The development is not same all of the ward. Park, Post Office , ward centre and Waste Transfer Station are proposed here. The proposal for service facilities of ward no 05 is shown in table 14-19 together with mouza name and plot number.

Table 14-20: Proposal for Other Facilities of Ward-05

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-5	Ward Centre	Partial-131,148,149	0.53	Hat Singra_339_00
PO-1	Post Office	Partial-110,111	0.11	Hat Singra_339_00
NP-2	Neighborhood Park	Partial 1-8,21-36	11.20	Poran Hati_334_00
WTS-2	Waste Transfer Station	Partial-1	0.13	Sundarpur_113_03

Map 14-11: The Proposed Urban Services and Drainage Network Facilities Map of Ward-05

Ward Action Plan for Ward-06

14.18 Demographic Conditions of Ward-06

Ward No. 06 is located more or less at the south part of Singra Paurashava. The area of the Ward is 521.98 acres. The Population was 2443 in 2001 and 2414 in 2011 according to BBS. Population projection shows 5209 population in 2031. The density will be 10 persons per acre in 2031.

Table 14-21: Population Statistics of Ward No. 06

Item	Year	
	2011	2031
Area (acre)	704.64	704.64
Population	2414	5209
Density of Population (acre)	5	10

Source: BBS 2001 and 2011

14.19 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 8.39 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 4.38 km road is pucca, 0.21 is semi-pucca and 3.79 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 5 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.20 Ward Action Plan Proposals

14.20.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 370.12 acres which is 13.68% of the total land. The second major land use is Residential land and occupying about 41.11 acres of the Paurashava area. Besides, there is about 92.09 acres water body, about 7.19 acres circulation network, about 0.58 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.20.2 Proposed Land Use Zoning

xi) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers

132.63 acres of land delineated up to the year 2031 in Ward No. 06, considering standard provided by LGED.

xii) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 4.47 acres designated up to 2031.

xiii) Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. Mixture of land uses will allow flexibility of development, instead of restricting development. This zone has an area of 0.29 acres designated up to 2031.

xiv) Education & Research Zone

The total area under this use has been determined as 13.30 acres of land designated up to 2031.

xv) Government Office

This zone covers all kinds of government offices in the town. The total area under this use has been proposed as 0.17 acres of land designated up to 2031.

xvi) Rural Settlement

The total area under this use has been proposed as 22.80 acres which is most portion of this land use.

xvii) Agricultural Zone

The Paurashava including Ward No. 06 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 195.95 acres that include existing and proposed land uses.

xviii) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 90.22 acres.

xix) Health Services

Proposed plan suggests a community clinic in this ward with 2.85 acres of land of the whole ward.

xx) Circulation Network

Existing and proposed roads covers a total of 26.31 acres of land of the whole ward.

xxi) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 25.57 acres of land for open space.

Map 14-12: The Proposed Land Use Zoning Map of Ward-06

14.20.3 Road Network Development Plan

The existing road network of ward no.6 is 8.39 km where 4.38 km road is pucca, 0.21 is semi-pucca and 3.79 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 26.31 acres of land is allotted for ward no 06. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-06 is shown in table 14-21 and Map 14-13.

Table 14-22: Proposal of Roads for Ward-06

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (ft)	Proposal Type
Local/Access Road	Widening Road	WR-13	2.009	20	Pucca
Secondary Road	Widening Road	WR-18	2.912	40	Pucca
Secondary Road	Widening Road	WR-56	1.033	30	Pucca
Local/Access Road	Widening Road	WR-69	0.825	20	Pucca
Local/Access Road	Widening Road	WR-77	0.308	20	Pucca
Primary Road	Widening Road	WR-1	4.521	100	Pucca
Secondary Road	Widening Road	WR-201	0.497	30	Pucca
Secondary Road	New Road	NR-17	1.328	50	Pucca
Secondary Road	New Road	NR-18	0.313	30	Pucca
Secondary Road	New Road	NR-19	0.745	30	Pucca
Secondary Road	New Road	NR-33	0.828	40	Pucca
Local/Access	New Road	NR-90	.488	20	Pucca
Local/Access	New Road	NR-89	.806	20	Pucca

*** Road length $\geq$ 200 meter incorporated here. Detail was given in Appendix*

14.20.4 Drainage Development Plan

Drain is necessary for discharge all its waste water and storm water. The plan proposes new drains for ward no. 06 which will be developed during the different phase. The natural sources of drainage are playing the critical roles in drainage plan.

Table 14-23: Proposal of Drain for Ward-06

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Primary Drain	PD-2	2.889	River	0.80
Primary Drain	PD-3	2.908	River	0.80
Secondary Drain	SD-12	5.562	River	0.80
Secondary Drain	SD-3	13.121	River	0.80
Tertiary Drain	TD-1	10.298	River	0.80
Tertiary Drain	TD-10	2.729	River	0.80

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Tertiary Drain	TD-11	5.929	River	0.80
Tertiary Drain	TD-2	16.326	River	0.80
Tertiary Drain	TD-3	0.506	River	0.80
Tertiary Drain	TD-40	456.260	River	0.80
Tertiary Drain	TD-41	225.046	River	0.80
Tertiary Drain	TD-5	1.427	River	0.80
Tertiary Drain	TD-6	5.131	River	0.80
Tertiary Drain	TD-7	5.324	River	0.80
Tertiary Drain	TD-9	4.165	River	0.80

14.20.5 Urban Services Development Plan of ward no-06

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 06 has much more potentiality due to situated in Natore-Singra road. Maximum number of service is proposed both side of Natore-Singra road. College, Clinic, Park, playground, Neighborhood market, Vocational Training Institute, Pump House and ward centre are proposed here. The proposal for service facilities of ward no 06 is shown in table 14-23 together with mouza name and plot number.

Table 14-24: Proposal for Other Facilities of Ward-06

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-5	Ward Centre	Partial-115	1.00	Baluvora_373_00
PLG-1	Playground	Partial 48,49,50,51,56,57,71,72, 73,74,75,76,77,81,82,83, 84,85,86,87,88,89,90,91, 92,476	4.85	Boro Sawail_387_01
PLG-2	Playground	Partial-195-203,236-245	7.16	Baluvora_373_00
CL-1	College	Partial-115,184-186,187- 191	6.72	Baluvora_373_00
VTI	Vocational Training Institute	Partial 115,178,179,180,184	4.47	Baluvora_373_00
NM-4	Neighborhood Market	Partial- 57-63	0.70	Patkol_372_00
NM-4	Neighborhood Market	Partial-92,93	2.53	Baluvora_373_00
PS-1	Primary School	2(P)	0.20	Poran Hati_334_00
NP-3	Neighborhood Park	20-22(p)	2.75	Baluvora_373_00
NP-4	Neighborhood Park	Partial-192-194,205-210	10.41	Baluvora_373_00
WPH-1	Water Pump House	115(P)	1.00	Baluvora_373_00
CLN-7	Clinic	Partial 261,285-289	1.00	Patkol_372_00
CLN-2	Clinic	Partial 41,43,58	1.74	Poran Hati_334_00
WPH-2	Water Pump House	Partial 263,266,281	1.00	Patkol_372_00

Map 14-13: The Proposed Urban Services and Drainage Network Facilities Map of Ward-06

Ward Action Plan for Ward-07

14.21 Demographic Conditions of Ward-07

Ward No. 07 is located at the Western part of Singra Paurashava. The area of the Ward is 192.47 acres. The Population was 2554 in 2001 and 2742 in 2011 according to BBS. Population projection shows 5916 population in 2031. The density will be 31 persons per acre in 2031.

Table 14-25: Population Statistics of Ward No. 07

Item	Year	
	2011	2031
Area (acre)	527.29	527.29
Population	2742	5916
Density of Population (acre)	14	31

Source: BBS 2001 and 2011

14.22 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 6.61 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 5.23 km road is pucca, 0.07 is semi-pucca and 1.30 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 14 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.23 Ward Action Plan Proposals

14.23.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 109.37 acres which is 4.04% of the total land. The second major land use is Residential land and occupying about 40.88 acres of the Paurashava area. Besides, there is about 32.31 acres water body, about 5.86 acres circulation network, about 0.62 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.23.2 Proposed Land Use Zoning

I) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers 0.02

acres of land delineated up to the year 2031 in Ward No. 07, considering standard provided by LGED.

li) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 1.09 acres designated up to 2031.

lii) Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. Mixture of land uses will allow flexibility of development, instead of restricting development. This zone has an area of 0.32 acres designated up to 2031.

liii) Education & Research Zone

The total area under this use has been determined as 2.58 acres of land designated up to 2031.

liv) Rural Settlement

The total area under this use has been proposed as 57.77 acres which is most portion of this land use.

lv) Agricultural Zone

The Paurashava including Ward No. 07 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 75.89 acres that include existing and proposed land uses.

lvi) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 31.52 acres.

lvii) Health Services

Proposed plan suggests a community clinic in this ward with 0.94 acres of land of the whole ward.

lviii) Circulation Network

Existing and proposed roads covers a total of 16.75 acres of land of the whole ward.

lix) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 3.44 acres of land for open space.

Map 14-14: The Proposed Land Use Zoning Map of Ward-07

14.23.3 Road Network Development Plan

The existing road network of ward no.7 is 6.61 km where 5.23 km road is pucca, 0.07 is semi-pucca and 1.3 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 16.75 acres of land is allotted for ward no 07. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-07 is shown in table 14-25 and Map 14-15.

Table 14-26: Proposal of Roads for Ward-07

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (ft)	Proposal Type
Primary Road	Widening Road	WR-1	0.795	100	Pucca
Secondary Road	Widening Road	WR-105	0.807	30	Pucca
Secondary Road	Widening Road	WR-107	0.736	30	Pucca
Local/Access Road	Widening Road	WR-117	0.219	20	Pucca
Local/Access Road	Widening Road	WR-135	0.215	20	Pucca
Local/Access Road	Widening Road	WR-169	0.303	20	Pucca
Local/Access Road	Widening Road	WR-182	0.262	20	Pucca
Local/Access Road	Widening Road	WR-192	0.447	20	Pucca
Local/Access Road	Widening Road	WR-352	1.361	20	Pucca
Local/Access Road	New Road	NR-91	.345	20	Pucca

*** Road length $\geq$ 200 meter incorporated here. Detail was given in Appendix*

14.23.4 Drainage Development Plan

Drain is necessary for discharge all its waste water and storm water. The plan proposes new drains for ward no. 07 which will be developed during the different phase. The natural sources of drainage are playing the critical roles in drainage plan.

Table 14-27: Proposal of Drain for Ward-07

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Tertiary Drain	TD-42	224.865	River	0.80
Tertiary Drain	TD-43	367.916	River	0.80
Tertiary Drain	TD-44	179.656	River	0.80
Tertiary Drain	TD-45	119.192	River	0.80
Tertiary Drain	TD-46	332.816	River	0.80
Tertiary Drain	TD-47	278.329	River	0.80

14.23.5 Urban Services Development Plan of ward no-07

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 07 has much more potentiality due to situated in Natore-Singra road. Clinic, Neighborhood Park, Playground, Primary School, ward centre and Tempo stand are proposed here. The proposal for service facilities of ward no 07 is shown in table 14-27 together with mouza name and plot number.

Table 14-28: Proposal for Other Facilities of Ward-07

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-7	Ward Centre	Partial-1385-1387	0.65	Niagain_333_02
NS-1	Nursery School	1325(p),3007(p),1326(p),1327(p),	0.49	Niagain_333_02
CLN-3	Clinic	Partial-1446-1448,1453	0.94	Niagain_333_02
CLN-4	Clinic	Partial-1398,1411,1414	0.21	Niagain_333_02
NP-1	Neighborhood Park	1399,1400,1334(P),1336(p)	1.65	Niagain_333_02
PL-2	Playground	1391(p),1392-1393(p),1397(p)	1.87	Niagain_333_02
TS-1	Tempo Stand	Partial 1502,1504,1505,1395	0.25	Niagain_333_02

Map 14-15: The Proposed Urban Services and Drainage Network Facilities Map of Ward-07

Ward Action Plan for Ward-08

14.24 Demographic Conditions of Ward-08

Ward No. 08 is located at the extreme middle part of Singra Paurashava. The area of the Ward is 123.67 acres. The Population was 3259 in 2001 and 4730 in 2011 according to BBS. Population projection shows 10206 population in 2031. The density will be 83 persons per acre in 2031.

Table 14-29: Population Statistics of Ward No. 08

Item	Year	
	2011	2031
Area (acre)	123.67	123.67
Population	4730	10206
Density of Population (acre)	38	83

Source: BBS 2001 and 2011

14.25 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 6.66 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 4.76 km road is pucca, 1.21 is semi-pucca and 0.68 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 5 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.26 Ward Action Plan Proposals

14.26.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 27.12 acres which is 1.01% of the total land. The second major land use is Residential land and occupying about 51.39 acres of the Paurashava area. Besides, there is about 21.51 acres water body, about 5.61 acres circulation network, about 6.61 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.26.2 Proposed Land Use Zoning

i) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers

58.24 acres of land delineated up to the year 2031 in Ward No. 08, considering standard provided by LGED.

ii) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 5.13 acres designated up to 2031.

iii) Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. Mixture of land uses will allow flexibility of development, instead of restricting development. This zone has an area of 2.18 acres designated up to 2031.

iv) Education & Research Zone

The total area under this use has been determined as 8.17 acres of land designated up to 2031.

iv) Government Office

This zone covers all kinds of government offices in the town. The total area under this use has been proposed as 1.66 acres of land designated up to 2031.

v) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 19.56 acres.

vi) Health Services

Proposed plan suggests a community clinic in this ward with 2.29 acres of land of the whole ward.

vii) Circulation Network

Existing and proposed roads covers a total of 19.63 acres of land of the whole ward.

viii) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 2.93 acres of land for open space.

Map 14-16: The Proposed Land Use Zoning Map of Ward-08

14.26.3 Road Network Development Plan

The existing road network of ward no.8 is 6.66 km where 4.76 km road is pucca, 1.21 is semi-pucca and 0.68 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 19.63 acres of land is allotted for ward no 08. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-08 is shown in table 14-29 and Map 14-17.

Table 14-30: Proposal of Roads for Ward-08

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (ft)	Proposal Type
Secondary Road	Widening Road	WR-2	0.496	50	Pucca
Local/Access Road	Widening Road	WR-80	0.205	20	Pucca
Local/Access Road	Widening Road	WR-82	0.233	20	Pucca
Secondary Road	Widening Road	WR-83	0.421	30	Pucca
Local/Access Road	Widening Road	WR-93	0.262	20	Pucca
Primary Road	Widening Road	WR-1	0.731	100	Pucca
Local/Access Road	Widening Road	WR-108	0.280	20	Pucca
Secondary Road	Widening Road	WR-127	0.321	50	Pucca
Local/Access Road	Widening Road	WR-134	0.256	20	Pucca
Secondary Road	New Road	NR-16	0.247	50	Pucca
Secondary Road	New Road	NR-26	0.205	40	Pucca
Local/Access Road	New Road	NR-30	0.224	20	Pucca
Secondary Road	New Road	NR-33	0.293	40	Pucca
Secondary Road	New Road	NR-34	0.233	40	Pucca

*** Road length ≥ 200 meter incorporated here. Detail was given in Appendix*

14.26.4 Drainage Development Plan

Drain is necessary for discharge all its waste water and storm water. The plan proposes new drains for ward no. 08 which will be developed during the different phase. The natural sources of drainage are playing the critical roles in drainage plan.

Table 14-31: Proposal of Drain for Ward-08

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Primary Drain	PD-1	372.469	River	0.80
Primary Drain	PD-2	354.829	River	0.80
Primary Drain	PD-3	384.355	River	0.80
Secondary Drain	SD-10	367.053	River	0.80
Secondary Drain	SD-11	212.989	River	0.80
Secondary Drain	SD-13	286.697	River	0.80

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Secondary Drain	SD-2	303.611	River	0.80
Secondary Drain	SD-3	23.073	River	0.80
Secondary Drain	SD-4	167.457	River	0.80
Secondary Drain	SD-9	36.323	River	0.80
Tertiary Drain	SD-9	364.269	River	0.80
Tertiary Drain	TD-1	352.038	River	0.80
Tertiary Drain	TD-12	56.923	River	0.80
Tertiary Drain	TD-13	353.544	River	0.80
Tertiary Drain	TD-2	493.626	River	0.80

14.26.5 Urban Services Development Plan of ward no-08

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 08 has much more potentiality due to situated in Natore-Singra road. Maximum number of service is proposed both side of Natore-Singra road. Eidgah, Clinic, Neighbourhood market, Central Park, Nursery School, Super Market, Tempo stand and waste transfer station are proposed here. Bus terminal is also located here that increases the potentiality of this ward. The proposal for service facilities of ward no 08 is shown in table 14-31 together with mouza name and plot number.

Table 14-32: Proposal for Other Facilities of Ward-08

ID	Use	Plot No.	Area (Acres)	Mouza Name
CP-1	Central Park	151(p),165-167(p)	2.72	Singra_342_00
WC-8	Ward Center	Partial-159,184-186	1.69	Singra_342_00
CLN-5	Clinic	Partial-394-398,172-176	2.12	Singra_342_00
NM-5	Neighbourhood market	Partial-199,203,204,208	0.45	Singra_342_00
SM-1	Super Market	Partial-199	0.65	Singra_342_00
PS-3	Primary School	Partial-400-403,437-442,188-190	5.61	Singra_342_00
NS-2	Nursery School	348,379(p),378(p)343,345,346,351	0.34	Singra_342_00
TS-2	Tempo Stand	Partial-190-191,197-199	0.48	Singra_342_00
WTS-1	Waste Transfer Station	Partial- 385	0.14	Singra_342_00

Map 14-17: The Proposed Urban Services and Drainage Network Facilities Map of Ward-08

Ward Action Plan for Ward-09

14.27 Demographic Conditions of Ward-09

Ward-9 is located at the more or less south part of Singra Paurashava. The area of the Ward is 275.57 acres. The Population was 2453 in 2001 and 3343 in 2011 according to BBS. Population projection shows 7213 population in 2031. The density will be 41 persons per acre in 2031.

Table 14-33: Population Statistics of Ward No. 09

Item	Year	
	2011	2031
Area (acre)	275.57	275.57
Population	3343	7213
Density of Population (acre)	19	41

Source: BBS 2001 and 2011

14.28 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 5.17 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 3.46 km road is pucca, 0.02 is semi-pucca and 1.69 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 19 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.29 Ward Action Plan Proposals

14.29.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 204.71 acres which is 7.57% of the total land. The second major land use is Residential land and occupying about 46.52 acres of the Paurashava area. Besides, there is about 14.15 acres water body, about 3.71 acres circulation network, about 1.12 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.29.2 Proposed Land Use Zoning

i) Urban Residential Zone

Urban residential zone refers to all categories of urban residential areas, including existing ones and the residential land use proposed under the present master plan. In total this zone covers 103.57 acres of land delineated up to the year 2031 in Ward No. 09, considering standard provided by LGED.

ii) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 3.62 acres designated up to 2031.

iii) Mixed Use Zone

Mixed use zones have been recommended to allow some flexibility in development. Mixture of land uses will allow flexibility of development, instead of restricting development. This zone has an area of 0.33 acres designated up to 2031.

iv) Education & Research Zone

The total area under this use has been determined as 6.69 acres of land designated up to 2031.

v) Rural Settlement

The total area under this use has been proposed as 0.76 acres which is most portion of this land use.

vi) Agricultural Zone

The Paurashava including Ward No. 09 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 103.43 acres that include existing and proposed land uses.

vii) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 13.71 acres.

viii) Health Services

Proposed plan suggests a community clinic in this ward with 1.18 acres of land of the whole ward.

ix) Circulation Network

Existing and proposed roads covers a total of 26.31 acres of land of the whole ward.

x) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 12.07 acres of land for open space.

Map 14-18: The Proposed Land Use Zoning Map of Ward-09

14.29.3 Road Network Development Plan

The existing road network of ward no.9 is 5.17 km where 3.46 km road is pucca, 0.02 is semi-pucca and 1.69 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 26.31 acres of land is allotted for ward no 09. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-09 is shown in table 14-33 and Map 14-19.

Table 14-34: Proposal of Roads for Ward-09

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (FT)	Proposal Type
Secondary Road	New Road	NR-12	0.321	20	Pucca
Local/Access Road	New Road	NR-15	0.289	20	Pucca
Secondary Road	New Road	NR-17	1.253	50	Pucca
Secondary Road	New Road	NR-26	1.159	40	Pucca
Local/Access Road	New Road	NR-28	0.228	20	Pucca
Local/Access Road	New Road	NR-67	0.268	20	Pucca
Local/Access Road	New Road	NR-68	0.420	20	Pucca
Secondary Road	New Road	NR-69	0.223	40	Pucca
Secondary Road	Widening Road	WR-2	1.225	50	Pucca
Local/Access Road	Widening Road	WR-39	0.316	20	Pucca
Local/Access Road	Widening Road	WR-43	0.242	20	Pucca
Local/Access Road	Widening Road	WR-58	0.214	20	Pucca
Local/Access Road	Widening Road	WR-61	0.356	20	Pucca
Local/Access Road	Widening Road	WR-62	0.222	20	Pucca
Local/Access Road	Widening Road	WR-65	0.310	20	Pucca
Local/Access Road	New Road	NR-87	.155	20	Pucca
Secondary Road	New Road	NR-85	.784	50	Pucca

*** Road length ≥ 200 meter incorporated here. Detail was given in Appendix*

14.29.4 Drainage Development Plan

Drain is necessary for discharge all its waste water and storm water. The plan proposes new drains for ward no. 09 which will be developed during the different phase. The natural sources of drainage are playing the critical roles in drainage plan.

Table 14-35: Proposal of Drain for Ward-09

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Secondary Drain	SD-10	70.704	River	0.80
Secondary Drain	SD-12	381.596	River	0.80
Secondary Drain	SD-9	1098.622	River	0.80

Drain Type	ID	Length (m)	Outfall	Average Width (m)
Tertiary Drain	TD-10	242.934	River	0.80
Tertiary Drain	TD-11	188.304	River	0.80
Tertiary Drain	TD-3	313.159	River	0.80
Tertiary Drain	TD-36	413.080	River	0.80
Tertiary Drain	TD-36	395.581	River	0.80
Tertiary Drain	TD-37	299.487	River	0.80
Tertiary Drain	TD-38	251.678	River	0.80
Tertiary Drain	TD-4	80.533	River	0.80
Tertiary Drain	TD-5	282.082	River	0.80
Tertiary Drain	TD-6	448.751	River	0.80
Tertiary Drain	TD-7	383.041	River	0.80
Tertiary Drain	TD-8	274.419	River	0.80
Tertiary Drain	TD-9	202.557	River	0.80

14.29.5 Urban Services Development Plan of ward no-09

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 09 has much more potentiality due to situated in Natore-Singra road. Stadium, Neighbourhood Market, Nursery, Playground, Neighbourhood Park, Community Centre, Corner Shop, Clinic, Rickshaw Stand, Tempo Stand and ward centre are proposed here. The proposal for service facilities of ward no 09 is shown in table 14-35 together with mouza name and plot number.

Table 14-36: Proposal for Other Facilities of Ward-09

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-9	Ward Centre	Partial-186-192	1.00	Sola Kuri_345_00
ST-1	Stadium	40-47(p),50-52(p)	6.45	Sola Kuri_345_00
NM-4	Neighbourhood Market	Partial-158,161,231,233	1.00	Chak Singra_344_00
NS-5	Nursery	Partial-238-247	2.09	Chak Singra_344_00
PL-6	Playground	Partial 180,181,182,183,204,208,209,210,211,212,213,214,216,217,218,219,220,221,222,223,224,225,226,227,228,244,246,251	4.76	Chak Singra_344_00
NP-4	Neighbourhood Park	Partial 242,261,264,265,268,274	3.3	Sola Kuri_345_00
NM-3	Neighbourhood Market	Partial 158,161,231-233	0.99	Chak Singra_344_00

ID	Use	Plot No.	Area (Acres)	Mouza Name
NM-14	Neighbourhood Market	Partial-88-97	1.27	Sohag Bari_371_00
CS-1	Corner Shop	Partial 357,361	0.50	Sola Kuri_345_00
RS-1	Rickshaw Stand	Partial-224,225,231,232	0.25	Sola Kuri_345_00
CC-1	Community Centre	Partial-374,380,386	1.00	Sola Kuri_345_00
MD-2	Madrasa	Partial-305-307	1.92	Sola Kuri_345_00
TS-2	Tempo Stand	Partial-378-380,384	0.25	Partial-378-380,384

Map 14-19: The Proposed Urban Services and Drainage Network Facilities Map of Ward-09

Ward Action Plan for Ward-10

14.30 Demographic Conditions of Ward-10

Ward No. 10 is located at the Southern part of Singra Paurashava. The area of the Ward is 64.90 acres. The Population was 1248 in 2011 according to BBS after declaration of ward 10. Population projection shows 2693 population in 2031. The density will be 25 persons per acre in 2031.

Table 14-37: Population Statistics of Ward No. 010

Item	Year	
	2011	2031
Area (acre)	64.90	64.90
Population	1248	2693
Density of Population (acre)	12	25

Source: BBS 2001 and 2011

14.31 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 2.83 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 1.70 km road is pucca and 1.12 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 12 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.32 Ward Action Plan Proposals

14.32.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 32.20 acres which is 1.19% of the total land. The second major land use is Residential land and occupying about 23.86 acres of the Paurashava area. Besides, there is about 5.71 acres water body, about 1.92 acres circulation network, about 0.08 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.32.2 Proposed Land Use Zoning

i) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 0.88 acres designated up to 2031.

ii) Education & Research Zone

The total area under this use has been determined as 6.84 acres of land designated up to 2031.

iii) Rural Settlement

The total area under this use has been proposed as 22.36 acres which is most portion of this land use.

iv) Agricultural Zone

The Paurashava including Ward No. 10 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 15.67 acres that include existing and proposed land uses.

v) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 5.28 acres.

vi) Health Services

Proposed plan suggests a community clinic in this ward with 0.99 acres of land of the whole ward.

vii) Circulation Network

Existing and proposed roads covers a total of 8.08 acres of land of the whole ward.

viii) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 3.58 acres of land for open space.

Map 14-20: The Proposed Land Use Zoning Map of Ward-10

14.32.3 Road Network Development Plan

The existing road network of ward no.9 is 2.83 km where 1.70 km road is pucca and 1.12 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 8.08 acres of land is allotted for ward no 10. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-10 is shown in table 14-37 and Map 14-21

Table 14-38: Proposal of Roads for Ward-10

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (FT)	Proposal Type
Secondary Road	Widening Road	WR-2	1.518	50	Pucca
Local/Access Road	Widening Road	WR-10	0.255	20	Pucca
Secondary Road	New Road	NR-99	.118	40	Pucca
Local/Access Road	New Road	NR-86	.718	20	Pucca
Secondary Road	New Road	NR-85	.113	50	Pucca

*** Road length $\geq$ 200 meter incorporated here. Detail was given in Appendix*

14.32.4 Urban Services Development Plan of ward no-10

The urban services is the pre condition of any potential development. The development is not same all of the ward. Ward no 10 has less potentiality. Primary school, High school, Neighbourhood Market, Playground, Neighborhood Park, Clinic, ward centre and tempo stand are proposed here. The proposal for service facilities of ward no 10 is shown in table 14-38 together with mouza name and plot number.

Table 14-39: Proposal for Other Facilities of Ward-10

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-10	Ward Centre	Partial-83-88,91	0.60	Katua Bari_370_00
HS-2	High School	Partial 152,153,154,156,157,158,159,160,161,162,163	2.64	Par Sawail_369_01
CLN-6	Clinic	Partial-132,136,139,142,143	1.00	Katua Bari_370_00
NS-4	Nursery school	68(p),69(p),101(p)	0.50	Par Sawail_369_01
PL-4	Play ground	139-142(p),132(p)	1.42	Par Sawail_369_01
NM-2	Neighborhood market	Partial- 151,152	0.12	Par Sawail_369_01
NM-7	Neighborhood market	Partial-138-143	0.54	Katua Bari_370_00
NP-7	Neighborhood Park	Partial-98,101-107,155-156	2.16	Par Sawail_369_01
TS-6	Tempo Stand	Partial-111,114,145-148	0.46	Par Sawail_369_01

Map 14-21: The Proposed Urban Services and Drainage Network Facilities Map of Ward-10

Ward Action Plan for Ward-11

14.33 Demographic Conditions of Ward-11

Ward-11 is located at the South-West part of Singra Paurashava. The area of the Ward is 172.90 acres. The Population was 2041 in 2011 according to BBS. Population projection shows 4404 population in 2031. The density will be 17 persons per acre in 2031.

Table 14-40: Population Statistics of Ward No. 11

Item	Year	
	2011	2031
Area (acre)	172.90	172.90
Population	2041	4404
Density of Population (acre)	8	17

Source: BBS 2001 and 2011

14.34 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 4.42 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory. Only about 2.42 km road is pucca and 1.99 km road is Katcha.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 8 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.35 Ward Action Plan Proposals

14.35.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 89.21 acres which is 3.29% of the total land. The second major land use is Residential land and occupying about 29.85 acres of the Paurashava area. Besides, there is about 47.09 acres water body, about 3.32 acres circulation network, about 0.57 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.35.2 Proposed Land Use Zoning

i) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 3.27 acres designated up to 2031.

ii) Education & Research Zone

The total area under this use has been determined as 5.72 acres of land designated up to 2031.

iii) Rural Settlement

The total area under this use has been proposed as 62.10 acres which is most portion of this land use.

iv) Agricultural Zone

The Paurashava including Ward No. 11 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 33.49 acres that include existing and proposed land uses.

v) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 46.44 acres.

vi) Health Services

Proposed plan suggests a community clinic in this ward with 2.03 acres of land of the whole ward.

vii) Circulation Network

Existing and proposed roads covers a total of 30.32 acres of land of the whole ward.

viii) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 6.96 acres of land for open space.

Map 14-22: The Proposed Land Use Zoning Map of Ward-11

14.35.3 Road Network Development Plan

The existing road network of ward no.11 is 4.42 km where 2.42 km road is pucca and 1.99 km road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 10.32 acres of land is allotted for ward no 11. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-11 is shown in table 14-40 and Map 14-23.

Table 14-41: Proposal of Roads for Ward-11

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (FT)	Proposal Type
Local/Access Road	Widening Road	WR-355	0.598	20	Pucca
Secondary Road	Widening Road	WR-9	0.587	40	Pucca
Local/Access Road	Widening Road	WR-12	0.569	20	Pucca
Secondary Road	Widening Road	WR-18	1.097	40	Pucca
Local/Access Road	Widening Road	WR-20	0.316	20	Pucca
Local/Access Road	Widening Road	WR-25	0.203	20	Pucca
Local/Access Road	New Toad	NR-70	0.330	20	Pucca
Secondary Road	New Road	NR-99	.352	40	Pucca
Local/Access Road	New Road	NR-80	.128	20	Pucca

*** Road length≥ 200 meter incorporated here. Detail was given in Appendix*

14.35.4 Urban Services Development Plan of ward no-11

The urban services is the pre condition of any potential development. The development is not same all of the ward. Primary school, Neighbourhood Market, Neighborhood Park, Clinic, ward centre and tempo stand are proposed here. The proposal for service facilities of ward no 11 is shown in table 14-41 together with mouza name and plot number.

Table 14-42: Proposal for Other Facilities of Ward-11

ID	Use	Plot No.	Area (Acres)	Mouza Name
WC-11	Ward Centre	Partial-259,290-292	1.00	Katua Bari_370_00
NP-7	Neighborhood Park	Partial-254-281	6.91	Boro Sawail_387_01
CLN-4	Clinic	Partial-306,307,309	2.03	Katua Bari_370_00
TS-7	Tempo Stand	Partial-255-257	0.40	Katua Bari_370_00
NM-8	Neighbourhood Market	Partial-231,232,234-238	1.52	Boro Sawail_387_01
NM-9	Neighbourhood Market	Partial-308-310,316-319,,187-190	1.44	Boro Sawail_387_01
PS-2	Primary School	238,242,245,246,250(p),247(p),251	2.45	Boro Sawail_387_01

Map 14-23: The Proposed Urban Services and Drainage Network Facilities Map of Ward-11

Ward Action Plan for Ward-12

14.36 Demographic Conditions of Ward-12

Ward-12 is located at the South-West part of Singra Paurashava. The area of the Ward is 179.63 acres. The Population was 1442 in 2011 according to BBS. Population projection shows 3111 population in 2031. The density will be 17 persons per acre in 2031.

Table 14-43: Population Statistics of Ward No. 12

Item	Year	
	2011	2031
Area (acre)	179.63	179.63
Population	1442	3111
Density of Population (acre)	8	17

Source: BBS 2001 and 2011

14.37 Critical Issues and Opportunities of the Ward

a. Critical Issues

i. Problems of Road Infrastructure

The ward is not served by adequate number of roads. The total length of roads in the ward is only 2.63 km. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. All these will pose serious problems in movement when population rises in the ward. Quality of roads on average is not satisfactory.

ii. Poor Drainage

The ward does not have adequate drainage network serving the entire area. All the households do not have drainage outlet to discharge their waste water. Lack of drainage, though, is not a serious problem now but will emerge as a critical problem as density of population increases in future. In future due to construction the net run off area will increase that will cause water logging at places. So, necessary arrangements will have to be made now to get rid of future drainage problems.

iii. Haphazard Development

Like all other urban areas, unplanned development is a typical characteristic of this ward. Land owners are building their houses and structures anywhere. There is no land use plan, no adherences to building constructions are observed. This is not only destroying the aesthetic of the area but also its livable environment.

iv. Water Supply

Like all other wards water supply is also a critical problem in this ward. Surface water is the main source of drinking and washing. When population will increase the existing ponds will be inadequate to supply adequate water for the local people that will lead to severe water crisis. More over, there are arrangements for proper maintenance of the ponds. There is likelihood that without proper maintenance caretaking the ponds might get polluted by unhygienic use of water that will endanger health of the local people.

v. Low Density of Population: Problem for Providing Infrastructure

Infrastructure development is not cost effective if the density of population remains very low. The cost of service line is the same for all sizes of population. So, if the population size is small more cost has to be incurred per head of population for providing infrastructure, which is not cost effective.

vi. Lack of Threshold Population for Business

The town possesses a very low level of population which is not adequate to run large retail business activities. This size of population will not help grow the local economy grow. Besides, the average income of the people is also very low which is not conducive to economic flourishing of the town. Higher the size of population more demand is created for goods and services leading to more economic activities and employment. No urban centre can flourish without adequate economic prosperity.

b. Development Opportunities

i. Low Density of Population

The present density of population in the ward is low, only 8 persons /acre. From environmental point of view this of population can create a very livable environment for the area with respect to ventilation, use of road and other basic services.

ii. Excellent External Connectivity

Dhaka is only 5-6 hours journey from Singra. It takes about 1 hour to reach Natore, the district headquarters.

iii. Potential for Small Scale Manufacturing

Cheap labour, availability of raw materials can help grow small scale manufacturing in this town. Jewelry, handicrafts of different kinds, small engineering can be developed here. This, however, would require local initiative. Local entrepreneurs may be provided with small capital to serve as incentive.

14.38 Ward Action Plan Proposals

14.38.1 Riview of Existing Land Use

Study of existing land use of the ward reveals that major land use goes to Agricultural land and it is 138.94 acres which is 5.13% of the total land. The second major land use is water body and occupying about 22.93 acres of the Paurashava area. Besides, there is about 13.92 acres Residential land, about 2.29 acres circulation network, about 0.73 acres commercial activities and other lands are being used for education, community service, government services, manufacturing or industry, service activity, Urban green space and vacant.

14.38.2 Proposed Land Use Zoning

i) Commercial Zone

The commercial zone is intended to provide locations, where commercial activities including retails can be set up and function, without creating hazards to surrounding land uses. This zone has an area of 2.78 acres designated up to 2031.

ii) Education & Research Zone

The total area under this use has been determined as 0.42 acres of land designated up to 2031.

iii) Rural Settlement

The total area under this use has been proposed as 35.98 acres which is most portion of this land use.

iv) Agricultural Zone

The Paurashava including Ward No. 12 has a vast area of agricultural land that demands formation of a separate zone like, agriculture zone. The total area under this use has been estimated as 55.63 acres that include existing and proposed land uses.

v) Waterbody

The plan suggests preserving most of the water bodies for two purposes, first, to serve as source of water, second to serve as water retention area during monsoon. The ponds with an area equal to or more than 0.2 acres will be preserved as the water retention ponds. The proposed retention area covers 22.91 acres.

vi) Health Services

Proposed plan suggests a community clinic in this ward with 0.99 acres of land of the whole ward.

vii) Circulation Network

Existing and proposed roads covers a total of 6.15 acres of land of the whole ward.

viii) Open Space

In this ward there is no outdoor recreational space like park, playground etc. So the consultants accommodate 2.56 acres of land for open space.

Map 14-24: The Proposed Land Use Zoning Map of Ward-12

14.38.3 Road Network Development Plan

The existing road network of ward no.12 is 2.63 km all road is Katcha. This length of roads will not be able to serve the entire area in future when settlements will increase. New road spaces being created on community efforts are usually very narrow. Another problem of roads is that they are meandering in their layout. In road network development plan there is about 6.15 acres of land is allotted for ward no 12. All of the roads of this Paurashava will be constructed as a pucca road in different phases of plan. Road widening is considered all of the existing road. Proposals of Roads for ward no-12 is shown in table 14-43 and Map 14-25.

Table 14-44: Proposal of Roads for Ward-12

Existing Road Type	Proposed Road Type	ID	Length (k.m)	Proposed Width (FT)	Proposal Type
Local/Access Road	Widening Road	WR-355	1.996	20	Pucca
Local/Access Road	Widening Road	WR-13	0.572	20	Pucca
Local/Access Road	New Road	NR-75	0.489	30	Pucca
Local/Access Road	New Road	NR-80	0.284	20	Pucca
Local/Access Road	New Road	NR-98	.283	20	Pucca
Local/Access Road	New Road	NR-91	.271	20	Pucca
Local/Access Road	New Road	NR-90	.249	20	Pucca
Local/Access Road	New Road	NR-81	.49	20	Pucca

**** Road length $\geq$ 200 meter incorporated here. Detail was given in Appendix**

14.38.4 Urban Services Development Plan of ward no-12

The urban services is the pre condition of any potential development. The development is not same all of the ward. Neighbourhood Market, Playground, truck terminal, Clinic and waste dumping area are proposed here. The proposal for service facilities of ward no 12 is shown in table 14-44 together with mouza name and plot number.

Table 14-45: Proposal for Other Facilities of Ward-12

ID	Use	Plot No.	Area (Acres)	Mouza Name
TT-1	Truck Terminal	Partial 1562,1563,1564	0.69	Niagain_333_01
WC-12	Ward Center	Partial 1557,1558,1568,1569,1575,	0.45	Niagain_333_01
CLN-8	Clinic	Partial 394,399	1.00	Patkol_372_00
PL-5	Play ground	336-338(p)	2.58	Patkol_372_00
WDG	Waste Dumping Area	1715,1718,1720,1721,1722,1724,1726,1727,8,9,1730,1734,1741,1748	7.49	Niagain_333_01

Map 14-25: The Proposed Urban Services and Drainage Network Facilities Map of Ward-12

14.39 Implementation Guidelines

14.39.1 Tasks of Paurashava Authority

As a planning and development authority Paurashava shoulders the responsibilities of undertaking and implementing Ward wise Action Plans. Discussion meetings and negotiations with local leaders will have to be carried out relentlessly for successful execution of any detailed area plan through their active participation. The Paurashava must have the Planning Unit.

14.39.2 Institutional Strengthening

In Ward wise planning the most significant role will be played by Paurashava Authority. The Planning Section must have to launch in the Paurashava which will carry out the entire work of project initiation and plan formulation. These works are complicated and time consuming, and require multidisciplinary professionals.

14.39.3 Role of Municipal Authority

According to the section 35 of Paurashava Law-2010, Paurashava may, and if so required by the prescribed authority shall, draw up a Master Plan for the municipality within five years of its establishment. The Paurashava should have to play an important role by implementing all the priority tasks without any delaying other wise the plan proposals will be inactive for implementation in wrong periods.

14.39.4 Publicity and Circulation of the Plans and Documents

In order to enable greater access of the Paurashava inhabitants, the plan documents must have wide circulation. This is necessary to create awareness among people about city planning and development. The plan document should be sent to every public office. Copies of plans and reports should be made available for purchase by people in general. This will be a step forward in promoting good governance through enabling beneficiary participating in planning and development activities.

14.40 Concluding Remarks

This master plan is developed a comprehensive vision for Singra in context with its location, natural resources, and visions of the community. Singra Master Plan will describe a strategy to address the need for facility improvements and for capital investments to support current and future development of the Paurashava. The community will be involved every step of the way. It will guide the future development of the Paurashava.

In order to make the plans sustainable through people's participation, it is now emphasized involvement of the local stakeholders in the planning development process. Such participation creates a sense of ownership of the plan among the stakeholders that brings support for the plan and helps to create favorable conditions to implement the plan provisions. Keeping this approach in mind the present Structure Plan, Urban Area Plan and Ward Action Plans for Singra Paurashava has been prepared. It will shape and guide the growth of city in order to meet its social, cultural, environmental, economical, and recreational and many other needs of city dwellers.

Paurashava will be not only the custodian of the plan; it will also be responsible for implementing much of the development projects. Besides, it will also be responsible for monitoring implementation of the development projects by other urban development and service giving agencies. This situation calls for strengthening the existing capacity of Paurashava to handle future volume of work.

Annexure

Annexure-A: Land Use Permission

a. Urban Residential Land Use**Land Use Permitted**

The following uses in the tables are proposed to be applicable for this zone only.

Table A.1: Land Use Permitted

Permitted Urban Residential Uses
Artisan's Shop
Assisted Living or Elderly Home
Confectionery Shop
Barber Shop
Child Daycare \ Preschool
Cleaning \ Laundry Shop
Communication Service Facilities
Communication Tower Within Permitted Height
Condominium or Apartment
Cottage
Cyber Café
Daycare Center (Commercial or Nonprofit)
Drug Store or Pharmacy
Employee Housing (Guards \ Drivers) \ Ancillary Use
General Store
Grocery Store
High School
Household Appliance and Furniture Repair Service (No Outside Storage)
Housing For Seasonal Firm Labor
Landscape and Horticultural Services
Mosque, Place Of Worship
Newspaper Stand
Nursery School
Orphanage
Eidgah
Photocopying and Duplicating Services (No Outside Storage)
Pipelines and Utility Lines
Playing Field
Primary School
Private Garages (Ancillary Use)
Project Identification Signs
Property Management Signs
Public Transport Facility
Satellite Dish Antenna
Shelter (Passers By)
Shoe Repair or Shoeshine Shop (Small)
CBO Office
Special Dwelling
Temporary Tent
Temporary tent for Permitted Function
Newspaper Stand
Specialized School: Dance, Art, Music, Physically Challenged & Others
Transmission Lines
Urban-Nature Reserve
Utility Lines
Woodlot
Children's Park (Must Have Parking)
ATM Booth
Water Pump \ Reservoir

Permitted Urban Residential Uses
Monument (Neighborhood Scale)
Bill Payment Booth
Boarding and Rooming House
Dormitory
Memorial Structure (Ancillary)
Neighborhood Center* (Where Neighborhood Center exists)
Permitted
Community Center
Doctor \ Dentist Chamber
Cultural Exhibits and Libraries
Fast Food Establishment \ Food Kiosk
Flowers, Nursery Stock and Florist Supplies
Fitness Centre
Gaming Clubs
Departmental Stores
Retail Shops \ Facilities

Source: Compiled by the Consultants

*Permission of Neighborhood Center Facilities in absence of formal neighborhood should be subject to Landuse Permit Committee

Land Use Conditionally Permitted

The following uses may be permitted or disallowed in this zone after review and approval by the authority/committee following appropriate procedure while the application meets the criteria mentioned in the requirement.

Table A.2: Land Use Conditionally Permitted

Conditionally Permitted Urban Residential Uses
Addiction Treatment Center
Amusement and Recreation (Indoors)
Funeral Services
Art Gallery, Art Studio \ Workshop
Automobile Driving Academy
Beauty and Body Service
Billiard Parlor \ Pool Hall
Book or Stationery Store or Newsstand
Building Maintenance \ Cleaning Services, No Outside Storage
Bus Passenger Shelter
Graveyard \ Cemetery
Coffee Shop \ Tea Stall
Correctional Institution
Courier Service
Crematorium
Plantation (Except Narcotic Plant)
Furniture & Variety Stores
Emergency Shelter
Energy Installation
Garages
Garden Center or Retail Nursery
Fire Brigade Station
Police Station
Temporary Rescue Shed

Conditionally Permitted Urban Residential Uses
Guest House
Slaughter House
Static Transformer Stations
Tourist Home or Resort
Market (Bazar)
Optical Goods Sales
Outdoor Fruit and Vegetable Markets
Community Hall
Neighborhood Co-Operative Office
Overhead Water Storage Tanks
Row House
Paints and Varnishes Store
Parking Lot
Patio Homes
Photofinishing Laboratory
Post Office
Postal Facilities
Sports and Recreation Club
Tennis Club
Flood Management Structure
Telephone Sub Station
Electrical Sub Station

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

b. General Industry

Land use Permitted

General Industry land use category approve only Green and Orange-A category industry mentioned in *The Environmental Conservation Rule, 1997*. The following uses in the tables are proposed to be applicable for this zone only.

Table A.3: Land Use Permitted

Permitted General Industrial Activities
Confectionery Shop
Bank & Financial Institution
Bicycle Assembly, Parts and Accessories
Blacksmith
Bus Passenger Shelter
Communication Tower Within Permitted Height
Freight Transport Facility
Police Box \ Barrack
Fire \ Rescue Station
Grocery Store
Household Appliance and Furniture Repair Service
Machine Sheds
Meat and Poultry (Packing & Processing)
Mosque, Place Of Worship
Newspaper Stand
Photocopying and Duplicating Services
Pipelines and Utility Lines
Printing, Publishing and Distributing
Restaurant
Retail Shops \ Facilities

Permitted General Industrial Activities
Salvage Processing
Salvage Yards
Satellite Dish Antenna
Sawmill, Chipping and Pallet Mill
Shelter (Passers By)
Television, Radio or Electronics Repair (No Outside Storage)
Transmission Lines
Truck Stop & Washing or Freight Terminal
Utility Lines
Wood Products
Woodlot
ATM Booth
Water Pump \ Reservoir
Effluent Treatment Plant
Social Forestry

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or denied in this zone after review and approval by the authority/committee following appropriate procedure.

Table A.4: Land Use Conditionally Permitted

Conditionally Permitted General Industrial Land Uses
Amusement and Recreation (Indoors)
Appliance Store
Plantation (Except Narcotic Plant)
Cyber Café
Daycare Center (Commercial or Nonprofit)
Doctor \ Dentist Chamber
Electrical and Electronic Equipment and Instruments Sales
Employee Housing
Energy Installation
Fast Food Establishment \ Food Kiosk
Garages
Grain & Feed Mills
Incineration Facility
Super Store
Lithographic or Print Shop
Motor Vehicle Fuelling Station \ Gas Station
Motorcycle Sales Outlet
Outdoor Fruit and Vegetable Markets
Outside Bulk Storage
Overhead Water Storage Tanks
Painting and Wallpaper Sales
Paints and Varnishes
Parking Lot
Parking Lot (Commercial)
Private Garages
Retail Shops Ancillary To Studio \ Workshop
Jute Mill

Source: Compiled by the Consultants

Restricted Uses

All other uses; except the permitted and conditionally permitted uses.

c. Commercial Zone

Land Use Permitted

Commercial zone is mainly intended for supporting the office and business works. There are several functions that are permitted in this zone.

Table A.5: Land Use Permitted

Permitted Commercial Activity
Accounting, Auditing or Bookkeeping Services
Billboards, Advertisements & Advertising Structure
Agri-Business
Agricultural Sales and Services
Ambulance Service
Antique Shop
Appliance Store
Auction Market
Auditorium, Coliseum, Meeting Halls, and Conference Facilities, Convention
Auto Leasing or Rental Office
Auto Paint Shop
Auto Parts and Accessory Sales (Indoors)
Auto Repair Shop (With Garage)
Automobile Wash
Automobile Sales
Confectionery Shop
Bakery or Confectionery Retail
Bank & Financial Institution
Bar (Licensed)
Barber Shop
Beauty and Body Service
Bicycle Shop
Billiard Parlor \ Pool Hall
Book or Stationery Store or Newsstand
Building Material Sales or Storage (Indoors)
Bulk Mail and Packaging
Bus Passenger Shelter
Cinema Hall
Communication Service Facilities
Communication Tower Within Permitted Height
Computer Maintenance and Repair
Computer Sales & Services
Conference Center
Construction Company
Courier Service
Cyber Café
Daycare Center (Commercial or Nonprofit)
Department Stores, Furniture & Variety Stores
Doctor \ Dentist Chamber
Drug Store or Pharmacy
Electrical and Electronic Equipment and Instruments Sales
Fast Food Establishment \ Food Kiosk
Freight Handling, Storage & Distribution
Freight Transport Facility
Freight Yard
General Store
Grocery Store
Guest House

Permitted Commercial Activity
Hotel or Motel
Inter-City Bus Terminal
Jewelry and Silverware Sales
Junk \ Salvage Yard
Super Store
Market (Bazar)
Mosque, Place Of Worship
Motorcycle Sales Outlet
Multi-Storey Car Park
Newspaper Stand
Outdoor Fruit and Vegetable Markets
Outdoor Recreation, Commercial
Parking Lot (Commercial)
Pet Store
Photocopying and Duplicating Services
Photofinishing Laboratory & Studio
Pipelines and Utility Lines
Post Office
Preserved Fruits and Vegetables Facility \ Cold Storage
Printing, Publishing and Distributing
Project Identification Signs
Property Management Signs
Public Transport Facility
Refrigerator or Large Appliance Repair
Resort
Restaurant
Retail Shops \ Facilities
Salvage Processing
Salvage Yards
Satellite Dish Antenna
Sawmill, Chipping and Pallet Mill
Shelter (Passers By)
Shopping Mall \ Plaza
Slaughter House
Software Development
Sporting Goods and Toys Sales
Taxi Stand
Telephone Exchanges
Television, Radio or Electronics Repair (No Outside Storage)
Theater (Indoor)
Transmission Lines
Utility Lines
Vehicle Sales & Service, Leasing or Rental
Veterinarian Clinics, Animal Hospitals, Kennels and Boarding Facilities
Warehousing
Wood Products
Woodlot
ATM Booth
Water Pump \ Reservoir
Agro-Based Industry (Rice Mill, Saw Mill, Cold Storage)
Social Forestry

Source: Compiled by the Consultants

Land Use Conditionally Permitted

Some functions are permitted with some condition in this zone.

Table A.6: Land Use Conditionally Permitted

Conditionally permitted commercial activities
Amusement and Recreation (Indoors)
Bicycle Assembly, Parts and Accessories
Broadcast Studio \ Recording Studio (No Audience)
Coffee Shop \ Tea Stall
Concert Hall, Stage Shows
Construction, Survey, Soil Testing Firms
Trade Shows
Craft Workshop
Plantation (Except Narcotic Plant)
Energy Installation
Firm Equipment Sales & Service
Agricultural Chemicals, Pesticides or Fertilizers Shop
Fitness Centre
Flowers, Nursery Stock and Florist Supplies
Forest Products Sales
Fuel and Ice Dealers
Garages
Garden Center or Retail Nursery
Police Box \ Barrack
Fire \ Rescue Station
Grain & Feed Mills
Household Appliance and Furniture Repair Service
Incineration Facility
Indoor Amusement Centers, Game Arcades
Indoor Theatre
Lithographic or Print Shop
Motor Vehicle Fuelling Station \ Gas Station
Musical Instrument Sales or Repair
Optical Goods Sales
Painting and Wallpaper Sales
Paints and Varnishes
Parking Lot
Patio Homes
Postal Facilities
Poultry
Private Garages
Professional Office
Retail Shops Ancillary To Studio \ Workshop
Stone \ Cut Stone Products Sales

Source: Compiled by the Consultants

Restricted Uses

All other uses except, the permitted and conditionally permitted uses.

d. Rural Settlement

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table A.7: Land Use Permitted

Permitted Rural Settlement
Agricultural Dwellings

Permitted Rural Settlement
Animal Husbandry
Animal Shelter
Graveyard \ Cemetery
Child Daycare \ Preschool
Primary School
Communication Tower Within Permitted Height
Cottage
Crematorium
Dairy Farming
General Store
Grocery Store
Handloom (Cottage Industry)
Housing For Seasonal Firm Labor
Mosque, Place Of Worship
Newspaper Stand
Nursery School
orphanage
Outdoor Religious Events (Eidgah)
Playing Field
Satellite Dish Antenna
NGO \ CBO Facilities
Special Dwelling (E.G. Dorm For Physically Challenged Etc.)
Temporary Shed \ Tent
Specialized School: Dance, Art, Music, Physically Challenged & Others
Static Electrical Sub Stations
Transmission Lines
Utility Lines
Woodlot
Plantation (Except Narcotic Plant)
Social Forestry
Memorial Structure

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or disallowed in this zone after review and approval by the authority/committee following appropriate procedure while the application meets the criteria mentioned in the requirement.

Table No. A.8: Land Use Conditionally Permitted

Conditionally permitted uses under Rural Settlement
Artisan's Shop (Potter, Blacksmith, and Goldsmith Etc.)
Research organization (Agriculture \ Fisheries)
Energy Installation
Fish Hatchery
Garden Center or Retail Nursery
Emergency Shelter
Sports and Recreation Club, Firing Range: Indoor

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

e. Mixed use zone

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table A.11: Land Use Permitted

Permitted uses in Mixed Use Zone
Accounting, Auditing or Bookkeeping Services
Addiction Treatment Center
Billboards, Advertisements & Advertising Structure
Agricultural Sales and Services
Antique Store
Appliance Store
Art Gallery, Art Studio \ Workshop
Artisan's Shop
Assisted Living or Elderly Home
Auditorium, Coliseum, Meeting Halls, and Conference Facilities, Convention
Auto Leasing or Rental Office
Automobile Wash
Automobile Driving Academy
Confectionery Shop
Bakery or Confectionery Retail
Bank & Financial Institution
Barber Shop
Bicycle Shop
Billiard Parlor \ Pool Hall
Blacksmith
Boarding and Rooming House
Book or Stationery Store or Newsstand
Bus Passenger Shelter
Child Daycare \ Preschool
Cleaning \ Laundry Shop
Commercial Recreational Buildings
Communication Service Facilities
Communication Tower Within Permitted Height
Community Center
Condominium or Apartment
Correctional Institution
Courier Service
Cyber Café
Daycare Center (Commercial or Nonprofit)
Doctor \ Dentist Chamber
Employee Housing
Fabric Store
Fast Food Establishment \ Food Kiosk
Funeral Services
General Store
Grocery Store
Guest House
Hospital
Jewelry and Silverware Sales
Landscape and Horticultural Services
Mosque, Place Of Worship
Newspaper Stand
Nursery School
Photocopying and Duplicating Services

Permitted uses in Mixed Use Zone
Pipelines and Utility Lines
Primary School
Project Identification Signs
Property Management Signs
Public Transport Facility
Resort
Satellite Dish Antenna
Shelter (Passers By)
Shoe Repair or Shoeshine Shop (Small)
Slaughter House
Social organization
Software Development
Special Dwelling
Toys and Hobby Goods Processing and Supplies
Training Centre
Transmission Lines
Utility Lines
Vehicle Sales & Service, Leasing or Rental
Warehousing
Woodlot
Children's Park
ATM Booth
Water Pump \ Reservoir
Social Forestry
Dormitory
Rickshaw \ Auto Rickshaw Stand

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or disallowed in this zone after review and approval by the authority/committee.

Table A.12: Land Use Conditionally Permitted

Conditionally permitted uses in Mixed Use Zone
Agricultural Chemicals, Pesticides or Fertilizers Shop
Amusement and Recreation (Indoors)
Beauty and Body Service
Broadcast Studio \ Recording Studio (No Audience)
Building Maintenance \ Cleaning Services, No Outside Storage
Building Material Sales or Storage (Indoors)
Graveyard \ Cemetery
Coffee Shop \ Tea Stall
Computer Maintenance and Repair
Computer Sales & Services
Concert Hall, Stage Shows
Conference Center
Construction Company
Construction, Survey, Soil Testing Firms
Cottage
Counseling Services
Craft Workshop
Crematorium
Plantation (Except Narcotic Plant)
Cultural Exhibits and Libraries
Department Stores, Furniture & Variety Stores
Drug Store or Pharmacy

Conditionally permitted uses in Mixed Use Zone
Energy Installation
Fitness Centre
Flowers, Nursery Stock and Florist Supplies
Freight Handling, Storage & Distribution
Freight Transport Facility
Gaming Clubs
Garages
Garden Center or Retail Nursery
Commercial Office
Project Office
Government Office
Hotel or Motel
Household Appliance and Furniture Repair Service
Indoor Amusement Centers, Game Arcades
Indoor Theatre
Lithographic or Print Shop
Market (Bazar)
Health Office, Dental Laboratory, Clinic or Lab
Musical Instrument Sales or Repair
Optical Goods Sales
Outdoor Café
Outdoor Fruit and Vegetable Markets
Painting and Wallpaper Sales
Paints and Varnishes
Patio Homes
Photofinishing Laboratory & Studio
Poultry
Printing, Publishing and Distributing
Psychiatric Hospital
Retail Shops Ancillary To Studio \ Workshop
Radio \ Television or T&T Station With Transmitter Tower
Refrigerator or Large Appliance Repair
Restaurant
Retail Shops \ Facilities
Sporting Goods and Toys Sales
Sports and Recreation Club, Firing Range: Indoor
Telephone Exchanges
Television, Radio or Electronics Repair (No Outside Storage)

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

f. Education and Research Area

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table A.13: Land Use Permitted

Permitted uses under Education & Research Zone
Addiction Treatment Center
Billboards, Advertisements & Advertising Structure
Art Gallery, Art Studio \ Workshop
Automobile Driving Academy
Confectionery Shop
Bus Passenger Shelter
Child Daycare \ Preschool

Permitted uses under Education & Research Zone
College, University, Technical Institute
Communication Service Facilities
Communication Tower Within Permitted Height
Conference Center
Correctional Institution
Cultural Exhibits and Libraries
Cyber Café
Freight Transport Facility
General Store
Grocery Store
High School
Hospital
Lithographic or Print Shop
Mosque, Place Of Worship
Multi-Storey Car Park
Newspaper Stand
Nursery School
Outdoor Religious Events
Photocopying and Duplicating Services
Post Office
Primary School
Professional Office
Project Identification Signs
Property Management Signs
Public Transport Facility
Satellite Dish Antenna
School (Retarded)
Scientific Research Establishment
Shelter (Passers By)
Specialized School: Dance, Art, Music & Others
Training Centre
Transmission Lines
Utility Lines
Vocational, Business, Secretarial School
Woodlot
ATM Booth
Water Pump \ Reservoir
Social Forestry
Dormitory
Veterinary School \ College and Hospital

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or denied in this zone after review and approval by the authority/committee.

Table A.14: Land Use Conditionally Permitted

Conditionally permitted uses under Education and Research Zone
Auditorium, Coliseum, Meeting Halls, and Conference Facilities, Convention
Bank & Financial Institution
Barber Shop
Boarding and Rooming House
Book or Stationery Store or Newsstand
Coffee Shop \ Tea Stall
Counseling Services

Conditionally permitted uses under Education and Research Zone
Courier Service
Plantation (Except Narcotic Plant)
Daycare Center (Commercial or Nonprofit)
Doctor \ Dentist Chamber
Drug Store or Pharmacy
Fast Food Establishment \ Food Kiosk
Flowers, Nursery Stock and Florist Supplies
Gallery \ Museum
Garages
Indoor Theatre
orphanage
Outdoor Café
Parking Lot
Pipelines and Utility Lines
Postal Facilities
Psychiatric Hospital

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

g. Government Office

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table A.15: Land Use Permitted

Permitted uses under Government Office Zone
Accounting, Auditing or Bookkeeping Services
Billboards, Advertisements & Advertising Structure
Confectionery Shop
Bus Passenger Shelter
Civic Administration
Communication Service Facilities
Communication Tower Within Permitted Height
Construction, Survey, Soil Testing Firms
Cultural Exhibits and Libraries
Cyber Café
Emergency Shelter
Freight Transport Facility
General Store
Project Office
Government Office
Grocery Store
Guest House
Multi-Storey Car Park
Newspaper Stand
Outdoor Religious Events
Photocopying and Duplicating Services
Post Office
Professional Office
Public Transport Facility
Satellite Dish Antenna
Scientific Research Establishment
Shelter (Passers By)
Training Centre
Transmission Lines

Permitted uses under Government Office Zone
Utility Lines
Woodlot
ATM Booth
Water Pump \ Reservoir
Social Forestry

Source: Compiled by the Consultants

Land Use Conditionally Permitted

The following uses may be permitted or denied in this zone after review and approval by the authority/committee.

Table A.16: Land Use Conditionally Permitted

Conditionally permitted uses under Government office
Amusement and Recreation (Indoors)
Auditorium, Coliseum, Meeting Halls, and Conference Facilities, Convention
Bank & Financial Institution
Boarding and Rooming House
Book or Stationery Store or Newsstand
Coffee Shop \ Tea Stall
Conference Center
Courier Service
Plantation (Except Narcotic Plant)
Daycare Center (Commercial or Nonprofit)
Detention Facilities
Doctor \ Dentist Chamber
Energy Installation
Fast Food Establishment \ Food Kiosk
Flowers, Nursery Stock and Florist Supplies
Freight Handling, Storage & Distribution
Freight Yard
Gallery \ Museum
Garages
Police Box \ Barrack
Fire \ Rescue Station
Lithographic or Print Shop
Mosque, Place Of Worship
Outdoor Café
Parking Lot
Parking Lot (Commercial)
Pipelines and Utility Lines
Postal Facilities

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

h. Agricultural Zone

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table A17: Land Use Permitted

Permitted uses under Agricultural Zone
Food Grain Cultivation
Vegetable Cultivation

Permitted uses under Agricultural Zone
Cash Crop Cultivation
Horticulture
Arboriculture
Dairy Farming
Deep Tube Well
Shallow Tube Well
Irrigation Facilities (Irrigation Canal, Culvert, Flood Wall etc)
Temporary Structure (Agricultural)
Animal Shelter
Duckery
Aquatic Recreation Facility (Without Structure)
Tree Plantation (Except Narcotic Plant)
Aquaculture
Static Transformer Stations
Transmission Lines
Utility Lines
Woodlot
Social Forestry

Source: Compiled by the Consultants

Land Use Conditionally Permitted

Table A18: Land Use Conditionally Permitted

Conditionally permitted uses under Agricultural Zone
Graveyard \ Cemetery
Communication Tower Within Permitted Height
Crematorium
Fish Hatchery
Garden Center or Retail Nursery
Poultry

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted in this zone.

j. Open Space

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table A.19: Land Use Permitted

Permitted uses under Open Space
Botanical Garden & Arboretum
Bus Passenger Shelter
Caravan Park \ Camping Ground
Carnivals and Fairs
Circus
Plantation (Except Narcotic Plant)
Landscape and Horticultural Services
Open Theater
Park and Recreation Facilities (General)
Pipelines and Utility Lines
Playing Field
Special Function Tent
Tennis Club
Transmission Lines
Urban-Nature Reserve
Utility Lines

Permitted uses under Open Space
Woodlot
Zoo
Roadside Parking
Social Forestry
Memorial Structure

Source: Compiled by the Consultants

Landuse Conditionally Permitted

Table A 20: Land Use Conditionally Permitted

Conditionally permitted uses under open space
Communication Tower Within Permitted Height
Trade Shows
Fitness Centre
Flowers, Nursery Stock and Florist Supplies
Golf Course
Motorized Recreation
Outdoor Recreation Facilities
Outdoor Recreation, Commercial
Outdoor Sports and Recreation
Park Maintenance Facility
Retreat Center
Sports and Recreation Club, Firing Range: Indoor

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted.

k. Water Body

Retaining water is the main purpose of this type of Landuse.

Land Use Permitted

The following uses in the tables are proposed to be applicable for this zone only.

Table A.21: Land Use Permitted

Permitted uses under Water Body
Aquatic Recreation Facility (Without Structure)
Fishing Club
Utility Lines
Water Parks
Memorial Structure

Source: Compiled by the Consultant

Land Use Conditionally Permitted

The following uses may be permitted or denied in this zone after review and approval by the authority/committee.

Table A.22: Land Use Conditionally Permitted

Conditionally permitted uses under water body
Plantation (Except Narcotic Plant)
Marina \ Boating Facility
Motorized Recreation

Source: Compiled by the Consultants

Restricted Uses

All uses except permitted and conditionally permitted uses are restricted.

**Annexure-B: Road Network Proposal of Singra
Paurashava**

Details of Road Network Proposalsof SingraPaurashava

Table B1: Details of Road Widening Proposals of Singra Paurashava (Phase 01: First to Fifth Year of Master Plan)

Type of Road	Existing Crest Width (ft.)	Proposed RoW (ft.)	Existing Road Id	Existing Road Id	Road Name	Ward No.	Length (m)
Secondary Road	3.34	50	2	WR-2	Singra - Kalom Road	Ward No. 10	3238.44
Secondary Road	3.34	50	2	WR-2	Singra - Kalom Road	Ward No. 09	3238.44
Secondary Road	3.34	50	2	WR-2	Singra - Kalom Road	Ward No. 08	3238.44
Secondary Road	3.699	40	9	WR-9	Singra- Gorudaspur Road	Ward No. 11	586.83
Secondary Road	3.699	40	18	WR-18	Singra- Gorudaspur Road	Ward No. 11	2912.20
Secondary Road	3.699	40	18	WR-18	Singra- Gorudaspur Road	Ward No. 06	2912.20
Primary Road	7.28	100	99	WR-1	Natore- Natore Road	Ward No. 08	4520.64
Primary Road	7.28	100	99	WR-1	Natore- Natore Road	Ward No. 07	4520.64
Primary Road	7.28	100	99	WR-1	Natore- Natore Road	Ward No. 06	4520.64
Primary Road	7.28	100	99	WR-1	Natore- Natore Road	Ward No. 04	4520.64
Primary Road	7.28	100	99	WR-1	Natore- Natore Road	Ward No. 03	4520.64
Secondary Road	3.397	30	119	WR-118		Ward No. 08	85.38
Secondary Road	2.536	30	120	WR-119		Ward No. 08	164.45
Secondary Road	2.493	30	121	WR-120		Ward No. 08	113.20
Secondary Road	3.397	30	124	WR-123		Ward No. 08	153.64
Secondary Road	3.963	50	128	WR-127	TNT Office Road	Ward No. 08	870.70
Secondary Road	3.963	50	128	WR-127	TNT Office Road	Ward No. 05	870.70
Secondary Road	3.963	50	128	WR-127	TNT Office Road	Ward No. 04	870.70
Secondary Road	7.28	40	159	WR-158	Natore- Natore Road	Ward No. 08	391.51
Secondary Road	7.28	40	159	WR-158	Natore- Natore Road	Ward No. 04	391.51
Secondary Road	7.28	30	180	WR-179	Natore- Natore Road	Ward No. 04	444.49
Secondary Road	4.547	40	191	WR-190		Ward No. 05	286.28
Secondary Road	7.28	30	202	WR-201	Natore- Natore Road	Ward No. 06	496.98
Local/Access Road	3.963	20	210	WR-209	TNT Office Road	Ward No. 05	161.68
Secondary Road	3.093	40	214	WR-213		Ward No. 05	130.31
Secondary Road	4.569	30	217	WR-216	Upazilla Parisad Road	Ward No. 04	395.25
Secondary Road	4.569	30	217	WR-216	Upazilla Parisad Road	Ward No. 01	395.25
Secondary Road	2.541	40	223	WR-222		Ward No. 05	108.46
Secondary Road	3.963	40	247	WR-246	TNT Office Road	Ward No. 01	870.03
Secondary Road	3.963	40	247	WR-246	TNT Office Road	Ward No. 03	870.03
Secondary Road	3.963	40	291	WR-290	TNT Office Road	Ward No. 03	376.18
Secondary Road	3.963	50	314	WR-313	TNT Office Road	Ward No. 05	2519.71
Secondary Road	3.963	50	314	WR-313	TNT Office Road	Ward No. 01	2519.71
Secondary Road	3.963	50	314	WR-313	TNT Office Road	Ward No. 03	2519.71
Secondary Road	3.963	40	347	WR-346	TNT Office Road	Ward No. 03	1541.96
Secondary Road	3.963	40	347	WR-346	TNT Office Road	Ward No. 02	1541.96
Secondary Road	4.547	30	355	WR-354		Ward No. 08	123.20
Secondary Road	4.547	30	355	WR-354		Ward No. 05	123.20

Source: Road Network Plan of Singra Paurashava

Table B2: Details of New Roads in Road Network Plan of Singra Paurashava (Phase 01: First to Fifth Year of Master Plan)

Type of Road	Proposed RoW (ft.)	Proposed Road Id	Road Name	Ward No.	Length (m)
Local/Access Road	20	NR-7		Ward No. 09	47.70
Local/Access Road	20	NR-35		Ward No. 08	91.64
Local/Access Road	20	NR-36		Ward No. 08	19.20
Local/Access Road	20	NR-41		Ward No. 01	29.23
Local/Access Road	20	NR-77		Ward No. 03	28.39
Local/Access Road	30	NR-78		Ward No. 01	549.52
Local/Access Road	20	NR-79		Ward No. 05	233.10
Local/Access Road	20	NR-80		Ward No. 11	151.74

Source: Road Network Plan of Singra Paurashava

Table B3: Details of Road Widening Proposals of Singra Paurashava (Phase 02: Sixth to Ten Year of Master Plan)

Type of Road	Existing Crest Width (ft.)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Length (m)
Local/Access Road	57.502	20	47	WR-47		Ward No. 09	57.502
Local/Access Road	104.608	20	50	WR-50		Ward No. 09	104.608
Local/Access Road	145.717	20	51	WR-51		Ward No. 09	145.717
Local/Access Road	90.712	20	52	WR-52		Ward No. 09	90.712
Secondary Road	1032.974	30	56	WR-56		Ward No. 06	1032.974
Local/Access Road	214.204	20	58	WR-58		Ward No. 09	214.204
Local/Access Road	102.990	20	59	WR-59		Ward No. 09	102.990
Local/Access Road	113.155	20	60	WR-60		Ward No. 09	113.155
Local/Access Road	356.251	20	61	WR-61		Ward No. 09	356.251
Local/Access Road	222.435	20	62	WR-62		Ward No. 09	222.435
Local/Access Road	136.757	20	63	WR-63	Singra - Kalom Road	Ward No. 09	136.757
Local/Access Road	310.216	20	65	WR-65		Ward No. 09	310.216
Local/Access Road	108.108	20	67	WR-67		Ward No. 06	108.108
Local/Access Road	94.221	20	68	WR-68		Ward No. 06	94.221
Local/Access Road	89.024	20	75	WR-75		Ward No. 09	89.024
Local/Access Road	132.804	20	76	WR-76	Singra - Kalom Road	Ward No. 09	132.804
Local/Access Road	307.885	20	77	WR-77		Ward No. 06	307.885
Local/Access Road	205.184	20	80	WR-80	Singra - Kalom Road	Ward No. 08	205.184
Local/Access Road	174.471	20	81	WR-81		Ward No. 08	174.471
Secondary Road	420.926	30	83	WR-83	Singra - Kalom Road	Ward No. 08	420.926
Local/Access Road	261.542	20	93	WR-93	Singra - Kalom Road	Ward No. 08	261.542
Local/Access Road	97.193	20	95	WR-95		Ward No. 08	97.193
Secondary Road	185.213	30	96	WR-96		Ward No. 06	185.213
Secondary Road	521.497	30	100	WR-99	Balua Baua Jame Mosque Road	Ward No. 04	521.497
Secondary Road	807.258	30	106	WR-105	Singra - karanpari Road	Ward No. 07	807.258
Secondary Road	736.007	30	108	WR-107		Ward No. 07	736.007
Local/Access Road	19.315	20	127	WR-126	Natore- Natore Road	Ward No. 08	19.315
Local/Access Road	153.400	20	129	WR-128		Ward No. 08	153.400
Local/Access Road	119.992	20	130	WR-129	Natore- Natore Road	Ward No. 04	119.992
Local/Access Road	23.765	20	131	WR-130	Natore- Natore Road	Ward No. 08	23.765
Local/Access Road	27.537	20	133	WR-132	Natore- Natore Road	Ward No. 08	27.537
Local/Access Road	110.580	20	134	WR-133		Ward No. 08	110.580
Local/Access Road	256.312	20	135	WR-134		Ward No. 08	256.312
Local/Access Road	186.372	20	137	WR-136	Natore- Natore Road	Ward No. 06	186.372
Local/Access Road	28.724	20	140	WR-139	Natore- Natore Road	Ward No. 08	28.724
Local/Access Road	28.724	20	140	WR-139	Natore- Natore Road	Ward No. 04	28.724
Local/Access Road	91.334	20	143	WR-142	Natore- Natore Road	Ward No. 06	91.334
Local/Access Road	86.755	20	144	WR-143		Ward No. 08	86.755
Local/Access Road	179.065	20	147	WR-146		Ward No. 08	179.065
Local/Access Road	189.949	20	150	WR-149	Natore- Natore Road	Ward No. 06	189.949
Secondary Road	702.033	30	172	WR-171		Ward No. 04	702.033
Secondary Road	202.974	30	219	WR-218		Ward No. 04	202.974
Secondary Road	202.974	30	219	WR-218		Ward No. 01	202.974
Secondary Road	190.845	30	220	WR-219		Ward No. 04	190.845
Secondary Road	67.650	30	305	WR=304	TNT Office Road	Ward No. 03	67.650
Local/Access Road	57.502	20	47	WR-47		Ward No. 09	57.502
Local/Access Road	104.608	20	50	WR-50		Ward No. 09	104.608
Local/Access Road	145.717	20	51	WR-51		Ward No. 09	145.717
Local/Access Road	90.712	20	52	WR-52		Ward No. 09	90.712
Secondary Road	1032.974	30	56	WR-56		Ward No. 06	1032.974
Local/Access Road	214.204	20	58	WR-58		Ward No. 09	214.204
Local/Access Road	102.990	20	59	WR-59		Ward No. 09	102.990
Local/Access Road	113.155	20	60	WR-60		Ward No. 09	113.155
Local/Access Road	356.251	20	61	WR-61		Ward No. 09	356.251
Local/Access Road	222.435	20	62	WR-62		Ward No. 09	222.435
Local/Access Road	136.757	20	63	WR-63	Singra - Kalom Road	Ward No. 09	136.757
Local/Access Road	310.216	20	65	WR-65		Ward No. 09	310.216
Local/Access Road	108.108	20	67	WR-67		Ward No. 06	108.108
Local/Access Road	94.221	20	68	WR-68		Ward No. 06	94.221
Local/Access Road	89.024	20	75	WR-75		Ward No. 09	89.024
Local/Access Road	132.804	20	76	WR-76	Singra - Kalom Road	Ward No. 09	132.804
Local/Access Road	307.885	20	77	WR-77		Ward No. 06	307.885

Type of Road	Existing Crest Width (ft.)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Length (m)
Local/Access Road	57.502	20	47	WR-47		Ward No. 09	57.502
Local/Access Road	104.608	20	50	WR-50		Ward No. 09	104.608
Local/Access Road	145.717	20	51	WR-51		Ward No. 09	145.717
Local/Access Road	205.184	20	80	WR-80	Singra - Kalom Road	Ward No. 08	205.184
Local/Access Road	174.471	20	81	WR-81		Ward No. 08	174.471
Secondary Road	420.926	30	83	WR-83	Singra - Kalom Road	Ward No. 08	420.926
Local/Access Road	261.542	20	93	WR-93	Singra - Kalom Road	Ward No. 08	261.542
Local/Access Road	97.193	20	95	WR-95		Ward No. 08	97.193
Secondary Road	185.213	30	96	WR-96		Ward No. 06	185.213
Secondary Road	521.497	30	100	WR-99	Balua Baua Jame Mosque Road	Ward No. 04	521.497
Secondary Road	807.258	30	106	WR-105	Singra - karanpari Road	Ward No. 07	807.258
Secondary Road	736.007	30	108	WR-107		Ward No. 07	736.007
Local/Access Road	19.315	20	127	WR-126	Natore- Natore Road	Ward No. 08	19.315
Local/Access Road	153.400	20	129	WR-128		Ward No. 08	153.400
Local/Access Road	119.992	20	130	WR-129	Natore- Natore Road	Ward No. 04	119.992
Local/Access Road	23.765	20	131	WR-130	Natore- Natore Road	Ward No. 08	23.765
Local/Access Road	27.537	20	133	WR-132	Natore- Natore Road	Ward No. 08	27.537
Local/Access Road	110.580	20	134	WR-133		Ward No. 08	110.580
Local/Access Road	256.312	20	135	WR-134		Ward No. 08	256.312
Local/Access Road	186.372	20	137	WR-136	Natore- Natore Road	Ward No. 06	186.372
Local/Access Road	28.724	20	140	WR-139	Natore- Natore Road	Ward No. 08	28.724
Local/Access Road	28.724	20	140	WR-139	Natore- Natore Road	Ward No. 04	28.724
Local/Access Road	91.334	20	143	WR-142	Natore- Natore Road	Ward No. 06	91.334
Local/Access Road	86.755	20	144	WR-143		Ward No. 08	86.755
Local/Access Road	179.065	20	147	WR-146		Ward No. 08	179.065
Local/Access Road	189.949	20	150	WR-149	Natore- Natore Road	Ward No. 06	189.949
Secondary Road	702.033	30	172	WR-171		Ward No. 04	702.033
Secondary Road	202.974	30	219	WR-218		Ward No. 04	202.974
Secondary Road	202.974	30	219	WR-218		Ward No. 01	202.974
Secondary Road	190.845	30	220	WR-219		Ward No. 04	190.845
Secondary Road	67.650	30	305	WR-304	TNT Office Road	Ward No. 03	67.650

Source: Road Network Plan of Singra Paurashava

Table B4: Details of New Roads in Road Network Plan of Singra Paurashava (Phase 01: Sixth to Tenth Year of Master Plan)

Type of Road	Proposed RoW (ft.)	Proposed Road Id	Road Name	Ward No.	Length (m)
Local/Access Road	20	NR-1		Ward No. 01	264.500
Local/Access Road	20	NR-1		Ward No. 03	264.500
Local/Access Road	20	NR-2		Ward No. 01	306.861
Local/Access Road	20	NR-2		Ward No. 03	306.861
Local/Access Road	20	NR-3		Ward No. 01	452.244
Local/Access Road	20	NR-3		Ward No. 03	452.244
Secondary Road	30	NR-4		Ward No. 01	431.942
Local/Access Road	20	NR-5		Ward No. 08	103.564
Local/Access Road	20	NR-6		Ward No. 08	153.283
Local/Access Road	20	NR-8		Ward No. 09	170.320
Local/Access Road	20	NR-9		Ward No. 09	91.744
Local/Access Road	20	NR-10		Ward No. 09	126.517
Local/Access Road	20	NR-11		Ward No. 09	125.140
Local/Access Road	20	NR-12		Ward No. 09	321.073
Local/Access Road	20	NR-13		Ward No. 09	194.557
Local/Access Road	20	NR-13		Ward No. 08	194.557
Local/Access Road	20	NR-14		Ward No. 08	138.038
Local/Access Road	20	NR-15		Ward No. 09	322.982
Local/Access Road	20	NR-15		Ward No. 08	322.982
Secondary Road	50	NR-16		Ward No. 08	246.600
Secondary Road	50	NR-17		Ward No. 09	1328.265
Secondary Road	50	NR-17		Ward No. 08	1328.265
Secondary Road	50	NR-17		Ward No. 06	1328.265
Local/Access Road	20	NR-20		Ward No. 05	304.472
Secondary Road	40	NR-21		Ward No. 01	1000.014
Secondary Road	40	NR-21		Ward No. 03	1000.014
Local/Access Road	20	NR-22		Ward No. 06	174.636
Local/Access Road	20	NR-33		Ward No. 09	110.837

Type of Road	Proposed RoW (ft.)	Proposed Road Id	Road Name	Ward No.	Length (m)
Local/Access Road	20	NR-24		Ward No. 09	81.503
Local/Access Road	20	NR-25		Ward No. 09	23.736
Secondary Road	40	NR-26		Ward No. 09	1364.682
Secondary Road	40	NR-26		Ward No. 08	1364.682
Local/Access Road	20	NR-27		Ward No. 09	141.626
Local/Access Road	20	NR-28		Ward No. 09	228.219
Local/Access Road	20	NR-29		Ward No. 09	75.145
Local/Access Road	20	NR-30		Ward No. 09	225.725
Local/Access Road	20	NR-30		Ward No. 08	225.725
Local/Access Road	20	NR-31		Ward No. 08	52.197
Local/Access Road	20	NR-32		Ward No. 08	83.262
Secondary Road	40	NR-33		Ward No. 08	827.692
Secondary Road	40	NR-33		Ward No. 06	827.692
Secondary Road	40	NR-33		Ward No. 05	827.692
Secondary Road	40	NR-33		Ward No. 01	827.692
Secondary Road	40	NR-34		Ward No. 08	232.889
Local/Access Road	20	NR-37		Ward No. 01	109.120
Local/Access Road	20	NR-38		Ward No. 01	32.542
Secondary Road	40	NR-39		Ward No. 04	1202.412
Secondary Road	40	NR-39		Ward No. 03	1202.412
Local/Access Road	20	NR-40		Ward No. 04	107.054
Local/Access Road	20	NR-42		Ward No. 04	157.918
Local/Access Road	20	NR-42		Ward No. 03	157.918
Local/Access Road	20	NR-43		Ward No. 01	102.292
Local/Access Road	20	NR-45		Ward No. 01	95.795
Local/Access Road	20	NR-46		Ward No. 01	53.843
Local/Access Road	20	NR-47		Ward No. 01	193.807
Local/Access Road	20	NR-50		Ward No. 02	18.862
Local/Access Road	20	NR-53		Ward No. 02	44.044
Local/Access Road	20	NR-67		Ward No. 09	268.035
Local/Access Road	20	NR-68		Ward No. 09	420.018
Secondary Road	40	NR-69		Ward No. 10	568.506
Secondary Road	40	NR-69		Ward No. 09	568.506
Local/Access Road	20	NR-70		Ward No. 11	330.398
Local/Access Road	20	NR-71		Ward No. 11	56.101
Local/Access Road	20	NR-72		Ward No. 11	58.600
Local/Access Road	20	NR-73		Ward No. 11	55.908
Local/Access Road	20	NR-74		Ward No. 11	148.769
Local/Access Road	20	NR-76		Ward No. 03	56.793
Local/Access Road	20	NR-1		Ward No. 01	264.500
Local/Access Road	20	NR-1		Ward No. 03	264.500
Local/Access Road	20	NR-2		Ward No. 01	306.861
Local/Access Road	20	NR-2		Ward No. 03	306.861
Local/Access Road	20	NR-3		Ward No. 01	452.244
Local/Access Road	20	NR-3		Ward No. 03	452.244
Secondary Road	30	NR-4		Ward No. 01	431.942
Local/Access Road	20	NR-5		Ward No. 08	103.564
Local/Access Road	20	NR-6		Ward No. 08	153.283
Local/Access Road	20	NR-8		Ward No. 09	170.320
Local/Access Road	20	NR-9		Ward No. 09	91.744
Local/Access Road	20	NR-10		Ward No. 09	126.517
Local/Access Road	20	NR-11		Ward No. 09	125.140
Local/Access Road	20	NR-12		Ward No. 09	321.073
Local/Access Road	20	NR-13		Ward No. 09	194.557
Local/Access Road	20	NR-13		Ward No. 08	194.557
Local/Access Road	20	NR-14		Ward No. 08	138.038
Local/Access Road	20	NR-15		Ward No. 09	322.982
Local/Access Road	20	NR-15		Ward No. 08	322.982
Secondary Road	50	NR-16		Ward No. 08	246.600
Secondary Road	50	NR-17		Ward No. 09	1328.265
Secondary Road	50	NR-17		Ward No. 08	1328.265
Secondary Road	50	NR-17		Ward No. 06	1328.265
Local/Access Road	20	NR-20		Ward No. 05	304.472
Secondary Road	40	NR-21		Ward No. 01	1000.014
Secondary Road	40	NR-21		Ward No. 03	1000.014
Local/Access Road	20	NR-22		Ward No. 06	174.636
Local/Access Road	20	NR-33		Ward No. 09	110.837
Local/Access Road	20	NR-24		Ward No. 09	81.503
Local/Access Road	20	NR-25		Ward No. 09	23.736

Type of Road	Proposed RoW (ft.)	Proposed Road Id	Road Name	Ward No.	Length (m)
Secondary Road	40	NR-26		Ward No. 09	1364.682
Secondary Road	40	NR-26		Ward No. 08	1364.682
Local/Access Road	20	NR-27		Ward No. 09	141.626
Local/Access Road	20	NR-28		Ward No. 09	228.219
Local/Access Road	20	NR-29		Ward No. 09	75.145
Local/Access Road	20	NR-30		Ward No. 09	225.725
Local/Access Road	20	NR-30		Ward No. 08	225.725
Local/Access Road	20	NR-31		Ward No. 08	52.197
Local/Access Road	20	NR-32		Ward No. 08	83.262
Secondary Road	40	NR-33		Ward No. 08	827.692
Secondary Road	40	NR-33		Ward No. 06	827.692
Secondary Road	40	NR-33		Ward No. 05	827.692
Secondary Road	40	NR-33		Ward No. 01	827.692
Secondary Road	40	NR-34		Ward No. 08	232.889
Local/Access Road	20	NR-37		Ward No. 01	109.120
Local/Access Road	20	NR-38		Ward No. 01	32.542
Secondary Road	40	NR-39		Ward No. 04	1202.412
Secondary Road	40	NR-39		Ward No. 03	1202.412
Local/Access Road	20	NR-40		Ward No. 04	107.054
Local/Access Road	20	NR-42		Ward No. 04	157.918
Local/Access Road	20	NR-42		Ward No. 03	157.918
Local/Access Road	20	NR-43		Ward No. 01	102.292
Local/Access Road	20	NR-45		Ward No. 01	95.795
Local/Access Road	20	NR-46		Ward No. 01	53.843
Local/Access Road	20	NR-47		Ward No. 01	193.807
Local/Access Road	20	NR-50		Ward No. 02	18.862
Local/Access Road	20	NR-53		Ward No. 02	44.044
Local/Access Road	20	NR-67		Ward No. 09	268.035
Local/Access Road	20	NR-68		Ward No. 09	420.018
Secondary Road	40	NR-69		Ward No. 10	568.506
Secondary Road	40	NR-69		Ward No. 09	568.506
Local/Access Road	20	NR-70		Ward No. 11	330.398
Local/Access Road	20	NR-71		Ward No. 11	56.101
Local/Access Road	20	NR-72		Ward No. 11	58.600
Local/Access Road	20	NR-73		Ward No. 11	55.908
Local/Access Road	20	NR-74		Ward No. 11	148.769
Local/Access Road	20	NR-76		Ward No. 03	56.793
Local/Access Road	20	NR-1		Ward No. 01	264.500
Local/Access Road	20	NR-1		Ward No. 03	264.500
Local/Access Road	20	NR-2		Ward No. 01	306.861
Local/Access Road	20	NR-2		Ward No. 03	306.861
Local/Access Road	20	NR-3		Ward No. 01	452.244
Local/Access Road	20	NR-3		Ward No. 03	452.244
Secondary Road	30	NR-4		Ward No. 01	431.942
Local/Access Road	20	NR-5		Ward No. 08	103.564
Local/Access Road	20	NR-6		Ward No. 08	153.283
Local/Access Road	20	NR-8		Ward No. 09	170.320
Local/Access Road	20	NR-9		Ward No. 09	91.744
Local/Access Road	20	NR-10		Ward No. 09	126.517
Local/Access Road	20	NR-11		Ward No. 09	125.140
Local/Access Road	20	NR-12		Ward No. 09	321.073
Local/Access Road	20	NR-13		Ward No. 09	194.557
Local/Access Road	20	NR-13		Ward No. 08	194.557
Local/Access Road	20	NR-14		Ward No. 08	138.038
Local/Access Road	20	NR-15		Ward No. 09	322.982
Local/Access Road	20	NR-15		Ward No. 08	322.982
Secondary Road	50	NR-16		Ward No. 08	246.600
Secondary Road	50	NR-17		Ward No. 09	1328.265
Secondary Road	50	NR-17		Ward No. 08	1328.265
Secondary Road	50	NR-17		Ward No. 06	1328.265
Local/Access Road	20	NR-20		Ward No. 05	304.472
Secondary Road	40	NR-21		Ward No. 01	1000.014
Secondary Road	40	NR-21		Ward No. 03	1000.014
Local/Access Road	20	NR-22		Ward No. 06	174.636
Local/Access Road	20	NR-33		Ward No. 09	110.837
Local/Access Road	20	NR-24		Ward No. 09	81.503
Local/Access Road	20	NR-25		Ward No. 09	23.736
Secondary Road	40	NR-26		Ward No. 09	1364.682
Secondary Road	40	NR-26		Ward No. 08	1364.682

Type of Road	Proposed RoW (ft.)	Proposed Road Id	Road Name	Ward No.	Length (m)
Local/Access Road	20	NR-27		Ward No. 09	141.626
Local/Access Road	20	NR-28		Ward No. 09	228.219
Local/Access Road	20	NR-29		Ward No. 09	75.145
Local/Access Road	20	NR-30		Ward No. 09	225.725
Local/Access Road	20	NR-30		Ward No. 08	225.725
Local/Access Road	20	NR-31		Ward No. 08	52.197
Local/Access Road	20	NR-32		Ward No. 08	83.262
Secondary Road	40	NR-33		Ward No. 08	827.692
Secondary Road	40	NR-33		Ward No. 06	827.692
Secondary Road	40	NR-33		Ward No. 05	827.692
Secondary Road	40	NR-33		Ward No. 01	827.692
Secondary Road	40	NR-34		Ward No. 08	232.889
Local/Access Road	20	NR-37		Ward No. 01	109.120
Local/Access Road	20	NR-38		Ward No. 01	32.542
Secondary Road	40	NR-39		Ward No. 04	1202.412
Secondary Road	40	NR-39		Ward No. 03	1202.412
Local/Access Road	20	NR-40		Ward No. 04	107.054
Local/Access Road	20	NR-42		Ward No. 04	157.918
Local/Access Road	20	NR-42		Ward No. 03	157.918
Local/Access Road	20	NR-43		Ward No. 01	102.292
Local/Access Road	20	NR-45		Ward No. 01	95.795
Local/Access Road	20	NR-46		Ward No. 01	53.843
Local/Access Road	20	NR-47		Ward No. 01	193.807
Local/Access Road	20	NR-50		Ward No. 02	18.862
Local/Access Road	20	NR-53		Ward No. 02	44.044
Local/Access Road	20	NR-67		Ward No. 09	268.035
Local/Access Road	20	NR-68		Ward No. 09	420.018
Secondary Road	40	NR-69		Ward No. 10	568.506
Secondary Road	40	NR-69		Ward No. 09	568.506
Local/Access Road	20	NR-70		Ward No. 11	330.398
Local/Access Road	20	NR-71		Ward No. 11	56.101
Local/Access Road	20	NR-72		Ward No. 11	58.600
Local/Access Road	20	NR-73		Ward No. 11	55.908
Local/Access Road	20	NR-74		Ward No. 11	148.769
Local/Access Road	20	NR-76		Ward No. 03	56.793

Source: Road Network Plan of Singra Paurashava

Table B5: Details of Road Widening Proposals of Singra Paurashava (Phase 03: Eleventh to Twentieth Year of Master Plan)

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	2593.923	20	1	WR-98	Ninguin Notun Para School Road	Ward No. 11	3.1
Local/Access Road	2593.923	20	1	WR-97	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	71.352	20	3	WR-94		Ward No. 10	1.532
Local/Access Road	56.923	20	4	WR-92		Ward No. 10	1.489
Local/Access Road	175.075	20	5	WR-91		Ward No. 10	1.529
Local/Access Road	26.720	20	6	WR-90		Ward No. 10	1.582
Local/Access Road	99.117	20	7	WR-89		Ward No. 10	2.5
Local/Access Road	157.591	20	8	WR-88		Ward No. 10	2.5
Local/Access Road	255.066	20	10	WR-87		Ward No. 10	2.398
Local/Access Road	39.421	20	11	WR-86		Ward No. 10	1.527
Local/Access Road	568.825	20	12	WR-85		Ward No. 11	3.215
Local/Access Road	2008.607	20	13	WR-84		Ward No. 11	3.25
Local/Access Road	2008.607	20	13	WR-82		Ward No. 12	3.25
Local/Access Road	2008.607	20	13	WR-8		Ward No. 06	3.25
Local/Access Road	42.841	20	14	WR-79		Ward No. 10	1.555
Local/Access Road	78.482	20	15	WR-78		Ward No. 10	1.543
Local/Access Road	89.440	20	16	WR-74		Ward No. 10	2.398
Local/Access Road	22.687	20	17	WR-73		Ward No. 11	2.51
Local/Access Road	103.830	20	19	WR-72		Ward No. 11	1.656
Local/Access Road	315.944	20	20	WR-71		Ward No. 11	3.414

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	90.620	20	21	WR-70		Ward No. 10	2.095
Local/Access Road	40.463	20	22	WR-7		Ward No. 11	2.191
Local/Access Road	52.701	20	23	WR-69		Ward No. 11	2.191
Local/Access Road	60.048	20	24	WR-66		Ward No. 11	3.528
Local/Access Road	202.825	20	25	WR-64		Ward No. 11	3.033
Local/Access Road	29.850	20	26	WR-6		Ward No. 11	3.326
Local/Access Road	42.429	20	27	WR-57		Ward No. 11	2.089
Local/Access Road	132.092	20	28	WR-57		Ward No. 10	2.51
Local/Access Road	147.600	20	29	WR-55		Ward No. 11	3.037
Local/Access Road	21.144	20	30	WR-54		Ward No. 11	2.787
Local/Access Road	47.500	20	31	WR-53		Ward No. 11	3.079
Local/Access Road	19.802	20	32	WR-5		Ward No. 06	2.271
Local/Access Road	163.957	20	33	WR-49		Ward No. 11	1.746
Local/Access Road	175.239	20	34	WR-48		Ward No. 11	3.055
Local/Access Road	49.292	20	35	WR-46	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	118.448	20	36	WR-45		Ward No. 11	2.216
Local/Access Road	61.946	20	37	WR-44		Ward No. 09	2.102
Local/Access Road	146.110	20	38	WR-43		Ward No. 09	2.102
Local/Access Road	315.505	20	39	WR-42		Ward No. 09	3.02
Local/Access Road	143.051	20	40	WR-41		Ward No. 09	3.011
Local/Access Road	113.172	20	41	WR-40		Ward No. 09	3.041
Local/Access Road	168.611	20	42	WR-4		Ward No. 09	2.998
Local/Access Road	241.851	20	43	WR-39		Ward No. 09	2.998
Local/Access Road	70.636	20	44	WR-38		Ward No. 09	3.619
Local/Access Road	45.323	20	45	WR-37		Ward No. 09	2.382
Local/Access Road	94.300	20	46	WR-36		Ward No. 06	1.962
Local/Access Road	35.065	20	48	WR-355		Ward No. 06	2.189
Local/Access Road	108.658	20	49	WR-355		Ward No. 06	1.567
Local/Access Road	86.405	20	53	WR-353		Ward No. 09	2.03
Local/Access Road	64.841	20	54	WR-352		Ward No. 06	2.164
Local/Access Road	49.887	20	55	WR-351		Ward No. 09	2.215
Local/Access Road	29.661	20	57	WR-350		Ward No. 06	2.62
Local/Access Road	59.490	20	64	WR-35		Ward No. 09	2.028
Local/Access Road	41.772	20	66	WR-349		Ward No. 09	2.088
Local/Access Road	825.147	20	69	WR-348		Ward No. 06	2.696
Local/Access Road	58.763	20	70	WR-347		Ward No. 09	3.061
Local/Access Road	30.856	20	71	WR-345		Ward No. 09	1.663
Local/Access Road	38.950	20	72	WR-344		Ward No. 09	2.6
Local/Access Road	175.835	20	73	WR-343		Ward No. 09	2.547
Local/Access Road	18.957	20	74	WR-342		Ward No. 09	2.182
Local/Access Road	69.816	20	78	WR-341	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	23.368	20	79	WR-340		Ward No. 08	1.525
Local/Access Road	233.012	20	82	WR-34	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	79.925	20	84	WR-339	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	18.310	20	85	WR-338		Ward No. 08	1.605
Local/Access Road	44.365	20	86	WR-337	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	31.902	20	87	WR-336		Ward No. 08	2.08
Local/Access Road	19.949	20	88	WR-335	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	96.157	20	89	WR-334		Ward No. 08	2.614
Local/Access Road	5.911	20	90	WR-333		Ward No. 08	1.725
Local/Access Road	28.967	20	91	WR-332		Ward No. 08	2.784
Local/Access Road	20.533	20	92	WR-331	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	88.141	20	94	WR-330		Ward No. 08	3.062
Local/Access Road	50.931	20	97	WR-33		Ward No. 08	2.24
Local/Access Road	39.296	20	98	WR-329		Ward No. 08	2.046
Local/Access Road	84.139	20	101	WR-328		Ward No. 06	4.062
Local/Access Road	13.312	20	102	WR-327		Ward No. 08	4.539
Local/Access Road	24.517	20	103	WR-326		Ward No. 08	2.011
Local/Access Road	51.922	20	104	WR-325		Ward No. 08	2.011
Local/Access Road	28.305	20	105	WR-324		Ward No. 08	2.561
Local/Access Road	33.036	20	107	WR-323		Ward No. 12	2.709

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	33.036	20	107	WR-322		Ward No. 07	2.709
Local/Access Road	280.500	20	109	WR-321		Ward No. 08	6.083
Local/Access Road	95.832	20	110	WR-320		Ward No. 07	2.55
Local/Access Road	58.011	20	111	WR-320		Ward No. 07	2.649
Local/Access Road	70.846	20	112	WR-32		Ward No. 08	2.691
Local/Access Road	20.748	20	113	WR-319		Ward No. 08	1.994
Local/Access Road	56.643	20	114	WR-318	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	72.071	20	115	WR-317	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	120.852	20	116	WR-316		Ward No. 04	2.043
Local/Access Road	30.204	20	117	WR-315		Ward No. 06	6.867
Local/Access Road	219.325	20	118	WR-314		Ward No. 07	3.104
Local/Access Road	113.873	20	122	WR-312		Ward No. 08	4.101
Local/Access Road	218.782	20	123	WR-311	Balua Baua Jame Mosque Road	Ward No. 08	4.059
Local/Access Road	218.782	20	123	WR-310	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	113.274	20	125	WR-31		Ward No. 08	3.71
Local/Access Road	46.048	20	126	WR-309	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	107.580	20	132	WR-308	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	214.625	20	136	WR-307		Ward No. 07	3.104
Local/Access Road	175.773	20	138	WR-306		Ward No. 06	3.062
Local/Access Road	35.980	20	139	WR-305		Ward No. 07	2.555
Local/Access Road	48.372	20	141	WR-303		Ward No. 08	2.297
Local/Access Road	56.911	20	142	WR-302		Ward No. 07	1.049
Local/Access Road	151.193	20	145	WR-301		Ward No. 07	3.03
Local/Access Road	115.717	20	146	WR-300		Ward No. 07	2.523
Local/Access Road	21.101	20	148	WR-30		Ward No. 08	2.097
Local/Access Road	34.631	20	149	WR-3		Ward No. 07	2.149
Local/Access Road	17.416	20	151	WR-299		Ward No. 08	2.198
Local/Access Road	41.693	20	152	WR-298		Ward No. 08	2.198
Local/Access Road	71.911	20	153	WR-297	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	57.817	20	154	WR-296		Ward No. 07	2.63
Local/Access Road	48.611	20	155	WR-295		Ward No. 04	3.073
Local/Access Road	37.504	20	156	WR-294		Ward No. 04	2.109
Local/Access Road	137.947	20	157	WR-293		Ward No. 08	2.109
Local/Access Road	137.947	20	157	WR-292		Ward No. 04	2.109
Local/Access Road	95.696	20	158	WR-292		Ward No. 08	2.533
Local/Access Road	35.481	20	160	WR-291		Ward No. 04	1.568
Local/Access Road	106.762	20	161	WR-29		Ward No. 08	2.287
Local/Access Road	158.450	20	162	WR-289		Ward No. 08	2.605
Local/Access Road	70.012	20	163	WR-289		Ward No. 04	2.017
Local/Access Road	18.897	20	164	WR-288		Ward No. 04	2.275
Local/Access Road	96.546	20	165	WR-287		Ward No. 04	2.639
Local/Access Road	47.885	20	166	WR-286		Ward No. 08	2.147
Local/Access Road	20.596	20	167	WR-286		Ward No. 07	2.597
Local/Access Road	136.634	20	168	WR-285		Ward No. 07	2.196
Local/Access Road	140.973	20	169	WR-284		Ward No. 04	3.652
Local/Access Road	303.345	20	170	WR-283		Ward No. 07	2.924
Local/Access Road	68.250	20	171	WR-282		Ward No. 04	3.049
Local/Access Road	15.655	20	173	WR-281		Ward No. 04	2.714
Local/Access Road	28.799	20	174	WR-280		Ward No. 07	2.561
Local/Access Road	150.380	20	175	WR-28		Ward No. 07	3.03
Local/Access Road	17.735	20	176	WR-279		Ward No. 08	2.497
Local/Access Road	114.186	20	177	WR-278		Ward No. 07	2.41
Local/Access Road	17.918	20	178	WR-277		Ward No. 04	2.62
Local/Access Road	27.200	20	179	WR-276		Ward No. 04	3.296
Local/Access Road	27.200	20	179	WR-275		Ward No. 03	3.296
Local/Access Road	18.623	20	181	WR-274		Ward No. 04	2.628
Local/Access Road	61.702	20	182	WR-273		Ward No. 07	2.196
Local/Access Road	261.973	20	183	WR-272		Ward No. 07	2.517
Local/Access Road	77.754	20	184	WR-271		Ward No. 07	2.068
Local/Access Road	53.661	20	185	WR-270		Ward No. 07	3.299
Local/Access Road	176.509	20	186	WR-27		Ward No. 04	2.417
Local/Access Road	82.268	20	187	WR-269		Ward No. 08	2.555

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	45.216	20	188	WR-268		Ward No. 04	4.123
Local/Access Road	31.092	20	189	WR-267		Ward No. 04	2.689
Local/Access Road	31.092	20	189	WR-266		Ward No. 03	2.689
Local/Access Road	25.744	20	190	WR-265		Ward No. 04	3.677
Local/Access Road	60.880	20	192	WR-264		Ward No. 08	2.623
Local/Access Road	60.880	20	192	WR-263		Ward No. 05	2.623
Local/Access Road	446.939	20	193	WR-262	Singra -karanpari Road	Ward No. 07	4.537
Local/Access Road	6.439	20	194	WR-261		Ward No. 04	2.27
Local/Access Road	20.068	20	195	WR-260		Ward No. 07	3.299
Local/Access Road	123.966	20	196	WR-26		Ward No. 07	3.299
Local/Access Road	30.676	20	197	WR-259		Ward No. 04	2.712
Local/Access Road	81.180	20	198	WR-258		Ward No. 04	2.712
Local/Access Road	80.530	20	199	WR-257		Ward No. 04	2.08
Local/Access Road	54.920	20	200	WR-256		Ward No. 07	3.299
Local/Access Road	19.724	20	201	WR-255		Ward No. 05	2.21
Local/Access Road	19.724	20	201	WR-254		Ward No. 04	2.21
Local/Access Road	27.943	20	203	WR-253		Ward No. 06	3.312
Local/Access Road	41.105	20	204	WR-253		Ward No. 06	3.312
Local/Access Road	106.730	20	205	WR-252		Ward No. 04	2.417
Local/Access Road	36.077	20	206	WR-251		Ward No. 08	2.133
Local/Access Road	117.577	20	207	WR-250		Ward No. 04	2.547
Local/Access Road	22.234	20	208	WR-25		Ward No. 08	2.1
Local/Access Road	22.234	20	208	WR-249		Ward No. 05	2.1
Local/Access Road	46.751	20	209	WR-248		Ward No. 04	6.127
Local/Access Road	128.071	20	211	WR-247		Ward No. 04	2.263
Local/Access Road	35.682	20	212	WR-245		Ward No. 04	2.866
Local/Access Road	56.762	20	213	WR-244		Ward No. 04	2.866
Local/Access Road	143.153	20	215	WR-243		Ward No. 08	2.548
Local/Access Road	143.153	20	215	WR-242		Ward No. 05	2.548
Local/Access Road	21.046	20	216	WR-241		Ward No. 08	2.281
Local/Access Road	21.046	20	216	WR-241		Ward No. 05	2.281
Local/Access Road	10.213	20	218	WR-240	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	10.213	20	218	WR-24	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	39.119	20	221	WR-239		Ward No. 05	2.599
Local/Access Road	26.114	20	222	WR-238	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	26.114	20	222	WR-237	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	218.029	20	224	WR-236		Ward No. 05	3.006
Local/Access Road	212.759	20	225	WR-235		Ward No. 05	3.006
Local/Access Road	12.886	20	226	WR-234	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	101.303	20	227	WR-234		Ward No. 04	2.047
Local/Access Road	101.303	20	227	WR-234		Ward No. 01	2.047
Local/Access Road	30.744	20	228	WR-232	TNT Office Road	Ward No. 05	3.963
Local/Access Road	80.821	20	229	WR-232		Ward No. 05	2.646
Local/Access Road	211.973	20	230	WR-231	TNT Office Road	Ward No. 05	3.963
Local/Access Road	211.973	20	230	WR-230	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.012	20	231	WR-23		Ward No. 05	3.412
Local/Access Road	107.993	20	232	WR-229		Ward No. 05	2.662
Local/Access Road	43.173	20	233	WR-229	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	43.173	20	233	WR-228	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	24.733	20	234	WR-227		Ward No. 05	2.58
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	19.301	20	236	WR-225		Ward No. 01	2.02
Local/Access Road	24.798	20	237	WR-224		Ward No. 01	3.417
Local/Access Road	48.985	20	238	WR-223		Ward No. 01	2.545
Local/Access Road	9.882	20	239	WR-221		Ward No. 01	2.136
Local/Access Road	46.171	20	240	WR-221		Ward No. 01	2.521
Local/Access Road	10.132	20	241	WR-220		Ward No. 01	2.124
Local/Access Road	130.993	20	242	WR-22	Upazilla Parisad Road	Ward No. 04	4.569

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	130.993	20	242	WR-217	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	156.036	20	243	WR-217		Ward No. 05	2.563
Local/Access Road	16.696	20	244	WR-215		Ward No. 01	2.112
Local/Access Road	9.602	20	245	WR-215		Ward No. 01	2.134
Local/Access Road	42.890	20	246	WR-214		Ward No. 01	2.534
Local/Access Road	28.277	20	248	WR-214	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.986	20	249	WR-212		Ward No. 01	2.534
Local/Access Road	28.567	20	250	WR-211		Ward No. 01	2.027
Local/Access Road	33.504	20	251	WR-210		Ward No. 01	2.013
Local/Access Road	21.871	20	252	WR-21	TNT Office Road	Ward No. 01	3.963
Local/Access Road	74.180	20	253	WR-208	TNT Office Road	Ward No. 01	3.963
Local/Access Road	131.986	20	254	WR-207		Ward No. 05	2.199
Local/Access Road	131.986	20	254	WR-207		Ward No. 01	2.199
Local/Access Road	90.645	20	255	WR-206		Ward No. 05	2.199
Local/Access Road	19.539	20	256	WR-205		Ward No. 01	2.096
Local/Access Road	61.338	20	257	WR-204		Ward No. 01	2.602
Local/Access Road	102.962	20	258	WR-203		Ward No. 01	3.15
Local/Access Road	50.968	20	259	WR-202		Ward No. 01	3.15
Local/Access Road	98.164	20	260	WR-200	TNT Office Road	Ward No. 01	3.963
Local/Access Road	39.365	20	261	WR-200		Ward No. 01	1.011
Local/Access Road	43.333	20	262	WR-20		Ward No. 01	1.991
Local/Access Road	101.371	20	263	WR-199	TNT Office Road	Ward No. 01	3.963
Local/Access Road	81.368	20	264	WR-198	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.327	20	265	WR-197		Ward No. 01	1.531
Local/Access Road	68.732	20	266	WR-196		Ward No. 01	1.513
Local/Access Road	13.394	20	267	WR-195		Ward No. 01	1.531
Local/Access Road	17.906	20	268	WR-194		Ward No. 01	1.513
Local/Access Road	13.524	20	269	WR-193		Ward No. 01	1.513
Local/Access Road	46.095	20	270	WR-192	TNT Office Road	Ward No. 01	3.963
Local/Access Road	109.827	20	271	WR-191		Ward No. 01	1.593
Local/Access Road	77.059	20	272	WR-191	TNT Office Road	Ward No. 01	3.963
Local/Access Road	278.669	20	273	WR-19	TNT Office Road	Ward No. 01	3.963
Local/Access Road	37.632	20	274	WR-189		Ward No. 01	1.508
Local/Access Road	269.941	20	275	WR-188	TNT Office Road	Ward No. 03	3.963
Local/Access Road	79.781	20	276	WR-188		Ward No. 03	1.503
Local/Access Road	57.331	20	277	WR-187		Ward No. 03	1.503
Local/Access Road	32.507	20	278	WR-186		Ward No. 01	2.054
Local/Access Road	28.586	20	279	WR-185		Ward No. 01	1.639
Local/Access Road	282.850	20	280	WR-184	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.326	20	281	WR-183	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.707	20	282	WR-182		Ward No. 01	2.011
Local/Access Road	63.817	20	283	WR-181		Ward No. 01	3.04
Local/Access Road	88.406	20	284	WR-180		Ward No. 01	3.04
Local/Access Road	89.512	20	285	WR-178		Ward No. 01	3.04
Local/Access Road	30.315	20	286	WR-178		Ward No. 01	1.995
Local/Access Road	33.167	20	287	WR-177	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.167	20	287	WR-176	TNT Office Road	Ward No. 03	3.963
Local/Access Road	15.693	20	288	WR-175		Ward No. 01	2.025
Local/Access Road	36.241	20	289	WR-174		Ward No. 01	1.99
Local/Access Road	289.425	20	290	WR-173		Ward No. 03	2.995
Local/Access Road	289.425	20	290	WR-172		Ward No. 02	2.995
Local/Access Road	60.058	20	292	WR-170		Ward No. 03	2.037
Local/Access Road	68.017	20	293	WR-17		Ward No. 01	2.026
Local/Access Road	68.017	20	293	WR-169		Ward No. 03	2.026
Local/Access Road	130.008	20	294	WR-168	TNT Office Road	Ward No. 03	3.963
Local/Access Road	12.034	20	295	WR-167		Ward No. 03	2.127
Local/Access Road	11.667	20	296	WR-166		Ward No. 03	2.076
Local/Access Road	17.426	20	297	WR-165		Ward No. 03	2.144
Local/Access Road	42.032	20	298	WR-164	TNT Office Road	Ward No. 03	3.963
Local/Access Road	150.774	20	299	WR-163		Ward No. 03	1.531
Local/Access Road	108.922	20	300	WR-162	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.369	20	301	WR-161		Ward No. 03	3.006
Local/Access Road	179.903	20	302	WR-160		Ward No. 03	3.001
Local/Access Road	67.096	20	303	WR-16		Ward No. 03	2.556
Local/Access Road	39.134	20	304	WR-159		Ward No. 03	2.556
Local/Access Road	50.329	20	306	WR-156		Ward No. 03	3.33
Local/Access Road	53.629	20	307	WR-156	TNT Office Road	Ward No. 03	3.963
Local/Access Road	16.882	20	308	WR-155		Ward No. 03	3.001

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	52.737	20	309	WR-154	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.018	20	310	WR-153	TNT Office Road	Ward No. 03	3.963
Local/Access Road	39.818	20	311	WR-152	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.452	20	312	WR-151	TNT Office Road	Ward No. 03	3.963
Local/Access Road	35.712	20	313	WR-150	TNT Office Road	Ward No. 03	3.963
Local/Access Road	26.264	20	315	WR-15	TNT Office Road	Ward No. 03	3.963
Local/Access Road	108.153	20	316	WR-148	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.676	20	317	WR-147	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.883	20	318	WR-145		Ward No. 03	2.055
Local/Access Road	42.975	20	319	WR-144	TNT Office Road	Ward No. 03	3.963
Local/Access Road	123.229	20	320	WR-141		Ward No. 02	5.027
Local/Access Road	51.280	20	321	WR-140	TNT Office Road	Ward No. 03	3.963
Local/Access Road	51.280	20	322	WR-138		Ward No. 02	3.963
Local/Access Road	464.379	20	322	WR-138		Ward No. 03	2.208
Local/Access Road	32.724	20	323	WR-137	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.057	20	324	WR-135	TNT Office Road	Ward No. 03	3.963
Local/Access Road	78.042	20	325	WR-131		Ward No. 03	2.127
Local/Access Road	434.075	20	326	WR-13		Ward No. 02	1.97
Local/Access Road	342.215	20	327	WR-13		Ward No. 03	2.742
Local/Access Road	79.045	20	328	WR-13		Ward No. 02	2.559
Local/Access Road	290.391	20	329	WR-125		Ward No. 02	1.502
Local/Access Road	206.448	20	330	WR-124		Ward No. 02	2.364
Local/Access Road	276.671	20	331	WR-122		Ward No. 02	6.678
Local/Access Road	47.087	20	332	WR-122		Ward No. 02	3.132
Local/Access Road	1121.400	20	333	WR-121		Ward No. 02	3.132
Local/Access Road	56.747	20	334	WR-12		Ward No. 02	1.242
Local/Access Road	240.242	20	335	WR-117		Ward No. 02	3.132
Local/Access Road	174.792	20	336	WR-116		Ward No. 02	6.678
Local/Access Road	30.317	20	337	WR-115		Ward No. 02	1.131
Local/Access Road	75.392	20	338	WR-114		Ward No. 02	3.132
Local/Access Road	251.225	20	339	WR-113		Ward No. 02	3.132
Local/Access Road	26.167	20	340	WR-112		Ward No. 02	3.132
Local/Access Road	35.513	20	341	WR-111		Ward No. 02	1.565
Local/Access Road	15.997	20	342	WR-110		Ward No. 02	1.048
Local/Access Road	30.980	20	343	WR-11		Ward No. 02	2.525
Local/Access Road	47.635	20	344	WR-109		Ward No. 02	3.132
Local/Access Road	81.911	20	345	WR-108		Ward No. 02	3.132
Local/Access Road	69.247	20	346	WR-106		Ward No. 02	2.12
Local/Access Road	55.144	20	348	WR-106		Ward No. 02	3.257
Local/Access Road	136.489	20	349	WR-104		Ward No. 02	3.257
Local/Access Road	393.674	20	350	WR-103		Ward No. 02	3.257
Local/Access Road	82.924	20	351	WR-102		Ward No. 02	2.103
Local/Access Road	126.541	20	352	WR-101		Ward No. 02	2.541
Local/Access Road	1361.006	40	353	WR-100		Ward No. 07	3.299
Local/Access Road	3.713	40	354	WR-10		Ward No. 04	2.139
Local/Access Road	2593.923	20	1	WR-98	Ninguin Notun Para School Road	Ward No. 11	3.1
Local/Access Road	2593.923	20	1	WR-97	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	71.352	20	3	WR-94		Ward No. 10	1.532
Local/Access Road	56.923	20	4	WR-92		Ward No. 10	1.489
Local/Access Road	175.075	20	5	WR-91		Ward No. 10	1.529
Local/Access Road	26.720	20	6	WR-90		Ward No. 10	1.582
Local/Access Road	99.117	20	7	WR-89		Ward No. 10	2.5
Local/Access Road	157.591	20	8	WR-88		Ward No. 10	2.5
Local/Access Road	255.066	20	10	WR-87		Ward No. 10	2.398
Local/Access Road	39.421	20	11	WR-86		Ward No. 10	1.527
Local/Access Road	568.825	20	12	WR-85		Ward No. 11	3.215
Local/Access Road	2008.607	20	13	WR-84		Ward No. 11	3.25
Local/Access Road	2008.607	20	13	WR-82		Ward No. 12	3.25
Local/Access Road	2008.607	20	13	WR-8		Ward No. 06	3.25
Local/Access Road	42.841	20	14	WR-79		Ward No. 10	1.555
Local/Access Road	78.482	20	15	WR-78		Ward No. 10	1.543
Local/Access Road	89.440	20	16	WR-74		Ward No. 10	2.398
Local/Access Road	22.687	20	17	WR-73		Ward No. 11	2.51
Local/Access Road	103.830	20	19	WR-72		Ward No. 11	1.656
Local/Access Road	315.944	20	20	WR-71		Ward No. 11	3.414

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	90.620	20	21	WR-70		Ward No. 10	2.095
Local/Access Road	40.463	20	22	WR-7		Ward No. 11	2.191
Local/Access Road	52.701	20	23	WR-69		Ward No. 11	2.191
Local/Access Road	60.048	20	24	WR-66		Ward No. 11	3.528
Local/Access Road	202.825	20	25	WR-64		Ward No. 11	3.033
Local/Access Road	29.850	20	26	WR-6		Ward No. 11	3.326
Local/Access Road	42.429	20	27	WR-57		Ward No. 11	2.089
Local/Access Road	132.092	20	28	WR-57		Ward No. 10	2.51
Local/Access Road	147.600	20	29	WR-55		Ward No. 11	3.037
Local/Access Road	21.144	20	30	WR-54		Ward No. 11	2.787
Local/Access Road	47.500	20	31	WR-53		Ward No. 11	3.079
Local/Access Road	19.802	20	32	WR-5		Ward No. 06	2.271
Local/Access Road	163.957	20	33	WR-49		Ward No. 11	1.746
Local/Access Road	175.239	20	34	WR-48		Ward No. 11	3.055
Local/Access Road	49.292	20	35	WR-46	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	118.448	20	36	WR-45		Ward No. 11	2.216
Local/Access Road	61.946	20	37	WR-44		Ward No. 09	2.102
Local/Access Road	146.110	20	38	WR-43		Ward No. 09	2.102
Local/Access Road	315.505	20	39	WR-42		Ward No. 09	3.02
Local/Access Road	143.051	20	40	WR-41		Ward No. 09	3.011
Local/Access Road	113.172	20	41	WR-40		Ward No. 09	3.041
Local/Access Road	168.611	20	42	WR-4		Ward No. 09	2.998
Local/Access Road	241.851	20	43	WR-39		Ward No. 09	2.998
Local/Access Road	70.636	20	44	WR-38		Ward No. 09	3.619
Local/Access Road	45.323	20	45	WR-37		Ward No. 09	2.382
Local/Access Road	94.300	20	46	WR-36		Ward No. 06	1.962
Local/Access Road	35.065	20	48	WR-355		Ward No. 06	2.189
Local/Access Road	108.658	20	49	WR-355		Ward No. 06	1.567
Local/Access Road	86.405	20	53	WR-353		Ward No. 09	2.03
Local/Access Road	64.841	20	54	WR-352		Ward No. 06	2.164
Local/Access Road	49.887	20	55	WR-351		Ward No. 09	2.215
Local/Access Road	29.661	20	57	WR-350		Ward No. 06	2.62
Local/Access Road	59.490	20	64	WR-35		Ward No. 09	2.028
Local/Access Road	41.772	20	66	WR-349		Ward No. 09	2.088
Local/Access Road	825.147	20	69	WR-348		Ward No. 06	2.696
Local/Access Road	58.763	20	70	WR-347		Ward No. 09	3.061
Local/Access Road	30.856	20	71	WR-345		Ward No. 09	1.663
Local/Access Road	38.950	20	72	WR-344		Ward No. 09	2.6
Local/Access Road	175.835	20	73	WR-343		Ward No. 09	2.547
Local/Access Road	18.957	20	74	WR-342		Ward No. 09	2.182
Local/Access Road	69.816	20	78	WR-341	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	23.368	20	79	WR-340		Ward No. 08	1.525
Local/Access Road	233.012	20	82	WR-34	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	79.925	20	84	WR-339	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	18.310	20	85	WR-338		Ward No. 08	1.605
Local/Access Road	44.365	20	86	WR-337	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	31.902	20	87	WR-336		Ward No. 08	2.08
Local/Access Road	19.949	20	88	WR-335	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	96.157	20	89	WR-334		Ward No. 08	2.614
Local/Access Road	5.911	20	90	WR-333		Ward No. 08	1.725
Local/Access Road	28.967	20	91	WR-332		Ward No. 08	2.784
Local/Access Road	20.533	20	92	WR-331	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	88.141	20	94	WR-330		Ward No. 08	3.062
Local/Access Road	50.931	20	97	WR-33		Ward No. 08	2.24
Local/Access Road	39.296	20	98	WR-329		Ward No. 08	2.046
Local/Access Road	84.139	20	101	WR-328		Ward No. 06	4.062
Local/Access Road	13.312	20	102	WR-327		Ward No. 08	4.539
Local/Access Road	24.517	20	103	WR-326		Ward No. 08	2.011
Local/Access Road	51.922	20	104	WR-325		Ward No. 08	2.011
Local/Access Road	28.305	20	105	WR-324		Ward No. 08	2.561
Local/Access Road	33.036	20	107	WR-323		Ward No. 12	2.709

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	33.036	20	107	WR-322		Ward No. 07	2.709
Local/Access Road	280.500	20	109	WR-321		Ward No. 08	6.083
Local/Access Road	95.832	20	110	WR-320		Ward No. 07	2.55
Local/Access Road	58.011	20	111	WR-320		Ward No. 07	2.649
Local/Access Road	70.846	20	112	WR-32		Ward No. 08	2.691
Local/Access Road	20.748	20	113	WR-319		Ward No. 08	1.994
Local/Access Road	56.643	20	114	WR-318	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	72.071	20	115	WR-317	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	120.852	20	116	WR-316		Ward No. 04	2.043
Local/Access Road	30.204	20	117	WR-315		Ward No. 06	6.867
Local/Access Road	219.325	20	118	WR-314		Ward No. 07	3.104
Local/Access Road	113.873	20	122	WR-312		Ward No. 08	4.101
Local/Access Road	218.782	20	123	WR-311	Balua Baua Jame Mosque Road	Ward No. 08	4.059
Local/Access Road	218.782	20	123	WR-310	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	113.274	20	125	WR-31		Ward No. 08	3.71
Local/Access Road	46.048	20	126	WR-309	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	107.580	20	132	WR-308	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	214.625	20	136	WR-307		Ward No. 07	3.104
Local/Access Road	175.773	20	138	WR-306		Ward No. 06	3.062
Local/Access Road	35.980	20	139	WR-305		Ward No. 07	2.555
Local/Access Road	48.372	20	141	WR-303		Ward No. 08	2.297
Local/Access Road	56.911	20	142	WR-302		Ward No. 07	1.049
Local/Access Road	151.193	20	145	WR-301		Ward No. 07	3.03
Local/Access Road	115.717	20	146	WR-300		Ward No. 07	2.523
Local/Access Road	21.101	20	148	WR-30		Ward No. 08	2.097
Local/Access Road	34.631	20	149	WR-3		Ward No. 07	2.149
Local/Access Road	17.416	20	151	WR-299		Ward No. 08	2.198
Local/Access Road	41.693	20	152	WR-298		Ward No. 08	2.198
Local/Access Road	71.911	20	153	WR-297	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	57.817	20	154	WR-296		Ward No. 07	2.63
Local/Access Road	48.611	20	155	WR-295		Ward No. 04	3.073
Local/Access Road	37.504	20	156	WR-294		Ward No. 04	2.109
Local/Access Road	137.947	20	157	WR-293		Ward No. 08	2.109
Local/Access Road	137.947	20	157	WR-292		Ward No. 04	2.109
Local/Access Road	95.696	20	158	WR-292		Ward No. 08	2.533
Local/Access Road	35.481	20	160	WR-291		Ward No. 04	1.568
Local/Access Road	106.762	20	161	WR-29		Ward No. 08	2.287
Local/Access Road	158.450	20	162	WR-289		Ward No. 08	2.605
Local/Access Road	70.012	20	163	WR-289		Ward No. 04	2.017
Local/Access Road	18.897	20	164	WR-288		Ward No. 04	2.275
Local/Access Road	96.546	20	165	WR-287		Ward No. 04	2.639
Local/Access Road	47.885	20	166	WR-286		Ward No. 08	2.147
Local/Access Road	20.596	20	167	WR-286		Ward No. 07	2.597
Local/Access Road	136.634	20	168	WR-285		Ward No. 07	2.196
Local/Access Road	140.973	20	169	WR-284		Ward No. 04	3.652
Local/Access Road	303.345	20	170	WR-283		Ward No. 07	2.924
Local/Access Road	68.250	20	171	WR-282		Ward No. 04	3.049
Local/Access Road	15.655	20	173	WR-281		Ward No. 04	2.714
Local/Access Road	28.799	20	174	WR-280		Ward No. 07	2.561
Local/Access Road	150.380	20	175	WR-28		Ward No. 07	3.03
Local/Access Road	17.735	20	176	WR-279		Ward No. 08	2.497
Local/Access Road	114.186	20	177	WR-278		Ward No. 07	2.41
Local/Access Road	17.918	20	178	WR-277		Ward No. 04	2.62
Local/Access Road	27.200	20	179	WR-276		Ward No. 04	3.296
Local/Access Road	27.200	20	179	WR-275		Ward No. 03	3.296
Local/Access Road	18.623	20	181	WR-274		Ward No. 04	2.628
Local/Access Road	61.702	20	182	WR-273		Ward No. 07	2.196
Local/Access Road	261.973	20	183	WR-272		Ward No. 07	2.517
Local/Access Road	77.754	20	184	WR-271		Ward No. 07	2.068
Local/Access Road	53.661	20	185	WR-270		Ward No. 07	3.299
Local/Access Road	176.509	20	186	WR-27		Ward No. 04	2.417
Local/Access Road	82.268	20	187	WR-269		Ward No. 08	2.555

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	45.216	20	188	WR-268		Ward No. 04	4.123
Local/Access Road	31.092	20	189	WR-267		Ward No. 04	2.689
Local/Access Road	31.092	20	189	WR-266		Ward No. 03	2.689
Local/Access Road	25.744	20	190	WR-265		Ward No. 04	3.677
Local/Access Road	60.880	20	192	WR-264		Ward No. 08	2.623
Local/Access Road	60.880	20	192	WR-263		Ward No. 05	2.623
Local/Access Road	446.939	20	193	WR-262	Singra -karanpari Road	Ward No. 07	4.537
Local/Access Road	6.439	20	194	WR-261		Ward No. 04	2.27
Local/Access Road	20.068	20	195	WR-260		Ward No. 07	3.299
Local/Access Road	123.966	20	196	WR-26		Ward No. 07	3.299
Local/Access Road	30.676	20	197	WR-259		Ward No. 04	2.712
Local/Access Road	81.180	20	198	WR-258		Ward No. 04	2.712
Local/Access Road	80.530	20	199	WR-257		Ward No. 04	2.08
Local/Access Road	54.920	20	200	WR-256		Ward No. 07	3.299
Local/Access Road	19.724	20	201	WR-255		Ward No. 05	2.21
Local/Access Road	19.724	20	201	WR-254		Ward No. 04	2.21
Local/Access Road	27.943	20	203	WR-253		Ward No. 06	3.312
Local/Access Road	41.105	20	204	WR-253		Ward No. 06	3.312
Local/Access Road	106.730	20	205	WR-252		Ward No. 04	2.417
Local/Access Road	36.077	20	206	WR-251		Ward No. 08	2.133
Local/Access Road	117.577	20	207	WR-250		Ward No. 04	2.547
Local/Access Road	22.234	20	208	WR-25		Ward No. 08	2.1
Local/Access Road	22.234	20	208	WR-249		Ward No. 05	2.1
Local/Access Road	46.751	20	209	WR-248		Ward No. 04	6.127
Local/Access Road	128.071	20	211	WR-247		Ward No. 04	2.263
Local/Access Road	35.682	20	212	WR-245		Ward No. 04	2.866
Local/Access Road	56.762	20	213	WR-244		Ward No. 04	2.866
Local/Access Road	143.153	20	215	WR-243		Ward No. 08	2.548
Local/Access Road	143.153	20	215	WR-242		Ward No. 05	2.548
Local/Access Road	21.046	20	216	WR-241		Ward No. 08	2.281
Local/Access Road	21.046	20	216	WR-241		Ward No. 05	2.281
Local/Access Road	10.213	20	218	WR-240	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	10.213	20	218	WR-24	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	39.119	20	221	WR-239		Ward No. 05	2.599
Local/Access Road	26.114	20	222	WR-238	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	26.114	20	222	WR-237	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	218.029	20	224	WR-236		Ward No. 05	3.006
Local/Access Road	212.759	20	225	WR-235		Ward No. 05	3.006
Local/Access Road	12.886	20	226	WR-234	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	101.303	20	227	WR-234		Ward No. 04	2.047
Local/Access Road	101.303	20	227	WR-234		Ward No. 01	2.047
Local/Access Road	30.744	20	228	WR-232	TNT Office Road	Ward No. 05	3.963
Local/Access Road	80.821	20	229	WR-232		Ward No. 05	2.646
Local/Access Road	211.973	20	230	WR-231	TNT Office Road	Ward No. 05	3.963
Local/Access Road	211.973	20	230	WR-230	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.012	20	231	WR-23		Ward No. 05	3.412
Local/Access Road	107.993	20	232	WR-229		Ward No. 05	2.662
Local/Access Road	43.173	20	233	WR-229	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	43.173	20	233	WR-228	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	24.733	20	234	WR-227		Ward No. 05	2.58
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	19.301	20	236	WR-225		Ward No. 01	2.02
Local/Access Road	24.798	20	237	WR-224		Ward No. 01	3.417
Local/Access Road	48.985	20	238	WR-223		Ward No. 01	2.545
Local/Access Road	9.882	20	239	WR-221		Ward No. 01	2.136
Local/Access Road	46.171	20	240	WR-221		Ward No. 01	2.521
Local/Access Road	10.132	20	241	WR-220		Ward No. 01	2.124
Local/Access Road	130.993	20	242	WR-22	Upazilla Parisad Road	Ward No. 04	4.569

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	130.993	20	242	WR-217	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	156.036	20	243	WR-217		Ward No. 05	2.563
Local/Access Road	16.696	20	244	WR-215		Ward No. 01	2.112
Local/Access Road	9.602	20	245	WR-215		Ward No. 01	2.134
Local/Access Road	42.890	20	246	WR-214		Ward No. 01	2.534
Local/Access Road	28.277	20	248	WR-214	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.986	20	249	WR-212		Ward No. 01	2.534
Local/Access Road	28.567	20	250	WR-211		Ward No. 01	2.027
Local/Access Road	33.504	20	251	WR-210		Ward No. 01	2.013
Local/Access Road	21.871	20	252	WR-21	TNT Office Road	Ward No. 01	3.963
Local/Access Road	74.180	20	253	WR-208	TNT Office Road	Ward No. 01	3.963
Local/Access Road	131.986	20	254	WR-207		Ward No. 05	2.199
Local/Access Road	131.986	20	254	WR-207		Ward No. 01	2.199
Local/Access Road	90.645	20	255	WR-206		Ward No. 05	2.199
Local/Access Road	19.539	20	256	WR-205		Ward No. 01	2.096
Local/Access Road	61.338	20	257	WR-204		Ward No. 01	2.602
Local/Access Road	102.962	20	258	WR-203		Ward No. 01	3.15
Local/Access Road	50.968	20	259	WR-202		Ward No. 01	3.15
Local/Access Road	98.164	20	260	WR-200	TNT Office Road	Ward No. 01	3.963
Local/Access Road	39.365	20	261	WR-200		Ward No. 01	1.011
Local/Access Road	43.333	20	262	WR-20		Ward No. 01	1.991
Local/Access Road	101.371	20	263	WR-199	TNT Office Road	Ward No. 01	3.963
Local/Access Road	81.368	20	264	WR-198	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.327	20	265	WR-197		Ward No. 01	1.531
Local/Access Road	68.732	20	266	WR-196		Ward No. 01	1.513
Local/Access Road	13.394	20	267	WR-195		Ward No. 01	1.531
Local/Access Road	17.906	20	268	WR-194		Ward No. 01	1.513
Local/Access Road	13.524	20	269	WR-193		Ward No. 01	1.513
Local/Access Road	46.095	20	270	WR-192	TNT Office Road	Ward No. 01	3.963
Local/Access Road	109.827	20	271	WR-191		Ward No. 01	1.593
Local/Access Road	77.059	20	272	WR-191	TNT Office Road	Ward No. 01	3.963
Local/Access Road	278.669	20	273	WR-19	TNT Office Road	Ward No. 01	3.963
Local/Access Road	37.632	20	274	WR-189		Ward No. 01	1.508
Local/Access Road	269.941	20	275	WR-188	TNT Office Road	Ward No. 03	3.963
Local/Access Road	79.781	20	276	WR-188		Ward No. 03	1.503
Local/Access Road	57.331	20	277	WR-187		Ward No. 03	1.503
Local/Access Road	32.507	20	278	WR-186		Ward No. 01	2.054
Local/Access Road	28.586	20	279	WR-185		Ward No. 01	1.639
Local/Access Road	282.850	20	280	WR-184	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.326	20	281	WR-183	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.707	20	282	WR-182		Ward No. 01	2.011
Local/Access Road	63.817	20	283	WR-181		Ward No. 01	3.04
Local/Access Road	88.406	20	284	WR-180		Ward No. 01	3.04
Local/Access Road	89.512	20	285	WR-178		Ward No. 01	3.04
Local/Access Road	30.315	20	286	WR-178		Ward No. 01	1.995
Local/Access Road	33.167	20	287	WR-177	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.167	20	287	WR-176	TNT Office Road	Ward No. 03	3.963
Local/Access Road	15.693	20	288	WR-175		Ward No. 01	2.025
Local/Access Road	36.241	20	289	WR-174		Ward No. 01	1.99
Local/Access Road	289.425	20	290	WR-173		Ward No. 03	2.995
Local/Access Road	289.425	20	290	WR-172		Ward No. 02	2.995
Local/Access Road	60.058	20	292	WR-170		Ward No. 03	2.037
Local/Access Road	68.017	20	293	WR-17		Ward No. 01	2.026
Local/Access Road	68.017	20	293	WR-169		Ward No. 03	2.026
Local/Access Road	130.008	20	294	WR-168	TNT Office Road	Ward No. 03	3.963
Local/Access Road	12.034	20	295	WR-167		Ward No. 03	2.127
Local/Access Road	11.667	20	296	WR-166		Ward No. 03	2.076
Local/Access Road	17.426	20	297	WR-165		Ward No. 03	2.144
Local/Access Road	42.032	20	298	WR-164	TNT Office Road	Ward No. 03	3.963
Local/Access Road	150.774	20	299	WR-163		Ward No. 03	1.531
Local/Access Road	108.922	20	300	WR-162	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.369	20	301	WR-161		Ward No. 03	3.006
Local/Access Road	179.903	20	302	WR-160		Ward No. 03	3.001
Local/Access Road	67.096	20	303	WR-16		Ward No. 03	2.556
Local/Access Road	39.134	20	304	WR-159		Ward No. 03	2.556
Local/Access Road	50.329	20	306	WR-156		Ward No. 03	3.33
Local/Access Road	53.629	20	307	WR-156	TNT Office Road	Ward No. 03	3.963
Local/Access Road	16.882	20	308	WR-155		Ward No. 03	3.001

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	52.737	20	309	WR-154	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.018	20	310	WR-153	TNT Office Road	Ward No. 03	3.963
Local/Access Road	39.818	20	311	WR-152	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.452	20	312	WR-151	TNT Office Road	Ward No. 03	3.963
Local/Access Road	35.712	20	313	WR-150	TNT Office Road	Ward No. 03	3.963
Local/Access Road	26.264	20	315	WR-15	TNT Office Road	Ward No. 03	3.963
Local/Access Road	108.153	20	316	WR-148	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.676	20	317	WR-147	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.883	20	318	WR-145		Ward No. 03	2.055
Local/Access Road	42.975	20	319	WR-144	TNT Office Road	Ward No. 03	3.963
Local/Access Road	123.229	20	320	WR-141		Ward No. 02	5.027
Local/Access Road	51.280	20	321	WR-140	TNT Office Road	Ward No. 03	3.963
Local/Access Road	51.280	20	322	WR-138		Ward No. 02	3.963
Local/Access Road	464.379	20	322	WR-138		Ward No. 03	2.208
Local/Access Road	32.724	20	323	WR-137	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.057	20	324	WR-135	TNT Office Road	Ward No. 03	3.963
Local/Access Road	78.042	20	325	WR-131		Ward No. 03	2.127
Local/Access Road	434.075	20	326	WR-13		Ward No. 02	1.97
Local/Access Road	342.215	20	327	WR-13		Ward No. 03	2.742
Local/Access Road	79.045	20	328	WR-13		Ward No. 02	2.559
Local/Access Road	290.391	20	329	WR-125		Ward No. 02	1.502
Local/Access Road	206.448	20	330	WR-124		Ward No. 02	2.364
Local/Access Road	276.671	20	331	WR-122		Ward No. 02	6.678
Local/Access Road	47.087	20	332	WR-122		Ward No. 02	3.132
Local/Access Road	1121.400	20	333	WR-121		Ward No. 02	3.132
Local/Access Road	56.747	20	334	WR-12		Ward No. 02	1.242
Local/Access Road	240.242	20	335	WR-117		Ward No. 02	3.132
Local/Access Road	174.792	20	336	WR-116		Ward No. 02	6.678
Local/Access Road	30.317	20	337	WR-115		Ward No. 02	1.131
Local/Access Road	75.392	20	338	WR-114		Ward No. 02	3.132
Local/Access Road	251.225	20	339	WR-113		Ward No. 02	3.132
Local/Access Road	26.167	20	340	WR-112		Ward No. 02	3.132
Local/Access Road	35.513	20	341	WR-111		Ward No. 02	1.565
Local/Access Road	15.997	20	342	WR-110		Ward No. 02	1.048
Local/Access Road	30.980	20	343	WR-11		Ward No. 02	2.525
Local/Access Road	47.635	20	344	WR-109		Ward No. 02	3.132
Local/Access Road	81.911	20	345	WR-108		Ward No. 02	3.132
Local/Access Road	69.247	20	346	WR-106		Ward No. 02	2.12
Local/Access Road	55.144	20	348	WR-106		Ward No. 02	3.257
Local/Access Road	136.489	20	349	WR-104		Ward No. 02	3.257
Local/Access Road	393.674	20	350	WR-103		Ward No. 02	3.257
Local/Access Road	82.924	20	351	WR-102		Ward No. 02	2.103
Local/Access Road	126.541	20	352	WR-101		Ward No. 02	2.541
Local/Access Road	1361.006	40	353	WR-100		Ward No. 07	3.299
Local/Access Road	3.713	40	354	WR-10		Ward No. 04	2.139
Local/Access Road	2593.923	20	1	WR-98	Ninguin Notun Para School Road	Ward No. 11	3.1
Local/Access Road	2593.923	20	1	WR-97	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	71.352	20	3	WR-94		Ward No. 10	1.532
Local/Access Road	56.923	20	4	WR-92		Ward No. 10	1.489
Local/Access Road	175.075	20	5	WR-91		Ward No. 10	1.529
Local/Access Road	26.720	20	6	WR-90		Ward No. 10	1.582
Local/Access Road	99.117	20	7	WR-89		Ward No. 10	2.5
Local/Access Road	157.591	20	8	WR-88		Ward No. 10	2.5
Local/Access Road	255.066	20	10	WR-87		Ward No. 10	2.398
Local/Access Road	39.421	20	11	WR-86		Ward No. 10	1.527
Local/Access Road	568.825	20	12	WR-85		Ward No. 11	3.215
Local/Access Road	2008.607	20	13	WR-84		Ward No. 11	3.25
Local/Access Road	2008.607	20	13	WR-82		Ward No. 12	3.25
Local/Access Road	2008.607	20	13	WR-8		Ward No. 06	3.25
Local/Access Road	42.841	20	14	WR-79		Ward No. 10	1.555
Local/Access Road	78.482	20	15	WR-78		Ward No. 10	1.543
Local/Access Road	89.440	20	16	WR-74		Ward No. 10	2.398
Local/Access Road	22.687	20	17	WR-73		Ward No. 11	2.51
Local/Access Road	103.830	20	19	WR-72		Ward No. 11	1.656
Local/Access Road	315.944	20	20	WR-71		Ward No. 11	3.414

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	90.620	20	21	WR-70		Ward No. 10	2.095
Local/Access Road	40.463	20	22	WR-7		Ward No. 11	2.191
Local/Access Road	52.701	20	23	WR-69		Ward No. 11	2.191
Local/Access Road	60.048	20	24	WR-66		Ward No. 11	3.528
Local/Access Road	202.825	20	25	WR-64		Ward No. 11	3.033
Local/Access Road	29.850	20	26	WR-6		Ward No. 11	3.326
Local/Access Road	42.429	20	27	WR-57		Ward No. 11	2.089
Local/Access Road	132.092	20	28	WR-57		Ward No. 10	2.51
Local/Access Road	147.600	20	29	WR-55		Ward No. 11	3.037
Local/Access Road	21.144	20	30	WR-54		Ward No. 11	2.787
Local/Access Road	47.500	20	31	WR-53		Ward No. 11	3.079
Local/Access Road	19.802	20	32	WR-5		Ward No. 06	2.271
Local/Access Road	163.957	20	33	WR-49		Ward No. 11	1.746
Local/Access Road	175.239	20	34	WR-48		Ward No. 11	3.055
Local/Access Road	49.292	20	35	WR-46	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	118.448	20	36	WR-45		Ward No. 11	2.216
Local/Access Road	61.946	20	37	WR-44		Ward No. 09	2.102
Local/Access Road	146.110	20	38	WR-43		Ward No. 09	2.102
Local/Access Road	315.505	20	39	WR-42		Ward No. 09	3.02
Local/Access Road	143.051	20	40	WR-41		Ward No. 09	3.011
Local/Access Road	113.172	20	41	WR-40		Ward No. 09	3.041
Local/Access Road	168.611	20	42	WR-4		Ward No. 09	2.998
Local/Access Road	241.851	20	43	WR-39		Ward No. 09	2.998
Local/Access Road	70.636	20	44	WR-38		Ward No. 09	3.619
Local/Access Road	45.323	20	45	WR-37		Ward No. 09	2.382
Local/Access Road	94.300	20	46	WR-36		Ward No. 06	1.962
Local/Access Road	35.065	20	48	WR-355		Ward No. 06	2.189
Local/Access Road	108.658	20	49	WR-355		Ward No. 06	1.567
Local/Access Road	86.405	20	53	WR-353		Ward No. 09	2.03
Local/Access Road	64.841	20	54	WR-352		Ward No. 06	2.164
Local/Access Road	49.887	20	55	WR-351		Ward No. 09	2.215
Local/Access Road	29.661	20	57	WR-350		Ward No. 06	2.62
Local/Access Road	59.490	20	64	WR-35		Ward No. 09	2.028
Local/Access Road	41.772	20	66	WR-349		Ward No. 09	2.088
Local/Access Road	825.147	20	69	WR-348		Ward No. 06	2.696
Local/Access Road	58.763	20	70	WR-347		Ward No. 09	3.061
Local/Access Road	30.856	20	71	WR-345		Ward No. 09	1.663
Local/Access Road	38.950	20	72	WR-344		Ward No. 09	2.6
Local/Access Road	175.835	20	73	WR-343		Ward No. 09	2.547
Local/Access Road	18.957	20	74	WR-342		Ward No. 09	2.182
Local/Access Road	69.816	20	78	WR-341	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	23.368	20	79	WR-340		Ward No. 08	1.525
Local/Access Road	233.012	20	82	WR-34	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	79.925	20	84	WR-339	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	18.310	20	85	WR-338		Ward No. 08	1.605
Local/Access Road	44.365	20	86	WR-337	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	31.902	20	87	WR-336		Ward No. 08	2.08
Local/Access Road	19.949	20	88	WR-335	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	96.157	20	89	WR-334		Ward No. 08	2.614
Local/Access Road	5.911	20	90	WR-333		Ward No. 08	1.725
Local/Access Road	28.967	20	91	WR-332		Ward No. 08	2.784
Local/Access Road	20.533	20	92	WR-331	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	88.141	20	94	WR-330		Ward No. 08	3.062
Local/Access Road	50.931	20	97	WR-33		Ward No. 08	2.24
Local/Access Road	39.296	20	98	WR-329		Ward No. 08	2.046
Local/Access Road	84.139	20	101	WR-328		Ward No. 06	4.062
Local/Access Road	13.312	20	102	WR-327		Ward No. 08	4.539
Local/Access Road	24.517	20	103	WR-326		Ward No. 08	2.011
Local/Access Road	51.922	20	104	WR-325		Ward No. 08	2.011
Local/Access Road	28.305	20	105	WR-324		Ward No. 08	2.561
Local/Access Road	33.036	20	107	WR-323		Ward No. 12	2.709

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	33.036	20	107	WR-322		Ward No. 07	2.709
Local/Access Road	280.500	20	109	WR-321		Ward No. 08	6.083
Local/Access Road	95.832	20	110	WR-320		Ward No. 07	2.55
Local/Access Road	58.011	20	111	WR-320		Ward No. 07	2.649
Local/Access Road	70.846	20	112	WR-32		Ward No. 08	2.691
Local/Access Road	20.748	20	113	WR-319		Ward No. 08	1.994
Local/Access Road	56.643	20	114	WR-318	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	72.071	20	115	WR-317	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	120.852	20	116	WR-316		Ward No. 04	2.043
Local/Access Road	30.204	20	117	WR-315		Ward No. 06	6.867
Local/Access Road	219.325	20	118	WR-314		Ward No. 07	3.104
Local/Access Road	113.873	20	122	WR-312		Ward No. 08	4.101
Local/Access Road	218.782	20	123	WR-311	Balua Baua Jame Mosque Road	Ward No. 08	4.059
Local/Access Road	218.782	20	123	WR-310	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	113.274	20	125	WR-31		Ward No. 08	3.71
Local/Access Road	46.048	20	126	WR-309	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	107.580	20	132	WR-308	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	214.625	20	136	WR-307		Ward No. 07	3.104
Local/Access Road	175.773	20	138	WR-306		Ward No. 06	3.062
Local/Access Road	35.980	20	139	WR-305		Ward No. 07	2.555
Local/Access Road	48.372	20	141	WR-303		Ward No. 08	2.297
Local/Access Road	56.911	20	142	WR-302		Ward No. 07	1.049
Local/Access Road	151.193	20	145	WR-301		Ward No. 07	3.03
Local/Access Road	115.717	20	146	WR-300		Ward No. 07	2.523
Local/Access Road	21.101	20	148	WR-30		Ward No. 08	2.097
Local/Access Road	34.631	20	149	WR-3		Ward No. 07	2.149
Local/Access Road	17.416	20	151	WR-299		Ward No. 08	2.198
Local/Access Road	41.693	20	152	WR-298		Ward No. 08	2.198
Local/Access Road	71.911	20	153	WR-297	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	57.817	20	154	WR-296		Ward No. 07	2.63
Local/Access Road	48.611	20	155	WR-295		Ward No. 04	3.073
Local/Access Road	37.504	20	156	WR-294		Ward No. 04	2.109
Local/Access Road	137.947	20	157	WR-293		Ward No. 08	2.109
Local/Access Road	137.947	20	157	WR-292		Ward No. 04	2.109
Local/Access Road	95.696	20	158	WR-292		Ward No. 08	2.533
Local/Access Road	35.481	20	160	WR-291		Ward No. 04	1.568
Local/Access Road	106.762	20	161	WR-29		Ward No. 08	2.287
Local/Access Road	158.450	20	162	WR-289		Ward No. 08	2.605
Local/Access Road	70.012	20	163	WR-289		Ward No. 04	2.017
Local/Access Road	18.897	20	164	WR-288		Ward No. 04	2.275
Local/Access Road	96.546	20	165	WR-287		Ward No. 04	2.639
Local/Access Road	47.885	20	166	WR-286		Ward No. 08	2.147
Local/Access Road	20.596	20	167	WR-286		Ward No. 07	2.597
Local/Access Road	136.634	20	168	WR-285		Ward No. 07	2.196
Local/Access Road	140.973	20	169	WR-284		Ward No. 04	3.652
Local/Access Road	303.345	20	170	WR-283		Ward No. 07	2.924
Local/Access Road	68.250	20	171	WR-282		Ward No. 04	3.049
Local/Access Road	15.655	20	173	WR-281		Ward No. 04	2.714
Local/Access Road	28.799	20	174	WR-280		Ward No. 07	2.561
Local/Access Road	150.380	20	175	WR-28		Ward No. 07	3.03
Local/Access Road	17.735	20	176	WR-279		Ward No. 08	2.497
Local/Access Road	114.186	20	177	WR-278		Ward No. 07	2.41
Local/Access Road	17.918	20	178	WR-277		Ward No. 04	2.62
Local/Access Road	27.200	20	179	WR-276		Ward No. 04	3.296
Local/Access Road	27.200	20	179	WR-275		Ward No. 03	3.296
Local/Access Road	18.623	20	181	WR-274		Ward No. 04	2.628
Local/Access Road	61.702	20	182	WR-273		Ward No. 07	2.196
Local/Access Road	261.973	20	183	WR-272		Ward No. 07	2.517
Local/Access Road	77.754	20	184	WR-271		Ward No. 07	2.068
Local/Access Road	53.661	20	185	WR-270		Ward No. 07	3.299
Local/Access Road	176.509	20	186	WR-27		Ward No. 04	2.417
Local/Access Road	82.268	20	187	WR-269		Ward No. 08	2.555

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	45.216	20	188	WR-268		Ward No. 04	4.123
Local/Access Road	31.092	20	189	WR-267		Ward No. 04	2.689
Local/Access Road	31.092	20	189	WR-266		Ward No. 03	2.689
Local/Access Road	25.744	20	190	WR-265		Ward No. 04	3.677
Local/Access Road	60.880	20	192	WR-264		Ward No. 08	2.623
Local/Access Road	60.880	20	192	WR-263		Ward No. 05	2.623
Local/Access Road	446.939	20	193	WR-262	Singra -karanpari Road	Ward No. 07	4.537
Local/Access Road	6.439	20	194	WR-261		Ward No. 04	2.27
Local/Access Road	20.068	20	195	WR-260		Ward No. 07	3.299
Local/Access Road	123.966	20	196	WR-26		Ward No. 07	3.299
Local/Access Road	30.676	20	197	WR-259		Ward No. 04	2.712
Local/Access Road	81.180	20	198	WR-258		Ward No. 04	2.712
Local/Access Road	80.530	20	199	WR-257		Ward No. 04	2.08
Local/Access Road	54.920	20	200	WR-256		Ward No. 07	3.299
Local/Access Road	19.724	20	201	WR-255		Ward No. 05	2.21
Local/Access Road	19.724	20	201	WR-254		Ward No. 04	2.21
Local/Access Road	27.943	20	203	WR-253		Ward No. 06	3.312
Local/Access Road	41.105	20	204	WR-253		Ward No. 06	3.312
Local/Access Road	106.730	20	205	WR-252		Ward No. 04	2.417
Local/Access Road	36.077	20	206	WR-251		Ward No. 08	2.133
Local/Access Road	117.577	20	207	WR-250		Ward No. 04	2.547
Local/Access Road	22.234	20	208	WR-25		Ward No. 08	2.1
Local/Access Road	22.234	20	208	WR-249		Ward No. 05	2.1
Local/Access Road	46.751	20	209	WR-248		Ward No. 04	6.127
Local/Access Road	128.071	20	211	WR-247		Ward No. 04	2.263
Local/Access Road	35.682	20	212	WR-245		Ward No. 04	2.866
Local/Access Road	56.762	20	213	WR-244		Ward No. 04	2.866
Local/Access Road	143.153	20	215	WR-243		Ward No. 08	2.548
Local/Access Road	143.153	20	215	WR-242		Ward No. 05	2.548
Local/Access Road	21.046	20	216	WR-241		Ward No. 08	2.281
Local/Access Road	21.046	20	216	WR-241		Ward No. 05	2.281
Local/Access Road	10.213	20	218	WR-240	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	10.213	20	218	WR-24	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	39.119	20	221	WR-239		Ward No. 05	2.599
Local/Access Road	26.114	20	222	WR-238	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	26.114	20	222	WR-237	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	218.029	20	224	WR-236		Ward No. 05	3.006
Local/Access Road	212.759	20	225	WR-235		Ward No. 05	3.006
Local/Access Road	12.886	20	226	WR-234	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	101.303	20	227	WR-234		Ward No. 04	2.047
Local/Access Road	101.303	20	227	WR-234		Ward No. 01	2.047
Local/Access Road	30.744	20	228	WR-232	TNT Office Road	Ward No. 05	3.963
Local/Access Road	80.821	20	229	WR-232		Ward No. 05	2.646
Local/Access Road	211.973	20	230	WR-231	TNT Office Road	Ward No. 05	3.963
Local/Access Road	211.973	20	230	WR-230	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.012	20	231	WR-23		Ward No. 05	3.412
Local/Access Road	107.993	20	232	WR-229		Ward No. 05	2.662
Local/Access Road	43.173	20	233	WR-229	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	43.173	20	233	WR-228	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	24.733	20	234	WR-227		Ward No. 05	2.58
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	19.301	20	236	WR-225		Ward No. 01	2.02
Local/Access Road	24.798	20	237	WR-224		Ward No. 01	3.417
Local/Access Road	48.985	20	238	WR-223		Ward No. 01	2.545
Local/Access Road	9.882	20	239	WR-221		Ward No. 01	2.136
Local/Access Road	46.171	20	240	WR-221		Ward No. 01	2.521
Local/Access Road	10.132	20	241	WR-220		Ward No. 01	2.124
Local/Access Road	130.993	20	242	WR-22	Upazilla Parisad Road	Ward No. 04	4.569

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	130.993	20	242	WR-217	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	156.036	20	243	WR-217		Ward No. 05	2.563
Local/Access Road	16.696	20	244	WR-215		Ward No. 01	2.112
Local/Access Road	9.602	20	245	WR-215		Ward No. 01	2.134
Local/Access Road	42.890	20	246	WR-214		Ward No. 01	2.534
Local/Access Road	28.277	20	248	WR-214	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.986	20	249	WR-212		Ward No. 01	2.534
Local/Access Road	28.567	20	250	WR-211		Ward No. 01	2.027
Local/Access Road	33.504	20	251	WR-210		Ward No. 01	2.013
Local/Access Road	21.871	20	252	WR-21	TNT Office Road	Ward No. 01	3.963
Local/Access Road	74.180	20	253	WR-208	TNT Office Road	Ward No. 01	3.963
Local/Access Road	131.986	20	254	WR-207		Ward No. 05	2.199
Local/Access Road	131.986	20	254	WR-207		Ward No. 01	2.199
Local/Access Road	90.645	20	255	WR-206		Ward No. 05	2.199
Local/Access Road	19.539	20	256	WR-205		Ward No. 01	2.096
Local/Access Road	61.338	20	257	WR-204		Ward No. 01	2.602
Local/Access Road	102.962	20	258	WR-203		Ward No. 01	3.15
Local/Access Road	50.968	20	259	WR-202		Ward No. 01	3.15
Local/Access Road	98.164	20	260	WR-200	TNT Office Road	Ward No. 01	3.963
Local/Access Road	39.365	20	261	WR-200		Ward No. 01	1.011
Local/Access Road	43.333	20	262	WR-20		Ward No. 01	1.991
Local/Access Road	101.371	20	263	WR-199	TNT Office Road	Ward No. 01	3.963
Local/Access Road	81.368	20	264	WR-198	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.327	20	265	WR-197		Ward No. 01	1.531
Local/Access Road	68.732	20	266	WR-196		Ward No. 01	1.513
Local/Access Road	13.394	20	267	WR-195		Ward No. 01	1.531
Local/Access Road	17.906	20	268	WR-194		Ward No. 01	1.513
Local/Access Road	13.524	20	269	WR-193		Ward No. 01	1.513
Local/Access Road	46.095	20	270	WR-192	TNT Office Road	Ward No. 01	3.963
Local/Access Road	109.827	20	271	WR-191		Ward No. 01	1.593
Local/Access Road	77.059	20	272	WR-191	TNT Office Road	Ward No. 01	3.963
Local/Access Road	278.669	20	273	WR-19	TNT Office Road	Ward No. 01	3.963
Local/Access Road	37.632	20	274	WR-189		Ward No. 01	1.508
Local/Access Road	269.941	20	275	WR-188	TNT Office Road	Ward No. 03	3.963
Local/Access Road	79.781	20	276	WR-188		Ward No. 03	1.503
Local/Access Road	57.331	20	277	WR-187		Ward No. 03	1.503
Local/Access Road	32.507	20	278	WR-186		Ward No. 01	2.054
Local/Access Road	28.586	20	279	WR-185		Ward No. 01	1.639
Local/Access Road	282.850	20	280	WR-184	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.326	20	281	WR-183	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.707	20	282	WR-182		Ward No. 01	2.011
Local/Access Road	63.817	20	283	WR-181		Ward No. 01	3.04
Local/Access Road	88.406	20	284	WR-180		Ward No. 01	3.04
Local/Access Road	89.512	20	285	WR-178		Ward No. 01	3.04
Local/Access Road	30.315	20	286	WR-178		Ward No. 01	1.995
Local/Access Road	33.167	20	287	WR-177	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.167	20	287	WR-176	TNT Office Road	Ward No. 03	3.963
Local/Access Road	15.693	20	288	WR-175		Ward No. 01	2.025
Local/Access Road	36.241	20	289	WR-174		Ward No. 01	1.99
Local/Access Road	289.425	20	290	WR-173		Ward No. 03	2.995
Local/Access Road	289.425	20	290	WR-172		Ward No. 02	2.995
Local/Access Road	60.058	20	292	WR-170		Ward No. 03	2.037
Local/Access Road	68.017	20	293	WR-17		Ward No. 01	2.026
Local/Access Road	68.017	20	293	WR-169		Ward No. 03	2.026
Local/Access Road	130.008	20	294	WR-168	TNT Office Road	Ward No. 03	3.963
Local/Access Road	12.034	20	295	WR-167		Ward No. 03	2.127
Local/Access Road	11.667	20	296	WR-166		Ward No. 03	2.076
Local/Access Road	17.426	20	297	WR-165		Ward No. 03	2.144
Local/Access Road	42.032	20	298	WR-164	TNT Office Road	Ward No. 03	3.963
Local/Access Road	150.774	20	299	WR-163		Ward No. 03	1.531
Local/Access Road	108.922	20	300	WR-162	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.369	20	301	WR-161		Ward No. 03	3.006
Local/Access Road	179.903	20	302	WR-160		Ward No. 03	3.001
Local/Access Road	67.096	20	303	WR-16		Ward No. 03	2.556
Local/Access Road	39.134	20	304	WR-159		Ward No. 03	2.556
Local/Access Road	50.329	20	306	WR-156		Ward No. 03	3.33
Local/Access Road	53.629	20	307	WR-156	TNT Office Road	Ward No. 03	3.963
Local/Access Road	16.882	20	308	WR-155		Ward No. 03	3.001

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	52.737	20	309	WR-154	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.018	20	310	WR-153	TNT Office Road	Ward No. 03	3.963
Local/Access Road	39.818	20	311	WR-152	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.452	20	312	WR-151	TNT Office Road	Ward No. 03	3.963
Local/Access Road	35.712	20	313	WR-150	TNT Office Road	Ward No. 03	3.963
Local/Access Road	26.264	20	315	WR-15	TNT Office Road	Ward No. 03	3.963
Local/Access Road	108.153	20	316	WR-148	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.676	20	317	WR-147	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.883	20	318	WR-145		Ward No. 03	2.055
Local/Access Road	42.975	20	319	WR-144	TNT Office Road	Ward No. 03	3.963
Local/Access Road	123.229	20	320	WR-141		Ward No. 02	5.027
Local/Access Road	51.280	20	321	WR-140	TNT Office Road	Ward No. 03	3.963
Local/Access Road	51.280	20	322	WR-138		Ward No. 02	3.963
Local/Access Road	464.379	20	322	WR-138		Ward No. 03	2.208
Local/Access Road	32.724	20	323	WR-137	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.057	20	324	WR-135	TNT Office Road	Ward No. 03	3.963
Local/Access Road	78.042	20	325	WR-131		Ward No. 03	2.127
Local/Access Road	434.075	20	326	WR-13		Ward No. 02	1.97
Local/Access Road	342.215	20	327	WR-13		Ward No. 03	2.742
Local/Access Road	79.045	20	328	WR-13		Ward No. 02	2.559
Local/Access Road	290.391	20	329	WR-125		Ward No. 02	1.502
Local/Access Road	206.448	20	330	WR-124		Ward No. 02	2.364
Local/Access Road	276.671	20	331	WR-122		Ward No. 02	6.678
Local/Access Road	47.087	20	332	WR-122		Ward No. 02	3.132
Local/Access Road	1121.400	20	333	WR-121		Ward No. 02	3.132
Local/Access Road	56.747	20	334	WR-12		Ward No. 02	1.242
Local/Access Road	240.242	20	335	WR-117		Ward No. 02	3.132
Local/Access Road	174.792	20	336	WR-116		Ward No. 02	6.678
Local/Access Road	30.317	20	337	WR-115		Ward No. 02	1.131
Local/Access Road	75.392	20	338	WR-114		Ward No. 02	3.132
Local/Access Road	251.225	20	339	WR-113		Ward No. 02	3.132
Local/Access Road	26.167	20	340	WR-112		Ward No. 02	3.132
Local/Access Road	35.513	20	341	WR-111		Ward No. 02	1.565
Local/Access Road	15.997	20	342	WR-110		Ward No. 02	1.048
Local/Access Road	30.980	20	343	WR-11		Ward No. 02	2.525
Local/Access Road	47.635	20	344	WR-109		Ward No. 02	3.132
Local/Access Road	81.911	20	345	WR-108		Ward No. 02	3.132
Local/Access Road	69.247	20	346	WR-106		Ward No. 02	2.12
Local/Access Road	55.144	20	348	WR-106		Ward No. 02	3.257
Local/Access Road	136.489	20	349	WR-104		Ward No. 02	3.257
Local/Access Road	393.674	20	350	WR-103		Ward No. 02	3.257
Local/Access Road	82.924	20	351	WR-102		Ward No. 02	2.103
Local/Access Road	126.541	20	352	WR-101		Ward No. 02	2.541
Local/Access Road	1361.006	40	353	WR-100		Ward No. 07	3.299
Local/Access Road	3.713	40	354	WR-10		Ward No. 04	2.139
Local/Access Road	2593.923	20	1	WR-98	Ninguin Notun Para School Road	Ward No. 11	3.1
Local/Access Road	2593.923	20	1	WR-97	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	71.352	20	3	WR-94		Ward No. 10	1.532
Local/Access Road	56.923	20	4	WR-92		Ward No. 10	1.489
Local/Access Road	175.075	20	5	WR-91		Ward No. 10	1.529
Local/Access Road	26.720	20	6	WR-90		Ward No. 10	1.582
Local/Access Road	99.117	20	7	WR-89		Ward No. 10	2.5
Local/Access Road	157.591	20	8	WR-88		Ward No. 10	2.5
Local/Access Road	255.066	20	10	WR-87		Ward No. 10	2.398
Local/Access Road	39.421	20	11	WR-86		Ward No. 10	1.527
Local/Access Road	568.825	20	12	WR-85		Ward No. 11	3.215
Local/Access Road	2008.607	20	13	WR-84		Ward No. 11	3.25
Local/Access Road	2008.607	20	13	WR-82		Ward No. 12	3.25
Local/Access Road	2008.607	20	13	WR-8		Ward No. 06	3.25
Local/Access Road	42.841	20	14	WR-79		Ward No. 10	1.555
Local/Access Road	78.482	20	15	WR-78		Ward No. 10	1.543
Local/Access Road	89.440	20	16	WR-74		Ward No. 10	2.398
Local/Access Road	22.687	20	17	WR-73		Ward No. 11	2.51
Local/Access Road	103.830	20	19	WR-72		Ward No. 11	1.656
Local/Access Road	315.944	20	20	WR-71		Ward No. 11	3.414

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	90.620	20	21	WR-70		Ward No. 10	2.095
Local/Access Road	40.463	20	22	WR-7		Ward No. 11	2.191
Local/Access Road	52.701	20	23	WR-69		Ward No. 11	2.191
Local/Access Road	60.048	20	24	WR-66		Ward No. 11	3.528
Local/Access Road	202.825	20	25	WR-64		Ward No. 11	3.033
Local/Access Road	29.850	20	26	WR-6		Ward No. 11	3.326
Local/Access Road	42.429	20	27	WR-57		Ward No. 11	2.089
Local/Access Road	132.092	20	28	WR-57		Ward No. 10	2.51
Local/Access Road	147.600	20	29	WR-55		Ward No. 11	3.037
Local/Access Road	21.144	20	30	WR-54		Ward No. 11	2.787
Local/Access Road	47.500	20	31	WR-53		Ward No. 11	3.079
Local/Access Road	19.802	20	32	WR-5		Ward No. 06	2.271
Local/Access Road	163.957	20	33	WR-49		Ward No. 11	1.746
Local/Access Road	175.239	20	34	WR-48		Ward No. 11	3.055
Local/Access Road	49.292	20	35	WR-46	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	118.448	20	36	WR-45		Ward No. 11	2.216
Local/Access Road	61.946	20	37	WR-44		Ward No. 09	2.102
Local/Access Road	146.110	20	38	WR-43		Ward No. 09	2.102
Local/Access Road	315.505	20	39	WR-42		Ward No. 09	3.02
Local/Access Road	143.051	20	40	WR-41		Ward No. 09	3.011
Local/Access Road	113.172	20	41	WR-40		Ward No. 09	3.041
Local/Access Road	168.611	20	42	WR-4		Ward No. 09	2.998
Local/Access Road	241.851	20	43	WR-39		Ward No. 09	2.998
Local/Access Road	70.636	20	44	WR-38		Ward No. 09	3.619
Local/Access Road	45.323	20	45	WR-37		Ward No. 09	2.382
Local/Access Road	94.300	20	46	WR-36		Ward No. 06	1.962
Local/Access Road	35.065	20	48	WR-355		Ward No. 06	2.189
Local/Access Road	108.658	20	49	WR-355		Ward No. 06	1.567
Local/Access Road	86.405	20	53	WR-353		Ward No. 09	2.03
Local/Access Road	64.841	20	54	WR-352		Ward No. 06	2.164
Local/Access Road	49.887	20	55	WR-351		Ward No. 09	2.215
Local/Access Road	29.661	20	57	WR-350		Ward No. 06	2.62
Local/Access Road	59.490	20	64	WR-35		Ward No. 09	2.028
Local/Access Road	41.772	20	66	WR-349		Ward No. 09	2.088
Local/Access Road	825.147	20	69	WR-348		Ward No. 06	2.696
Local/Access Road	58.763	20	70	WR-347		Ward No. 09	3.061
Local/Access Road	30.856	20	71	WR-345		Ward No. 09	1.663
Local/Access Road	38.950	20	72	WR-344		Ward No. 09	2.6
Local/Access Road	175.835	20	73	WR-343		Ward No. 09	2.547
Local/Access Road	18.957	20	74	WR-342		Ward No. 09	2.182
Local/Access Road	69.816	20	78	WR-341	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	23.368	20	79	WR-340		Ward No. 08	1.525
Local/Access Road	233.012	20	82	WR-34	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	79.925	20	84	WR-339	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	18.310	20	85	WR-338		Ward No. 08	1.605
Local/Access Road	44.365	20	86	WR-337	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	31.902	20	87	WR-336		Ward No. 08	2.08
Local/Access Road	19.949	20	88	WR-335	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	96.157	20	89	WR-334		Ward No. 08	2.614
Local/Access Road	5.911	20	90	WR-333		Ward No. 08	1.725
Local/Access Road	28.967	20	91	WR-332		Ward No. 08	2.784
Local/Access Road	20.533	20	92	WR-331	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	88.141	20	94	WR-330		Ward No. 08	3.062
Local/Access Road	50.931	20	97	WR-33		Ward No. 08	2.24
Local/Access Road	39.296	20	98	WR-329		Ward No. 08	2.046
Local/Access Road	84.139	20	101	WR-328		Ward No. 06	4.062
Local/Access Road	13.312	20	102	WR-327		Ward No. 08	4.539
Local/Access Road	24.517	20	103	WR-326		Ward No. 08	2.011
Local/Access Road	51.922	20	104	WR-325		Ward No. 08	2.011
Local/Access Road	28.305	20	105	WR-324		Ward No. 08	2.561
Local/Access Road	33.036	20	107	WR-323		Ward No. 12	2.709

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	33.036	20	107	WR-322		Ward No. 07	2.709
Local/Access Road	280.500	20	109	WR-321		Ward No. 08	6.083
Local/Access Road	95.832	20	110	WR-320		Ward No. 07	2.55
Local/Access Road	58.011	20	111	WR-320		Ward No. 07	2.649
Local/Access Road	70.846	20	112	WR-32		Ward No. 08	2.691
Local/Access Road	20.748	20	113	WR-319		Ward No. 08	1.994
Local/Access Road	56.643	20	114	WR-318	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	72.071	20	115	WR-317	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	120.852	20	116	WR-316		Ward No. 04	2.043
Local/Access Road	30.204	20	117	WR-315		Ward No. 06	6.867
Local/Access Road	219.325	20	118	WR-314		Ward No. 07	3.104
Local/Access Road	113.873	20	122	WR-312		Ward No. 08	4.101
Local/Access Road	218.782	20	123	WR-311	Balua Baua Jame Mosque Road	Ward No. 08	4.059
Local/Access Road	218.782	20	123	WR-310	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	113.274	20	125	WR-31		Ward No. 08	3.71
Local/Access Road	46.048	20	126	WR-309	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	107.580	20	132	WR-308	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	214.625	20	136	WR-307		Ward No. 07	3.104
Local/Access Road	175.773	20	138	WR-306		Ward No. 06	3.062
Local/Access Road	35.980	20	139	WR-305		Ward No. 07	2.555
Local/Access Road	48.372	20	141	WR-303		Ward No. 08	2.297
Local/Access Road	56.911	20	142	WR-302		Ward No. 07	1.049
Local/Access Road	151.193	20	145	WR-301		Ward No. 07	3.03
Local/Access Road	115.717	20	146	WR-300		Ward No. 07	2.523
Local/Access Road	21.101	20	148	WR-30		Ward No. 08	2.097
Local/Access Road	34.631	20	149	WR-3		Ward No. 07	2.149
Local/Access Road	17.416	20	151	WR-299		Ward No. 08	2.198
Local/Access Road	41.693	20	152	WR-298		Ward No. 08	2.198
Local/Access Road	71.911	20	153	WR-297	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	57.817	20	154	WR-296		Ward No. 07	2.63
Local/Access Road	48.611	20	155	WR-295		Ward No. 04	3.073
Local/Access Road	37.504	20	156	WR-294		Ward No. 04	2.109
Local/Access Road	137.947	20	157	WR-293		Ward No. 08	2.109
Local/Access Road	137.947	20	157	WR-292		Ward No. 04	2.109
Local/Access Road	95.696	20	158	WR-292		Ward No. 08	2.533
Local/Access Road	35.481	20	160	WR-291		Ward No. 04	1.568
Local/Access Road	106.762	20	161	WR-29		Ward No. 08	2.287
Local/Access Road	158.450	20	162	WR-289		Ward No. 08	2.605
Local/Access Road	70.012	20	163	WR-289		Ward No. 04	2.017
Local/Access Road	18.897	20	164	WR-288		Ward No. 04	2.275
Local/Access Road	96.546	20	165	WR-287		Ward No. 04	2.639
Local/Access Road	47.885	20	166	WR-286		Ward No. 08	2.147
Local/Access Road	20.596	20	167	WR-286		Ward No. 07	2.597
Local/Access Road	136.634	20	168	WR-285		Ward No. 07	2.196
Local/Access Road	140.973	20	169	WR-284		Ward No. 04	3.652
Local/Access Road	303.345	20	170	WR-283		Ward No. 07	2.924
Local/Access Road	68.250	20	171	WR-282		Ward No. 04	3.049
Local/Access Road	15.655	20	173	WR-281		Ward No. 04	2.714
Local/Access Road	28.799	20	174	WR-280		Ward No. 07	2.561
Local/Access Road	150.380	20	175	WR-28		Ward No. 07	3.03
Local/Access Road	17.735	20	176	WR-279		Ward No. 08	2.497
Local/Access Road	114.186	20	177	WR-278		Ward No. 07	2.41
Local/Access Road	17.918	20	178	WR-277		Ward No. 04	2.62
Local/Access Road	27.200	20	179	WR-276		Ward No. 04	3.296
Local/Access Road	27.200	20	179	WR-275		Ward No. 03	3.296
Local/Access Road	18.623	20	181	WR-274		Ward No. 04	2.628
Local/Access Road	61.702	20	182	WR-273		Ward No. 07	2.196
Local/Access Road	261.973	20	183	WR-272		Ward No. 07	2.517
Local/Access Road	77.754	20	184	WR-271		Ward No. 07	2.068
Local/Access Road	53.661	20	185	WR-270		Ward No. 07	3.299
Local/Access Road	176.509	20	186	WR-27		Ward No. 04	2.417
Local/Access Road	82.268	20	187	WR-269		Ward No. 08	2.555

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	45.216	20	188	WR-268		Ward No. 04	4.123
Local/Access Road	31.092	20	189	WR-267		Ward No. 04	2.689
Local/Access Road	31.092	20	189	WR-266		Ward No. 03	2.689
Local/Access Road	25.744	20	190	WR-265		Ward No. 04	3.677
Local/Access Road	60.880	20	192	WR-264		Ward No. 08	2.623
Local/Access Road	60.880	20	192	WR-263		Ward No. 05	2.623
Local/Access Road	446.939	20	193	WR-262	Singra -karanpari Road	Ward No. 07	4.537
Local/Access Road	6.439	20	194	WR-261		Ward No. 04	2.27
Local/Access Road	20.068	20	195	WR-260		Ward No. 07	3.299
Local/Access Road	123.966	20	196	WR-26		Ward No. 07	3.299
Local/Access Road	30.676	20	197	WR-259		Ward No. 04	2.712
Local/Access Road	81.180	20	198	WR-258		Ward No. 04	2.712
Local/Access Road	80.530	20	199	WR-257		Ward No. 04	2.08
Local/Access Road	54.920	20	200	WR-256		Ward No. 07	3.299
Local/Access Road	19.724	20	201	WR-255		Ward No. 05	2.21
Local/Access Road	19.724	20	201	WR-254		Ward No. 04	2.21
Local/Access Road	27.943	20	203	WR-253		Ward No. 06	3.312
Local/Access Road	41.105	20	204	WR-253		Ward No. 06	3.312
Local/Access Road	106.730	20	205	WR-252		Ward No. 04	2.417
Local/Access Road	36.077	20	206	WR-251		Ward No. 08	2.133
Local/Access Road	117.577	20	207	WR-250		Ward No. 04	2.547
Local/Access Road	22.234	20	208	WR-25		Ward No. 08	2.1
Local/Access Road	22.234	20	208	WR-249		Ward No. 05	2.1
Local/Access Road	46.751	20	209	WR-248		Ward No. 04	6.127
Local/Access Road	128.071	20	211	WR-247		Ward No. 04	2.263
Local/Access Road	35.682	20	212	WR-245		Ward No. 04	2.866
Local/Access Road	56.762	20	213	WR-244		Ward No. 04	2.866
Local/Access Road	143.153	20	215	WR-243		Ward No. 08	2.548
Local/Access Road	143.153	20	215	WR-242		Ward No. 05	2.548
Local/Access Road	21.046	20	216	WR-241		Ward No. 08	2.281
Local/Access Road	21.046	20	216	WR-241		Ward No. 05	2.281
Local/Access Road	10.213	20	218	WR-240	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	10.213	20	218	WR-24	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	39.119	20	221	WR-239		Ward No. 05	2.599
Local/Access Road	26.114	20	222	WR-238	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	26.114	20	222	WR-237	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	218.029	20	224	WR-236		Ward No. 05	3.006
Local/Access Road	212.759	20	225	WR-235		Ward No. 05	3.006
Local/Access Road	12.886	20	226	WR-234	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	101.303	20	227	WR-234		Ward No. 04	2.047
Local/Access Road	101.303	20	227	WR-234		Ward No. 01	2.047
Local/Access Road	30.744	20	228	WR-232	TNT Office Road	Ward No. 05	3.963
Local/Access Road	80.821	20	229	WR-232		Ward No. 05	2.646
Local/Access Road	211.973	20	230	WR-231	TNT Office Road	Ward No. 05	3.963
Local/Access Road	211.973	20	230	WR-230	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.012	20	231	WR-23		Ward No. 05	3.412
Local/Access Road	107.993	20	232	WR-229		Ward No. 05	2.662
Local/Access Road	43.173	20	233	WR-229	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	43.173	20	233	WR-228	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	24.733	20	234	WR-227		Ward No. 05	2.58
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	19.301	20	236	WR-225		Ward No. 01	2.02
Local/Access Road	24.798	20	237	WR-224		Ward No. 01	3.417
Local/Access Road	48.985	20	238	WR-223		Ward No. 01	2.545
Local/Access Road	9.882	20	239	WR-221		Ward No. 01	2.136
Local/Access Road	46.171	20	240	WR-221		Ward No. 01	2.521
Local/Access Road	10.132	20	241	WR-220		Ward No. 01	2.124
Local/Access Road	130.993	20	242	WR-22	Upazilla Parisad Road	Ward No. 04	4.569

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	130.993	20	242	WR-217	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	156.036	20	243	WR-217		Ward No. 05	2.563
Local/Access Road	16.696	20	244	WR-215		Ward No. 01	2.112
Local/Access Road	9.602	20	245	WR-215		Ward No. 01	2.134
Local/Access Road	42.890	20	246	WR-214		Ward No. 01	2.534
Local/Access Road	28.277	20	248	WR-214	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.986	20	249	WR-212		Ward No. 01	2.534
Local/Access Road	28.567	20	250	WR-211		Ward No. 01	2.027
Local/Access Road	33.504	20	251	WR-210		Ward No. 01	2.013
Local/Access Road	21.871	20	252	WR-21	TNT Office Road	Ward No. 01	3.963
Local/Access Road	74.180	20	253	WR-208	TNT Office Road	Ward No. 01	3.963
Local/Access Road	131.986	20	254	WR-207		Ward No. 05	2.199
Local/Access Road	131.986	20	254	WR-207		Ward No. 01	2.199
Local/Access Road	90.645	20	255	WR-206		Ward No. 05	2.199
Local/Access Road	19.539	20	256	WR-205		Ward No. 01	2.096
Local/Access Road	61.338	20	257	WR-204		Ward No. 01	2.602
Local/Access Road	102.962	20	258	WR-203		Ward No. 01	3.15
Local/Access Road	50.968	20	259	WR-202		Ward No. 01	3.15
Local/Access Road	98.164	20	260	WR-200	TNT Office Road	Ward No. 01	3.963
Local/Access Road	39.365	20	261	WR-200		Ward No. 01	1.011
Local/Access Road	43.333	20	262	WR-20		Ward No. 01	1.991
Local/Access Road	101.371	20	263	WR-199	TNT Office Road	Ward No. 01	3.963
Local/Access Road	81.368	20	264	WR-198	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.327	20	265	WR-197		Ward No. 01	1.531
Local/Access Road	68.732	20	266	WR-196		Ward No. 01	1.513
Local/Access Road	13.394	20	267	WR-195		Ward No. 01	1.531
Local/Access Road	17.906	20	268	WR-194		Ward No. 01	1.513
Local/Access Road	13.524	20	269	WR-193		Ward No. 01	1.513
Local/Access Road	46.095	20	270	WR-192	TNT Office Road	Ward No. 01	3.963
Local/Access Road	109.827	20	271	WR-191		Ward No. 01	1.593
Local/Access Road	77.059	20	272	WR-191	TNT Office Road	Ward No. 01	3.963
Local/Access Road	278.669	20	273	WR-19	TNT Office Road	Ward No. 01	3.963
Local/Access Road	37.632	20	274	WR-189		Ward No. 01	1.508
Local/Access Road	269.941	20	275	WR-188	TNT Office Road	Ward No. 03	3.963
Local/Access Road	79.781	20	276	WR-188		Ward No. 03	1.503
Local/Access Road	57.331	20	277	WR-187		Ward No. 03	1.503
Local/Access Road	32.507	20	278	WR-186		Ward No. 01	2.054
Local/Access Road	28.586	20	279	WR-185		Ward No. 01	1.639
Local/Access Road	282.850	20	280	WR-184	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.326	20	281	WR-183	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.707	20	282	WR-182		Ward No. 01	2.011
Local/Access Road	63.817	20	283	WR-181		Ward No. 01	3.04
Local/Access Road	88.406	20	284	WR-180		Ward No. 01	3.04
Local/Access Road	89.512	20	285	WR-178		Ward No. 01	3.04
Local/Access Road	30.315	20	286	WR-178		Ward No. 01	1.995
Local/Access Road	33.167	20	287	WR-177	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.167	20	287	WR-176	TNT Office Road	Ward No. 03	3.963
Local/Access Road	15.693	20	288	WR-175		Ward No. 01	2.025
Local/Access Road	36.241	20	289	WR-174		Ward No. 01	1.99
Local/Access Road	289.425	20	290	WR-173		Ward No. 03	2.995
Local/Access Road	289.425	20	290	WR-172		Ward No. 02	2.995
Local/Access Road	60.058	20	292	WR-170		Ward No. 03	2.037
Local/Access Road	68.017	20	293	WR-17		Ward No. 01	2.026
Local/Access Road	68.017	20	293	WR-169		Ward No. 03	2.026
Local/Access Road	130.008	20	294	WR-168	TNT Office Road	Ward No. 03	3.963
Local/Access Road	12.034	20	295	WR-167		Ward No. 03	2.127
Local/Access Road	11.667	20	296	WR-166		Ward No. 03	2.076
Local/Access Road	17.426	20	297	WR-165		Ward No. 03	2.144
Local/Access Road	42.032	20	298	WR-164	TNT Office Road	Ward No. 03	3.963
Local/Access Road	150.774	20	299	WR-163		Ward No. 03	1.531
Local/Access Road	108.922	20	300	WR-162	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.369	20	301	WR-161		Ward No. 03	3.006
Local/Access Road	179.903	20	302	WR-160		Ward No. 03	3.001
Local/Access Road	67.096	20	303	WR-16		Ward No. 03	2.556
Local/Access Road	39.134	20	304	WR-159		Ward No. 03	2.556
Local/Access Road	50.329	20	306	WR-156		Ward No. 03	3.33
Local/Access Road	53.629	20	307	WR-156	TNT Office Road	Ward No. 03	3.963
Local/Access Road	16.882	20	308	WR-155		Ward No. 03	3.001

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	52.737	20	309	WR-154	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.018	20	310	WR-153	TNT Office Road	Ward No. 03	3.963
Local/Access Road	39.818	20	311	WR-152	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.452	20	312	WR-151	TNT Office Road	Ward No. 03	3.963
Local/Access Road	35.712	20	313	WR-150	TNT Office Road	Ward No. 03	3.963
Local/Access Road	26.264	20	315	WR-15	TNT Office Road	Ward No. 03	3.963
Local/Access Road	108.153	20	316	WR-148	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.676	20	317	WR-147	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.883	20	318	WR-145		Ward No. 03	2.055
Local/Access Road	42.975	20	319	WR-144	TNT Office Road	Ward No. 03	3.963
Local/Access Road	123.229	20	320	WR-141		Ward No. 02	5.027
Local/Access Road	51.280	20	321	WR-140	TNT Office Road	Ward No. 03	3.963
Local/Access Road	51.280	20	322	WR-138		Ward No. 02	3.963
Local/Access Road	464.379	20	322	WR-138		Ward No. 03	2.208
Local/Access Road	32.724	20	323	WR-137	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.057	20	324	WR-135	TNT Office Road	Ward No. 03	3.963
Local/Access Road	78.042	20	325	WR-131		Ward No. 03	2.127
Local/Access Road	434.075	20	326	WR-13		Ward No. 02	1.97
Local/Access Road	342.215	20	327	WR-13		Ward No. 03	2.742
Local/Access Road	79.045	20	328	WR-13		Ward No. 02	2.559
Local/Access Road	290.391	20	329	WR-125		Ward No. 02	1.502
Local/Access Road	206.448	20	330	WR-124		Ward No. 02	2.364
Local/Access Road	276.671	20	331	WR-122		Ward No. 02	6.678
Local/Access Road	47.087	20	332	WR-122		Ward No. 02	3.132
Local/Access Road	1121.400	20	333	WR-121		Ward No. 02	3.132
Local/Access Road	56.747	20	334	WR-12		Ward No. 02	1.242
Local/Access Road	240.242	20	335	WR-117		Ward No. 02	3.132
Local/Access Road	174.792	20	336	WR-116		Ward No. 02	6.678
Local/Access Road	30.317	20	337	WR-115		Ward No. 02	1.131
Local/Access Road	75.392	20	338	WR-114		Ward No. 02	3.132
Local/Access Road	251.225	20	339	WR-113		Ward No. 02	3.132
Local/Access Road	26.167	20	340	WR-112		Ward No. 02	3.132
Local/Access Road	35.513	20	341	WR-111		Ward No. 02	1.565
Local/Access Road	15.997	20	342	WR-110		Ward No. 02	1.048
Local/Access Road	30.980	20	343	WR-11		Ward No. 02	2.525
Local/Access Road	47.635	20	344	WR-109		Ward No. 02	3.132
Local/Access Road	81.911	20	345	WR-108		Ward No. 02	3.132
Local/Access Road	69.247	20	346	WR-106		Ward No. 02	2.12
Local/Access Road	55.144	20	348	WR-106		Ward No. 02	3.257
Local/Access Road	136.489	20	349	WR-104		Ward No. 02	3.257
Local/Access Road	393.674	20	350	WR-103		Ward No. 02	3.257
Local/Access Road	82.924	20	351	WR-102		Ward No. 02	2.103
Local/Access Road	126.541	20	352	WR-101		Ward No. 02	2.541
Local/Access Road	1361.006	40	353	WR-100		Ward No. 07	3.299
Local/Access Road	3.713	40	354	WR-10		Ward No. 04	2.139
Local/Access Road	2593.923	20	1	WR-98	Ninguin Notun Para School Road	Ward No. 11	3.1
Local/Access Road	2593.923	20	1	WR-97	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	71.352	20	3	WR-94		Ward No. 10	1.532
Local/Access Road	56.923	20	4	WR-92		Ward No. 10	1.489
Local/Access Road	175.075	20	5	WR-91		Ward No. 10	1.529
Local/Access Road	26.720	20	6	WR-90		Ward No. 10	1.582
Local/Access Road	99.117	20	7	WR-89		Ward No. 10	2.5
Local/Access Road	157.591	20	8	WR-88		Ward No. 10	2.5
Local/Access Road	255.066	20	10	WR-87		Ward No. 10	2.398
Local/Access Road	39.421	20	11	WR-86		Ward No. 10	1.527
Local/Access Road	568.825	20	12	WR-85		Ward No. 11	3.215
Local/Access Road	2008.607	20	13	WR-84		Ward No. 11	3.25
Local/Access Road	2008.607	20	13	WR-82		Ward No. 12	3.25
Local/Access Road	2008.607	20	13	WR-8		Ward No. 06	3.25
Local/Access Road	42.841	20	14	WR-79		Ward No. 10	1.555
Local/Access Road	78.482	20	15	WR-78		Ward No. 10	1.543
Local/Access Road	89.440	20	16	WR-74		Ward No. 10	2.398
Local/Access Road	22.687	20	17	WR-73		Ward No. 11	2.51
Local/Access Road	103.830	20	19	WR-72		Ward No. 11	1.656
Local/Access Road	315.944	20	20	WR-71		Ward No. 11	3.414

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	90.620	20	21	WR-70		Ward No. 10	2.095
Local/Access Road	40.463	20	22	WR-7		Ward No. 11	2.191
Local/Access Road	52.701	20	23	WR-69		Ward No. 11	2.191
Local/Access Road	60.048	20	24	WR-66		Ward No. 11	3.528
Local/Access Road	202.825	20	25	WR-64		Ward No. 11	3.033
Local/Access Road	29.850	20	26	WR-6		Ward No. 11	3.326
Local/Access Road	42.429	20	27	WR-57		Ward No. 11	2.089
Local/Access Road	132.092	20	28	WR-57		Ward No. 10	2.51
Local/Access Road	147.600	20	29	WR-55		Ward No. 11	3.037
Local/Access Road	21.144	20	30	WR-54		Ward No. 11	2.787
Local/Access Road	47.500	20	31	WR-53		Ward No. 11	3.079
Local/Access Road	19.802	20	32	WR-5		Ward No. 06	2.271
Local/Access Road	163.957	20	33	WR-49		Ward No. 11	1.746
Local/Access Road	175.239	20	34	WR-48		Ward No. 11	3.055
Local/Access Road	49.292	20	35	WR-46	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	118.448	20	36	WR-45		Ward No. 11	2.216
Local/Access Road	61.946	20	37	WR-44		Ward No. 09	2.102
Local/Access Road	146.110	20	38	WR-43		Ward No. 09	2.102
Local/Access Road	315.505	20	39	WR-42		Ward No. 09	3.02
Local/Access Road	143.051	20	40	WR-41		Ward No. 09	3.011
Local/Access Road	113.172	20	41	WR-40		Ward No. 09	3.041
Local/Access Road	168.611	20	42	WR-4		Ward No. 09	2.998
Local/Access Road	241.851	20	43	WR-39		Ward No. 09	2.998
Local/Access Road	70.636	20	44	WR-38		Ward No. 09	3.619
Local/Access Road	45.323	20	45	WR-37		Ward No. 09	2.382
Local/Access Road	94.300	20	46	WR-36		Ward No. 06	1.962
Local/Access Road	35.065	20	48	WR-355		Ward No. 06	2.189
Local/Access Road	108.658	20	49	WR-355		Ward No. 06	1.567
Local/Access Road	86.405	20	53	WR-353		Ward No. 09	2.03
Local/Access Road	64.841	20	54	WR-352		Ward No. 06	2.164
Local/Access Road	49.887	20	55	WR-351		Ward No. 09	2.215
Local/Access Road	29.661	20	57	WR-350		Ward No. 06	2.62
Local/Access Road	59.490	20	64	WR-35		Ward No. 09	2.028
Local/Access Road	41.772	20	66	WR-349		Ward No. 09	2.088
Local/Access Road	825.147	20	69	WR-348		Ward No. 06	2.696
Local/Access Road	58.763	20	70	WR-347		Ward No. 09	3.061
Local/Access Road	30.856	20	71	WR-345		Ward No. 09	1.663
Local/Access Road	38.950	20	72	WR-344		Ward No. 09	2.6
Local/Access Road	175.835	20	73	WR-343		Ward No. 09	2.547
Local/Access Road	18.957	20	74	WR-342		Ward No. 09	2.182
Local/Access Road	69.816	20	78	WR-341	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	23.368	20	79	WR-340		Ward No. 08	1.525
Local/Access Road	233.012	20	82	WR-34	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	79.925	20	84	WR-339	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	18.310	20	85	WR-338		Ward No. 08	1.605
Local/Access Road	44.365	20	86	WR-337	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	31.902	20	87	WR-336		Ward No. 08	2.08
Local/Access Road	19.949	20	88	WR-335	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	96.157	20	89	WR-334		Ward No. 08	2.614
Local/Access Road	5.911	20	90	WR-333		Ward No. 08	1.725
Local/Access Road	28.967	20	91	WR-332		Ward No. 08	2.784
Local/Access Road	20.533	20	92	WR-331	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	88.141	20	94	WR-330		Ward No. 08	3.062
Local/Access Road	50.931	20	97	WR-33		Ward No. 08	2.24
Local/Access Road	39.296	20	98	WR-329		Ward No. 08	2.046
Local/Access Road	84.139	20	101	WR-328		Ward No. 06	4.062
Local/Access Road	13.312	20	102	WR-327		Ward No. 08	4.539
Local/Access Road	24.517	20	103	WR-326		Ward No. 08	2.011
Local/Access Road	51.922	20	104	WR-325		Ward No. 08	2.011
Local/Access Road	28.305	20	105	WR-324		Ward No. 08	2.561
Local/Access Road	33.036	20	107	WR-323		Ward No. 12	2.709

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	33.036	20	107	WR-322		Ward No. 07	2.709
Local/Access Road	280.500	20	109	WR-321		Ward No. 08	6.083
Local/Access Road	95.832	20	110	WR-320		Ward No. 07	2.55
Local/Access Road	58.011	20	111	WR-320		Ward No. 07	2.649
Local/Access Road	70.846	20	112	WR-32		Ward No. 08	2.691
Local/Access Road	20.748	20	113	WR-319		Ward No. 08	1.994
Local/Access Road	56.643	20	114	WR-318	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	72.071	20	115	WR-317	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	120.852	20	116	WR-316		Ward No. 04	2.043
Local/Access Road	30.204	20	117	WR-315		Ward No. 06	6.867
Local/Access Road	219.325	20	118	WR-314		Ward No. 07	3.104
Local/Access Road	113.873	20	122	WR-312		Ward No. 08	4.101
Local/Access Road	218.782	20	123	WR-311	Balua Baua Jame Mosque Road	Ward No. 08	4.059
Local/Access Road	218.782	20	123	WR-310	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	113.274	20	125	WR-31		Ward No. 08	3.71
Local/Access Road	46.048	20	126	WR-309	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	107.580	20	132	WR-308	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	214.625	20	136	WR-307		Ward No. 07	3.104
Local/Access Road	175.773	20	138	WR-306		Ward No. 06	3.062
Local/Access Road	35.980	20	139	WR-305		Ward No. 07	2.555
Local/Access Road	48.372	20	141	WR-303		Ward No. 08	2.297
Local/Access Road	56.911	20	142	WR-302		Ward No. 07	1.049
Local/Access Road	151.193	20	145	WR-301		Ward No. 07	3.03
Local/Access Road	115.717	20	146	WR-300		Ward No. 07	2.523
Local/Access Road	21.101	20	148	WR-30		Ward No. 08	2.097
Local/Access Road	34.631	20	149	WR-3		Ward No. 07	2.149
Local/Access Road	17.416	20	151	WR-299		Ward No. 08	2.198
Local/Access Road	41.693	20	152	WR-298		Ward No. 08	2.198
Local/Access Road	71.911	20	153	WR-297	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	57.817	20	154	WR-296		Ward No. 07	2.63
Local/Access Road	48.611	20	155	WR-295		Ward No. 04	3.073
Local/Access Road	37.504	20	156	WR-294		Ward No. 04	2.109
Local/Access Road	137.947	20	157	WR-293		Ward No. 08	2.109
Local/Access Road	137.947	20	157	WR-292		Ward No. 04	2.109
Local/Access Road	95.696	20	158	WR-292		Ward No. 08	2.533
Local/Access Road	35.481	20	160	WR-291		Ward No. 04	1.568
Local/Access Road	106.762	20	161	WR-29		Ward No. 08	2.287
Local/Access Road	158.450	20	162	WR-289		Ward No. 08	2.605
Local/Access Road	70.012	20	163	WR-289		Ward No. 04	2.017
Local/Access Road	18.897	20	164	WR-288		Ward No. 04	2.275
Local/Access Road	96.546	20	165	WR-287		Ward No. 04	2.639
Local/Access Road	47.885	20	166	WR-286		Ward No. 08	2.147
Local/Access Road	20.596	20	167	WR-286		Ward No. 07	2.597
Local/Access Road	136.634	20	168	WR-285		Ward No. 07	2.196
Local/Access Road	140.973	20	169	WR-284		Ward No. 04	3.652
Local/Access Road	303.345	20	170	WR-283		Ward No. 07	2.924
Local/Access Road	68.250	20	171	WR-282		Ward No. 04	3.049
Local/Access Road	15.655	20	173	WR-281		Ward No. 04	2.714
Local/Access Road	28.799	20	174	WR-280		Ward No. 07	2.561
Local/Access Road	150.380	20	175	WR-28		Ward No. 07	3.03
Local/Access Road	17.735	20	176	WR-279		Ward No. 08	2.497
Local/Access Road	114.186	20	177	WR-278		Ward No. 07	2.41
Local/Access Road	17.918	20	178	WR-277		Ward No. 04	2.62
Local/Access Road	27.200	20	179	WR-276		Ward No. 04	3.296
Local/Access Road	27.200	20	179	WR-275		Ward No. 03	3.296
Local/Access Road	18.623	20	181	WR-274		Ward No. 04	2.628
Local/Access Road	61.702	20	182	WR-273		Ward No. 07	2.196
Local/Access Road	261.973	20	183	WR-272		Ward No. 07	2.517
Local/Access Road	77.754	20	184	WR-271		Ward No. 07	2.068
Local/Access Road	53.661	20	185	WR-270		Ward No. 07	3.299
Local/Access Road	176.509	20	186	WR-27		Ward No. 04	2.417
Local/Access Road	82.268	20	187	WR-269		Ward No. 08	2.555

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	45.216	20	188	WR-268		Ward No. 04	4.123
Local/Access Road	31.092	20	189	WR-267		Ward No. 04	2.689
Local/Access Road	31.092	20	189	WR-266		Ward No. 03	2.689
Local/Access Road	25.744	20	190	WR-265		Ward No. 04	3.677
Local/Access Road	60.880	20	192	WR-264		Ward No. 08	2.623
Local/Access Road	60.880	20	192	WR-263		Ward No. 05	2.623
Local/Access Road	446.939	20	193	WR-262	Singra -karanpari Road	Ward No. 07	4.537
Local/Access Road	6.439	20	194	WR-261		Ward No. 04	2.27
Local/Access Road	20.068	20	195	WR-260		Ward No. 07	3.299
Local/Access Road	123.966	20	196	WR-26		Ward No. 07	3.299
Local/Access Road	30.676	20	197	WR-259		Ward No. 04	2.712
Local/Access Road	81.180	20	198	WR-258		Ward No. 04	2.712
Local/Access Road	80.530	20	199	WR-257		Ward No. 04	2.08
Local/Access Road	54.920	20	200	WR-256		Ward No. 07	3.299
Local/Access Road	19.724	20	201	WR-255		Ward No. 05	2.21
Local/Access Road	19.724	20	201	WR-254		Ward No. 04	2.21
Local/Access Road	27.943	20	203	WR-253		Ward No. 06	3.312
Local/Access Road	41.105	20	204	WR-253		Ward No. 06	3.312
Local/Access Road	106.730	20	205	WR-252		Ward No. 04	2.417
Local/Access Road	36.077	20	206	WR-251		Ward No. 08	2.133
Local/Access Road	117.577	20	207	WR-250		Ward No. 04	2.547
Local/Access Road	22.234	20	208	WR-25		Ward No. 08	2.1
Local/Access Road	22.234	20	208	WR-249		Ward No. 05	2.1
Local/Access Road	46.751	20	209	WR-248		Ward No. 04	6.127
Local/Access Road	128.071	20	211	WR-247		Ward No. 04	2.263
Local/Access Road	35.682	20	212	WR-245		Ward No. 04	2.866
Local/Access Road	56.762	20	213	WR-244		Ward No. 04	2.866
Local/Access Road	143.153	20	215	WR-243		Ward No. 08	2.548
Local/Access Road	143.153	20	215	WR-242		Ward No. 05	2.548
Local/Access Road	21.046	20	216	WR-241		Ward No. 08	2.281
Local/Access Road	21.046	20	216	WR-241		Ward No. 05	2.281
Local/Access Road	10.213	20	218	WR-240	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	10.213	20	218	WR-24	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	39.119	20	221	WR-239		Ward No. 05	2.599
Local/Access Road	26.114	20	222	WR-238	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	26.114	20	222	WR-237	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	218.029	20	224	WR-236		Ward No. 05	3.006
Local/Access Road	212.759	20	225	WR-235		Ward No. 05	3.006
Local/Access Road	12.886	20	226	WR-234	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	101.303	20	227	WR-234		Ward No. 04	2.047
Local/Access Road	101.303	20	227	WR-234		Ward No. 01	2.047
Local/Access Road	30.744	20	228	WR-232	TNT Office Road	Ward No. 05	3.963
Local/Access Road	80.821	20	229	WR-232		Ward No. 05	2.646
Local/Access Road	211.973	20	230	WR-231	TNT Office Road	Ward No. 05	3.963
Local/Access Road	211.973	20	230	WR-230	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.012	20	231	WR-23		Ward No. 05	3.412
Local/Access Road	107.993	20	232	WR-229		Ward No. 05	2.662
Local/Access Road	43.173	20	233	WR-229	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	43.173	20	233	WR-228	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	24.733	20	234	WR-227		Ward No. 05	2.58
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	19.301	20	236	WR-225		Ward No. 01	2.02
Local/Access Road	24.798	20	237	WR-224		Ward No. 01	3.417
Local/Access Road	48.985	20	238	WR-223		Ward No. 01	2.545
Local/Access Road	9.882	20	239	WR-221		Ward No. 01	2.136
Local/Access Road	46.171	20	240	WR-221		Ward No. 01	2.521
Local/Access Road	10.132	20	241	WR-220		Ward No. 01	2.124
Local/Access Road	130.993	20	242	WR-22	Upazilla Parisad Road	Ward No. 04	4.569

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	130.993	20	242	WR-217	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	156.036	20	243	WR-217		Ward No. 05	2.563
Local/Access Road	16.696	20	244	WR-215		Ward No. 01	2.112
Local/Access Road	9.602	20	245	WR-215		Ward No. 01	2.134
Local/Access Road	42.890	20	246	WR-214		Ward No. 01	2.534
Local/Access Road	28.277	20	248	WR-214	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.986	20	249	WR-212		Ward No. 01	2.534
Local/Access Road	28.567	20	250	WR-211		Ward No. 01	2.027
Local/Access Road	33.504	20	251	WR-210		Ward No. 01	2.013
Local/Access Road	21.871	20	252	WR-21	TNT Office Road	Ward No. 01	3.963
Local/Access Road	74.180	20	253	WR-208	TNT Office Road	Ward No. 01	3.963
Local/Access Road	131.986	20	254	WR-207		Ward No. 05	2.199
Local/Access Road	131.986	20	254	WR-207		Ward No. 01	2.199
Local/Access Road	90.645	20	255	WR-206		Ward No. 05	2.199
Local/Access Road	19.539	20	256	WR-205		Ward No. 01	2.096
Local/Access Road	61.338	20	257	WR-204		Ward No. 01	2.602
Local/Access Road	102.962	20	258	WR-203		Ward No. 01	3.15
Local/Access Road	50.968	20	259	WR-202		Ward No. 01	3.15
Local/Access Road	98.164	20	260	WR-200	TNT Office Road	Ward No. 01	3.963
Local/Access Road	39.365	20	261	WR-200		Ward No. 01	1.011
Local/Access Road	43.333	20	262	WR-20		Ward No. 01	1.991
Local/Access Road	101.371	20	263	WR-199	TNT Office Road	Ward No. 01	3.963
Local/Access Road	81.368	20	264	WR-198	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.327	20	265	WR-197		Ward No. 01	1.531
Local/Access Road	68.732	20	266	WR-196		Ward No. 01	1.513
Local/Access Road	13.394	20	267	WR-195		Ward No. 01	1.531
Local/Access Road	17.906	20	268	WR-194		Ward No. 01	1.513
Local/Access Road	13.524	20	269	WR-193		Ward No. 01	1.513
Local/Access Road	46.095	20	270	WR-192	TNT Office Road	Ward No. 01	3.963
Local/Access Road	109.827	20	271	WR-191		Ward No. 01	1.593
Local/Access Road	77.059	20	272	WR-191	TNT Office Road	Ward No. 01	3.963
Local/Access Road	278.669	20	273	WR-19	TNT Office Road	Ward No. 01	3.963
Local/Access Road	37.632	20	274	WR-189		Ward No. 01	1.508
Local/Access Road	269.941	20	275	WR-188	TNT Office Road	Ward No. 03	3.963
Local/Access Road	79.781	20	276	WR-188		Ward No. 03	1.503
Local/Access Road	57.331	20	277	WR-187		Ward No. 03	1.503
Local/Access Road	32.507	20	278	WR-186		Ward No. 01	2.054
Local/Access Road	28.586	20	279	WR-185		Ward No. 01	1.639
Local/Access Road	282.850	20	280	WR-184	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.326	20	281	WR-183	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.707	20	282	WR-182		Ward No. 01	2.011
Local/Access Road	63.817	20	283	WR-181		Ward No. 01	3.04
Local/Access Road	88.406	20	284	WR-180		Ward No. 01	3.04
Local/Access Road	89.512	20	285	WR-178		Ward No. 01	3.04
Local/Access Road	30.315	20	286	WR-178		Ward No. 01	1.995
Local/Access Road	33.167	20	287	WR-177	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.167	20	287	WR-176	TNT Office Road	Ward No. 03	3.963
Local/Access Road	15.693	20	288	WR-175		Ward No. 01	2.025
Local/Access Road	36.241	20	289	WR-174		Ward No. 01	1.99
Local/Access Road	289.425	20	290	WR-173		Ward No. 03	2.995
Local/Access Road	289.425	20	290	WR-172		Ward No. 02	2.995
Local/Access Road	60.058	20	292	WR-170		Ward No. 03	2.037
Local/Access Road	68.017	20	293	WR-17		Ward No. 01	2.026
Local/Access Road	68.017	20	293	WR-169		Ward No. 03	2.026
Local/Access Road	130.008	20	294	WR-168	TNT Office Road	Ward No. 03	3.963
Local/Access Road	12.034	20	295	WR-167		Ward No. 03	2.127
Local/Access Road	11.667	20	296	WR-166		Ward No. 03	2.076
Local/Access Road	17.426	20	297	WR-165		Ward No. 03	2.144
Local/Access Road	42.032	20	298	WR-164	TNT Office Road	Ward No. 03	3.963
Local/Access Road	150.774	20	299	WR-163		Ward No. 03	1.531
Local/Access Road	108.922	20	300	WR-162	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.369	20	301	WR-161		Ward No. 03	3.006
Local/Access Road	179.903	20	302	WR-160		Ward No. 03	3.001
Local/Access Road	67.096	20	303	WR-16		Ward No. 03	2.556
Local/Access Road	39.134	20	304	WR-159		Ward No. 03	2.556
Local/Access Road	50.329	20	306	WR-156		Ward No. 03	3.33
Local/Access Road	53.629	20	307	WR-156	TNT Office Road	Ward No. 03	3.963
Local/Access Road	16.882	20	308	WR-155		Ward No. 03	3.001

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	52.737	20	309	WR-154	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.018	20	310	WR-153	TNT Office Road	Ward No. 03	3.963
Local/Access Road	39.818	20	311	WR-152	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.452	20	312	WR-151	TNT Office Road	Ward No. 03	3.963
Local/Access Road	35.712	20	313	WR-150	TNT Office Road	Ward No. 03	3.963
Local/Access Road	26.264	20	315	WR-15	TNT Office Road	Ward No. 03	3.963
Local/Access Road	108.153	20	316	WR-148	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.676	20	317	WR-147	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.883	20	318	WR-145		Ward No. 03	2.055
Local/Access Road	42.975	20	319	WR-144	TNT Office Road	Ward No. 03	3.963
Local/Access Road	123.229	20	320	WR-141		Ward No. 02	5.027
Local/Access Road	51.280	20	321	WR-140	TNT Office Road	Ward No. 03	3.963
Local/Access Road	51.280	20	322	WR-138		Ward No. 02	3.963
Local/Access Road	464.379	20	322	WR-138		Ward No. 03	2.208
Local/Access Road	32.724	20	323	WR-137	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.057	20	324	WR-135	TNT Office Road	Ward No. 03	3.963
Local/Access Road	78.042	20	325	WR-131		Ward No. 03	2.127
Local/Access Road	434.075	20	326	WR-13		Ward No. 02	1.97
Local/Access Road	342.215	20	327	WR-13		Ward No. 03	2.742
Local/Access Road	79.045	20	328	WR-13		Ward No. 02	2.559
Local/Access Road	290.391	20	329	WR-125		Ward No. 02	1.502
Local/Access Road	206.448	20	330	WR-124		Ward No. 02	2.364
Local/Access Road	276.671	20	331	WR-122		Ward No. 02	6.678
Local/Access Road	47.087	20	332	WR-122		Ward No. 02	3.132
Local/Access Road	1121.400	20	333	WR-121		Ward No. 02	3.132
Local/Access Road	56.747	20	334	WR-12		Ward No. 02	1.242
Local/Access Road	240.242	20	335	WR-117		Ward No. 02	3.132
Local/Access Road	174.792	20	336	WR-116		Ward No. 02	6.678
Local/Access Road	30.317	20	337	WR-115		Ward No. 02	1.131
Local/Access Road	75.392	20	338	WR-114		Ward No. 02	3.132
Local/Access Road	251.225	20	339	WR-113		Ward No. 02	3.132
Local/Access Road	26.167	20	340	WR-112		Ward No. 02	3.132
Local/Access Road	35.513	20	341	WR-111		Ward No. 02	1.565
Local/Access Road	15.997	20	342	WR-110		Ward No. 02	1.048
Local/Access Road	30.980	20	343	WR-11		Ward No. 02	2.525
Local/Access Road	47.635	20	344	WR-109		Ward No. 02	3.132
Local/Access Road	81.911	20	345	WR-108		Ward No. 02	3.132
Local/Access Road	69.247	20	346	WR-106		Ward No. 02	2.12
Local/Access Road	55.144	20	348	WR-106		Ward No. 02	3.257
Local/Access Road	136.489	20	349	WR-104		Ward No. 02	3.257
Local/Access Road	393.674	20	350	WR-103		Ward No. 02	3.257
Local/Access Road	82.924	20	351	WR-102		Ward No. 02	2.103
Local/Access Road	126.541	20	352	WR-101		Ward No. 02	2.541
Local/Access Road	1361.006	40	353	WR-100		Ward No. 07	3.299
Local/Access Road	3.713	40	354	WR-10		Ward No. 04	2.139
Local/Access Road	2593.923	20	1	WR-98	Ninguin Notun Para School Road	Ward No. 11	3.1
Local/Access Road	2593.923	20	1	WR-97	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	71.352	20	3	WR-94		Ward No. 10	1.532
Local/Access Road	56.923	20	4	WR-92		Ward No. 10	1.489
Local/Access Road	175.075	20	5	WR-91		Ward No. 10	1.529
Local/Access Road	26.720	20	6	WR-90		Ward No. 10	1.582
Local/Access Road	99.117	20	7	WR-89		Ward No. 10	2.5
Local/Access Road	157.591	20	8	WR-88		Ward No. 10	2.5
Local/Access Road	255.066	20	10	WR-87		Ward No. 10	2.398
Local/Access Road	39.421	20	11	WR-86		Ward No. 10	1.527
Local/Access Road	568.825	20	12	WR-85		Ward No. 11	3.215
Local/Access Road	2008.607	20	13	WR-84		Ward No. 11	3.25
Local/Access Road	2008.607	20	13	WR-82		Ward No. 12	3.25
Local/Access Road	2008.607	20	13	WR-8		Ward No. 06	3.25
Local/Access Road	42.841	20	14	WR-79		Ward No. 10	1.555
Local/Access Road	78.482	20	15	WR-78		Ward No. 10	1.543
Local/Access Road	89.440	20	16	WR-74		Ward No. 10	2.398
Local/Access Road	22.687	20	17	WR-73		Ward No. 11	2.51
Local/Access Road	103.830	20	19	WR-72		Ward No. 11	1.656
Local/Access Road	315.944	20	20	WR-71		Ward No. 11	3.414

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	90.620	20	21	WR-70		Ward No. 10	2.095
Local/Access Road	40.463	20	22	WR-7		Ward No. 11	2.191
Local/Access Road	52.701	20	23	WR-69		Ward No. 11	2.191
Local/Access Road	60.048	20	24	WR-66		Ward No. 11	3.528
Local/Access Road	202.825	20	25	WR-64		Ward No. 11	3.033
Local/Access Road	29.850	20	26	WR-6		Ward No. 11	3.326
Local/Access Road	42.429	20	27	WR-57		Ward No. 11	2.089
Local/Access Road	132.092	20	28	WR-57		Ward No. 10	2.51
Local/Access Road	147.600	20	29	WR-55		Ward No. 11	3.037
Local/Access Road	21.144	20	30	WR-54		Ward No. 11	2.787
Local/Access Road	47.500	20	31	WR-53		Ward No. 11	3.079
Local/Access Road	19.802	20	32	WR-5		Ward No. 06	2.271
Local/Access Road	163.957	20	33	WR-49		Ward No. 11	1.746
Local/Access Road	175.239	20	34	WR-48		Ward No. 11	3.055
Local/Access Road	49.292	20	35	WR-46	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	118.448	20	36	WR-45		Ward No. 11	2.216
Local/Access Road	61.946	20	37	WR-44		Ward No. 09	2.102
Local/Access Road	146.110	20	38	WR-43		Ward No. 09	2.102
Local/Access Road	315.505	20	39	WR-42		Ward No. 09	3.02
Local/Access Road	143.051	20	40	WR-41		Ward No. 09	3.011
Local/Access Road	113.172	20	41	WR-40		Ward No. 09	3.041
Local/Access Road	168.611	20	42	WR-4		Ward No. 09	2.998
Local/Access Road	241.851	20	43	WR-39		Ward No. 09	2.998
Local/Access Road	70.636	20	44	WR-38		Ward No. 09	3.619
Local/Access Road	45.323	20	45	WR-37		Ward No. 09	2.382
Local/Access Road	94.300	20	46	WR-36		Ward No. 06	1.962
Local/Access Road	35.065	20	48	WR-355		Ward No. 06	2.189
Local/Access Road	108.658	20	49	WR-355		Ward No. 06	1.567
Local/Access Road	86.405	20	53	WR-353		Ward No. 09	2.03
Local/Access Road	64.841	20	54	WR-352		Ward No. 06	2.164
Local/Access Road	49.887	20	55	WR-351		Ward No. 09	2.215
Local/Access Road	29.661	20	57	WR-350		Ward No. 06	2.62
Local/Access Road	59.490	20	64	WR-35		Ward No. 09	2.028
Local/Access Road	41.772	20	66	WR-349		Ward No. 09	2.088
Local/Access Road	825.147	20	69	WR-348		Ward No. 06	2.696
Local/Access Road	58.763	20	70	WR-347		Ward No. 09	3.061
Local/Access Road	30.856	20	71	WR-345		Ward No. 09	1.663
Local/Access Road	38.950	20	72	WR-344		Ward No. 09	2.6
Local/Access Road	175.835	20	73	WR-343		Ward No. 09	2.547
Local/Access Road	18.957	20	74	WR-342		Ward No. 09	2.182
Local/Access Road	69.816	20	78	WR-341	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	23.368	20	79	WR-340		Ward No. 08	1.525
Local/Access Road	233.012	20	82	WR-34	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	79.925	20	84	WR-339	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	18.310	20	85	WR-338		Ward No. 08	1.605
Local/Access Road	44.365	20	86	WR-337	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	31.902	20	87	WR-336		Ward No. 08	2.08
Local/Access Road	19.949	20	88	WR-335	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	96.157	20	89	WR-334		Ward No. 08	2.614
Local/Access Road	5.911	20	90	WR-333		Ward No. 08	1.725
Local/Access Road	28.967	20	91	WR-332		Ward No. 08	2.784
Local/Access Road	20.533	20	92	WR-331	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	88.141	20	94	WR-330		Ward No. 08	3.062
Local/Access Road	50.931	20	97	WR-33		Ward No. 08	2.24
Local/Access Road	39.296	20	98	WR-329		Ward No. 08	2.046
Local/Access Road	84.139	20	101	WR-328		Ward No. 06	4.062
Local/Access Road	13.312	20	102	WR-327		Ward No. 08	4.539
Local/Access Road	24.517	20	103	WR-326		Ward No. 08	2.011
Local/Access Road	51.922	20	104	WR-325		Ward No. 08	2.011
Local/Access Road	28.305	20	105	WR-324		Ward No. 08	2.561
Local/Access Road	33.036	20	107	WR-323		Ward No. 12	2.709

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	33.036	20	107	WR-322		Ward No. 07	2.709
Local/Access Road	280.500	20	109	WR-321		Ward No. 08	6.083
Local/Access Road	95.832	20	110	WR-320		Ward No. 07	2.55
Local/Access Road	58.011	20	111	WR-320		Ward No. 07	2.649
Local/Access Road	70.846	20	112	WR-32		Ward No. 08	2.691
Local/Access Road	20.748	20	113	WR-319		Ward No. 08	1.994
Local/Access Road	56.643	20	114	WR-318	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	72.071	20	115	WR-317	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	120.852	20	116	WR-316		Ward No. 04	2.043
Local/Access Road	30.204	20	117	WR-315		Ward No. 06	6.867
Local/Access Road	219.325	20	118	WR-314		Ward No. 07	3.104
Local/Access Road	113.873	20	122	WR-312		Ward No. 08	4.101
Local/Access Road	218.782	20	123	WR-311	Balua Baua Jame Mosque Road	Ward No. 08	4.059
Local/Access Road	218.782	20	123	WR-310	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	113.274	20	125	WR-31		Ward No. 08	3.71
Local/Access Road	46.048	20	126	WR-309	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	107.580	20	132	WR-308	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	214.625	20	136	WR-307		Ward No. 07	3.104
Local/Access Road	175.773	20	138	WR-306		Ward No. 06	3.062
Local/Access Road	35.980	20	139	WR-305		Ward No. 07	2.555
Local/Access Road	48.372	20	141	WR-303		Ward No. 08	2.297
Local/Access Road	56.911	20	142	WR-302		Ward No. 07	1.049
Local/Access Road	151.193	20	145	WR-301		Ward No. 07	3.03
Local/Access Road	115.717	20	146	WR-300		Ward No. 07	2.523
Local/Access Road	21.101	20	148	WR-30		Ward No. 08	2.097
Local/Access Road	34.631	20	149	WR-3		Ward No. 07	2.149
Local/Access Road	17.416	20	151	WR-299		Ward No. 08	2.198
Local/Access Road	41.693	20	152	WR-298		Ward No. 08	2.198
Local/Access Road	71.911	20	153	WR-297	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	57.817	20	154	WR-296		Ward No. 07	2.63
Local/Access Road	48.611	20	155	WR-295		Ward No. 04	3.073
Local/Access Road	37.504	20	156	WR-294		Ward No. 04	2.109
Local/Access Road	137.947	20	157	WR-293		Ward No. 08	2.109
Local/Access Road	137.947	20	157	WR-292		Ward No. 04	2.109
Local/Access Road	95.696	20	158	WR-292		Ward No. 08	2.533
Local/Access Road	35.481	20	160	WR-291		Ward No. 04	1.568
Local/Access Road	106.762	20	161	WR-29		Ward No. 08	2.287
Local/Access Road	158.450	20	162	WR-289		Ward No. 08	2.605
Local/Access Road	70.012	20	163	WR-289		Ward No. 04	2.017
Local/Access Road	18.897	20	164	WR-288		Ward No. 04	2.275
Local/Access Road	96.546	20	165	WR-287		Ward No. 04	2.639
Local/Access Road	47.885	20	166	WR-286		Ward No. 08	2.147
Local/Access Road	20.596	20	167	WR-286		Ward No. 07	2.597
Local/Access Road	136.634	20	168	WR-285		Ward No. 07	2.196
Local/Access Road	140.973	20	169	WR-284		Ward No. 04	3.652
Local/Access Road	303.345	20	170	WR-283		Ward No. 07	2.924
Local/Access Road	68.250	20	171	WR-282		Ward No. 04	3.049
Local/Access Road	15.655	20	173	WR-281		Ward No. 04	2.714
Local/Access Road	28.799	20	174	WR-280		Ward No. 07	2.561
Local/Access Road	150.380	20	175	WR-28		Ward No. 07	3.03
Local/Access Road	17.735	20	176	WR-279		Ward No. 08	2.497
Local/Access Road	114.186	20	177	WR-278		Ward No. 07	2.41
Local/Access Road	17.918	20	178	WR-277		Ward No. 04	2.62
Local/Access Road	27.200	20	179	WR-276		Ward No. 04	3.296
Local/Access Road	27.200	20	179	WR-275		Ward No. 03	3.296
Local/Access Road	18.623	20	181	WR-274		Ward No. 04	2.628
Local/Access Road	61.702	20	182	WR-273		Ward No. 07	2.196
Local/Access Road	261.973	20	183	WR-272		Ward No. 07	2.517
Local/Access Road	77.754	20	184	WR-271		Ward No. 07	2.068
Local/Access Road	53.661	20	185	WR-270		Ward No. 07	3.299
Local/Access Road	176.509	20	186	WR-27		Ward No. 04	2.417
Local/Access Road	82.268	20	187	WR-269		Ward No. 08	2.555

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	45.216	20	188	WR-268		Ward No. 04	4.123
Local/Access Road	31.092	20	189	WR-267		Ward No. 04	2.689
Local/Access Road	31.092	20	189	WR-266		Ward No. 03	2.689
Local/Access Road	25.744	20	190	WR-265		Ward No. 04	3.677
Local/Access Road	60.880	20	192	WR-264		Ward No. 08	2.623
Local/Access Road	60.880	20	192	WR-263		Ward No. 05	2.623
Local/Access Road	446.939	20	193	WR-262	Singra -karanpari Road	Ward No. 07	4.537
Local/Access Road	6.439	20	194	WR-261		Ward No. 04	2.27
Local/Access Road	20.068	20	195	WR-260		Ward No. 07	3.299
Local/Access Road	123.966	20	196	WR-26		Ward No. 07	3.299
Local/Access Road	30.676	20	197	WR-259		Ward No. 04	2.712
Local/Access Road	81.180	20	198	WR-258		Ward No. 04	2.712
Local/Access Road	80.530	20	199	WR-257		Ward No. 04	2.08
Local/Access Road	54.920	20	200	WR-256		Ward No. 07	3.299
Local/Access Road	19.724	20	201	WR-255		Ward No. 05	2.21
Local/Access Road	19.724	20	201	WR-254		Ward No. 04	2.21
Local/Access Road	27.943	20	203	WR-253		Ward No. 06	3.312
Local/Access Road	41.105	20	204	WR-253		Ward No. 06	3.312
Local/Access Road	106.730	20	205	WR-252		Ward No. 04	2.417
Local/Access Road	36.077	20	206	WR-251		Ward No. 08	2.133
Local/Access Road	117.577	20	207	WR-250		Ward No. 04	2.547
Local/Access Road	22.234	20	208	WR-25		Ward No. 08	2.1
Local/Access Road	22.234	20	208	WR-249		Ward No. 05	2.1
Local/Access Road	46.751	20	209	WR-248		Ward No. 04	6.127
Local/Access Road	128.071	20	211	WR-247		Ward No. 04	2.263
Local/Access Road	35.682	20	212	WR-245		Ward No. 04	2.866
Local/Access Road	56.762	20	213	WR-244		Ward No. 04	2.866
Local/Access Road	143.153	20	215	WR-243		Ward No. 08	2.548
Local/Access Road	143.153	20	215	WR-242		Ward No. 05	2.548
Local/Access Road	21.046	20	216	WR-241		Ward No. 08	2.281
Local/Access Road	21.046	20	216	WR-241		Ward No. 05	2.281
Local/Access Road	10.213	20	218	WR-240	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	10.213	20	218	WR-24	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	39.119	20	221	WR-239		Ward No. 05	2.599
Local/Access Road	26.114	20	222	WR-238	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	26.114	20	222	WR-237	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	218.029	20	224	WR-236		Ward No. 05	3.006
Local/Access Road	212.759	20	225	WR-235		Ward No. 05	3.006
Local/Access Road	12.886	20	226	WR-234	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	101.303	20	227	WR-234		Ward No. 04	2.047
Local/Access Road	101.303	20	227	WR-234		Ward No. 01	2.047
Local/Access Road	30.744	20	228	WR-232	TNT Office Road	Ward No. 05	3.963
Local/Access Road	80.821	20	229	WR-232		Ward No. 05	2.646
Local/Access Road	211.973	20	230	WR-231	TNT Office Road	Ward No. 05	3.963
Local/Access Road	211.973	20	230	WR-230	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.012	20	231	WR-23		Ward No. 05	3.412
Local/Access Road	107.993	20	232	WR-229		Ward No. 05	2.662
Local/Access Road	43.173	20	233	WR-229	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	43.173	20	233	WR-228	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	24.733	20	234	WR-227		Ward No. 05	2.58
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	252.195	20	235	WR-226	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	19.301	20	236	WR-225		Ward No. 01	2.02
Local/Access Road	24.798	20	237	WR-224		Ward No. 01	3.417
Local/Access Road	48.985	20	238	WR-223		Ward No. 01	2.545
Local/Access Road	9.882	20	239	WR-221		Ward No. 01	2.136
Local/Access Road	46.171	20	240	WR-221		Ward No. 01	2.521
Local/Access Road	10.132	20	241	WR-220		Ward No. 01	2.124
Local/Access Road	130.993	20	242	WR-22	Upazilla Parisad Road	Ward No. 04	4.569

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	130.993	20	242	WR-217	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	156.036	20	243	WR-217		Ward No. 05	2.563
Local/Access Road	16.696	20	244	WR-215		Ward No. 01	2.112
Local/Access Road	9.602	20	245	WR-215		Ward No. 01	2.134
Local/Access Road	42.890	20	246	WR-214		Ward No. 01	2.534
Local/Access Road	28.277	20	248	WR-214	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.986	20	249	WR-212		Ward No. 01	2.534
Local/Access Road	28.567	20	250	WR-211		Ward No. 01	2.027
Local/Access Road	33.504	20	251	WR-210		Ward No. 01	2.013
Local/Access Road	21.871	20	252	WR-21	TNT Office Road	Ward No. 01	3.963
Local/Access Road	74.180	20	253	WR-208	TNT Office Road	Ward No. 01	3.963
Local/Access Road	131.986	20	254	WR-207		Ward No. 05	2.199
Local/Access Road	131.986	20	254	WR-207		Ward No. 01	2.199
Local/Access Road	90.645	20	255	WR-206		Ward No. 05	2.199
Local/Access Road	19.539	20	256	WR-205		Ward No. 01	2.096
Local/Access Road	61.338	20	257	WR-204		Ward No. 01	2.602
Local/Access Road	102.962	20	258	WR-203		Ward No. 01	3.15
Local/Access Road	50.968	20	259	WR-202		Ward No. 01	3.15
Local/Access Road	98.164	20	260	WR-200	TNT Office Road	Ward No. 01	3.963
Local/Access Road	39.365	20	261	WR-200		Ward No. 01	1.011
Local/Access Road	43.333	20	262	WR-20		Ward No. 01	1.991
Local/Access Road	101.371	20	263	WR-199	TNT Office Road	Ward No. 01	3.963
Local/Access Road	81.368	20	264	WR-198	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.327	20	265	WR-197		Ward No. 01	1.531
Local/Access Road	68.732	20	266	WR-196		Ward No. 01	1.513
Local/Access Road	13.394	20	267	WR-195		Ward No. 01	1.531
Local/Access Road	17.906	20	268	WR-194		Ward No. 01	1.513
Local/Access Road	13.524	20	269	WR-193		Ward No. 01	1.513
Local/Access Road	46.095	20	270	WR-192	TNT Office Road	Ward No. 01	3.963
Local/Access Road	109.827	20	271	WR-191		Ward No. 01	1.593
Local/Access Road	77.059	20	272	WR-191	TNT Office Road	Ward No. 01	3.963
Local/Access Road	278.669	20	273	WR-19	TNT Office Road	Ward No. 01	3.963
Local/Access Road	37.632	20	274	WR-189		Ward No. 01	1.508
Local/Access Road	269.941	20	275	WR-188	TNT Office Road	Ward No. 03	3.963
Local/Access Road	79.781	20	276	WR-188		Ward No. 03	1.503
Local/Access Road	57.331	20	277	WR-187		Ward No. 03	1.503
Local/Access Road	32.507	20	278	WR-186		Ward No. 01	2.054
Local/Access Road	28.586	20	279	WR-185		Ward No. 01	1.639
Local/Access Road	282.850	20	280	WR-184	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.326	20	281	WR-183	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.707	20	282	WR-182		Ward No. 01	2.011
Local/Access Road	63.817	20	283	WR-181		Ward No. 01	3.04
Local/Access Road	88.406	20	284	WR-180		Ward No. 01	3.04
Local/Access Road	89.512	20	285	WR-178		Ward No. 01	3.04
Local/Access Road	30.315	20	286	WR-178		Ward No. 01	1.995
Local/Access Road	33.167	20	287	WR-177	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.167	20	287	WR-176	TNT Office Road	Ward No. 03	3.963
Local/Access Road	15.693	20	288	WR-175		Ward No. 01	2.025
Local/Access Road	36.241	20	289	WR-174		Ward No. 01	1.99
Local/Access Road	289.425	20	290	WR-173		Ward No. 03	2.995
Local/Access Road	289.425	20	290	WR-172		Ward No. 02	2.995
Local/Access Road	60.058	20	292	WR-170		Ward No. 03	2.037
Local/Access Road	68.017	20	293	WR-17		Ward No. 01	2.026
Local/Access Road	68.017	20	293	WR-169		Ward No. 03	2.026
Local/Access Road	130.008	20	294	WR-168	TNT Office Road	Ward No. 03	3.963
Local/Access Road	12.034	20	295	WR-167		Ward No. 03	2.127
Local/Access Road	11.667	20	296	WR-166		Ward No. 03	2.076
Local/Access Road	17.426	20	297	WR-165		Ward No. 03	2.144
Local/Access Road	42.032	20	298	WR-164	TNT Office Road	Ward No. 03	3.963
Local/Access Road	150.774	20	299	WR-163		Ward No. 03	1.531
Local/Access Road	108.922	20	300	WR-162	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.369	20	301	WR-161		Ward No. 03	3.006
Local/Access Road	179.903	20	302	WR-160		Ward No. 03	3.001
Local/Access Road	67.096	20	303	WR-16		Ward No. 03	2.556
Local/Access Road	39.134	20	304	WR-159		Ward No. 03	2.556
Local/Access Road	50.329	20	306	WR-156		Ward No. 03	3.33
Local/Access Road	53.629	20	307	WR-156	TNT Office Road	Ward No. 03	3.963
Local/Access Road	16.882	20	308	WR-155		Ward No. 03	3.001

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	52.737	20	309	WR-154	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.018	20	310	WR-153	TNT Office Road	Ward No. 03	3.963
Local/Access Road	39.818	20	311	WR-152	TNT Office Road	Ward No. 03	3.963
Local/Access Road	57.452	20	312	WR-151	TNT Office Road	Ward No. 03	3.963
Local/Access Road	35.712	20	313	WR-150	TNT Office Road	Ward No. 03	3.963
Local/Access Road	26.264	20	315	WR-15	TNT Office Road	Ward No. 03	3.963
Local/Access Road	108.153	20	316	WR-148	TNT Office Road	Ward No. 03	3.963
Local/Access Road	104.676	20	317	WR-147	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.883	20	318	WR-145		Ward No. 03	2.055
Local/Access Road	42.975	20	319	WR-144	TNT Office Road	Ward No. 03	3.963
Local/Access Road	123.229	20	320	WR-141		Ward No. 02	5.027
Local/Access Road	51.280	20	321	WR-140	TNT Office Road	Ward No. 03	3.963
Local/Access Road	51.280	20	321	WR-14	TNT Office Road	Ward No. 02	3.963
Local/Access Road	464.379	20	322	WR-138		Ward No. 03	2.208
Local/Access Road	32.724	20	323	WR-137	TNT Office Road	Ward No. 03	3.963
Local/Access Road	24.057	20	324	WR-135	TNT Office Road	Ward No. 03	3.963
Local/Access Road	78.042	20	325	WR-131		Ward No. 03	2.127
Local/Access Road	434.075	20	326	WR-13		Ward No. 02	1.97
Local/Access Road	342.215	20	327	WR-13		Ward No. 03	2.742
Local/Access Road	79.045	20	328	WR-13		Ward No. 02	2.559
Local/Access Road	290.391	20	329	WR-125		Ward No. 02	1.502
Local/Access Road	206.448	20	330	WR-124		Ward No. 02	2.364
Local/Access Road	276.671	20	331	WR-122		Ward No. 02	6.678
Local/Access Road	47.087	20	332	WR-122		Ward No. 02	3.132
Local/Access Road	1121.400	20	333	WR-121		Ward No. 02	3.132
Local/Access Road	56.747	20	334	WR-12		Ward No. 02	1.242
Local/Access Road	240.242	20	335	WR-117		Ward No. 02	3.132
Local/Access Road	174.792	20	336	WR-116		Ward No. 02	6.678
Local/Access Road	30.317	20	337	WR-115		Ward No. 02	1.131
Local/Access Road	75.392	20	338	WR-114		Ward No. 02	3.132
Local/Access Road	251.225	20	339	WR-113		Ward No. 02	3.132
Local/Access Road	26.167	20	340	WR-112		Ward No. 02	3.132
Local/Access Road	35.513	20	341	WR-111		Ward No. 02	1.565
Local/Access Road	15.997	20	342	WR-110		Ward No. 02	1.048
Local/Access Road	30.980	20	343	WR-11		Ward No. 02	2.525
Local/Access Road	47.635	20	344	WR-109		Ward No. 02	3.132
Local/Access Road	81.911	20	345	WR-108		Ward No. 02	3.132
Local/Access Road	69.247	20	346	WR-106		Ward No. 02	2.12
Local/Access Road	55.144	20	348	WR-106		Ward No. 02	3.257
Local/Access Road	136.489	20	349	WR-104		Ward No. 02	3.257
Local/Access Road	393.674	20	350	WR-103		Ward No. 02	3.257
Local/Access Road	82.924	20	351	WR-102		Ward No. 02	2.103
Local/Access Road	126.541	20	352	WR-101		Ward No. 02	2.541
Local/Access Road	1361.006	40	353	WR-100		Ward No. 07	3.299
Local/Access Road	3.713	40	354	WR-10		Ward No. 04	2.139
Local/Access Road	2593.923	20	1	WR-167	Ninguin Notun Para School Road	Ward No. 11	3.1
Local/Access Road	2593.923	20	1	WR-166	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	71.352	20	3	WR-165		Ward No. 10	1.532
Local/Access Road	56.923	20	4	WR-164		Ward No. 10	1.489
Local/Access Road	175.075	20	5	WR-163		Ward No. 10	1.529
Local/Access Road	26.720	20	6	WR-162		Ward No. 10	1.582
Local/Access Road	99.117	20	7	WR-161		Ward No. 10	2.5
Local/Access Road	157.591	20	8	WR-160		Ward No. 10	2.5
Local/Access Road	255.066	20	10	WR-16		Ward No. 10	2.398
Local/Access Road	39.421	20	11	WR-159		Ward No. 10	1.527
Local/Access Road	568.825	20	12	WR-156		Ward No. 11	3.215
Local/Access Road	2008.607	20	13	WR-156		Ward No. 11	3.25
Local/Access Road	2008.607	20	13	WR-155		Ward No. 12	3.25
Local/Access Road	2008.607	20	13	WR-154		Ward No. 06	3.25
Local/Access Road	42.841	20	14	WR-153		Ward No. 10	1.555
Local/Access Road	78.482	20	15	WR-152		Ward No. 10	1.543
Local/Access Road	89.440	20	16	WR-151		Ward No. 10	2.398
Local/Access Road	22.687	20	17	WR-150		Ward No. 11	2.51
Local/Access Road	103.830	20	19	WR-15		Ward No. 11	1.656
Local/Access Road	315.944	20	20	WR-148		Ward No. 11	3.414

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	90.620	20	21	WR-147		Ward No. 10	2.095
Local/Access Road	40.463	20	22	WR-145		Ward No. 11	2.191
Local/Access Road	52.701	20	23	WR-144		Ward No. 11	2.191
Local/Access Road	60.048	20	24	WR-141		Ward No. 11	3.528
Local/Access Road	202.825	20	25	WR-140		Ward No. 11	3.033
Local/Access Road	29.850	20	26	WR-14		Ward No. 11	3.326
Local/Access Road	42.429	20	27	WR-138		Ward No. 11	2.089
Local/Access Road	132.092	20	28	WR-137		Ward No. 10	2.51
Local/Access Road	147.600	20	29	WR-135		Ward No. 11	3.037
Local/Access Road	21.144	20	30	WR-131		Ward No. 11	2.787
Local/Access Road	47.500	20	31	WR-13		Ward No. 11	3.079
Local/Access Road	19.802	20	32	WR-13		Ward No. 06	2.271
Local/Access Road	163.957	20	33	WR-13		Ward No. 11	1.746
Local/Access Road	175.239	20	34	WR-125		Ward No. 11	3.055
Local/Access Road	49.292	20	35	WR-124	Ninguin Notun Para School Road	Ward No. 12	3.1
Local/Access Road	118.448	20	36	WR-122		Ward No. 11	2.216
Local/Access Road	61.946	20	37	WR-122		Ward No. 09	2.102
Local/Access Road	146.110	20	38	WR-121		Ward No. 09	2.102
Local/Access Road	315.505	20	39	WR-12		Ward No. 09	3.02
Local/Access Road	143.051	20	40	WR-117		Ward No. 09	3.011
Local/Access Road	113.172	20	41	WR-116		Ward No. 09	3.041
Local/Access Road	168.611	20	42	WR-115		Ward No. 09	2.998
Local/Access Road	241.851	20	43	WR-114		Ward No. 09	2.998
Local/Access Road	70.636	20	44	WR-113		Ward No. 09	3.619
Local/Access Road	45.323	20	45	WR-112		Ward No. 09	2.382
Local/Access Road	94.300	20	46	WR-111		Ward No. 06	1.962
Local/Access Road	35.065	20	48	WR-110		Ward No. 06	2.189
Local/Access Road	108.658	20	49	WR-11		Ward No. 06	1.567
Local/Access Road	86.405	20	53	WR-109		Ward No. 09	2.03
Local/Access Road	64.841	20	54	WR-108		Ward No. 06	2.164
Local/Access Road	49.887	20	55	WR-106		Ward No. 09	2.215
Local/Access Road	29.661	20	57	WR-106		Ward No. 06	2.62
Local/Access Road	59.490	20	64	WR-104		Ward No. 09	2.028
Local/Access Road	41.772	20	66	WR-103		Ward No. 09	2.088
Local/Access Road	825.147	20	69	WR-102		Ward No. 06	2.696
Local/Access Road	58.763	20	70	WR-101		Ward No. 09	3.061
Local/Access Road	30.856	20	71	WR-100		Ward No. 09	1.663
Local/Access Road	38.950	20	72	WR-10		Ward No. 09	2.6
Local/Access Road	175.835	20	73	WR-167		Ward No. 09	2.547
Local/Access Road	18.957	20	74	WR-166		Ward No. 09	2.182
Local/Access Road	69.816	20	78	WR-165	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	23.368	20	79	WR-164		Ward No. 08	1.525
Local/Access Road	233.012	20	82	WR-163	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	79.925	20	84	WR-162	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	18.310	20	85	WR-161		Ward No. 08	1.605
Local/Access Road	44.365	20	86	WR-160	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	31.902	20	87	WR-16		Ward No. 08	2.08
Local/Access Road	19.949	20	88	WR-159	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	96.157	20	89	WR-156		Ward No. 08	2.614
Local/Access Road	5.911	20	90	WR-156		Ward No. 08	1.725
Local/Access Road	28.967	20	91	WR-155		Ward No. 08	2.784
Local/Access Road	20.533	20	92	WR-154	Singra - Kalom Road	Ward No. 08	3.34
Local/Access Road	88.141	20	94	WR-153		Ward No. 08	3.062
Local/Access Road	50.931	20	97	WR-152		Ward No. 08	2.24
Local/Access Road	39.296	20	98	WR-151		Ward No. 08	2.046
Local/Access Road	84.139	20	101	WR-150		Ward No. 06	4.062
Local/Access Road	13.312	20	102	WR-15		Ward No. 08	4.539
Local/Access Road	24.517	20	103	WR-148		Ward No. 08	2.011
Local/Access Road	51.922	20	104	WR-147		Ward No. 08	2.011
Local/Access Road	28.305	20	105	WR-145		Ward No. 08	2.561
Local/Access Road	33.036	20	107	WR-144		Ward No. 12	2.709

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	33.036	20	107	WR-141		Ward No. 07	2.709
Local/Access Road	280.500	20	109	WR-140		Ward No. 08	6.083
Local/Access Road	95.832	20	110	WR-14		Ward No. 07	2.55
Local/Access Road	58.011	20	111	WR-138		Ward No. 07	2.649
Local/Access Road	70.846	20	112	WR-137		Ward No. 08	2.691
Local/Access Road	20.748	20	113	WR-135		Ward No. 08	1.994
Local/Access Road	56.643	20	114	WR-131	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	72.071	20	115	WR-13	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	120.852	20	116	WR-13		Ward No. 04	2.043
Local/Access Road	30.204	20	117	WR-13		Ward No. 06	6.867
Local/Access Road	219.325	20	118	WR-125		Ward No. 07	3.104
Local/Access Road	113.873	20	122	WR-124		Ward No. 08	4.101
Local/Access Road	218.782	20	123	WR-122	Balua Baua Jame Mosque Road	Ward No. 08	4.059
Local/Access Road	218.782	20	123	WR-122	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	113.274	20	125	WR-121		Ward No. 08	3.71
Local/Access Road	46.048	20	126	WR-12	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	107.580	20	132	WR-117	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	214.625	20	136	WR-116		Ward No. 07	3.104
Local/Access Road	175.773	20	138	WR-115		Ward No. 06	3.062
Local/Access Road	35.980	20	139	WR-114		Ward No. 07	2.555
Local/Access Road	48.372	20	141	WR-113		Ward No. 08	2.297
Local/Access Road	56.911	20	142	WR-112		Ward No. 07	1.049
Local/Access Road	151.193	20	145	WR-111		Ward No. 07	3.03
Local/Access Road	115.717	20	146	WR-110		Ward No. 07	2.523
Local/Access Road	21.101	20	148	WR-11		Ward No. 08	2.097
Local/Access Road	34.631	20	149	WR-109		Ward No. 07	2.149
Local/Access Road	17.416	20	151	WR-108		Ward No. 08	2.198
Local/Access Road	41.693	20	152	WR-106		Ward No. 08	2.198
Local/Access Road	71.911	20	153	WR-106	Balua Baua Jame Mosque Road	Ward No. 04	4.059
Local/Access Road	57.817	20	154	WR-104		Ward No. 07	2.63
Local/Access Road	48.611	20	155	WR-103		Ward No. 04	3.073
Local/Access Road	37.504	20	156	WR-102		Ward No. 04	2.109
Local/Access Road	137.947	20	157	WR-101		Ward No. 08	2.109
Local/Access Road	137.947	20	157	WR-100		Ward No. 04	2.109
Local/Access Road	95.696	20	158	WR-10		Ward No. 08	2.533
Local/Access Road	35.481	20	160	WR-167		Ward No. 04	1.568
Local/Access Road	106.762	20	161	WR-166		Ward No. 08	2.287
Local/Access Road	158.450	20	162	WR-165		Ward No. 08	2.605
Local/Access Road	70.012	20	163	WR-164		Ward No. 04	2.017
Local/Access Road	18.897	20	164	WR-163		Ward No. 04	2.275
Local/Access Road	96.546	20	165	WR-162		Ward No. 04	2.639
Local/Access Road	47.885	20	166	WR-161		Ward No. 08	2.147
Local/Access Road	20.596	20	167	WR-160		Ward No. 07	2.597
Local/Access Road	136.634	20	168	WR-16		Ward No. 07	2.196
Local/Access Road	140.973	20	169	WR-159		Ward No. 04	3.652
Local/Access Road	303.345	20	170	WR-156		Ward No. 07	2.924
Local/Access Road	68.250	20	171	WR-156		Ward No. 04	3.049
Local/Access Road	15.655	20	173	WR-155		Ward No. 04	2.714
Local/Access Road	28.799	20	174	WR-154		Ward No. 07	2.561
Local/Access Road	150.380	20	175	WR-153		Ward No. 07	3.03
Local/Access Road	17.735	20	176	WR-152		Ward No. 08	2.497
Local/Access Road	114.186	20	177	WR-151		Ward No. 07	2.41
Local/Access Road	17.918	20	178	WR-150		Ward No. 04	2.62
Local/Access Road	27.200	20	179	WR-15		Ward No. 04	3.296
Local/Access Road	27.200	20	179	WR-148		Ward No. 03	3.296
Local/Access Road	18.623	20	181	WR-147		Ward No. 04	2.628
Local/Access Road	61.702	20	182	WR-145		Ward No. 07	2.196
Local/Access Road	261.973	20	183	WR-144		Ward No. 07	2.517
Local/Access Road	77.754	20	184	WR-141		Ward No. 07	2.068
Local/Access Road	53.661	20	185	WR-140		Ward No. 07	3.299
Local/Access Road	176.509	20	186	WR-14		Ward No. 04	2.417
Local/Access Road	82.268	20	187	WR-138		Ward No. 08	2.555

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	45.216	20	188	WR-137		Ward No. 04	4.123
Local/Access Road	31.092	20	189	WR-135		Ward No. 04	2.689
Local/Access Road	31.092	20	189	WR-131		Ward No. 03	2.689
Local/Access Road	25.744	20	190	WR-13		Ward No. 04	3.677
Local/Access Road	60.880	20	192	WR-13		Ward No. 08	2.623
Local/Access Road	60.880	20	192	WR-13		Ward No. 05	2.623
Local/Access Road	446.939	20	193	WR-125	Singra -karanpari Road	Ward No. 07	4.537
Local/Access Road	6.439	20	194	WR-124		Ward No. 04	2.27
Local/Access Road	20.068	20	195	WR-122		Ward No. 07	3.299
Local/Access Road	123.966	20	196	WR-122		Ward No. 07	3.299
Local/Access Road	30.676	20	197	WR-121		Ward No. 04	2.712
Local/Access Road	81.180	20	198	WR-12		Ward No. 04	2.712
Local/Access Road	80.530	20	199	WR-117		Ward No. 04	2.08
Local/Access Road	54.920	20	200	WR-116		Ward No. 07	3.299
Local/Access Road	19.724	20	201	WR-115		Ward No. 05	2.21
Local/Access Road	19.724	20	201	WR-114		Ward No. 04	2.21
Local/Access Road	27.943	20	203	WR-113		Ward No. 06	3.312
Local/Access Road	41.105	20	204	WR-112		Ward No. 06	3.312
Local/Access Road	106.730	20	205	WR-111		Ward No. 04	2.417
Local/Access Road	36.077	20	206	WR-110		Ward No. 08	2.133
Local/Access Road	117.577	20	207	WR-11		Ward No. 04	2.547
Local/Access Road	22.234	20	208	WR-109		Ward No. 08	2.1
Local/Access Road	22.234	20	208	WR-108		Ward No. 05	2.1
Local/Access Road	46.751	20	209	WR-106		Ward No. 04	6.127
Local/Access Road	128.071	20	211	WR-106		Ward No. 04	2.263
Local/Access Road	35.682	20	212	WR-104		Ward No. 04	2.866
Local/Access Road	56.762	20	213	WR-103		Ward No. 04	2.866
Local/Access Road	143.153	20	215	WR-102		Ward No. 08	2.548
Local/Access Road	143.153	20	215	WR-101		Ward No. 05	2.548
Local/Access Road	21.046	20	216	WR-100		Ward No. 08	2.281
Local/Access Road	21.046	20	216	WR-10		Ward No. 05	2.281
Local/Access Road	10.213	20	218	WR-167	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	10.213	20	218	WR-166	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	39.119	20	221	WR-165		Ward No. 05	2.599
Local/Access Road	26.114	20	222	WR-164	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	26.114	20	222	WR-163	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	218.029	20	224	WR-162		Ward No. 05	3.006
Local/Access Road	212.759	20	225	WR-161		Ward No. 05	3.006
Local/Access Road	12.886	20	226	WR-160	Upazilla Parisad Road	Ward No. 04	4.569
Local/Access Road	101.303	20	227	WR-16		Ward No. 04	2.047
Local/Access Road	101.303	20	227	WR-159		Ward No. 01	2.047
Local/Access Road	30.744	20	228	WR-156	TNT Office Road	Ward No. 05	3.963
Local/Access Road	80.821	20	229	WR-156		Ward No. 05	2.646
Local/Access Road	211.973	20	230	WR-155	TNT Office Road	Ward No. 05	3.963
Local/Access Road	211.973	20	230	WR-154	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.012	20	231	WR-153		Ward No. 05	3.412
Local/Access Road	107.993	20	232	WR-152		Ward No. 05	2.662
Local/Access Road	43.173	20	233	WR-151	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	43.173	20	233	WR-150	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	24.733	20	234	WR-15		Ward No. 05	2.58
Local/Access Road	252.195	20	235	WR-148	Upazilla Parisad Road	Ward No. 05	4.569
Local/Access Road	252.195	20	235	WR-147	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	19.301	20	236	WR-145		Ward No. 01	2.02
Local/Access Road	24.798	20	237	WR-144		Ward No. 01	3.417
Local/Access Road	48.985	20	238	WR-141		Ward No. 01	2.545
Local/Access Road	9.882	20	239	WR-140		Ward No. 01	2.136
Local/Access Road	46.171	20	240	WR-14		Ward No. 01	2.521
Local/Access Road	10.132	20	241	WR-138		Ward No. 01	2.124
Local/Access Road	130.993	20	242	WR-137	Upazilla Parisad Road	Ward No. 04	4.569

Type of Road	Length (m)	Proposed RoW (ft.)	Existing Road Id	Proposed Road Id	Road Name	Ward No.	Existing Width(m)
Local/Access Road	130.993	20	242	WR-135	Upazilla Parisad Road	Ward No. 01	4.569
Local/Access Road	156.036	20	243	WR-131		Ward No. 05	2.563
Local/Access Road	16.696	20	244	WR-13		Ward No. 01	2.112
Local/Access Road	9.602	20	245	WR-13		Ward No. 01	2.134
Local/Access Road	42.890	20	246	WR-13		Ward No. 01	2.534
Local/Access Road	28.277	20	248	WR-125	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.986	20	249	WR-124		Ward No. 01	2.534
Local/Access Road	28.567	20	250	WR-122		Ward No. 01	2.027
Local/Access Road	33.504	20	251	WR-122		Ward No. 01	2.013
Local/Access Road	21.871	20	252	WR-121	TNT Office Road	Ward No. 01	3.963
Local/Access Road	74.180	20	253	WR-12	TNT Office Road	Ward No. 01	3.963
Local/Access Road	131.986	20	254	WR-117		Ward No. 05	2.199
Local/Access Road	131.986	20	254	WR-116		Ward No. 01	2.199
Local/Access Road	90.645	20	255	WR-115		Ward No. 05	2.199
Local/Access Road	19.539	20	256	WR-114		Ward No. 01	2.096
Local/Access Road	61.338	20	257	WR-113		Ward No. 01	2.602
Local/Access Road	102.962	20	258	WR-112		Ward No. 01	3.15
Local/Access Road	50.968	20	259	WR-111		Ward No. 01	3.15
Local/Access Road	98.164	20	260	WR-110	TNT Office Road	Ward No. 01	3.963
Local/Access Road	39.365	20	261	WR-11		Ward No. 01	1.011
Local/Access Road	43.333	20	262	WR-109		Ward No. 01	1.991
Local/Access Road	101.371	20	263	WR-108	TNT Office Road	Ward No. 01	3.963
Local/Access Road	81.368	20	264	WR-106	TNT Office Road	Ward No. 01	3.963
Local/Access Road	55.327	20	265	WR-106		Ward No. 01	1.531
Local/Access Road	68.732	20	266	WR-104		Ward No. 01	1.513
Local/Access Road	13.394	20	267	WR-103		Ward No. 01	1.531
Local/Access Road	17.906	20	268	WR-102		Ward No. 01	1.513
Local/Access Road	13.524	20	269	WR-101		Ward No. 01	1.513
Local/Access Road	46.095	20	270	WR-100	TNT Office Road	Ward No. 01	3.963
Local/Access Road	109.827	20	271	WR-10		Ward No. 01	1.593
Local/Access Road	77.059	20	272	WR-121	TNT Office Road	Ward No. 01	3.963
Local/Access Road	278.669	20	273	WR-12	TNT Office Road	Ward No. 01	3.963
Local/Access Road	37.632	20	274	WR-117		Ward No. 01	1.508
Local/Access Road	269.941	20	275	WR-116	TNT Office Road	Ward No. 03	3.963
Local/Access Road	79.781	20	276	WR-115		Ward No. 03	1.503
Local/Access Road	57.331	20	277	WR-114		Ward No. 03	1.503
Local/Access Road	32.507	20	278	WR-113		Ward No. 01	2.054
Local/Access Road	28.586	20	279	WR-112		Ward No. 01	1.639
Local/Access Road	282.850	20	280	WR-111	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.326	20	281	WR-110	TNT Office Road	Ward No. 01	3.963
Local/Access Road	46.707	20	282	WR-11		Ward No. 01	2.011
Local/Access Road	63.817	20	283	WR-109		Ward No. 01	3.04
Local/Access Road	88.406	20	284	WR-108		Ward No. 01	3.04
Local/Access Road	89.512	20	285	WR-106		Ward No. 01	3.04
Local/Access Road	30.315	20	286	WR-106		Ward No. 01	1.995
Local/Access Road	33.167	20	287	WR-104	TNT Office Road	Ward No. 01	3.963
Local/Access Road	33.167	20	287	WR-103	TNT Office Road	Ward No. 03	3.963
Local/Access Road	15.693	20	288	WR-102		Ward No. 01	2.025
Local/Access Road	36.241	20	289	WR-101		Ward No. 01	1.99
Local/Access Road	289.425	20	290	WR-100		Ward No. 03	2.995
Local/Access Road	289.425	20	290	WR-10		Ward No. 02	2.995

Source: Road Network Plan of Singra Paurashava

Table B6: Details of Proposals New Roads in Road Network Plan of Singra Paurashava (Phase 03: Eleventh to Twentieth Year of Master Plan)

Type of Road	Proposed RoW (ft.)	Proposed Road Id	Road Name	Ward No.	Length (m)
Secondary Road	30	NR-18		Ward No. 07	313.090
Secondary Road	30	NR-18		Ward No. 06	313.090
Secondary Road	30	NR-19		Ward No. 06	745.460
Local/Access Road	20	NR-44		Ward No. 01	105.902
Local/Access Road	20	NR-48		Ward No. 02	85.886
Local/Access Road	20	NR-49		Ward No. 02	75.187
Local/Access Road	20	NR-51		Ward No. 02	159.262
Local/Access Road	20	NR-52		Ward No. 02	95.866
Local/Access Road	20	NR-54		Ward No. 02	142.466
Local/Access Road	20	NR-55		Ward No. 02	220.087

Type of Road	Proposed RoW (ft.)	Proposed Road Id	Road Name	Ward No.	Length (m)
Local/Access Road	20	NR-56		Ward No. 02	109.980
Local/Access Road	20	NR-57		Ward No. 02	97.570
Local/Access Road	20	NR-58		Ward No. 02	370.946
Local/Access Road	20	NR-59		Ward No. 02	100.174
Local/Access Road	20	NR-60		Ward No. 02	141.562
Local/Access Road	20	NR-61		Ward No. 02	73.859
Local/Access Road	20	NR-62		Ward No. 07	73.057
Local/Access Road	20	NR-63		Ward No. 07	165.098
Local/Access Road	20	NR-64		Ward No. 07	80.531
Local/Access Road	20	NR-65		Ward No. 07	76.199
Local/Access Road	20	NR-66		Ward No. 07	60.597
Local/Access Road	30	NR-75		Ward No. 12	508.771
Local/Access Road	30	NR-75		Ward No. 07	508.771
Local/Access Road	20	NR-80		Ward No. 12	289.936
Local/Access Road	20	NR-81		Ward No. 12	49.153
Local/Access Road	20	NR-64		Ward No. 07	80.531
Local/Access Road	20	NR-65		Ward No. 07	76.199
Secondary Road	30	NR-18		Ward No. 07	313.090
Secondary Road	30	NR-18		Ward No. 06	313.090
Secondary Road	30	NR-19		Ward No. 06	745.460
Local/Access Road	20	NR-44		Ward No. 01	105.902
Local/Access Road	20	NR-48		Ward No. 02	85.886
Local/Access Road	20	NR-49		Ward No. 02	75.187
Local/Access Road	20	NR-51		Ward No. 02	159.262
Local/Access Road	20	NR-52		Ward No. 02	95.866
Local/Access Road	20	NR-54		Ward No. 02	142.466
Local/Access Road	20	NR-55		Ward No. 02	220.087
Local/Access Road	20	NR-56		Ward No. 02	109.980
Local/Access Road	20	NR-57		Ward No. 02	97.570
Local/Access Road	20	NR-58		Ward No. 02	370.946
Local/Access Road	20	NR-59		Ward No. 02	100.174
Local/Access Road	20	NR-60		Ward No. 02	141.562
Local/Access Road	20	NR-61		Ward No. 02	73.859
Local/Access Road	20	NR-62		Ward No. 07	73.057
Local/Access Road	20	NR-63		Ward No. 07	165.098
Local/Access Road	20	NR-64		Ward No. 07	80.531
Local/Access Road	20	NR-65		Ward No. 07	76.199
Local/Access Road	20	NR-66		Ward No. 07	60.597
Local/Access Road	30	NR-75		Ward No. 12	508.771
Local/Access Road	30	NR-75		Ward No. 07	508.771
Local/Access Road	20	NR-80		Ward No. 12	289.936
Local/Access Road	20	NR-81		Ward No. 12	49.153
Local/Access Road	20	NR-64		Ward No. 07	80.531
Local/Access Road	20	NR-65		Ward No. 07	76.199
Secondary Road	30	NR-18		Ward No. 07	313.090
Secondary Road	30	NR-18		Ward No. 06	313.090
Secondary Road	30	NR-19		Ward No. 06	745.460
Local/Access Road	20	NR-44		Ward No. 01	105.902
Local/Access Road	20	NR-48		Ward No. 02	85.886
Local/Access Road	20	NR-49		Ward No. 02	75.187
Local/Access Road	20	NR-51		Ward No. 02	159.262
Local/Access Road	20	NR-52		Ward No. 02	95.866
Local/Access Road	20	NR-54		Ward No. 02	142.466
Local/Access Road	20	NR-55		Ward No. 02	220.087
Local/Access Road	20	NR-56		Ward No. 02	109.980
Local/Access Road	20	NR-57		Ward No. 02	97.570
Local/Access Road	20	NR-58		Ward No. 02	370.946
Local/Access Road	20	NR-59		Ward No. 02	100.174
Local/Access Road	20	NR-60		Ward No. 02	141.562
Local/Access Road	20	NR-61		Ward No. 02	73.859
Local/Access Road	20	NR-62		Ward No. 07	73.057
Local/Access Road	20	NR-63		Ward No. 07	165.098
Local/Access Road	20	NR-64		Ward No. 07	80.531
Local/Access Road	20	NR-65		Ward No. 07	76.199
Local/Access Road	20	NR-80		Ward No. 11	128.626
Local/Access Road	20	NR-98		Ward No. 12	283.796
Local/Access Road	20	NR-81		Ward No. 12	49.153
Secondary Road	40	NR-99		Ward No. 10	11.854
Secondary Road	40	NR-99		Ward No. 11	35.280

Type of Road	Proposed RoW (ft.)	Proposed Road Id	Road Name	Ward No.	Length (m)
Secondary Road	50	NR-85		Ward No. 10	113.179
Secondary Road	50	NR-85		Ward No. 09	784.589
Secondary Road	50	NR-85		Ward No. 04	1093.047
Local/Access Road	20	NR-82		Ward No. 03	106.127
Local/Access Road	20	NR-83		Ward No. 03	57.933
Local/Access Road	20	NR-84		Ward No. 04	83.301
Local/Access Road	20	NR-84		Ward No. 03	531.596
Local/Access Road	20	NR-86		Ward No. 10	71.827
Local/Access Road	20	NR-87		Ward No. 09	15.593
Local/Access Road	20	NR-88		Ward No. 02	363.876
Local/Access Road	20	NR-89		Ward No. 06	806.719
Local/Access Road	20	NR-90		Ward No. 12	249.773
Local/Access Road	20	NR-90		Ward No. 06	488.085
Local/Access Road	20	NR-91		Ward No. 12	271.890
Local/Access Road	20	NR-91		Ward No. 07	34.509
Local/Access Road	20	NR-93		Ward No. 04	320.480
Local/Access Road	20	NR-95		Ward No. 04	706.224
Local/Access Road	20	NR-96		Ward No. 04	677.461
Local/Access Road	20	NR-96		Ward No. 03	341.510
Local/Access Road	20	NR-97		Ward No. 04	535.811

Source: Road Network Plan of Singra Paurashava

Annexure-C: Proposed Drain Inventory

Details of Drainage Network Proposals of SingraPaurashava

Table C1: Details of Drainage Network Proposals of SingraPaurashava (Phase 01: First to Fifth Year of Master Plan)

Type of Drain	Propo sed Id	Proposal Status	Proposed Width (m)	Proposed Depth (m)	Ward No.	Length (m)	Outfall
Secondary Drain	SD-1	New Drain	0.80	0.40	Ward no-08	215.868	River
Secondary Drain	SD-2	New Drain	0.80	0.40	Ward no-08	282.968	River
Secondary Drain	SD-3	New Drain	0.80	0.40	Ward no-08	36.194	River
Secondary Drain	SD-4	New Drain	0.80	0.40	Ward no-08	167.457	River
Tertiary Drain	TD-1	New Drain	0.80	0.40	Ward no-08	362.336	River
Tertiary Drain	TD-2	New Drain	0.80	0.40	Ward no-08	509.952	River
Tertiary Drain	TD-3	New Drain	0.80	0.40	Ward no-09	313.665	River
Tertiary Drain	TD-4	New Drain	0.80	0.40	Ward no-09	80.533	River
Tertiary Drain	TD-5	New Drain	0.80	0.40	Ward no-09	260.258	River
Tertiary Drain	TD-6	New Drain	0.80	0.40	Ward no-09	453.882	River
Tertiary Drain	TD-7	New Drain	0.80	0.40	Ward no-09	388.365	River
Tertiary Drain	TD-8	New Drain	0.80	0.40	Ward no-09	274.419	River
Tertiary Drain	TD-9	New Drain	0.80	0.40	Ward no-09	206.722	River
Tertiary Drain	TD-10	New Drain	0.80	0.40	Ward no-09	245.663	River
Tertiary Drain	TD-11	New Drain	0.80	0.40	Ward no-09	194.234	River
Tertiary Drain	TD-12	New Drain	0.80	0.40	Ward no-08	56.923	River
Tertiary Drain	TD-13	New Drain	0.80	0.40	Ward no-08	353.544	River
Tertiary Drain	TD-14	New Drain	0.80	0.40	Ward no-05	157.706	River
Tertiary Drain	TD-15	New Drain	0.80	0.40	Ward no-05	81.152	River
Tertiary Drain	TD-16	New Drain	0.80	0.40	Ward no-05	116.583	River
Secondary Drain	SD-5	New Drain	0.80	0.40	Ward no-04	450.874	Khal
Secondary Drain	SD-6	New Drain	0.80	0.40	Ward no-05	542.061	River
Secondary Drain	SD-8	New Drain	0.80	0.40	Ward no-04	922.541	River
Tertiary Drain	TD-29	New Drain	0.80	0.40	Ward no-01	174.745	River
Tertiary Drain	TD-30	New Drain	0.80	0.40	Ward no-01	72.777	Khal
Tertiary Drain	TD-31	New Drain	0.80	0.40	Ward no-01	270.539	Khal
Tertiary Drain	TD-32	New Drain	0.80	0.40	Ward no-08	115.626	Khal
Tertiary Drain	TD-33	New Drain	0.80	0.40	Ward no-03	205.428	SD-7
Tertiary Drain	TD-34	New Drain	0.80	0.40	Ward no-01	291.719	River
Tertiary Drain	TD-35	New Drain	0.80	0.40	Ward no-01	74.625	River
Secondary Drain	SD-8	New Drain	0.80	0.40	Ward no-08	290.023	SD-8
Secondary Drain	SD-1	New Drain	0.80	0.40	Ward no-08	215.868	River
Secondary Drain	SD-2	New Drain	0.80	0.40	Ward no-08	282.968	River
Secondary Drain	SD-3	New Drain	0.80	0.40	Ward no-08	36.194	River
Secondary Drain	SD-4	New Drain	0.80	0.40	Ward no-08	167.457	River
Tertiary Drain	TD-1	New Drain	0.80	0.40	Ward no-08	362.336	River
Tertiary Drain	TD-2	New Drain	0.80	0.40	Ward no-08	509.952	River
Tertiary Drain	TD-3	New Drain	0.80	0.40	Ward no-09	313.665	River
Tertiary Drain	TD-4	New Drain	0.80	0.40	Ward no-09	80.533	River
Tertiary Drain	TD-5	New Drain	0.80	0.40	Ward no-09	260.258	River
Tertiary Drain	TD-6	New Drain	0.80	0.40	Ward no-09	453.882	River
Tertiary Drain	TD-7	New Drain	0.80	0.40	Ward no-09	388.365	River
Tertiary Drain	TD-8	New Drain	0.80	0.40	Ward no-09	274.419	River
Tertiary Drain	TD-9	New Drain	0.80	0.40	Ward no-09	206.722	River
Tertiary Drain	TD-10	New Drain	0.80	0.40	Ward no-09	245.663	River
Tertiary Drain	TD-11	New Drain	0.80	0.40	Ward no-09	194.234	River
Tertiary Drain	TD-12	New Drain	0.80	0.40	Ward no-08	56.923	River
Tertiary Drain	TD-13	New Drain	0.80	0.40	Ward no-08	353.544	River
Tertiary Drain	TD-14	New Drain	0.80	0.40	Ward no-05	157.706	River
Tertiary Drain	TD-15	New Drain	0.80	0.40	Ward no-05	81.152	River
Tertiary Drain	TD-16	New Drain	0.80	0.40	Ward no-05	116.583	River
Secondary Drain	SD-5	New Drain	0.80	0.40	Ward no-04	450.874	Khal
Secondary Drain	SD-6	New Drain	0.80	0.40	Ward no-05	542.061	River
Secondary Drain	SD-8	New Drain	0.80	0.40	Ward no-04	922.541	River

Type of Drain	Proposed Id	Proposal Status	Proposed Width (m)	Proposed Depth (m)	Ward No.	Length (m)	Outfall
Tertiary Drain	TD-29	New Drain	0.80	0.40	Ward no-01	174.745	River
Tertiary Drain	TD-30	New Drain	0.80	0.40	Ward no-01	72.777	Khal
Tertiary Drain	TD-31	New Drain	0.80	0.40	Ward no-01	270.539	Khal
Tertiary Drain	TD-32	New Drain	0.80	0.40	Ward no-08	115.626	Khal
Tertiary Drain	TD-33	New Drain	0.80	0.40	Ward no-03	205.428	SD-7
Tertiary Drain	TD-34	New Drain	0.80	0.40	Ward no-01	291.719	River
Tertiary Drain	TD-35	New Drain	0.80	0.40	Ward no-01	74.625	River
Secondary Drain	SD-8	New Drain	0.80	0.40	Ward no-08	290.023	SD-8
Secondary Drain	SD-1	New Drain	0.80	0.40	Ward no-08	215.868	River
Secondary Drain	SD-2	New Drain	0.80	0.40	Ward no-08	282.968	River
Secondary Drain	SD-3	New Drain	0.80	0.40	Ward no-08	36.194	River
Secondary Drain	SD-4	New Drain	0.80	0.40	Ward no-08	167.457	River
Tertiary Drain	TD-1	New Drain	0.80	0.40	Ward no-08	362.336	River
Tertiary Drain	TD-2	New Drain	0.80	0.40	Ward no-08	509.952	River
Tertiary Drain	TD-3	New Drain	0.80	0.40	Ward no-09	313.665	River
Tertiary Drain	TD-4	New Drain	0.80	0.40	Ward no-09	80.533	River
Tertiary Drain	TD-5	New Drain	0.80	0.40	Ward no-09	260.258	River
Tertiary Drain	TD-6	New Drain	0.80	0.40	Ward no-09	453.882	River
Tertiary Drain	TD-7	New Drain	0.80	0.40	Ward no-09	388.365	River
Tertiary Drain	TD-8	New Drain	0.80	0.40	Ward no-09	274.419	River
Tertiary Drain	TD-9	New Drain	0.80	0.40	Ward no-09	206.722	River
Tertiary Drain	TD-10	New Drain	0.80	0.40	Ward no-09	245.663	River
Tertiary Drain	TD-11	New Drain	0.80	0.40	Ward no-09	194.234	River
Tertiary Drain	TD-12	New Drain	0.80	0.40	Ward no-08	56.923	River
Tertiary Drain	TD-13	New Drain	0.80	0.40	Ward no-08	353.544	River
Tertiary Drain	TD-14	New Drain	0.80	0.40	Ward no-05	157.706	River
Tertiary Drain	TD-15	New Drain	0.80	0.40	Ward no-05	81.152	River
Tertiary Drain	TD-16	New Drain	0.80	0.40	Ward no-05	116.583	River
Secondary Drain	SD-5	New Drain	0.80	0.40	Ward no-04	450.874	Khal
Secondary Drain	SD-6	New Drain	0.80	0.40	Ward no-05	542.061	River
Secondary Drain	SD-8	New Drain	0.80	0.40	Ward no-04	922.541	River

Source: Drainage and Environmental Management Plan

Table C-2: Details of Drainage Network Proposals of Singra Paurashava (Phase 02: Sixth to Tenth Year of Master Plan)

Type of Drain	Proposed Id	Proposal Status	Proposed Width (m)	Proposed Depth (m)	Ward No.	Length (m)	Outfall
Tertiary Drain	TD-17	New Drain	0.80	0.40	Ward no-01	318.038	River
Tertiary Drain	TD-18	New Drain	0.80	0.40	Ward no-04	121.197	River
Tertiary Drain	TD-19	New Drain	0.80	0.40	Ward no-08	85.196	Khal
Secondary Drain	SD-7	New Drain	0.80	0.40	Ward no-03	1302.752	Khal
Tertiary Drain	TD-20	New Drain	0.80	0.40	Ward no-01	256.700	SD-7
Tertiary Drain	TD-21	New Drain	0.80	0.40	Ward no-01	369.323	SD-7
Tertiary Drain	TD-22	New Drain	0.80	0.40	Ward no-01	426.025	SD-7
Tertiary Drain	TD-23	New Drain	0.80	0.40	Ward no-04	226.417	SD-7
Tertiary Drain	TD-24	New Drain	0.80	0.40	Ward no-04	324.581	SD-7
Tertiary Drain	TD-25	New Drain	0.80	0.40	Ward no-01	293.339	SD-7
Tertiary Drain	TD-26	New Drain	0.80	0.40	Ward no-01	229.037	SD-7
Tertiary Drain	TD-27	New Drain	0.80	0.40	Ward no-01	84.200	SD-7
Tertiary Drain	TD-28	New Drain	0.80	0.40	Ward no-01	141.870	SD-7
Secondary Drain	SD-8	New Drain	0.80	0.40	Ward no-09	1134.945	River
Tertiary Drain	TD-36	New Drain	0.80	0.40	Ward no-09	413.080	SD-8
Tertiary Drain	TD-36	New Drain	0.80	0.40	Ward no-09	368.798	SD-8
Tertiary Drain	TD-37	New Drain	0.80	0.40	Ward no-09	304.676	SD-8
Tertiary Drain	TD-38	New Drain	0.80	0.40	Ward no-09	251.760	SD-8
Tertiary Drain	TD-39	New Drain	0.80	0.40	Ward no-09	223.368	SD-8
Secondary Drain	SD-9	New Drain	0.80	0.40	Ward no-08	365.666	SD-8
Secondary Drain	SD-10	New Drain	0.80	0.40	Ward no-08	437.757	SD-8
Secondary Drain	SD-11	New Drain	0.80	0.40	Ward no-08	211.597	River
Tertiary Drain	TD-40	New Drain	0.80	0.40	Ward no-06	456.260	River
Tertiary Drain	TD-41	New Drain	0.80	0.40	Ward no-06	225.046	River

Type of Drain	Proposed Id	Proposal Status	Proposed Width (m)	Proposed Depth (m)	Ward No.	Length (m)	Outfall
Tertiary Drain	TD-42	New Drain	0.80	0.40	Ward no-07	224.865	River
Tertiary Drain	TD-43	New Drain	0.80	0.40	Ward no-07	367.916	River
Tertiary Drain	TD-44	New Drain	0.80	0.40	Ward no-07	179.656	River
Tertiary Drain	TD-45	New Drain	0.80	0.40	Ward no-07	119.192	River
Primery Drain	PD-1	New Drain	0.80	0.40	Ward no-01	105.165	River
Tertiary Drain	TD-17	New Drain	0.80	0.40	Ward no-04	318.038	River
Tertiary Drain	TD-18	New Drain	0.80	0.40	Ward no-08	121.197	Khal
Tertiary Drain	TD-19	New Drain	0.80	0.40	Ward no-03	85.196	Khal
Secondary Drain	SD-7	New Drain	0.80	0.40	Ward no-01	1302.752	SD-7
Tertiary Drain	TD-20	New Drain	0.80	0.40	Ward no-01	256.700	SD-7
Tertiary Drain	TD-21	New Drain	0.80	0.40	Ward no-01	369.323	SD-7
Tertiary Drain	TD-22	New Drain	0.80	0.40	Ward no-04	426.025	SD-7
Tertiary Drain	TD-23	New Drain	0.80	0.40	Ward no-04	226.417	SD-7
Tertiary Drain	TD-24	New Drain	0.80	0.40	Ward no-01	324.581	SD-7
Tertiary Drain	TD-25	New Drain	0.80	0.40	Ward no-01	293.339	SD-7
Tertiary Drain	TD-26	New Drain	0.80	0.40	Ward no-01	229.037	SD-7
Tertiary Drain	TD-27	New Drain	0.80	0.40	Ward no-01	84.200	SD-7
Tertiary Drain	TD-28	New Drain	0.80	0.40	Ward no-09	141.870	River
Secondary Drain	SD-8	New Drain	0.80	0.40	Ward no-09	1134.945	SD-8
Tertiary Drain	TD-36	New Drain	0.80	0.40	Ward no-09	413.080	SD-8
Tertiary Drain	TD-36	New Drain	0.80	0.40	Ward no-09	368.798	SD-8
Tertiary Drain	TD-37	New Drain	0.80	0.40	Ward no-09	304.676	SD-8
Tertiary Drain	TD-38	New Drain	0.80	0.40	Ward no-09	251.760	SD-8
Tertiary Drain	TD-39	New Drain	0.80	0.40	Ward no-08	223.368	SD-8
Secondary Drain	SD-9	New Drain	0.80	0.40	Ward no-08	365.666	SD-8
Secondary Drain	SD-10	New Drain	0.80	0.40	Ward no-08	437.757	River
Secondary Drain	SD-11	New Drain	0.80	0.40	Ward no-06	211.597	River
Tertiary Drain	TD-40	New Drain	0.80	0.40	Ward no-06	456.260	River
Tertiary Drain	TD-41	New Drain	0.80	0.40	Ward no-07	225.046	River
Tertiary Drain	TD-42	New Drain	0.80	0.40	Ward no-07	224.865	River
Tertiary Drain	TD-43	New Drain	0.80	0.40	Ward no-07	367.916	River
Tertiary Drain	TD-44	New Drain	0.80	0.40	Ward no-07	179.656	River
Tertiary Drain	TD-45	New Drain	0.80	0.40	Ward no-01	119.192	River
Primery Drain	PD-1	New Drain	0.80	0.40	Ward no-04	105.165	River
Tertiary Drain	TD-17	New Drain	0.80	0.40	Ward no-08	318.038	Khal
Tertiary Drain	TD-18	New Drain	0.80	0.40	Ward no-03	121.197	Khal
Tertiary Drain	TD-19	New Drain	0.80	0.40	Ward no-01	85.196	SD-7
Secondary Drain	SD-7	New Drain	0.80	0.40	Ward no-01	1302.752	SD-7
Tertiary Drain	TD-20	New Drain	0.80	0.40	Ward no-01	256.700	SD-7
Tertiary Drain	TD-21	New Drain	0.80	0.40	Ward no-04	369.323	SD-7
Tertiary Drain	TD-22	New Drain	0.80	0.40	Ward no-04	426.025	SD-7
Tertiary Drain	TD-23	New Drain	0.80	0.40	Ward no-01	226.417	SD-7
Tertiary Drain	TD-24	New Drain	0.80	0.40	Ward no-01	324.581	SD-7
Tertiary Drain	TD-25	New Drain	0.80	0.40	Ward no-01	293.339	SD-7
Tertiary Drain	TD-26	New Drain	0.80	0.40	Ward no-01	229.037	SD-7
Tertiary Drain	TD-27	New Drain	0.80	0.40	Ward no-09	84.200	River
Tertiary Drain	TD-28	New Drain	0.80	0.40	Ward no-09	141.870	SD-8
Secondary Drain	SD-8	New Drain	0.80	0.40	Ward no-09	1134.945	SD-8
Tertiary Drain	TD-36	New Drain	0.80	0.40	Ward no-09	413.080	SD-8
Tertiary Drain	TD-36	New Drain	0.80	0.40	Ward no-09	368.798	SD-8
Tertiary Drain	TD-37	New Drain	0.80	0.40	Ward no-09	304.676	SD-8
Tertiary Drain	TD-38	New Drain	0.80	0.40	Ward no-08	251.760	SD-8
Tertiary Drain	TD-39	New Drain	0.80	0.40	Ward no-08	223.368	SD-8
Secondary Drain	SD-9	New Drain	0.80	0.40	Ward no-08	365.666	River
Secondary Drain	SD-10	New Drain	0.80	0.40	Ward no-06	437.757	River
Secondary Drain	SD-11	New Drain	0.80	0.40	Ward no-06	211.597	River
Tertiary Drain	TD-40	New Drain	0.80	0.40	Ward no-07	456.260	River
Tertiary Drain	TD-41	New Drain	0.80	0.40	Ward no-07	225.046	River
Tertiary Drain	TD-42	New Drain	0.80	0.40	Ward no-07	224.865	River
Tertiary Drain	TD-43	New Drain	0.80	0.40	Ward no-07	367.916	River
Tertiary Drain	TD-44	New Drain	0.80	0.40	Ward no-01	179.656	River
Tertiary Drain	TD-45	New Drain	0.80	0.40	Ward no-04	119.192	River
Primery Drain	PD-1	New Drain	0.80	0.40	Ward no-08	105.165	Khal

Source: Drainage and Environmental Management Plan

**Annexure-D: Planning Schedule of Waterbody of Singra
Paurashava**

Planning Schedule of Waterbodyof SingraPaurashava


Type of Land Use	Mouza Name	Plot No.	Area (Acres)
Water Body	Aow Kuri_343_00	25,24,22,19,19,17,17,15,16,14,11,8,9,2,11,8,7,6,5,2,3,4,24,22,21,23,5	12.22
	Balua Basua_341_00	97,96,96,62,56,61,51,50,47,63,64,47,45,46,51,56,53,60,57,59,17,16,87,37,38,35,24,16,87,15,14,87,87,87,12,87,87,86,87,17,19,18,15,7,8,4,3,2,1,20,11,24	8.25
	Baluvora_373_00	280,159,128,127,115,115,406,115,10,9,11,115,10,27,28,26,53,55,49,50,57,56,109,108,102,101,74,44,45,73,65,81,82,80,83,19,17,16,1,65,68,69,86,88,90,91,1228,380,342,358,359,361,380,1228,1228,1228	17.88
	Boro Has Pukuria_279_00	162,285,200	15.41
	Boro Maguri_346_00	10,12,56,57	0.90
	Boro Sawail_387_01	460,463,462,460,459,461,461,458,457,447,456,479,439,438,290,289,288,297,284,287,433,435,434,350,350,349,297,286,298,299,287,299,301,194,193,283,282,301,302,193,191,190,332,182,178,178,269,265,178,177,177,259,244,243,242,241,240,239,280,277,276,274,273,270,271,999,268,203,267,266,264,204,263,205,262,206,261,257,256,207,255,254,253,208,249,209,248,210,242,241,240,239,223,228,229,275,128,127,123,115,114,113,116,112,117,102,100,999,86,68,67,71,57,56,52,51,50,39,46,42,43,40,41,460,459,1320,458,455,1319,454,451,450,1111,292,440,293,1110,1107,439,438,437,436,435,305,434,306,312,313,324,350,325,328,349,348,329,346,335,345,336,344,343,340,342,97,92,92,91,476,90,84,82,96,81,73,999,999,74,75,76,77,89,78,48,47,46,44,94,93,95,93,96,93,95	35.66
	Bosta_348_00	57,58,49,53,54,54,61,62,59,58,49,47,48,38,37,63,98,99,100,96,21,17,4,4	4.63
	Chak Gopal_337_00	72,69,69,66,69,59,57,56,58,55,47,46,52,46,50,51,44,43,28,26,20,30,25,29,21,6,24	2.43
	Chak Singra_344_00	240,61,62,64,63,149,58,59,159,153,160,151,72,71,104,166,167,161,168,167,169,78,81,104,98,84,83,85,82,97,105,100,148,106,149,145,169,144,208,181,182,95,120,94,100,96,95,119,113,114,94,107,106,108,100,109,111,112,113,110,149,93,21,94,123,19,137,135,134,54,39,1,43,39,54,52	13.09
	Dakhin Domdoma_276_00	174,173,174,179,175,179,179,179,175,171,165,166,168,144,164,149,184,148,147,145,164,124,146,145,139,142,141,140,124,118,50,109,40,108,49,46,48,45,44,42,4,77,74,73,8,19,18	10.80
	Falia_259_00	29,999,127,999,130,125,174,175,132,999,130,174,142,143,125,122,127,999,126,125,122	1.33
	Hat Singra_339_00	149,148,146,144,143,131,82,97,96,98,112,104,101,100,99,98,1,2,13,4,1	5.64
	Kata Pukuria_338_00	391,401,359,358,360,355,390,361,362,364,363,366,367,388,363,388,375,366,374,397,384,383,352,351,350,349,348,343,338,340,337,344,336,377,378,382,381,310,309,379,380,323,325,324,277,326,325,278,326,277,307,284,283,297,297,274,273,267,283,283,285,267,297,295,272,270,267,293,300,268,269,267,271,270,303,246,270,267,267,266,266,265,264,233,231,232,147,146,209,149,148,146,135,134,133,120,114,106,152,154,153,156,161,160,159,158,120,121,123,122,105,127,132,81,82,83,84,85,89,157,146,199,200,78,77,76,75,72,168,170,167,177,171,165,167,166,146,177,178,176,171,52,53,72,20,22,14,46,49,47,44,45,40,22,21,27,29,192,193,194,27,29,48,68,39,59,67,60,40,62,64,28,29,109,108,103,102,72,11,10,7,5,6,4,3,1	18.74
	Katua Bari_370_00	291,266,396,397,398,672,689,690,687,398,398,79,78,78,690,686,683,681,659,653,264,86,87,77,351,349,348,346,345,456,86,88,76,89,90,450,589,443,444,450,287,288,289,290,260,335,334,445,597,594,445,333,138,137,292,260,258,242,252,251,243,301,302,300,303,249,248,332,304,305,248,306,247,246,243,236,274,275,276,266,277,279,265,280,281,282,264,283,262,284,285,261,260,1108,267,1109,291,268,269,274,266,261,672,687,686,683,681,685,684,659,682,657,82,653,654,671,658,642,656,643,655,652,651,644,645,646,631,647,638,640,629,637,648,636,635,632,627,634,625,628,633,626,624,623,639,619,621,622,617,620,616,615,614,613,610,612,607,611,609,219,608,218,999,315,314,210,209,203,313,312,194,199,711,244,708,243,192,709,231,230,229,193,228,190,228,190,218,210,209,203,202,204,201,198,194,195,199,711,196,	30.34

Type of Land Use	Mouza Name	Plot No.	Area (Acres)
		192,191,193,189,228,190,219,218,228,82,228,190	
	Niagain_333_01	1808,1806,1788,1796,1797,1830,1829,1688,1822,1821,1812,1808,1806,0,1803,1693,1696,1802,1797,1690,1691,1692,1702,1703,1796,1780	9.40
	Niagain_333_02	1394,1395,1393,1392,1391,1396,1395,1397,1430,1431,1432,1395,1476,1504,1503,1395,1421,1420,1418,1397,1476,1433,1434,1476,1429,1426,1436,1442,1443,1390,1442,1418,1417,1415,1397,1398,1438,1439,1440,1450,1476,1451,1475,1476,1390,1397,1475,1476,1415,1414,1398,1388,1387,1383,1382,1854,1346,1497,1496,1495,1476,1414,1398,1854,1442,1443,1445,1448,1444,1414,1413,1423,1381,1370,1369,1854,1345,1854,1398,1346,1454,1452,1453,1451,1854,1854,1397,1398,1251,1252,1154,99999,1347,1333,1326,1290,1288,1075,1289,1078,1089,1087,1085,1099,1098,1094,1096,1082,1034,1017,1016,1001,1016,22,1227,1210,1316,1485,1484,1477,1245,1467,1466,1243,1246,1463,1461,1459,1249,1457,1238,1455,1456,1423,1237,1406,1250,1254,1405,1404,1260,1403,1401,1273,1400,1275,1332,1295,1331,1318,1092,1013,1316,1216,1213,1210,1233,22	26.94
	Niagain_333_03	3148,3149,3149,3154,3150,3153,3150,3141,3151,3151,3129,3132,3130,3134,3131,3128,3124,3125,3135,3123,3008,3010,3029,3011,3006,3012,3013,3014,3015,3005,3014,3005,3014,3018,3022,3021,3020,3019,3004,3003,3002,3001	4.29
	Par Sawail_369_01	133,130,129,360,1293,115,116,113,115,114,113,127,116,113,117,114,113,111,112,127,120,121,113,117,112,66,330,336,335,360,339,328,64,62,63,66,110,107,112,118,105,151,150,110,149,150,109,108,60,300,68,70,154,70,159,72,71,73,59,73,58,159,58,57,58,58,46,291,290,289,56,50,49,9999,163,1293,52,51,9,11,5,2,10,10,1	3.41
	Patkol_372_00	349,323,323,323,324,323,324,324,327,322,330,358,312,313,412,413,413,221,221,208,209,207,239,205,206,241,241,189,189,199,194,188,187,186,189,185,183,173,262,183,142,146,141,144,146,147,190,192,145,141,137,129,130,123,122,109,126,108,112,98,99,95,96,75,63,64,60,51,51,49,65,72,66,50,51,67,48,49,46,49,36,49,33,34,35,45,262,38,46,39,13,12,11,10,4,6,5,19,20,2,1,217,213,212,210,209,203,202,201,200,189,199,198,196,195,140,139,138,137,134,128,127,126,107,106,105,102,101,55,54,53,52,49,32,31,30,29,28,27,26,25,24,23,22,21,334,333,339,325,360,329,359,331,317,548,547,316,546,315,545,314,544,543,542,541,540,253,253,404,405,406,407,408,411,274,275,276,332,276,262,277,274,275,332,332,332,304,305,314,315,316,315,332,317,316,331,317,332,328,329,326,328,325,326,332,325,332	22.12
	Poran Hati_334_00	63,62,63,62,57,56,55,56,55,54,53,40,42,45,39,38,19,39,38,19,37,15,13,12,9,39,38	7.73
	Porbo Masinda_335_0	60,54,53,53,50,49,47,20,33,19,18,21,17,16,15,7,14,8,9,10	8.90
	Singra_342_00	442,436,439,324,323,324,368,324,414,413,324,412,411,402,317,427,422,423,424,426,425,437,421,420,403,404,405,327,327,403,391,317,314,309,365,364,354,355,391,407,386,407,386,388,387,385,386,385,180,347,345,346,348,183,187,186,287,286,185,286,295,296,283,288,195,190,191,205,203,275,204,206,207,208,199,151,151,276,275,274,224,223,151,151,151,214,151,219,218,212,151,239,214,215,151,229,230,228,231,233,53,53,130,129,151,128,127,126,235,236,239,114,57,61,59,58,62,67,68,113,104,107,237,239,40,34,41,33,44,42,69,102,98,95,99,66,65,90,52,50,67,44,66,68,65,90,71,70,90,71,69,71,70,24,23,89,72,91,88,24,74,23,75,247,255,254,247,272,255,366,327,372,365,364,331,353,351,352,373,330,361,360,333,332,334,359,336,309,308,307,303,302,305,304,335,298	21.92
	Sohag Bari_371_00	67,71,72,70,73,75,49,48,51,48,25,48,22,85,109,108,32,31,30,375	1.73
	Sola Kuri_345_00	347,346,348,349,338,349,385,384,355,381,383,382,317,318,301,324,323,320,318,319,299,350,320,298,353,299,350,355,377,376,375,374,365,301,303,302,294,295,293,295,296,293,290,280,279,278,356,285,284,278,274,207,275,276,277,228,356,206,204,203,202,201,208,207,275,276,241,240,207,227,209,226,228,225,231,223,257,229,228,230,256,238,246,245,247,237,255,248,220,219,235,233,234,31,28,18,45,44,28,14,13,14,28,9,9,11,40,43,7,6,12,9,8,6,395,5,395,3,395,2,1,311,310,271,267,259,254,253,252,392,251,259,254,253,252,392,251,266,263,326,313,311,310,271,350,270,267,392	22.40
	Uttar Domdoma_336_00	902,901,903,916,897,909,910,805,806,1015,1032,1027,951,941,939,942,950,938,915,917,914,911,912,913,918,898,916,930,917,929,924,918,793,794,799,804,1017,1016,952,954,960,1018,1019,1020,1021,924,918,919,920,898,788,780,787,898,890,888,891,818,939,940,934,933,935,958,959,789,790,788,791,1035,787,786,792,785,780,779,778,777,782,781,995,1004,1005,994,996,1003,850,851,849,820,821,833,823,822,834,832,831,830,829,547,548,552,549,554,553,551,493,492,494,491,495,504,498,499,503,505,501,500,502,513,523,512,514,515,435,481,482,436,435,515,431,437,429,428,431,430,436,437,451,446,439,444,443,44	33.24

Type of Land Use	Mouza Name	Plot No.	Area (Acres)
		2,483,482,485,489,484,488,487,423,427,430,438,439,435,434,442,397,454,387,386,391,397,399,396,388,397,389,390,396,399,418,417,413,388,390,394,392,391,395,411,406,413,412,401,402,383,347,349,346,329,328,366,367,355,356,354,353,357,359,358,367,357,353,351,352,345,315,352,345,287,332,344,342,343,306,282,293,281,264,279,265,263,278,149,304,299,150,154,303,151,275,276,277,274,273,278,300,271,308,309,148,273,278,300,1033,303,168,272,271,301,165,164,164,160,163,130,136,132,160,161,131,160,163,161,130,100,101,126,102,140,138,134,22,18,843,844,536,537,845,772,535,531,529,528,525,538,546,524,522,523,521,520,519,518,425,424,423,421,420,418,417,383,898,775,985,801,997,773,998,815,999,774,1000,816,768,753,751,750,742,579,580,564,772,758,747,546,757,754,577,735,756,746,759,674,673,587,672,591,671,670,669,592,752,663,598,860,859,858,841,843,772,772,774,772,774,816,772,772,774,801,774,772,804,815,772,775,775,775,985,997,898,773	

Annexure-E: Resolution of Final Consultation Meeting

Annexure-F: Gazette of Singra Paurashava



গণপ্রজাতন্ত্রী বাংলাদেশ সরকার

স্থানীয় সরকার, পল্লী উন্নয়ন ও সমবায় মন্ত্রণালয়

স্থানীয় সরকার বিভাগ

(স্বাধীনতা পৌর-২)

প্রজ্ঞাপন

তারিখ: ৬ই মে ১৯৯৯

নং পৌর-২/আই-৬/৯৮/৫৬৬—Paurashava Ordinance, 1977 (XXVI of 1977) এর section 19 এবং section 24 এ প্রদত্ত ক্ষমতাবলে সংসদ এইভাবে সিদ্ধান্ত গ্রহণ করিয়াছে যে,—

- নিম্নের তফসিলের কলাম ৩-এ উল্লিখিত সিউনিশিয়ালিটি একই তফসিলের কলাম ৪-এ উল্লিখিত সংখ্যক ওয়ার্ডে বিভক্ত হইবে;
- উক্ত তফসিলের কলাম ৫-এ উল্লিখিত সংখ্যক সংরক্ষিত মহিলা আসনে শুল্কবিহীন হইবে;
- উক্ত তফসিলের কলাম ৬-এ উল্লিখিত সংখ্যক হইবে সংশ্লিষ্ট পৌরসভার, সংরক্ষিত মহিলা আসন ব্যতীত, কনিষ্ঠার সংখ্যা;
- উক্ত তফসিলের কলাম ৭-এ উল্লিখিত সংখ্যক হইবে সংরক্ষিত মহিলা কনিষ্ঠার সংখ্যা।

(২২৩৭)

মূল্য: টাকা ০.০০

সিংগার পৌর, জরিপ, মে ১, ১৯৯৯

১১৩৯

১ ২ ৩ ৪ ৫

পানির টাংকী হতে সোজা সিংগারী নদী ভায়া রাগেলের জাতি কসিং বিল এবং পশ্চিমে দখলি পাকা বাড়ী।

উত্তরে-ধরলা নদী ও বাটার পাড়া পিংকি বহিল হতে সোজা রতন সাহাৰ বাড়ীর পাড়া বাড়ী হতে বাটগ্রাম রেল ষ্টেশন পর্যন্ত ভায়া রাগেলের মোড়, দক্ষিণে-সিংগারী নদী, পূর্বে সুবো বাসুর ডাটার বিল হতে সোজা সিংগারী নদী ভায়া সুবুর উদ্দিনের বাড়ী এবং পশ্চিমে রেল ষ্টেশনের পাড়ার টাংকী হতে সোজা সিংগারী নদী ভায়া রাগেলের জাতির কসিং বিল।

উত্তরে ধরলা নদী ও বাটার বাড়ী মোজার পাশে, দক্ষিণে-সিংগারী নদী ও মির্জার কোটি মোজার শেষ জায়গা, পূর্বে-ধরলা নদী ও মোমিনপুর মোজা এবং পশ্চিমে সুবো বাসুর ডাটার বিল হতে সোজা সিংগারী নদী ভায়া সুবুর উদ্দিনের বাড়ী।

গ্রাম/বহমা: কাটা পুকুরিয়া, চক গোপাল, পূর্ব বহিন্দা। লোহানা-উত্তরে-উত্তর বহমা এবং একটি খাল বহিয়াছে। যাহার নাটোর বগুড়া মহাসড়কের দিকে চলিয়া গিয়াছে। দক্ষিণে চান্দপুর মোজা এবং খানা পরিষদের পাশে দিয়া একটি পাকা বাড়ী সিংজা বাগড়াতে মিলিত হইয়াছে। পূর্বে-সুদামা-বাসুয়া মোজা এবং চলন বিলের পশ্চিম প্রান্তে পশ্চিম-গাইর পাড়া মোজা।

গ্রাম: উত্তর বহমা, বড়হাঁসপুকুরিয়া, ছোট হাঁসপুকুরিয়া। উত্তরে-রাখালগাঁছা মোজা এবং বহমা হইতে অচলখার উত্তর পূর্ব পর্যন্ত বাড়ী বহিয়াছে, দক্ষিণে-জিয়া খাল যাহা বহমা হইতে বড়িয়া গিয়াছে। পূর্বে-নাটোর বগুড়া মহাসড়ক অবস্থিত। পশ্চিমে-কোন গ্রাম নাই। তবে হাঁস পুকুরিয়া গ্রামের দ্বিটি বাড়ী আছে। হাঁসপুকুরিয়া গ্রামের আশেপাশে পৌর এলাকার মধ্যে বহিয়াছে। যাহার বাহুর বহু বহু বিস্তৃত-সড়-হাস-

১৩ বাটোর

সিংজা

১২৪৪

বাংলাদেশ সোভেট, অতিরিক্ত, মে ১, ১৯৯৯

১

২

৩

৪

৫

পুকুরিয়া, ১৬০ হইতে ২০৭ পর্যন্ত, ছোট্ট হাসপুকুরিয়া ৩২-৪৪, ৪৮-৫২ দাগ নং পর্যন্ত।

৩ গ্রাম-দক্ষিণ দক্ষিণ, হাতিগড়া উত্তরে উত্তর দক্ষিণ ও জিমা খাল অবস্থিত দক্ষিণে-কাটা পুকুরিয়া ও বড়া মৌজা অবস্থিত। পূর্বে-নাটোর-বগুড়া মহাসড়ক পশ্চিমে-হাসপুকুরিয়া মৌজা এবং নাগর নদী অবস্থিত।

৪ গ্রাম-চাঁদপুর, মাদারীপুর, বালুয়াবাসিয়া, বড়া। উত্তরে-কাটা পুকুরিয়া, দক্ষিণে-সিংড়া মৌজা, পূর্বে-চন্দন বিল, পশ্চিমে পশ্চিমে-অমলগর মৌজা এবং খামা পরিষদের পাকা রাস্তা, যাহা সিওড়া বাসট্যাংকে মিলিত হইয়াছে।

৫ গ্রাম হাটগিঞ্জা, গাইনপাড়া, অমলগর। উত্তরে-কাটা পুকুরিয়া, দক্ষিণে-সিংড়া মৌজা এবং নাটোর-বগুড়া মহাসড়ক। পূর্বে-কাটা পুকুরিয়া মৌজা এবং খামা পরিষদের পাকা রাস্তা। পশ্চিমে হাসপুকুরিয়া মৌজা এবং গুড় নদী।

৬ গ্রাম-পারগিঞ্জা, বালুভরা, পাটকোল, আউকুরি। উত্তরে-পরানঘাট ও গুড় নদী অবস্থিত। দক্ষিণে-বড়শাঐল মৌজা পূর্বে সিংড়া মৌজা, পশ্চিমে শৈলবারী ও নিংগুইন মৌজার আংশিক অংশ। যে সকল মৌজার আংশিক অংশ পৌরসভার অন্তর্গত হইয়াছে সেই সকল মৌজার দাগ নংসমূহ নিম্নে প্রদত্ত হইল: বালুভরা: ১-৬১, ৬৩-১১৭, ১১৯, ১২১-১৬০, ১৭০-১৮০, ১৮৪-১৮৯, ৩৩৮-৪০৬। পাটকোল ১-৩৬১ আংশিক, আউকুরি ১-২৫০ আংশিক।

৭ নিংগুইন গ্রাম: উত্তরে-আড় মলিকা দক্ষিণে-শৈলবারী ও নিংগুইনের আংশিক, সোনায়া। পূর্বে বালুভরা, পশ্চিমে আড় মলিকা, নিংগুইন মৌজার যে সমস্ত দাগ পৌরসভার অন্তর্গত হইয়াছে: ১০০১-১০৫০, ১০৬৪-১১০৬, ১১২২-১১৩৩, ১১৪৭-১১৫৭, ১১৬৫-১১৭৭, ১১৮৬-১১৮৮, ১২০০-১৫১৮, ১৮৪৭-১৮৫০,

সিংরা পৌরসভা, প্রতিবেদন, মে ৯, ১৯৯১

২৭৪৫

১৮৫৬-১৮৫৮, ৩০৩১-৩০৬১, ৩০৬৪, ৩১০৬-৩১৭৮, ৩০৪৩-৩০৫৪।

গ্রাম-সিংড়া। উত্তরে-হাট সিংড়া, মৌমা, দক্ষিণে-টঙ্গী সিংড়া মৌমা, পূর্বে মাদারীপুর কাটা পুকুরিয়া মৌমা এবং থানা পর্যবেদর পাখা রাখা আছে। পশ্চিমে পারসিংড়া ও শুভাদী।

গ্রাম-চক সিংড়া। পোনাকুড়া, গোহাগবাড়ী, কতুয়াবাড়ী, উত্তরে-সিংড়া মৌমা ও নাটোর বড়ুয়া মহাপুত্র, দক্ষিণে-শুভ নদীর উত্তর তীর পর্যন্ত। পূর্বে বড়ুয়াখরী মৌমা ও কৃষি মাঠ। কতুয়াবাড়ী ও গোহাগবাড়ী মৌমার আশেপাশে যে সমস্ত এলাকা পৌর-সভার অন্তর্গত হইয়াছে তাহার সীমা ন্যূনতম প্রদত্ত হইল : গোহাগবাড়ী ১-১৩৬ ৩৬৭-৩৬৯, ৩৭৩-৩৭৫, ৩৭৭, ৩৭৮, ৪৩২-৪৩৪, ১৫৭-২২৭, ৭০৩ ও ৭১১।

রাষ্ট্রপতির আদেশক্রমে,
আবদুল সাত্তার খান
উপ-ম্যাজিস্ট্রেট (পৌর)।

প্রজ্ঞাপন

তারিখ, ২০শে বৈশাখ ১৪০৬/৬ই মে ১৯৯৯

সং পৌর-২/ওয়ার্ড-৬/৯৮/০০৭—Paurashava Ordinance, 1977 (XXVI of 1977) এর section 21A এর বিধানানুসারে ডিনিফিকেশন অফ দ্য কমার্স কলেক্টর চত্বারসুত; নিম্ন তহসিলে বর্ণিত বিভাগীয় প্যান্ডিটিগনহের সংরক্ষিত মহিলা আসনে নির্বাচনের লক্ষ্যে সংরক্ষিত মহিলা ওয়ার্ড গঠন করে সরকার আদেশ জারী করিল :—

ক্রমিক সং	মেম্বারের নাম	মিউনিসি- প্যান্ডিটি নাম	সংরক্ষিত মহিলা ওয়ার্ড সং	ওয়ার্ডের মাঝে অন্তর্ভুক্ত এলাকার সীমানা (পূর্বে, পশ্চিমে, উত্তরে ও দক্ষিণে গের প্রতিষ্ঠিত মোড়, গলি, বহলা, খাল হুতাদির বর্ণনা)
১	২	৩	৪	৫
১	আনানুপুর	মঙ্গলদহ	১	সাধারণ ওয়ার্ড ১, ২, ৩ সবরয়ে গঠিত। সীমানা: উত্তরে-পূর্বকোণে ভোজা নিয়ার বাড়ী রাখা হইতে শ্রীকৃষ্ণ নদীর পাড় হইয়া মেম্বার বাড়ী মোড়ার দক্ষিণ প্রান্তে হাসেমের বাড়ী পর্যন্ত।

সংরক্ষিত - মহানগর আওতা ৪

১৯৪৮

বাংলাদেশ সিজেট, প্রতিষ্ঠিত, মে ১, ১৯৯৯

১	২	৩	৪	৫
৩. নাটোর	সিংড়া	১	গ্রাম-কাটাপুকুরিয়া, চকগোপাল, পূর্ব মণিলা, উত্তর দমনবা, বড় হাঙ্গপুকুরিয়া, ছোট হাঙ্গপুকুরিয়া দক্ষিণ দমনবা, হাতিগাজী। সীমানা-উত্তরে-রাখালগাজী, দক্ষিণে-চাঁদপুর বৌদ্ধ এবং পান্না পরিষদের পাকা রাজা মাথা সিংড়া বাগটগাওঁর মিলিত হইয়াছে। পূর্বে-নাটোর-বগুড়া মহাসড়ক। পশ্চিমে-গাইন গাজী বৌদ্ধা, বড়হাঙ্গ- পুকুরিয়া বৌদ্ধাঃ ১৬০-২০৭ দাগ এবং ছোট হাঙ্গপুকুরিয়ার ৩২-৪৪, ৪৮-৫৯ দাগসমূহ।	
		২	গ্রাম-চাঁদপুর, মাদারীপুর, বালুয়া, বাসুয়া, বজা, হাটগিঞ্জা, পাজাখনগর, গাইনগাজী, পারগিঞ্জা, বালুভা, পাটকোল। সীমানা-উত্তরে-কাটাপুকুরিয়া বৌদ্ধা দক্ষিণে-বড় পাটল বৌদ্ধা। পূর্বে- নাটোর-বগুড়া মহাসড়ক। পশ্চিমে- সিংগুইন বৌদ্ধা।	
		৩	গ্রাম-সিংগুইন, সিংড়া, চক সিংড়া, গোলকুড়া মোহাংবাড়ী। সীমানা-উত্তরে-হাটগিঞ্জা বৌদ্ধা, দক্ষিণে- কতুয়াবাড়ীর দক্ষিণ এলাকা (পৌর সংস্থিত এলাকা - পূর্বে-মাদারীপুর-বালুয়া- বাসুয়া, পশ্চিমে-ছোট মসিকা বৌদ্ধা, মোহাংবাড়ী বৌদ্ধার দার দখল সমূহ-১-১৩৬, ৩৬৭-৩৬৯, ৩৭৩-৩৭৫, ৩৭৭, ৩৭৮। কতুয়া বৌদ্ধার দাগ নং ৭০, ৭১, ৭৬-১০৫, ১০২-১০৪, ১০৭-২২৭, ৭০৭ ও ৭১১।	

মহানগর আদেশক্রমে

মাকসুদ সাত্তার বিয়া

উপ-ম্যাজিস্ট্রেট (পৌর)।

মোঃ আবদুল করিম সরকার (উপ-ম্যাজিস্ট্রেট) উপ-নিয়ন্ত্রক, বাংলাদেশ সরকারী মুদ্রণালয়
ঢাকা কর্তৃক মুদ্রিত।

মোঃ আমিনুজ্জোব্বারী খালিম, উপ-নিয়ন্ত্রক, বাংলাদেশ সরকার ও প্রকাশনী প্রতিষ্ঠান
তেজগাঁও, ঢাকা কর্তৃক প্রকাশিত।

Appendix

Appendix-1: Structure Plan Map of SingraPaurashava

Appendix-2: Land Use Plan Map of Singra Paurashava

**Appendix-3: Transportation and Traffic Management
Plan**

**Appendix-4: Drainage and Environmental Management
Plan**

10

